

The background of the entire cover is a photograph of a multi-tiered waterfall cascading over dark, wet rocks. The water is in motion, creating a blurred effect in some areas, particularly in the lower half of the image.

JavaTM



HOW TO PROGRAM

TENTH EDITION
LATE OBJECTS VERSION

PAUL DEITEL
HARVEY DEITEL

Use with
JavaTM SE 7
or JavaTM SE 8

ONLINE ACCESS

Thank you for purchasing a new copy of *Java™ How to Program, Tenth Edition, Late Objects Version*. Your textbook includes 12 months of prepaid access to the book's Companion Website. This prepaid subscription provides you with full access to the following student support areas:

- VideoNotes (step-by-step video tutorials specifically designed to enhance the programming concepts presented in this textbook)
- Source code
- Premium web chapters and appendices

**Use a coin to scratch off the coating and reveal your student access code.
Do not use a knife or other sharp object as it may damage the code.**

To access the *Java How to Program, Tenth Edition, Late Objects Version* Companion Website for the first time, you will need to register online using a computer with an Internet connection and a web browser. The process takes just a couple of minutes and only needs to be completed once.

- 1.** Go to <http://www.pearsonhighered.com/deitel/>
- 2.** Click on **Companion Website**.
- 3.** Click on the **Register** button.
- 4.** On the registration page, enter your student access code* found beneath the scratch-off panel. Do not type the dashes. You can use lower- or uppercase.
- 5.** Follow the on-screen instructions. If you need help at any time during the online registration process, simply click the **Need Help?** icon.
- 6.** Once your personal Login Name and Password are confirmed, you can begin using the *Java How to Program, Tenth Edition, Late Objects Version* Companion Website!

To log in after you have registered:

You only need to register for this Companion Website once. After that, you can log in any time at <http://www.pearsonhighered.com/deitel/> by providing your Login Name and Password when prompted.

*Important: The access code can only be used once. This subscription is valid for 12 months upon activation and is not transferable. If this access code has already been revealed, it may no longer be valid. If this is the case, you can purchase a subscription at <http://www.pearsonhighered.com/deitel/> by going to the *Java How to Program, Tenth Edition, Late Objects Version* book and following the on-screen instructions.



JavaTM

HOW TO PROGRAM

TENTH EDITION

LATE OBJECTS VERSION

Deitel® Series Page

How To Program Series

Android How to Program, 2/E
C++ How to Program, 9/E
C How to Program, 7/E
Java™ How to Program, 10/E
Java™ How to Program, Late Objects Version, 10/E
Internet & World Wide Web How to Program, 5/E
Visual C++® 2008 How to Program, 2/E
Visual Basic® 2012 How to Program, 6/E
Visual C#® 2012 How to Program, 5/E

Simply Series

Simply C++: An App-Driven Tutorial Approach
Simply Java™ Programming: An App-Driven Tutorial Approach
Simply C#: An App-Driven Tutorial Approach
Simply Visual Basic® 2010: An App-Driven Approach, 4/E

CourseSmart Web Books

www.deitel.com/books/CourseSmart/
C++ How to Program, 8/E and 9/E
Simply C++: An App-Driven Tutorial Approach
Java™ How to Program, 9/E and 10/E
Simply Visual Basic® 2010: An App-Driven Approach, 4/E

(continued from previous column)

Visual Basic® 2012 How to Program, 6/E
Visual Basic® 2010 How to Program, 5/E
Visual C#® 2012 How to Program, 5/E
Visual C#® 2010 How to Program, 4/E

Deitel® Developer Series

Android for Programmers: An App-Driven Approach, 2/E, Volume 1
C for Programmers with an Introduction to C11
C++11 for Programmers
C# 2012 for Programmers
Dive Into® iOS 6 for Programmers: An App-Driven Approach
Java™ for Programmers, 3/E
JavaScript for Programmers

LiveLessons Video Learning Products

www.deitel.com/books/LiveLessons/
Android App Development Fundamentals
C++ Fundamentals
Java™ Fundamentals
C# 2012 Fundamentals
C# 2010 Fundamentals
iOS® 6 App Development Fundamentals
JavaScript Fundamentals
Visual Basic® Fundamentals

To receive updates on Deitel publications, Resource Centers, training courses, partner offers and more, please join the Deitel communities on

- Facebook®—[facebook.com/DeitelFan](https://www.facebook.com/DeitelFan)
- Twitter®—[@deitel](https://twitter.com/deitel)
- Google+™—[google.com/+DeitelFan](https://plus.google.com/+DeitelFan)
- YouTube™—[youtube.com/DeitelTV](https://www.youtube.com/DeitelTV)
- LinkedIn®—[linkedin.com/company/deitel-&-associates](https://www.linkedin.com/company/deitel-&-associates)

and register for the free *Deitel® Buzz Online* e-mail newsletter at:

www.deitel.com/newsletter/subscribe.html

To communicate with the authors, send e-mail to:

deitel@deitel.com

For information on *Dive-Into® Series* on-site seminars offered by Deitel & Associates, Inc. worldwide, write to us at deitel@deitel.com or visit:

www.deitel.com/training/

For continuing updates on Pearson/Deitel publications visit:

www.deitel.com
www.pearsonhighered.com/deitel/

Visit the Deitel Resource Centers that will help you master programming languages, software development, Android and iOS app development, and Internet- and web-related topics:

www.deitel.com/ResourceCenters.html

JavaTM

HOW TO PROGRAM

TENTH EDITION

LATE OBJECTS VERSION

Paul Deitel

Deitel & Associates, Inc.

Harvey Deitel

Deitel & Associates, Inc.



DEITEL[®]

PEARSON

Boston Columbus Indianapolis New York San Francisco Upper Saddle River
Amsterdam Cape Town Dubai London Madrid Milan Munich Paris Montreal Toronto
Delhi Mexico City Sao Paulo Sydney Hong Kong Seoul Singapore Taipei Tokyo

Editorial Director, ECS: *Marcia Horton*
Executive Editor: *Tracy Johnson (Dunkelberger)*
Director of Marketing: *Christy Lesko*
Marketing Manager: *Yez Alayan*
Marketing Assistant: *Jon Bryant*
Director of Program Management: *Erin Gregg*
Program Management—Team Lead: *Scott Disanno*
Program Manager: *Carole Snyder*
Project Management—Team Lead: *Laura Burgess*
Project Manager: *Robert Engelhardt*
Procurement Specialist: *Linda Sager*
Cover Design: *Paul Deitel, Harvey Deitel, Abbey Deitel, Barbara Deitel, Marta Samsel*
Permissions Supervisor: *Michael Joyce*
Permissions Administrator: *Jenell Forschler*
Director, Image Asset Services: *Annie Atherton*
Manager, Visual Research: *Karen Sanatar*
Cover Art: © *Elina Elisseeva/Shutterstock*
Media Project Manager: *Renata Butera*

Credits and acknowledgments borrowed from other sources and reproduced, with permission, in this textbook appear on page vi.

The authors and publisher of this book have used their best efforts in preparing this book. These efforts include the development, research, and testing of the theories and programs to determine their effectiveness. The authors and publisher make no warranty of any kind, expressed or implied, with regard to these programs or to the documentation contained in this book. The authors and publisher shall not be liable in any event for incidental or consequential damages in connection with, or arising out of, the furnishing, performance, or use of these programs.

Copyright © 2015 and 2010 Pearson Education, Inc. All rights reserved. Manufactured in the United States of America. This publication is protected by Copyright, and permission should be obtained from the publisher prior to any prohibited reproduction, storage in a retrieval system, or transmission in any form or by any means, electronic, mechanical, photocopying, recording, or likewise. To obtain permission(s) to use material from this work, please submit a written request to Pearson Education, Inc., Permissions Department, One Lake Street, Upper Saddle River, New Jersey 07458, or you may fax your request to 201-236-3290.

Many of the designations by manufacturers and sellers to distinguish their products are claimed as trademarks. Where those designations appear in this book, and the publisher was aware of a trademark claim, the designations have been printed in initial caps or all caps.

Library of Congress Cataloging-in-Publication Data
On file

10 9 8 7 6 5 4 3 2 1

ISBN-10: 0-13-257565-5

ISBN-13: 978-0-13-257565-2

PEARSON

*To Brian Goetz,
Oracle's Java Language Architect and
Specification Lead for Java SE 8's Project Lambda:*

*Your mentorship helped us make a better book.
Thank you for insisting that we get it right.*

Paul and Harvey Deitel

Trademarks

DEITEL, the double-thumbs-up bug and DIVE INTO are registered trademarks of Deitel and Associates, Inc.

Oracle and Java are registered trademarks of Oracle and/or its affiliates. Other names may be trademarks of their respective owners.

Microsoft and/or its respective suppliers make no representations about the suitability of the information contained in the documents and related graphics published as part of the services for any purpose. All such documents and related graphics are provided “as is” without warranty of any kind. Microsoft and/or its respective suppliers hereby disclaim all warranties and conditions with regard to this information, including all warranties and conditions of merchantability, whether express, implied or statutory, fitness for a particular purpose, title and non-infringement. In no event shall Microsoft and/or its respective suppliers be liable for any special, indirect or consequential damages or any damages whatsoever resulting from loss of use, data or profits, whether in an action of contract, negligence or other tortious action, arising out of or in connection with the use or performance of information available from the services.

The documents and related graphics contained herein could include technical inaccuracies or typographical errors. Changes are periodically added to the information herein. Microsoft and/or its respective suppliers may make improvements and/or changes in the product(s) and/or the program(s) described herein at any time. Partial screen shots may be viewed in full within the software version specified.

Microsoft® and Windows® are registered trademarks of the Microsoft Corporation in the U.S.A. and other countries. Screen shots and icons reprinted with permission from the Microsoft Corporation. This book is not sponsored or endorsed by or affiliated with the Microsoft Corporation. UNIX is a registered trademark of The Open Group.

Apache is a trademark of The Apache Software Foundation.

CSS and XML are registered trademarks of the World Wide Web Consortium.

Firefox is a registered trademark of the Mozilla Foundation.

Google is a trademark of Google, Inc.

Mac and OS X are trademarks of Apple Inc., registered in the U.S. and other countries.

Linux is a registered trademark of Linus Torvalds. All trademarks are property of their respective owners.

Throughout this book, trademarks are used. Rather than put a trademark symbol in every occurrence of a trademarked name, we state that we are using the names in an editorial fashion only and to the benefit of the trademark owner, with no intention of infringement of the trademark.



Contents

Chapters 26–34 and Appendices F–N are PDF documents posted online at the book's Companion Website (located at www.pearsonhighered.com/deitel/). See the inside front cover for information on accessing the Companion Website.

Foreword	xxiii
-----------------	--------------

Preface	xxv
----------------	------------

Before You Begin	xxxix
-------------------------	--------------

I Introduction to Computers, the Internet and Java I

1.1	Introduction	2
1.2	Hardware and Software	4
1.2.1	Moore's Law	4
1.2.2	Computer Organization	5
1.3	Data Hierarchy	6
1.4	Machine Languages, Assembly Languages and High-Level Languages	9
1.5	Introduction to Object Technology	10
1.5.1	The Automobile as an Object	10
1.5.2	Methods and Classes	11
1.5.3	Instantiation	11
1.5.4	Reuse	11
1.5.5	Messages and Method Calls	11
1.5.6	Attributes and Instance Variables	11
1.5.7	Encapsulation and Information Hiding	12
1.5.8	Inheritance	12
1.5.9	Interfaces	12
1.5.10	Object-Oriented Analysis and Design (OOAD)	12
1.5.11	The UML (Unified Modeling Language)	13
1.6	Operating Systems	13
1.6.1	Windows—A Proprietary Operating System	13
1.6.2	Linux—An Open-Source Operating System	14
1.6.3	Android	14
1.7	Programming Languages	15
1.8	Java	17
1.9	A Typical Java Development Environment	17
1.10	Test-Driving a Java Application	21

1.11	Internet and World Wide Web	25
1.11.1	The Internet: A Network of Networks	26
1.11.2	The World Wide Web: Making the Internet User-Friendly	26
1.11.3	Web Services and Mashups	26
1.11.4	Ajax	27
1.11.5	The Internet of Things	27
1.12	Software Technologies	28
1.13	Keeping Up-to-Date with Information Technologies	30

2 Introduction to Java Applications; Input/Output and Operators 34

2.1	Introduction	35
2.2	Your First Program in Java: Printing a Line of Text	35
2.3	Modifying Your First Java Program	41
2.4	Displaying Text with <code>printf</code>	43
2.5	Another Application: Adding Integers	44
2.5.1	<code>import</code> Declarations	45
2.5.2	Declaring Class <code>Addition</code>	46
2.5.3	Declaring and Creating a Scanner to Obtain User Input from the Keyboard	46
2.5.4	Declaring Variables to Store Integers	47
2.5.5	Prompting the User for Input	48
2.5.6	Obtaining an <code>int</code> as Input from the User	48
2.5.7	Prompting for and Inputting a Second <code>int</code>	49
2.5.8	Using Variables in a Calculation	49
2.5.9	Displaying the Result of the Calculation	49
2.5.10	Java API Documentation	49
2.6	Memory Concepts	50
2.7	Arithmetic	51
2.8	Decision Making: Equality and Relational Operators	54
2.9	(Optional) GUI and Graphics Case Study: Using Dialog Boxes	58
2.10	Wrap-Up	61

3 Control Statements: Part I; Assignment, `++` and `--` Operators 72

3.1	Introduction	73
3.2	Algorithms	73
3.3	Pseudocode	74
3.4	Control Structures	74
3.5	<code>if</code> Single-Selection Statement	76
3.6	<code>if...else</code> Double-Selection Statement	77
3.7	<code>while</code> Repetition Statement	82
3.8	Formulating Algorithms: Counter-Controlled Repetition	83
3.9	Formulating Algorithms: Sentinel-Controlled Repetition	87

3.10	Formulating Algorithms: Nested Control Statements	95
3.11	Compound Assignment Operators	99
3.12	Increment and Decrement Operators	100
3.13	Primitive Types	103
3.14	(Optional) GUI and Graphics Case Study: Creating Simple Drawings	103
3.15	Wrap-Up	107

4 Control Statements: Part 2; Logical Operators 121

4.1	Introduction	122
4.2	Essentials of Counter-Controlled Repetition	122
4.3	for Repetition Statement	124
4.4	Examples Using the for Statement	128
4.5	do...while Repetition Statement	132
4.6	switch Multiple-Selection Statement	134
4.7	break and continue Statements	140
4.8	Logical Operators	142
4.9	Structured Programming Summary	147
4.10	(Optional) GUI and Graphics Case Study: Drawing Rectangles and Ovals	152
4.11	Wrap-Up	154

5 Methods 164

5.1	Introduction	165
5.2	Program Modules in Java	165
5.3	static Methods, static Variables and Class Math	167
5.4	Declaring Methods	169
5.5	Notes on Declaring and Using Methods	173
5.6	Method-Call Stack and Stack Frames	174
5.7	Argument Promotion and Casting	175
5.8	Java API Packages	176
5.9	Case Study: Secure Random-Number Generation	178
5.10	Case Study: A Game of Chance; Introducing enum Types	183
5.11	Scope of Declarations	187
5.12	Method Overloading	189
5.13	(Optional) GUI and Graphics Case Study: Colors and Filled Shapes	192
5.14	Wrap-Up	195

6 Arrays and ArrayLists 208

6.1	Introduction	209
6.2	Primitive Types vs. Reference Types	210
6.3	Arrays	210
6.4	Declaring and Creating Arrays	212
6.5	Examples Using Arrays	213
6.5.1	Creating and Initializing an Array	213

6.5.2	Using an Array Initializer	214
6.5.3	Calculating the Values to Store in an Array	215
6.5.4	Summing the Elements of an Array	217
6.5.5	Using Bar Charts to Display Array Data Graphically	217
6.5.6	Using the Elements of an Array as Counters	219
6.5.7	Using Arrays to Analyze Survey Results	220
6.6	Exception Handling: Processing the Incorrect Response	222
6.6.1	The <code>try</code> Statement	222
6.6.2	Executing the <code>catch</code> Block	222
6.6.3	<code>toString</code> Method of the Exception Parameter	223
6.7	Enhanced <code>for</code> Statement	223
6.8	Passing Arrays to Methods	224
6.9	Pass-By-Value vs. Pass-By-Reference	227
6.10	Multidimensional Arrays	228
6.11	Variable-Length Argument Lists	231
6.12	Using Command-Line Arguments	233
6.13	Class Arrays	235
6.14	Introduction to Collections and Class <code>ArrayList</code>	238
6.15	(Optional) GUI and Graphics Case Study: Drawing Arcs	241
6.16	Wrap-Up	244

7 Introduction to Classes and Objects 265

7.1	Introduction	266
7.2	Instance Variables, <i>set</i> Methods and <i>get</i> Methods	267
7.2.1	Account Class with an Instance Variable, a <i>set</i> Method and a <i>get</i> Method	267
7.2.2	AccountTest Class That Creates and Uses an Object of Class Account	269
7.2.3	Compiling and Executing an App with Multiple Classes	272
7.2.4	Account UML Class Diagram with an Instance Variable and <i>set</i> and <i>get</i> Methods	272
7.2.5	Additional Notes on This Example	274
7.2.6	Software Engineering with <code>private</code> Instance Variables and <code>public set</code> and <i>get</i> Methods	274
7.3	Default and Explicit Initialization for Instance Variables	276
7.4	Account Class: Initializing Objects with Constructors	276
7.4.1	Declaring an Account Constructor for Custom Object Initialization	276
7.4.2	Class AccountTest: Initializing Account Objects When They're Created	277
7.5	Account Class with a Balance; Floating-Point Numbers	279
7.5.1	Account Class with a <code>balance</code> Instance Variable of Type <code>double</code>	279
7.5.2	AccountTest Class to Use Class Account	281
7.6	Case Study: Card Shuffling and Dealing Simulation	284
7.7	Case Study: Class GradeBook Using an Array to Store Grades	289

7.8	Case Study: Class GradeBook Using a Two-Dimensional Array	294
7.9	Wrap-Up	300

8 Classes and Objects: A Deeper Look 307

8.1	Introduction	308
8.2	Time Class Case Study	308
8.3	Controlling Access to Members	313
8.4	Referring to the Current Object's Members with the <code>this</code> Reference	314
8.5	Time Class Case Study: Overloaded Constructors	316
8.6	Default and No-Argument Constructors	322
8.7	Notes on <i>Set</i> and <i>Get</i> Methods	322
8.8	Composition	324
8.9	<code>enum</code> Types	327
8.10	Garbage Collection	329
8.11	<code>static</code> Class Members	330
8.12	<code>static</code> Import	334
8.13	<code>final</code> Instance Variables	335
8.14	Package Access	336
8.15	Using <code>BigDecimal</code> for Precise Monetary Calculations	337
8.16	(Optional) GUI and Graphics Case Study: Using Objects with Graphics	340
8.17	Wrap-Up	344

9 Object-Oriented Programming: Inheritance 352

9.1	Introduction	353
9.2	Superclasses and Subclasses	354
9.3	<code>protected</code> Members	356
9.4	Relationship Between Superclasses and Subclasses	357
9.4.1	Creating and Using a <code>CommissionEmployee</code> Class	357
9.4.2	Creating and Using a <code>BasePlusCommissionEmployee</code> Class	363
9.4.3	Creating a <code>CommissionEmployee–BasePlusCommissionEmployee</code> Inheritance Hierarchy	368
9.4.4	<code>CommissionEmployee–BasePlusCommissionEmployee</code> Inheritance Hierarchy Using <code>protected</code> Instance Variables	371
9.4.5	<code>CommissionEmployee–BasePlusCommissionEmployee</code> Inheritance Hierarchy Using <code>private</code> Instance Variables	374
9.5	Constructors in Subclasses	379
9.6	Class Object	379
9.7	(Optional) GUI and Graphics Case Study: Displaying Text and Images Using Labels	380
9.8	Wrap-Up	383

10 Object-Oriented Programming: Polymorphism and Interfaces 387

10.1	Introduction	388
------	--------------	-----

10.2	Polymorphism Examples	390
10.3	Demonstrating Polymorphic Behavior	391
10.4	Abstract Classes and Methods	393
10.5	Case Study: Payroll System Using Polymorphism	396
10.5.1	Abstract Superclass <code>Employee</code>	397
10.5.2	Concrete Subclass <code>SalariedEmployee</code>	399
10.5.3	Concrete Subclass <code>HourlyEmployee</code>	401
10.5.4	Concrete Subclass <code>CommissionEmployee</code>	403
10.5.5	Indirect Concrete Subclass <code>BasePlusCommissionEmployee</code>	405
10.5.6	Polymorphic Processing, <code>instanceof</code> and Downcasting	406
10.6	Allowed Assignments Between Superclass and Subclass Variables	411
10.7	<code>final</code> Methods and Classes	411
10.8	A Deeper Explanation of Issues with Calling Methods from Constructors	412
10.9	Creating and Using Interfaces	413
10.9.1	Developing a Payable Hierarchy	414
10.9.2	Interface <code>Payable</code>	415
10.9.3	Class <code>Invoice</code>	416
10.9.4	Modifying Class <code>Employee</code> to Implement Interface <code>Payable</code>	418
10.9.5	Modifying Class <code>SalariedEmployee</code> for Use in the Payable Hierarchy	420
10.9.6	Using Interface <code>Payable</code> to Process Invoices and Employees Polymorphically	422
10.9.7	Some Common Interfaces of the Java API	423
10.10	Java SE 8 Interface Enhancements	424
10.10.1	<code>default</code> Interface Methods	424
10.10.2	<code>static</code> Interface Methods	425
10.10.3	Functional Interfaces	425
10.11	(Optional) GUI and Graphics Case Study: Drawing with Polymorphism	425
10.12	Wrap-Up	428

11 Exception Handling: A Deeper Look **433**

11.1	Introduction	434
11.2	Example: Divide by Zero without Exception Handling	435
11.3	Example: Handling <code>ArithmeticExceptions</code> and <code>InputMismatchExceptions</code>	437
11.4	When to Use Exception Handling	443
11.5	Java Exception Hierarchy	443
11.6	<code>finally</code> Block	446
11.7	Stack Unwinding and Obtaining Information from an Exception Object	451
11.8	Chained Exceptions	453
11.9	Declaring New Exception Types	456
11.10	Preconditions and Postconditions	457
11.11	Assertions	457
11.12	<code>try-with-Resources</code> : Automatic Resource Deallocation	459
11.13	Wrap-Up	459

12 GUI Components: Part I 465

12.1	Introduction	466
12.2	Java's Nimbus Look-and-Feel	467
12.3	Simple GUI-Based Input/Output with JOptionPane	468
12.4	Overview of Swing Components	471
12.5	Displaying Text and Images in a Window	473
12.6	Text Fields and an Introduction to Event Handling with Nested Classes	477
12.7	Common GUI Event Types and Listener Interfaces	483
12.8	How Event Handling Works	485
12.9	JButton	487
12.10	Buttons That Maintain State	490
	12.10.1 JCheckBox	491
	12.10.2 JRadioButton	493
12.11	JComboBox; Using an Anonymous Inner Class for Event Handling	496
12.12	JList	500
12.13	Multiple-Selection Lists	503
12.14	Mouse Event Handling	505
12.15	Adapter Classes	510
12.16	JPanel Subclass for Drawing with the Mouse	514
12.17	Key Event Handling	517
12.18	Introduction to Layout Managers	520
	12.18.1 FlowLayout	522
	12.18.2 BorderLayout	524
	12.18.3 GridLayout	528
12.19	Using Panels to Manage More Complex Layouts	530
12.20	JTextArea	531
12.21	Wrap-Up	534

13 Graphics and Java 2D 547

13.1	Introduction	548
13.2	Graphics Contexts and Graphics Objects	550
13.3	Color Control	551
13.4	Manipulating Fonts	558
13.5	Drawing Lines, Rectangles and Ovals	563
13.6	Drawing Arcs	567
13.7	Drawing Polygons and Polylines	570
13.8	Java 2D API	573
13.9	Wrap-Up	580

14 Strings, Characters and Regular Expressions 588

14.1	Introduction	589
14.2	Fundamentals of Characters and Strings	589
14.3	Class String	590
	14.3.1 String Constructors	590

14.3.2	String Methods <code>length</code> , <code>charAt</code> and <code>getChars</code>	591
14.3.3	Comparing Strings	592
14.3.4	Locating Characters and Substrings in Strings	597
14.3.5	Extracting Substrings from Strings	599
14.3.6	Concatenating Strings	600
14.3.7	Miscellaneous String Methods	600
14.3.8	String Method <code>valueOf</code>	602
14.4	Class <code>StringBuilder</code>	603
14.4.1	<code>StringBuilder</code> Constructors	604
14.4.2	<code>StringBuilder</code> Methods <code>length</code> , <code>capacity</code> , <code>setLength</code> and <code>ensureCapacity</code>	604
14.4.3	<code>StringBuilder</code> Methods <code>charAt</code> , <code>setCharAt</code> , <code>getChars</code> and <code>reverse</code>	606
14.4.4	<code>StringBuilder</code> <code>append</code> Methods	607
14.4.5	<code>StringBuilder</code> Insertion and Deletion Methods	609
14.5	Class <code>Character</code>	610
14.6	Tokenizing Strings	615
14.7	Regular Expressions, Class <code>Pattern</code> and Class <code>Matcher</code>	616
14.8	Wrap-Up	625

15 Files, Streams and Object Serialization 636

15.1	Introduction	637
15.2	Files and Streams	637
15.3	Using NIO Classes and Interfaces to Get File and Directory Information	639
15.4	Sequential-Access Text Files	643
15.4.1	Creating a Sequential-Access Text File	643
15.4.2	Reading Data from a Sequential-Access Text File	647
15.4.3	Case Study: A Credit-Inquiry Program	649
15.4.4	Updating Sequential-Access Files	653
15.5	Object Serialization	654
15.5.1	Creating a Sequential-Access File Using Object Serialization	655
15.5.2	Reading and Deserializing Data from a Sequential-Access File	660
15.6	Opening Files with <code>JFileChooser</code>	662
15.7	(Optional) Additional <code>java.io</code> Classes	665
15.7.1	Interfaces and Classes for Byte-Based Input and Output	665
15.7.2	Interfaces and Classes for Character-Based Input and Output	667
15.8	Wrap-Up	668

16 Generic Collections 676

16.1	Introduction	677
16.2	Collections Overview	677
16.3	Type-Wrapper Classes	679
16.4	Autoboxing and Auto-Unboxing	679
16.5	Interface <code>Collection</code> and Class <code>Collections</code>	679

16.6	Lists	680
16.6.1	ArrayList and Iterator	681
16.6.2	LinkedList	683
16.7	Collections Methods	688
16.7.1	Method sort	689
16.7.2	Method shuffle	692
16.7.3	Methods reverse, fill, copy, max and min	694
16.7.4	Method binarySearch	696
16.7.5	Methods addAll, frequency and disjoint	698
16.8	Stack Class of Package java.util	700
16.9	Class PriorityQueue and Interface Queue	702
16.10	Sets	703
16.11	Maps	706
16.12	Properties Class	710
16.13	Synchronized Collections	713
16.14	Unmodifiable Collections	713
16.15	Abstract Implementations	714
16.16	Wrap-Up	714

17 Java SE 8 Lambdas and Streams 721

17.1	Introduction	722
17.2	Functional Programming Technologies Overview	723
17.2.1	Functional Interfaces	724
17.2.2	Lambda Expressions	725
17.2.3	Streams	726
17.3	IntStream Operations	728
17.3.1	Creating an IntStream and Displaying Its Values with the forEach Terminal Operation	730
17.3.2	Terminal Operations count, min, max, sum and average	731
17.3.3	Terminal Operation reduce	731
17.3.4	Intermediate Operations: Filtering and Sorting IntStream Values	733
17.3.5	Intermediate Operation: Mapping	734
17.3.6	Creating Streams of ints with IntStream Methods range and rangeClosed	735
17.4	Stream<Integer> Manipulations	735
17.4.1	Creating a Stream<Integer>	736
17.4.2	Sorting a Stream and Collecting the Results	737
17.4.3	Filtering a Stream and Storing the Results for Later Use	737
17.4.4	Filtering and Sorting a Stream and Collecting the Results	737
17.4.5	Sorting Previously Collected Results	737
17.5	Stream<String> Manipulations	738
17.5.1	Mapping Strings to Uppercase Using a Method Reference	739
17.5.2	Filtering Strings Then Sorting Them in Case-Insensitive Ascending Order	740

17.5.3	Filtering Strings Then Sorting Them in Case-Insensitive Descending Order	740
17.6	Stream<Employee> Manipulations	740
17.6.1	Creating and Displaying a List<Employee>	742
17.6.2	Filtering Employees with Salaries in a Specified Range	743
17.6.3	Sorting Employees By Multiple Fields	744
17.6.4	Mapping Employees to Unique Last Name Strings	746
17.6.5	Grouping Employees By Department	747
17.6.6	Counting the Number of Employees in Each Department	748
17.6.7	Summing and Averaging Employee Salaries	748
17.7	Creating a Stream<String> from a File	750
17.8	Generating Streams of Random Values	753
17.9	Lambda Event Handlers	755
17.10	Additional Notes on Java SE 8 Interfaces	755
17.11	Java SE 8 and Functional Programming Resources	756
17.12	Wrap-Up	756

18 Recursion **768**

18.1	Introduction	769
18.2	Recursion Concepts	770
18.3	Example Using Recursion: Factorials	771
18.4	Reimplementing Class FactorialCalculator Using Class BigInteger	773
18.5	Example Using Recursion: Fibonacci Series	775
18.6	Recursion and the Method-Call Stack	778
18.7	Recursion vs. Iteration	779
18.8	Towers of Hanoi	781
18.9	Fractals	783
18.9.1	Koch Curve Fractal	783
18.9.2	(Optional) Case Study: Lo Feather Fractal	784
18.10	Recursive Backtracking	793
18.11	Wrap-Up	794

19 Searching, Sorting and Big O **802**

19.1	Introduction	803
19.2	Linear Search	804
19.3	Big O Notation	806
19.3.1	$O(1)$ Algorithms	806
19.3.2	$O(n)$ Algorithms	807
19.3.3	$O(n^2)$ Algorithms	807
19.3.4	Big O of the Linear Search	808
19.4	Binary Search	808
19.4.1	Binary Search Implementation	809
19.4.2	Efficiency of the Binary Search	812
19.5	Sorting Algorithms	812

19.6	Selection Sort	813
19.6.1	Selection Sort Implementation	813
19.6.2	Efficiency of the Selection Sort	816
19.7	Insertion Sort	816
19.7.1	Insertion Sort Implementation	817
19.7.2	Efficiency of the Insertion Sort	819
19.8	Merge Sort	819
19.8.1	Merge Sort Implementation	820
19.8.2	Efficiency of the Merge Sort	824
19.9	Big O Summary for This Chapter's Searching and Sorting Algorithms	825
19.10	Wrap-Up	826

20 Generic Classes and Methods 831

20.1	Introduction	832
20.2	Motivation for Generic Methods	832
20.3	Generic Methods: Implementation and Compile-Time Translation	834
20.4	Additional Compile-Time Translation Issues: Methods That Use a Type Parameter as the Return Type	837
20.5	Overloading Generic Methods	840
20.6	Generic Classes	841
20.7	Raw Types	848
20.8	Wildcards in Methods That Accept Type Parameters	852
20.9	Wrap-Up	856

21 Custom Generic Data Structures 861

21.1	Introduction	862
21.2	Self-Referential Classes	863
21.3	Dynamic Memory Allocation	863
21.4	Linked Lists	864
21.4.1	Singly Linked Lists	864
21.4.2	Implementing a Generic List Class	865
21.4.3	Generic Classes ListNode and List	870
21.4.4	Class ListTest	870
21.4.5	List Method insertAtFront	870
21.4.6	List Method insertAtBack	871
21.4.7	List Method removeFromFront	872
21.4.8	List Method removeFromBack	873
21.4.9	List Method print	874
21.4.10	Creating Your Own Packages	874
21.5	Stacks	878
21.6	Queues	882
21.7	Trees	885
21.8	Wrap-Up	892

22	GUI Components: Part 2	903
22.1	Introduction	904
22.2	JSlider	904
22.3	Understanding Windows in Java	908
22.4	Using Menus with Frames	909
22.5	JPopupMenu	917
22.6	Pluggable Look-and-Feel	920
22.7	JDesktopPane and JInternalFrame	925
22.8	JTabbedPane	928
22.9	BoxLayout Layout Manager	930
22.10	GridBagLayout Layout Manager	934
22.11	Wrap-Up	944
23	Concurrency	949
23.1	Introduction	950
23.2	Thread States and Life Cycle	952
23.2.1	<i>New</i> and <i>Runnable</i> States	953
23.2.2	<i>Waiting</i> State	953
23.2.3	<i>Timed Waiting</i> State	953
23.2.4	<i>Blocked</i> State	953
23.2.5	<i>Terminated</i> State	953
23.2.6	Operating-System View of the <i>Runnable</i> State	954
23.2.7	Thread Priorities and Thread Scheduling	954
23.2.8	Indefinite Postponement and Deadlock	955
23.3	Creating and Executing Threads with the Executor Framework	955
23.4	Thread Synchronization	959
23.4.1	Immutable Data	960
23.4.2	Monitors	960
23.4.3	Unsynchronized Mutable Data Sharing	961
23.4.4	Synchronized Mutable Data Sharing—Making Operations Atomic	966
23.5	Producer/Consumer Relationship without Synchronization	968
23.6	Producer/Consumer Relationship: ArrayBlockingQueue	976
23.7	(Advanced) Producer/Consumer Relationship with synchronized, wait, notify and notifyAll	979
23.8	(Advanced) Producer/Consumer Relationship: Bounded Buffers	986
23.9	(Advanced) Producer/Consumer Relationship: The Lock and Condition Interfaces	994
23.10	Concurrent Collections	1001
23.11	Multithreading with GUI: SwingWorker	1003
23.11.1	Performing Computations in a Worker Thread: Fibonacci Numbers	1004
23.11.2	Processing Intermediate Results: Sieve of Eratosthenes	1010
23.12	sort/parallelSort Timings with the Java SE 8 Date/Time API	1017
23.13	Java SE 8: Sequential vs. Parallel Streams	1019
23.14	(Advanced) Interfaces Callable and Future	1022

23.15 (Advanced) Fork/Join Framework	1026
23.16 Wrap-Up	1026

24 Accessing Databases with JDBC **1037**

24.1 Introduction	1038
24.2 Relational Databases	1039
24.3 A books Database	1040
24.4 SQL	1044
24.4.1 Basic SELECT Query	1044
24.4.2 WHERE Clause	1045
24.4.3 ORDER BY Clause	1047
24.4.4 Merging Data from Multiple Tables: INNER JOIN	1048
24.4.5 INSERT Statement	1050
24.4.6 UPDATE Statement	1051
24.4.7 DELETE Statement	1052
24.5 Setting up a Java DB Database	1052
24.5.1 Creating the Chapter's Databases on Windows	1053
24.5.2 Creating the Chapter's Databases on Mac OS X	1054
24.5.3 Creating the Chapter's Databases on Linux	1055
24.6 Manipulating Databases with JDBC	1055
24.6.1 Connecting to and Querying a Database	1055
24.6.2 Querying the books Database	1059
24.7 RowSet Interface	1072
24.8 PreparedStatement	1074
24.9 Stored Procedures	1090
24.10 Transaction Processing	1090
24.11 Wrap-Up	1091

25 JavaFX GUI: Part I **1099**

25.1 Introduction	1100
25.2 JavaFX Scene Builder and the NetBeans IDE	1101
25.3 JavaFX App Window Structure	1102
25.4 Welcome App—Displaying Text and an Image	1103
25.4.1 Creating the App's Project	1103
25.4.2 NetBeans Projects Window—Viewing the Project Contents	1105
25.4.3 Adding an Image to the Project	1106
25.4.4 Opening JavaFX Scene Builder from NetBeans	1106
25.4.5 Changing to a VBox Layout Container	1107
25.4.6 Configuring the VBox Layout Container	1108
25.4.7 Adding and Configuring a Label	1108
25.4.8 Adding and Configuring an ImageView	1108
25.4.9 Running the Welcome App	1109
25.5 Tip Calculator App—Introduction to Event Handling	1110
25.5.1 Test-Driving the Tip Calculator App	1111

25.5.2	Technologies Overview	1111
25.5.3	Building the App's GUI	1114
25.5.4	TipCalculator Class	1118
25.5.5	TipCalculatorController Class	1120
25.6	Features Covered in the Online JavaFX Chapters	1125
25.7	Wrap-Up	1126

Chapters on the Web **I 133**

A Operator Precedence Chart **I 135**

B ASCII Character Set **I 137**

C Keywords and Reserved Words **I 138**

D Primitive Types **I 139**

E Using the Debugger **I 140**

E.1	Introduction	1141
E.2	Breakpoints and the run, stop, cont and print Commands	1141
E.3	The print and set Commands	1145
E.4	Controlling Execution Using the step, step up and next Commands	1147
E.5	The watch Command	1150
E.6	The clear Command	1152
E.7	Wrap-Up	1154

Appendices on the Web **I 157**

Index **I 159**

Online Chapters and Appendices

Chapters 26–34 and Appendices F–N are PDF documents posted online at the book's Companion Website (located at www.pearsonhighered.com/deitel/). See the inside front cover for information on accessing the Companion Website.

26 JavaFX GUI: Part 2

27 JavaFX Graphics and Multimedia

28 Networking

- 29** Java Persistence API (JPA)
- 30** JavaServer™ Faces Web Apps: Part 1
- 31** JavaServer™ Faces Web Apps: Part 2
- 32** REST-Based Web Services
- 33** (Optional) ATM Case Study, Part 1:
Object-Oriented Design with the UML
- 34** (Optional) ATM Case Study, Part 2:
Implementing an Object-Oriented Design
- F** Using the Java API Documentation
- G** Creating Documentation with javadoc
- H** Unicode®
- I** Formatted Output
- J** Number Systems
- K** Bit Manipulation
- L** Labeled break and continue Statements
- M** UML 2: Additional Diagram Types
- N** Design Patterns

This page intentionally left blank



Foreword

I've been enamored with Java even prior to its 1.0 release in 1995, and have subsequently been a Java developer, author, speaker, teacher and Oracle Java Technology Ambassador. In this journey, it has been my privilege to call Paul Deitel a colleague, and to often leverage and recommend his *Java How To Program* book. In its many editions, this book has proven to be a great text for college and professional courses that I and others have developed to teach the Java programming language.

One of the qualities that makes this book a great resource is its thorough and insightful coverage of Java concepts, including those introduced recently in Java SE 8. Another useful quality is its treatment of concepts and practices essential to effective software development.

As a long-time fan of this book, I'd like to point out some of the features of this tenth edition about which I'm most excited:

- An ambitious new chapter on Java lambda expressions and streams. This chapter starts out with a primer on functional programming, introducing Java lambda expressions and how to use streams to perform functional programming tasks on collections.
- Although concurrency has been addressed since the first edition of the book, it is increasingly important because of multi-core architectures. There are timing examples—using the new Date/Time API classes introduced in Java SE 8—in the concurrency chapter that show the performance improvements with multi-core over single-core.
- JavaFX is Java's GUI/graphics/multimedia technology moving forward, so it is nice to see a three-chapter treatment of JavaFX in the Deitel live-code pedagogic style. One of these chapters is in the printed book and the other two are online.

Please join me in congratulating Paul and Harvey Deitel on their latest edition of a wonderful resource for computer science students and software developers alike!

James L. Weaver
Java Technology Ambassador
Oracle Corporation

This page intentionally left blank



Preface

“The chief merit of language is clearness...”

—Galen

Welcome to the Java programming language and *Java How to Program, Tenth Edition, Late Objects Version*! This book, which we call “Java Love,” presents leading-edge computing technologies for students, instructors and software developers. It’s appropriate for introductory academic and professional course sequences based on the curriculum recommendations of the ACM and the IEEE, and for AP Computer Science exam preparation. If you haven’t already done so, please read the back cover and inside back cover—these concisely capture the essence of the book. In this Preface we provide more detail.

We focus on software engineering best practices. At the heart of the book is the Deitel signature “live-code approach”—rather than using code snippets, we present concepts in the context of complete working programs that run on recent versions of Windows®, OS X® and Linux®. Each complete code example is accompanied by live sample executions.

Keeping in Touch with the Authors

As you read the book, if you have questions, send an e-mail to us at

deitel@deitel.com

and we’ll respond promptly. For updates on this book, visit

<http://www.deitel.com/books/jhtp10LOV>

subscribe to the *Deitel® Buzz Online* newsletter at

<http://www.deitel.com/newsletter/subscribe.html>

and join the Deitel social networking communities on

- Facebook® (<http://www.deitel.com/deitelfan>)
- Twitter® (@deitel)
- Google+™ (<http://google.com/+DeitelFan>)
- YouTube® (<http://youtube.com/DeitelTV>)
- LinkedIn® (<http://linkedin.com/company/deitel-&-associates>)

Source Code and VideoNotes

All the source code is available at:

<http://www.deitel.com/books/jhtp10LOV>

and at the book’s Companion Website (which also contains extensive VideoNotes):

<http://www.pearsonhighered.com/deitel>

Motivation for *Java How to Program, 10/e, Late Objects Version*

There are several approaches to teaching first courses in Java programming. The two most popular are the *late objects approach* and the *early objects approach*. To meet these diverse needs, we have published two versions of this book:

- *Java How to Program, 10/e, Late Objects Version*, and
- *Java How to Program, 10/e, Early Objects*

The key difference between these two editions is the order in which topics are presented in Chapters 1–7. The books have identical content from Chapters 8 to 31.

Chapters 1–6 in *Java How to Program, 10/e, Late Objects Version*, form the core of a pure-procedural programming CS1 course that covers operators, data types, input/output, control statements, methods and arrays. Instructors who want to cover some key material on strings early can present Sections 14.1–14.3 immediately after Chapter 6. Instructors who want to cover some key material on files early can present Sections 15.1–15.4 immediately after Chapter 6. Instructors who want to introduce *some* object-oriented programming in a first course can include some or all of Chapters 7–11 (see below).

Modular Organization¹

Java How to Program, 10/e, Late Objects Version, is appropriate for programming courses at various levels, most notably CS 1 and CS 2 courses and introductory course sequences in related disciplines. The book's modular organization helps instructors plan their syllabi:

Introduction

- Chapter 1, Introduction to Computers, the Internet and Java
- Chapter 2, Introduction to Java Applications; Input/Output and Operators

Additional Programming Fundamentals

- Chapter 3, Control Statements: Part 1; Assignment, ++ and -- Operators
- Chapter 4, Control Statements: Part 2; Logical Operators
- Chapter 5, Methods
- Chapter 6, Arrays and ArrayLists
- Chapter 14, Strings, Characters and Regular Expressions
- Chapter 15, Files, Streams and Object Serialization

Object-Oriented Programming and Object-Oriented Design

- Chapter 7, Introduction to Classes and Objects
- Chapter 8, Classes and Objects: A Deeper Look
- Chapter 9, Object-Oriented Programming: Inheritance
- Chapter 10, Object-Oriented Programming: Polymorphism and Interfaces
- Chapter 11, Exception Handling: A Deeper Look
- (Online optional module) Chapter 33, ATM Case Study, Part 1: Object-Oriented Design with the UML

1. The online chapters will be available on the book's Companion Website for Fall 2014 classes.

- (Online optional module) Chapter 34, ATM Case Study Part 2: Implementing an Object-Oriented Design

Swing Graphical User Interfaces and Java 2D Graphics

- Chapter 12, GUI Components: Part 1
- Chapter 13, Graphics and Java 2D
- Chapter 22, GUI Components: Part 2

Data Structures, Collections, Lambdas and Streams

- Chapter 16, Generic Collections
- Chapter 17, Java SE 8 Lambdas and Streams
- Chapter 18, Recursion
- Chapter 19, Searching, Sorting and Big O
- Chapter 20, Generic Classes and Methods
- Chapter 21, Custom Generic Data Structures

Concurrency; Networking

- Chapter 23, Concurrency
- (Online) Chapter 28, Networking

JavaFX Graphical User Interfaces, Graphics and Multimedia

- Chapter 25, JavaFX GUI: Part 1
- (Online) Chapter 26, JavaFX GUI: Part 2
- (Online) Chapter 27, JavaFX Graphics and Multimedia

Database-Driven Desktop and Web Development

- Chapter 24, Accessing Databases with JDBC
- (Online) Chapter 29, Java Persistence API (JPA)
- (Online) Chapter 30, JavaServer™ Faces Web Apps: Part 1
- (Online) Chapter 31, JavaServer™ Faces Web Apps: Part 2
- (Online) Chapter 32, REST-Based Web Services

New and Updated Features

Here are the updates we've made for *Java How to Program, 10/e, Late Objects Version*:

Java Standard Edition: Java SE 7 and the New Java SE 8

- *Easy to use with Java SE 7 or Java SE 8.* To meet the needs of our audiences, we designed the book for college and professional courses based on Java SE 7, Java SE 8 or a mixture of both. The Java SE 8 features are covered in optional, easy-to-include-or-omit sections. The new Java SE 8 capabilities can dramatically improve the programming process. Figure 1 lists some new Java SE 8 features that we cover.

Java SE 8 features
Lambda expressions
Type-inference improvements
@FunctionalInterface annotation
Parallel array sorting
Bulk data operations for Java Collections— <code>filter</code> , <code>map</code> and <code>reduce</code>
Library enhancements to support lambdas (e.g., <code>java.util.stream</code> , <code>java.util.function</code>)
Date & Time API (<code>java.time</code>)
Java concurrency API improvements
<code>static</code> and <code>default</code> methods in interfaces
Functional interfaces—interfaces that define only one abstract method and can include <code>static</code> and <code>default</code> methods
JavaFX enhancements

Fig. 1 | Some new Java SE 8 features.

- Java SE 8 lambdas, streams, and interfaces with **default** and **static** methods.*

The most significant new features in JavaSE 8 are lambdas and complementary technologies, which we cover in detail in the optional Chapter 17 and optional sections marked “Java SE 8” in later chapters. In Chapter 17, you’ll see that functional programming with lambdas and streams can help you write programs faster, more concisely, more simply, with fewer bugs and that are easier to parallelize (to get performance improvements on multi-core systems) than programs written with previous techniques. You’ll see that functional programming complements object-oriented programming. After you read Chapter 17, you’ll be able to cleverly reimplement many of the Java SE 7 examples throughout the book (Fig. 2).

Pre-Java-SE-8 topics	Corresponding Java SE 8 discussions and examples
Chapter 6, Arrays and ArrayLists	Sections 17.3—17.4 introduce basic lambda and streams capabilities that process one-dimensional arrays.
Chapter 10, Object-Oriented Programming: Polymorphism and Interfaces	Section 10.10 introduces the new Java SE 8 interface features (<code>default</code> methods, <code>static</code> methods and the concept of functional interfaces) that support functional programming with lambdas and streams.
Chapters 12 and 22, GUI Components: Part 1 and 2, respectively	Section 17.9 shows how to use a lambda to implement a Swing event-listener functional interface.
Chapter 14, Strings, Characters and Regular Expressions	Section 17.5 shows how to use lambdas and streams to process collections of <code>String</code> objects.

Fig. 2 | Java SE 8 lambdas and streams discussions and examples. (Part 1 of 2.)

Pre-Java-SE-8 topics	Corresponding Java SE 8 discussions and examples
Chapter 15, Files, Streams and Object Serialization	Section 17.7 shows how to use lambdas and streams to process lines of text from a file.
Chapter 23, Concurrency	Shows that functional programs are easier to parallelize so that they can take advantage of multi-core architectures to enhance performance. Demonstrates parallel stream processing. Shows that Arrays method <code>parallelSort</code> improves performance on multi-core architectures when sorting large arrays.
Chapter 25, JavaFX GUI: Part 1	Section 25.5.5 shows how to use a lambda to implement a JavaFX event-listener functional interface.

Fig. 2 | Java SE 8 lambdas and streams discussions and examples. (Part 2 of 2.)

- **Java SE 7's *try-with-resources* statement and the *AutoClosable* Interface.** `AutoClosable` objects reduce the likelihood of resource leaks when you use them with the *try-with-resources* statement, which automatically closes the `AutoClosable` objects. In this edition, we use *try-with-resources* and `AutoClosable` objects as appropriate starting in Chapter 15, Files, Streams and Object Serialization.
- **Java security.** We audited our book against the CERT Oracle Secure Coding Standard for Java as appropriate for an introductory textbook.

<http://bit.ly/CERTOracleSecureJava>

See the Secure Java Programming section of this Preface for more information about CERT.

- **Java NIO API.** We updated the file-processing examples in Chapter 15 to use features from the Java NIO (new IO) API.
- **Java Documentation.** Throughout the book, we provide links to Java documentation where you can learn more about various topics that we present. For Java SE 7 documentation, the links begin with

<http://docs.oracle.com/javase/7/>

and for Java SE 8 documentation, the links begin with

<http://download.java.net/jdk8/>

These links could change when Oracle releases Java SE 8—*possibly* to links beginning with

<http://docs.oracle.com/javase/8/>

For any links that change after publication, we'll post updates at

<http://www.deitel.com/books/jhttp10LOV>

Swing and JavaFX GUI, Graphics and Multimedia

- **Swing GUI and Java 2D graphics.** Java's Swing GUI is discussed in the optional GUI and graphics sections in Chapters 2–6 and 8–10, and in Chapters 12 and

22. Swing is now in maintenance mode—Oracle has stopped development and will provide only bug fixes going forward, however it will remain part of Java and is still widely used. Chapter 13 discusses Java 2D graphics.

- *JavaFX GUI, graphics and multimedia.* Java’s GUI, graphics and multimedia API going forward is JavaFX. In Chapter 25, we use JavaFX 2.2 (released in 2012) with Java SE 7. Our online Chapters 26 and 27—located on the book’s companion website (see the inside front cover of this book)—present additional JavaFX GUI features and introduce JavaFX graphics and multimedia in the context of Java FX 8 and Java SE 8. In Chapters 25–27 we use Scene Builder—a drag-and-drop tool for creating JavaFX GUIs quickly and conveniently. It’s a standalone tool that you can use separately or with any of the Java IDEs.
- *Scalable GUI and graphics presentation.* Instructors teaching introductory courses have a broad choice of the amount of GUI, graphics and multimedia to cover—from none at all, to optional introductory sections in the early chapters, to a deep treatment of Swing GUI and Java 2D graphics in Chapters 12, 13 and 22, and a deep treatment of JavaFX GUI, graphics and multimedia in Chapter 25 and online Chapters 26–27.

Concurrency

- *Concurrency for optimal multi-core performance.* In this edition, we were privileged to have as a reviewer Brian Goetz, co-author of *Java Concurrency in Practice* (Addison-Wesley). We updated Chapter 23, with Java SE 8 technology and idiom. We added a `parallelSort` vs. `sort` example that uses the Java SE 8 `Date/Time` API to time each operation and demonstrate `parallelSort`’s better performance on a multi-core system. We include a Java SE 8 `parallel` vs. `sequential` stream processing example, again using the `Date/Time` API to show performance improvements. Finally, we added a Java SE 8 `CompletableFuture` example that demonstrates sequential and parallel execution of long-running calculations.
- *SwingWorker class.* We use class `SwingWorker` to create multithreaded user interfaces. In online Chapter 26, we show how JavaFX handles concurrency.
- *Concurrency is challenging.* Programming concurrent applications is difficult and error-prone. There’s a great variety of concurrency features. We point out the ones that most people should use and mention those that should be left to the experts.

Getting Monetary Amounts Right

- *Monetary amounts.* In the early chapters, for convenience, we use type `double` to represent monetary amounts. Due to the potential for incorrect monetary calculations with type `double`, class `BigDecimal` (which is a bit more complex) should be used to represent monetary amounts. We demonstrate `BigDecimal` in Chapters 8 and 25.

Object Technology

- *Object-oriented programming and design.* We use a *late objects* approach, covering programming fundamentals such as data types, variables, operators, control

statements, methods and arrays in the early chapters. Then students develop their first customized classes and objects in Chapter 7. [For courses that require an early-objects approach, consider *Java How to Program, 10/e, Early Objects*.]

- ***Real-world case studies.*** The object-oriented programing presentation features Account, Time, Employee, GradeBook and Card shuffling-and-dealing case studies.
- ***Inheritance, Interfaces, Polymorphism and Composition.*** We use a series of real-world case studies to illustrate these OO concepts and explain situations in which each is preferred in building industrial-strength applications.
- ***Exception handling.*** We integrate basic exception handling early in the book then present a deeper treatment in Chapter 11. Exception handling is important for building “mission-critical” and “business-critical” applications. Programmers need to be concerned with, “What happens when the component I call on to do a job experiences difficulty? How will that component signal that it had a problem?” To use a Java component, you need to know not only how that component behaves when “things go well,” but also what exceptions that component “throws” when “things go poorly.”
- ***Class Arrays and ArrayList.*** Chapter 6 covers class Arrays—which contains methods for performing common array manipulations—and class ArrayList—which implements a dynamically resizable array-like data structure. The chapter’s rich selection of exercises includes a substantial project on building your own computer through the technique of software simulation. The Chapter 21 exercises include a follow-on project on building your own compiler that can compile high-level language programs into machine language code that will execute on your computer simulator.
- ***Optional Online Case Study: Developing an Object-Oriented Design and Java Implementation of an ATM.*** Online Chapters 33–34 include an *optional* case study on object-oriented design using the UML (Unified Modeling Language™)—the industry-standard graphical language for modeling object-oriented systems. We design and implement the software for a simple automated teller machine (ATM). We analyze a typical requirements document that specifies the system to be built. We determine the classes needed to implement that system, the attributes the classes need to have, the behaviors the classes need to exhibit and specify how the classes must interact with one another to meet the system requirements. From the design we produce a complete Java implementation. Students often report having a “light-bulb moment”—the case study helps them “tie it all together” and really understand object orientation.

Data Structures and Generic Collections

- ***Data structures presentation.*** We begin with generic class ArrayList in Chapter 6. Our later data structures discussions (Chapters 16–21) provide a deeper treatment of generic collections—showing how to use the built-in collections of the Java API. We discuss recursion, which is important for implementing tree-like, data-structure classes. We discuss popular searching and sorting algorithms for manipulating the contents of collections, and provide a friendly introduction to Big O—a means of describing how hard an algorithm might have to work to solve a problem. We then

show how to implement generic methods and classes, and *custom* generic data structures (this is intended for computer-science majors—most programmers should use the pre-built generic collections). Lambdas and streams (introduced in Chapter 17) are especially useful for working with generic collections.

Database

- **JDBC.** Chapter 24 covers JDBC and uses the Java DB database management system. The chapter introduces Structured Query Language (SQL) and features an OO case study on developing a database-driven address book that demonstrates PreparedStatements.
- **Java Persistence API.** The new online Chapter 29 covers the Java Persistence API (JPA)—a standard for object relational mapping (ORM) that uses JDBC “under the hood.” ORM tools can look at a database’s schema and generate a set of classes that enabled you to interact with a database without having to use JDBC and SQL directly. This speeds database-application development, reduces errors and produces more portable code.

Web Application Development

- **Java Server Faces (JSF).** Online Chapters 30–31 have been updated to introduce the latest JavaServer Faces (JSF) technology for building web-based applications. Chapter 30 includes examples on building web application GUIs, validating forms and session tracking. Chapter 31 discusses data-driven, Ajax-enabled JSF applications—the chapter features a database-driven multitier web address book that allows users to add and search for contacts.
- **Web services.** Chapter 32 now concentrates on creating and consuming REST-based web services. The vast majority of today’s web services now use REST.

Secure Java Programming

It’s difficult to build industrial-strength systems that stand up to attacks from viruses, worms, and other forms of “malware.” Today, via the Internet, such attacks can be instantaneous and global in scope. Building security into software from the beginning of the development cycle can greatly reduce vulnerabilities. We incorporate various secure Java coding practices (as appropriate for an introductory textbook) into our discussions and code examples.

The CERT[®] Coordination Center (www.cert.org) was created to analyze and respond promptly to attacks. CERT—the Computer Emergency Response Team—is a government-funded organization within the Carnegie Mellon University Software Engineering Institute[™]. CERT publishes and promotes secure coding standards for various popular programming languages to help software developers implement industrial-strength systems that avoid the programming practices which leave systems open to attack.

We’d like to thank Robert C. Seacord, Secure Coding Manager at CERT and an adjunct professor in the Carnegie Mellon University School of Computer Science. Mr. Seacord was a technical reviewer for our book, *C How to Program, 7/e*, where he scrutinized our C programs from a security standpoint, recommending that we adhere to the *CERT C Secure Coding Standard*. This experience influenced our coding practices in *C++ How to Program, 9/e* and *Java How to Program, 10/e, Late Objects Version* as well.

Optional GUI and Graphics Case Study

Students enjoy building GUI and graphics applications. For courses that introduce GUI and graphics early, we've integrated an optional 10-segment introduction to creating graphics and Swing-based graphical user interfaces (GUIs). The goal of this case study is to create a simple polymorphic drawing application in which the user can select a shape to draw, select the characteristics of the shape (such as its color) and use the mouse to draw the shape. The case study builds gradually toward that goal, with the reader implementing polymorphic drawing in Chapter 10, adding an event-driven GUI in Chapter 12 and enhancing the drawing capabilities in Chapter 13 with Java 2D.

- Section 2.9—Using Dialog Boxes
- Section 3.14—Creating Simple Drawings
- Section 4.10—Drawing Rectangles and Ovals
- Section 5.13—Colors and Filled Shapes
- Section 6.14—Drawing Arcs
- Section 8.16—Using Objects with Graphics
- Section 9.7—Displaying Text and Images Using Labels
- Section 10.11—Drawing with Polymorphism
- Exercise 12.17—Expanding the Interface
- Exercise 13.31—Adding Java2D

Teaching Approach

Java How to Program, 10/e, Late Objects Version contains hundreds of complete working examples. We stress program clarity and concentrate on building well-engineered software.

VideoNotes. The Companion Website includes extensive VideoNotes in which co-author Paul Deitel explains in detail most of the programs in the book's core chapters. Students like viewing the VideoNotes for reinforcement of core concepts and for additional insights.

Syntax Shading. For readability, we syntax shade all the Java code, similar to the way most Java integrated-development environments and code editors syntax color code. Our syntax-shading conventions are as follows:

comments appear in light gray like this
keywords appear bold black like this
 constants and literal values appear in bold dark gray like this
 all other code appears in black like this

Code Highlighting. We place gray rectangles around key code segments.

Using Fonts for Emphasis. We place the key terms and the index's page reference for each defining occurrence in **bold** text for easier reference. We emphasize on-screen components in the **bold Helvetica** font (e.g., the **File** menu) and emphasize Java program text in the **Lucida** font (for example, `int x = 5;`).

Web Access. All of the source-code examples can be downloaded from:

<http://www.deitel.com/books/jhttp10LOV>
<http://www.pearsonhighered.com/deitel>

Objectives. The opening quotes are followed by a list of chapter objectives.

Illustrations/Figures. Abundant tables, line drawings, UML diagrams, programs and program outputs are included.

Programming Tips. We include programming tips to help you focus on important aspects of program development. These tips and practices represent the best we've gleaned from a combined seven decades of programming and teaching experience.



Good Programming Practice

The Good Programming Practices call attention to techniques that will help you produce programs that are clearer, more understandable and more maintainable.



Common Programming Error

Pointing out these Common Programming Errors reduces the likelihood that you'll make them.



Error-Prevention Tip

These tips contain suggestions for exposing bugs and removing them from your programs; many describe aspects of Java that prevent bugs from getting into programs in the first place.



Performance Tip

These tips highlight opportunities for making your programs run faster or minimizing the amount of memory that they occupy.



Portability Tip

The Portability Tips help you write code that will run on a variety of platforms.



Software Engineering Observation

The Software Engineering Observations highlight architectural and design issues that affect the construction of software systems, especially large-scale systems.



Look-and-Feel Observation

The Look-and-Feel Observations highlight graphical-user-interface conventions. These observations help you design attractive, user-friendly graphical user interfaces that conform to industry norms.

Summary Bullets. We present a section-by-section bullet-list summary of the chapter. For ease of reference, we include the page number of each key term's defining occurrence in the text.

Self-Review Exercises and Answers. Extensive self-review exercises and answers are included for self study. All of the exercises in the optional ATM case study are fully solved.

Exercises. The chapter exercises include:

- simple recall of important terminology and concepts
- What’s wrong with this code?
- What does this code do?
- writing individual statements and small portions of methods and classes
- writing complete methods, classes and programs
- major projects
- in many chapters, Making a Difference exercises that encourage you to use computers and the Internet to research and solve significant social problems.

Exercises that are purely SE 8 are marked as such. Check out our Programming Projects Resource Center for lots of additional exercise and project possibilities (www.deitel.com/ProgrammingProjects/).

Index. We’ve included an extensive index. Defining occurrences of key terms are highlighted with a **bold** page number. The print book index mentions only those terms used in the print book. The online chapters index includes all the print book terms and the online chapter terms.

Software Used in Java How to Program, 10/e, Late Objects Version

All the software you’ll need for this book is available free for download from the Internet. See the Before You Begin section that follows this Preface for links to each download.

We wrote most of the examples in *Java How to Program, 10/e, Late Objects Version*, using the free Java Standard Edition Development Kit (JDK) 7. For the optional Java SE 8 modules, we used the OpenJDK’s early access version of JDK 8. In Chapter 25 and several online chapters, we also used the Netbeans IDE. See the Before You Begin section that follows this Preface for more information.

Instructor Supplements

The following supplements are available to qualified instructors only through Pearson Education’s Instructor Resource Center (www.pearsonhighered.com/irc):

- *PowerPoint® slides* containing all the code and figures in the text, plus bulleted items that summarize key points.
- *Test Item File* of multiple-choice questions (approximately two per book section).
- *Solutions Manual* with solutions to the vast majority of the end-of-chapter exercises. Check the IRC to determine the exercises for which we provide solutions.

Please do not write to us requesting access to the Pearson Instructor’s Resource Center which contains the book’s instructor supplements, including the exercise solutions. Access is limited strictly to college instructors teaching from the book. Instructors may obtain access only through their Pearson representatives. Solutions are *not* provided for “project” exercises.

If you're not a registered faculty member, contact your Pearson representative or visit www.pearsonhighered.com/educator/replocator/.

Acknowledgments

We'd like to thank Abbey Deitel and Barbara Deitel for long hours devoted to this project. We're fortunate to have worked on this project with the dedicated team of publishing professionals at Pearson. We appreciate the guidance, wisdom and energy of Tracy Johnson, Executive Editor, Computer Science. Tracy and her team handle all of our academic textbooks. Carole Snyder recruited the book's academic reviewers and managed the review process. Bob Engelhardt managed the book's publication. We selected the cover art and Laura Gardner designed the cover.

Reviewers

We wish to acknowledge the efforts of our recent editions reviewers—a distinguished group of academics, Oracle Java team members, Oracle Java Champions and other industry professionals. They scrutinized the text and the programs and provided countless suggestions for improving the presentation.

Tenth Edition reviewers: Lance Andersen (Oracle Corporation), Dr. Danny Coward (Oracle Corporation), Brian Goetz (Oracle Corporation), Evan Golub (University of Maryland), Dr. Huiwei Guan (Professor, Department of Computer & Information Science, North Shore Community College), Manfred Riem (Java Champion), Simon Ritter (Oracle Corporation), Robert C. Seacord (CERT, Software Engineering Institute, Carnegie Mellon University), Khallai Taylor (Assistant Professor, Triton College and Adjunct Professor, LoneStar College—Kingwood), Jorge Vargas (Yumbling and a Java Champion), Johan Vos (LodgON, co-author of *Pro JavaFX 2* and Oracle Java Champion) and James L. Weaver (Oracle Corporation and co-author of *Pro JavaFX 2*).

Previous editions reviewers: Soundararajan Angusamy (Sun Microsystems), Joseph Bowbeer (Consultant), William E. Duncan (Louisiana State University), Diana Franklin (University of California, Santa Barbara), Edward F. Gehringer (North Carolina State University), Ric Heishman (George Mason University), Dr. Heinz Kabutz (JavaSpecialists.eu), Patty Kraft (San Diego State University), Lawrence Premkumar (Sun Microsystems), Tim Margush (University of Akron), Sue McFarland Metzger (Villanova University), Shyamal Mitra (The University of Texas at Austin), Peter Pilgrim (Consultant), Manjeet Rege, Ph.D. (Rochester Institute of Technology), Susan Rodger (Duke University), Amr Sabry (Indiana University), José Antonio González Seco (Parliament of Andalusia), Sang Shin (Sun Microsystems), S. Sivakumar (Astra Infotech Private Limited), Raghavan “Rags” Srinivas (Intuit), Monica Sweat (Georgia Tech), Vinod Varma (Astra Infotech Private Limited) and Alexander Zuev (Sun Microsystems).

A Special Thank You to Brian Goetz

We were privileged to have Brian Goetz, Oracle's Java Language Architect and Specification Lead for Java SE 8's Project Lambda, and co-author of *Java Concurrency in Practice*, do a detailed full-book review. He thoroughly scrutinized every chapter, providing extremely helpful insights and constructive comments. Any remaining faults in the book are our own.

Well, there you have it! As you read the book, we'd appreciate your comments, criticisms, corrections and suggestions for improvement. Please address all correspondence to:

`deitel@deitel.com`

We'll respond promptly. We hope you enjoy working with *Java How to Program, 10/e, Late Objects Version* as much as we enjoyed writing it!

Paul and Harvey Deitel

About the Authors



Paul Deitel, CEO and Chief Technical Officer of Deitel & Associates, Inc., is a graduate of MIT, where he studied Information Technology. He holds the Java Certified Programmer and Java Certified Developer designations, and is an Oracle Java Champion. Through Deitel & Associates, Inc., he has delivered hundreds of programming courses worldwide to clients, including Cisco, IBM, Siemens, Sun Microsystems, Dell, Fidelity, NASA at the Kennedy Space Center, the National Severe Storm Laboratory, White Sands Missile Range, Rogue Wave Software, Boeing, SunGard Higher Education, Nortel Networks, Puma, iRobot, Invensys and many more. He and his co-author, Dr. Harvey M. Deitel, are the world's best-selling programming-language textbook/professional book/video authors.

Dr. Harvey Deitel, Chairman and Chief Strategy Officer of Deitel & Associates, Inc., has over 50 years of experience in the computer field. Dr. Deitel earned B.S. and M.S. degrees in Electrical Engineering from MIT and a Ph.D. in Mathematics from Boston University. He has extensive college teaching experience, including earning tenure and serving as the Chairman of the Computer Science Department at Boston College before founding Deitel & Associates, Inc., in 1991 with his son, Paul. The Deitels' publications have earned international recognition, with translations published in Japanese, German, Russian, Spanish, French, Polish, Italian, Simplified Chinese, Traditional Chinese, Korean, Portuguese, Greek, Urdu and Turkish. Dr. Deitel has delivered hundreds of programming courses to corporate, academic, government and military clients.

About Deitel® & Associates, Inc.

Deitel & Associates, Inc., founded by Paul Deitel and Harvey Deitel, is an internationally recognized authoring and corporate training organization, specializing in computer programming languages, object technology, mobile app development and Internet and web software technology. The company's training clients include many of the world's largest companies, government agencies, branches of the military and academic institutions. The company offers instructor-led training courses delivered at client sites worldwide on major programming languages and platforms, including Java™, Android app development, Objective-C and iOS app development, C++, C, Visual C#®, Visual Basic®, Visual C++®, Python®, object technology, Internet and web programming and a growing list of additional programming and software development courses.

Through its 39-year publishing partnership with Pearson/Prentice Hall, Deitel & Associates, Inc., publishes leading-edge programming textbooks and professional books in print and a wide range of e-book formats, and *LiveLessons* video courses. Deitel & Associates, Inc. and the authors can be reached at:

`deitel@deitel.com`

To learn more about Deitel's *Dive-Into*® *Series* Corporate Training curriculum, visit:

`http://www.deitel.com/training`

To request a proposal for worldwide on-site, instructor-led training at your organization, e-mail `deitel@deitel.com`.

Individuals wishing to purchase Deitel books and *LiveLessons* video training can do so through `www.deitel.com`. Bulk orders by corporations, the government, the military and academic institutions should be placed directly with Pearson. For more information, visit

`http://www.informit.com/store/sales.aspx`



Before You Begin

This section contains information you should review before using this book. Any updates to the information presented here will be posted at:

<http://www.deitel.com/books/jhttp10LOV>

In addition, we provide Dive-Into® videos (which will be available in time for Fall 2014 classes) that demonstrate the instructions in this Before You Begin section.

Font and Naming Conventions

We use fonts to distinguish between on-screen components (such as menu names and menu items) and Java code or commands. Our convention is to emphasize on-screen components in a sans-serif bold **Helvetica** font (for example, **File** menu) and to emphasize Java code and commands in a sans-serif *Lucida* font (for example, `System.out.println()`).

Software Used in the Book

All the software you'll need for this book is available free for download from the web. With the exception of the examples that are specific to Java SE 8, all of the examples were tested with the Java SE 7 and Java SE 8 Java Standard Edition Development Kits (JDKs).

Java Standard Edition Development Kit 7 (JDK 7)

JDK 7 for Windows, OS X and Linux platforms is available from:

<http://www.oracle.com/technetwork/java/javase/downloads/index.html>

Java Standard Edition Development Kit (JDK) 8

At the time of this publication, the near-final version of JDK 8 for Windows, OS X and Linux platforms was available from:

<https://jdk8.java.net/download.html>

Once JDK 8 is released as final, it will be available from:

<http://www.oracle.com/technetwork/java/javase/downloads/index.html>

JDK Installation Instructions

After downloading the JDK installer, be sure to carefully follow the JDK installation instructions for your platform at:

<http://docs.oracle.com/javase/7/docs/webnotes/install/index.html>

Though these instructions are for JDK 7, they also apply to JDK 8—you'll need to update the JDK version number in any version-specific instructions.

Setting the PATH Environment Variable

The PATH environment variable on your computer designates which directories the computer searches when looking for applications, such as the applications that enable you to compile and run your Java applications (called `javac` and `java`, respectively). *Carefully follow the installation instructions for Java on your platform to ensure that you set the PATH environment variable correctly.* The steps for setting environment variables differ by operating system and sometimes by operating system version (e.g., Windows 7 vs. Windows 8). Instructions for various platforms are listed at:

<http://www.java.com/en/download/help/path.xml>

If you do not set the PATH variable correctly on Windows and some Linux installations, when you use the JDK's tools, you'll receive a message like:

```
'java' is not recognized as an internal or external command,
operable program or batch file.
```

In this case, go back to the installation instructions for setting the PATH and recheck your steps. If you've downloaded a newer version of the JDK, you may need to change the name of the JDK's installation directory in the PATH variable.

*JDK Installation Directory and the **bin** Subdirectory*

The JDK's installation directory varies by platform. The directories listed below are for Oracle's JDK 7 update 51:

- 32-bit JDK on Windows:
C:\Program Files (x86)\Java\jdk1.7.0_51
- 64-bit JDK on Windows:
C:\Program Files\Java\jdk1.7.0_51
- Mac OS X:
/Library/Java/JavaVirtualMachines/jdk1.7.0_51.jdk/Contents/Home
- Ubuntu Linux:
/usr/lib/jvm/java-7-oracle

Depending on your platform, the JDK installation folder's name might differ if you're using a different update of JDK 7 or using JDK 8. For Linux, the install location depends on the installer you use and possibly the version of Linux that you use. We used Ubuntu Linux. The PATH environment variable must point to the JDK installation directory's **bin** subdirectory.

When setting the PATH, be sure to use the proper JDK-installation-directory name for the specific version of the JDK you installed—as newer JDK releases become available, the JDK-installation-directory name changes to include an *update version number*. For example, at the time of this writing, the most recent JDK 7 release was update 51. For this version, the JDK-installation-directory name ends with "_51".

Setting the CLASSPATH Environment Variable

If you attempt to run a Java program and receive a message like

```
Exception in thread "main" java.lang.NoClassDefFoundError: YourClass
```

then your system has a CLASSPATH environment variable that must be modified. To fix the preceding error, follow the steps in setting the PATH environment variable, to locate the CLASSPATH variable, then edit the variable's value to include the local directory—typically represented as a dot (.). On Windows add

```
.;
```

at the beginning of the CLASSPATH's value (with no spaces before or after these characters). On other platforms, replace the semicolon with the appropriate path separator characters—typically a colon (:).

Setting the JAVA_HOME Environment Variable

The Java DB database software that you'll use in Chapter 24 and several online chapters requires you to set the JAVA_HOME environment variable to your JDK's installation directory. The same steps you used to set the PATH may also be used to set other environment variables, such as JAVA_HOME.

Java Integrated Development Environments (IDEs)

There are many Java integrated development environments that you can use for Java programming. For this reason, we used only the JDK command-line tools for most of the book's examples. We provide Dive-Into® videos (which will be available in time for Fall 2014 classes) that show how to download, install and use three popular IDEs—NetBeans, Eclipse and IntelliJ IDEA. We use NetBeans in Chapter 25 and several of the book's online chapters.

NetBeans Downloads

You can download the JDK/NetBeans bundle from:

```
http://www.oracle.com/technetwork/java/javase/downloads/index.html
```

The NetBeans version that's bundled with the JDK is for Java SE development. The online JavaServer Faces (JSF) chapters and web services chapter use the Java Enterprise Edition (Java EE) version of NetBeans, which you can download from:

```
https://netbeans.org/downloads/
```

This version supports both Java SE and Java EE development.

Eclipse Downloads

You can download the Eclipse IDE from:

```
https://www.eclipse.org/downloads/
```

For Java SE development choose the Eclipse IDE for Java Developers. For Java Enterprise Edition (Java EE) development (such as JSF and web services), choose the Eclipse IDE for Java EE Developers—this version supports both Java SE and Java EE development.

IntelliJ IDEA Community Edition Downloads

You can download the free IntelliJ IDEA Community Edition from:

```
http://www.jetbrains.com/idea/download/index.html
```

The free version supports only Java SE development.

Obtaining the Code Examples

The examples for *Java How to Program, 10/e, Late Objects Version* are available for download at

<http://www.deitel.com/books/jhttp10LOV/>

under the heading **Download Code Examples and Other Premium Content**. The examples are also available from

<http://www.pearsonhighered.com/deitel>

When you download the ZIP archive file, write down the location where you choose to save it on your computer.

Extract the contents of `examples.zip` using a ZIP extraction tool such as 7-Zip (www.7-zip.org), WinZip (www.winzip.com) or the built-in capabilities of your operating system. Instructions throughout the book assume that the examples are located at:

- `C:\examples` on Windows
- your user account home folder's `examples` subfolder on Linux
- your Documents folders `examples` subfolder on Mac OS X

Java's Nimbus Look-and-Feel

Java comes bundled with a cross-platform look-and-feel known as Nimbus. For programs with Swing graphical user interfaces (e.g., Chapters 12 and 22), we configured our test computers to use Nimbus as the default look-and-feel.

To set Nimbus as the default for all Java applications, you must create a text file named `swing.properties` in the `lib` folder of both your JDK installation folder and your JRE installation folder. Place the following line of code in the file:

```
swing.defaultlaf=com.sun.java.swing.plaf.nimbus.NimbusLookAndFeel
```

For more information on locating these folders visit <http://docs.oracle.com/javase/7/docs/webnotes/install/index.html>. [*Note:* In addition to the standalone JRE, there's a JRE nested in your JDK's installation folder. If you're using an IDE that depends on the JDK (e.g., NetBeans), you may also need to place the `swing.properties` file in the nested `jre` folder's `lib` folder.]

You're now ready to begin your Java studies with *Java How to Program, 10/e, Late Objects Version*. We hope you enjoy the book!

Introduction to Computers, the Internet and Java

I



Man is still the most extraordinary computer of all.

—John F. Kennedy

Good design is good business.

—Thomas J. Watson, Founder of IBM

Objectives

In this chapter you'll:

- Learn about exciting recent developments in the computer field.
- Learn computer hardware, software and networking basics.
- Understand the data hierarchy.
- Understand the different types of programming languages.
- Understand the importance of Java and other leading programming languages.
- Understand object-oriented programming basics.
- Learn the importance of the Internet and the web.
- Learn a typical Java program-development environment.
- Test-drive a Java application.
- Learn some key recent software technologies.
- See how to keep up-to-date with information technologies.

- 1.1 Introduction
- 1.2 Hardware and Software
 - 1.2.1 Moore's Law
 - 1.2.2 Computer Organization
- 1.3 Data Hierarchy
- 1.4 Machine Languages, Assembly Languages and High-Level Languages
- 1.5 Introduction to Object Technology
 - 1.5.1 The Automobile as an Object
 - 1.5.2 Methods and Classes
 - 1.5.3 Instantiation
 - 1.5.4 Reuse
 - 1.5.5 Messages and Method Calls
 - 1.5.6 Attributes and Instance Variables
 - 1.5.7 Encapsulation and Information Hiding
 - 1.5.8 Inheritance
 - 1.5.9 Interfaces
 - 1.5.10 Object-Oriented Analysis and Design (OOAD)
 - 1.5.11 The UML (Unified Modeling Language)
- 1.6 Operating Systems
 - 1.6.1 Windows—A Proprietary Operating System
 - 1.6.2 Linux—An Open-Source Operating System
 - 1.6.3 Android
- 1.7 Programming Languages
- 1.8 Java
- 1.9 A Typical Java Development Environment
- 1.10 Test-Driving a Java Application
- 1.11 Internet and World Wide Web
 - 1.11.1 The Internet: A Network of Networks
 - 1.11.2 The World Wide Web: Making the Internet User-Friendly
 - 1.11.3 Web Services and Mashups
 - 1.11.4 Ajax
 - 1.11.5 The Internet of Things
- 1.12 Software Technologies
- 1.13 Keeping Up-to-Date with Information Technologies

Self-Review Exercises | Answers to Self-Review Exercises | Exercises | Making a Difference

1.1 Introduction

Welcome to Java—one of the world's most widely used computer programming languages. You're already familiar with the powerful tasks computers perform. Using this textbook, you'll write instructions commanding computers to perform those tasks. **Software** (i.e., the instructions you write) controls **hardware** (i.e., computers).

You'll learn *object-oriented programming*—today's key programming methodology. You'll create and work with many *software objects*.

For many organizations, the preferred language for meeting their enterprise programming needs is Java. Java is also widely used for implementing Internet-based applications and software for devices that communicate over a network.

Forrester Research predicts more than two billion PCs will be in use by 2015.¹ According to Oracle, 97% of enterprise desktops, 89% of PC desktops, three billion devices (Fig. 1.1) and 100% of all Blu-ray Disc™ players run Java, and there are over 9 million Java developers.²

According to a study by Gartner, mobile devices will continue to outpace PCs as users' primary computing devices; an estimated 1.96 billion smartphones and 388 million tablets will be shipped in 2015—8.7 times the number of PCs.³ By 2018, the mobile applications

1. <http://www.worldometers.info/computers>.

2. <http://www.oracle.com/technetwork/articles/java/javaone12review-1863742.html>.

3. <http://www.gartner.com/newsroom/id/2645115>.

Devices		
Airplane systems	ATMs	Automobile infotainment systems
Blu-ray Disc™ players	Cable boxes	Copiers
Credit cards	CT scanners	Desktop computers
e-Readers	Game consoles	GPS navigation systems
Home appliances	Home security systems	Light switches
Lottery terminals	Medical devices	Mobile phones
MRIs	Parking payment stations	Printers
Transportation passes	Robots	Routers
Smart cards	Smart meters	Smartpens
Smartphones	Tablets	Televisions
TV set-top boxes	Thermostats	Vehicle diagnostic systems

Fig. 1.1 | Some devices that use Java.

(apps) market is expected to reach \$92 billion.⁴ This is creating significant career opportunities for people who program mobile applications, many of which are programmed in Java (see Section 1.6.3).

Java Standard Edition

Java has evolved so rapidly that this tenth edition of *Java How to Program*—based on **Java Standard Edition 7 (Java SE 7)** and **Java Standard Edition 8 (Java SE 8)**—was published just 17 years after the first edition. Java Standard Edition contains the capabilities needed to develop desktop and server applications. The book can be used with *either* Java SE 7 *or* Java SE 8 (released just after this book was published). All of the Java SE 8 features are discussed in modular, easy-to-include-or-omit sections throughout the book.

Prior to Java SE 8, Java supported three programming paradigms—*procedural programming*, *object-oriented programming* and *generic programming*. Java SE 8 adds *functional programming*. In Chapter 17, we’ll show how to use functional programming to write programs faster, more concisely, with fewer bugs and that are easier to *parallelize* (i.e., perform multiple calculations simultaneously) to take advantage of today’s multi-core hardware architectures to enhance application performance.

Java Enterprise Edition

Java is used in such a broad spectrum of applications that it has two other editions. The **Java Enterprise Edition (Java EE)** is geared toward developing large-scale, distributed networking applications and web-based applications. In the past, most computer applications ran on “standalone” computers (computers that were not networked together). Today’s applications can be written with the aim of communicating among the world’s computers via the Internet and the web. Later in this book we discuss how to build such web-based applications with Java.

4. <https://www.abiresearch.com/press/tablets-will-generate-35-of-this-years-25-billion->

Java Micro Edition

The **Java Micro Edition (Java ME)**—a subset of Java SE—is geared toward developing applications for resource-constrained embedded devices, such as smartwatches, MP3 players, television set-top boxes, smart meters (for monitoring electric energy usage) and more.

1.2 Hardware and Software

Computers can perform calculations and make logical decisions phenomenally faster than human beings can. Many of today’s personal computers can perform billions of calculations in one second—more than a human can perform in a lifetime. *Supercomputers* are already performing *thousands of trillions (quadrillions)* of instructions per second! China’s National University of Defense Technology’s Tianhe-2 supercomputer can perform over 33 quadrillion calculations per second (33.86 *petaflops*)!⁵ To put that in perspective, *the Tianhe-2 supercomputer can perform in one second about 3 million calculations for every person on the planet!* And—these supercomputing “upper limits” are growing quickly.

Computers process data under the control of sequences of instructions called **computer programs**. These software programs guide the computer through ordered actions specified by people called computer **programmers**. In this book, you’ll learn a key programming methodology that’s enhancing programmer productivity, thereby reducing software development costs—*object-oriented programming*.

A computer consists of various devices referred to as hardware (e.g., the keyboard, screen, mouse, hard disks, memory, DVD drives and processing units). Computing costs are *dropping dramatically*, owing to rapid developments in hardware and software technologies. Computers that might have filled large rooms and cost millions of dollars decades ago are now inscribed on silicon chips smaller than a fingernail, costing perhaps a few dollars each. Ironically, silicon is one of the most abundant materials on Earth—it’s an ingredient in common sand. Silicon-chip technology has made computing so economical that computers have become a commodity.

1.2.1 Moore’s Law

Every year, you probably expect to pay at least a little more for most products and services. The opposite has been the case in the computer and communications fields, especially with regard to the hardware supporting these technologies. For many decades, hardware costs have fallen rapidly.

Every year or two, the capacities of computers have approximately *doubled* inexpensively. This remarkable trend often is called **Moore’s Law**, named for the person who identified it in the 1960s, Gordon Moore, co-founder of Intel—the leading manufacturer of the processors in today’s computers and embedded systems. Moore’s Law and related observations apply especially to the amount of memory that computers have for programs, the amount of secondary storage (such as disk storage) they have to hold programs and data over longer periods of time, and their processor speeds—the speeds at which they *execute* their programs (i.e., do their work).

5. <http://www.top500.org/>.

Similar growth has occurred in the communications field—costs have plummeted as enormous demand for communications *bandwidth* (i.e., information-carrying capacity) has attracted intense competition. We know of no other fields in which technology improves so quickly and costs fall so rapidly. Such phenomenal improvement is truly fostering the *Information Revolution*.

1.2.2 Computer Organization

Regardless of differences in *physical* appearance, computers can be envisioned as divided into various **logical units** or sections (Fig. 1.2).

Logical unit	Description
Input unit	This “receiving” section obtains information (data and computer programs) from input devices and places it at the disposal of the other units for processing. Most user input is entered into computers through keyboards, touch screens and mouse devices. Other forms of input include receiving voice commands, scanning images and barcodes, reading from secondary storage devices (such as hard drives, DVD drives, Blu-ray Disc™ drives and USB flash drives—also called “thumb drives” or “memory sticks”), receiving video from a webcam and having your computer receive information from the Internet (such as when you stream videos from YouTube® or download e-books from Amazon). Newer forms of input include position data from a GPS device, and motion and orientation information from an <i>accelerometer</i> (a device that responds to up/down, left/right and forward/backward acceleration) in a smartphone or game controller (such as Microsoft® Kinect® and Xbox®, Wii™ Remote and Sony® PlayStation® Move).
Output unit	This “shipping” section takes information the computer has processed and places it on various output devices to make it available for use outside the computer. Most information that’s output from computers today is displayed on screens (including touch screens), printed on paper (“going green” discourages this), played as audio or video on PCs and media players (such as Apple’s iPods) and giant screens in sports stadiums, transmitted over the Internet or used to control other devices, such as robots and “intelligent” appliances. Information is also commonly output to secondary storage devices, such as hard drives, DVD drives and USB flash drives. A popular recent form of output is smartphone vibration.
Memory unit	This rapid-access, relatively low-capacity “warehouse” section retains information that has been entered through the input unit, making it immediately available for processing when needed. The memory unit also retains processed information until it can be placed on output devices by the output unit. Information in the memory unit is <i>volatile</i> —it’s typically lost when the computer’s power is turned off. The memory unit is often called either memory , primary memory or RAM (Random Access Memory). Main memories on desktop and notebook computers contain as much as 128 GB of RAM. GB stands for gigabytes; a gigabyte is approximately one billion bytes. A byte is eight bits. A bit is either a 0 or a 1.

Fig. 1.2 | Logical units of a computer. (Part 1 of 2.)

Logical unit	Description
Arithmetic and logic unit (ALU)	This “manufacturing” section performs <i>calculations</i> , such as addition, subtraction, multiplication and division. It also contains the <i>decision</i> mechanisms that allow the computer, for example, to compare two items from the memory unit to determine whether they’re equal. In today’s systems, the ALU is implemented as part of the next logical unit, the CPU.
Central processing unit (CPU)	This “administrative” section coordinates and supervises the operation of the other sections. The CPU tells the input unit when information should be read into the memory unit, tells the ALU when information from the memory unit should be used in calculations and tells the output unit when to send information from the memory unit to certain output devices. Many of today’s computers have multiple CPUs and, hence, can perform many operations simultaneously. A multi-core processor implements multiple processors on a single integrated-circuit chip—a <i>dual-core processor</i> has two CPUs and a <i>quad-core processor</i> has four CPUs. Today’s desktop computers have processors that can execute billions of instructions per second.
Secondary storage unit	This is the long-term, high-capacity “warehousing” section. Programs or data not actively being used by the other units normally are placed on secondary storage devices (e.g., your <i>hard drive</i>) until they’re again needed, possibly hours, days, months or even years later. Information on secondary storage devices is <i>persistent</i> —it’s preserved even when the computer’s power is turned off. Secondary storage information takes much longer to access than information in primary memory, but its cost per unit is much less. Examples of secondary storage devices include hard drives, DVD drives and USB flash drives, some of which can hold over 2 TB (TB stands for tera-bytes; a terabyte is approximately one trillion bytes). Typical hard drives on desktop and notebook computers hold up to 2 TB, and some desktop hard drives can hold up to 4 TB.

Fig. 1.2 | Logical units of a computer. (Part 2 of 2.)

1.3 Data Hierarchy

Data items processed by computers form a **data hierarchy** that becomes larger and more complex in structure as we progress from the simplest data items (called “bits”) to richer ones, such as characters and fields. Figure 1.3 illustrates a portion of the data hierarchy.

Bits

The smallest data item in a computer can assume the value 0 or the value 1. It’s called a **bit** (short for “binary digit”—a digit that can assume one of *two* values). Remarkably, the impressive functions performed by computers involve only the simplest manipulations of 0s and 1s—*examining a bit’s value*, *setting a bit’s value* and *reversing a bit’s value* (from 1 to 0 or from 0 to 1).

Characters

It’s tedious for people to work with data in the low-level form of bits. Instead, they prefer to work with *decimal digits* (0–9), *letters* (A–Z and a–z), and *special symbols* (e.g., \$, @, %,




Fig. I.3 | Data hierarchy.

&, *, (,), -, +, ", :, ? and /). Digits, letters and special symbols are known as **characters**. The computer's **character set** is the set of all the characters used to write programs and represent data items. Computers process only 1s and 0s, so a computer's character set represents every character as a pattern of 1s and 0s. Java uses **Unicode®** characters that are composed of one, two or four bytes (8, 16 or 32 bits). Unicode contains characters for many of the world's languages. See Appendix H for more information on Unicode. See Appendix B for more information on the **ASCII (American Standard Code for Information Interchange)** character set—the popular subset of Unicode that represents uppercase and lowercase letters, digits and some common special characters.

Fields

Just as characters are composed of bits, **fields** are composed of characters or bytes. A field is a group of characters or bytes that conveys meaning. For example, a field consisting of uppercase and lowercase letters can be used to represent a person's name, and a field consisting of decimal digits could represent a person's age.

Records

Several related fields can be used to compose a **record** (implemented as a `class` in Java). In a payroll system, for example, the record for an employee might consist of the following fields (possible types for these fields are shown in parentheses):

- Employee identification number (a whole number)
- Name (a string of characters)
- Address (a string of characters)
- Hourly pay rate (a number with a decimal point)
- Year-to-date earnings (a number with a decimal point)
- Amount of taxes withheld (a number with a decimal point)

Thus, a record is a group of related fields. In the preceding example, all the fields belong to the *same* employee. A company might have many employees and a payroll record for each.

Files

A **file** is a group of related records. [Note: More generally, a file contains arbitrary data in arbitrary formats. In some operating systems, a file is viewed simply as a *sequence of bytes*—any organization of the bytes in a file, such as organizing the data into records, is a view created by the application programmer. You’ll see how to do that in Chapter 15.] It’s not unusual for an organization to have many files, some containing billions, or even trillions, of characters of information.

Database

A **database** is a collection of data organized for easy access and manipulation. The most popular model is the *relational database*, in which data is stored in simple *tables*. A table includes *records* and *fields*. For example, a table of students might include first name, last name, major, year, student ID number and grade point average fields. The data for each student is a record, and the individual pieces of information in each record are the fields. You can *search*, *sort* and otherwise manipulate the data based on its relationship to multiple tables or databases. For example, a university might use data from the student database in combination with data from databases of courses, on-campus housing, meal plans, etc. We discuss databases in Chapter 24.

Big Data

The amount of data being produced worldwide is enormous and growing quickly. According to IBM, approximately 2.5 quintillion bytes (2.5 *exabytes*) of data are created daily and 90% of the world’s data was created in just the past two years!⁶ According to a Digital Universe study, the global data supply reached 2.8 *zettabytes* (equal to 2.8 trillion gigabytes) in 2012.⁷ Figure 1.4 shows some common byte measurements. **Big data** applications deal with such massive amounts of data and this field is growing quickly, creating lots of opportunity for software developers. According to a study by Gartner Group, over 4 million IT jobs globally will support big data by 2015.⁸

6. <http://www-01.ibm.com/software/data/bigdata/>.

7. <http://www.guardian.co.uk/news/datablog/2012/dec/19/big-data-study-digital-universe-global-volume>.

8. <http://tech.fortune.cnn.com/2013/09/04/big-data-employment-boom/>.

Unit	Bytes	Which is approximately
1 kilobyte (KB)	1024 bytes	10^3 (1024 bytes exactly)
1 megabyte (MB)	1024 kilobytes	10^6 (1,000,000 bytes)
1 gigabyte (GB)	1024 megabytes	10^9 (1,000,000,000 bytes)
1 terabyte (TB)	1024 gigabytes	10^{12} (1,000,000,000,000 bytes)
1 petabyte (PB)	1024 terabytes	10^{15} (1,000,000,000,000,000 bytes)
1 exabyte (EB)	1024 petabytes	10^{18} (1,000,000,000,000,000,000 bytes)
1 zettabyte (ZB)	1024 exabytes	10^{21} (1,000,000,000,000,000,000,000 bytes)

Fig. 1.4 | Byte measurements.

1.4 Machine Languages, Assembly Languages and High-Level Languages

Programmers write instructions in various programming languages, some directly understandable by computers and others requiring intermediate *translation* steps. Hundreds of such languages are in use today. These may be divided into three general types:

1. Machine languages
2. Assembly languages
3. High-level languages

Machine Languages

Any computer can directly understand only its own **machine language**, defined by its hardware design. Machine languages generally consist of strings of numbers (ultimately reduced to 1s and 0s) that instruct computers to perform their most elementary operations one at a time. Machine languages are *machine dependent* (a particular machine language can be used on only one type of computer). Such languages are cumbersome for humans. For example, here's a section of an early machine-language payroll program that adds overtime pay to base pay and stores the result in gross pay:

```
+1300042774
+1400593419
+1200274027
```

Assembly Languages and Assemblers

Programming in machine language was simply too slow and tedious for most programmers. Instead of using the strings of numbers that computers could directly understand, programmers began using English-like abbreviations to represent elementary operations. These abbreviations formed the basis of **assembly languages**. *Translator programs* called **assemblers** were developed to convert early assembly-language programs to machine language at computer speeds. The following section of an assembly-language payroll program also adds overtime pay to base pay and stores the result in gross pay:

```
load    basepay
add     overpay
store   grosspay
```

Although such code is clearer to humans, it's incomprehensible to computers until translated to machine language.

High-Level Languages and Compilers

With the advent of assembly languages, computer usage increased rapidly, but programmers still had to use numerous instructions to accomplish even the simplest tasks. To speed the programming process, **high-level languages** were developed in which single statements could be written to accomplish substantial tasks. Translator programs called **compilers** convert high-level language programs into machine language. High-level languages allow you to write instructions that look almost like everyday English and contain commonly used mathematical notations. A payroll program written in a high-level language might contain a *single* statement such as

```
grossPay = basePay + overTimePay
```

From the programmer's standpoint, high-level languages are preferable to machine and assembly languages. Java is one of the most widely used high-level programming languages.

Interpreters

Compiling a large high-level language program into machine language can take considerable computer time. *Interpreter* programs, developed to execute high-level language programs directly, avoid the delay of compilation, although they run slower than compiled programs. We'll say more about interpreters in Section 1.9, where you'll learn that Java uses a clever performance-tuned mixture of compilation and interpretation to run programs.

1.5 Introduction to Object Technology

Today, as demands for new and more powerful software are soaring, building software quickly, correctly and economically remains an elusive goal. *Objects*, or more precisely, the *classes* objects come from, are essentially *reusable* software components. There are date objects, time objects, audio objects, video objects, automobile objects, people objects, etc. Almost any *noun* can be reasonably represented as a software object in terms of *attributes* (e.g., name, color and size) and *behaviors* (e.g., calculating, moving and communicating). Software-development groups can use a modular, object-oriented design-and-implementation approach to be much more productive than with earlier popular techniques like "structured programming"—object-oriented programs are often easier to understand, correct and modify.

1.5.1 The Automobile as an Object

To help you understand objects and their contents, let's begin with a simple analogy. Suppose you want to *drive a car and make it go faster by pressing its accelerator pedal*. What must happen before you can do this? Well, before you can drive a car, someone has to *design* it. A car typically begins as engineering drawings, similar to the *blueprints* that describe the design of a house. These drawings include the design for an accelerator pedal. The pedal *hides* from the driver the complex mechanisms that actually make the car go faster, just as the brake pedal "hides" the mechanisms that slow the car, and the steering wheel "hides" the mechanisms that turn the car. This enables people with little or no knowledge of how engines, braking and steering mechanisms work to drive a car easily.

Just as you cannot cook meals in the kitchen of a blueprint, you cannot drive a car's engineering drawings. Before you can drive a car, it must be *built* from the engineering drawings that describe it. A completed car has an *actual* accelerator pedal to make it go faster, but even that's not enough—the car won't accelerate on its own (hopefully!), so the driver must *press* the pedal to accelerate the car.

1.5.2 Methods and Classes

Let's use our car example to introduce some key object-oriented programming concepts. Performing a task in a program requires a **method**. The method houses the program statements that actually perform its tasks. The method hides these statements from its user, just as the accelerator pedal of a car hides from the driver the mechanisms of making the car go faster. In Java, we create a program unit called a **class** to house the set of methods that perform the class's tasks. For example, a class that represents a bank account might contain one method to *deposit* money to an account, another to *withdraw* money from an account and a third to *inquire* what the account's current balance is. A class is similar in concept to a car's engineering drawings, which house the design of an accelerator pedal, steering wheel, and so on.

1.5.3 Instantiation

Just as someone has to *build a car* from its engineering drawings before you can actually drive a car, you must *build an object* of a class before a program can perform the tasks that the class's methods define. The process of doing this is called *instantiation*. An object is then referred to as an **instance** of its class.

1.5.4 Reuse

Just as a car's engineering drawings can be *reused* many times to build many cars, you can *reuse* a class many times to build many objects. Reuse of existing classes when building new classes and programs saves time and effort. Reuse also helps you build more reliable and effective systems, because existing classes and components often have undergone extensive *testing*, *debugging* and *performance* tuning. Just as the notion of *interchangeable parts* was crucial to the Industrial Revolution, reusable classes are crucial to the software revolution that has been spurred by object technology.



Software Engineering Observation 1.1

Use a building-block approach to creating your programs. Avoid reinventing the wheel—use existing high-quality pieces wherever possible. This software reuse is a key benefit of object-oriented programming.

1.5.5 Messages and Method Calls

When you drive a car, pressing its gas pedal sends a *message* to the car to perform a task—that is, to go faster. Similarly, you *send messages to an object*. Each message is implemented as a **method call** that tells a method of the object to perform its task. For example, a program might call a bank-account object's *deposit* method to increase the account's balance.

1.5.6 Attributes and Instance Variables

A car, besides having capabilities to accomplish tasks, also has *attributes*, such as its color, its number of doors, the amount of gas in its tank, its current speed and its record of total

miles driven (i.e., its odometer reading). Like its capabilities, the car's attributes are represented as part of its design in its engineering diagrams (which, for example, include an odometer and a fuel gauge). As you drive an actual car, these attributes are carried along with the car. Every car maintains its *own* attributes. For example, each car knows how much gas is in its own gas tank, but *not* how much is in the tanks of *other* cars.

An object, similarly, has attributes that it carries along as it's used in a program. These attributes are specified as part of the object's class. For example, a bank-account object has a *balance attribute* that represents the amount of money in the account. Each bank-account object knows the balance in the account it represents, but *not* the balances of the *other* accounts in the bank. Attributes are specified by the class's **instance variables**.

1.5.7 Encapsulation and Information Hiding

Classes (and their objects) **encapsulate**, i.e., encase, their attributes and methods. A class's (and its object's) attributes and methods are intimately related. Objects may communicate with one another, but they're normally not allowed to know how other objects are implemented—implementation details are *hidden* within the objects themselves. This **information hiding**, as we'll see, is crucial to good software engineering.

1.5.8 Inheritance

A new class of objects can be created conveniently by **inheritance**—the new class (called the **subclass**) starts with the characteristics of an existing class (called the **superclass**), possibly customizing them and adding unique characteristics of its own. In our car analogy, an object of class “convertible” certainly *is* an object of the more *general* class “automobile,” but more *specifically*, the roof can be raised or lowered.

1.5.9 Interfaces

Java also supports **interfaces**—collections of related methods that typically enable you to tell objects *what* to do, but not *how* to do it (we'll see an exception to this in Java SE 8). In the car analogy, a “basic-driving-capabilities” interface consisting of a steering wheel, an accelerator pedal and a brake pedal would enable a driver to tell the car *what* to do. Once you know how to use this interface for turning, accelerating and braking, you can drive many types of cars, even though manufacturers may *implement* these systems *differently*.

A class **implements** zero or more interfaces, each of which can have one or more methods, just as a car implements separate interfaces for basic driving functions, controlling the radio, controlling the heating and air conditioning systems, and the like. Just as car manufacturers implement capabilities *differently*, classes may implement an interface's methods *differently*. For example a software system may include a “backup” interface that offers the methods *save* and *restore*. Classes may implement those methods differently, depending on the types of things being backed up, such as programs, text, audios, videos, etc., and the types of devices where these items will be stored.

1.5.10 Object-Oriented Analysis and Design (OOAD)

Soon you'll be writing programs in Java. How will you create the **code** (i.e., the program instructions) for your programs? Perhaps, like many programmers, you'll simply turn on

your computer and start typing. This approach may work for small programs (like the ones we present in the early chapters of the book), but what if you were asked to create a software system to control thousands of automated teller machines for a major bank? Or suppose you were asked to work on a team of 1,000 software developers building the next generation of the U.S. air traffic control system? For projects so large and complex, you should not simply sit down and start writing programs.

To create the best solutions, you should follow a detailed **analysis** process for determining your project's **requirements** (i.e., defining *what* the system is supposed to do) and developing a **design** that satisfies them (i.e., specifying *how* the system should do it). Ideally, you'd go through this process and carefully review the design (and have your design reviewed by other software professionals) before writing any code. If this process involves analyzing and designing your system from an object-oriented point of view, it's called an **object-oriented analysis-and-design (OOAD) process**. Languages like Java are object oriented. Programming in such a language, called **object-oriented programming (OOP)**, allows you to implement an object-oriented design as a working system.

1.5.1.1 The UML (Unified Modeling Language)

Although many different OOAD processes exist, a single graphical language for communicating the results of *any* OOAD process has come into wide use. The Unified Modeling Language (UML) is now the most widely used graphical scheme for modeling object-oriented systems. We present our first UML diagrams in Chapters 3 and 4, then use them in our deeper treatment of object-oriented programming through Chapter 11. In our *optional* online ATM Software Engineering Case Study in Chapters 33–34 we present a simple subset of the UML's features as we guide you through an object-oriented design experience.

1.6 Operating Systems

Operating systems are software systems that make using computers more convenient for users, application developers and system administrators. They provide services that allow each application to execute safely, efficiently and *concurrently* (i.e., in parallel) with other applications. The software that contains the core components of the operating system is the **kernel**. Popular desktop operating systems include Linux, Windows and Mac OS X. Popular mobile operating systems used in smartphones and tablets include Google's Android, Apple's iOS (for its iPhone, iPad and iPod Touch devices), Windows Phone 8 and BlackBerry OS.

1.6.1 Windows—A Proprietary Operating System

In the mid-1980s, Microsoft developed the **Windows operating system**, consisting of a graphical user interface built on top of DOS—an enormously popular personal-computer operating system that users interacted with by typing commands. Windows borrowed many concepts (such as icons, menus and windows) popularized by early Apple Macintosh operating systems and originally developed by Xerox PARC. Windows 8 is Microsoft's latest operating system—its features include PC and tablet support, a tiles-based user interface, security enhancements, touch-screen and multi-touch support, and more. Windows is a *proprietary* operating system—it's controlled by Microsoft exclusively. It's by far the world's most widely used operating system.

1.6.2 Linux—An Open-Source Operating System

The **Linux** operating system—which is popular in servers, personal computers and embedded systems—is perhaps the greatest success of the *open-source* movement. The **open-source software** development style departs from the *proprietary* development style (used, for example, with Microsoft’s Windows and Apple’s Mac OS X). With open-source development, individuals and companies—often worldwide—contribute their efforts in developing, maintaining and evolving software. Anyone can use and customize it for their own purposes, typically at no charge. The Java Development Kit and many related Java technologies are now open source.

Some organizations in the open-source community are the *Eclipse Foundation* (the *Eclipse Integrated Development Environment* helps Java programmers conveniently develop software), the *Mozilla Foundation* (creators of the *Firefox web browser*), the *Apache Software Foundation* (creators of the *Apache web server* that *delivers web pages over the Internet* in response to web-browser requests) and *GitHub* and *SourceForge* (which provide the *tools for managing open-source projects*).

Rapid improvements to computing and communications, decreasing costs and open-source software have made it easier and more economical to create software-based businesses now than just a few decades ago. Facebook, which was launched from a college dorm room, was built with open-source software.⁹

A variety of issues—such as Microsoft’s market power, the relatively small number of user-friendly Linux applications and the diversity of Linux distributions (Red Hat Linux, Ubuntu Linux and many others)—have prevented widespread Linux use on desktop computers. But Linux has become extremely popular on servers and in embedded systems, such as Google’s Android-based smartphones.

1.6.3 Android

Android—the fastest-growing mobile and smartphone operating system—is based on the Linux kernel and uses Java. Experienced Java programmers can quickly dive into Android development. One benefit of developing Android apps is the openness of the platform. The operating system is open source and free.

The Android operating system was developed by Android, Inc., which was acquired by Google in 2005. In 2007, the Open Handset Alliance™—which now has 87 company members worldwide (http://www.openhandsetalliance.com/oha_members.html)—was formed to develop, maintain and evolve Android, driving innovation in mobile technology and improving the user experience while reducing costs. As of April 2013, more than 1.5 million Android devices (smartphones, tablets, etc.) were being activated *daily*.¹⁰ By October 2013, a Strategy Analytics report showed that Android had 81.3% of the global *smartphone* market share, compared to 13.4% for Apple, 4.1% for Microsoft and 1% for BlackBerry.¹¹ Android devices now include smartphones, tablets, e-readers, robots, jet engines, NASA satellites, game consoles, refrigerators, televisions, cameras, health-care

9. <http://developers.facebook.com/opensource>.

10. <http://www.technobuffalo.com/2013/04/16/google-daily-android-activations-1-5-million/>.

11. <http://blogs.strategyanalytics.com/WSS/post/2013/10/31/Android-Captures-Record-81-Percent-Share-of-Global-Smartphone-Shipments-in-Q3-2013.aspx>.

devices, smartwatches, automobile in-vehicle infotainment systems (for controlling the radio, GPS, phone calls, thermostat, etc.) and more.¹²

Android smartphones include the functionality of a mobile phone, Internet client (for web browsing and Internet communication), MP3 player, gaming console, digital camera and more. These handheld devices feature full-color *multitouch screens* which allow you to control the device with *gestures* involving one touch or multiple simultaneous touches. You can download apps directly onto your Android device through Google Play and other app marketplaces. At the time of this writing, there were over one million apps in **Google Play**, and the number is growing quickly.¹³

We present an introduction to Android app development in our textbook, *Android How to Program, Second Edition*, and in our professional book, *Android for Programmers: An App-Driven Approach, Second Edition*. After you learn Java, you'll find it straightforward to begin developing and running Android apps. You can place your apps on Google Play (play.google.com), and if they're successful, you may even be able to launch a business. Just remember—Facebook, Microsoft and Dell were all launched from college dorm rooms.

1.7 Programming Languages

In this section, we comment briefly on several popular programming languages (Fig. 1.5). In the next section, we introduce Java.

Programming language	Description
Fortran	Fortran (FORMula TRANslator) was developed by IBM Corporation in the mid-1950s for scientific and engineering applications that require complex mathematical computations. It's still widely used, and its latest versions support object-oriented programming.
COBOL	COBOL (COMmon Business Oriented Language) was developed in the late 1950s by computer manufacturers, the U.S. government and industrial computer users based on a language developed by Grace Hopper, a U.S. Navy Rear Admiral and computer scientist who also advocated for the international standardization of programming languages. COBOL is still widely used for commercial applications that require precise and efficient manipulation of large amounts of data. Its latest version supports object-oriented programming.
Pascal	Research in the 1960s resulted in <i>structured programming</i> —a disciplined approach to writing programs that are clearer, easier to test and debug and easier to modify than large programs produced with previous techniques. One result of this research was the development in 1971 of the Pascal programming language, which was designed for teaching structured programming and was popular in college courses for several decades.

Fig. 1.5 | Some other programming languages. (Part 1 of 3.)

12. <http://www.businessweek.com/articles/2013-05-29/behind-the-internet-of-things-is-android-and-its-everywhere>.

13. http://en.wikipedia.org/wiki/Google_Play.

Programming language	Description
Ada	Ada, based on Pascal, was developed under the sponsorship of the U.S. Department of Defense (DOD) during the 1970s and early 1980s. The DOD wanted a single language that would fill most of its needs. The Ada language was named after Lady Ada Lovelace, daughter of the poet Lord Byron. She's credited with writing the world's first computer program in the early 1800s (for the Analytical Engine mechanical computing device designed by Charles Babbage). Ada also supports object-oriented programming.
Basic	Basic was developed in the 1960s at Dartmouth College to familiarize novices with programming techniques. Many of its latest versions are object oriented.
C	C was developed in the early 1970s by Dennis Ritchie at Bell Laboratories. It initially became widely known as the UNIX operating system's development language. Today, most of the code for general-purpose operating systems is written in C or C++.
C++	C++, which is based on C, was developed by Bjarne Stroustrup in the early 1980s at Bell Laboratories. C++ provides several features that "spruce up" the C language, but more important, it provides capabilities for object-oriented programming.
Objective-C	Objective-C is another object-oriented language based on C. It was developed in the early 1980s and later acquired by NeXT, which in turn was acquired by Apple. It has become the key programming language for the OS X operating system and all iOS-powered devices (such as iPods, iPhones and iPads).
Visual Basic	Microsoft's Visual Basic language was introduced in the early 1990s to simplify the development of Microsoft Windows applications. Its latest versions support object-oriented programming.
Visual C#	Microsoft's three object-oriented primary programming languages are Visual Basic (based on the original Basic), Visual C++ (based on C++) and Visual C# (based on C++ and Java, and developed for integrating the Internet and the web into computer applications).
PHP	PHP, an object-oriented, open-source scripting language supported by a community of users and developers, is used by millions of websites. PHP is platform independent—implementations exist for all major UNIX, Linux, Mac and Windows operating systems. PHP also supports many databases, including the popular open-source MySQL.
Perl	Perl (Practical Extraction and Report Language), one of the most widely used object-oriented scripting languages for web programming, was developed in 1987 by Larry Wall. It features rich text-processing capabilities.
Python	Python, another object-oriented scripting language, was released publicly in 1991. Developed by Guido van Rossum of the National Research Institute for Mathematics and Computer Science in Amsterdam (CWI), Python draws heavily from Modula-3—a systems programming language. Python is "extensible"—it can be extended through classes and programming interfaces.
JavaScript	JavaScript is the most widely used scripting language. It's primarily used to add dynamic behavior to web pages—for example, animations and improved interactivity with the user. It's provided with all major web browsers.

Fig. 1.5 | Some other programming languages. (Part 2 of 3.)

Programming language	Description
Ruby on Rails	Ruby, created in the mid-1990s, is an open-source, object-oriented programming language with a simple syntax that's similar to Python. Ruby on Rails combines the scripting language Ruby with the Rails web application framework developed by 37Signals. Their book, <i>Getting Real</i> (gettingreal.37signals.com/toc.php), is a must read for web developers. Many Ruby on Rails developers have reported productivity gains over other languages when developing database-intensive web applications.

Fig. 1.5 | Some other programming languages. (Part 3 of 3.)

1.8 Java

The microprocessor revolution's most important contribution to date is that it enabled the development of personal computers. Microprocessors have had a profound impact in intelligent consumer-electronic devices. Recognizing this, Sun Microsystems in 1991 funded an internal corporate research project led by James Gosling, which resulted in a C++-based object-oriented programming language that Sun called Java.

A key goal of Java is to be able to write programs that will run on a great variety of computer systems and computer-controlled devices. This is sometimes called “write once, run anywhere.”

The web exploded in popularity in 1993, and Sun saw the potential of using Java to add *dynamic content*, such as interactivity and animations, to web pages. Java drew the attention of the business community because of the phenomenal interest in the web. Java is now used to develop large-scale enterprise applications, to enhance the functionality of web servers (the computers that provide the content we see in our web browsers), to provide applications for consumer devices (cell phones, smartphones, television set-top boxes and more) and for many other purposes. Java is also the key language for developing Android smartphone and tablet apps. Sun Microsystems was acquired by Oracle in 2010.

Java Class Libraries

You can create each class and method you need to form your Java programs. However, most Java programmers take advantage of the rich collections of existing classes and methods in the **Java class libraries**, also known as the **Java APIs** (**A**pplication **P**rogramming **I**nterfaces).



Performance Tip 1.1

Using Java API classes and methods instead of writing your own versions can improve program performance, because they're carefully written to perform efficiently. This also shortens program development time.

1.9 A Typical Java Development Environment

We now explain the steps to create and execute a Java application. Normally there are five phases—edit, compile, load, verify and execute. We discuss them in the context of the Java

SE 8 Development Kit (JDK). See the *Before You Begin* section for information on downloading and installing the JDK on Windows, Linux and OS X.

Phase 1: Creating a Program

Phase 1 consists of editing a file with an *editor program*, normally known simply as an *editor* (Fig. 1.6). Using the editor, you type a Java program (typically referred to as **source code**), make any necessary corrections and save it on a secondary storage device, such as your hard drive. Java source code files are given a name ending with the **.java extension**, indicating that the file contains Java source code.




Fig. 1.6 | Typical Java development environment—editing phase.

Two editors widely used on Linux systems are **vi** and **emacs**. Windows provides **Notepad**. OS X provides **TextEdit**. Many freeware and shareware editors are also available online, including Notepad++ (notepad-plus-plus.org), EditPlus (www.editplus.com), TextPad (www.textpad.com) and jEdit (www.jedit.org).

Integrated development environments (IDEs) provide tools that support the software development process, such as editors, debuggers for locating **logic errors** (errors that cause programs to execute incorrectly) and more. There are many popular Java IDEs, including:

- Eclipse (www.eclipse.org)
- NetBeans (www.netbeans.org)
- IntelliJ IDEA (www.jetbrains.com)

On the book's website at

www.deitel.com/books/jhttp10lov

we provide Dive-Into® videos that show you how to execute this book's Java applications and how to develop new Java applications with Eclipse, NetBeans and IntelliJ IDEA.

Phase 2: Compiling a Java Program into Bytecodes

In Phase 2, you use the command **javac** (the **Java compiler**) to **compile** a program (Fig. 1.7). For example, to compile a program called `Welcome.java`, you'd type

```
javac Welcome.java
```

in your system's command window (i.e., the **Command Prompt** in Windows, the **Terminal** application in OS X) or a Linux shell (also called **Terminal** in some versions of Linux). If the program compiles, the compiler produces a **.class** file called `Welcome.class` that contains the compiled version. IDEs typically provide a menu item, such as **Build** or **Make**, that invokes the `javac` command for you. If the compiler detects errors, you'll need to go back to Phase 1 and correct them. In Chapter 2, we'll say more about the kinds of errors the compiler can detect.




Fig. 1.7 | Typical Java development environment—compilation phase.

The Java compiler translates Java source code into **bytecodes** that represent the tasks to execute in the execution phase (Phase 5). The **Java Virtual Machine (JVM)**—a part of the JDK and the foundation of the Java platform—executes bytecodes. A **virtual machine (VM)** is a software application that simulates a computer but hides the underlying operating system and hardware from the programs that interact with it. If the same VM is implemented on many computer platforms, applications written for that type of VM can be used on all those platforms. The JVM is one of the most widely used virtual machines. Microsoft's .NET uses a similar virtual-machine architecture.

Unlike machine-language instructions, which are *platform dependent* (that is, dependent on specific computer hardware), bytecode instructions are *platform independent*. So, Java's bytecodes are **portable**—without recompiling the source code, the same bytecode instructions can execute on any platform containing a JVM that understands the version of Java in which the bytecodes were compiled. The JVM is invoked by the **java** command. For example, to execute a Java application called `Welcome`, you'd type the command

```
java Welcome
```

in a command window to invoke the JVM, which would then initiate the steps necessary to execute the application. This begins Phase 3. IDEs typically provide a menu item, such as **Run**, that invokes the `java` command for you.

Phase 3: Loading a Program into Memory

In Phase 3, the JVM places the program in memory to execute it—this is known as **loading** (Fig. 1.8). The JVM's **class loader** takes the `.class` files containing the program's bytecodes and transfers them to primary memory. It also loads any of the `.class` files provided by Java that your program uses. The `.class` files can be loaded from a disk on your system or over a network (e.g., your local college or company network, or the Internet).




Fig. 1.8 | Typical Java development environment—loading phase.

Phase 4: Bytecode Verification

In Phase 4, as the classes are loaded, the **bytecode verifier** examines their bytecodes to ensure that they're valid and do not violate Java's security restrictions (Fig. 1.9). Java enforces strong security to make sure that Java programs arriving over the network do not damage your files or your system (as computer viruses and worms might).




Fig. 1.9 | Typical Java development environment—verification phase.

Phase 5: Execution

In Phase 5, the JVM **executes** the program's bytecodes, thus performing the actions specified by the program (Fig. 1.10). In early Java versions, the JVM was simply an *interpreter* for Java bytecodes. Most Java programs would execute slowly, because the JVM would interpret and execute one bytecode at a time. Some modern computer architectures can execute several instructions in parallel. Today's JVMs typically execute bytecodes using a combination of interpretation and so-called **just-in-time (JIT) compilation**. In this process, the JVM analyzes the bytecodes as they're interpreted, searching for *hot spots*—parts of the bytecodes that execute frequently. For these parts, a **just-in-time (JIT) compiler**, such as Oracle's **Java HotSpot™ compiler**, translates the bytecodes into the underlying computer's machine language. When the JVM encounters these compiled parts again, the faster machine-language code executes. Thus Java programs actually go through *two* compilation phases—one in which source code is translated into bytecodes (for portability across JVMs on different computer platforms) and a second in which, during execution, the *bytecodes* are translated into *machine language* for the actual computer on which the program executes.




Fig. 1.10 | Typical Java development environment—execution phase.

Problems That May Occur at Execution Time

Programs might not work on the first try. Each of the preceding phases can fail because of various errors that we'll discuss throughout this book. For example, an executing program

might try to divide by zero (an illegal operation for whole-number arithmetic in Java). This would cause the Java program to display an error message. If this occurred, you'd have to return to the edit phase, make the necessary corrections and proceed through the remaining phases again to determine that the corrections fixed the problem(s). [Note: Most programs in Java input or output data. When we say that a program displays a message, we normally mean that it displays that message on your computer's screen. Messages and other data may be output to other devices, such as disks and hardcopy printers, or even to a network for transmission to other computers.]



Common Programming Error 1.1

*Errors such as division by zero occur as a program runs, so they're called **runtime errors** or **execution-time errors**. **Fatal runtime errors** cause programs to terminate immediately without having successfully performed their jobs. **Nonfatal runtime errors** allow programs to run to completion, often producing incorrect results.*

1.10 Test-Driving a Java Application

In this section, you'll run and interact with your first Java application. The **Painter** application, which you'll build over the course of several exercises, allows you to drag the mouse to "paint." The elements and functionality you see here are typical of what you'll learn to program in this book. Using the **Painter's** graphical user interface (GUI), you can control the drawing color, the shape to draw (line, rectangle or oval) and whether the shape is filled with the drawing color. You can also undo the last shape you added to the drawing or clear the entire drawing. [Note: We use fonts to distinguish between features. Our convention is to emphasize screen features like titles and menus (e.g., the **File** menu) in a semibold sans-serif Helvetica font and to emphasize nonscreen elements, such as file names, program code or input (e.g., `ProgramName.java`), in a sans-serif Lucida font.]

The steps in this section show you how to execute the **Painter** app from a **Command Prompt** (Windows), **Terminal** (OS X) or shell (Linux) window on your system. Throughout the book, we'll refer to these windows simply as *command windows*. Perform the following steps to use the **Painter** application to draw a smiley face:

1. **Checking your setup.** Read the Before You Begin section to confirm that you've set up Java properly on your computer, that you've copied the book's examples to your hard drive and that you know how to open a command window on your system.
2. **Changing to the completed application's directory.** Open a command window and use the `cd` command to change to the directory (also called a *folder*) for the **Painter** application. We assume that the book's examples are located in `C:\examples` on Windows or in your user account's `Documents/examples` folder on Linux/OS X. On Windows type `cd C:\examples\ch01\painter`, then press *Enter*. On Linux/OS X, type `cd ~/Documents/examples/ch01/painter`, then press *Enter*.
3. **Running the Painter application.** Recall that the `java` command, followed by the name of the application's `.class` file (in this case, `Painter`), executes the application. Type the command `java Painter` and press *Enter* to execute the app. Figure 1.11 shows the app running on Windows, Linux and OS X, respectively—we shortened the windows to save space.




Fig. 1.11 | **Painter** app executing in Windows 7, Linux and OS X.

[*Note:* Java commands are *case sensitive*—that is, uppercase letters are different from lowercase letters. It’s important to type the name of this application as **Painter** with a capital P. Otherwise, the application will *not* execute. Specifying the `.class` extension when using the java command results in an error. Also, if you receive the error message, “Exception in thread “main” java.lang.NoClassDefFoundError: Painter,” your system has a CLASSPATH problem. Please refer to the Before You Begin section for instructions to help you fix this problem.]

4. **Drawing a filled yellow oval for the face.** Select **Yellow** as the drawing color, **Oval** as the shape and check the **Filled** checkbox, then drag the mouse to draw a large oval (Fig. 1.12).




Fig. 1.12 | Drawing a filled yellow oval for the face.

5. *Drawing blue eyes.* Select **Blue** as the drawing color, then draw two small ovals as the eyes (Fig. 1.13).




Fig. 1.13 | Drawing blue eyes.

6. *Drawing black eyebrows and a nose.* Select **Black** as the drawing color and **Line** as the shape, then draw eyebrows and a nose (Fig. 1.14). Lines do not have fill, so leaving the **Filled** checkbox checked has no effect when drawing lines.




Fig. 1.14 | Drawing black eyebrows and a nose.

7. *Drawing a magenta mouth.* Select **Magenta** as the drawing color and **Oval** as the shape, then draw a mouth (Fig. 1.15).



Fig. 1.15 | Drawing a magenta mouth.

8. *Drawing a yellow oval on the mouth to make a smile.* Select **Yellow** as the drawing color, then draw an oval to change the magenta oval into a smile (Fig. 1.16).




Fig. 1.16 | Drawing a yellow oval on the mouth to make a smile.

9. *Exiting the Painter application.* To exit the **Painter** application, click the **Close** button (in the window's upper-right corner on Windows and the upper-left corner on Linux and OS X). Closing the window causes the **Painter** application to terminate.

1.11 Internet and World Wide Web

In the late 1960s, ARPA—the Advanced Research Projects Agency of the United States Department of Defense—rolled out plans for networking the main computer systems of approximately a dozen ARPA-funded universities and research institutions. The computers were to be connected with communications lines operating at speeds on the order of 50,000 bits per second, a stunning rate at a time when most people (of the few who even had networking access) were connecting over telephone lines to computers at a rate of 110 bits per second. Academic research was about to take a giant leap forward. ARPA proceeded to implement what quickly became known as the ARPANET, the precursor to today's **Internet**. Today's fastest Internet speeds are on the order of billions of bits per second with trillion-bit-per-second speeds on the horizon!

Things worked out differently from the original plan. Although the ARPANET enabled researchers to network their computers, its main benefit proved to be the capability for quick and easy communication via what came to be known as electronic mail (e-mail). This is true even on today's Internet, with e-mail, instant messaging, file transfer and social media such as Facebook and Twitter enabling billions of people worldwide to communicate quickly and easily.

The protocol (set of rules) for communicating over the ARPANET became known as the **Transmission Control Protocol (TCP)**. TCP ensured that messages, consisting of sequentially numbered pieces called *packets*, were properly routed from sender to receiver, arrived intact and were assembled in the correct order.

1.11.1 The Internet: A Network of Networks

In parallel with the early evolution of the Internet, organizations worldwide were implementing their own networks for both intraorganization (that is, within an organization) and interorganization (that is, between organizations) communication. A huge variety of networking hardware and software appeared. One challenge was to enable these different networks to communicate with each other. ARPA accomplished this by developing the Internet Protocol (IP), which created a true “network of networks,” the current architecture of the Internet. The combined set of protocols is now called **TCP/IP**.

Businesses rapidly realized that by using the Internet, they could improve their operations and offer new and better services to their clients. Companies started spending large amounts of money to develop and enhance their Internet presence. This generated fierce competition among communications carriers and hardware and software suppliers to meet the increased infrastructure demand. As a result, **bandwidth**—the information-carrying capacity of communications lines—on the Internet has increased tremendously, while hardware costs have plummeted.

1.11.2 The World Wide Web: Making the Internet User-Friendly

The **World Wide Web** (simply called “the web”) is a collection of hardware and software associated with the Internet that allows computer users to locate and view multimedia-based documents (documents with various combinations of text, graphics, animations, audios and videos) on almost any subject. The introduction of the web was a relatively recent event. In 1989, Tim Berners-Lee of CERN (the European Organization for Nuclear Research) began to develop a technology for sharing information via “hyperlinked” text documents. Berners-Lee called his invention the **HyperText Markup Language** (HTML). He also wrote communication protocols such as **HyperText Transfer Protocol** (HTTP) to form the backbone of his new hypertext information system, which he referred to as the World Wide Web.

In 1994, Berners-Lee founded an organization, called the **World Wide Web Consortium** (W3C, www.w3.org), devoted to developing web technologies. One of the W3C’s primary goals is to make the web universally accessible to everyone regardless of disabilities, language or culture. In this book, you’ll use Java to build web-based applications.

1.11.3 Web Services and Mashups

In online Chapter 32, we include a substantial treatment of web services (Fig. 1.17). The applications-development methodology of *mashups* enables you to rapidly develop powerful software applications by combining (often free) complementary web services and other forms of information feeds. One of the first mashups combined the real-estate listings provided by www.craigslist.org with the mapping capabilities of *Google Maps* to offer maps that showed the locations of homes for sale or rent in a given area.

Web services source	How it’s used
Google Maps	Mapping services
Twitter	Microblogging

Fig. 1.17 | Some popular web services (www.programmableweb.com/apis/directory/1?sort=mashups). (Part 1 of 2.)

Web services source	How it's used
YouTube	Video search
Facebook	Social networking
Instagram	Photo sharing
Foursquare	Mobile check-in
LinkedIn	Social networking for business
Groupon	Social commerce
Netflix	Movie rentals
eBay	Internet auctions
Wikipedia	Collaborative encyclopedia
PayPal	Payments
Last.fm	Internet radio
Amazon eCommerce	Shopping for books and many other products
Salesforce.com	Customer Relationship Management (CRM)
Skype	Internet telephony
Microsoft Bing	Search
Flickr	Photo sharing
Zillow	Real-estate pricing
Yahoo Search	Search
WeatherBug	Weather

Fig. 1.17 | Some popular web services (www.programmableweb.com/apis/directory/1?sort=mashups). (Part 2 of 2.)

1.11.4 Ajax

Ajax helps Internet-based applications perform like desktop applications—a difficult task, given that such applications suffer transmission delays as data is shuttled back and forth between your computer and server computers on the Internet. Using Ajax, applications like Google Maps have achieved excellent performance and approach the look-and-feel of desktop applications. Although we don't discuss "raw" Ajax programming (which is quite complex) in this text, we do show in online Chapter 31 how to build Ajax-enabled applications using JavaServer Faces (JSF) Ajax-enabled components.

1.11.5 The Internet of Things

The Internet is no longer just a network of computers—it's an **Internet of Things**. A *thing* is any object with an IP address and the ability to send data automatically over a network—e.g., a car with a transponder for paying tolls, a heart monitor implanted in a human, a smart meter that reports energy usage, mobile apps that can track your movement and location, and smart thermostats that adjust room temperatures based on weather forecasts and activity in the home. You'll use IP addresses to build networked applications in online Chapter 28.

1.12 Software Technologies

Figure 1.18 lists a number of buzzwords that you'll hear in the software development community. We've created Resource Centers on most of these topics, with more on the way.

Technology	Description
Agile software development	Agile software development is a set of methodologies that try to get software implemented faster and using fewer resources. Check out the Agile Alliance (www.agilealliance.org) and the Agile Manifesto (www.agilemanifesto.org).
Refactoring	Refactoring involves reworking programs to make them clearer and easier to maintain while preserving their correctness and functionality. It's widely employed with agile development methodologies. Many IDEs contain built-in <i>refactoring tools</i> to do major portions of the reworking automatically.
Design patterns	Design patterns are proven architectures for constructing flexible and maintainable object-oriented software. The field of design patterns tries to enumerate those recurring patterns, encouraging software designers to <i>reuse</i> them to develop better-quality software using less time, money and effort. We discuss Java design patterns in the online Appendix N.
LAMP	LAMP is an acronym for the open-source technologies that many developers use to build web applications—it stands for <i>Linux</i> , <i>Apache</i> , <i>MySQL</i> and <i>PHP</i> (or <i>Perl</i> or <i>Python</i> —two other scripting languages). MySQL is an open-source database management system. PHP is the most popular open-source server-side “scripting” language for developing web applications. Apache is the most popular web server software. The equivalent for Windows development is WAMP— <i>Windows</i> , <i>Apache</i> , <i>MySQL</i> and <i>PHP</i> .
Software as a Service (SaaS)	Software has generally been viewed as a product; most software still is offered this way. If you want to run an application, you buy a software package from a software vendor—often a CD, DVD or web download. You then install that software on your computer and run it as needed. As new versions appear, you upgrade your software, often at considerable cost in time and money. This process can become cumbersome for organizations that must maintain tens of thousands of systems on a diverse array of computer equipment. With Software as a Service (SaaS) , the software runs on servers elsewhere on the Internet. When that server is updated, all clients worldwide see the new capabilities—no local installation is needed. You access the service through a browser. Browsers are quite portable, so you can run the same applications on a wide variety of computers from anywhere in the world. Salesforce.com, Google, and Microsoft's Office Live and Windows Live all offer SaaS.
Platform as a Service (PaaS)	Platform as a Service (PaaS) provides a computing platform for developing and running applications as a service over the web, rather than installing the tools on your computer. Some PaaS providers are Google App Engine, Amazon EC2 and Windows Azure™.

Fig. 1.18 | Software technologies. (Part 1 of 2.)

Technology	Description
Cloud computing	SaaS and PaaS are examples of cloud computing . You can use software and data stored in the “cloud”—i.e., accessed on remote computers (or servers) via the Internet and available on demand—rather than having it stored on your desktop, notebook computer or mobile device. This allows you to increase or decrease computing resources to meet your needs at any given time, which is more cost effective than purchasing hardware to provide enough storage and processing power to meet occasional peak demands. Cloud computing also saves money by shifting the burden of managing these apps to the service provider.
Software Development Kit (SDK)	Software Development Kits (SDKs) include the tools and documentation developers use to program applications. For example, you'll use the Java Development Kit (JDK) to build and run Java applications.

Fig. 1.18 | Software technologies. (Part 2 of 2.)

Software is complex. Large, real-world software applications can take many months or even years to design and implement. When large software products are under development, they typically are made available to the user communities as a series of releases, each more complete and polished than the last (Fig. 1.19).

Version	Description
Alpha	<i>Alpha</i> software is the earliest release of a software product that's still under active development. Alpha versions are often buggy, incomplete and unstable and are released to a relatively small number of developers for testing new features, getting early feedback, etc.
Beta	<i>Beta</i> versions are released to a larger number of developers later in the development process after most major bugs have been fixed and new features are nearly complete. Beta software is more stable, but still subject to change.
Release candidates	<i>Release candidates</i> are generally <i>feature complete</i> , (mostly) bug free and ready for use by the community, which provides a diverse testing environment—the software is used on different systems, with varying constraints and for a variety of purposes.
Final release	Any bugs that appear in the release candidate are corrected, and eventually the final product is released to the general public. Software companies often distribute incremental updates over the Internet.
Continuous beta	Software that's developed using this approach (for example, Google search or Gmail) generally does not have version numbers. It's hosted in the <i>cloud</i> (not installed on your computer) and is constantly evolving so that users always have the latest version.

Fig. 1.19 | Software product-release terminology.

1.13 Keeping Up-to-Date with Information Technologies

Figure 1.20 lists key technical and business publications that will help you stay up-to-date with the latest news and trends and technology. You can also find a growing list of Internet- and web-related Resource Centers at www.deitel.com/ResourceCenters.html.

Publication	URL
AllThingsD	allthingsd.com
Bloomberg BusinessWeek	www.businessweek.com
CNET	news.cnet.com
Communications of the ACM	cacm.acm.org
Computerworld	www.computerworld.com
Engadget	www.engadget.com
eWeek	www.eweek.com
Fast Company	www.fastcompany.com/
Fortune	money.cnn.com/magazines/fortune
GigaOM	gigaom.com
Hacker News	news.ycombinator.com
IEEE Computer Magazine	www.computer.org/portal/web/computingnow/computer
InfoWorld	www.infoworld.com
Mashable	mashable.com
PCWorld	www.pcworld.com
SD Times	www.sdtimes.com
Slashdot	slashdot.org/
Technology Review	technologyreview.com
Techcrunch	techcrunch.com
The Next Web	thenextweb.com
The Verge	www.theverge.com
Wired	www.wired.com

Fig. 1.20 | Technical and business publications.

Self-Review Exercises

1.1 Fill in the blanks in each of the following statements:

- Computers process data under the control of sets of instructions called _____.
- The key logical units of the computer are the _____, _____, _____, _____, _____ and _____.
- The three types of languages discussed in the chapter are _____, _____ and _____.
- The programs that translate high-level language programs into machine language are called _____.

- e) _____ is an operating system for mobile devices based on the Linux kernel and Java.
- f) _____ software is generally feature complete, (supposedly) bug free and ready for use by the community.
- g) The Wii Remote, as well as many smartphones, use a(n) _____ which allows the device to respond to motion.

1.2 Fill in the blanks in each of the following sentences about the Java environment:

- a) The _____ command from the JDK executes a Java application.
- b) The _____ command from the JDK compiles a Java program.
- c) A Java source code file must end with the _____ file extension.
- d) When a Java program is compiled, the file produced by the compiler ends with the _____ file extension.
- e) The file produced by the Java compiler contains _____ that are executed by the Java Virtual Machine.

1.3 Fill in the blanks in each of the following statements (based on Section 1.5):

- a) Objects enable the design practice of _____—although they may know how to communicate with one another across well-defined interfaces, they normally are not allowed to know how other objects are implemented.
- b) Java programmers concentrate on creating _____, which contain fields and the set of methods that manipulate those fields and provide services to clients.
- c) The process of analyzing and designing a system from an object-oriented point of view is called _____.
- d) A new class of objects can be created conveniently by _____—the new class (called the subclass) starts with the characteristics of an existing class (called the superclass), possibly customizing them and adding unique characteristics of its own.
- e) _____ is a graphical language that allows people who design software systems to use an industry-standard notation to represent them.
- f) The size, shape, color and weight of an object are considered _____ of the object's class.

Answers to Self-Review Exercises

1.1 a) programs. b) input unit, output unit, memory unit, central processing unit, arithmetic and logic unit, secondary storage unit. c) machine languages, assembly languages, high-level languages. d) compilers. e) Android. f) Release candidate. g) accelerometer.

1.2 a) java. b) javac. c) .java. d) .class. e) bytecodes.

1.3 a) information hiding. b) classes. c) object-oriented analysis and design (OOAD). d) inheritance. e) The Unified Modeling Language (UML). f) attributes.

Exercises

1.4 Fill in the blanks in each of the following statements:

- a) The logical unit that receives information from outside the computer for use by the computer is the _____.
- b) The process of instructing the computer to solve a problem is called _____.
- c) _____ is a type of computer language that uses Englishlike abbreviations for machine-language instructions.
- d) _____ is a logical unit that sends information which has already been processed by the computer to various devices so that it may be used outside the computer.
- e) _____ and _____ are logical units of the computer that retain information.
- f) _____ is a logical unit of the computer that performs calculations.
- g) _____ is a logical unit of the computer that makes logical decisions.

- h) _____ languages are most convenient to the programmer for writing programs quickly and easily.
- i) The only language a computer can directly understand is that computer's _____.
- j) _____ is a logical unit of the computer that coordinates the activities of all the other logical units.

1.5 Fill in the blanks in each of the following statements:

- a) The _____ programming language is now used to develop large-scale enterprise applications, to enhance the functionality of web servers, to provide applications for consumer devices and for many other purposes.
- b) _____ initially became widely known as the development language of the UNIX operating system.
- c) The _____ ensures that messages, consisting of sequentially numbered pieces called bytes, were properly routed from sender to receiver, arrived intact and were assembled in the correct order.
- d) The _____ programming language was developed by Bjarne Stroustrup in the early 1980s at Bell Laboratories.

1.6 Fill in the blanks in each of the following statements:

- a) Java programs normally go through five phases—_____, _____, _____, _____ and _____.
- b) A(n) _____ provides many tools that support the software development process, such as editors for writing and editing programs, debuggers for locating logic errors in programs, and many other features.
- c) The command `java` invokes the _____, which executes Java programs.
- d) A(n) _____ is a software application that simulates a computer, but hides the underlying operating system and hardware from the programs that interact with it.
- e) The _____ takes the `.class` files containing the program's bytecodes and transfers them to primary memory.
- f) The _____ examines bytecodes to ensure that they're valid.

1.7 Explain the two compilation phases of Java programs.

1.8 One of the world's most common objects is a wrist watch. Discuss how each of the following terms and concepts applies to the notion of a watch: object, attributes, behaviors, class, inheritance (consider, for example, an alarm clock), modeling, messages, encapsulation, interface and information hiding.

Making a Difference

Throughout the book we've included Making a Difference exercises in which you'll be asked to work on problems that really matter to individuals, communities, countries and the world. For more information about worldwide organizations working to make a difference, and for related programming project ideas, visit our Making a Difference Resource Center at www.deitel.com/makingadifference.

1.9 (*Test-Drive: Carbon Footprint Calculator*) Some scientists believe that carbon emissions, especially from the burning of fossil fuels, contribute significantly to global warming and that this can be combatted if individuals take steps to limit their use of carbon-based fuels. Organizations and individuals are increasingly concerned about their "carbon footprints." Websites such as TerraPass

<http://www.terrapass.com/carbon-footprint-calculator/>

and Carbon Footprint

<http://www.carbonfootprint.com/calculator.aspx>

provide carbon-footprint calculators. Test-drive these calculators to determine your carbon footprint. Exercises in later chapters will ask you to program your own carbon-footprint calculator. To prepare for this, use the web to research the formulas for calculating carbon footprints.

1.10 (*Test-Drive: Body Mass Index Calculator*) Obesity causes significant increases in illnesses such as diabetes and heart disease. To determine whether a person is overweight or obese, you can use a measure called the body mass index (BMI). The United States Department of Health and Human Services provides a BMI calculator at <http://www.nhlbi.nih.gov/guidelines/obesity/BMI/bmicalc.htm>. Use it to calculate your own BMI. A forthcoming exercise will ask you to program your own BMI calculator. To prepare for this, use the web to research the formulas for calculating BMI.

1.11 (*Attributes of Hybrid Vehicles*) In this chapter you learned some basics of classes. Now you'll "flesh out" aspects of a class called "Hybrid Vehicle." Hybrid vehicles are becoming increasingly popular, because they often get much better mileage than purely gasoline-powered vehicles. Browse the web and study the features of four or five of today's popular hybrid cars, then list as many of their hybrid-related attributes as you can. Some common attributes include city-miles-per-gallon and highway-miles-per-gallon. Also list the attributes of the batteries (type, weight, etc.).

1.12 (*Gender Neutrality*) Many people want to eliminate sexism in all forms of communication. You've been asked to create a program that can process a paragraph of text and replace gender-specific words with gender-neutral ones. Assuming that you've been given a list of gender-specific words and their gender-neutral replacements (e.g., replace both "wife" and "husband" with "spouse," "man" and "woman" with "person," "daughter" and "son" with "child"), explain the procedure you'd use to read through a paragraph of text and manually perform these replacements. How might your procedure generate a strange term like "woperchild?" You'll soon learn that a more formal term for "procedure" is "algorithm," and that an algorithm specifies the steps to be performed and the order in which to perform them. We'll show how to develop algorithms then convert them to Java programs which can be run on computers.

2

Introduction to Java Applications; Input/Output and Operators

*What's in a name?
That which we call a rose
By any other name would
smell as sweet.*

—William Shakespeare

*The chief merit of language
is clearness.*

—Galen

*One person can make a
difference and every person
should try.*

—John F. Kennedy

Objectives

In this chapter you'll:

- Write simple Java applications.
- Use input and output statements.
- Learn about Java's primitive types.
- Understand basic memory concepts.
- Use arithmetic operators.
- Learn the precedence of arithmetic operators.
- Write decision-making statements.
- Use relational and equality operators.



2.1 Introduction	2.5.7 Prompting for and Inputting a Second <code>int</code>
2.2 Your First Program in Java: Printing a Line of Text	2.5.8 Using Variables in a Calculation
2.3 Modifying Your First Java Program	2.5.9 Displaying the Result of the Calculation
2.4 Displaying Text with <code>printf</code>	2.5.10 Java API Documentation
2.5 Another Application: Adding Integers	2.6 Memory Concepts
2.5.1 <code>import</code> Declarations	2.7 Arithmetic
2.5.2 Declaring Class <code>Addition</code>	2.8 Decision Making: Equality and Relational Operators
2.5.3 Declaring and Creating a <code>Scanner</code> to Obtain User Input from the Keyboard	2.9 (Optional) GUI and Graphics Case Study: Using Dialog Boxes
2.5.4 Declaring Variables to Store Integers	2.10 Wrap-Up
2.5.5 Prompting the User for Input	
2.5.6 Obtaining an <code>int</code> as Input from the User	

Summary | Self-Review Exercises | Answers to Self-Review Exercises | Exercises | Making a Difference

2.1 Introduction

This chapter introduces Java application programming. We begin with examples of programs that display (output) messages on the screen. We then present a program that obtains (inputs) two numbers from a user, calculates their sum and displays the result. You'll learn how to instruct the computer to perform arithmetic calculations and save their results for later use. The last example demonstrates how to make decisions. The application compares two numbers, then displays messages that show the comparison results. You'll use the JDK command-line tools to compile and run this chapter's programs. If you prefer to use an integrated development environment (IDE), we've also posted Dive Into[®] videos at <http://www.deitel.com/books/jhttp10LOV/> for Eclipse, NetBeans and IntelliJ IDEA.

2.2 Your First Program in Java: Printing a Line of Text

A Java **application** is a computer program that executes when you use the **java** command to launch the Java Virtual Machine (JVM). Later in this section we'll discuss how to compile and run a Java application. First we consider a simple application that displays a line of text. Figure 2.1 shows the program followed by a box that displays its output.

```

1 // Fig. 2.1: Welcome1.java
2 // Text-printing program.
3
4 public class Welcome1
5 {
6     // main method begins execution of Java application
7     public static void main(String[] args)
8     {
9         System.out.println("Welcome to Java Programming!");
10    } // end method main
11 } // end class Welcome1

```

Fig. 2.1 | Text-printing program. (Part 1 of 2.)

```
Welcome to Java Programming!
```

Fig. 2.1 | Text-printing program. (Part 2 of 2.)

The program includes line numbers. We've added these for instructional purposes—they're *not* part of a Java program. This example illustrates several important Java features. We'll see that line 9 does the work—displaying the phrase `Welcome to Java Programming!` on the screen.

Commenting Your Programs

We insert **comments** to **document programs** and improve their readability. The Java compiler *ignores* comments, so they do *not* cause the computer to perform any action when the program is run.

By convention, we begin every program with a comment indicating the figure number and filename. The comment in line 1

```
// Fig. 2.1: Welcome1.java
```

begins with `//`, indicating that it's an **end-of-line comment**—it terminates at the end of the line on which the `//` appears. An end-of-line comment need not begin a line; it also can begin in the middle of a line and continue until the end (as in lines 6, 10 and 11). Line 2

```
// Text-printing program.
```

by our convention, is a comment that describes the purpose of the program.

Java also has **traditional comments**, which can be spread over several lines as in

```
/* This is a traditional comment. It
   can be split over multiple lines */
```

These begin and end with delimiters, `/*` and `*/`. The compiler ignores all text between the delimiters. Java incorporated traditional comments and end-of-line comments from the C and C++ programming languages, respectively. We prefer using `//` comments.

Java provides comments of a third type—**Javadoc comments**. These are delimited by `/**` and `*/`. The compiler ignores all text between the delimiters. Javadoc comments enable you to embed program documentation directly in your programs. Such comments are the preferred Java documenting format in industry. The **javadoc utility program** (part of the JDK) reads Javadoc comments and uses them to prepare program documentation in HTML format. We demonstrate Javadoc comments and the javadoc utility in online Appendix G, Creating Documentation with javadoc.



Common Programming Error 2.1

*Forgetting one of the delimiters of a traditional or Javadoc comment is a syntax error. A **syntax error** occurs when the compiler encounters code that violates Java's language rules (i.e., its syntax). These rules are similar to a natural language's grammar rules specifying sentence structure. Syntax errors are also called **compiler errors**, **compile-time errors** or **compilation errors**, because the compiler detects them when compiling the program. When a syntax error is encountered, the compiler issues an error message. You must eliminate all compilation errors before your program will compile properly.*



Good Programming Practice 2.1

Some organizations require that every program begin with a comment that states the purpose of the program and the author, date and time when the program was last modified.

Using Blank Lines

Line 3 is a blank line. Blank lines, space characters and tabs make programs easier to read. Together, they're known as **white space** (or whitespace). The compiler ignores white space.



Good Programming Practice 2.2

Use blank lines and spaces to enhance program readability.

Declaring a Class

Line 4

```
public class Welcome1
```

begins a **class declaration** for class `Welcome1`. Every Java program consists of at least one class that you (the programmer) define. The **class keyword** introduces a class declaration and is immediately followed by the **class name** (`Welcome1`). **Keywords** (sometimes called **reserved words**) are reserved for use by Java and are always spelled with all lowercase letters. The complete list of keywords is shown in Appendix C.

In Chapters 1–7, every class we define begins with the **public** keyword. For now, we simply require `public`. You'll learn more about `public` and non-`public` classes in Chapter 8.

Filename for a `public` Class

A `public` class *must* be placed in a file that has a filename of the form `ClassName.java`, so class `Welcome1` is stored in the file `Welcome1.java`.



Common Programming Error 2.2

A compilation error occurs if a `public` class's filename is not exactly same name as the class (in terms of both spelling and capitalization) followed by the `.java` extension.

Class Names and Identifiers

By convention, class names begin with a capital letter and capitalize the first letter of each word they include (e.g., `SampleClassName`). A class name is an **identifier**—a series of characters consisting of letters, digits, underscores (`_`) and dollar signs (`$`) that does *not* begin with a digit and does *not* contain spaces. Some valid identifiers are `Welcome1`, `$value`, `_value`, `m_inputField1` and `button7`. The name `7button` is *not* a valid identifier because it begins with a digit, and the name `input field` is *not* a valid identifier because it contains a space. Normally, an identifier that does not begin with a capital letter is not a class name. Java is **case sensitive**—uppercase and lowercase letters are distinct—so `value` and `Value` are different (but both valid) identifiers.

Class Body

A **left brace** (as in line 5), `{`, begins the **body** of every class declaration. A corresponding **right brace** (at line 11), `}`, must end each class declaration. Lines 6–10 are indented.



Good Programming Practice 2.3

Indent the entire body of each class declaration one “level” between the left brace and the right brace that delimit the body of the class. This format emphasizes the class declaration’s structure and makes it easier to read. We use three spaces to form a level of indent—many programmers prefer two or four spaces. Whatever you choose, use it consistently.



Error-Prevention Tip 2.1

When you type an opening left brace, {, immediately type the closing right brace, }, then reposition the cursor between the braces and indent to begin typing the body. This practice helps prevent errors due to missing braces. Many IDEs insert the closing right brace for you when you type the opening left brace.



Common Programming Error 2.3

It’s a syntax error if braces do not occur in matching pairs.



Good Programming Practice 2.4

IDEs typically indent code for you. The Tab key may also be used to indent code. You can configure each IDE to specify the number of spaces inserted when you press Tab.

Declaring a Method

Line 6

```
// main method begins execution of Java application
```

is an end-of-line comment indicating the purpose of lines 7–10 of the program. Line 7

```
public static void main(String[] args)
```

is the starting point of every Java application. The **parentheses** after the identifier `main` indicate that it’s a program building block called a **method**. Java class declarations normally contain one or more methods. For a Java application, one of the methods *must* be called `main` and must be defined as shown in line 7; otherwise, the Java Virtual Machine (JVM) will not execute the application. Methods perform tasks and can return information when they complete their tasks. We’ll explain the purpose of keyword `static` in Chapter 5. Keyword **`void`** indicates that this method will *not* return any information. Later, we’ll see how a method can return information. For now, simply mimic `main`’s first line in your Java applications. In line 7, the `String[] args` in parentheses is a required part of the method `main`’s declaration—we discuss this in Chapter 6.

The left brace in line 8 begins the **body of the method declaration**. A corresponding right brace must end it (line 10). Line 9 in the method body is indented between the braces.



Good Programming Practice 2.5

Indent the entire body of each method declaration one “level” between the braces that define the body of the method. This makes the structure of the method stand out and makes the method declaration easier to read.

Performing Output with `System.out.println`

Line 9

```
System.out.println("Welcome to Java Programming!");
```

instructs the computer to perform an action—namely, to display the characters contained between the double quotation marks (the quotation marks themselves are *not* displayed). Together, the quotation marks and the characters between them are a **string**—also known as a **character string** or a **string literal**. White-space characters in strings are *not* ignored by the compiler. Strings *cannot* span multiple lines of code.

The **System.out** object—which is predefined for you—is known as the **standard output object**. It allows a Java application to display information in the **command window** from which it executes. In recent versions of Microsoft Windows, the command window is the **Command Prompt**. In UNIX/Linux/Mac OS X, the command window is called a **terminal window** or a **shell**. Many programmers call it simply the **command line**.

Method **System.out.println** displays (or prints) a line of text in the command window. The string in the parentheses in line 9 is the **argument** to the method. When **System.out.println** completes its task, it positions the output cursor (the location where the next character will be displayed) at the beginning of the next line in the command window. This is similar to what happens when you press the *Enter* key while typing in a text editor—the cursor appears at the beginning of the next line in the document.

The entire line 9, including **System.out.println**, the argument "Welcome to Java Programming!" in the parentheses and the **semicolon (;)**, is called a **statement**. A method typically contains one or more statements that perform its task. Most statements end with a semicolon. When the statement in line 9 executes, it displays **Welcome to Java Programming!** in the command window.

When learning how to program, sometimes it's helpful to "break" a working program so you can familiarize yourself with the compiler's syntax-error messages. These messages do not always state the exact problem in the code. When you encounter an error message, it will give you an idea of what caused the error. [Try removing a semicolon or brace from the program of Fig. 2.1, then recompile the program to see the error messages generated by the omission.]



Error-Prevention Tip 2.2

When the compiler reports a syntax error, it may not be on the line that the error message indicates. First, check the line for which the error was reported. If you don't find an error on that line, check several preceding lines.

Using End-of-Line Comments on Right Braces for Readability

As an aid to programming novices, we include an end-of-line comment after a closing brace that ends a method declaration and after a closing brace that ends a class declaration. For example, line 10

```
} // end method main
```

indicates the closing brace of method **main**, and line 11

```
} // end class Welcome1
```

indicates the closing brace of class **Welcome1**. Each comment indicates the method or class that the right brace terminates. We'll omit such ending comments after this chapter.

Compiling Your First Java Application

We're now ready to compile and execute our program. We assume you're using the Java Development Kit's command-line tools, not an IDE. To help you compile and run your

programs in an IDE, we provide online Dive Into® videos for the popular IDEs Eclipse, NetBeans and IntelliJ IDEA. These are located on the book's website:

```
http://www.deitel.com/books/jhttp10LOV
```

To prepare to compile the program, open a command window and change to the directory where the program is stored. Many operating systems use the command `cd` to change directories. On Windows, for example,

```
cd c:\examples\ch02\fig02_01
```

changes to the `fig02_01` directory. On UNIX/Linux/Max OS X, the command

```
cd ~/examples/ch02/fig02_01
```

changes to the `fig02_01` directory. To compile the program, type

```
javac Welcome1.java
```

If the program contains no compilation errors, this command creates a new file called `Welcome1.class` (known as the **class file** for `Welcome1`) containing the platform-independent Java bytecodes that represent our application. When we use the `java` command to execute the application on a given platform, the JVM will translate these bytecodes into instructions that are understood by the underlying operating system and hardware.



Common Programming Error 2.4

*When using `javac`, if you receive a message such as “bad command or filename,” “`javac`: command not found” or “`javac` is not recognized as an internal or external command, operable program or batch file,” then your Java software installation was not completed properly. This indicates that the system’s `PATH` environment variable was not set properly. Carefully review the installation instructions in the *Before You Begin* section of this book. On some systems, after correcting the `PATH`, you may need to reboot your computer or open a new command window for these settings to take effect.*

Each syntax-error message contains the filename and line number where the error occurred. For example, `Welcome1.java:6` indicates that an error occurred at line 6 in `Welcome1.java`. The rest of the message provides information about the syntax error.



Common Programming Error 2.5

The compiler error message “class `Welcome1` is public, should be declared in a file named `Welcome1.java`” indicates that the filename does not match the name of the public class in the file or that you typed the class name incorrectly when compiling the class.

Executing the `Welcome1` Application

The following instructions assume that the book's examples are located in `C:\examples` on Windows or in your user account's `Documents/examples` folder on Linux/OS X. To execute this program in a command window, change to the directory containing `Welcome1.java`—`C:\examples\ch02\fig02_01` on Microsoft Windows or `~/Documents/examples/ch02/fig02_01` on Linux/OS X. Next, type

```
java Welcome1
```

and press *Enter*. This command launches the JVM, which loads the `Welcome1.class` file. The command *omits* the `.class` file-name extension; otherwise, the JVM will *not* execute

the program. The JVM calls class `Welcome1`'s `main` method. Next, the statement at line 9 of `main` displays "Welcome to Java Programming!". Figure 2.2 shows the program executing in a Microsoft Windows **Command Prompt** window. [Note: Many environments show command windows with black backgrounds and white text. We adjusted these settings to make our screen captures more readable.]



Error-Prevention Tip 2.3

When attempting to run a Java program, if you receive a message such as "Exception in thread "main" java.lang.NoClassDefFoundError: Welcome1," your CLASSPATH environment variable has not been set properly. Please carefully review the installation instructions in the Before You Begin section of this book. On some systems, you may need to reboot your computer or open a new command window after configuring the CLASSPATH.

You type this command to execute the application

The program outputs to the screen
Welcome to Java Programming!

Fig. 2.2 | Executing `Welcome1` from the **Command Prompt**.

2.3 Modifying Your First Java Program

In this section, we modify the example in Fig. 2.1 to print text on one line by using multiple statements and to print text on several lines by using a single statement.

Displaying a Single Line of Text with Multiple Statements

Welcome to Java Programming! can be displayed several ways. Class `Welcome2`, shown in Fig. 2.3, uses two statements (lines 9–10) to produce the output shown in Fig. 2.1. [Note: From this point forward, we highlight with a yellow background the new and key features in each code listing, as we've done for lines 9–10.]

```

1 // Fig. 2.3: Welcome2.java
2 // Printing a line of text with multiple statements.
3
4 public class Welcome2
5 {
6     // main method begins execution of Java application
7     public static void main(String[] args)
8     {
9         System.out.print("Welcome to ");
10        System.out.println("Java Programming!");
11    } // end method main
12 } // end class Welcome2

```

Fig. 2.3 | Printing a line of text with multiple statements. (Part I of 2.)

```
Welcome to Java Programming!
```

Fig. 2.3 | Printing a line of text with multiple statements. (Part 2 of 2.)

The program is similar to Fig. 2.1, so we discuss only the changes here. Line 2

```
// Printing a line of text with multiple statements.
```

is an end-of-line comment stating the purpose of the program. Line 4 begins the `Welcome2` class declaration. Lines 9–10 of method `main`

```
System.out.print("Welcome to ");
System.out.println("Java Programming!");
```

display one line of text. The first statement uses `System.out`'s method `print` to display a string. Each `print` or `println` statement resumes displaying characters from where the last `print` or `println` statement stopped displaying characters. Unlike `println`, after displaying its argument, `print` does *not* position the output cursor at the beginning of the next line in the command window—the next character the program displays will appear *immediately after* the last character that `print` displays. So, line 10 positions the first character in its argument (the letter “J”) immediately after the last character that line 9 displays (the *space character* before the string's closing double-quote character).

Displaying Multiple Lines of Text with a Single Statement

A single statement can display multiple lines by using **newline characters**, which indicate to `System.out`'s `print` and `println` methods when to position the output cursor at the beginning of the next line in the command window. Like blank lines, space characters and tab characters, newline characters are whitespace characters. The program in Fig. 2.4 outputs four lines of text, using newline characters to determine when to begin each new line. Most of the program is identical to those in Figs. 2.1 and 2.3.

```
1 // Fig. 2.4: Welcome3.java
2 // Printing multiple lines of text with a single statement.
3
4 public class Welcome3
5 {
6     // main method begins execution of Java application
7     public static void main(String[] args)
8     {
9         System.out.println("Welcome\nto\nJava\nProgramming!");
10    } // end method main
11 } // end class Welcome3
```

```
Welcome
to
Java
Programming!
```

Fig. 2.4 | Printing multiple lines of text with a single statement.

Line 9

```
System.out.println("Welcome\nto\nJava\nProgramming!");
```

displays four separate lines of text in the command window. Normally, the characters in a string are displayed *exactly* as they appear in the double quotes. Note, however, that the paired characters `\` and `n` (repeated three times in the statement) do *not* appear on the screen. The **backslash** (`\`) is an **escape character**, which has special meaning to `System.out`'s `print` and `println` methods. When a backslash appears in a string, Java combines it with the next character to form an **escape sequence**. The escape sequence `\n` represents the newline character. When a newline character appears in a string being output with `System.out`, the newline character causes the screen's output cursor to move to the beginning of the next line in the command window.

Figure 2.5 lists several common escape sequences and describes how they affect the display of characters in the command window. For the complete list of escape sequences, visit

```
http://docs.oracle.com/javase/specs/jls/se7/html/
jls-3.html#jls-3.10.6
```

Escape sequence	Description
<code>\n</code>	Newline. Position the screen cursor at the beginning of the <i>next</i> line.
<code>\t</code>	Horizontal tab. Move the screen cursor to the next tab stop.
<code>\r</code>	Carriage return. Position the screen cursor at the beginning of the <i>current</i> line—do <i>not</i> advance to the next line. Any characters output after the carriage return <i>overwrite</i> the characters previously output on that line.
<code>\\</code>	Backslash. Used to print a backslash character.
<code>\"</code>	Double quote. Used to print a double-quote character. For example, <code>System.out.println("\"in quotes\")</code> ; displays <code>"in quotes"</code> .

Fig. 2.5 | Some common escape sequences.

2.4 Displaying Text with printf

The `System.out.printf` method (`f` means “formatted”) displays *formatted* data. Figure 2.6 uses this method to output on two lines the strings “Welcome to” and “Java Programming!”. Lines 9–10

```
System.out.printf("%s%n%s%n",
    "Welcome to", "Java Programming!");
```

call method `System.out.printf` to display the program's output. The method call specifies three arguments. When a method requires multiple arguments, they're placed in a comma-separated list.



Good Programming Practice 2.6

Place a space after each comma (,) in an argument list to make programs more readable.

```

1 // Fig. 2.6: Welcome4.java
2 // Displaying multiple lines with method System.out.printf.
3
4 public class Welcome4
5 {
6     // main method begins execution of Java application
7     public static void main(String[] args)
8     {
9         System.out.printf("%s%n%s%n",
10             "Welcome to", "Java Programming!");
11     } // end method main
12 } // end class Welcome4

```

```

Welcome to
Java Programming!

```

Fig. 2.6 | Displaying multiple lines with method `System.out.printf`.

Lines 9–10 represent only *one* statement. Java allows large statements to be split over many lines. We indent line 10 to indicate that it's a *continuation* of line 9.



Common Programming Error 2.6

Splitting a statement in the middle of an identifier or a string is a syntax error.

Method `printf`'s first argument is a **format string** that may consist of **fixed text** and **format specifiers**. Fixed text is output by `printf` just as it would be by `print` or `println`. Each format specifier is a *placeholder* for a value and specifies the *type of data* to output. Format specifiers also may include optional formatting information.

Format specifiers begin with a percent sign (%) followed by a character that represents the *data type*. For example, the format specifier **%s** is a placeholder for a string. The format string in line 9 specifies that `printf` should output two strings, each followed by a newline character. At the first format specifier's position, `printf` substitutes the value of the first argument after the format string. At each subsequent format specifier's position, `printf` substitutes the value of the next argument. So this example substitutes "Welcome to" for the first %s and "Java Programming!" for the second %s. The output shows that two lines of text are displayed on two lines.

Notice that instead of using the escape sequence `\n`, we used the **%n** format specifier, which is a line separator that's *portable* across operating systems. You cannot use `%n` in the argument to `System.out.print` or `System.out.println`; however, the line separator output by `System.out.println` *after* it displays its argument *is* portable across operating systems. Online Appendix I presents more details of formatting output with `printf`.

2.5 Another Application: Adding Integers

Our next application reads (or inputs) two **integers** (whole numbers, such as -22, 7, 0 and 1024) typed by a user at the keyboard, computes their sum and displays it. This program must keep track of the numbers supplied by the user for the calculation later in the program. Programs remember numbers and other data in the computer's memory and access

that data through program elements called **variables**. The program of Fig. 2.7 demonstrates these concepts. In the sample output, we use bold text to identify the user's input (i.e., **45** and **72**). As in prior programs, Lines 1–2 state the figure number, filename and purpose of the program.

```

1 // Fig. 2.7: Addition.java
2 // Addition program that inputs two numbers then displays their sum.
3 import java.util.Scanner; // program uses class Scanner
4
5 public class Addition
6 {
7     // main method begins execution of Java application
8     public static void main(String[] args)
9     {
10        // create a Scanner to obtain input from the command window
11        Scanner input = new Scanner(System.in);
12
13        int number1; // first number to add
14        int number2; // second number to add
15        int sum; // sum of number1 and number2
16
17        System.out.print("Enter first integer: "); // prompt
18        number1 = input.nextInt(); // read first number from user
19
20        System.out.print("Enter second integer: "); // prompt
21        number2 = input.nextInt(); // read second number from user
22
23        sum = number1 + number2; // add numbers, then store total in sum
24
25        System.out.printf("Sum is %d\n", sum); // display sum
26    } // end method main
27 } // end class Addition

```

```

Enter first integer: 45
Enter second integer: 72
Sum is 117

```

Fig. 2.7 | Addition program that inputs two numbers then displays their sum.

2.5.1 import Declarations

A great strength of Java is its rich set of predefined classes that you can *reuse* rather than “reinventing the wheel.” These classes are grouped into **packages**—*named groups of related classes*—and are collectively referred to as the **Java class library**, or the **Java Application Programming Interface (Java API)**. Line 3

```
import java.util.Scanner; // program uses class Scanner
```

is an **import declaration** that helps the compiler locate a class that's used in this program. It indicates that this example uses Java's predefined Scanner class (discussed shortly) from the package that is named **java.util**. This enables the compiler to ensure that you use the class correctly.



Common Programming Error 2.7

All import declarations must appear before the first class declaration in the file. Placing an import declaration inside or after a class declaration is a syntax error.



Common Programming Error 2.8

Forgetting to include an import declaration for a class that must be imported results in a compilation error containing a message such as “cannot find symbol.” When this occurs, check that you provided the proper import declarations and that the names in them are correct, including proper capitalization.



Software Engineering Observation 2.1

*In each new Java version, the APIs typically contain new capabilities that fix bugs, improve performance or offer better means for accomplishing tasks. The corresponding older versions are no longer needed and should not be used. Such APIs are said to be **deprecated** and might be removed from later Java versions.*

You'll often encounter deprecated APIs when browsing the online API documentation. The compiler will warn you when you compile code that uses deprecated APIs. If you compile your code with javac using the command-line argument `-deprecation`, the compiler will tell you which deprecated features you're using. For each one, the online documentation (<http://docs.oracle.com/javase/7/docs/api/>) indicates and typically links to the new feature that replaces the deprecated one.

2.5.2 Declaring Class Addition

Line 5

```
public class Addition
```

begins the declaration of class `Addition`. The filename for this public class must be `Addition.java`. Remember that the body of each class declaration starts with an opening left brace (line 6) and ends with a closing right brace (line 27).

The application begins execution with the `main` method (lines 8–26). The left brace (line 9) marks the beginning of method `main`'s body, and the corresponding right brace (line 26) marks its end. Method `main` is indented one level in the body of class `Addition`, and the code in the body of `main` is indented another level for readability.

2.5.3 Declaring and Creating a Scanner to Obtain User Input from the Keyboard

A **variable** is a location in the computer's memory where a value can be stored for use later in a program. All Java variables *must* be declared with a **name** and a **type** *before* they can be used. A variable's *name* enables the program to access the *value* of the variable in memory. A variable's name can be any valid identifier—again, a series of characters consisting of letters, digits, underscores (`_`) and dollar signs (`$`) that does *not* begin with a digit and does *not* contain spaces. A variable's *type* specifies what kind of information is stored at that location in memory. Like other statements, declaration statements end with a semicolon (`;`).

Line 11

```
Scanner input = new Scanner(System.in);
```

is a **variable declaration statement** that specifies the *name* (input) and *type* (Scanner) of a variable that's used in this program. A **Scanner** enables a program to read data (e.g., numbers and strings) for use in a program. The data can come from many sources, such as the user at the keyboard or a file on disk. Before using a Scanner, you must create it and specify the *source* of the data.

The = in line 11 indicates that Scanner variable input should be **initialized** (i.e., prepared for use in the program) in its declaration with the result of the expression to the right of the equals sign—new Scanner(System.in). This expression uses the **new** keyword to create a Scanner object that reads characters typed by the user at the keyboard. The **standard input object, System.in**, enables applications to read *bytes* of data typed by the user. The Scanner translates these bytes into types (like ints) that can be used in a program.

2.5.4 Declaring Variables to Store Integers

The variable declaration statements in lines 13–15

```
int number1; // first number to add
int number2; // second number to add
int sum; // sum of number1 and number2
```

declare that variables number1, number2 and sum hold data of type **int**—they can hold *integer* values (whole numbers such as 72, -1127 and 0). These variables are *not* yet initialized. The range of values for an int is -2,147,483,648 to +2,147,483,647. [Note: The int values you use in a program may not contain commas.]

Some other types of data are **float** and **double**, for holding real numbers, and **char**, for holding character data. Real numbers contain decimal points, such as in 3.4, 0.0 and -11.19. Variables of type char represent individual characters, such as an uppercase letter (e.g., A), a digit (e.g., 7), a special character (e.g., * or %) or an escape sequence (e.g., the tab character, \t). The types int, float, double and char are called **primitive types**. Primitive-type names are keywords and must appear in all lowercase letters. Appendix D summarizes the characteristics of the eight primitive types (boolean, byte, char, short, int, long, float and double).

Several variables of the same type may be declared in a single declaration with the variable names separated by commas (i.e., a comma-separated list of variable names). For example, lines 13–15 can also be written as:

```
int number1, // first number to add
    number2, // second number to add
    sum; // sum of number1 and number2
```



Good Programming Practice 2.7

Declare each variable in its own declaration. This format allows a descriptive comment to be inserted next to each variable being declared.



Good Programming Practice 2.8

Choosing meaningful variable names helps a program to be self-documenting (i.e., one can understand the program simply by reading it rather than by reading associated documentation or creating and viewing an excessive number of comments).



Good Programming Practice 2.9

*By convention, variable-name identifiers begin with a lowercase letter, and every word in the name after the first word begins with a capital letter. For example, variable-name identifier `firstNumber` starts its second word, `Number`, with a capital N. This naming convention is known as **camel case**, because the uppercase letters stand out like a camel's humps.*

2.5.5 Prompting the User for Input

Line 17

```
System.out.print("Enter first integer: "); // prompt
```

uses `System.out.print` to display the message "Enter first integer: ". This message is called a **prompt** because it directs the user to take a specific action. We use method `print` here rather than `println` so that the user's input appears on the same line as the prompt. Recall from Section 2.2 that identifiers starting with capital letters typically represent class names. Class `System` is part of package `java.lang`. Notice that class `System` is *not* imported with an `import` declaration at the beginning of the program.



Software Engineering Observation 2.2

By default, package `java.lang` is imported in every Java program; thus, classes in `java.lang` are the only ones in the Java API that do not require an `import` declaration.

2.5.6 Obtaining an `int` as Input from the User

Line 18

```
number1 = input.nextInt(); // read first number from user
```

uses `Scanner` object `input`'s `nextInt` method to obtain an integer from the user at the keyboard. At this point the program *waits* for the user to type the number and press the *Enter* key to submit the number to the program.

Our program assumes that the user enters a valid integer value. If not, a runtime logic error will occur and the program will terminate. Chapter 11, *Exception Handling: A Deeper Look*, discusses how to make your programs more robust by enabling them to handle such errors. This is also known as making your program *fault tolerant*.

In line 18, we place the result of the call to method `nextInt` (an `int` value) in variable `number1` by using the **assignment operator**, `=`. The statement is read as "number1 *gets* the value of `input.nextInt()`." Operator `=` is called a **binary operator**, because it has *two operands*—`number1` and the result of the method call `input.nextInt()`. This statement is called an *assignment statement*, because it *assigns* a value to a variable. Everything to the *right* of the assignment operator, `=`, is always evaluated *before* the assignment is performed.



Good Programming Practice 2.10

Place spaces on either side of a binary operator for readability.

2.5.7 Prompting for and Inputting a Second int

Line 20

```
System.out.print("Enter second integer: "); // prompt
```

prompts the user to enter the second integer. Line 21

```
number2 = input.nextInt(); // read second number from user
```

reads the second integer and assigns it to variable `number2`.

2.5.8 Using Variables in a Calculation

Line 23

```
sum = number1 + number2; // add numbers then store total in sum
```

is an assignment statement that calculates the sum of the variables `number1` and `number2` then assigns the result to variable `sum` by using the assignment operator, `=`. The statement is read as “`sum` gets the value of `number1 + number2`.” When the program encounters the addition operation, it performs the calculation using the values stored in the variables `number1` and `number2`. In the preceding statement, the addition operator is a *binary operator*—its *two* operands are the variables `number1` and `number2`. Portions of statements that contain calculations are called **expressions**. In fact, an expression is any portion of a statement that has a *value* associated with it. For example, the value of the expression `number1 + number2` is the *sum* of the numbers. Similarly, the value of the expression `input.nextInt()` is the integer typed by the user.

2.5.9 Displaying the Result of the Calculation

After the calculation has been performed, line 25

```
System.out.printf("Sum is %d\n", sum); // display sum
```

uses method `System.out.printf` to display the sum. The format specifier `%d` is a *placeholder* for an `int` value (in this case the value of `sum`)—the letter `d` stands for “decimal integer.” The remaining characters in the format string are all fixed text. So, method `printf` displays “Sum is ”, followed by the value of `sum` (in the position of the `%d` format specifier) and a newline.

Calculations can also be performed *inside* `printf` statements. We could have combined the statements at lines 23 and 25 into the statement

```
System.out.printf("Sum is %d\n", (number1 + number2));
```

The parentheses around the expression `number1 + number2` are optional—they’re included to emphasize that the value of the *entire* expression is output in the position of the `%d` format specifier. Such parentheses are said to be **redundant**.

2.5.10 Java API Documentation

For each new Java API class we use, we indicate the package in which it’s located. This information helps you locate descriptions of each package and class in the Java API documentation. A web-based version of this documentation can be found at

```
http://docs.oracle.com/javase/7/docs/api/index.html
```

You can download it from the Additional Resources section at

<http://www.oracle.com/technetwork/java/javase/downloads/index.html>

Appendix F shows how to use this documentation.

2.6 Memory Concepts

Variable names such as `number1`, `number2` and `sum` actually correspond to *locations* in the computer's memory. Every variable has a **name**, a **type**, a **size** (in bytes) and a **value**.

In the addition program of Fig. 2.7, when the following statement (line 18) executes:

```
number1 = input.nextInt(); // read first number from user
```

the number typed by the user is placed into a memory location corresponding to the name `number1`. Suppose that the user enters 45. The computer places that integer value into location `number1` (Fig. 2.8), replacing the previous value (if any) in that location. The previous value is lost, so this process is said to be *destructive*.

number1	45
---------	----

Fig. 2.8 | Memory location showing the name and value of variable `number1`.

When the statement (line 21)

```
number2 = input.nextInt(); // read second number from user
```

executes, suppose that the user enters 72. The computer places that integer value into location `number2`. The memory now appears as shown in Fig. 2.9.

number1	45
---------	----

number2	72
---------	----

Fig. 2.9 | Memory locations after storing values for `number1` and `number2`.

After the program of Fig. 2.7 obtains values for `number1` and `number2`, it adds the values and places the total into variable `sum`. The statement (line 23)

```
sum = number1 + number2; // add numbers, then store total in sum
```

performs the addition, then replaces any previous value in `sum`. After `sum` has been calculated, memory appears as shown in Fig. 2.10. The values of `number1` and `number2` appear exactly as they did before they were used in the calculation of `sum`. These values were used, but *not* destroyed, as the computer performed the calculation. When a value is read from a memory location, the process is *nondestructive*.

number1	45
number2	72
sum	117

Fig. 2.10 | Memory locations after storing the sum of number1 and number2.

2.7 Arithmetic

Most programs perform arithmetic calculations. The **arithmetic operators** are summarized in Fig. 2.11. Note the use of various special symbols not used in algebra. The **asterisk** (*) indicates multiplication, and the percent sign (%) is the **remainder operator**, which we'll discuss shortly. The arithmetic operators in Fig. 2.11 are *binary* operators, because each operates on *two* operands. For example, the expression `f + 7` contains the binary operator `+` and the two operands `f` and `7`.

Java operation	Operator	Algebraic expression	Java expression
Addition	<code>+</code>	$f + 7$	<code>f + 7</code>
Subtraction	<code>-</code>	$p - c$	<code>p - c</code>
Multiplication	<code>*</code>	bm	<code>b * m</code>
Division	<code>/</code>	x / y or $\frac{x}{y}$ or $x \div y$	<code>x / y</code>
Remainder	<code>%</code>	$r \bmod s$	<code>r % s</code>

Fig. 2.11 | Arithmetic operators.

Integer division yields an integer quotient. For example, the expression `7 / 4` evaluates to 1, and the expression `17 / 5` evaluates to 3. Any fractional part in integer division is simply *truncated* (i.e., *discarded*)—no *rounding* occurs. Java provides the remainder operator, `%`, which yields the remainder after division. The expression `x % y` yields the remainder after `x` is divided by `y`. Thus, `7 % 4` yields 3, and `17 % 5` yields 2. This operator is most commonly used with integer operands but it can also be used with other arithmetic types. In this chapter's exercises and in later chapters, we consider several interesting applications of the remainder operator, such as determining whether one number is a multiple of another.

Arithmetic Expressions in Straight-Line Form

Arithmetic expressions in Java must be written in **straight-line form** to facilitate entering programs into the computer. Thus, expressions such as “a divided by b” must be written as `a / b`, so that all constants, variables and operators appear in a straight line. The following algebraic notation is generally not acceptable to compilers:

$$\frac{a}{b}$$

Parentheses for Grouping Subexpressions

Parentheses are used to group terms in Java expressions in the same manner as in algebraic expressions. For example, to multiply a times the quantity $b + c$, we write

```
a * (b + c)
```

If an expression contains **nested parentheses**, such as

```
((a + b) * c)
```

the expression in the *innermost* set of parentheses ($a + b$ in this case) is evaluated *first*.

Rules of Operator Precedence

Java applies the operators in arithmetic expressions in a precise sequence determined by the **rules of operator precedence**, which are generally the same as those followed in algebra:

1. Multiplication, division and remainder operations are applied first. If an expression contains several such operations, they're applied from left to right. Multiplication, division and remainder operators have the same level of precedence.
2. Addition and subtraction operations are applied next. If an expression contains several such operations, the operators are applied from left to right. Addition and subtraction operators have the same level of precedence.

These rules enable Java to apply operators in the correct *order*.¹ When we say that operators are applied from left to right, we're referring to their **associativity**. Some operators associate from right to left. Figure 2.12 summarizes these rules of operator precedence. A complete precedence chart is included in Appendix A.

Operator(s)	Operation(s)	Order of evaluation (precedence)
* / %	Multiplication Division Remainder	Evaluated first. If there are several operators of this type, they're evaluated from <i>left to right</i> .
+ -	Addition Subtraction	Evaluated next. If there are several operators of this type, they're evaluated from <i>left to right</i> .
=	Assignment	Evaluated last.

Fig. 2.12 | Precedence of arithmetic operators.

Sample Algebraic and Java Expressions

Now let's consider several expressions in light of the rules of operator precedence. Each example lists an algebraic expression and its Java equivalent. The following is an example of an arithmetic mean (average) of five terms:

1. We use simple examples to explain the *order of evaluation* of expressions. Subtle issues occur in the more complex expressions you'll encounter later in the book. For more information on order of evaluation, see Chapter 15 of *The Java™ Language Specification* (<http://docs.oracle.com/javase/specs/jls/se7/html/index.html>).

Algebra: $m = \frac{a + b + c + d + e}{5}$
 Java: `m = (a + b + c + d + e) / 5;`

The parentheses are required because division has higher precedence than addition. The entire quantity $(a + b + c + d + e)$ is to be divided by 5. If the parentheses are erroneously omitted, we obtain $a + b + c + d + e / 5$, which evaluates as

$$a + b + c + d + \frac{e}{5}$$

Here's an example of the equation of a straight line:

Algebra: $y = mx + b$
 Java: `y = m * x + b;`

No parentheses are required. The multiplication operator is applied first because multiplication has a higher precedence than addition. The assignment occurs last because it has a lower precedence than multiplication or addition.

The following example contains remainder (%), multiplication, division, addition and subtraction operations:

Algebra: $z = pr \% q + w / x - y$
 Java: `z = p * r \% q + w / x - y;`

6
1
2
4
3
5

The circled numbers under the statement indicate the *order* in which Java applies the operators. The *, % and / operations are evaluated first in *left-to-right* order (i.e., they associate from left to right), because they have higher precedence than + and -. The + and - operations are evaluated next. These operations are also applied from *left to right*. The assignment (=) operation is evaluated last.

Evaluation of a Second-Degree Polynomial

To develop a better understanding of the rules of operator precedence, consider the evaluation of an assignment expression that includes a second-degree polynomial $ax^2 + bx + c$:

`y = a * x * x + b * x + c;`

6
1
2
4
3
5

The multiplication operations are evaluated first in left-to-right order (i.e., they associate from left to right), because they have higher precedence than addition. (Java has no arithmetic operator for exponentiation, so x^2 is represented as $x * x$. Section 4.4 shows an alternative for performing exponentiation.) The addition operations are evaluated next from *left to right*. Suppose that a, b, c and x are initialized (given values) as follows: a = 2, b = 3, c = 7 and x = 5. Figure 2.13 illustrates the order in which the operators are applied.

You can use *redundant parentheses* (unnecessary parentheses) to make an expression clearer. For example, the preceding statement might be parenthesized as follows:

`y = (a * x * x) + (b * x) + c;`




Fig. 2.13 | Order in which a second-degree polynomial is evaluated.

2.8 Decision Making: Equality and Relational Operators

A **condition** is an expression that can be **true** or **false**. This section introduces Java’s **if selection statement**, which allows a program to make a **decision** based on a condition’s value. For example, the condition “grade is greater than or equal to 60” determines whether a student passed a test. If the condition in an **if** statement is *true*, the body of the **if** statement executes. If the condition is *false*, the body does not execute. We’ll see an example shortly.

Conditions in **if** statements can be formed by using the **equality operators** (`==` and `!=`) and **relational operators** (`>`, `<`, `>=` and `<=`) summarized in Fig. 2.14. Both equality operators have the same level of precedence, which is *lower* than that of the relational operators. The equality operators associate from *left to right*. The relational operators all have the same level of precedence and also associate from *left to right*.

Algebraic operator	Java equality or relational operator	Sample Java condition	Meaning of Java condition
<i>Equality operators</i>			
<code>=</code>	<code>==</code>	<code>x == y</code>	x is equal to y
<code>1</code>	<code>!=</code>	<code>x != y</code>	x is not equal to y

Fig. 2.14 | Equality and relational operators. (Part I of 2.)

Algebraic operator	Java equality or relational operator	Sample Java condition	Meaning of Java condition
<i>Relational operators</i>			
>	>	x > y	x is greater than y
<	<	x < y	x is less than y
≥	>=	x >= y	x is greater than or equal to y
≤	<=	x <= y	x is less than or equal to y

Fig. 2.14 | Equality and relational operators. (Part 2 of 2.)

Figure 2.15 uses six if statements to compare two integers input by the user. If the condition in any of these if statements is *true*, the statement associated with that if statement executes; otherwise, the statement is skipped. We use a Scanner to input the integers from the user and store them in variables `number1` and `number2`. The program *compares* the numbers and displays the results of the comparisons that are true.

```

1 // Fig. 2.15: Comparison.java
2 // Compare integers using if statements, relational operators
3 // and equality operators.
4 import java.util.Scanner; // program uses class Scanner
5
6 public class Comparison
7 {
8     // main method begins execution of Java application
9     public static void main(String[] args)
10    {
11        // create Scanner to obtain input from command line
12        Scanner input = new Scanner(System.in);
13
14        int number1; // first number to compare
15        int number2; // second number to compare
16
17        System.out.print("Enter first integer: "); // prompt
18        number1 = input.nextInt(); // read first number from user
19
20        System.out.print("Enter second integer: "); // prompt
21        number2 = input.nextInt(); // read second number from user
22
23        if (number1 == number2)
24            System.out.printf("%d == %d\n", number1, number2);
25
26        if (number1 != number2)
27            System.out.printf("%d != %d\n", number1, number2);
28
29        if (number1 < number2)
30            System.out.printf("%d < %d\n", number1, number2);

```

Fig. 2.15 | Compare integers using if statements, relational operators and equality operators. (Part 1 of 2.)

```

31
32     if (number1 > number2)
33         System.out.printf("%d > %d%n", number1, number2);
34
35     if (number1 <= number2)
36         System.out.printf("%d <= %d%n", number1, number2);
37
38     if (number1 >= number2)
39         System.out.printf("%d >= %d%n", number1, number2);
40 } // end method main
41 } // end class Comparison

```

```

Enter first integer: 777
Enter second integer: 777
777 == 777
777 <= 777
777 >= 777

```

```

Enter first integer: 1000
Enter second integer: 2000
1000 != 2000
1000 < 2000
1000 <= 2000

```

```

Enter first integer: 2000
Enter second integer: 1000
2000 != 1000
2000 > 1000
2000 >= 1000

```

Fig. 2.15 | Compare integers using `if` statements, relational operators and equality operators.
(Part 2 of 2.)

The declaration of class `Comparison` begins at line 6

```
public class Comparison
```

The class's main method (lines 9–40) begins the execution of the program. Line 12

```
Scanner input = new Scanner(System.in);
```

declares `Scanner` variable `input` and assigns it a `Scanner` that inputs data from the standard input (i.e., the keyboard).

Lines 14–15

```
int number1; // first number to compare
int number2; // second number to compare
```

declare the `int` variables used to store the values input from the user.

Lines 17–18

```
System.out.print("Enter first integer: "); // prompt
number1 = input.nextInt(); // read first number from user

```


prompt the user to enter the first integer and input the value, respectively. The value is stored in variable `number1`.

Lines 20–21

```
System.out.print("Enter second integer: "); // prompt
number2 = input.nextInt(); // read second number from user
```

prompt the user to enter the second integer and input the value, respectively. The value is stored in variable `number2`.

Lines 23–24

```
if (number1 == number2)
    System.out.printf("%d == %d\n", number1, number2);
```

compare the values of `number1` and `number2` to determine whether they're equal. An `if` statement always begins with keyword `if`, followed by a condition in parentheses. An `if` statement expects one statement in its body, but may contain multiple statements if they're enclosed in a set of braces (`{}`). The indentation of the body statement shown here is not required, but it improves the program's readability by emphasizing that the statement in line 24 *is part of* the `if` statement that begins at line 23. Line 24 executes only if the numbers stored in variables `number1` and `number2` are equal (i.e., the condition is *true*). The `if` statements in lines 26–27, 29–30, 32–33, 35–36 and 38–39 compare `number1` and `number2` using the operators `!=`, `<`, `>`, `<=` and `>=`, respectively. If the condition in one or more of the `if` statements is *true*, the corresponding body statement executes.



Common Programming Error 2.9

Confusing the equality operator, `==`, with the assignment operator, `=`, can cause a logic error or a compilation error. The equality operator should be read as “is equal to” and the assignment operator as “gets” or “gets the value of.” To avoid confusion, some people read the equality operator as “double equals” or “equals equals.”



Good Programming Practice 2.11

Place only one statement per line in a program for readability.

There's no semicolon (`;`) at the end of the first line of each `if` statement. Such a semicolon would result in a logic error at execution time. For example,

```
if (number1 == number2); // logic error
    System.out.printf("%d == %d\n", number1, number2);
```

would actually be interpreted by Java as

```
if (number1 == number2)
    ; // empty statement
    System.out.printf("%d == %d\n", number1, number2);
```

where the semicolon on the line by itself—called the **empty statement**—is the statement to execute if the condition in the `if` statement is *true*. When the empty statement executes, no task is performed. The program then continues with the output statement, which *always* executes, *regardless* of whether the condition is true or false, because the output statement is *not* part of the `if` statement.

White space

Note the use of white space in Fig. 2.15. Recall that the compiler normally ignores white space. So, statements may be split over several lines and may be spaced according to your preferences without affecting a program's meaning. It's incorrect to split identifiers and strings. Ideally, statements should be kept small, but this is not always possible.



Error-Prevention Tip 2.4

A lengthy statement can be spread over several lines. If a single statement must be split across lines, choose natural breaking points, such as after a comma in a comma-separated list, or after an operator in a lengthy expression. If a statement is split across two or more lines, indent all subsequent lines until the end of the statement.

Operators Discussed So Far

Figure 2.16 shows the operators discussed so far in decreasing order of precedence. All but the assignment operator, `=`, associate from *left to right*. The assignment operator, `=`, associates from *right to left*. An assignment expression's value is whatever was assigned to the variable on the `=` operator's left side—for example, the value of the expression `x = 7` is 7. So an expression like `x = y = 0` is evaluated as if it had been written as `x = (y = 0)`, which first assigns the value 0 to variable `y`, then assigns the result of that assignment, 0, to `x`.



Good Programming Practice 2.12

When writing expressions containing many operators, refer to the operator precedence chart (Appendix A). Confirm that the operations in the expression are performed in the order you expect. If, in a complex expression, you're uncertain about the order of evaluation, use parentheses to force the order, exactly as you'd do in algebraic expressions.

Operators	Associativity	Type
* / %	left to right	multiplicative
+ -	left to right	additive
< <= > >=	left to right	relational
== !=	left to right	equality
=	right to left	assignment

Fig. 2.16 | Precedence and associativity of operators discussed.

2.9 (Optional) GUI and Graphics Case Study: Using Dialog Boxes

This optional case study is designed for those who want to begin learning Java's capabilities for creating graphical user interfaces (GUIs) and graphics early in the book, before the deeper discussions of these topics later in the book. This case study features Java's mature Swing technology, which as of this writing is still a bit more popular than the newer JavaFX technology presented in later chapters.

This GUI and Graphics Case Study appears in 10 brief sections (see Fig. 2.17). Each section introduces new concepts and provides examples with screen captures that show

sample interactions and results. In the first few sections, you'll create your first graphical apps. In subsequent sections, you'll use object-oriented programming concepts to create an app that draws a variety of shapes. When we formally introduce GUIs in Chapter 12, we use the mouse to choose exactly which shapes to draw and where to draw them. In Chapter 13, we add capabilities of the Java 2D graphics API to draw the shapes with different line thicknesses and fills. We hope you find this case study informative and entertaining.

Location	Title—Exercise(s)
Section 2.4	Using Dialog Boxes—Basic input and output with dialog boxes
Section 3.14	Creating Simple Drawings—Displaying and drawing lines on the screen
Section 4.10	Drawing Rectangles and Ovals—Using shapes to represent data
Section 5.13	Colors and Filled Shapes—Drawing a bull's-eye and random graphics
Section 6.14	Drawing Arcs—Drawing spirals with arcs
Section 8.16	Using Objects with Graphics—Storing shapes as objects
Section 9.7	Displaying Text and Images Using Labels—Providing status information
Section 10.11	Drawing with Polymorphism—Identifying the similarities between shapes
Exercise 12.17	Expanding the Interface—Using GUI components and event handling
Exercise 13.31	Adding Java 2D—Using the Java 2D API to enhance drawings

Fig. 2.17 | Summary of the GUI and Graphics Case Study in each chapter.

Displaying Text in a Dialog Box

The programs presented thus far display output in the *command window*. Many apps use windows or **dialog boxes** (also called **dialogs**) to display output. Web browsers such as Chrome, Firefox, Internet Explorer, Safari and Opera display web pages in their own windows. E-mail programs allow you to type and read messages in a window. Typically, dialog boxes are windows in which programs display important messages to users. Class **JOptionPane** provides prebuilt dialog boxes that enable programs to display windows containing messages—such windows are called **message dialogs**. Figure 2.18 displays the String "Welcome to Java" in a message dialog.

```

1 // Fig. 2.18: Dialog1.java
2 // Using JOptionPane to display multiple lines in a dialog box.
3 import javax.swing.JOptionPane;
4
5 public class Dialog1
6 {
7     public static void main(String[] args)
8     {
9         // display a dialog with a message
10        JOptionPane.showMessageDialog(null, "Welcome to Java");
11    }
12 } // end class Dialog1

```

Fig. 2.18 | Using JOptionPane to display multiple lines in a dialog box. (Part 1 of 2.)



Fig. 2.18 | Using JOptionPane to display multiple lines in a dialog box. (Part 2 of 2.)

JOptionPane Class static Method showMessageDialog

Line 3 indicates that the program uses class JOptionPane from package `javax.swing`. This package contains many classes that help you create **graphical user interfaces (GUIs)**. GUI **components** facilitate data entry by a program's user and presentation of outputs to the user. Line 10 calls JOptionPane method `showMessageDialog` to display a dialog box containing a message. The method requires two arguments. The first helps the Java app determine where to position the dialog box. A dialog is typically displayed from a GUI app with its own window. The first argument refers to that window (known as the *parent window*) and causes the dialog to appear centered over the app's window. If the first argument is null, the dialog box is displayed at the center of your screen. The second argument is the String to display in the dialog box.

Introducing static Methods

JOptionPane method `showMessageDialog` is a so-called **static method**. Such methods often define frequently used tasks. For example, many programs display dialog boxes, and the code to do this is the same each time. Rather than requiring you to “reinvent the wheel” and create code to display a dialog, the designers of class JOptionPane declared a static method that performs this task for you. A static method is called by using its class name followed by a dot (.) and the method name, as in

```
ClassName.methodName(arguments)
```

Notice that you do *not* create an object of class JOptionPane to use its static method `showMessageDialog`. We discuss static methods in more detail in Chapter 5.

Entering Text in a Dialog

Figure 2.19 uses another predefined JOptionPane dialog called an **input dialog** that allows the user to *enter data* into a program. The program asks for the user's name and responds with a message dialog containing a greeting and the name that the user entered.

```
1 // Fig. 2.19: NameDialog.java
2 // Obtaining user input from a dialog.
3 import javax.swing.JOptionPane;
4
5 public class NameDialog
6 {
7     public static void main(String[] args)
8     {
```

Fig. 2.19 | Obtaining user input from a dialog. (Part 1 of 2.)

```

9      // prompt user to enter name
10     String name = JOptionPane.showInputDialog("What is your name?");
11
12     // create the message
13     String message =
14         String.format("Welcome, %s, to Java Programming!", name);
15
16     // display the message to welcome the user by name
17     JOptionPane.showMessageDialog(null, message);
18 } // end main
19 } // end class NameDialog

```



Fig. 2.19 | Obtaining user input from a dialog. (Part 2 of 2.)

JOptionPane Class static Method showInputDialog

Line 10 uses `JOptionPane` method **showInputDialog** to display an input dialog containing a prompt and a *field* (known as a **text field**) in which you can enter text. Method `showInputDialog`'s argument is the prompt that indicates what you should enter. You type characters in the text field, then click the **OK** button or press the *Enter* key to return the `String` to the program. Method `showInputDialog` returns a `String` containing the characters you typed. We store the `String` in variable `name`. If you press the dialog's **Cancel** button or press the *Esc* key, the method returns `null` and the program displays the word "null" as the name.

String Class static Method format

Lines 13–14 use static `String` method **format** to return a `String` containing a greeting with the user's name. Method `format` works like method `System.out.printf`, except that `format` returns the formatted `String` rather than displaying it in a command window. Line 17 displays the greeting in a message dialog, just as we did in Fig. 2.18.

GUI and Graphics Case Study Exercise

2.1 Modify the addition program in Fig. 2.7 to use dialog-based input and output with the methods of class `JOptionPane`. Since method `showInputDialog` returns a `String`, you must convert the `String` the user enters to an `int` for use in calculations. The static method `parseInt` of class `Integer` (package `java.lang`) takes a `String` argument representing an integer and returns the value as an `int`. If the `String` does not contain a valid integer, the program will terminate with an error.

2.10 Wrap-Up

In this chapter, you learned many important features of Java, including displaying data on the screen in a **Command Prompt**, inputting data from the keyboard, performing calculations and making decisions. The applications presented here introduced you to many basic programming concepts. In the next chapter we begin our introduction to control statements, which specify the order in which a program's actions are performed.

Summary

Section 2.2 Your First Program in Java: Printing a Line of Text

- A Java application (p. 35) executes when you use the `java` command to launch the JVM.
- Comments (p. 36) document programs and improve their readability. The compiler ignores them.
- A comment that begins with `//` is an end-of-line comment—it terminates at the end of the line on which it appears.
- Traditional comments (p. 36) can be spread over several lines and are delimited by `/*` and `*/`.
- Javadoc comments (p. 36), delimited by `/**` and `*/`, enable you to embed program documentation in your code. The javadoc utility program generates HTML pages based on these comments.
- A syntax error (p. 36; also called a compiler error, compile-time error or compilation error) occurs when the compiler encounters code that violates Java's language rules. It's similar to a grammar error in a natural language.
- Blank lines, space characters and tab characters are known as white space (p. 37). White space makes programs easier to read and is ignored by the compiler.
- Keywords (p. 37) are reserved for use by Java and are always spelled with all lowercase letters.
- Keyword `class` (p. 37) introduces a class declaration.
- By convention, all class names in Java begin with a capital letter and capitalize the first letter of each word they include (e.g., `SampleClassName`).
- A Java class name is an identifier—a series of characters consisting of letters, digits, underscores (`_`) and dollar signs (`$`) that does not begin with a digit and does not contain spaces.
- Java is case sensitive (p. 37)—that is, uppercase and lowercase letters are distinct.
- The body of every class declaration (p. 37) is delimited by braces, `{` and `}`.
- A `public` (p. 37) class declaration must be saved in a file with the same name as the class followed by the `".java"` file-name extension.
- Method `main` (p. 38) is the starting point of every Java application and must begin with

```
public static void main(String[] args)
```

otherwise, the JVM will not execute the application.

- Methods perform tasks and return information when they complete them. Keyword `void` (p. 38) indicates that a method will perform a task but return no information.
- Statements instruct the computer to perform actions.
- A string (p. 39) in double quotes is sometimes called a character string or a string literal.
- The standard output object (`System.out`; p. 39) displays characters in the command window.
- Method `System.out.println` (p. 39) displays its argument (p. 39) in the command window followed by a newline character to position the output cursor to the beginning of the next line.
- You compile a program with the command `javac`. If the program contains no syntax errors, a class file (p. 40) containing the Java bytecodes that represent the application is created. These bytecodes are interpreted by the JVM when you execute the program.
- To run an application, type `java` followed by the name of the class that contains the `main` method.

Section 2.3 Modifying Your First Java Program

- `System.out.print` (p. 42) displays its argument and positions the output cursor immediately after the last character displayed.
- A backslash (`\`) in a string is an escape character (p. 43). Java combines it with the next character to form an escape sequence (p. 43). The escape sequence `\n` (p. 43) represents the newline character.

*Section 2.4 Displaying Text with **printf***

- `System.out.printf` method (p. 43; `f` means “formatted”) displays formatted data.
- Method `printf`’s first argument is a format string (p. 44) containing fixed text and/or format specifiers. Each format specifier (p. 44) indicates the type of data to output and is a placeholder for a corresponding argument that appears after the format string.
- Format specifiers begin with a percent sign (%) and are followed by a character that represents the data type. The format specifier `%s` (p. 44) is a placeholder for a string.
- The `%n` format specifier (p. 44) is a portable line separator. You cannot use `%n` in the argument to `System.out.print` or `System.out.println`; however, the line separator output by `System.out.println` after it displays its argument is portable across operating systems.

Section 2.5 Another Application: Adding Integers

- An `import` declaration (p. 45) helps the compiler locate a class that’s used in a program.
- Java’s rich set of predefined classes are grouped into packages (p. 45)—named groups of classes. These are referred to as the Java class library (p. 45), or the Java Application Programming Interface (Java API).
- A variable (p. 46) is a location in the computer’s memory where a value can be stored for use later in a program. All variables must be declared with a name and a type before they can be used.
- A variable’s name enables the program to access the variable’s value in memory.
- A `Scanner` (package `java.util`; p. 47) enables a program to read data that the program will use. Before a `Scanner` can be used, the program must create it and specify the source of the data.
- Variables should be initialized (p. 47) to prepare them for use in a program.
- The expression `new Scanner(System.in)` creates a `Scanner` that reads from the standard input object (`System.in`; p. 47)—normally the keyboard.
- Data type `int` (p. 47) is used to declare variables that will hold integer values. The range of values for an `int` is $-2,147,483,648$ to $+2,147,483,647$.
- Types `float` and `double` (p. 47) specify real numbers with decimal points, such as `3.4` and `-11.19`.
- Variables of type `char` (p. 47) represent individual characters, such as an uppercase letter (e.g., `A`), a digit (e.g., `7`), a special character (e.g., `*` or `%`) or an escape sequence (e.g., `tab`, `\t`).
- Types such as `int`, `float`, `double` and `char` are primitive types (p. 47). Primitive-type names are keywords; thus, they must appear in all lowercase letters.
- A prompt (p. 48) directs the user to take a specific action.
- `Scanner` method `nextInt` obtains an integer for use in a program.
- The assignment operator, `=` (p. 48), enables the program to give a value to a variable. It’s called a binary operator (p. 48) because it has two operands.
- Portions of statements that have values are called expressions (p. 49).
- The format specifier `%d` (p. 49) is a placeholder for an `int` value.

Section 2.6 Memory Concepts

- Variable names (p. 50) correspond to locations in the computer’s memory. Every variable has a name, a type, a size and a value.
- A value that’s placed in a memory location replaces the location’s previous value, which is lost.

Section 2.7 Arithmetic

- The arithmetic operators (p. 51) are `+` (addition), `-` (subtraction), `*` (multiplication), `/` (division) and `%` (remainder).

- Integer division (p. 51) yields an integer quotient.
- The remainder operator, % (p. 51), yields the remainder after division.
- Arithmetic expressions must be written in straight-line form (p. 51).
- If an expression contains nested parentheses (p. 52), the innermost set is evaluated first.
- Java applies the operators in arithmetic expressions in a precise sequence determined by the rules of operator precedence (p. 52).
- When we say that operators are applied from left to right, we're referring to their associativity (p. 52). Some operators associate from right to left.
- Redundant parentheses (p. 53) can make an expression clearer.

Section 2.8 Decision Making: Equality and Relational Operators

- The `if` statement (p. 54) makes a decision based on a condition's value (true or false).
- Conditions in `if` statements can be formed by using the equality (`==` and `!=`) and relational (`>`, `<`, `>=` and `<=`) operators (p. 54).
- An `if` statement begins with keyword `if` followed by a condition in parentheses and expects one statement in its body.
- The empty statement (p. 57) is a statement that does not perform a task.

Self-Review Exercises

- 2.1** Fill in the blanks in each of the following statements:
- A(n) _____ begins the body of every method, and a(n) _____ ends the body of every method.
 - You can use the _____ statement to make decisions.
 - _____ begins an end-of-line comment.
 - _____, _____ and _____ are called white space.
 - _____ are reserved for use by Java.
 - Java applications begin execution at method _____.
 - Methods _____, _____ and _____ display information in a command window.
- 2.2** State whether each of the following is *true* or *false*. If *false*, explain why.
- Comments cause the computer to print the text after the `//` on the screen when the program executes.
 - All variables must be given a type when they're declared.
 - Java considers the variables `number` and `NumBEr` to be identical.
 - The remainder operator (`%`) can be used only with integer operands.
 - The arithmetic operators `*`, `/`, `%`, `+` and `-` all have the same level of precedence.
- 2.3** Write statements to accomplish each of the following tasks:
- Declare variables `c`, `thisIsAVariable`, `q76354` and `number` to be of type `int`.
 - Prompt the user to enter an integer.
 - Input an integer and assign the result to `int` variable `value`. Assume `Scanner` variable `input` can be used to read a value from the keyboard.
 - Print "This is a Java program" on one line in the command window. Use method `System.out.println`.
 - Print "This is a Java program" on two lines in the command window. The first line should end with `Java`. Use method `System.out.printf` and two `%s` format specifiers.
 - If the variable `number` is not equal to 7, display "The variable number is not equal to 7".

- 2.4** Identify and correct the errors in each of the following statements:
- a) `if (c < 7);`
`System.out.println("c is less than 7");`
 - b) `if (c ==> 7)`
`System.out.println("c is equal to or greater than 7");`
- 2.5** Write declarations, statements or comments that accomplish each of the following tasks:
- a) State that a program will calculate the product of three integers.
 - b) Create a Scanner called `input` that reads values from the standard input.
 - c) Declare the variables `x`, `y`, `z` and `result` to be of type `int`.
 - d) Prompt the user to enter the first integer.
 - e) Read the first integer from the user and store it in the variable `x`.
 - f) Prompt the user to enter the second integer.
 - g) Read the second integer from the user and store it in the variable `y`.
 - h) Prompt the user to enter the third integer.
 - i) Read the third integer from the user and store it in the variable `z`.
 - j) Compute the product of the three integers contained in variables `x`, `y` and `z`, and assign the result to the variable `result`.
 - k) Use `System.out.printf` to display the message "Product is" followed by the value of the variable `result`.
- 2.6** Using the statements you wrote in Exercise 2.5, write a complete program that calculates and prints the product of three integers.

Answers to Self-Review Exercises

- 2.1** a) left brace (`{`), right brace (`}`). b) `if`. c) `//`. d) Space characters, newlines and tabs. e) Keywords. f) `main`. g) `System.out.print`, `System.out.println` and `System.out.printf`.
- 2.2** a) False. Comments do not cause any action to be performed when the program executes. They're used to document programs and improve their readability.
 b) True.
 c) False. Java is case sensitive, so these variables are distinct.
 d) False. The remainder operator can also be used with noninteger operands in Java.
 e) False. The operators `*`, `/` and `%` are higher precedence than operators `+` and `-`.
- 2.3** a) `int c, thisIsAVariable, q76354, number;`
 or
`int c;`
`int thisIsAVariable;`
`int q76354;`
`int number;`
 b) `System.out.print("Enter an integer: ");`
 c) `value = input.nextInt();`
 d) `System.out.println("This is a Java program");`
 e) `System.out.printf("%s%n%s%n", "This is a Java", "program");`
 f) `if (number != 7)`
`System.out.println("The variable number is not equal to 7");`
- 2.4** a) Error: Semicolon after the right parenthesis of the condition (`c < 7`) in the `if`.
 Correction: Remove the semicolon after the right parenthesis. [*Note:* As a result, the output statement will execute regardless of whether the condition in the `if` is true.]
 b) Error: The relational operator `=>` is incorrect. Correction: Change `=>` to `>=`.

- 2.5**
- a) `// Calculate the product of three integers`
 - b) `Scanner input = new Scanner(System.in);`
 - c) `int x, y, z, result;`
or
`int x;`
`int y;`
`int z;`
`int result;`
 - d) `System.out.print("Enter first integer: ");`
 - e) `x = input.nextInt();`
 - f) `System.out.print("Enter second integer: ");`
 - g) `y = input.nextInt();`
 - h) `System.out.print("Enter third integer: ");`
 - i) `z = input.nextInt();`
 - j) `result = x * y * z;`
 - k) `System.out.printf("Product is %d\n", result);`

2.6 The solution to Self-Review Exercise 2.6 is as follows:

```

1  // Ex. 2.6: Product.java
2  // Calculate the product of three integers.
3  import java.util.Scanner; // program uses Scanner
4
5  public class Product
6  {
7      public static void main(String[] args)
8      {
9          // create Scanner to obtain input from command window
10         Scanner input = new Scanner(System.in);
11
12         int x; // first number input by user
13         int y; // second number input by user
14         int z; // third number input by user
15         int result; // product of numbers
16
17         System.out.print("Enter first integer: "); // prompt for input
18         x = input.nextInt(); // read first integer
19
20         System.out.print("Enter second integer: "); // prompt for input
21         y = input.nextInt(); // read second integer
22
23         System.out.print("Enter third integer: "); // prompt for input
24         z = input.nextInt(); // read third integer
25
26         result = x * y * z; // calculate product of numbers
27
28         System.out.printf("Product is %d\n", result);
29     } // end method main
30 } // end class Product

```

```

Enter first integer: 10
Enter second integer: 20
Enter third integer: 30
Product is 6000

```

Exercises

- 2.7** Fill in the blanks in each of the following statements:
- _____ are used to document a program and improve its readability.
 - A decision can be made in a Java program with a(n) _____.
 - Calculations are normally performed by _____ statements.
 - The arithmetic operators with the same precedence as multiplication are _____ and _____.
 - When parentheses in an arithmetic expression are nested, the _____ set of parentheses is evaluated first.
 - A location in the computer's memory that may contain different values at various times throughout the execution of a program is called a(n) _____.
- 2.8** Write Java statements that accomplish each of the following tasks:
- Display the message "Enter an integer: ", leaving the cursor on the same line.
 - Assign the product of variables b and c to variable a.
 - Use a comment to state that a program performs a sample payroll calculation.
- 2.9** State whether each of the following is *true* or *false*. If *false*, explain why.
- Java operators are evaluated from left to right.
 - The following are all valid variable names: `_under_bar_`, `m928134`, `t5`, `j7`, `her_sales$`, `his_$account_total`, `a`, `b$`, `c`, `z` and `z2`.
 - A valid Java arithmetic expression with no parentheses is evaluated from left to right.
 - The following are all invalid variable names: `3g`, `87`, `67h2`, `h22` and `2h`.
- 2.10** Assuming that `x = 2` and `y = 3`, what does each of the following statements display?
- `System.out.printf("x = %d\n", x);`
 - `System.out.printf("Value of %d + %d is %d\n", x, x, (x + x));`
 - `System.out.printf("x =");`
 - `System.out.printf("%d = %d\n", (x + y), (y + x));`
- 2.11** Which of the following Java statements contain variables whose values are modified?
- `p = i + j + k + 7;`
 - `System.out.println("variables whose values are modified");`
 - `System.out.println("a = 5");`
 - `value = input.nextInt();`
- 2.12** Given that $y = ax^3 + 7$, which of the following are correct Java statements for this equation?
- `y = a * x * x * x + 7;`
 - `y = a * x * x * (x + 7);`
 - `y = (a * x) * x * (x + 7);`
 - `y = (a * x) * x * x + 7;`
 - `y = a * (x * x * x) + 7;`
 - `y = a * x * (x * x + 7);`
- 2.13** State the order of evaluation of the operators in each of the following Java statements, and show the value of x after each statement is performed:
- `x = 7 + 3 * 6 / 2 - 1;`
 - `x = 2 % 2 + 2 * 2 - 2 / 2;`
 - `x = (3 * 9 * (3 + (9 * 3 / (3))));`
- 2.14** Write an application that displays the numbers 1 to 4 on the same line, with each pair of adjacent numbers separated by one space. Use the following techniques:
- Use one `System.out.println` statement.
 - Use four `System.out.print` statements.
 - Use one `System.out.printf` statement.

2.15 (*Arithmetic*) Write an application that asks the user to enter two integers, obtains them from the user and prints their sum, product, difference and quotient (division). Use the techniques shown in Fig. 2.7.

2.16 (*Comparing Integers*) Write an application that asks the user to enter two integers, obtains them from the user and displays the larger number followed by the words "is larger". If the numbers are equal, print the message "These numbers are equal". Use the techniques shown in Fig. 2.15.

2.17 (*Arithmetic, Smallest and Largest*) Write an application that inputs three integers from the user and displays the sum, average, product, smallest and largest of the numbers. Use the techniques shown in Fig. 2.15. [Note: The calculation of the average in this exercise should result in an integer representation of the average. So, if the sum of the values is 7, the average should be 2, not 2.3333....]

2.18 (*Displaying Shapes with Asterisks*) Write an application that displays a box, an oval, an arrow and a diamond using asterisks (*), as follows:

```

*****      ***      *      *
*      *      *      *      ***      *      *
*      *      *      *      *****      *      *
*      *      *      *      *      *      *      *
*      *      *      *      *      *      *      *
*      *      *      *      *      *      *      *
*      *      *      *      *      *      *      *
*      *      *      *      *      *      *      *
*****      ***      *      *

```

2.19 What does the following code print?

```
System.out.printf("%n**%n***%n****%n*****%n");
```

2.20 What does the following code print?

```
System.out.println("");
System.out.println("****");
System.out.println("*****");
System.out.println("*****");
System.out.println("****");
```

2.21 What does the following code print?

```
System.out.print("");
System.out.print("****");
System.out.print("*****");
System.out.print("*****");
System.out.println("****");
```

2.22 What does the following code print?

```
System.out.print("");
System.out.println("****");
System.out.println("*****");
System.out.print("*****");
System.out.println("****");
```

2.23 What does the following code print?

```
System.out.printf("%s%n%s%n%s%n", "", "****", "*****");
```

2.24 (*Largest and Smallest Integers*) Write an application that reads five integers and determines and prints the largest and smallest integers in the group. Use only the programming techniques you learned in this chapter.

2.25 (Odd or Even) Write an application that reads an integer and determines and prints whether it's odd or even. [*Hint:* Use the remainder operator. An even number is a multiple of 2. Any multiple of 2 leaves a remainder of 0 when divided by 2.]

2.26 (Multiples) Write an application that reads two integers, determines whether the first is a multiple of the second and prints the result. [*Hint:* Use the remainder operator.]

2.27 (Checkerboard Pattern of Asterisks) Write an application that displays a checkerboard pattern, as follows:

```
* * * * *
 * * * * *
* * * * *
 * * * * *
* * * * *
 * * * * *
* * * * *
 * * * * *
```

2.28 (Diameter, Circumference and Area of a Circle) Here's a peek ahead. In this chapter, you learned about integers and the type `int`. Java can also represent floating-point numbers that contain decimal points, such as 3.14159. Write an application that inputs from the user the radius of a circle as an integer and prints the circle's diameter, circumference and area using the floating-point value 3.14159 for π . Use the techniques shown in Fig. 2.7. [*Note:* You may also use the predefined constant `Math.PI` for the value of π . This constant is more precise than the value 3.14159. Class `Math` is defined in package `java.lang`. Classes in that package are imported automatically, so you do not need to import class `Math` to use it.] Use the following formulas (r is the radius):

$$\begin{aligned} \text{diameter} &= 2r \\ \text{circumference} &= 2\pi r \\ \text{area} &= \pi r^2 \end{aligned}$$

Do not store the results of each calculation in a variable. Rather, specify each calculation as the value that will be output in a `System.out.printf` statement. The values produced by the circumference and area calculations are floating-point numbers. Such values can be output with the format specifier `%f` in a `System.out.printf` statement. You'll learn more about floating-point numbers in Chapter 3.

2.29 (Integer Value of a Character) Here's another peek ahead. In this chapter, you learned about integers and the type `int`. Java can also represent uppercase letters, lowercase letters and a considerable variety of special symbols. Every character has a corresponding integer representation. The set of characters a computer uses together with the corresponding integer representations for those characters is called that computer's character set. You can indicate a character value in a program simply by enclosing that character in single quotes, as in `'A'`.

You can determine a character's integer equivalent by preceding that character with `(int)`, as in

```
(int) 'A'
```

An operator of this form is called a cast operator. (You'll learn about cast operators in Chapter 3.) The following statement outputs a character and its integer equivalent:

```
System.out.printf("The character %c has the value %d\n", 'A', ((int) 'A'));
```

When the preceding statement executes, it displays the character `A` and the value 65 (from the Unicode® character set) as part of the string. The format specifier `%c` is a placeholder for a character (in this case, the character `'A'`).

Using statements similar to the one shown earlier in this exercise, write an application that displays the integer equivalents of some uppercase letters, lowercase letters, digits and special symbols. Display the integer equivalents of the following: `A B C a b c 0 1 2 $ * + /` and the blank character.

2.30 (*Separating the Digits in an Integer*) Write an application that inputs one number consisting of five digits from the user, separates the number into its individual digits and prints the digits separated from one another by three spaces each. For example, if the user types in the number 42339, the program should print

```
4   2   3   3   9
```

Assume that the user enters the correct number of digits. What happens when you enter a number with more than five digits? What happens when you enter a number with fewer than five digits? [*Hint:* It's possible to do this exercise with the techniques you learned in this chapter. You'll need to use both division and remainder operations to "pick off" each digit.]

2.31 (*Table of Squares and Cubes*) Using only the programming techniques you learned in this chapter, write an application that calculates the squares and cubes of the numbers from 0 to 10 and prints the resulting values in table format, as shown below.

number	square	cube
0	0	0
1	1	1
2	4	8
3	9	27
4	16	64
5	25	125
6	36	216
7	49	343
8	64	512
9	81	729
10	100	1000

2.32 (*Negative, Positive and Zero Values*) Write a program that inputs five numbers and determines and prints the number of negative numbers input, the number of positive numbers input and the number of zeros input.

Making a Difference

2.33 (*Body Mass Index Calculator*) We introduced the body mass index (BMI) calculator in Exercise 1.10. The formulas for calculating BMI are

$$BMI = \frac{weightInPounds \times 703}{heightInInches \times heightInInches}$$

or

$$BMI = \frac{weightInKilograms}{heightInMeters \times heightInMeters}$$

Create a BMI calculator that reads the user's weight in pounds and height in inches (or, if you prefer, the user's weight in kilograms and height in meters), then calculates and displays the user's body mass index. Also, display the following information from the Department of Health and Human Services/National Institutes of Health so the user can evaluate his/her BMI:

```
BMI VALUES
Underweight: less than 18.5
Normal:      between 18.5 and 24.9
Overweight:  between 25 and 29.9
Obese:       30 or greater
```

[*Note:* In this chapter, you learned to use the `int` type to represent whole numbers. The BMI calculations when done with `int` values will both produce whole-number results. In Chapter 3, you'll learn to use the `double` type to represent numbers with decimal points. When the BMI calculations are performed with `doubles`, they'll both produce numbers with decimal points—these are called “floating-point” numbers.]

2.34 (*World Population Growth Calculator*) Use the web to determine the current world population and the annual world population growth rate. Write an application that inputs these values, then displays the estimated world population after one, two, three, four and five years.

2.35 (*Car-Pool Savings Calculator*) Research several car-pooling websites. Create an application that calculates your daily driving cost, so that you can estimate how much money could be saved by car pooling, which also has other advantages such as reducing carbon emissions and reducing traffic congestion. The application should input the following information and display the user's cost per day of driving to work:

- a) Total miles driven per day.
- b) Cost per gallon of gasoline.
- c) Average miles per gallon.
- d) Parking fees per day.
- e) Tolls per day.

3

Control Statements: Part I; Assignment, ++ and -- Operators

Let's all move one place on.

—Lewis Carroll

*How many apples fell on
Newton's head before he took the
hint!*

—Robert Frost

Objectives

In this chapter you'll:

- Learn basic problem-solving techniques.
- Develop algorithms through the process of top-down, stepwise refinement.
- Use the `if` and `if...else` selection statements to choose between alternative actions.
- Use the `while` repetition statement to execute statements in a program repeatedly.
- Use counter-controlled repetition and sentinel-controlled repetition.
- Use the compound assignment operator, and the increment and decrement operators.
- Learn about the portability of primitive data types.



3.1 Introduction	3.9 Formulating Algorithms: Sentinel-Controlled Repetition
3.2 Algorithms	3.10 Formulating Algorithms: Nested Control Statements
3.3 Pseudocode	3.11 Compound Assignment Operators
3.4 Control Structures	3.12 Increment and Decrement Operators
3.5 <code>if</code> Single-Selection Statement	3.13 Primitive Types
3.6 <code>if...else</code> Double-Selection Statement	3.14 (Optional) GUI and Graphics Case Study: Creating Simple Drawings
3.7 <code>while</code> Repetition Statement	3.15 Wrap-Up
3.8 Formulating Algorithms: Counter-Controlled Repetition	

Summary | Self-Review Exercises | Answers to Self-Review Exercises | Exercises | Making a Difference

3.1 Introduction

Before writing a program to solve a problem, you should have a thorough understanding of the problem and a carefully planned approach to solving it. When writing a program, you also should understand the available building blocks and employ proven program-construction techniques. In this chapter and the next, we discuss these issues in presenting the theory and principles of structured programming. As you'll see when we get into object-oriented programming (starting in Chapter 7), the concepts presented here are crucial in constructing classes and manipulating objects. We discuss Java's `if` statement in additional detail, and introduce the `if...else` and `while` statements—all of these building blocks allow you to specify the logic required for methods to perform their tasks. We also introduce the compound assignment operator and the increment and decrement operators. Finally, we consider the portability of Java's primitive types.

3.2 Algorithms

Any computing problem can be solved by executing a series of actions in a specific order. A *procedure* for solving a problem in terms of

1. the **actions** to execute and
2. the **order** in which these actions execute

is called an **algorithm**. The following example demonstrates that correctly specifying the order in which the actions execute is important.

Consider the “rise-and-shine algorithm” followed by one executive for getting out of bed and going to work: (1) Get out of bed; (2) take off pajamas; (3) take a shower; (4) get dressed; (5) eat breakfast; (6) carpool to work. This routine gets the executive to work well prepared to make critical decisions. Suppose that the same steps are performed in a slightly different order: (1) Get out of bed; (2) take off pajamas; (3) get dressed; (4) take a shower; (5) eat breakfast; (6) carpool to work. In this case, our executive shows up for work soaking wet. Specifying the order in which statements (actions) execute in a program is called **program control**. This chapter investigates program control using Java's **control statements**.

3.3 Pseudocode

Pseudocode is an informal language that helps you develop algorithms without having to worry about the strict details of Java language syntax. The pseudocode we present is particularly useful for developing algorithms that will be converted to structured portions of Java programs. The pseudocode we use in this book is similar to everyday English—it's convenient and user friendly, but it's not an actual computer programming language. You'll see an algorithm written in pseudocode in Fig. 3.5. You may, of course, use your own native language(s) to develop your own pseudocode.

Pseudocode does not execute on computers. Rather, it helps you “think out” a program before attempting to write it in a programming language, such as Java. This chapter provides several examples of using pseudocode to develop Java programs.

The style of pseudocode we present consists purely of characters, so you can type pseudocode conveniently, using any text-editor program. A carefully prepared pseudocode program can easily be converted to a corresponding Java program.

Pseudocode normally describes only statements representing the *actions* that occur after you convert a program from pseudocode to Java and the program is run on a computer. Such actions might include *input*, *output* or *calculations*. In our pseudocode, we typically do *not* include variable declarations, but some programmers choose to list variables and mention their purposes.

3.4 Control Structures

Normally, statements in a program are executed one after the other in the order in which they're written. This process is called **sequential execution**. Various Java statements, which we'll soon discuss, enable you to specify that the next statement to execute is *not* necessarily the *next* one in sequence. This is called **transfer of control**.

During the 1960s, it became clear that the indiscriminate use of transfers of control was the root of much difficulty experienced by software development groups. The blame was pointed at the **goto statement** (used in most programming languages of the time), which allows you to specify a transfer of control to one of a wide range of destinations in a program. [Note: Java does *not* have a goto statement; however, the word goto is *reserved* by Java and should *not* be used as an identifier in programs.]

The research of Bohm and Jacopini¹ had demonstrated that programs could be written *without* any goto statements. The challenge of the era for programmers was to shift their styles to “goto-less programming.” The term **structured programming** became almost synonymous with “goto elimination.” Not until the 1970s did most programmers start taking structured programming seriously. The results were impressive. Software development groups reported shorter development times, more frequent on-time delivery of systems and more frequent within-budget completion of software projects. The key to these successes was that structured programs were clearer, easier to debug and modify, and more likely to be bug free in the first place.

Bohm and Jacopini's work demonstrated that all programs could be written in terms of only three control structures—the **sequence structure**, the **selection structure** and the

1. C. Bohm, and G. Jacopini, “Flow Diagrams, Turing Machines, and Languages with Only Two Formation Rules,” *Communications of the ACM*, Vol. 9, No. 5, May 1966, pp. 336–371.

repetition structure. When we introduce Java’s control-structure implementations, we’ll refer to them in the terminology of the *Java Language Specification* as “control statements.”

Sequence Structure in Java

The sequence structure is built into Java. Unless directed otherwise, the computer executes Java statements one after the other in the order in which they’re written—that is, in sequence. The **activity diagram** in Fig. 3.1 illustrates a typical sequence structure in which two calculations are performed in order. Java lets you have as many actions as you want in a sequence structure. As we’ll soon see, anywhere a single action may be placed, we may place several actions in sequence.




Fig. 3.1 | Sequence-structure activity diagram.

A UML activity diagram models the **workflow** (also called the **activity**) of a portion of a software system. Such workflows may include a portion of an algorithm, like the sequence structure in Fig. 3.1. Activity diagrams are composed of symbols, such as **action-state symbols** (rectangles with their left and right sides replaced with outward arcs), **diamonds** and **small circles**. These symbols are connected by **transition arrows**, which represent the *flow of the activity*—that is, the *order* in which the actions should occur.

Like pseudocode, activity diagrams help you develop and represent algorithms. Activity diagrams clearly show how control structures operate. We use the UML in this chapter and Chapter 4 to show control flow in control statements. Online Chapters 33–34 use the UML in a real-world automated-teller-machine case study.

Consider the sequence-structure activity diagram in Fig. 3.1. It contains two **action states**, each containing an **action expression**—for example, “add grade to total” or “add 1 to counter”—that specifies a particular action to perform. Other actions might include calculations or input/output operations. The arrows in the activity diagram represent **transitions**, which indicate the *order* in which the actions represented by the action states occur. The program that implements the activities illustrated by the diagram in Fig. 3.1 first adds grade to total, then adds 1 to counter.

The **solid circle** at the top of the activity diagram represents the **initial state**—the *beginning* of the workflow *before* the program performs the modeled actions. The **solid circle surrounded by a hollow circle** at the bottom of the diagram represents the **final state**—the *end* of the workflow *after* the program performs its actions.

Figure 3.1 also includes rectangles with the upper-right corners folded over. These are UML **notes** (like comments in Java)—explanatory remarks that describe the purpose of sym-

bols in the diagram. Figure 3.1 uses UML notes to show the Java code associated with each action state. A **dotted line** connects each note with the element it describes. Activity diagrams normally do *not* show the Java code that implements the activity. We do this here to illustrate how the diagram relates to Java code. For more information on the UML, see our optional online object-oriented design case study (Chapters 33–34) or visit www.uml.org.

Selection Statements in Java

Java has three types of **selection statements** (discussed in this chapter and Chapter 4). The *if statement* either performs (selects) an action, if a condition is *true*, or skips it, if the condition is *false*. The *if...else statement* performs an action if a condition is *true* and performs a different action if the condition is *false*. The *switch statement* (Chapter 4) performs one of *many* different actions, depending on the value of an expression.

The *if* statement is a **single-selection statement** because it selects or ignores a *single* action (or, as we'll soon see, a *single group of actions*). The *if...else* statement is called a **double-selection statement** because it selects between *two different actions* (or *groups of actions*). The *switch* statement is called a **multiple-selection statement** because it selects among *many different actions* (or *groups of actions*).

Repetition Statements in Java

Java provides three **repetition statements** (also called **iteration statements** or **looping statements**) that enable programs to perform statements repeatedly as long as a condition (called the **loop-continuation condition**) remains *true*. The repetition statements are the *while*, *do...while*, *for* and enhanced *for* statements. (Chapter 4 presents the *do...while* and *for* statements and Chapter 6 presents the enhanced *for* statement.) The *while* and *for* statements perform the action (or group of actions) in their bodies zero or more times—if the loop-continuation condition is initially *false*, the action (or group of actions) will *not* execute. The *do...while* statement performs the action (or group of actions) in its body *one or more* times. The words *if*, *else*, *switch*, *while*, *do* and *for* are Java keywords. A complete list of Java keywords appears in Appendix C.

Summary of Control Statements in Java

Java has only three kinds of control structures, which from this point forward we refer to as *control statements*: the *sequence statement*, *selection statements* (three types) and *repetition statements* (three types). Every program is formed by combining as many of these statements as is appropriate for the algorithm the program implements. We can model each control statement as an activity diagram. Like Fig. 3.1, each diagram contains an initial state and a final state that represent a control statement's entry point and exit point, respectively. **Single-entry/single-exit control statements** make it easy to build programs—we simply connect the exit point of one to the entry point of the next. We call this **control-statement stacking**. We'll learn that there's only one other way in which control statements may be connected—**control-statement nesting**—in which one control statement appears *inside* another. Thus, algorithms in Java programs are constructed from only three kinds of control statements, combined in only two ways. This is the essence of simplicity.

3.5 *if* Single-Selection Statement

Programs use selection statements to choose among alternative courses of action. For example, suppose that the passing grade on an exam is 60. The *pseudocode* statement

*If student's grade is greater than or equal to 60
Print "Passed"*

determines whether the *condition* “student’s grade is greater than or equal to 60” is *true*. If so, “Passed” is printed, and the next pseudocode statement in order is “performed.” (Remember, pseudocode is not a real programming language.) If the condition is *false*, the *Print* statement is ignored, and the next pseudocode statement in order is performed. The indentation of the second line of this selection statement is optional, but recommended, because it emphasizes the inherent structure of structured programs.

The preceding pseudocode *If* statement may be written in Java as

```
if (studentGrade >= 60)
    System.out.println("Passed");
```

The Java code corresponds closely to the pseudocode. This is one of the properties of pseudocode that makes it such a useful program development tool.

UML Activity Diagram for an if Statement

Figure 3.2 illustrates the single-selection *if* statement. This figure contains the most important symbol in an activity diagram—the *diamond*, or **decision symbol**, which indicates that a *decision* is to be made. The workflow continues along a path determined by the symbol’s associated **guard conditions**, which can be *true* or *false*. Each transition arrow emerging from a decision symbol has a guard condition (specified in *square brackets* next to the arrow). If a guard condition is *true*, the workflow enters the action state to which the transition arrow points. In Fig. 3.2, if the grade is greater than or equal to 60, the program prints “Passed,” then transitions to the activity’s final state. If the grade is less than 60, the program immediately transitions to the final state without displaying a message.




Fig. 3.2 | if single-selection statement UML activity diagram.

The *if* statement is a single-entry/single-exit control statement. We’ll see that the activity diagrams for the remaining control statements also contain initial states, transition arrows, action states that indicate actions to perform, decision symbols (with associated guard conditions) that indicate decisions to be made, and final states.

3.6 if...else Double-Selection Statement

The *if* single-selection statement performs an indicated action only when the condition is *true*; otherwise, the action is skipped. The **if...else double-selection statement** allows you to specify an action to perform when the condition is *true* and another action when the condition is *false*. For example, the pseudocode statement

```

    If student's grade is greater than or equal to 60
        Print "Passed"
    Else
        Print "Failed"

```

prints “Passed” if the student’s grade is greater than or equal to 60, but prints “Failed” if it’s less than 60. In either case, after printing occurs, the next pseudocode statement in sequence is “performed.”

The preceding *If...Else* pseudocode statement can be written in Java as

```

if (grade >= 60)
    System.out.println("Passed");
else
    System.out.println("Failed");

```

The body of the `else` is also indented. Whatever indentation convention you choose should be applied consistently throughout your programs.



Good Programming Practice 3.1

Indent both body statements of an if...else statement. Many IDEs do this for you.



Good Programming Practice 3.2

If there are several levels of indentation, each level should be indented the same additional amount of space.

UML Activity Diagram for an if...else Statement

Figure 3.3 illustrates the flow of control in the `if...else` statement. Once again, the symbols in the UML activity diagram (besides the initial state, transition arrows and final state) represent action states and decisions.




Fig. 3.3 | `if...else` double-selection statement UML activity diagram.

Nested if...else Statements

A program can test multiple cases by placing `if...else` statements inside other `if...else` statements to create **nested if...else statements**. For example, the following pseudocode represents a nested `if...else` that prints A for exam grades greater than or equal to 90, B for grades 80 to 89, C for grades 70 to 79, D for grades 60 to 69 and F for all other grades:

```

If student's grade is greater than or equal to 90
    Print "A"
else
    If student's grade is greater than or equal to 80
        Print "B"
    else
        If student's grade is greater than or equal to 70
            Print "C"
        else
            If student's grade is greater than or equal to 60
                Print "D"
            else
                Print "F"

```

This pseudocode may be written in Java as

```

if (studentGrade >= 90)
    System.out.println("A");
else
    if (studentGrade >= 80)
        System.out.println("B");
    else
        if (studentGrade >= 70)
            System.out.println("C");
        else
            if (studentGrade >= 60)
                System.out.println("D");
            else
                System.out.println("F");

```



Error-Prevention Tip 3.1

In a nested if...else statement, ensure that you test for all possible cases.

If variable `studentGrade` is greater than or equal to 90, the first four conditions in the nested if...else statement will be true, but only the statement in the if part of the first if...else statement will execute. After that statement executes, the else part of the “outermost” if...else statement is skipped. Many programmers prefer to write the preceding nested if...else statement as

```

if (studentGrade >= 90)
    System.out.println("A");
else if (studentGrade >= 80)
    System.out.println("B");
else if (studentGrade >= 70)
    System.out.println("C");
else if (studentGrade >= 60)
    System.out.println("D");
else
    System.out.println("F");

```

The two forms are identical except for the spacing and indentation, which the compiler ignores. The latter form avoids deep indentation of the code to the right. Such indentation often leaves little room on a line of source code, forcing lines to be split.

Dangling-else Problem

The Java compiler always associates an `else` with the immediately preceding `if` unless told to do otherwise by the placement of braces (`{` and `}`). This behavior can lead to what is referred to as the **dangling-else problem**. For example,

```
if (x > 5)
    if (y > 5)
        System.out.println("x and y are > 5");
else
    System.out.println("x is <= 5");
```

appears to indicate that if `x` is greater than 5, the nested `if` statement determines whether `y` is also greater than 5. If so, the string "x and y are > 5" is output. Otherwise, it appears that if `x` is not greater than 5, the `else` part of the `if...else` outputs the string "x is <= 5". Beware! This nested `if...else` statement does *not* execute as it appears. The compiler actually interprets the statement as

```
if (x > 5)
    if (y > 5)
        System.out.println("x and y are > 5");
    else
        System.out.println("x is <= 5");
```

in which the body of the first `if` is a *nested* `if...else`. The outer `if` statement tests whether `x` is greater than 5. If so, execution continues by testing whether `y` is also greater than 5. If the second condition is *true*, the proper string—"x and y are > 5"—is displayed. However, if the second condition is *false*, the string "x is <= 5" is displayed, even though we know that `x` is greater than 5. Equally bad, if the outer `if` statement's condition is false, the inner `if...else` is skipped and nothing is displayed.

To force the nested `if...else` statement to execute as it was originally intended, we must write it as follows:

```
if (x > 5)
{
    if (y > 5)
        System.out.println("x and y are > 5");
}
else
    System.out.println("x is <= 5");
```

The braces indicate that the second `if` is in the body of the first and that the `else` is associated with the *first* `if`. Exercises 3.273.28 investigate the dangling-else problem further.

Blocks

The `if` statement normally expects only *one* statement in its body. To include *several* statements in the body of an `if` (or the body of an `else` for an `if...else` statement), enclose the statements in braces. Statements contained in a pair of braces (such as the body of a

method) form a **block**. A block can be placed anywhere in a method that a single statement can be placed.

The following example includes a block in the `else` part of an `if...else` statement:

```
if (grade >= 60)
    System.out.println("Passed");
else
{
    System.out.println("Failed");
    System.out.println("You must take this course again.");
}
```

In this case, if `grade` is less than 60, the program executes *both* statements in the body of the `else` and prints

```
Failed
You must take this course again.
```

Note the braces surrounding the two statements in the `else` clause. These braces are important. Without the braces, the statement

```
System.out.println("You must take this course again.");
```

would be outside the body of the `else` part of the `if...else` statement and would execute *regardless* of whether the grade was less than 60.

Syntax errors (e.g., when one brace in a block is left out of the program) are caught by the compiler. A **logic error** (e.g., when both braces in a block are left out of the program) has its effect at execution time. A **fatal logic error** causes a program to fail and terminate prematurely. A **nonfatal logic error** allows a program to continue executing but causes it to produce incorrect results.

Just as a block can be placed anywhere a single statement can be placed, it's also possible to have an empty statement. Recall from Section 2.8 that the empty statement is represented by placing a semicolon (;) where a statement would normally be.



Common Programming Error 3.1

Placing a semicolon after the condition in an `if` or `if...else` statement leads to a logic error in single-selection `if` statements and a syntax error in double-selection `if...else` statements (when the `if`-part contains an actual body statement).

Conditional Operator (?:)

Java provides the **conditional operator** (`?:`) that can be used in place of an `if...else` statement. This can make your code shorter and clearer. The conditional operator is Java's only **ternary operator** (i.e., an operator that takes *three* operands). Together, the operands and the `?:` symbol form a **conditional expression**. The first operand (to the left of the `?`) is a **boolean expression** (i.e., a *condition* that evaluates to a boolean value—**true** or **false**), the second operand (between the `?` and `:`) is the value of the conditional expression if the boolean expression is true and the third operand (to the right of the `:`) is the value of the conditional expression if the boolean expression evaluates to false. For example, the statement

```
System.out.println(studentGrade >= 60 ? "Passed" : "Failed");
```

prints the value of `println`'s conditional-expression argument. The conditional expression in this statement evaluates to the string "Passed" if the boolean expression `student-Grade >= 60` is true and to the string "Failed" if it's false. Thus, this statement with the conditional operator performs essentially the same function as the `if...else` statement shown earlier in this section. The precedence of the conditional operator is low, so the entire conditional expression is normally placed in parentheses. We'll see that conditional expressions can be used in some situations where `if...else` statements cannot.



Error-Prevention Tip 3.2

Use expressions of the same type for the second and third operands of the `?:` operator to avoid subtle errors.

3.7 while Repetition Statement

A repetition statement allows you to specify that a program should repeat an action while some condition remains *true*. The pseudocode statement

*While there are more items on my shopping list
Purchase next item and cross it off my list*

describes the repetition during a shopping trip. The condition "there are more items on my shopping list" may be true or false. If it's *true*, then the action "Purchase next item and cross it off my list" is performed. This action will be performed *repeatedly* while the condition remains *true*. The statement(s) contained in the *While* repetition statement constitute its body, which may be a single statement or a block. Eventually, the condition will become *false* (when the shopping list's last item has been purchased and crossed off). At this point, the repetition terminates, and the first statement after the repetition statement executes.

As an example of Java's **while repetition statement**, consider a program segment that finds the first power of 3 larger than 100. Suppose that the `int` variable `product` is initialized to 3. After the following `while` statement executes, `product` contains the result:

```
while (product <= 100)
    product = 3 * product;
```

Each iteration of the `while` statement multiplies `product` by 3, so `product` takes on the values 9, 27, 81 and 243 successively. When `product` becomes 243, `product <= 100` becomes false. This terminates the repetition, so the final value of `product` is 243. At this point, program execution continues with the next statement after the `while` statement.



Common Programming Error 3.2

*Not providing in the body of a `while` statement an action that eventually causes the condition in the `while` to become false normally results in a logic error called an **infinite loop** (the loop never terminates).*

UML Activity Diagram for a `while` Statement

The UML activity diagram in Fig. 3.4 illustrates the flow of control in the preceding `while` statement. Once again, the symbols in the diagram (besides the initial state, transition arrows, a final state and three notes) represent an action state and a decision. This diagram introduces the UML's **merge symbol**. The UML represents both the merge symbol

and the decision symbol as diamonds. The merge symbol joins two flows of activity into one. In this diagram, the merge symbol joins the transitions from the initial state and from the action state, so they both flow into the decision that determines whether the loop should begin (or continue) executing.




Fig. 3.4 | `while` repetition statement UML activity diagram.

The decision and merge symbols can be distinguished by the number of “incoming” and “outgoing” transition arrows. A decision symbol has one transition arrow pointing to the diamond and two or more pointing out from it to indicate possible transitions from that point. In addition, each transition arrow pointing out of a decision symbol has a guard condition next to it. A merge symbol has two or more transition arrows pointing to the diamond and only one pointing from the diamond, to indicate multiple activity flows merging to continue the activity. *None* of the transition arrows associated with a merge symbol has a guard condition.

Figure 3.4 clearly shows the repetition of the `while` statement discussed earlier in this section. The transition arrow emerging from the action state points back to the merge, from which program flow transitions back to the decision that’s tested at the beginning of each iteration of the loop. The loop continues to execute until the guard condition `product > 100` becomes true. Then the `while` statement exits (reaches its final state), and control passes to the next statement in sequence in the program.

3.8 Formulating Algorithms: Counter-Controlled Repetition

To illustrate how algorithms are developed, we solve two variations of a problem that averages student grades. Consider the following problem statement:

A class of ten students took a quiz. The grades (integers in the range 0–100) for this quiz are available to you. Determine the class average on the quiz.

The class average is equal to the sum of the grades divided by the number of students. The algorithm for solving this problem on a computer must input each grade, keep track of the total of all grades input, perform the averaging calculation and print the result.

Pseudocode Algorithm with Counter-Controlled Repetition

Let's use pseudocode to list the actions to execute and specify the order in which they should execute. We use **counter-controlled repetition** to input the grades one at a time. This technique uses a variable called a **counter** (or **control variable**) to control the number of times a set of statements will execute. Counter-controlled repetition is often called **definite repetition**, because the number of repetitions is known *before* the loop begins executing. In this example, repetition terminates when the counter exceeds 10. This section presents a fully developed pseudocode algorithm (Fig. 3.5) and a corresponding Java program (Fig. 3.6) that implements the algorithm. In Section 3.9, we demonstrate how to use pseudocode to develop such an algorithm from scratch.

Note the references in the algorithm of Fig. 3.5 to a total and a counter. A **total** is a variable used to accumulate the sum of several values. A counter is a variable used to count—in this case, the grade counter indicates which of the 10 grades is about to be entered by the user. Variables used to store totals are normally initialized to zero before being used in a program.

**Software Engineering Observation 3.1**

Experience has shown that the most difficult part of solving a problem on a computer is developing the algorithm for the solution. Once a correct algorithm has been specified, producing a working Java program from it is usually straightforward.

```

1  Set total to zero
2  Set grade counter to one
3
4  While grade counter is less than or equal to ten
5      Prompt the user to enter the next grade
6      Input the next grade
7      Add the grade into the total
8      Add one to the grade counter
9
10 Set the class average to the total divided by ten
11 Print the class average

```

Fig. 3.5 | Pseudocode algorithm that uses counter-controlled repetition to solve the class-average problem.

Implementing Counter-Controlled Repetition

In Fig. 3.6, class `ClassAverage`'s main method (lines 7–31) implements the class-averaging algorithm described by the pseudocode in Fig. 3.5—it allows the user to enter 10 grades, then calculates and displays the average.

```

1  // Fig. 3.6: ClassAverage.java
2  // Solving the class-average problem using counter-controlled repetition.
3  import java.util.Scanner; // program uses class Scanner
4

```

Fig. 3.6 | Solving the class-average problem using counter-controlled repetition. (Part I of 2.)

```

5  public class ClassAverage
6  {
7      public static void main(String[] args)
8      {
9          // create Scanner to obtain input from command window
10         Scanner input = new Scanner(System.in);
11
12         // initialization phase
13         int total = 0; // initialize sum of grades entered by the user
14         int gradeCounter = 1; // initialize # of grade to be entered next
15
16         // processing phase uses counter-controlled repetition
17         while (gradeCounter <= 10) // loop 10 times
18         {
19             System.out.print("Enter grade: "); // prompt
20             int grade = input.nextInt(); // input next grade
21             total = total + grade; // add grade to total
22             gradeCounter = gradeCounter + 1; // increment counter by 1
23         }
24
25         // termination phase
26         int average = total / 10; // integer division yields integer result
27
28         // display total and average of grades
29         System.out.printf("\nTotal of all 10 grades is %d\n", total);
30         System.out.printf("Class average is %d\n", average);
31     }
32 } // end class ClassAverage

```

```

Enter grade: 67
Enter grade: 78
Enter grade: 89
Enter grade: 67
Enter grade: 87
Enter grade: 98
Enter grade: 93
Enter grade: 85
Enter grade: 82
Enter grade: 100

Total of all 10 grades is 846
Class average is 84

```

Fig. 3.6 | Solving the class-average problem using counter-controlled repetition. (Part 2 of 2.)

Local Variables in Method main

Line 10 declares and initializes Scanner object `input`, which is used to read values entered by the user. Lines 13, 14, 20 and 26 declare local variables `total`, `gradeCounter`, `grade` and `average`, respectively, to be of type `int`. Variable `grade` stores the user input.

These declarations appear in the body of method `main`. Recall that variables declared in a method body are local variables and can be used only from the line of their declaration to the closing right brace of the method declaration. A local variable's declaration must appear *before* the variable is used in that method. A local variable cannot be accessed out-

side the method in which it's declared. Variable `grade`, declared in the body of the `while` loop, can be used only in that block.

Initialization Phase: Initializing Variables `total` and `gradeCounter`

The assignments (in lines 13–14) initialize `total` to 0 and `gradeCounter` to 1. These initializations occur *before* the variables are used in calculations.



Common Programming Error 3.3

Using the value of a local variable before it's initialized results in a compilation error. All local variables must be initialized before their values are used in expressions.



Error-Prevention Tip 3.3

Initialize each `total` and `counter`, either in its declaration or in an assignment statement. Totals are normally initialized to 0. Counters are normally initialized to 0 or 1, depending on how they're used (we'll show examples of when to use 0 and when to use 1).

Processing Phase: Reading 10 Grades from the User

Line 17 indicates that the `while` statement should continue looping (also called **iterating**) as long as `gradeCounter`'s value is less than or equal to 10. While this condition remains *true*, the `while` statement repeatedly executes the statements between the braces that delimit its body (lines 18–23).

Line 19 displays the prompt "Enter grade: ". Line 20 reads the grade entered by the user and assigns it to variable `grade`. Then line 21 adds the new grade entered by the user to the `total` and assigns the result to `total`, which replaces its previous value.

Line 22 adds 1 to `gradeCounter` to indicate that the program has processed a grade and is ready to input the next grade from the user. Incrementing `gradeCounter` eventually causes it to exceed 10. Then the loop terminates, because its condition (line 17) becomes *false*.

Termination Phase: Calculating and Displaying the Class Average

When the loop terminates, line 26 performs the averaging calculation and assigns its result to the variable `average`. Line 29 uses `System.out`'s `printf` method to display the text "Total of all 10 grades is " followed by variable `total`'s value. Line 30 then uses `printf` to display the text "Class average is " followed by variable `average`'s value. When execution reaches line 31, the program terminates.

Notes on Integer Division and Truncation

The averaging calculation performed by method `main` produces an integer result. The program's output indicates that the sum of the grade values in the sample execution is 846, which, when divided by 10, should yield the floating-point number 84.6. However, the result of the calculation `total / 10` (line 26 of Fig. 3.6) is the integer 84, because `total` and 10 are both integers. Dividing two integers results in **integer division**—any fractional part of the calculation is **truncated** (i.e., *lost*). In the next section we'll see how to obtain a floating-point result from the averaging calculation.



Common Programming Error 3.4

Assuming that integer division rounds (rather than truncates) can lead to incorrect results. For example, $7 \div 4$, which yields 1.75 in conventional arithmetic, truncates to 1 in integer arithmetic, rather than rounding to 2.

A Note About Arithmetic Overflow

In Fig. 3.6, line 21

```
total = total + grade; // add grade to total
```

added each grade entered by the user to the `total`. Even this simple statement has a *potential* problem—adding the integers could result in a value that’s *too large* to store in an `int` variable. This is known as **arithmetic overflow** and causes *undefined behavior*, which can lead to unintended results (http://en.wikipedia.org/wiki/Integer_overflow#Security_ramifications). Figure 2.7’s Addition program had the same issue in line 23, which calculated the sum of two `int` values entered by the user:

```
sum = number1 + number2; // add numbers, then store total in sum
```

The maximum and minimum values that can be stored in an `int` variable are represented by the constants `MIN_VALUE` and `MAX_VALUE`, respectively, which are defined in class `Integer`. There are similar constants for the other integral types and for floating-point types. Each primitive type has a corresponding class type in package `java.lang`. You can see the values of these constants in each class’s online documentation. The online documentation for class `Integer` is located at:

```
http://docs.oracle.com/javase/7/docs/api/java/lang/Integer.html
```

It’s considered a good practice to ensure, *before* you perform arithmetic calculations like those in line 21 of Fig. 3.6 and line 23 of Fig. 2.7, that they will *not* overflow. The code for doing this is shown on the CERT website www.securecoding.cert.org—just search for guideline “NUM00-J.” The code uses the `&&` (logical AND) and `||` (logical OR) operators, which are introduced in Chapter 4. In industrial-strength code, you should perform checks like these for *all* calculations.

A Deeper Look at Receiving User Input

Any time a program receives input from the user, various problems might occur. For example, in line 20 of Fig. 3.6

```
int grade = input.nextInt(); // input next grade
```

we assume that the user will enter an integer grade in the range 0 to 100. However, the person entering a grade could enter an integer less than 0, an integer greater than 100, an integer outside the range of values that can be stored in an `int` variable, a number containing a decimal point or a value containing letters or special symbols that’s not even an integer.

To ensure that inputs are valid, industrial-strength programs must test for all possible erroneous cases. A program that inputs grades should **validate** the grades by using **range checking** to ensure that they are values from 0 to 100. You can then ask the user to reenter any value that’s out of range. If a program requires inputs from a specific set of values (e.g., nonsequential product codes), you can ensure that each input matches a value in the set.

3.9 Formulating Algorithms: Sentinel-Controlled Repetition

Let’s generalize Section 3.8’s class-average problem. Consider the following problem:

Develop a class-averaging program that processes grades for an arbitrary number of students each time it’s run.

In the previous class-average example, the problem statement specified the number of students, so the number of grades (10) was known in advance. In this example, no indication is given of how many grades the user will enter during the program's execution. The program must process an arbitrary number of grades. How can it determine when to stop the input of grades? How will it know when to calculate and print the class average?

One way to solve this problem is to use a special value called a **sentinel value** (also called a **signal value**, a **dummy value** or a **flag value**) to indicate "end of data entry." The user enters grades until all legitimate grades have been entered. The user then types the sentinel value to indicate that no more grades will be entered. **Sentinel-controlled repetition** is often called **indefinite repetition** because the number of repetitions is *not* known before the loop begins executing.

Clearly, a sentinel value must be chosen that cannot be confused with an acceptable input value. Grades on a quiz are nonnegative integers, so -1 is an acceptable sentinel value for this problem. Thus, a run of the class-average program might process a stream of inputs such as 95, 96, 75, 74, 89 and -1 . The program would then compute and print the class average for the grades 95, 96, 75, 74 and 89; since -1 is the sentinel value, it should *not* enter into the averaging calculation.

Developing the Pseudocode Algorithm with Top-Down, Stepwise Refinement: The Top and First Refinement

We approach this class-average program with a technique called **top-down, stepwise refinement**, which is essential to the development of well-structured programs. We begin with a pseudocode representation of the **top**—a single statement that conveys the overall function of the program:

Determine the class average for the quiz

The top is, in effect, a *complete* representation of a program. Unfortunately, the top rarely conveys sufficient detail from which to write a Java program. So we now begin the refinement process. We divide the top into a series of smaller tasks and list these in the order in which they'll be performed. This results in the following **first refinement**:

Initialize variables

Input, sum and count the quiz grades

Calculate and print the class average

This refinement uses only the *sequence structure*—the steps listed should execute in order, one after the other.



Software Engineering Observation 3.2

Each refinement, as well as the top itself, is a complete specification of the algorithm—only the level of detail varies.



Software Engineering Observation 3.3

Many programs can be divided logically into three phases: an initialization phase that initializes the variables; a processing phase that inputs data values and adjusts program variables accordingly; and a termination phase that calculates and outputs the final results.

Proceeding to the Second Refinement

The preceding Software Engineering Observation is often all you need for the first refinement in the top-down process. To proceed to the next level of refinement—that is, the **second refinement**—we commit to specific variables. In this example, we need a running total of the numbers, a count of how many numbers have been processed, a variable to receive the value of each grade as it's input by the user and a variable to hold the calculated average. The pseudocode statement

Initialize variables

can be refined as follows:

Initialize total to zero
Initialize counter to zero

Only the variables *total* and *counter* need to be initialized before they're used. The variables *average* and *grade* (for the calculated average and the user input, respectively) need not be initialized, because their values will be replaced as they're calculated or input.

The pseudocode statement

Input, sum and count the quiz grades

requires *repetition* to successively input each grade. We do not know in advance how many grades will be entered, so we'll use sentinel-controlled repetition. The user enters grades one at a time. After entering the last grade, the user enters the sentinel value. The program tests for the sentinel value after each grade is input and terminates the loop when the user enters the sentinel value. The second refinement of the preceding pseudocode statement is then

Prompt the user to enter the first grade
Input the first grade (possibly the sentinel)
While the user has not yet entered the sentinel
 Add this grade into the running total
 Add one to the grade counter
 Prompt the user to enter the next grade
 Input the next grade (possibly the sentinel)

In pseudocode, we do *not* use braces around the statements that form the body of the *While* structure. We simply indent the statements under the *While* to show that they belong to the *While*. Again, pseudocode is only an informal program development aid.

The pseudocode statement

Calculate and print the class average

can be refined as follows:

If the counter is not equal to zero
 Set the average to the total divided by the counter
 Print the average
else
 Print "No grades were entered"

We're careful here to test for the possibility of *division by zero*—a *logic error* that, if undetected, would cause the program to fail or produce invalid output. The complete second refinement of the pseudocode for the class-average problem is shown in Fig. 3.7.



Error-Prevention Tip 3.4

When performing division (/) or remainder (%) calculations in which the right operand could be zero, test for this and handle it (e.g., display an error message) rather than allowing the error to occur.

```

1  Initialize total to zero
2  Initialize counter to zero
3
4  Prompt the user to enter the first grade
5  Input the first grade (possibly the sentinel)
6
7  While the user has not yet entered the sentinel
8      Add this grade into the running total
9      Add one to the grade counter
10 Prompt the user to enter the next grade
11 Input the next grade (possibly the sentinel)
12
13 If the counter is not equal to zero
14     Set the average to the total divided by the counter
15     Print the average
16 else
17     Print "No grades were entered"

```

Fig. 3.7 | Class-average pseudocode algorithm with sentinel-controlled repetition.

In Figs. 3.5 and 3.7, we included blank lines and indentation in the pseudocode to make it more readable. The blank lines separate the algorithms into their phases and set off control statements; the indentation emphasizes the bodies of the control statements.

The pseudocode algorithm in Fig. 3.7 solves the more general class-average problem. This algorithm was developed after two refinements. Sometimes more are needed.



Software Engineering Observation 3.4

Terminate the top-down, stepwise refinement process when you've specified the pseudocode algorithm in sufficient detail for you to convert the pseudocode to Java. Normally, implementing the Java program is then straightforward.



Software Engineering Observation 3.5

Some programmers do not use program development tools like pseudocode. They feel that their ultimate goal is to solve the problem on a computer and that writing pseudocode merely delays the production of final outputs. Although this may work for simple and familiar problems, it can lead to serious errors and delays in large, complex projects.

Implementing Sentinel-Controlled Repetition

In Fig. 3.8, method `main` (lines 7–46) implements the pseudocode algorithm of Fig. 3.7. Although each grade is an `int`, the averaging calculation is likely to produce a number with a *decimal point*—in other words, a real (floating-point) number. The type `int` cannot represent such a number, so this class uses type `double` to do so. You'll also see that control statements may be *stacked* on top of one another (in sequence). The `while` statement (lines 22–30) is followed in sequence by an `if...else` statement (lines 34–45). Much of the code in this program is identical to that in Fig. 3.6, so we concentrate on the new concepts.

```

1  // Fig. 3.8: ClassAverage.java
2  // Solving the class-average problem using sentinel-controlled repetition.
3  import java.util.Scanner; // program uses class Scanner
4
5  public class ClassAverage
6  {
7      public static void main(String[] args)
8      {
9          // create Scanner to obtain input from command window
10         Scanner input = new Scanner(System.in);
11
12         // initialization phase
13         int total = 0; // initialize sum of grades
14         int gradeCounter = 0; // initialize # of grades entered so far
15
16         // processing phase
17         // prompt for input and read grade from user
18         System.out.print("Enter grade or -1 to quit: ");
19         int grade = input.nextInt();
20
21         // loop until sentinel value read from user
22         while (grade != -1)
23         {
24             total = total + grade; // add grade to total
25             gradeCounter = gradeCounter + 1; // increment counter
26
27             // prompt for input and read next grade from user
28             System.out.print("Enter grade or -1 to quit: ");
29             grade = input.nextInt();
30         }
31
32         // termination phase
33         // if user entered at least one grade...
34         if (gradeCounter != 0)
35         {
36             // use number with decimal point to calculate average of grades
37             double average = (double) total / gradeCounter;
38
39             // display total and average (with two digits of precision)
40             System.out.printf("%nTotal of the %d grades entered is %d%n",
41                             gradeCounter, total);

```

Fig. 3.8 | Solving the class-average problem using sentinel-controlled repetition. (Part I of 2.)

```

42         System.out.printf("Class average is %.2f\n", average);
43     }
44     else // no grades were entered, so output appropriate message
45         System.out.println("No grades were entered");
46 }
47 } // end class ClassAverage

```

```

Enter grade or -1 to quit: 97
Enter grade or -1 to quit: 88
Enter grade or -1 to quit: 72
Enter grade or -1 to quit: -1

Total of the 3 grades entered is 257
Class average is 85.67

```

Fig. 3.8 | Solving the class-average problem using sentinel-controlled repetition. (Part 2 of 2.)

Floating-Point Number Precision and Memory Requirements

Most averages are not integers. So, this example calculates the class average as a **floating-point number**—a number with a *decimal point*, such as 43.95, 0.0, -129.8873. Java provides two primitive types for storing floating-point numbers in memory—`float` and `double`. Variables of type `float` represent **single-precision floating-point numbers** and can hold up to *seven significant digits*. Variables of type `double` represent **double-precision floating-point numbers**. These require *twice* as much memory as `float` variables and can hold up to *15 significant digits*—about *double* the precision of `float` variables.

Most programmers represent floating-point numbers with type `double`. In fact, Java treats all floating-point numbers you type in a program's source code (such as 7.33 and 0.0975) as `double` values by default. Such values in the source code are known as **floating-point literals**. See Appendix D, Primitive Types, for the precise ranges of values for `float`s and `double`s.

Program Logic for Sentinel-Controlled Repetition vs. Counter-Controlled Repetition

Line 37 declares `double` variable `average`, which allows us to store the class average as a floating-point number. Line 14 initializes `gradeCounter` to 0, because no grades have been entered yet. Remember that this program uses *sentinel-controlled repetition* to input the grades. To keep an accurate record of the number of grades entered, the program increments `gradeCounter` only when the user enters a valid grade.

Compare the program logic for sentinel-controlled repetition in this application with that for counter-controlled repetition in Fig. 3.6. In counter-controlled repetition, each iteration of the `while` statement (lines 17–23 of Fig. 3.6) reads a value from the user, for the specified number of iterations. In sentinel-controlled repetition, the program reads the first value (lines 18–19 of Fig. 3.8) before reaching the `while`. This value determines whether the program's flow of control should enter the body of the `while`. If the condition of the `while` is false, the user entered the sentinel value, so the body of the `while` does not execute (i.e., no grades were entered). If, on the other hand, the condition is *true*, the body begins execution, and the loop adds the grade value to the `total` and increments the `gradeCounter` (lines 24–25). Then lines 28–29 in the loop body input the next value from the user. Next, program control reaches the closing right brace of the loop body at line 30,

so execution continues with the test of the `while`'s condition (line 22). The condition uses the most recent grade input by the user to determine whether the loop body should execute again. The value of variable `grade` is always input from the user immediately before the program tests the `while` condition. This allows the program to determine whether the value just input is the sentinel value *before* the program processes that value (i.e., adds it to the `total`). If the sentinel value is input, the loop terminates, and the program does not add `-1` to the `total`.



Good Programming Practice 3.3

In a sentinel-controlled loop, prompts should remind the user of the sentinel.

After the loop terminates, the `if...else` statement at lines 34–45 executes. The condition at line 34 determines whether any grades were input. If none were input, the `else` part (lines 44–45) of the `if...else` statement executes and displays the message "No grades were entered" and the method returns control to the calling method.

Braces in a `while` statement

Notice the `while` statement's *block* in Fig. 3.8 (lines 23–30). Without the braces, the loop would consider its body to be only the first statement, which adds the `grade` to the `total`. The last three statements in the block would fall outside the loop body, causing the computer to interpret the code incorrectly as follows:

```
while (grade != -1)
    total = total + grade; // add grade to total
    gradeCounter = gradeCounter + 1; // increment counter
    // prompt for input and read next grade from user
    System.out.print("Enter grade or -1 to quit: ");
    grade = input.nextInt();
```

The preceding code would cause an *infinite loop* in the program if the user did not input the sentinel `-1` at line 19 (before the `while` statement).



Common Programming Error 3.5

Omitting the braces that delimit a block can lead to logic errors, such as infinite loops. To prevent this problem, some programmers enclose the body of every control statement in braces, even if the body contains only a single statement.

Explicitly and Implicitly Converting Between Primitive Types

If at least one grade was entered, line 37 of Fig. 3.8 calculates the average of the grades. Recall from Fig. 3.6 that integer division yields an integer result. Even though variable `average` is declared as a `double`, if we had written the averaging calculation as

```
double average = total / gradeCounter;
```

it would lose the fractional part of the quotient *before* the result of the division is assigned to `average`. This occurs because `total` and `gradeCounter` are *both* integers, and integer division yields an integer result.

Most averages are not whole numbers (e.g., 0, `-22` and `1024`). For this reason, we calculate the class average in this example as a floating-point number. To perform a floating-

point calculation with integer values, we must *temporarily* treat these values as floating-point numbers for use in the calculation. Java provides the **unary cast operator** to accomplish this task. Line 37 of Fig. 3.8 uses the **(double)** cast operator—a unary operator—to create a *temporary* floating-point copy of its operand `total` (which appears to the right of the operator). Using a cast operator in this manner is called **explicit conversion** or **type casting**. The value stored in `total` is still an integer.

The calculation now consists of a floating-point value (the temporary `double` copy of `total`) divided by the integer `gradeCounter`. Java can evaluate only arithmetic expressions in which the operands' types are *identical*. To ensure this, Java performs an operation called **promotion** (or **implicit conversion**) on selected operands. For example, in an expression containing `int` and `double` values, the `int` values are promoted to `double` values for use in the expression. In this example, the value of `gradeCounter` is promoted to type `double`, then floating-point division is performed and the result of the calculation is assigned to `average`. As long as the **(double)** cast operator is applied to *any* variable in the calculation, the calculation will yield a `double` result. Later in this chapter, we discuss all the primitive types. You'll learn more about the promotion rules in Section 5.7.



Common Programming Error 3.6

A cast operator can be used to convert between primitive numeric types, such as `int` and `double`. Casting to the wrong type may cause compilation errors.

A cast operator is formed by placing parentheses around any type's name. The operator is a **unary operator** (i.e., an operator that takes only one operand). Java also supports unary versions of the plus (+) and minus (−) operators, so you can write expressions like `-7` or `+5`. Cast operators associate from *right to left* and have the same precedence as other unary operators, such as unary + and unary −. This precedence is one level higher than that of the **multiplicative operators** *, / and %. (See the operator precedence chart in Appendix A.) We indicate the cast operator with the notation (*type*) in our precedence charts, to indicate that any type name can be used to form a cast operator.

Line 42 displays the class average. In this example, we display the class average *rounded* to the nearest hundredth. The format specifier `%.2f` in `printf`'s format control string indicates that variable `average`'s value should be displayed with two digits of precision to the right of the decimal point—indicated by `.2` in the format specifier. The three grades entered during the sample execution (Fig. 3.8) total 257, which yields the average 85.666666.... Method `printf` uses the precision in the format specifier to round the value to the specified number of digits. In this program, the average is rounded to the hundredths position and is displayed as 85.67.

Floating-Point Number Precision

Floating-point numbers are not always 100% precise, but they have numerous applications. For example, when we speak of a “normal” body temperature of 98.6, we do not need to be precise to a large number of digits. When we read the temperature on a thermometer as 98.6, it may actually be 98.5999473210643. Calling this number simply 98.6 is fine for most applications involving body temperatures.

Floating-point numbers often arise as a result of division, such as in this example's class-average calculation. In conventional arithmetic, when we divide 10 by 3, the result is 3.333333..., with the sequence of 3s repeating infinitely. The computer allocates only a

fixed amount of space to hold such a value, so clearly the stored floating-point value can be only an approximation.

Owing to the imprecise nature of floating-point numbers, type `double` is preferred over type `float`, because `double` variables can represent floating-point numbers more accurately. For this reason, we primarily use type `double` throughout the book. In some applications, the precision of `float` and `double` variables will be inadequate. For precise floating-point numbers (such as those required by monetary calculations), Java provides class `BigDecimal` (package `java.math`), which we'll discuss in Chapter 8.



Common Programming Error 3.7

Using floating-point numbers in a manner that assumes they're represented precisely can lead to incorrect results.

3.10 Formulating Algorithms: Nested Control Statements

For the next example, we once again formulate an algorithm by using pseudocode and top-down, stepwise refinement, and write a corresponding Java program. We've seen that control statements can be stacked on top of one another (in sequence). In this case study, we examine the only other structured way control statements can be connected—namely, by **nesting** one control statement within another.

Consider the following problem statement:

A college offers a course that prepares students for the state licensing exam for real-estate brokers. Last year, ten of the students who completed this course took the exam. The college wants to know how well its students did on the exam. You've been asked to write a program to summarize the results. You've been given a list of these 10 students. Next to each name is written a 1 if the student passed the exam or a 2 if the student failed.

Your program should analyze the results of the exam as follows:

1. *Input each test result (i.e., a 1 or a 2). Display the message "Enter result" on the screen each time the program requests another test result.*
2. *Count the number of test results of each type.*
3. *Display a summary of the test results, indicating the number of students who passed and the number who failed.*
4. *If more than eight students passed the exam, print "Bonus to instructor!"*

After reading the problem statement carefully, we make the following observations:

1. The program must process test results for 10 students. A counter-controlled loop can be used, because the number of test results is known in advance.
2. Each test result has a numeric value—either a 1 or a 2. Each time it reads a test result, the program must determine whether it's a 1 or a 2. We test for a 1 in our algorithm. If the number is not a 1, we assume that it's a 2. (Exercise 3.24 considers the consequences of this assumption.)
3. Two counters are used to keep track of the exam results—one to count the number of students who passed the exam and one to count the number who failed.
4. After the program has processed all the results, it must decide whether more than eight students passed the exam.

Let's proceed with top-down, stepwise refinement. We begin with a pseudocode representation of the top:

Analyze exam results and decide whether a bonus should be paid

Once again, the top is a *complete* representation of the program, but several refinements are likely to be needed before the pseudocode can evolve naturally into a Java program.

Our first refinement is

Initialize variables

Input the 10 exam results, and count passes and failures

Print a summary of the exam results and decide whether a bonus should be paid

Here, too, even though we have a *complete* representation of the entire program, further refinement is necessary. We now commit to specific variables. Counters are needed to record the passes and failures, a counter will be used to control the looping process and a variable is needed to store the user input. The variable in which the user input will be stored is *not* initialized at the start of the algorithm, because its value is read from the user during each iteration of the loop.

The pseudocode statement

Initialize variables

can be refined as follows:

Initialize passes to zero

Initialize failures to zero

Initialize student counter to one

Notice that only the counters are initialized at the start of the algorithm.

The pseudocode statement

Input the 10 exam results, and count passes and failures

requires a loop that successively inputs the result of each exam. We know in advance that there are precisely 10 exam results, so counter-controlled looping is appropriate. Inside the loop (i.e., *nested* within the loop), a double-selection structure will determine whether each exam result is a pass or a failure and will increment the appropriate counter. The refinement of the preceding pseudocode statement is then

While student counter is less than or equal to 10

Prompt the user to enter the next exam result

Input the next exam result

If the student passed

Add one to passes

Else

Add one to failures

Add one to student counter

We use blank lines to isolate the *If...Else* control structure, which improves readability.

The pseudocode statement

Print a summary of the exam results and decide whether a bonus should be paid

can be refined as follows:

Print the number of passes
Print the number of failures
If more than eight students passed
 Print "Bonus to instructor!"

Complete Second Refinement of Pseudocode and Conversion to Class Analysis

The complete second refinement appears in Fig. 3.9. Notice that blank lines are also used to set off the *While* structure for program readability. This pseudocode is now sufficiently refined for conversion to Java.

```

1  Initialize passes to zero
2  Initialize failures to zero
3  Initialize student counter to one
4
5  While student counter is less than or equal to 10
6      Prompt the user to enter the next exam result
7      Input the next exam result
8
9      If the student passed
10         Add one to passes
11     Else
12         Add one to failures
13
14     Add one to student counter
15
16 Print the number of passes
17 Print the number of failures
18
19 If more than eight students passed
20     Print "Bonus to instructor!"

```

Fig. 3.9 | Pseudocode for examination-results problem.

The Java class that implements the pseudocode algorithm and two sample executions are shown in Fig. 3.10. Lines 13, 14, 15 and 22 of `main` declare the variables that are used to process the examination results.



Error-Prevention Tip 3.5

Initializing local variables when they're declared helps you avoid compilation errors that might arise from attempts to use uninitialized variables. While Java does not require that local-variable initializations be incorporated into declarations, it does require that each local variable be given a value before its value is used in an expression.

The `while` statement (lines 18–32) loops 10 times. During each iteration, the loop inputs and processes one exam result. Notice that the `if...else` statement (lines 25–28) for processing each result is *nested* in the `while` statement. If the `result` is 1, the `if...else` statement increments `passes`; otherwise, it assumes the `result` is 2 and increments `failures`. Line 31 increments `studentCounter` before the loop condition is tested again at line 18. After 10 values have been input, the loop terminates and line 35 displays the number of passes and failures. The `if` statement at lines 38–39 determines whether more than eight students passed the exam and, if so, outputs the message "Bonus to instructor!".

```

1 // Fig. 3.10: Analysis.java
2 // Analysis of examination results using nested control statements.
3 import java.util.Scanner; // class uses class Scanner
4
5 public class Analysis
6 {
7     public static void main(String[] args)
8     {
9         // create Scanner to obtain input from command window
10        Scanner input = new Scanner(System.in);
11
12        // initializing variables in declarations
13        int passes = 0;
14        int failures = 0;
15        int studentCounter = 1;
16
17        // process 10 students using counter-controlled loop
18        while (studentCounter <= 10)
19        {
20            // prompt user for input and obtain value from user
21            System.out.print("Enter result (1 = pass, 2 = fail): ");
22            int result = input.nextInt();
23
24            // if...else is nested in the while statement
25            if (result == 1)
26                passes = passes + 1;
27            else
28                failures = failures + 1;
29
30            // increment studentCounter so loop eventually terminates
31            studentCounter = studentCounter + 1;
32        }
33
34        // termination phase; prepare and display results
35        System.out.printf("Passed: %d\nFailed: %d\n", passes, failures);
36
37        // determine whether more than 8 students passed
38        if (passes > 8)
39            System.out.println("Bonus to instructor!");
40    }
41 } // end class Analysis

```

Fig. 3.10 | Analysis of examination results using nested control statements. (Part I of 2.)

```

Enter result (1 = pass, 2 = fail): 1
Enter result (1 = pass, 2 = fail): 2
Enter result (1 = pass, 2 = fail): 1
Enter result (1 = pass, 2 = fail): 1
Enter result (1 = pass, 2 = fail): 1
Enter result (1 = pass, 2 = fail): 1
Enter result (1 = pass, 2 = fail): 1
Enter result (1 = pass, 2 = fail): 1
Enter result (1 = pass, 2 = fail): 1
Enter result (1 = pass, 2 = fail): 1
Passed: 9
Failed: 1
Bonus to instructor!

```

```

Enter result (1 = pass, 2 = fail): 1
Enter result (1 = pass, 2 = fail): 2
Enter result (1 = pass, 2 = fail): 1
Enter result (1 = pass, 2 = fail): 2
Enter result (1 = pass, 2 = fail): 1
Enter result (1 = pass, 2 = fail): 2
Enter result (1 = pass, 2 = fail): 2
Enter result (1 = pass, 2 = fail): 1
Enter result (1 = pass, 2 = fail): 1
Enter result (1 = pass, 2 = fail): 1
Passed: 6
Failed: 4

```

Fig. 3.10 | Analysis of examination results using nested control statements. (Part 2 of 2.)

Figure 3.10 shows the input and output from two sample executions of the program. During the first, the condition at line 38 of method `main` is `true`—more than eight students passed the exam, so the program outputs a message to bonus the instructor.

3.11 Compound Assignment Operators

The **compound assignment operators** abbreviate assignment expressions. Statements like

```
variable = variable operator expression;
```

where *operator* is one of the binary operators `+`, `-`, `*`, `/` or `%` (or others we discuss later in the text) can be written in the form

```
variable operator = expression;
```

For example, you can abbreviate the statement

```
c = c + 3;
```

with the **addition compound assignment operator**, `+=`, as

```
c += 3;
```

The `+=` operator adds the value of the expression on its right to the value of the variable on its left and stores the result in the variable on the left of the operator. Thus, the assignment

expression `c += 3` adds 3 to `c`. Figure 3.11 shows the arithmetic compound assignment operators, sample expressions using the operators and explanations of what the operators do.

Assignment operator	Sample expression	Explanation	Assigns
<i>Assume: int c = 3, d = 5, e = 4, f = 6, g = 12;</i>			
<code>+=</code>	<code>c += 7</code>	<code>c = c + 7</code>	10 to <code>c</code>
<code>-=</code>	<code>d -= 4</code>	<code>d = d - 4</code>	1 to <code>d</code>
<code>*=</code>	<code>e *= 5</code>	<code>e = e * 5</code>	20 to <code>e</code>
<code>/=</code>	<code>f /= 3</code>	<code>f = f / 3</code>	2 to <code>f</code>
<code>%=</code>	<code>g %= 9</code>	<code>g = g % 9</code>	3 to <code>g</code>

Fig. 3.11 | Arithmetic compound assignment operators.

3.12 Increment and Decrement Operators

Java provides two unary operators (summarized in Fig. 3.12) for adding 1 to or subtracting 1 from the value of a numeric variable. These are the unary **increment operator**, `++`, and the unary **decrement operator**, `--`. A program can increment by 1 the value of a variable called `c` using the increment operator, `++`, rather than the expression `c = c + 1` or `c += 1`. An increment or decrement operator that's prefixed to (placed before) a variable is referred to as the **prefix increment** or **prefix decrement operator**, respectively. An increment or decrement operator that's postfix to (placed after) a variable is referred to as the **postfix increment** or **postfix decrement operator**, respectively.

Operator	Operator name	Sample expression	Explanation
<code>++</code>	prefix increment	<code>++a</code>	Increment <code>a</code> by 1, then use the new value of <code>a</code> in the expression in which <code>a</code> resides.
<code>++</code>	postfix increment	<code>a++</code>	Use the current value of <code>a</code> in the expression in which <code>a</code> resides, then increment <code>a</code> by 1.
<code>--</code>	prefix decrement	<code>--b</code>	Decrement <code>b</code> by 1, then use the new value of <code>b</code> in the expression in which <code>b</code> resides.
<code>--</code>	postfix decrement	<code>b--</code>	Use the current value of <code>b</code> in the expression in which <code>b</code> resides, then decrement <code>b</code> by 1.

Fig. 3.12 | Increment and decrement operators.

Using the prefix increment (or decrement) operator to add 1 to (or subtract 1 from) a variable is known as **preincrementing** (or **predecrementing**). This causes the variable to be incremented (decremented) by 1; then the new value of the variable is used in the expression in which it appears. Using the postfix increment (or decrement) operator to add 1 to (or subtract 1 from) a variable is known as **postincrementing** (or **postdecrementing**).

This causes the current value of the variable to be used in the expression in which it appears; then the variable's value is incremented (decremented) by 1.



Good Programming Practice 3.4

Unlike binary operators, the unary increment and decrement operators should be placed next to their operands, with no intervening spaces.

Difference Between Prefix Increment and Postfix Increment Operators

Figure 3.13 demonstrates the difference between the prefix increment and postfix increment versions of the ++ increment operator. The decrement operator (--) works similarly.

Line 9 initializes the variable `c` to 5, and line 10 outputs `c`'s initial value. Line 11 outputs the value of the expression `c++`. This expression postincrements the variable `c`, so `c`'s *original* value (5) is output, then `c`'s value is incremented (to 6). Thus, line 11 outputs `c`'s initial value (5) again. Line 12 outputs `c`'s new value (6) to prove that the variable's value was indeed incremented in line 11.

Line 17 resets `c`'s value to 5, and line 18 outputs `c`'s value. Line 19 outputs the value of the expression `++c`. This expression preincrements `c`, so its value is incremented; then the *new* value (6) is output. Line 20 outputs `c`'s value again to show that the value of `c` is still 6 after line 19 executes.

```

1 // Fig. 3.13: Increment.java
2 // Prefix increment and postfix increment operators.
3
4 public class Increment
5 {
6     public static void main(String[] args)
7     {
8         // demonstrate postfix increment operator
9         int c = 5;
10        System.out.printf("c before postincrement: %d\n", c); // prints 5
11        System.out.printf("    postincrementing c: %d\n", c++); // prints 5
12        System.out.printf(" c after postincrement: %d\n", c); // prints 6
13
14        System.out.println(); // skip a line
15
16        // demonstrate prefix increment operator
17        c = 5;
18        System.out.printf(" c before preincrement: %d\n", c); // prints 5
19        System.out.printf("    preincrementing c: %d\n", ++c); // prints 6
20        System.out.printf(" c after preincrement: %d\n", c); // prints 6
21    }
22 } // end class Increment

```

```

c before postincrement: 5
    postincrementing c: 5
 c after postincrement: 6

c before preincrement: 5
    preincrementing c: 6
 c after preincrement: 6

```

Fig. 3.13 | Prefix increment and postfix increment operators.

Simplifying Statements with the Arithmetic Compound Assignment, Increment and Decrement Operators

The arithmetic compound assignment operators and the increment and decrement operators can be used to simplify program statements. For example, the three assignment statements in Fig. 3.10 (lines 26, 28 and 31)

```
passes = passes + 1;
failures = failures + 1;
studentCounter = studentCounter + 1;
```

can be written more concisely with compound assignment operators as

```
passes += 1;
failures += 1;
studentCounter += 1;
```

with prefix increment operators as

```
++passes;
++failures;
++studentCounter;
```

or with postfix increment operators as

```
passes++;
failures++;
studentCounter++;
```

When incrementing or decrementing a variable in a statement by itself, the prefix increment and postfix increment forms have the *same* effect, and the prefix decrement and postfix decrement forms have the *same* effect. It's only when a variable appears in the context of a larger expression that preincrementing and postincrementing the variable have different effects (and similarly for predecrementing and postdecrementing).

**Common Programming Error 3.8**

Attempting to use the increment or decrement operator on an expression other than one to which a value can be assigned is a syntax error. For example, writing ++(x + 1) is a syntax error, because (x + 1) is not a variable.

Operator Precedence and Associativity

Figure 3.14 shows the precedence and associativity of the operators we've introduced. They're shown from top to bottom in decreasing order of precedence. The second column describes the associativity of the operators at each level of precedence. The conditional operator (? :); the unary operators increment (++), decrement (--), plus (+) and minus (-); the cast operators and the assignment operators =, +=, -=, *=, /= and %= associate from *right to left*. All the other operators in the operator precedence chart in Fig. 3.14 associate from left to right. The third column lists the type of each group of operators.

**Good Programming Practice 3.5**

Refer to Appendix A, Operator Precedence Chart, when writing expressions containing many operators. Confirm that the operators in the expression are performed in the order you expect. If you're uncertain about the evaluation order, break the expression into smaller statements or use parentheses to force the evaluation order, exactly as you'd do in an algebraic expression. Some operators such as assignment (=) associate right to left rather than left to right.

Operators	Associativity	Type
++ --	right to left	unary postfix
++ -- + - (<i>type</i>)	right to left	unary prefix
* / %	left to right	multiplicative
+ -	left to right	additive
< <= > >=	left to right	relational
== !=	left to right	equality
?:	right to left	conditional
= += -= *= /= %=	right to left	assignment

Fig. 3.14 | Precedence and associativity of the operators discussed so far.

3.13 Primitive Types

The table in Appendix D lists the eight primitive types in Java. Like its predecessor languages C and C++, Java requires all variables to have a type. For this reason, Java is referred to as a **strongly typed language**.

In C and C++, programmers frequently have to write separate versions of programs to support different computer platforms, because the primitive types are not guaranteed to be identical from computer to computer. For example, an `int` on one machine might be represented by 16 bits (2 bytes) of memory, on a second machine by 32 bits (4 bytes), and on another machine by 64 bits (8 bytes). In Java, `int` values are always 32 bits (4 bytes).



Portability Tip 3.1

The primitive types in Java are portable across all computer platforms that support Java.

Each type in Appendix D is listed with its size in bits (there are eight bits to a byte) and its range of values. Because the designers of Java want to ensure portability, they use internationally recognized standards for character formats (Unicode; for more information, visit www.unicode.org) and floating-point numbers (IEEE 754; for more information, visit groupenr.ieee.org/groups/754/).

3.14 (Optional) GUI and Graphics Case Study: Creating Simple Drawings

An appealing feature of Java is its graphics support, which enables you to visually enhance your applications. We now introduce one of Java's graphical capabilities—drawing lines. It also covers the basics of creating a window to display a drawing on the computer screen.

Java's Coordinate System

To draw in Java, you must understand Java's **coordinate system** (Fig. 3.15), a scheme for identifying points on the screen. By default, the upper-left corner of a GUI component has the coordinates (0, 0). A coordinate pair is composed of an **x-coordinate** (the **horizontal coordinate**) and a **y-coordinate** (the **vertical coordinate**). The *x*-coordinate is the hor-

horizontal location moving from *left to right*. The *y*-coordinate is the vertical location moving from *top to bottom*. The *x*-axis describes every horizontal coordinate, and the *y*-axis every vertical coordinate. Coordinates indicate where graphics should be displayed on a screen. Coordinate units are measured in **pixels**. The term pixel stands for “picture element.” A pixel is a display monitor’s smallest unit of resolution.




Fig. 3.15 | Java coordinate system. Units are measured in pixels.

First Drawing Application

Our first drawing application simply draws two lines. Class `DrawPanel` (Fig. 3.16) performs the actual drawing, while class `DrawPanelTest` (Fig. 3.17) creates a window to display the drawing. In class `DrawPanel`, the `import` statements in lines 3–4 allow us to use class **Graphics** (from package `java.awt`), which provides various methods for drawing text and shapes onto the screen, and class **JPanel** (from package `javax.swing`), which provides an area on which we can draw.

```

1 // Fig. 3.16: DrawPanel.java
2 // Using drawLine to connect the corners of a panel.
3 import java.awt.Graphics;
4 import javax.swing.JPanel;
5
6 public class DrawPanel extends JPanel
7 {
8     // draws an X from the corners of the panel
9     public void paintComponent(Graphics g)
10    {
11        // call paintComponent to ensure the panel displays correctly
12        super.paintComponent(g);
13
14        int width = getWidth(); // total width
15        int height = getHeight(); // total height
16
17        // draw a line from the upper-left to the lower-right
18        g.drawLine(0, 0, width, height);
19
20        // draw a line from the lower-left to the upper-right
21        g.drawLine(0, height, width, 0);
22    }
23 } // end class DrawPanel

```

Fig. 3.16 | Using `drawLine` to connect the corners of a panel.

```

1 // Fig. 3.17: DrawPanelTest.java
2 // Creating JFrame to display DrawPanel.
3 import javax.swing.JFrame;
4
5 public class DrawPanelTest
6 {
7     public static void main(String[] args)
8     {
9         // create a panel that contains our drawing
10        DrawPanel panel = new DrawPanel();
11
12        // create a new frame to hold the panel
13        JFrame application = new JFrame();
14
15        // set the frame to exit when it is closed
16        application.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
17
18        application.add(panel); // add the panel to the frame
19        application.setSize(250, 250); // set the size of the frame
20        application.setVisible(true); // make the frame visible
21    }
22 } // end class DrawPanelTest

```




Fig. 3.17 | Creating JFrame to display DrawPanel.

Line 6 uses the keyword **extends** to indicate that class `DrawPanel` is an enhanced type of `JPanel`. The keyword **extends** represents a so-called *inheritance* relationship in which our new class `DrawPanel` begins with the existing members (data and methods) from class `JPanel`. The class from which `DrawPanel` **inherits**, `JPanel`, appears to the right of keyword **extends**. In this inheritance relationship, `JPanel` is called the **superclass** and `DrawPanel` is called the **subclass**. This results in a `DrawPanel` class that has the attributes (data) and behaviors (methods) of class `JPanel` as well as the new features we're adding in our `DrawPanel` class declaration—specifically, the ability to draw two lines along the diagonals of the panel. Inheritance is explained in detail in Chapter 9. For now, you should mimic our `DrawPanel` class when creating your own graphics programs.

Method `paintComponent`

Every `JPanel`, including our `DrawPanel`, has a **`paintComponent`** method (lines 9–22), which the system automatically calls every time it needs to display the `DrawPanel`. Method `paintComponent` must be declared as shown in line 9—otherwise, the system will not call

it. This method is called when a `JPanel` is first displayed on the screen, when it's *covered* then *uncovered* by a window on the screen, and when the window in which it appears is *resized*. Method `paintComponent` requires one argument, a `Graphics` object, that's provided by the system when it calls `paintComponent`. This `Graphics` object is used to draw lines, rectangles, ovals and other graphics.

The first statement in every `paintComponent` method you create should always be

```
super.paintComponent(g);
```

which ensures that the panel is properly rendered before we begin drawing on it. Next, lines 14–15 call methods that class `DrawPanel` inherits from `JPanel`. Because `DrawPanel` extends `JPanel`, `DrawPanel` can use any public methods of `JPanel`. Methods `getWidth` and `getHeight` return the `JPanel`'s width and height, respectively. Lines 14–15 store these values in the local variables `width` and `height`. Finally, lines 18 and 21 use the `Graphics` variable `g` to call method `drawLine` to draw the two lines. Method `drawLine` draws a line between two points represented by its four arguments. The first two arguments are the *x*- and *y*-coordinates for one endpoint, and the last two arguments are the coordinates for the other endpoint. If you *resize* the window, the lines will *scale* accordingly, because the arguments are based on the width and height of the panel. Resizing the window in this application causes the system to call `paintComponent` to *redraw* the `DrawPanel`'s contents.

Class `DrawPanelTest`

To display the `DrawPanel` on the screen, you must place it in a window. You create a window with an object of class `JFrame`. In `DrawPanelTest.java` (Fig. 3.17), line 3 imports class `JFrame` from package `javax.swing`. Line 10 in `main` creates a `DrawPanel` object, which contains our drawing, and line 13 creates a new `JFrame` that can hold and display our panel. Line 16 calls `JFrame` method `setDefaultCloseOperation` with the argument `JFrame.EXIT_ON_CLOSE` to indicate that the application should terminate when the user closes the window. Line 18 uses class `JFrame`'s **add method** to *attach* the `DrawPanel` to the `JFrame`. Line 19 sets the *size* of the `JFrame`. Method `setSize` takes two parameters that represent the width and height of the `JFrame`, respectively. Finally, line 20 *displays* the `JFrame` by calling its **setVisible method** with the argument `true`. When the `JFrame` is displayed, the `DrawPanel`'s `paintComponent` method (lines 9–22 of Fig. 3.16) is implicitly called, and the two lines are drawn (see the sample outputs in Fig. 3.17). Try resizing the window to see that the lines always draw based on the window's current width and height.

GUI and Graphics Case Study Exercises

- 3.1 Using loops and control statements to draw lines can lead to many interesting designs.
 - a) Create the design in the left screen capture of Fig. 3.18. This design draws lines from the top-left corner, fanning them out until they cover the upper-left half of the panel. One approach is to divide the width and height into an equal number of steps (we found 15 steps worked well). The first endpoint of a line will always be in the top-left corner (0, 0). The second endpoint can be found by starting at the bottom-left corner and moving up one vertical step and right one horizontal step. Draw a line between the two endpoints. Continue moving up and to the right one step to find each successive endpoint. The figure should scale accordingly as you resize the window.
 - b) Modify part (a) to have lines fan out from all four corners, as shown in the right screen capture of Fig. 3.18. Lines from opposite corners should intersect along the middle.




Fig. 3.18 | Lines fanning from a corner.

- 3.2** Figure 3.19 displays two additional designs created using `while` loops and `drawLine`.
- Create the design in the left screen capture of Fig. 3.19. Begin by dividing each edge into an equal number of increments (we chose 15 again). The first line starts in the top-left corner and ends one step right on the bottom edge. For each successive line, move down one increment on the left edge and right one increment on the bottom edge. Continue drawing lines until you reach the bottom-right corner. The figure should scale as you resize the window so that the endpoints always touch the edges.
 - Modify your answer in part (a) to mirror the design in all four corners, as shown in the right screen capture of Fig. 3.19.




Fig. 3.19 | Line art with loops and `drawLine`.

3.15 Wrap-Up

This chapter presented basic problem solving for building classes and developing methods for these classes. We demonstrated how to construct an algorithm (i.e., an approach to solving a problem), then how to refine the algorithm through several phases of pseudocode development, resulting in Java code that can be executed as part of a method. The chapter showed how to use top-down, stepwise refinement to plan out the specific actions that a method must perform and the order in which the method must perform these actions.

Only three types of control structures—sequence, selection and repetition—are needed to develop any problem-solving algorithm. Specifically, this chapter demonstrated the `if` single-selection statement, the `if...else` double-selection statement and the `while` repetition statement. These are some of the building blocks used to construct solutions to many problems. We used control-statement stacking to total and compute the average of a set of student grades with counter- and sentinel-controlled repetition, and we used control-statement nesting to analyze and make decisions based on a set of exam results. We introduced Java's compound assignment operators and its increment and decrement operators. Finally, we discussed Java's primitive types. In Chapter 4, we continue our discussion of control statements, introducing the `for`, `do...while` and `switch` statements.

Summary

Section 3.1 Introduction

- Before writing a program to solve a problem, you must have a thorough understanding of the problem and a carefully planned approach to solving it. You must also understand the building blocks that are available and employ proven program-construction techniques.

Section 3.2 Algorithms

- Any computing problem can be solved by executing a series of actions (p. 73) in a specific order.
- A procedure for solving a problem in terms of the actions to execute and the order in which they execute is called an algorithm (p. 73).
- Specifying the order in which statements execute in a program is called program control (p. 73).

Section 3.3 Pseudocode

- Pseudocode (p. 74) is an informal language that helps you develop algorithms without having to worry about the strict details of Java language syntax.
- The pseudocode we use in this book is similar to everyday English—it's convenient and user friendly, but it's not an actual computer programming language. You may, of course, use your own native language(s) to develop your own pseudocode.
- Pseudocode helps you “think out” a program before attempting to write it in a programming language, such as Java.
- Carefully prepared pseudocode can easily be converted to a corresponding Java program.

Section 3.4 Control Structures

- Normally, statements in a program are executed one after the other in the order in which they're written. This process is called sequential execution (p. 74).
- Various Java statements enable you to specify that the next statement to execute is not necessarily the next one in sequence. This is called transfer of control (p. 74).
- Bohm and Jacopini demonstrated that all programs could be written in terms of only three control structures (p. 74)—the sequence structure, the selection structure and the repetition structure.
- The term “control structures” comes from the field of computer science. The *Java Language Specification* refers to “control structures” as “control statements” (p. 75).

- The sequence structure is built into Java. Unless directed otherwise, the computer executes Java statements one after the other in the order in which they're written—that is, in sequence.
- Anywhere a single action may be placed, several actions may be placed in sequence.
- Activity diagrams (p. 75) are part of the UML. An activity diagram models the workflow (p. 75; also called the activity) of a portion of a software system.
- Activity diagrams are composed of symbols (p. 75)—such as action-state symbols, diamonds and small circles—that are connected by transition arrows, which represent the flow of the activity.
- Action states (p. 75) contain action expressions that specify particular actions to perform.
- The arrows in an activity diagram represent transitions, which indicate the order in which the actions represented by the action states occur.
- The solid circle located at the top of an activity diagram represents the activity's initial state (p. 75)—the beginning of the workflow before the program performs the modeled actions.
- The solid circle surrounded by a hollow circle that appears at the bottom of the diagram represents the final state (p. 75)—the end of the workflow after the program performs its actions.
- Rectangles with their upper-right corners folded over are UML notes (p. 75)—explanatory remarks that describe the purpose of symbols in the diagram.
- Java has three types of selection statements (p. 76).
- The `if` single-selection statement (p. 76) selects or ignores one or more actions.
- The `if...else` double-selection statement selects between two actions or groups of actions.
- The `switch` statement is called a multiple-selection statement (p. 76) because it selects among many different actions or groups of actions.
- Java provides the `while`, `do...while` and `for` repetition (also called iteration or looping) statements that enable programs to perform statements repeatedly as long as a loop-continuation condition remains true.
- The `while` and `for` statements perform the action(s) in their bodies zero or more times—if the loop-continuation condition (p. 76) is initially false, the action(s) will not execute. The `do...while` statement performs the action(s) in its body one or more times.
- The words `if`, `else`, `switch`, `while`, `do` and `for` are Java keywords. Keywords cannot be used as identifiers, such as variable names.
- Every program is formed by combining as many sequence, selection and repetition statements (p. 76) as is appropriate for the algorithm the program implements.
- Single-entry/single-exit control statements (p. 76) are attached to one another by connecting the exit point of one to the entry point of the next. This is known as control-statement stacking.
- A control statement may also be nested (p. 76) inside another control statement.

Section 3.5 if Single-Selection Statement

- Programs use selection statements to choose among alternative courses of action.
- The single-selection `if` statement's activity diagram contains the diamond symbol, which indicates that a decision is to be made. The workflow follows a path determined by the symbol's associated guard conditions (p. 77). If a guard condition is true, the workflow enters the action state to which the corresponding transition arrow points.
- The `if` statement is a single-entry/single-exit control statement.

Section 3.6 if...else Double-Selection Statement

- The `if` single-selection statement performs an indicated action only when the condition is true.

- The `if...else` double-selection (p. 76) statement performs one action when the condition is true and another action when the condition is false.
- A program can test multiple cases with nested `if...else` statements (p. 78).
- The conditional operator (`?:`, p. 81) is Java's only ternary operator—it takes three operands. Together, the operands and the `?:` symbol form a conditional expression (p. 81).
- The Java compiler associates an `else` with the immediately preceding `if` unless told to do otherwise by the placement of braces.
- The `if` statement expects one statement in its body. To include several statements in the body of an `if` (or the body of an `else` for an `if...else` statement), enclose the statements in braces.
- A block (p. 81) of statements can be placed anywhere that a single statement can be placed.
- A logic error (p. 81) has its effect at execution time. A fatal logic error (p. 81) causes a program to fail and terminate prematurely. A nonfatal logic error (p. 81) allows a program to continue executing, but causes it to produce incorrect results.
- Just as a block can be placed anywhere a single statement can be placed, you can also use an empty statement, represented by placing a semicolon (`;`) where a statement would normally be.

Section 3.7 *while* Repetition Statement

- The `while` repetition statement (p. 82) allows you to specify that a program should repeat an action while some condition remains true.
- The UML's merge (p. 82) symbol joins two flows of activity into one.
- The decision and merge symbols can be distinguished by the number of incoming and outgoing transition arrows. A decision symbol has one transition arrow pointing to the diamond and two or more transition arrows pointing out from the diamond to indicate possible transitions from that point. Each transition arrow pointing out of a decision symbol has a guard condition. A merge symbol has two or more transition arrows pointing to the diamond and only one transition arrow pointing from the diamond, to indicate multiple activity flows merging to continue the activity. None of the transition arrows associated with a merge symbol has a guard condition.

Section 3.8 *Formulating Algorithms: Counter-Controlled Repetition*

- Counter-controlled repetition (p. 84) uses a variable called a counter (or control variable) to control the number of times a set of statements execute.
- Counter-controlled repetition is often called definite repetition (p. 84), because the number of repetitions is known before the loop begins executing.
- A total (p. 84) is a variable used to accumulate the sum of several values. Variables used to store totals are normally initialized to zero before being used in a program.
- A local variable's declaration must appear before the variable is used in that method. A local variable cannot be accessed outside the method in which it's declared.
- Dividing two integers results in integer division—the calculation's fractional part is truncated.

Section 3.9 *Formulating Algorithms: Sentinel-Controlled Repetition*

- In sentinel-controlled repetition (p. 88), a special value called a sentinel value (also called a signal value, a dummy value or a flag value) is used to indicate "end of data entry."
- A sentinel value must be chosen that cannot be confused with an acceptable input value.
- Top-down, stepwise refinement (p. 88) is essential to the development of well-structured programs.
- Division by zero is a logic error.
- To perform a floating-point calculation with integer values, cast one of the integers to type `double`.

- Java knows how to evaluate only arithmetic expressions in which the operands' types are identical. To ensure this, Java performs an operation called promotion on selected operands.
- The unary cast operator is formed by placing parentheses around the name of a type.

Section 3.11 Compound Assignment Operators

- The compound assignment operators (p. 99) abbreviate assignment expressions. Statements of the form

variable = *variable* *operator* *expression*;

where *operator* is one of the binary operators +, -, *, / or %, can be written in the form

variable *operator* = *expression*;

- The += operator adds the value of the expression on the right of the operator to the value of the variable on the left of the operator and stores the result in the variable on the left of the operator.

Section 3.12 Increment and Decrement Operators

- The unary increment operator, ++, and the unary decrement operator, --, add 1 to or subtract 1 from the value of a numeric variable (p. 100).
- An increment or decrement operator that's prefixed (p. 100) to a variable is the prefix increment or prefix decrement operator, respectively. An increment or decrement operator that's postfix (p. 100) to a variable is the postfix increment or postfix decrement operator, respectively.
- Using the prefix increment or decrement operator to add or subtract 1 is known as preincrementing or predecrementing, respectively.
- Preincrementing or predecrementing a variable causes the variable to be incremented or decremented by 1; then the new value of the variable is used in the expression in which it appears.
- Using the postfix increment or decrement operator to add or subtract 1 is known as postincrementing or postdecrementing, respectively.
- Postincrementing or postdecrementing the variable causes its value to be used in the expression in which it appears; then the variable's value is incremented or decremented by 1.
- When incrementing or decrementing a variable in a statement by itself, the prefix and postfix increment have the same effect, and the prefix and postfix decrement have the same effect.

Section 3.13 Primitive Types

- Java requires all variables to have a type. Thus, Java is referred to as a strongly typed language (p. 103).
- Java uses Unicode characters and IEEE 754 floating-point numbers.

Self-Review Exercises

3.1 Fill in the blanks in each of the following statements:

- All programs can be written in terms of three types of control structures: _____, _____ and _____.
- The _____ statement is used to execute one action when a condition is true and another when that condition is false.
- Repeating a set of instructions a specific number of times is called _____ repetition.
- When it's not known in advance how many times a set of statements will be repeated, a(n) _____ value can be used to terminate the repetition.
- The _____ structure is built into Java; by default, statements execute in the order they appear.

- f) Instance variables of types `char`, `byte`, `short`, `int`, `long`, `float` and `double` are all given the value _____ by default.
- g) Java is a(n) _____ language; it requires all variables to have a type.
- h) If the increment operator is _____ to a variable, first the variable is incremented by 1, then its new value is used in the expression.

3.2 State whether each of the following is *true* or *false*. If *false*, explain why.

- a) An algorithm is a procedure for solving a problem in terms of the actions to execute and the order in which they execute.
- b) A set of statements contained within a pair of parentheses is called a block.
- c) A selection statement specifies that an action is to be repeated while some condition remains true.
- d) A nested control statement appears in the body of another control statement.
- e) Java provides the arithmetic compound assignment operators `+=`, `-=`, `*=`, `/=` and `%=` for abbreviating assignment expressions.
- f) The primitive types (`boolean`, `char`, `byte`, `short`, `int`, `long`, `float` and `double`) are portable across only Windows platforms.
- g) Specifying the order in which statements execute in a program is called program control.
- h) The unary cast operator (`double`) creates a temporary integer copy of its operand.
- i) Instance variables of type `boolean` are given the value `true` by default.
- j) Pseudocode helps you think out a program before attempting to write it in a programming language.

3.3 Write four different Java statements that each add 1 to integer variable `x`.

3.4 Write Java statements to accomplish each of the following tasks:

- a) Use one statement to assign the sum of `x` and `y` to `z`, then increment `x` by 1.
- b) Test whether variable `count` is greater than 10. If it is, print "Count is greater than 10".
- c) Use one statement to decrement the variable `x` by 1, then subtract it from variable `total` and store the result in variable `total`.
- d) Calculate the remainder after `q` is divided by `divisor`, and assign the result to `q`. Write this statement in two different ways.

3.5 Write a Java statement to accomplish each of the following tasks:

- a) Declare variables `sum` of type `int` and initialize it to 0.
- b) Declare variables `x` of type `int` and initialize it to 1.
- c) Add variable `x` to variable `sum`, and assign the result to variable `sum`.
- d) Print "The sum is: ", followed by the value of variable `sum`.

3.6 Combine the statements that you wrote in Exercise 3.5 into a Java application that calculates and prints the sum of the integers from 1 to 10. Use a `while` statement to loop through the calculation and increment statements. The loop should terminate when the value of `x` becomes 11.

3.7 Determine the value of the variables in the statement `product *= x++;` after the calculation is performed. Assume that all variables are type `int` and initially have the value 5.

3.8 Identify and correct the errors in each of the following sets of code:

- a)

```
while (c <= 5)
{
    product *= c;
    ++c;
}
```
- b)

```
if (gender == 1)
    System.out.println("Woman");
else;
    System.out.println("Man");
```


3.9 What is wrong with the following while statement?

```
while (z >= 0)
    sum += z;
```

Answers to Self-Review Exercises

3.1 a) sequence, selection, repetition. b) if...else. c) counter-controlled (or definite). d) sentinel, signal, flag or dummy. e) sequence. f) 0 (zero). g) strongly typed. h) prefixed.

3.2 a) True. b) False. A set of statements contained within a pair of braces ({ and }) is called a block. c) False. A repetition statement specifies that an action is to be repeated while some condition remains true. d) True. e) True. f) False. The primitive types (boolean, char, byte, short, int, long, float and double) are portable across all computer platforms that support Java. g) True. h) False. The unary cast operator (double) creates a temporary floating-point copy of its operand. i) False. Instance variables of type boolean are given the value false by default. j) True.

3.3 x = x + 1;
x += 1;
++x;
x++;

3.4 a) z = x++ + y;
b) if (count > 10)
 System.out.println("Count is greater than 10");
c) total -= --x;
d) q %= divisor;
 q = q % divisor;

3.5 a) int sum = 0;
b) int x = 1;
c) sum += x; or sum = sum + x;
d) System.out.printf("The sum is: %d\n", sum);

3.6 The program is as follows:

```
1 // Exercise 3.6: Calculate.java
2 // Calculate the sum of the integers from 1 to 10
3 public class Calculate
4 {
5     public static void main(String[] args)
6     {
7         int sum = 0;
8         int x = 1;
9
10        while (x <= 10) // while x is less than or equal to 10
11        {
12            sum += x; // add x to sum
13            ++x; // increment x
14        }
15
16        System.out.printf("The sum is: %d\n", sum);
17    }
18 } // end class Calculate
```

The sum is: 55

3.7 product = 25, x = 6

- 3.8** a) Error: The closing right brace of the `while` statement's body is missing.
Correction: Add a closing right brace after the statement `++c`;
b) Error: The semicolon after `else` results in a logic error. The second output statement will always be executed.
Correction: Remove the semicolon after `else`.

3.9 The value of the variable `z` is never changed in the `while` statement. Therefore, if the loop-continuation condition (`z >= 0`) is true, an infinite loop is created. To prevent an infinite loop from occurring, `z` must be decremented so that it eventually becomes less than 0.

Exercises

3.10 Compare and contrast the `if` single-selection statement and the `while` repetition statement. How are these two statements similar? How are they different?

3.11 Explain what happens when a Java program attempts to divide one integer by another. What happens to the fractional part of the calculation? How can you avoid that outcome?

3.12 Describe the two ways in which control statements can be combined.

3.13 What type of repetition would be appropriate for calculating the sum of the first 100 positive integers? What type would be appropriate for calculating the sum of an arbitrary number of positive integers? Briefly describe how each of these tasks could be performed.

3.14 What is the difference between preincrementing and postincrementing a variable?

3.15 Identify and correct the errors in each of the following pieces of code. [*Note:* There may be more than one error in each piece of code.]

- a) `if (age >= 65);`
 `System.out.println("Age is greater than or equal to 65");`
 `else`
 `System.out.println("Age is less than 65");`
- b) `int x = 1, total;`
 `while (x <= 10)`
 {
 `total += x;`
 `++x;`
 }
- c) `while (x <= 100)`
 `total += x;`
 `++x;`
- d) `while (y > 0)`
 {
 `System.out.println(y);`
 `++y;`
 }

3.16 What does the following program print?

```
1 // Exercise 3.16: Mystery.java
2 public class Mystery
3 {
4     public static void main(String[] args)
5     {
6         int x = 1;
7         int total = 0;
```

```

8
9     while (x <= 10)
10    {
11        int y = x * x;
12        System.out.println(y);
13        total += y;
14        ++x;
15    }
16
17    System.out.printf("Total is %d\n", total);
18 }
19 } // end class Mystery

```

For Exercises 3.17 through 3.20, perform each of the following steps:

- Read the problem statement.
- Formulate the algorithm using pseudocode and top-down, stepwise refinement.
- Write a Java program.
- Test, debug and execute the Java program.
- Process three complete sets of data.

3.17 (Gas Mileage) Drivers are concerned with the mileage their automobiles get. One driver has kept track of several trips by recording the miles driven and gallons used for each tankful. Develop a Java application that will input the miles driven and gallons used (both as integers) for each trip. The program should calculate and display the miles per gallon obtained for each trip and print the combined miles per gallon obtained for all trips up to this point. All averaging calculations should produce floating-point results. Use class `Scanner` and sentinel-controlled repetition to obtain the data from the user.

3.18 (Credit Limit Calculator) Develop a Java application that determines whether any of several department-store customers has exceeded the credit limit on a charge account. For each customer, the following facts are available:

- account number
- balance at the beginning of the month
- total of all items charged by the customer this month
- total of all credits applied to the customer's account this month
- allowed credit limit.

The program should input all these facts as integers, calculate the new balance ($= \text{beginning balance} + \text{charges} - \text{credits}$), display the new balance and determine whether the new balance exceeds the customer's credit limit. For those customers whose credit limit is exceeded, the program should display the message "Credit limit exceeded".

3.19 (Sales Commission Calculator) A large company pays its salespeople on a commission basis. The salespeople receive \$200 per week plus 9% of their gross sales for that week. For example, a salesperson who sells \$5,000 worth of merchandise in a week receives \$200 plus 9% of \$5000, or a total of \$650. You've been supplied with a list of the items sold by each salesperson. The values of these items are as follows:

Item	Value
1	239.99
2	129.75
3	99.95
4	350.89

Develop a Java application that inputs one salesperson's items sold for last week and calculates and displays that salesperson's earnings. There's no limit to the number of items that can be sold.

3.20 (*Salary Calculator*) Develop a Java application that determines the gross pay for each of three employees. The company pays straight time for the first 40 hours worked by each employee and time and a half for all hours worked in excess of 40. You're given a list of the employees, their number of hours worked last week and their hourly rates. Your program should input this information for each employee, then determine and display the employee's gross pay. Use class Scanner to input the data.

3.21 (*Find the Largest Number*) The process of finding the largest value is used frequently in computer applications. For example, a program that determines the winner of a sales contest would input the number of units sold by each salesperson. The salesperson who sells the most units wins the contest. Write a pseudocode program, then a Java application that inputs a series of 10 integers and determines and prints the largest integer. Your program should use at least the following three variables:

- a) counter: A counter to count to 10 (i.e., to keep track of how many numbers have been input and to determine when all 10 numbers have been processed).
- b) number: The integer most recently input by the user.
- c) largest: The largest number found so far.

3.22 (*Tabular Output*) Write a Java application that uses looping to print the following table of values:

N	10*N	100*N	1000*N
1	10	100	1000
2	20	200	2000
3	30	300	3000
4	40	400	4000
5	50	500	5000

3.23 (*Find the Two Largest Numbers*) Using an approach similar to that for Exercise 3.21, find the *two* largest values of the 10 values entered. [Note: You may input each number only once.]

3.24 (*Validating User Input*) Modify the program in Fig. 3.10 to validate its inputs. For any input, if the value entered is other than 1 or 2, keep looping until the user enters a correct value.

3.25 What does the following program print?

```

1 // Exercise 3.25: Mystery2.java
2 public class Mystery2
3 {
4     public static void main(String[] args)
5     {
6         int count = 1;
7
8         while (count <= 10)
9         {
10            System.out.println(count % 2 == 1 ? "*****" : "+++++++");
11            ++count;
12        }
13    }
14 } // end class Mystery2

```

3.26 What does the following program print?

```

1 // Exercise 3.26: Mystery3.java
2 public class Mystery3
3 {
4     public static void main(String[] args)
5     {

```

```

6      int row = 10;
7
8      while (row >= 1)
9      {
10         int column = 1;
11
12         while (column <= 10)
13         {
14             System.out.print(row % 2 == 1 ? "<" : ">");
15             ++column;
16         }
17
18         --row;
19         System.out.println();
20     }
21 }
22 } // end class Mystery3

```

3.27 (Dangling-else Problem) Determine the output for each of the given sets of code when x is 9 and y is 11 and when x is 11 and y is 9. The compiler ignores the indentation in a Java program. Also, the Java compiler always associates an `else` with the immediately preceding `if` unless told to do otherwise by the placement of braces (`{}`). On first glance, you may not be sure which `if` a particular `else` matches—this situation is referred to as the “dangling-else problem.” We’ve eliminated the indentation from the following code to make the problem more challenging. [Hint: Apply the indentation conventions you’ve learned.]

```

a) if (x < 10)
    if (y > 10)
        System.out.println("*****");
    else
        System.out.println("#####");
    System.out.println("$$$$$");
b) if (x < 10)
    {
        if (y > 10)
            System.out.println("*****");
    }
    else
    {
        System.out.println("#####");
        System.out.println("$$$$$");
    }

```

3.28 (Another Dangling-else Problem) Modify the given code to produce the output shown in each part of the problem. Use proper indentation techniques. Make no changes other than inserting braces and changing the indentation of the code. The compiler ignores indentation in a Java program. We’ve eliminated the indentation from the given code to make the problem more challenging. [Note: It’s possible that no modification is necessary for some of the parts.]

```

if (y == 8)
if (x == 5)
    System.out.println("@@@@");
else
    System.out.println("#####");
System.out.println("$$$$$");
System.out.println("&&&&&");

```

- a) Assuming that $x = 5$ and $y = 8$, the following output is produced:

```
@@@@
$$$$$
&&&&&
```

- b) Assuming that $x = 5$ and $y = 8$, the following output is produced:

```
@@@@
```

- c) Assuming that $x = 5$ and $y = 8$, the following output is produced:

```
@@@@
```

- d) Assuming that $x = 5$ and $y = 7$, the following output is produced. [Note: The last three output statements after the `else` are all part of a block.]

```
####
$$$$$
&&&&&
```

3.29 (*Square of Asterisks*) Write an application that prompts the user to enter the size of the side of a square, then displays a hollow square of that size made of asterisks. Your program should work for squares of all side lengths between 1 and 20.

3.30 (*Palindromes*) A palindrome is a sequence of characters that reads the same backward as forward. For example, each of the following five-digit integers is a palindrome: 12321, 55555, 45554 and 11611. Write an application that reads in a five-digit integer and determines whether it's a palindrome. If the number is not five digits long, display an error message and allow the user to enter a new value.

3.31 (*Printing the Decimal Equivalent of a Binary Number*) Write an application that inputs an integer containing only 0s and 1s (i.e., a binary integer) and prints its decimal equivalent. [Hint: Use the remainder and division operators to pick off the binary number's digits one at a time, from right to left. In the decimal number system, the rightmost digit has a positional value of 1 and the next digit to the left a positional value of 10, then 100, then 1000, and so on. The decimal number 234 can be interpreted as $4 * 1 + 3 * 10 + 2 * 100$. In the binary number system, the rightmost digit has a positional value of 1, the next digit to the left a positional value of 2, then 4, then 8, and so on. The decimal equivalent of binary 1101 is $1 * 1 + 0 * 2 + 1 * 4 + 1 * 8$, or $1 + 0 + 4 + 8$ or, 13.]

3.32 (*Checkerboard Pattern of Asterisks*) Write an application that uses only the output statements

```
System.out.print("* ");
System.out.print(" ");
System.out.println();
```

to display the checkerboard pattern that follows. A `System.out.println` method call with no arguments causes the program to output a single newline character. [Hint: Repetition statements are required.]

```
* * * * *
 * * * * *
* * * * *
 * * * * *
* * * * *
 * * * * *
* * * * *
 * * * * *
* * * * *
```

3.33 (*Multiples of 2 with an Infinite Loop*) Write an application that keeps displaying in the command window the multiples of the integer 2—namely, 2, 4, 8, 16, 32, 64, and so on. Your loop should not terminate (i.e., it should create an infinite loop). What happens when you run this program?

3.34 (*What's Wrong with This Code?*) What is wrong with the following statement? Provide the correct statement to add one to the sum of x and y .

```
System.out.println(++(x + y));
```

3.35 (*Sides of a Triangle*) Write an application that reads three nonzero values entered by the user and determines and prints whether they could represent the sides of a triangle.

3.36 (*Sides of a Right Triangle*) Write an application that reads three nonzero integers and determines and prints whether they could represent the sides of a right triangle.

3.37 (*Factorial*) The factorial of a nonnegative integer n is written as $n!$ (pronounced “ n factorial”) and is defined as follows:

$$n! = n \cdot (n - 1) \cdot (n - 2) \cdot \dots \cdot 1 \quad (\text{for values of } n \text{ greater than or equal to } 1)$$

and

$$n! = 1 \quad (\text{for } n = 0)$$

For example, $5! = 5 \cdot 4 \cdot 3 \cdot 2 \cdot 1$, which is 120.

- Write an application that reads a nonnegative integer and computes and prints its factorial.
- Write an application that estimates the value of the mathematical constant e by using the following formula. Allow the user to enter the number of terms to calculate.

$$e = 1 + \frac{1}{1!} + \frac{1}{2!} + \frac{1}{3!} + \dots$$

- Write an application that computes the value of e^x by using the following formula. Allow the user to enter the number of terms to calculate.

$$e^x = 1 + \frac{x}{1!} + \frac{x^2}{2!} + \frac{x^3}{3!} + \dots$$

Making a Difference

3.38 (*Enforcing Privacy with Cryptography*) The explosive growth of Internet communications and data storage on Internet-connected computers has greatly increased privacy concerns. The field of cryptography is concerned with coding data to make it difficult (and hopefully—with the most advanced schemes—impossible) for unauthorized users to read. In this exercise you'll investigate a simple scheme for encrypting and decrypting data. A company that wants to send data over the Internet has asked you to write a program that will encrypt it so that it may be transmitted more securely. All the data is transmitted as four-digit integers. Your application should read a four-digit integer entered by the user and encrypt it as follows: Replace each digit with the result of adding 7 to the digit and getting the remainder after dividing the new value by 10. Then swap the first digit with the third, and swap the second digit with the fourth. Then print the encrypted integer. Write a separate application that inputs an encrypted four-digit integer and decrypts it (by reversing the encryption scheme) to form the original number. [*Optional reading project:* Research “public key cryptography” in general and the PGP (Pretty Good Privacy) specific public key scheme. You may also want to investigate the RSA scheme, which is widely used in industrial-strength applications.]

3.39 (*World Population Growth*) World population has grown considerably over the centuries. Continued growth could eventually challenge the limits of breathable air, drinkable water, arable cropland and other limited resources. There's evidence that growth has been slowing in recent years and that world population could peak sometime this century, then start to decline.

For this exercise, research world population growth issues online. *Be sure to investigate various viewpoints.* Get estimates for the current world population and its growth rate (the percentage by which it's likely to increase this year). Write a program that calculates world population growth each year for the next 75 years, *using the simplifying assumption that the current growth rate will stay*

constant. Print the results in a table. The first column should display the year from year 1 to year 75. The second column should display the anticipated world population at the end of that year. The third column should display the numerical increase in the world population that would occur that year. Using your results, determine the year in which the population would be double what it is today, if this year's growth rate were to persist.

Control Statements: Part 2; Logical Operators

4



The wheel is come full circle.

—William Shakespeare

*All the evolution we know of
proceeds from the vague to the
definite.*

—Charles Sanders Peirce

Objectives

In this chapter you'll:

- Learn the essentials of counter-controlled repetition.
- Use the **for** and **do...while** repetition statements to execute statements in a program repeatedly.
- Understand multiple selection using the **switch** selection statement.
- Use the **break** and **continue** program control statements to alter the flow of control.
- Use the logical operators to form complex conditional expressions in control statements.

4.1 Introduction	4.7 <code>break</code> and <code>continue</code> Statements
4.2 Essentials of Counter-Controlled Repetition	4.8 Logical Operators
4.3 <code>for</code> Repetition Statement	4.9 Structured Programming Summary
4.4 Examples Using the <code>for</code> Statement	4.10 (Optional) GUI and Graphics Case Study: Drawing Rectangles and Ovals
4.5 <code>do...while</code> Repetition Statement	4.11 Wrap-Up
4.6 <code>switch</code> Multiple-Selection Statement	

Summary | Self-Review Exercises | Answers to Self-Review Exercises | Exercises | Making a Difference

4.1 Introduction

This chapter continues our presentation of structured programming theory and principles by introducing all but one of Java's remaining control statements. We demonstrate Java's `for`, `do...while` and `switch` statements. Through a series of short examples using `while` and `for`, we explore the essentials of counter-controlled repetition. We use a `switch` statement to count the number of A, B, C, D and F grade equivalents in a set of numeric grades entered by the user. We introduce the `break` and `continue` program-control statements. We discuss Java's logical operators, which enable you to use more complex conditional expressions in control statements. Finally, we summarize Java's control statements and the proven problem-solving techniques presented in this chapter and Chapter 3.

4.2 Essentials of Counter-Controlled Repetition

This section uses the `while` repetition statement introduced in Chapter 3 to formalize the elements required to perform counter-controlled repetition, which requires

1. a **control variable** (or loop counter)
2. the **initial value** of the control variable
3. the **increment** by which the control variable is modified each time through the loop (also known as **each iteration of the loop**)
4. the **loop-continuation condition** that determines if looping should continue.

To see these elements of counter-controlled repetition, consider the application of Fig. 4.1, which uses a loop to display the numbers from 1 through 10.

```

1 // Fig. 4.1: WhileCounter.java
2 // Counter-controlled repetition with the while repetition statement.
3
4 public class WhileCounter
5 {
6     public static void main(String[] args)
7     {

```

Fig. 4.1 | Counter-controlled repetition with the `while` repetition statement. (Part 1 of 2.)

```

8      int counter = 1; // declare and initialize control variable
9
10     while (counter <= 10) // loop-continuation condition
11     {
12         System.out.printf("%d ", counter);
13         ++counter; // increment control variable
14     }
15
16     System.out.println();
17 }
18 } // end class WhileCounter

```

```
1 2 3 4 5 6 7 8 9 10
```

Fig. 4.1 | Counter-controlled repetition with the `while` repetition statement. (Part 2 of 2.)

In Fig. 4.1, the elements of counter-controlled repetition are defined in lines 8, 10 and 13. Line 8 *declares* the control variable (`counter`) as an `int`, *reserves space* for it in memory and sets its *initial value* to 1. Variable `counter` also could have been declared and initialized with the following local-variable declaration and assignment statements:

```

int counter; // declare counter
counter = 1; // initialize counter to 1

```

Line 12 displays control variable `counter`'s value during each iteration of the loop. Line 13 *increments* the control variable by 1 for each iteration of the loop. The loop-continuation condition in the `while` (line 10) tests whether the value of the control variable is less than or equal to 10 (the final value for which the condition is `true`). The program performs the body of this `while` even when the control variable is 10. The loop terminates when the control variable exceeds 10 (i.e., `counter` becomes 11).



Common Programming Error 4.1

Because floating-point values may be approximate, controlling loops with floating-point variables may result in imprecise counter values and inaccurate termination tests.



Error-Prevention Tip 4.1

Use integers to control counting loops.

The program in Fig. 4.1 can be made more concise by initializing `counter` to 0 in line 8 and *preincrementing* `counter` in the `while` condition as follows:

```

while (++counter <= 10) // loop-continuation condition
    System.out.printf("%d ", counter);

```

This code saves a statement, because the `while` condition performs the increment before testing the condition. (Recall from Section 3.12 that the precedence of `++` is higher than that of `<=`.) Coding in such a condensed fashion takes practice, might make code more difficult to read, debug, modify and maintain, and typically should be avoided.



Software Engineering Observation 4.1

"Keep it simple" is good advice for most of the code you'll write.

4.3 for Repetition Statement

Section 4.2 presented the essentials of counter-controlled repetition. The `while` statement can be used to implement any counter-controlled loop. Java also provides the **for repetition statement**, which specifies the counter-controlled-repetition details in a single line of code. Figure 4.2 reimplements the application of Fig. 4.1 using `for`.

```

1  // Fig. 4.2: ForCounter.java
2  // Counter-controlled repetition with the for repetition statement.
3
4  public class ForCounter
5  {
6      public static void main(String[] args)
7      {
8          // for statement header includes initialization,
9          // loop-continuation condition and increment
10         for (int counter = 1; counter <= 10; counter++)
11             System.out.printf("%d ", counter);
12
13         System.out.println();
14     }
15 } // end class ForCounter

```

```
1 2 3 4 5 6 7 8 9 10
```

Fig. 4.2 | Counter-controlled repetition with the `for` repetition statement.

When the `for` statement (lines 10–11) begins executing, the control variable `counter` is *declared* and *initialized* to 1. (Recall from Section 4.2 that the first two elements of counter-controlled repetition are the *control variable* and its *initial value*.) Next, the program checks the *loop-continuation condition*, `counter <= 10`, which is between the two required semicolons. Because the initial value of `counter` is 1, the condition initially is true. Therefore, the body statement (line 11) displays control variable `counter`'s value, namely 1. After executing the loop's body, the program increments `counter` in the expression `counter++`, which appears to the right of the second semicolon. Then the loop-continuation test is performed again to determine whether the program should continue with the next iteration of the loop. At this point, the control variable's value is 2, so the condition is still true (the *final value* is not exceeded)—thus, the program performs the body statement again (i.e., the next iteration of the loop). This process continues until the numbers 1 through 10 have been displayed and the `counter`'s value becomes 11, causing the loop-continuation test to fail and repetition to terminate (after 10 repetitions of the loop body). Then the program performs the first statement after the `for`—in this case, line 13.

Figure 4.2 uses (in line 10) the loop-continuation condition `counter <= 10`. If you incorrectly specified `counter < 10` as the condition, the loop would iterate only nine times. This is a common *logic error* called an **off-by-one error**.



Common Programming Error 4.2

Using an incorrect relational operator or an incorrect final value of a loop counter in the loop-continuation condition of a repetition statement can cause an off-by-one error.

**Error-Prevention Tip 4.2**

Using the final value and operator `<=` in a loop's condition helps avoid off-by-one errors. For a loop that outputs 1 to 10, the loop-continuation condition should be `counter <= 10` rather than `counter < 10` (which causes an off-by-one error) or `counter < 11` (which is correct). Many programmers prefer so-called zero-based counting, in which to count 10 times, counter would be initialized to zero and the loop-continuation test would be `counter < 10`.

**Error-Prevention Tip 4.3**

As Chapter 3 mentioned, integers can overflow, causing logic errors. A loop's control variable also could overflow. Write your loop conditions carefully to prevent this.

A Closer Look at the `for` Statement's Header

Figure 4.3 takes a closer look at the `for` statement in Fig. 4.2. The first line—including the keyword `for` and everything in parentheses after `for` (line 10 in Fig. 4.2)—is sometimes called the **for statement header**. The `for` header “does it all”—it specifies each item needed for counter-controlled repetition with a control variable. If there's more than one statement in the body of the `for`, braces are required to define the body of the loop.




Fig. 4.3 | `for` statement header components.

General Format of a `for` Statement

The general format of the `for` statement is

```
for (initialization; loopContinuationCondition; increment)
    statement
```

where the *initialization* expression names the loop's control variable and *optionally* provides its initial value, *loopContinuationCondition* determines whether the loop should continue executing and *increment* modifies the control variable's value, so that the loop-continuation condition eventually becomes false. The two semicolons in the `for` header are required. If the loop-continuation condition is initially false, the program does *not* execute the `for` statement's body. Instead, execution proceeds with the statement following the `for`.

Representing a `for` Statement with an Equivalent `while` Statement

The `for` statement often can be represented with an equivalent `while` statement as follows:

```
initialization;
while (loopContinuationCondition)
{
    statement
    increment;
}
```

In Section 4.7, we show a case in which a `for` statement cannot be represented with an equivalent `while` statement. Typically, `for` statements are used for counter-controlled repetition and `while` statements for sentinel-controlled repetition. However, `while` and `for` can each be used for either repetition type.

*Scope of a **for** Statement's Control Variable*

If the *initialization* expression in the `for` header declares the control variable (i.e., the control variable's type is specified before the variable name, as in Fig. 4.2), the control variable can be used *only* in that `for` statement—it will not exist outside it. This restricted use is known as the variable's **scope**. The scope of a variable defines where it can be used in a program. For example, a *local variable* can be used *only* in the method that declares it and *only* from the point of declaration through the end of the method. Scope is discussed in detail in Chapter 5, Methods.



Common Programming Error 4.3

When a `for` statement's control variable is declared in the initialization section of the `for`'s header, using the control variable after the `for`'s body is a compilation error.

*Expressions in a **for** Statement's Header Are Optional*

All three expressions in a `for` header are optional. If the *loopContinuationCondition* is omitted, Java assumes that the loop-continuation condition is *always true*, thus creating an *infinite loop*. You might omit the *initialization* expression if the program initializes the control variable *before* the loop. You might omit the *increment* expression if the program calculates the increment with statements in the loop's body or if no increment is needed. The increment expression in a `for` acts as if it were a standalone statement at the end of the `for`'s body. Therefore, the expressions

```
counter = counter + 1
counter += 1
++counter
counter++
```

are equivalent increment expressions in a `for` statement. Many programmers prefer `counter++` because it's concise and because a `for` loop evaluates its increment expression *after* its body executes, so the postfix increment form seems more natural. In this case, the variable being incremented does not appear in a larger expression, so preincrementing and postincrementing actually have the *same* effect.



Common Programming Error 4.4

Placing a semicolon immediately to the right of the right parenthesis of a `for` header makes that `for`'s body an empty statement. This is normally a logic error.



Error-Prevention Tip 4.4

Infinite loops occur when the loop-continuation condition in a repetition statement never becomes `false`. To prevent this situation in a counter-controlled loop, ensure that the control variable is modified during each iteration of the loop so that the loop-continuation condition will eventually become `false`. In a sentinel-controlled loop, ensure that the sentinel value is able to be input.

Placing Arithmetic Expressions in a for Statement's Header

The initialization, loop-continuation condition and increment portions of a for statement can contain arithmetic expressions. For example, assume that $x = 2$ and $y = 10$. If x and y are not modified in the body of the loop, the statement

```
for (int j = x; j <= 4 * x * y; j += y / x)
```

is equivalent to the statement

```
for (int j = 2; j <= 80; j += 5)
```

The increment of a for statement may also be *negative*, in which case it's a **decrement**, and the loop counts *downward*.

Using a for Statement's Control Variable in the Statement's Body

Programs frequently display the control-variable value or use it in calculations in the loop body, but this use is *not* required. The control variable is commonly used to control repetition *without* being mentioned in the body of the for.

**Error-Prevention Tip 4.5**

Although the value of the control variable can be changed in the body of a for loop, avoid doing so, because this practice can lead to subtle errors.

UML Activity Diagram for the for Statement

The for statement's UML activity diagram is similar to that of the while statement (Fig. 3.4). Figure 4.4 shows the activity diagram of the for statement in Fig. 4.2. The diagram makes it clear that initialization occurs *once before* the loop-continuation test is evaluated the first time, and that incrementing occurs *each* time through the loop *after* the body statement executes.




Fig. 4.4 | UML activity diagram for the for statement in Fig. 4.2.

4.4 Examples Using the for Statement

The following examples show techniques for varying the control variable in a for statement. In each case, we write *only* the appropriate for header. Note the change in the relational operator for the loops that *decrement* the control variable.

- a) Vary the control variable from 1 to 100 in increments of 1.

```
for (int i = 1; i <= 100; i++)
```

- b) Vary the control variable from 100 to 1 in *decrements* of 1.

```
for (int i = 100; i >= 1; i--)
```

- c) Vary the control variable from 7 to 77 in increments of 7.

```
for (int i = 7; i <= 77; i += 7)
```

- d) Vary the control variable from 20 to 2 in *decrements* of 2.

```
for (int i = 20; i >= 2; i -= 2)
```

- e) Vary the control variable over the values 2, 5, 8, 11, 14, 17, 20.

```
for (int i = 2; i <= 20; i += 3)
```

- f) Vary the control variable over the values 99, 88, 77, 66, 55, 44, 33, 22, 11, 0.

```
for (int i = 99; i >= 0; i -= 11)
```



Common Programming Error 4.5

Using an incorrect relational operator in the loop-continuation condition of a loop that counts downward (e.g., using `i <= 1` instead of `i >= 1` in a loop counting down to 1) is usually a logic error.



Common Programming Error 4.6

Do not use equality operators (`!=` or `==`) in a loop-continuation condition if the loop's control variable increments or decrements by more than 1. For example, consider the for statement header `for (int counter = 1; counter != 10; counter += 2)`. The loop-continuation test `counter != 10` never becomes false (resulting in an infinite loop) because `counter` increments by 2 after each iteration.

Application: Summing the Even Integers from 2 to 20

We now consider two sample applications that demonstrate simple uses of for. The application in Fig. 4.5 uses a for statement to sum the even integers from 2 to 20 and store the result in an int variable called `total`.

```
1 // Fig. 4.5: Sum.java
2 // Summing integers with the for statement.
3
4 public class Sum
5 {
```

Fig. 4.5 | Summing integers with the for statement. (Part 1 of 2.)


```

6   public static void main(String[] args)
7   {
8       int total = 0;
9
10      // total even integers from 2 through 20
11      for (int number = 2; number <= 20; number += 2)
12          total += number;
13
14      System.out.printf("Sum is %d\n", total);
15  }
16  } // end class Sum

```

```
Sum is 110
```

Fig. 4.5 | Summing integers with the for statement. (Part 2 of 2.)

The *initialization* and *increment* expressions can be comma-separated lists that enable you to use multiple initialization expressions or multiple increment expressions. For example, *although this is discouraged*, you could merge the body of the for statement in lines 11–12 of Fig. 4.5 into the increment portion of the for header by using a comma as follows:

```

for (int number = 2; number <= 20; total += number, number += 2)
    ; // empty statement

```



Good Programming Practice 4.1

For readability limit the size of control-statement headers to a single line if possible.

Application: Compound-Interest Calculations

Let's use the for statement to compute compound interest. Consider the following problem:

A person invests \$1,000 in a savings account yielding 5% interest. Assuming that all the interest is left on deposit, calculate and print the amount of money in the account at the end of each year for 10 years. Use the following formula to determine the amounts:

$$a = p(1 + r)^n$$

where

p is the original amount invested (i.e., the principal)

r is the annual interest rate (e.g., use 0.05 for 5%)

n is the number of years

a is the amount on deposit at the end of the n th year.

The solution to this problem (Fig. 4.6) involves a loop that performs the indicated calculation for each of the 10 years the money remains on deposit. Lines 8–10 in method `main` declare `double` variables `amount`, `principal` and `rate`, and initialize `principal` to 1000.0 and `rate` to 0.05. Java treats floating-point constants like 1000.0 and 0.05 as type `double`. Similarly, Java treats whole-number constants like 7 and -22 as type `int`.

```

1 // Fig. 4.6: Interest.java
2 // Compound-interest calculations with for.
3
4 public class Interest
5 {
6     public static void main(String[] args)
7     {
8         double amount; // amount on deposit at end of each year
9         double principal = 1000.0; // initial amount before interest
10        double rate = 0.05; // interest rate
11
12        // display headers
13        System.out.printf("%s%20s%n", "Year", "Amount on deposit");
14
15        // calculate amount on deposit for each of ten years
16        for (int year = 1; year <= 10; ++year)
17        {
18            // calculate new amount for specified year
19            amount = principal * Math.pow(1.0 + rate, year);
20
21            // display the year and the amount
22            System.out.printf("%4d%,20.2f%n", year, amount);
23        }
24    }
25 } // end class Interest

```

Year	Amount on deposit
1	1,050.00
2	1,102.50
3	1,157.63
4	1,215.51
5	1,276.28
6	1,340.10
7	1,407.10
8	1,477.46
9	1,551.33
10	1,628.89

Fig. 4.6 | Compound-interest calculations with for.

Formatting Strings with Field Widths and Justification

Line 13 outputs the headers for two columns of output. The first column displays the year and the second column the amount on deposit at the end of that year. We use the format specifier `%20s` to output the String "Amount on Deposit". The integer 20 between the `%` and the conversion character `s` indicates that the value should be displayed with a **field width** of 20—that is, `printf` displays the value with at least 20 character positions. If the value to be output is less than 20 character positions wide (17 characters in this example), the value is **right justified** in the field by default. If the year value to be output were more than four character positions wide, the field width would be extended to the right to accommodate the entire value—this would push the amount field to the right, upsetting the neat columns of our tabular output. To output values **left justified**, simply precede the field width with the **minus sign** (`-`) **formatting flag** (e.g., `%-20s`).

*Performing the Interest Calculations with **static Method pow** of Class **Math***

The for statement (lines 16–23) executes its body 10 times, varying control variable `year` from 1 to 10 in increments of 1. This loop terminates when `year` becomes 11. (Variable `year` represents n in the problem statement.)

Classes provide methods that perform common tasks on objects. In fact, most methods must be called on a specific object. For example, to output text in Fig. 4.6, line 13 calls method `printf` on the `System.out` object, and to input `int` values from the user at the keyboard you called method `nextInt` on a `Scanner` object. Some classes also provide methods that perform common tasks and do *not* require objects. These are called **static methods**. For example, Java does *not* include an exponentiation operator, so the designers of Java's `Math` class defined **static method** `pow` for raising a value to a power. You can call a **static method** by specifying the *class name* followed by a dot (`.`) and the method name, as in

```
ClassName.methodName(arguments)
```

In Chapter 5, you'll learn how to implement static methods in your own classes.

We use static method `pow` of class `Math` to perform the compound-interest calculation in Fig. 4.6. `Math.pow(x, y)` calculates the value of x raised to the y^{th} power. The method receives two `double` arguments and returns a `double` value. Line 19 performs the calculation $a = p(1 + r)^n$, where a is amount, p is principal, r is rate and n is year. Class `Math` is defined in package `java.lang`, so you do *not* need to import class `Math` to use it.

The body of the for statement contains the calculation `1.0 + rate`, which appears as an argument to the `Math.pow` method. In fact, this calculation produces the *same* result each time through the loop, so repeating it in every iteration of the loop is wasteful.



Performance Tip 4.1

In loops, avoid calculations for which the result never changes—such calculations should typically be placed before the loop. Many of today's sophisticated optimizing compilers will place such calculations outside loops in the compiled code.

Formatting Floating-Point Numbers

After each calculation, line 22 outputs the year and the amount on deposit at the end of that year. The year is output in a field width of four characters (as specified by `%4d`). The amount is output as a floating-point number with the format specifier `%,20.2f`. The **comma (,) formatting flag** indicates that the floating-point value should be output with a **grouping separator**. The actual separator used is specific to the user's locale (i.e., country). For example, in the United States, the number will be output using commas to separate every three digits and a decimal point to separate the fractional part of the number, as in 1,234.45. The number 20 in the format specification indicates that the value should be output right justified in a *field width* of 20 characters. The `.2` specifies the formatted number's *precision*—in this case, the number is *rounded* to the nearest hundredth and output with two digits to the right of the decimal point.

A Warning about Displaying Rounded Values

We declared variables `amount`, `principal` and `rate` to be of type `double` in this example. We're dealing with fractional parts of dollars and thus need a type that allows decimal points in its values. Unfortunately, floating-point numbers can cause trouble. Here's a simple explanation of what can go wrong when using `double` (or `float`) to represent dollar

amounts (assuming that dollar amounts are displayed with two digits to the right of the decimal point): Two double dollar amounts stored in the machine could be 14.234 (which would normally be rounded to 14.23 for display purposes) and 18.673 (which would normally be rounded to 18.67 for display purposes). When these amounts are added, they produce the internal sum 32.907, which would normally be rounded to 32.91 for display purposes. Thus, your output could appear as

```

14.23
+ 18.67
-----
32.91

```

but a person adding the individual numbers as displayed would expect the sum to be 32.90. You've been warned!



Error-Prevention Tip 4.6

Do not use variables of type double (or float) to perform precise monetary calculations. The imprecision of floating-point numbers can lead to errors. In the exercises, you'll learn how to use integers to perform precise monetary calculations—Java also provides class `java.math.BigDecimal` for this purpose, which we demonstrate in Fig. 8.16.

4.5 do...while Repetition Statement

The **do...while repetition statement** is similar to the while statement. In the while, the program tests the loop-continuation condition at the *beginning* of the loop, *before* executing the loop's body; if the condition is *false*, the body *never* executes. The do...while statement tests the loop-continuation condition *after* executing the loop's body; therefore, *the body always executes at least once*. When a do...while statement terminates, execution continues with the next statement in sequence. Figure 4.7 uses a do...while to output the numbers 1–10.

```

1  // Fig. 4.7: DoWhileTest.java
2  // do...while repetition statement.
3
4  public class DoWhileTest
5  {
6      public static void main(String[] args)
7      {
8          int counter = 1;
9
10         do
11         {
12             System.out.printf("%d ", counter);
13             ++counter;
14         } while (counter <= 10); // end do...while
15
16         System.out.println();
17     }
18 } // end class DoWhileTest

```

Fig. 4.7 | do...while repetition statement. (Part 1 of 2.)


1	2	3	4	5	6	7	8	9	10
---	---	---	---	---	---	---	---	---	----

Fig. 4.7 | do...while repetition statement. (Part 2 of 2.)

Line 8 declares and initializes control variable `counter`. Upon entering the `do...while` statement, line 12 outputs `counter`'s value and line 13 increments `counter`. Then the program evaluates the loop-continuation test at the *bottom* of the loop (line 14). If the condition is *true*, the loop continues at the first body statement (line 12). If the condition is *false*, the loop terminates and the program continues at the next statement after the loop.

UML Activity Diagram for the `do...while` Repetition Statement

Figure 4.8 contains the UML activity diagram for the `do...while` statement. This diagram makes it clear that the loop-continuation condition is not evaluated until *after* the loop performs the action state *at least once*. Compare this activity diagram with that of the `while` statement (Fig. 3.4).

**Fig. 4.8** | do...while repetition statement UML activity diagram.

Braces in a `do...while` Repetition Statement

It isn't necessary to use braces in the `do...while` repetition statement if there's only one statement in the body. However, many programmers include the braces, to avoid confusion between the `while` and `do...while` statements. For example,

```
while (condition)
```

is normally the first line of a `while` statement. A `do...while` statement with no braces around a single-statement body appears as:

```
do
    statement
while (condition);
```

which can be confusing. A reader may misinterpret the last line—`while(condition);`—as a `while` statement containing an empty statement (the semicolon by itself). Thus, the `do...while` statement with one body statement is usually written with braces as follows:

```
do
{
    statement
} while (condition);
```



Good Programming Practice 4.2

Always include braces in a `do...while` statement. This helps eliminate ambiguity between the `while` statement and a `do...while` statement containing only one statement.

4.6 switch Multiple-Selection Statement

Chapter 3 discussed the `if` single-selection statement and the `if...else` double-selection statement. The **switch multiple-selection statement** performs different actions based on the possible values of a **constant integral expression** of type `byte`, `short`, `int` or `char`. As of Java SE 7, the expression may also be a `String`.

Using a `switch` Statement to Count A, B, C, D and F Grades

Figure 4.9 calculates the class average of a set of numeric grades entered by the user, and uses a `switch` statement to determine whether each grade is the equivalent of an A, B, C, D or F and to increment the appropriate grade counter. The program also displays a summary of the number of students who received each grade.

Like earlier versions of the class-average program, the `main` method of class `LetterGrades` (Fig. 4.9) declares local variables `total` (line 9) and `gradeCounter` (line 10) to keep track of the sum of the grades entered by the user and the number of grades entered, respectively. Lines 11–15 declare counter variables for each grade category. Note that the variables in lines 9–15 are explicitly initialized to 0.

Method `main` has two key parts. Lines 26–56 read an arbitrary number of integer grades from the user using sentinel-controlled repetition, update instance variables `total` and `gradeCounter`, and increment an appropriate letter-grade counter for each grade entered. Lines 59–80 output a report containing the total of all grades entered, the average of the grades and the number of students who received each letter grade. Let's examine these parts in more detail.

```
1 // Fig. 4.9: LetterGrades.java
2 // LetterGrades class uses the switch statement to count letter grades.
3 import java.util.Scanner;
4
5 public class LetterGrades
6 {
7     public static void main(String[] args)
8     {
```

Fig. 4.9 | `LetterGrades` class uses the `switch` statement to count letter grades. (Part 1 of 3.)

```

 9      int total = 0; // sum of grades
10      int gradeCounter = 0; // number of grades entered
11      int aCount = 0; // count of A grades
12      int bCount = 0; // count of B grades
13      int cCount = 0; // count of C grades
14      int dCount = 0; // count of D grades
15      int fCount = 0; // count of F grades
16
17      Scanner input = new Scanner(System.in);
18
19      System.out.printf("%s\n%s\n  %s\n  %s\n",
20          "Enter the integer grades in the range 0-100.",
21          "Type the end-of-file indicator to terminate input:",
22          "On UNIX/Linux/Mac OS X type <Ctrl> d then press Enter",
23          "On Windows type <Ctrl> z then press Enter");
24
25      // loop until user enters the end-of-file indicator
26      while (input.hasNext())
27      {
28          int grade = input.nextInt(); // read grade
29          total += grade; // add grade to total
30          ++gradeCounter; // increment number of grades
31
32          // increment appropriate letter-grade counter
33          switch (grade / 10)
34          {
35              case 9: // grade was between 90
36                  case 10: // and 100, inclusive
37                      ++aCount;
38                      break; // exits switch
39
40                  case 8: // grade was between 80 and 89
41                      ++bCount;
42                      break; // exits switch
43
44                  case 7: // grade was between 70 and 79
45                      ++cCount;
46                      break; // exits switch
47
48                  case 6: // grade was between 60 and 69
49                      ++dCount;
50                      break; // exits switch
51
52                  default: // grade was less than 60
53                      ++fCount;
54                      break; // optional; exits switch anyway
55          } // end switch
56      } // end while
57
58      // display grade report
59      System.out.printf("\nGrade Report:\n");
60

```

Fig. 4.9 | LetterGrades class uses the switch statement to count letter grades. (Part 2 of 3.)

```

61      // if user entered at least one grade...
62      if (gradeCounter != 0)
63      {
64          // calculate average of all grades entered
65          double average = (double) total / gradeCounter;
66
67          // output summary of results
68          System.out.printf("Total of the %d grades entered is %d\n",
69                          gradeCounter, total);
70          System.out.printf("Class average is %.2f\n", average);
71          System.out.printf("%n%s%n%s%d%n%s%d%n%s%d%n%s%d%n",
72                          "Number of students who received each grade:",
73                          "A: ", aCount, // display number of A grades
74                          "B: ", bCount, // display number of B grades
75                          "C: ", cCount, // display number of C grades
76                          "D: ", dCount, // display number of D grades
77                          "F: ", fCount); // display number of F grades
78      } // end if
79      else // no grades were entered, so output appropriate message
80          System.out.println("No grades were entered");
81  } // end main
82 } // end class LetterGrades

```

Enter the integer grades in the range 0-100.
 Type the end-of-file indicator to terminate input:
 On UNIX/Linux/Mac OS X type <Ctrl> d then press Enter
 On Windows type <Ctrl> z then press Enter

```

99
92
45
57
63
71
76
85
90
100
^Z

```

Grade Report:
 Total of the 10 grades entered is 778
 Class average is 77.80

Number of students who received each grade:
 A: 4
 B: 1
 C: 2
 D: 1
 F: 2

Fig. 4.9 | LetterGrades class uses the switch statement to count letter grades. (Part 3 of 3.)

Reading Grades from the User

Lines 19–23 prompt the user to enter integer grades and to type the end-of-file indicator to terminate the input. The **end-of-file indicator** is a system-dependent keystroke combi-

nation which the user enters to indicate that there's *no more data to input*. In Chapter 15, Files, Streams and Object Serialization, you'll see how the end-of-file indicator is used when a program reads its input from a file.

On UNIX/Linux/Mac OS X systems, end-of-file is entered by typing the sequence

```
<Ctrl> d
```

on a line by itself. This notation means to simultaneously press both the *Ctrl* key and the *d* key. On Windows systems, end-of-file can be entered by typing

```
<Ctrl> z
```

[*Note:* On some systems, you must press *Enter* after typing the end-of-file key sequence. Also, Windows typically displays the characters ^Z on the screen when the end-of-file indicator is typed, as shown in the output of Fig. 4.9.]



Portability Tip 4.1

The keystroke combinations for entering end-of-file are system dependent.

The `while` statement (lines 26–56) obtains the user input. The condition at line 26 calls `Scanner` method `hasNext` to determine whether there's more data to input. This method returns the `boolean` value `true` if there's more data; otherwise, it returns `false`. The returned value is then used as the value of the condition in the `while` statement. Method `hasNext` returns `false` once the user types the end-of-file indicator.

Line 28 inputs a grade value from the user. Line 29 adds grade to `total`. Line 30 increments `gradeCounter`. These variables are used to compute the average of the grades. Lines 33–55 use a `switch` statement to increment the appropriate letter-grade counter based on the numeric grade entered.

Processing the Grades

The `switch` statement (lines 33–55) determines which counter to increment. We assume that the user enters a valid grade in the range 0–100. A grade in the range 90–100 represents A, 80–89 represents B, 70–79 represents C, 60–69 represents D and 0–59 represents F. The `switch` statement consists of a block that contains a sequence of **case labels** and an optional **default case**. These are used in this example to determine which counter to increment based on the grade.

When the flow of control reaches the `switch`, the program evaluates the expression in the parentheses (`grade / 10`) following keyword `switch`. This is the `switch`'s **controlling expression**. The program compares this expression's value (which must evaluate to an integral value of type `byte`, `char`, `short` or `int`, or to a `String`) with each case label. The controlling expression in line 33 performs integer division, which *truncates the fractional part* of the result. Thus, when we divide a value from 0 to 100 by 10, the result is always a value from 0 to 10. We use several of these values in our case labels. For example, if the user enters the integer 85, the controlling expression evaluates to 8. The `switch` compares 8 with each case label. If a match occurs (case 8: at line 40), the program executes that case's statements. For the integer 8, line 41 increments `bCount`, because a grade in the 80s is a B. The **break statement** (line 42) causes program control to proceed with the first statement after the `switch`—in this program, we reach the end of the `while` loop, so con-

control returns to the loop-continuation condition in line 26 to determine whether the loop should continue executing.

The cases in our `switch` explicitly test for the values 10, 9, 8, 7 and 6. Note the cases at lines 35–36 that test for the values 9 and 10 (both of which represent the grade A). Listing cases consecutively in this manner with no statements between them enables the cases to perform the same set of statements—when the controlling expression evaluates to 9 or 10, the statements in lines 37–38 will execute. The `switch` statement does *not* provide a mechanism for testing *ranges* of values, so *every* value you need to test must be listed in a separate case label. Each case can have multiple statements. The `switch` statement differs from other control statements in that it does *not* require braces around multiple statements in a case.

case without a break Statement

Without `break` statements, each time a match occurs in the `switch`, the statements for that case and subsequent cases execute until a `break` statement or the end of the `switch` is encountered. This is often referred to as “falling through” to the statements in subsequent cases. (This feature is perfect for writing a concise program that displays the iterative song “The Twelve Days of Christmas” in Exercise 4.29.)



Common Programming Error 4.7

Forgetting a break statement when one is needed in a switch is a logic error.

The default Case

If no match occurs between the controlling expression’s value and a case label, the `default` case (lines 52–54) executes. We use the `default` case in this example to process all controlling-expression values that are less than 6—that is, all failing grades. If no match occurs and the `switch` does not contain a `default` case, program control simply continues with the first statement after the `switch`.



Error-Prevention Tip 4.7

In a switch statement, ensure that you test for all possible values of the controlling expression.

Displaying the Grade Report

Lines 59–80 output a report based on the grades entered (as shown in the input/output window in Fig. 4.9). Line 62 determines whether the user entered at least one grade—this helps us avoid dividing by zero. If so, line 65 calculates the average of the grades. Lines 68–77 then output the total of all the grades, the class average and the number of students who received each letter grade. If no grades were entered, line 80 outputs an appropriate message. The output in Fig. 4.9 shows a sample grade report based on 10 grades.

switch Statement UML Activity Diagram

Figure 4.10 shows the UML activity diagram for the general `switch` statement. Most `switch` statements use a `break` in each case to terminate the `switch` statement after processing the case. Figure 4.10 emphasizes this by including `break` statements in the activity diagram. The diagram makes it clear that the `break` statement at the end of a case causes control to exit the `switch` statement immediately.




Fig. 4.10 | switch multiple-selection statement UML activity diagram with break statements.

The break statement is *not* required for the switch's last case (or the optional default case, when it appears last), because execution continues with the next statement after the switch.



Error-Prevention Tip 4.8

Provide a default case in switch statements. This focuses you on the need to process exceptional conditions.



Good Programming Practice 4.3

Although each case and the default case in a switch can occur in any order, place the default case last. When the default case is listed last, the break for that case is not required.

Notes on the Expression in Each case of a switch

When using the switch statement, remember that each case must contain a **String** or a constant integral expression—that is, any combination of integer constants that evaluates to a constant integer value (e.g., `-7`, `0` or `221`). An integer constant is simply an integer value. In addition, you can use **character constants**—specific characters in single quotes, such as `'A'`, `'7'` or `'$'`—which represent the integer values of characters and enum constants (introduced in Section 5.10). (Appendix B shows the integer values of the characters in the ASCII character set, which is a subset of the Unicode[®] character set used by Java.)

The expression in each case can also be a **constant variable**—a variable containing a value which does not change for the entire program. Such a variable is declared with keyword `final` (discussed in Chapter 5). Java has a feature called enum types, which we also present in Chapter 5—enum type constants can also be used in case labels.

In Chapter 10, Object-Oriented Programming: Polymorphism and Interfaces, we present a more elegant way to implement switch logic—we use a technique called *polymorphism* to create programs that are often clearer, easier to maintain and easier to extend than programs using switch logic.

4.7 break and continue Statements

In addition to selection and repetition statements, Java provides statements **break** (which we discussed in the context of the **switch** statement) and **continue** (presented in this section and online Appendix L) to alter the flow of control. The preceding section showed how **break** can be used to terminate a **switch** statement's execution. This section discusses how to use **break** in repetition statements.

break Statement

The **break** statement, when executed in a **while**, **for**, **do...while** or **switch**, causes *immediate* exit from that statement. Execution continues with the first statement after the control statement. Common uses of the **break** statement are to escape early from a loop or to skip the remainder of a **switch** (as in Fig. 4.9). Figure 4.11 demonstrates a **break** statement exiting a **for**.

```

1 // Fig. 4.11: BreakTest.java
2 // break statement exiting a for statement.
3 public class BreakTest
4 {
5     public static void main(String[] args)
6     {
7         int count; // control variable also used after loop terminates
8
9         for (count = 1; count <= 10; count++) // loop 10 times
10        {
11            if (count == 5)
12                break; // terminates loop if count is 5
13
14            System.out.printf("%d ", count);
15        }
16
17        System.out.printf("\nBroke out of loop at count = %d\n", count);
18    }
19 } // end class BreakTest

```

```

1 2 3 4
Broke out of loop at count = 5

```

Fig. 4.11 | **break** statement exiting a **for** statement.

When the **if** statement nested at lines 11–12 in the **for** statement (lines 9–15) detects that **count** is 5, the **break** statement at line 12 executes. This terminates the **for** statement, and the program proceeds to line 17 (immediately after the **for** statement), which displays a message indicating the value of the control variable when the loop terminated. The loop fully executes its body only four times instead of 10.

continue Statement

The continue statement, when executed in a while, for or do...while, skips the remaining statements in the loop body and proceeds with the *next iteration* of the loop. In while and do...while statements, the program evaluates the loop-continuation test immediately after the continue statement executes. In a for statement, the increment expression executes, then the program evaluates the loop-continuation test.

```

1 // Fig. 4.12: ContinueTest.java
2 // continue statement terminating an iteration of a for statement.
3 public class ContinueTest
4 {
5     public static void main(String[] args)
6     {
7         for (int count = 1; count <= 10; count++) // loop 10 times
8         {
9             if (count == 5)
10                continue; // skip remaining code in loop body if count is 5
11
12             System.out.printf("%d ", count);
13         }
14
15         System.out.printf("\nUsed continue to skip printing 5\n");
16     }
17 } // end class ContinueTest

```

```

1 2 3 4 6 7 8 9 10
Used continue to skip printing 5

```

Fig. 4.12 | continue statement terminating an iteration of a for statement.

Figure 4.12 uses continue (line 10) to skip the statement at line 12 when the nested if determines that count's value is 5. When the continue statement executes, program control continues with the increment of the control variable in the for statement (line 7).

In Section 4.3, we stated that while could be used in most cases in place of for. This is *not* true when the increment expression in the while follows a continue statement. In this case, the increment does *not* execute before the program evaluates the repetition-continuation condition, so the while does not execute in the same manner as the for.



Software Engineering Observation 4.2

Some programmers feel that break and continue violate structured programming. Since the same effects are achievable with structured programming techniques, these programmers do not use break or continue.



Software Engineering Observation 4.3

There's a tension between achieving quality software engineering and achieving the best-performing software. Sometimes one of these goals is achieved at the expense of the other. For all but the most performance-intensive situations, apply the following rule of thumb: First, make your code simple and correct; then make it fast and small, but only if necessary.

4.8 Logical Operators

The `if`, `if...else`, `while`, `do...while` and `for` statements each require a *condition* to determine how to continue a program's flow of control. So far, we've studied only simple conditions, such as `count <= 10`, `number != sentinelValue` and `total > 1000`. Simple conditions are expressed in terms of the relational operators `>`, `<`, `>=` and `<=` and the equality operators `==` and `!=`, and each expression tests only one condition. To test *multiple* conditions in the process of making a decision, we performed these tests in separate statements or in nested `if` or `if...else` statements. Sometimes control statements require more complex conditions to determine a program's flow of control.

Java's **logical operators** enable you to form more complex conditions by *combining* simple conditions. The logical operators are `&&` (conditional AND), `||` (conditional OR), `&` (boolean logical AND), `|` (boolean logical inclusive OR), `^` (boolean logical exclusive OR) and `!` (logical NOT). [Note: The `&`, `|` and `^` operators are also bitwise operators when they're applied to integral operands. We discuss the bitwise operators in online Appendix K.]

Conditional AND (&&) Operator

Suppose we wish to ensure at some point in a program that two conditions are *both* true before we choose a certain path of execution. In this case, we can use the `&&` (conditional AND) operator, as follows:

```
if (gender == FEMALE && age >= 65)
    ++seniorFemales;
```

This `if` statement contains two simple conditions. The condition `gender == FEMALE` compares variable `gender` to the constant `FEMALE` to determine whether a person is female. The condition `age >= 65` might be evaluated to determine whether a person is a senior citizen. The `if` statement considers the combined condition

```
gender == FEMALE && age >= 65
```

which is true if and only if *both* simple conditions are true. In this case, the `if` statement's body increments `seniorFemales` by 1. If either or both of the simple conditions are false, the program skips the increment. Some programmers find that the preceding combined condition is more readable when *redundant* parentheses are added, as in:

```
(gender == FEMALE) && (age >= 65)
```

The table in Fig. 4.13 summarizes the `&&` operator. The table shows all four possible combinations of false and true values for *expression1* and *expression2*. Such tables are called **truth tables**. Java evaluates to false or true all expressions that include relational operators, equality operators or logical operators.

expression1	expression2	expression1 && expression2
false	false	false
false	true	false
true	false	false
true	true	true

Fig. 4.13 | `&&` (conditional AND) operator truth table.

Conditional OR (||) Operator

Now suppose we wish to ensure that *either or both* of two conditions are true before we choose a certain path of execution. In this case, we use the || (conditional OR) operator, as in the following program segment:

```
if ((semesterAverage >= 90) || (finalExam >= 90))
    System.out.println ("Student grade is A");
```

The preceding statement also contains two simple conditions. The condition `semesterAverage >= 90` evaluates to determine whether the student deserves an A in the course because of a solid performance throughout the semester. The condition `finalExam >= 90` evaluates to determine whether the student deserves an A in the course because of an outstanding performance on the final exam. The `if` statement then considers the combined condition

```
(semesterAverage >= 90) || (finalExam >= 90)
```

and awards the student an A if *either or both* of the simple conditions are true. The only time the message "Student grade is A" is *not* printed is when *both* of the simple conditions are *false*. Figure 4.14 shows the truth table for operator conditional OR (||). Operator `&&` has a higher precedence than operator `||`. Both operators associate from left to right.

expression1	expression2	expression1 expression2
false	false	false
false	true	true
true	false	true
true	true	true

Fig. 4.14 | || (conditional OR) operator truth table.

Short-Circuit Evaluation of Complex Conditions

The parts of an expression containing `&&` or `||` operators are evaluated *only* until it's known whether the condition is true or false. Thus, evaluation of the expression

```
(gender == FEMALE) && (age >= 65)
```

stops immediately if `gender` is *not* equal to `FEMALE` (i.e., the entire expression is `false`) and continues if `gender` is equal to `FEMALE` (i.e., the entire expression could still be true if the condition `age >= 65` is true). This feature of conditional AND and conditional OR expressions is called **short-circuit evaluation**.



Common Programming Error 4.8

In expressions using operator `&&`, a condition—we'll call this the dependent condition—may require another condition to be true for the evaluation of the dependent condition to be meaningful. In this case, the dependent condition should be placed after the `&&` operator to prevent errors. Consider the expression `(i != 0) && (10 / i == 2)`. The dependent condition `(10 / i == 2)` must appear after the `&&` operator to prevent the possibility of division by zero.

Boolean Logical AND (&) and Boolean Logical Inclusive OR (|) Operators

The **boolean logical AND (&)** and **boolean logical inclusive OR (|)** operators are identical to the **&&** and **||** operators, except that the **&** and **|** operators *always* evaluate *both* of their operands (i.e., they do *not* perform short-circuit evaluation). So, the expression

```
(gender == 1) & (age >= 65)
```

evaluates `age >= 65` *regardless* of whether `gender` is equal to 1. This is useful if the right operand has a required **side effect**—a modification of a variable’s value. For example, the expression

```
(birthday == true) | (++age >= 65)
```

guarantees that the condition `++age >= 65` will be evaluated. Thus, the variable `age` is incremented, regardless of whether the overall expression is `true` or `false`.

**Error-Prevention Tip 4.9**

For clarity, avoid expressions with side effects (such as assignments) in conditions. They can make code harder to understand and can lead to subtle logic errors.

**Error-Prevention Tip 4.10**

Assignment (=) expressions generally should not be used in conditions. Every condition must result in a boolean value; otherwise, a compilation error occurs. In a condition, an assignment will compile only if a boolean expression is assigned to a boolean variable.

Boolean Logical Exclusive OR (^) Operator

A simple condition containing the **boolean logical exclusive OR (^)** operator is *true if and only if one of its operands is true and the other is false*. If both are `true` or both are `false`, the entire condition is `false`. Figure 4.15 is a truth table for the boolean logical exclusive OR operator (^). This operator is guaranteed to evaluate *both* of its operands.

expression1	expression2	expression1 ^ expression2
false	false	false
false	true	true
true	false	true
true	true	false

Fig. 4.15 | ^ (boolean logical exclusive OR) operator truth table.

Logical Negation (!) Operator

The **!** (**logical NOT**, also called **logical negation** or **logical complement**) operator “reverses” the meaning of a condition. Unlike the logical operators **&&**, **||**, **&**, **|** and **^**, which are *binary* operators that combine two conditions, the logical negation operator is a *unary* operator that has only one condition as an operand. The operator is placed *before* a condition to choose a path of execution if the original condition (without the logical negation operator) is `false`, as in the program segment

```
if (! (grade == sentinelValue))
    System.out.printf("The next grade is %d\n", grade);
```


which executes the `printf` call only if `grade` is *not* equal to `sentinelValue`. The parentheses around the condition `grade == sentinelValue` are needed because the logical negation operator has a *higher* precedence than the equality operator.

In most cases, you can avoid using logical negation by expressing the condition differently with an appropriate relational or equality operator. For example, the previous statement may also be written as follows:

```
if (grade != sentinelValue)
    System.out.printf("The next grade is %d%n", grade);
```

This flexibility can help you express a condition in a more convenient manner. Figure 4.16 is a truth table for the logical negation operator.

expression	!expression
false	true
true	false

Fig. 4.16 | ! (logical NOT) operator truth table.

Logical Operators Example

Figure 4.17 uses logical operators to produce the truth tables discussed in this section. The output shows the `boolean` expression that was evaluated and its result. We used the **%b** format specifier to display the word “true” or the word “false” based on a `boolean` expression’s value. Lines 9–13 produce the truth table for `&&`. Lines 16–20 produce the truth table for `||`. Lines 23–27 produce the truth table for `&`. Lines 30–35 produce the truth table for `|`. Lines 38–43 produce the truth table for `^`. Lines 46–47 produce the truth table for `!`.

```
1 // Fig. 4.17: LogicalOperators.java
2 // Logical operators.
3
4 public class LogicalOperators
5 {
6     public static void main(String[] args)
7     {
8         // create truth table for && (conditional AND) operator
9         System.out.printf("%s%n%s: %b%n%s: %b%n%s: %b%n%s: %b%n%n",
10             "Conditional AND (&&)", "false && false", (false && false) ,
11             "false && true", (false && true) ,
12             "true && false", (true && false) ,
13             "true && true", (true && true) );
14
15         // create truth table for || (conditional OR) operator
16         System.out.printf("%s%n%s: %b%n%s: %b%n%s: %b%n%s: %b%n%n",
17             "Conditional OR (||)", "false || false", (false || false) ,
18             "false || true", (false || true) ,
19             "true || false", (true || false) ,
20             "true || true", (true || true) );
```

Fig. 4.17 | Logical operators. (Part I of 3.)

```

21
22 // create truth table for & (boolean logical AND) operator
23 System.out.printf("%s\n%s: %b\n%s: %b\n%s: %b\n%s: %b\n\n",
24 "Boolean logical AND (&)", "false & false", (false & false) ,
25 "false & true", (false & true) ,
26 "true & false", (true & false) ,
27 "true & true", (true & true) );
28
29 // create truth table for | (boolean logical inclusive OR) operator
30 System.out.printf("%s\n%s: %b\n%s: %b\n%s: %b\n%s: %b\n\n",
31 "Boolean logical inclusive OR (|)",
32 "false | false", (false | false) ,
33 "false | true", (false | true) ,
34 "true | false", (true | false) ,
35 "true | true", (true | true) );
36
37 // create truth table for ^ (boolean logical exclusive OR) operator
38 System.out.printf("%s\n%s: %b\n%s: %b\n%s: %b\n%s: %b\n\n",
39 "Boolean logical exclusive OR (^)",
40 "false ^ false", (false ^ false) ,
41 "false ^ true", (false ^ true) ,
42 "true ^ false", (true ^ false) ,
43 "true ^ true", (true ^ true) );
44
45 // create truth table for ! (logical negation) operator
46 System.out.printf("%s\n%s: %b\n%s: %b\n", "Logical NOT (!)",
47 "!false", (!false) , "!true", (!true) );
48 }
49 } // end class LogicalOperators

```

```

Conditional AND (&&)
false && false: false
false && true: false
true && false: false
true && true: true

Conditional OR (||)
false || false: false
false || true: true
true || false: true
true || true: true

Boolean logical AND (&)
false & false: false
false & true: false
true & false: false
true & true: true

Boolean logical inclusive OR (|)
false | false: false
false | true: true
true | false: true
true | true: true

```

Fig. 4.17 | Logical operators. (Part 2 of 3.)

```

Boolean logical exclusive OR (^)
false ^ false: false
false ^ true: true
true ^ false: true
true ^ true: false

Logical NOT (!)
!false: true
!true: false

```

Fig. 4.17 | Logical operators. (Part 3 of 3.)

Precedence and Associativity of the Operators Presented So Far

Figure 4.18 shows the precedence and associativity of the Java operators introduced so far. The operators are shown from top to bottom in decreasing order of precedence.

Operators	Associativity	Type
++ --	right to left	unary postfix
++ -- + - ! (type)	right to left	unary prefix
* / %	left to right	multiplicative
+ -	left to right	additive
< <= > >=	left to right	relational
== !=	left to right	equality
&	left to right	boolean logical AND
^	left to right	boolean logical exclusive OR
	left to right	boolean logical inclusive OR
&&	left to right	conditional AND
	left to right	conditional OR
?:	right to left	conditional
= += -= *= /= %=	right to left	assignment

Fig. 4.18 | Precedence/associativity of the operators discussed so far.

4.9 Structured Programming Summary

Just as architects design buildings by employing the collective wisdom of their profession, so should programmers design programs. Our field is much younger than architecture, and our collective wisdom is considerably sparser. We've learned that structured programming produces programs that are easier than unstructured programs to understand, test, debug, modify and even prove correct in a mathematical sense.

Java Control Statements Are Single-Entry/Single-Exit

Figure 4.19 uses UML activity diagrams to summarize Java's control statements. The initial and final states indicate the *single entry point* and the *single exit point* of each control




Fig. 4.19 | Java's single-entry/single-exit sequence, selection and repetition statements.

statement. Arbitrarily connecting individual symbols in an activity diagram can lead to unstructured programs. Therefore, the programming profession has chosen a limited set of control statements that can be combined in only two simple ways to build structured programs.

For simplicity, Java includes only *single-entry/single-exit* control statements—there’s only one way to enter and only one way to exit each control statement. Connecting control statements in sequence to form structured programs is simple. The final state of one control statement is connected to the initial state of the next—that is, the control statements are placed one after another in a program in sequence. We call this *control-statement stacking*. The rules for forming structured programs also allow for control statements to be *nested*.

Rules for Forming Structured Programs

Figure 4.20 shows the rules for forming structured programs. The rules assume that action states may be used to indicate *any* action. The rules also assume that we begin with the simplest activity diagram (Fig. 4.21) consisting of only an initial state, an action state, a final state and transition arrows.

Rules for forming structured programs

1. Begin with the simplest activity diagram (Fig. 4.21).
2. Any action state can be replaced by two action states in sequence.
3. Any action state can be replaced by any control statement (sequence of action states, if, if...else, switch, while, do...while or for).
4. Rules 2 and 3 can be applied as often as you like and in any order.

Fig. 4.20 | Rules for forming structured programs.




Fig. 4.21 | Simplest activity diagram.

Applying the rules in Fig. 4.20 always results in a properly structured activity diagram with a neat, building-block appearance. For example, repeatedly applying rule 2 to the simplest activity diagram results in an activity diagram containing many action states in sequence (Fig. 4.22). Rule 2 generates a *stack* of control statements, so let’s call rule 2 the **stacking rule**. The vertical dashed lines in Fig. 4.22 are not part of the UML—we use them to separate the four activity diagrams that demonstrate rule 2 of Fig. 4.20 being applied.




Fig. 4.22 | Repeatedly applying rule 2 of Fig. 4.20 to the simplest activity diagram.

Rule 3 is called the **nesting rule**. Repeatedly applying rule 3 to the simplest activity diagram results in one with nearly *nested* control statements. For example, in Fig. 4.23, the action state in the simplest activity diagram is replaced with a double-selection (`if...else`) statement. Then rule 3 is applied again to the action states in the double-selection statement, replacing each with a double-selection statement. The dashed action-state symbol around each double-selection statement represents the action state that was replaced. [Note: The dashed arrows and dashed action-state symbols shown in Fig. 4.23 are not part of the UML. They're used here to illustrate that *any* action state can be replaced with a control statement.]

Rule 4 generates larger, more involved and more deeply nested statements. The diagrams that emerge from applying the rules in Fig. 4.20 constitute the set of all possible structured activity diagrams and hence the set of all possible structured programs. The beauty of the structured approach is that we use *only seven* simple single-entry/single-exit control statements and assemble them in *only two* simple ways.

If the rules in Fig. 4.20 are followed, an “unstructured” activity diagram (like the one in Fig. 4.24) cannot be created. If you're uncertain about whether a particular diagram is structured, apply the rules of Fig. 4.20 in reverse to reduce it to the simplest activity diagram. If you can reduce it, the original diagram is structured; otherwise, it's not.

Three Forms of Control

Structured programming promotes simplicity. Only three forms of control are needed to implement an algorithm:

- sequence
- selection
- repetition

The sequence structure is trivial. Simply list the statements to execute in the order in which they should execute. Selection is implemented in one of three ways:




Fig. 4.23 | Repeatedly applying rule 3 of Fig. 4.20 to the simplest activity diagram.




Fig. 4.24 | "Unstructured" activity diagram.

- `if` statement (single selection)
- `if...else` statement (double selection)
- `switch` statement (multiple selection)

In fact, it's straightforward to prove that the simple `if` statement is sufficient to provide *any* form of selection—everything that can be done with the `if...else` statement and the `switch` statement can be implemented by combining `if` statements (although perhaps not as clearly and efficiently).

Repetition is implemented in one of three ways:

- `while` statement
- `do...while` statement
- `for` statement

[*Note:* There's a fourth repetition statement—the *enhanced for statement*—that we discuss in Section 6.6.] It's straightforward to prove that the `while` statement is sufficient to provide *any* form of repetition. Everything that can be done with `do...while` and `for` can be done with the `while` statement (although perhaps not as conveniently).

Combining these results illustrates that *any* form of control ever needed in a Java program can be expressed in terms of

- sequence
- `if` statement (selection)
- `while` statement (repetition)

and that these can be combined in only two ways—*stacking* and *nesting*. Indeed, structured programming is the essence of simplicity.

4.10 (Optional) GUI and Graphics Case Study: Drawing Rectangles and Ovals

Our next program (Fig. 4.25) demonstrates drawing rectangles and ovals, using the Graphics methods `drawRect` and `drawOval`, respectively. Method `paintComponent` (lines 10–21) performs the actual drawing. Remember, the first statement in every `paintComponent` method must be a call to `super.paintComponent`, as in line 12. Lines 14–20 loop 10 times to draw 10 rectangles and 10 ovals.

```

1 // Fig. 4.25: Shapes.java
2 // Drawing a cascade of shapes based on the user's choice.
3 import java.awt.Graphics;
4 import javax.swing.JPanel;
5 import javax.swing.JFrame;
6
7 public class Shapes extends JPanel
8 {

```

Fig. 4.25 | Drawing a cascade of shapes based on the user's choice. (Part 1 of 2.)


```

 9      // draws a cascade of shapes starting from the top-left corner
10      public void paintComponent(Graphics g)
11      {
12          super.paintComponent(g);
13
14          for (int i = 0; i < 10; i++)
15          {
16              g.drawRect(10 + i * 10, 10 + i * 10,
17                        50 + i * 10, 50 + i * 10);
18              g.drawOval(240 + i * 10, 10 + i * 10,
19                       50 + i * 10, 50 + i * 10);
20          }
21      }
22
23      public static void main( String[] args )
24      {
25          Shapes panel = new Shapes(); // create the panel
26          JFrame application = new JFrame(); // creates a new JFrame
27
28          application.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
29          application.add(panel);
30          application.setSize(500, 290);
31          application.setVisible(true);
32      }
33  } // end class Shapes

```




Fig. 4.25 | Drawing a cascade of shapes based on the user's choice. (Part 2 of 2.)

Lines 16–17 call Graphics method `drawRect`, which requires four arguments. The first two represent the *x*- and *y*-coordinates of the upper-left corner of the rectangle; the next two represent the rectangle's width and height. In this example, we start at a position 10 pixels down and 10 pixels right of the top-left corner, and every iteration of the loop moves the upper-left corner another 10 pixels down and to the right. The width and the height of the rectangle start at 50 pixels and increase by 10 pixels in each iteration.

Lines 18–19 in the loop draw ovals. Method `drawOval` creates an imaginary rectangle called a **bounding rectangle** and places inside it an oval that touches the midpoints of all four sides. The method's four arguments represent the *x*- and *y*-coordinates of the upper-

left corner of the bounding rectangle and the bounding rectangle's width and height. The values passed to `drawOval` in this example are exactly the same as those passed to `drawRect` in lines 16–17, except that the first oval's bounding box has an *x*-coordinate that starts 240 pixels from the left side of the panel. Since the width and height of the bounding rectangle are identical in this example, lines 18–19 draw a circle. As an exercise, modify the program to draw both rectangles and ovals with the same arguments. This will allow you to see how each oval touches all four sides of the corresponding rectangle.

Line 25 in `main` creates a `Shapes` object. Lines 26–31 perform the standard operations that create and set up a window in this case study—create a frame, set it to exit the application when closed, add the drawing to the frame, set the frame size and make it visible.

GUI and Graphics Case Study Exercise

4.1 Draw 12 concentric circles in the center of a `JPanel` (Fig. 4.26). The innermost circle should have a radius of 10 pixels, and each successive circle should have a radius 10 pixels larger than the previous one. Begin by finding the center of the `JPanel`. To get the upper-left corner of a circle, move up one radius and to the left one radius from the center. The width and height of the bounding rectangle are both the same as the circle's diameter (i.e., twice the radius).




Fig. 4.26 | Drawing concentric circles.

4.11 Wrap-Up

In this chapter, we completed our introduction to control statements, which enable you to control the flow of execution in methods. Chapter 3 discussed `if`, `if...else` and `while`. This chapter demonstrated `for`, `do...while` and `switch`. We showed that any algorithm can be developed using combinations of the sequence structure, the three types of selection statements—`if`, `if...else` and `switch`—and the three types of repetition statements—`while`, `do...while` and `for`. In this chapter and Chapter 3, we discussed how you can combine these building blocks to utilize proven program-construction and problem-solving techniques. You used the `break` statement to exit a `switch` statement and to immediately terminate a loop, and used a `continue` statement to terminate a loop's current iteration and proceed with the loop's next iteration. This chapter also introduced Java's logical operators, which enable you to use more complex conditional expressions in control statements. In Chapter 5, we examine methods.

Summary

Section 4.2 Essentials of Counter-Controlled Repetition

- Counter-controlled repetition (p. 122) requires a control variable, the initial value of the control variable, the increment by which the control variable is modified each time through the loop (also known as each iteration of the loop) and the loop-continuation condition that determines whether looping should continue.
- You can declare a variable and initialize it in the same statement.

Section 4.3 for Repetition Statement

- The `while` statement can be used to implement any counter-controlled loop.
- The `for` statement (p. 124) specifies all the details of counter-controlled repetition in its header.
- When the `for` statement begins executing, its control variable is declared and initialized. If the loop-continuation condition is initially true, the body executes. After executing the loop's body, the increment expression executes. Then the loop-continuation test is performed again to determine whether the program should continue with the next iteration of the loop.
- The general format of the `for` statement is

```
for (initialization; loopContinuationCondition; increment)
    statement
```

where the *initialization* expression names the loop's control variable and provides its initial value, *loopContinuationCondition* determines whether the loop should continue executing and *increment* modifies the control variable's value, so that the loop-continuation condition eventually becomes false. The two semicolons in the `for` header are required.

- Most `for` statements can be represented with equivalent `while` statements as follows:

```
initialization;
while (loopContinuationCondition)
{
    statement
    increment;
}
```

- Typically, `for` statements are used for counter-controlled repetition and `while` statements for sentinel-controlled repetition.
- If the *initialization* expression in the `for` header declares the control variable, the control variable can be used only in that `for` statement—it will not exist outside the `for` statement.
- The expressions in a `for` header are optional. If the *loopContinuationCondition* is omitted, Java assumes that it's always true, thus creating an infinite loop. You might omit the *initialization* expression if the control variable is initialized before the loop. You might omit the *increment* expression if the increment is calculated with statements in the loop's body or if no increment is needed.
- The increment expression in a `for` acts as if it's a standalone statement at the end of the `for`'s body.
- A `for` statement can count downward by using a negative increment—i.e., a decrement (p. 127).
- If the loop-continuation condition is initially `false`, the `for` statement's body does not execute.

Section 4.4 Examples Using the for Statement

- Java treats floating-point constants like `1000.0` and `0.05` as type `double`. Similarly, Java treats whole-number constants like `7` and `-22` as type `int`.
- The format specifier `%4s` outputs a `String` in a field width (p. 130) of 4—that is, `printf` displays the value with at least 4 character positions. If the value to be output is less than 4 character po-

sitions wide, the value is right justified (p. 130) in the field by default. If the value is greater than 4 character positions wide, the field width expands to accommodate the appropriate number of characters. To left justify (p. 130) the value, use a negative integer to specify the field width.

- `Math.pow(x, y)` (p. 131) calculates the value of x raised to the y th power. The method receives two `double` arguments and returns a `double` value.
- The comma (,) formatting flag (p. 131) in a format specifier indicates that a floating-point value should be output with a grouping separator (p. 131). The actual separator used is specific to the user's locale (i.e., country). In the United States, the number will have commas separating every three digits and a decimal point separating the fractional part of the number, as in 1,234.45.
- The . in a format specifier indicates that the integer to its right is the number's precision.

Section 4.5 *do...while Repetition Statement*

- The `do...while` statement (p. 132) is similar to the `while` statement. In the `while`, the program tests the loop-continuation condition at the beginning of the loop, before executing its body; if the condition is false, the body never executes. The `do...while` statement tests the loop-continuation condition *after* executing the loop's body; therefore, the body always executes at least once.

Section 4.6 *switch Multiple-Selection Statement*

- The `switch` statement (p. 134) performs different actions based on the possible values of a constant integral expression (a constant value of type `byte`, `short`, `int` or `char`, but not `long`), or a `String`.
- The end-of-file indicator is a system-dependent keystroke combination that terminates user input. On UNIX/Linux/Mac OS X systems, end-of-file is entered by typing the sequence `<Ctrl>d` on a line by itself. This notation means to simultaneously press both the `Ctrl` key and the `d` key. On Windows systems, enter end-of-file by typing `<Ctrl>z`.
- `Scanner` method `hasNext` (p. 137) determines whether there's more data to input. This method returns the `boolean` value `true` if there's more data; otherwise, it returns `false`. As long as the end-of-file indicator has not been typed, method `hasNext` will return `true`.
- The `switch` statement consists of a block that contains a sequence of case labels (p. 137) and an optional default case (p. 137).
- In a `switch`, the program evaluates the controlling expression and compares its value with each case label. If a match occurs, the program executes the statements for that case.
- Listing cases consecutively with no statements between them enables the cases to perform the same set of statements.
- Every value you wish to test in a `switch` must be listed in a separate case label.
- Each case can have multiple statements, and these need not be placed in braces.
- A case's statements typically end with a `break` statement (p. 137) that terminates the `switch`'s execution.
- Without `break` statements, each time a match occurs in the `switch`, the statements for that case and subsequent cases execute until a `break` statement or the end of the `switch` is encountered.
- If no match occurs between the controlling expression's value and a case label, the optional default case executes. If no match occurs and the `switch` does not contain a default case, program control simply continues with the first statement after the `switch`.

Section 4.7 *break and continue Statements*

- The `break` statement, when executed in a `while`, `for`, `do...while` or `switch`, causes immediate exit from that statement.

- The `continue` statement (p. 140), when executed in a `while`, `for` or `do...while`, skips the loop's remaining body statements and proceeds with its next iteration. In `while` and `do...while` statements, the program evaluates the loop-continuation test immediately. In a `for` statement, the increment expression executes, then the program evaluates the loop-continuation test.

Section 4.8 Logical Operators

- Simple conditions are expressed in terms of the relational operators `>`, `<`, `>=` and `<=` and the equality operators `==` and `!=`, and each expression tests only one condition.
- Logical operators (p. 142) enable you to form more complex conditions by combining simple conditions. The logical operators are `&&` (conditional AND), `||` (conditional OR), `&` (boolean logical AND), `|` (boolean logical inclusive OR), `^` (boolean logical exclusive OR) and `!` (logical NOT).
- To ensure that two conditions are *both* true, use the `&&` (conditional AND) operator. If either or both of the simple conditions are false, the entire expression is false.
- To ensure that either *or* both of two conditions are true, use the `||` (conditional OR) operator, which evaluates to true if either or both of its simple conditions are true.
- A condition using `&&` or `||` operators (p. 142) uses short-circuit evaluation (p. 143)—they're evaluated only until it's known whether the condition is true or false.
- The `&` and `|` operators (p. 144) work identically to the `&&` and `||` operators but always evaluate both operands.
- A simple condition containing the boolean logical exclusive OR (`^`; p. 144) operator is true *if and only if one of its operands is true and the other is false*. If both operands are true or both are false, the entire condition is false. This operator is also guaranteed to evaluate both of its operands.
- The unary `!` (logical NOT; p. 144) operator “reverses” the value of a condition.

Self-Review Exercises

- 4.1** Fill in the blanks in each of the following statements:
- Typically, _____ statements are used for counter-controlled repetition and _____ statements for sentinel-controlled repetition.
 - The `do...while` statement tests the loop-continuation condition _____ executing the loop's body; therefore, the body always executes at least once.
 - The _____ statement selects among multiple actions based on the possible values of an integer variable or expression, or a `String`.
 - The _____ statement, when executed in a repetition statement, skips the remaining statements in the loop body and proceeds with the next iteration of the loop.
 - The _____ operator can be used to ensure that two conditions are *both* true before choosing a certain path of execution.
 - If the loop-continuation condition in a `for` header is initially _____, the program does not execute the `for` statement's body.
 - Methods that perform common tasks and do not require objects are called _____ methods.
- 4.2** State whether each of the following is *true* or *false*. If *false*, explain why.
- The default case is required in the `switch` selection statement.
 - The `break` statement is required in the last case of a `switch` selection statement.
 - The expression `((x > y) && (a < b))` is true if either `x > y` is true or `a < b` is true.
 - An expression containing the `||` operator is true if either or both of its operands are true.
 - The comma `(,)` formatting flag in a format specifier (e.g., `%, 20.2f`) indicates that a value should be output with a thousands separator.

- f) To test for a range of values in a switch statement, use a hyphen (-) between the start and end values of the range in a case label.
- g) Listing cases consecutively with no statements between them enables the cases to perform the same set of statements.
- 4.3** Write a Java statement or a set of Java statements to accomplish each of the following tasks:
- Sum the odd integers between 1 and 99, using a `for` statement. Assume that the integer variables `sum` and `count` have been declared.
 - Calculate the value of 2.5 raised to the power of 3, using the `pow` method.
 - Print the integers from 1 to 20, using a `while` loop and the counter variable `i`. Assume that the variable `i` has been declared, but not initialized. Print only five integers per line. [*Hint: Use the calculation `i % 5`. When the value of this expression is 0, print a newline character; otherwise, print a tab character. Assume that this code is an application. Use the `System.out.println()` method to output the newline character, and use the `System.out.print('\t')` method to output the tab character.*]
 - Repeat part (c), using a `for` statement.
- 4.4** Find the error in each of the following code segments, and explain how to correct it:
- ```
i = 1;
while (i <= 10);
 ++i;
}
```
  - ```
for (k = 0.1; k != 1.0; k += 0.1)
    System.out.println(k);
```
 - ```
switch (n)
{
 case 1:
 System.out.println("The number is 1");
 case 2:
 System.out.println("The number is 2");
 break;
 default:
 System.out.println("The number is not 1 or 2");
 break;
}
```
  - The following code should print the values 1 to 10:
- ```
n = 1;
while (n < 10)
    System.out.println(n++);
```

Answers to Self-Review Exercises

- 4.1** a) `for`, `while`. b) `after`. c) `switch`. d) `continue`. e) `&&` (conditional AND). f) `false`. g) `static`.
- 4.2** a) `False`. The default case is optional. If no default action is needed, then there's no need for a default case. b) `False`. The `break` statement is used to exit the `switch` statement. The `break` statement is not required for the last case in a `switch` statement. c) `False`. *Both* of the relational expressions must be true for the entire expression to be true when using the `&&` operator. d) `True`. e) `True`. f) `False`. The `switch` statement does not provide a mechanism for testing ranges of values, so every value that must be tested should be listed in a separate case label. g) `True`.
- 4.3** a) `sum = 0;`
`for (count = 1; count <= 99; count += 2)`
`sum += count;`

- b) `double result = Math.pow(2.5, 3);`
 c) `i = 1;`

```
while (i <= 20)
{
    System.out.print(i);

    if (i % 5 == 0)
        System.out.println();
    else
        System.out.print('\t');

    ++i;
}
```

- d) `for (i = 1; i <= 20; i++)`
`{`
 `System.out.print(i);`

 `if (i % 5 == 0)`
 `System.out.println();`
 `else`
 `System.out.print('\t');`
`}`

- 4.4** a) Error: The semicolon after the `while` header causes an infinite loop, and there's a missing left brace.

Correction: Replace the semicolon by a `{`, or remove both the `;` and the `}`.

- b) Error: Using a floating-point number to control a `for` statement may not work, because floating-point numbers are represented only approximately by most computers.

Correction: Use an integer, and perform the proper calculation in order to get the values you desire:

```
for (k = 1; k != 10; k++)
    System.out.println((double) k / 10);
```

- c) Error: The missing code is the `break` statement in the statements for the first case.
 Correction: Add a `break` statement at the end of the statements for the first case. This omission is not necessarily an error if you want the statement of case 2: to execute every time the case 1: statement executes.
- d) Error: An improper relational operator is used in the `while`'s continuation condition.
 Correction: Use `<=` rather than `<`, or change 10 to 11.

Exercises

- 4.5** Describe the four basic elements of counter-controlled repetition.
- 4.6** Compare and contrast the `while` and `for` repetition statements.
- 4.7** Discuss a situation in which it would be more appropriate to use a `do...while` statement than a `while` statement. Explain why.
- 4.8** Compare and contrast the `break` and `continue` statements.
- 4.9** Find and correct the error(s) in each of the following segments of code:
- a) `For (i = 100, i >= 1, i++)`
 `System.out.println(i);`

- b) The following code should print whether integer value is odd or even:

```
switch (value % 2)
{
    case 0:
        System.out.println("Even integer");
    case 1:
        System.out.println("Odd integer");
}
```

- c) The following code should output the odd integers from 19 to 1:

```
for (i = 19; i >= 1; i -= 2)
    System.out.println(i);
```

- d) The following code should output the even integers from 2 to 100:

```
counter = 2;
do
{
    System.out.println(counter);
    counter += 2;
} while (counter < 100);
```

4.10 What does the following program do?

```
1 // Exercise 4.10: Printing.java
2 public class Printing
3 {
4     public static void main(String[] args)
5     {
6         for (int i = 1; i <= 10; i++)
7         {
8             for (int j = 1; j <= 5; j++)
9                 System.out.print('@');
10            System.out.println();
11        }
12    }
13 }
14 } // end class Printing
```

4.11 (Find the Smallest Value) Write an application that finds the smallest of several integers. Assume that the first value read specifies the number of values to input from the user.

4.12 (Calculating the Product of Odd Integers) Write an application that calculates the product of the odd integers from 1 to 15.

4.13 (Factorials) Factorials are used frequently in probability problems. The factorial of a positive integer n (written $n!$ and pronounced “ n factorial”) is equal to the product of the positive integers from 1 to n . Write an application that calculates the factorials of 1 through 20. Use type `long`. Display the results in tabular format. What difficulty might prevent you from calculating the factorial of 100?

4.14 (Modified Compound-Interest Program) Modify the compound-interest application of Fig. 4.6 to repeat its steps for interest rates of 5%, 6%, 7%, 8%, 9% and 10%. Use a `for` loop to vary the interest rate.

4.15 (Triangle Printing Program) Write an application that displays the following patterns separately, one below the other. Use `for` loops to generate the patterns. All asterisks (*) should be print-

4.21 (Pythagorean Triples) A right triangle can have sides whose lengths are all integers. The set of three integer values for the lengths of the sides of a right triangle is called a Pythagorean triple. The lengths of the three sides must satisfy the relationship that the sum of the squares of two of the sides is equal to the square of the hypotenuse. Write an application that displays a table of the Pythagorean triples for `side1`, `side2` and the hypotenuse, all no larger than 500. Use a triple-nested for loop that tries all possibilities. This method is an example of “brute-force” computing. You’ll learn in more advanced computer science courses that for many interesting problems there’s no known algorithmic approach other than using sheer brute force.

4.22 (Modified Triangle Printing Program) Modify Exercise 4.15 to combine your code from the four separate triangles of asterisks such that all four patterns print side by side. [Hint: Make clever use of nested for loops.]

4.23 (De Morgan’s Laws) In this chapter, we discussed the logical operators `&&`, `&`, `||`, `|`, `^` and `!`. De Morgan’s laws can sometimes make it more convenient for us to express a logical expression. These laws state that the expression `!(condition1 && condition2)` is logically equivalent to the expression `(!condition1 || !condition2)`. Also, the expression `!(condition1 || condition2)` is logically equivalent to the expression `(!condition1 && !condition2)`. Use De Morgan’s laws to write equivalent expressions for each of the following, then write an application to show that both the original expression and the new expression in each case produce the same value:

- a) `!(x < 5) && !(y >= 7)`
- b) `!(a == b) || !(g != 5)`
- c) `!((x <= 8) && (y > 4))`
- d) `!((i > 4) || (j <= 6))`

4.24 (Diamond Printing Program) Write an application that prints the following diamond shape. You may use output statements that print a single asterisk (*), a single space or a single new-line character. Maximize your use of repetition (with nested for statements), and minimize the number of output statements.

```

    *
   **
  ***
 ****
*****
*****
*****
*****
  ***
   **
    *
```

4.25 (Modified Diamond Printing Program) Modify the application you wrote in Exercise 4.24 to read an odd number in the range 1–19 to specify the number of rows in the diamond. Your program should then display a diamond of the appropriate size.

4.26 A criticism of the `break` statement and the `continue` statement is that each is unstructured. Actually, these statements can always be replaced by structured statements, although doing so can be awkward. Describe in general how you’d remove any `break` statement from a loop in a program and replace it with some structured equivalent. [Hint: The `break` statement exits a loop from the body of the loop. The other way to exit is by failing the loop-continuation test. Consider using in the loop-continuation test a second test that indicates “early exit because of a ‘break’ condition.”] Use the technique you develop here to remove the `break` statement from the application in Fig. 4.11.

4.27 What does the following program segment do?

```
for (i = 1; i <= 5; i++)
{
    for (j = 1; j <= 3; j++)
    {
        for (k = 1; k <= 4; k++)
            System.out.print('*');

        System.out.println();
    } // end inner for

    System.out.println();
} // end outer for
```

4.28 Describe in general how you'd remove any `continue` statement from a loop in a program and replace it with some structured equivalent. Use the technique you develop here to remove the `continue` statement from the program in Fig. 4.12.

4.29 (*"The Twelve Days of Christmas" Song*) Write an application that uses repetition and `switch` statements to print the song "The Twelve Days of Christmas." One `switch` statement should be used to print the day ("first," "second," and so on). A separate `switch` statement should be used to print the remainder of each verse. Visit the website [en.wikipedia.org/wiki/The_Twelve_Days_of_Christmas_\(song\)](http://en.wikipedia.org/wiki/The_Twelve_Days_of_Christmas_(song)) for the lyrics of the song.

Making a Difference

4.30 (*Global Warming Facts Quiz*) The controversial issue of global warming has been widely publicized by the film "An Inconvenient Truth," featuring former Vice President Al Gore. Mr. Gore and a U.N. network of scientists, the Intergovernmental Panel on Climate Change, shared the 2007 Nobel Peace Prize in recognition of "their efforts to build up and disseminate greater knowledge about man-made climate change." Research *both* sides of the global warming issue online (you might want to search for phrases like "global warming skeptics"). Create a five-question multiple-choice quiz on global warming, each question having four possible answers (numbered 1–4). Be objective and try to fairly represent both sides of the issue. Next, write an application that administers the quiz, calculates the number of correct answers (zero through five) and returns a message to the user. If the user correctly answers five questions, print "Excellent"; if four, print "Very good"; if three or fewer, print "Time to brush up on your knowledge of global warming," and include a list of some of the websites where you found your facts.

4.31 (*Tax Plan Alternatives; The "FairTax"*) There are many proposals to make taxation fairer. Check out the FairTax initiative in the United States at www.fairtax.org. Research how the proposed FairTax works. One suggestion is to eliminate income taxes and most other taxes in favor of a 23% consumption tax on all products and services that you buy. Some FairTax opponents question the 23% figure and say that because of the way the tax is calculated, it would be more accurate to say the rate is 30%—check this carefully. Write a program that prompts the user to enter expenses in various expense categories they have (e.g., housing, food, clothing, transportation, education, health care, vacations), then prints the estimated FairTax that person would pay.

4.32 (*Facebook User Base Growth*) According to CNNMoney.com, Facebook hit one billion users in October 2012. Using the compound-growth technique you learned in Fig. 4.6 and assuming its user base grows at a rate of 4% per month, how many months will it take for Facebook to grow its user base to 1.5 billion users? How many months will it take for Facebook to grow its user base to two billion users?

5

Methods

Form ever follows function.

—Louis Henri Sullivan

*E pluribus unum.
(One composed of many.)*

—Virgil

*O! call back yesterday,
bid time return.*

—William Shakespeare

Answer me in one word.

—William Shakespeare

Objectives

In this chapter you'll:

- Declare your own methods and call them.
- Use common Math methods from the Java API.
- Understand how the method-call/return mechanism is supported by the method-call stack.
- Learn about argument promotion and casting.
- Use secure random-number generation to implement game-playing applications.
- Understand how the visibility of declarations is limited to specific regions of programs.
- Understand what method overloading is and how to create overloaded methods.



- | | |
|--|--|
| 5.1 Introduction | 5.9 Case Study: Secure Random-Number Generation |
| 5.2 Program Modules in Java | 5.10 Case Study: A Game of Chance; Introducing <code>enum</code> Types |
| 5.3 <code>static</code> Methods, <code>static</code> Variables and Class <code>Math</code> | 5.11 Scope of Declarations |
| 5.4 Declaring Methods | 5.12 Method Overloading |
| 5.5 Notes on Declaring and Using Methods | 5.13 (Optional) GUI and Graphics Case Study: Colors and Filled Shapes |
| 5.6 Method-Call Stack and Stack Frames | 5.14 Wrap-Up |
| 5.7 Argument Promotion and Casting | |
| 5.8 Java API Packages | |

Summary | Self-Review Exercises | Answers to Self-Review Exercises | Exercises | Making a Difference

5.1 Introduction

Experience has shown that the best way to develop and maintain a large program is to construct it from small, simple pieces, or **modules**. This technique is called **divide and conquer**. In this chapter, you'll learn how to declare and use methods to facilitate the design, implementation, operation and maintenance of large programs.

Previously, you've called methods on specific objects—for example, method `nextInt` on `Scanner` objects and methods `printf` and `println` on the `System.out` object. You'll see that it's possible for certain methods, called `static` methods, to be called on a class rather than an object. You'll learn how to declare `static` methods, then call them from other methods (such as `main`). You'll also learn how Java is able to keep track of which method is currently executing, how local variables of methods are maintained in memory and how a method knows where to return after it completes execution.

We'll take a brief diversion into simulation techniques with random-number generation and develop a version of the dice game called craps that uses most of the programming techniques you've used to this point in the book. In addition, you'll learn how to declare constants in your programs.

Many of the classes you'll use or create while developing applications will have more than one method of the same name. This technique, called *overloading*, is used to implement methods that perform similar tasks for arguments of different types or for different numbers of arguments.

We continue discussing methods in Chapter 7, Introduction to Classes and Objects, where you'll declare your own classes, create objects of those classes and invoke their methods. We discuss methods further in Chapter 18, Recursion. Recursion provides an intriguing way of thinking about methods and algorithms.

5.2 Program Modules in Java

You write Java programs by combining new methods and classes with predefined ones available in the **Java Application Programming Interface** (also referred to as the **Java API** or **Java class library**) and in various other class libraries. Related classes are typically grouped into *packages* so that they can be *imported* into programs and *reused*. You'll learn how to group

your own classes into *packages* in Section 21.4.10. The Java API provides a rich collection of predefined classes that contain methods for performing common mathematical calculations, string manipulations, character manipulations, input/output operations, database operations, networking operations, file processing, error checking and more.



Software Engineering Observation 5.1

Familiarize yourself with the rich collection of classes and methods provided by the Java API (<http://docs.oracle.com/javase/7/docs/api/>). Section 5.8 overviews several common packages. Online Appendix F explains how to navigate the API documentation. Don't reinvent the wheel. When possible, reuse Java API classes and methods. This reduces program development time and avoids introducing programming errors.

Divide and Conquer with Methods

Methods help you modularize a program by separating its tasks into self-contained units. You've declared a `main` method in every program you've written. The `main` method is special in that it is called once to begin a program's execution. When you create other methods, the statements in the method bodies are written only once, are hidden from other methods and can be reused from several locations in a program.

One motivation for modularizing a program into methods is the *divide-and-conquer* approach, which makes program development more manageable by constructing programs from small, simple pieces. Another is **software reusability**—using existing methods as building blocks to create new programs. Often, you can create programs mostly from existing classes and methods rather than by building customized code. For example, in earlier programs, we did not define how to read data from the keyboard—Java provides these capabilities in the `Scanner` class's methods. A third motivation is to *avoid repeating code*. Dividing a program into meaningful methods—and as you'll see starting in Chapter 7, classes—makes the program easier to debug and maintain.



Software Engineering Observation 5.2

To promote software reusability, every method should be limited to performing a single, well-defined task, and the name of the method should express that task effectively.



Error-Prevention Tip 5.1

A method that performs one task is easier to test and debug than one that performs many tasks.



Software Engineering Observation 5.3

If you cannot choose a concise name that expresses a method's task, your method might be attempting to perform too many tasks. Break such a method into several smaller ones.

Hierarchical Relationship Between Method Calls

A method is invoked by a method call, and when the called method completes its task, it returns control—and possibly a result—to the caller. An analogy to this program structure is the hierarchical form of management (Fig. 5.1). A boss (the caller) asks a worker (the called method) to perform a task and report back (return) the results after completing the task. The boss method does not know how the worker method performs its designated tasks. The worker may also call other worker methods, unbeknown to the boss. This “hid-

ing” of implementation details promotes good software engineering. Figure 5.1 shows the boss method communicating with several worker methods in a hierarchical manner. The boss method divides its responsibilities among the various worker methods. Here, worker1 acts as a “boss method” to worker4 and worker5.



Error-Prevention Tip 5.2

When you call a method that returns a value indicating whether the method performed its task successfully, be sure to check the return value of that method and, if that method was unsuccessful, deal with the issue appropriately.




Fig. 5.1 | Hierarchical boss-method/worker-method relationship.

5.3 static Methods, static Variables and Class Math

Most methods execute in response to method calls *on specific objects* (but this is not always the case). Sometimes a method performs a task that does not depend on an object. Such a method applies to the class in which it’s declared as a whole and is known as a **static method** or a **class method**.

It’s common for classes to contain convenient static methods to perform common tasks. For example, recall that we used static method `pow` of class `Math` to raise a value to a power in Fig. 4.6. For any class imported into your program, you can call the class’s static methods by specifying the name of the class in which the method is declared, followed by a dot (`.`) and the method name, as in

```
ClassName.methodName(arguments)
```

Math Class Methods

We use `Math` class methods here to present the concept of static methods. Class `Math` provides a collection of methods that enable you to perform common mathematical calculations. For example, you can calculate the square root of 900.0 with the static method call

```
Math.sqrt(900.0)
```

This expression evaluates to 30.0. Method `sqrt` takes an argument of type `double` and returns a result of type `double`. To output the value of the preceding method call in the command window, you might write the statement

```
System.out.println(Math.sqrt(900.0));
```

In this statement, the value that `sqrt` returns becomes the argument to method `println`. There was no need to create a `Math` object before calling method `sqrt`. Also *all* `Math` class methods are *static*—therefore, each is called by preceding its name with the class name `Math` and the dot (`.`) separator.



Software Engineering Observation 5.4

Class `Math` is part of the `java.lang` package, which is implicitly imported by the compiler, so it's not necessary to import class `Math` to use its methods.

Method arguments may be constants, variables or expressions. If `c = 13.0`, `d = 3.0` and `f = 4.0`, then the statement

```
System.out.println(Math.sqrt(c + d * f));
```

calculates and prints the square root of $13.0 + 3.0 * 4.0 = 25.0$ —namely, 5.0 . Figure 5.2 summarizes several `Math` class methods. In the figure, x and y are of type `double`.

Method	Description	Example
<code>abs(x)</code>	absolute value of x	<code>abs(23.7)</code> is 23.7 <code>abs(0.0)</code> is 0.0 <code>abs(-23.7)</code> is 23.7
<code>ceil(x)</code>	rounds x to the smallest integer not less than x	<code>ceil(9.2)</code> is 10.0 <code>ceil(-9.8)</code> is -9.0
<code>cos(x)</code>	trigonometric cosine of x (x in radians)	<code>cos(0.0)</code> is 1.0
<code>exp(x)</code>	exponential method e^x	<code>exp(1.0)</code> is 2.71828 <code>exp(2.0)</code> is 7.38906
<code>floor(x)</code>	rounds x to the largest integer not greater than x	<code>floor(9.2)</code> is 9.0 <code>floor(-9.8)</code> is -10.0
<code>log(x)</code>	natural logarithm of x (base e)	<code>log(Math.E)</code> is 1.0 <code>log(Math.E * Math.E)</code> is 2.0
<code>max(x, y)</code>	larger value of x and y	<code>max(2.3, 12.7)</code> is 12.7 <code>max(-2.3, -12.7)</code> is -2.3
<code>min(x, y)</code>	smaller value of x and y	<code>min(2.3, 12.7)</code> is 2.3 <code>min(-2.3, -12.7)</code> is -12.7
<code>pow(x, y)</code>	x raised to the power y (i.e., x^y)	<code>pow(2.0, 7.0)</code> is 128.0 <code>pow(9.0, 0.5)</code> is 3.0
<code>sin(x)</code>	trigonometric sine of x (x in radians)	<code>sin(0.0)</code> is 0.0
<code>sqrt(x)</code>	square root of x	<code>sqrt(900.0)</code> is 30.0
<code>tan(x)</code>	trigonometric tangent of x (x in radians)	<code>tan(0.0)</code> is 0.0

Fig. 5.2 | `Math` class methods.

Class Variables and `Math` Class static Constants `PI` and `E`

Just as a class may contain static methods, a class also may contain static variables. Such variables are known as **class variables**. Class `Math` declares two constants, `Math.PI`

and `Math.E`, that represent *high-precision approximations* to commonly used mathematical constants. `Math.PI` (3.141592653589793) is the ratio of a circle's circumference to its diameter. `Math.E` (2.718281828459045) is the base value for natural logarithms (calculated with static `Math` method `log`). These constants are declared in class `Math` with the modifiers `public`, `static` and `final`:

- Making them `public` allows you to use them in your own classes.
- Making them `static` allows them to be accessed via the class name `Math` and a dot (`.`) separator, just as class `Math`'s methods are.
- Making them `final` indicates that they are *constants*—their values cannot change after they are initialized. As you'll see in Fig. 5.8, static variables are not required to be constants.

A class's variables are sometimes called **fields**. You'll learn in Chapter 7 that a class's fields consist of its static variables and instance variables. You'll learn more about static fields in Section 8.11.

Why Is Method `main` Declared `static`?

When you execute the Java Virtual Machine (JVM) with the `java` command, the JVM attempts to invoke the `main` method of the class you specify. Declaring `main` as `static` allows the JVM to invoke `main` without creating an object of the class. When you execute your application, you specify its class name as an argument to the `java` command, as in

```
java ClassName argument1 argument2 ...
```

The JVM loads the class specified by *ClassName* and uses that class name to invoke method `main`. In the preceding command, *ClassName* is a **command-line argument** to the JVM that tells it which class to execute. Following the *ClassName*, you can also specify a list of `Strings` (separated by spaces) as command-line arguments that the JVM will pass to your application. Such arguments might be used to specify options (e.g., a filename) to run the application. As you'll learn in Chapter 6, Arrays and `ArrayLists`, your application can access those command-line arguments and use them to customize the application.

5.4 Declaring Methods

So far, each class we declared contained one method named `main`. Class `MaximumFinder` (Fig. 5.3) has two methods—`main` (lines 8–25) and `maximum` (lines 28–41). The `maximum` method determines and returns the largest of three `double` values. Recall that `main` is a special method that is always called automatically by the Java Virtual Machine (JVM) when you execute an application. Most methods do not get called automatically. As you'll soon see, you must call method `maximum` explicitly to tell it to perform its task. We begin our discussion with method `maximum`'s declaration.

```
1 // Fig. 5.3: MaximumFinder.java
2 // Programmer-declared method maximum with three double parameters.
3 import java.util.Scanner;
```

Fig. 5.3 | Programmer-declared method `maximum` with three `double` parameters. (Part I of 2.)

```

4
5 public class MaximumFinder
6 {
7     // obtain three floating-point values and locate the maximum value
8     public static void main(String[] args)
9     {
10         // create Scanner for input from command window
11         Scanner input = new Scanner(System.in);
12
13         // prompt for and input three floating-point values
14         System.out.print(
15             "Enter three floating-point values separated by spaces: ");
16         double number1 = input.nextDouble(); // read first double
17         double number2 = input.nextDouble(); // read second double
18         double number3 = input.nextDouble(); // read third double
19
20         // determine the maximum value
21         double result = maximum(number1, number2, number3);
22
23         // display maximum value
24         System.out.println("Maximum is: " + result);
25     }
26
27     // returns the maximum of its three double parameters
28     public static double maximum(double x, double y, double z)
29     {
30         double maximumValue = x; // assume x is the largest to start
31
32         // determine whether y is greater than maximumValue
33         if (y > maximumValue)
34             maximumValue = y;
35
36         // determine whether z is greater than maximumValue
37         if (z > maximumValue)
38             maximumValue = z;
39
40         return maximumValue;
41     }
42 } // end class MaximumFinder

```

Enter three floating-point values separated by spaces: 9.35 2.74 5.1
Maximum is: 9.35

Enter three floating-point values separated by spaces: 5.8 12.45 8.32
Maximum is: 12.45

Enter three floating-point values separated by spaces: 6.46 4.12 10.54
Maximum is: 10.54

Fig. 5.3 | Programmer-declared method maximum with three double parameters. (Part 2 of 2.)

*The **public** and **static** Keywords*

Method `maximum`'s declaration begins with keyword `public` to indicate that the method is “available to the public”—it can be called from methods of other classes. The keyword `static` enables the `main` method (another `static` method) to call `maximum` as shown in line 21 without qualifying the method name with the class name `MaximumFinder`—`static` methods in the same class can call each other directly. Any other class that uses `maximum` must fully qualify the method name with the class name. The examples in this chapter and the next begin every method declaration with the keywords `public` and `static`. (You'll learn about non-`public` and non-`static` methods in Chapter 7.)

The Return Type

After keywords `public` and `static` is the method's **return type**, which specifies the type of data the method returns (that is, gives back to its *caller*) after performing its task. For example, when you go to an automated teller machine (ATM) and request your account balance, you expect the ATM to give you back a value that represents your balance. Similarly, when a statement calls method `maximum` in this example, the statement expects to receive back the largest of the three values. The return type `double` indicates that this method will perform a task then return a `double` value to the **calling method** (that is, `main` in this example). You've already used methods that return information—for example, `Scanner` method `nextInt` inputs an integer typed by the user at the keyboard, then returns that value for use in the program. In some cases, you'll define methods that perform a task but will *not* return any information. Such methods use the return type `void` (as in `main`).

The Method Name and Parameters

The method name, `maximum`, follows the return type. Class names, method names and variable names are all *identifiers* and by convention all use the same *camel case* naming scheme we discussed in Chapter 2. Also by convention, class names begin with an initial *uppercase* letter, and method names and variable names begin with an initial *lowercase* letter.

The parentheses after the method name indicate that this is a method. For a method that requires additional information to perform its task, the method can specify one or more **parameters** that represent that additional information. If the parentheses are empty, the method does not require additional information to perform its task.

Parameters are defined in a comma-separated **parameter list**, which is located in the parentheses that follow the method name. Each parameter must specify a type and an identifier. Method `maximum` requires three `double` parameters, which we named `x`, `y` and `z`. A method's parameters are considered to be local variables of that method and can be used only in that method's body. Collectively, the elements in line 28 are often referred to as the **method header**.



Common Programming Error 5.1

Declaring method parameters of the same type as `float x, y` instead of `float x, float y` is a syntax error—a type is required for each parameter in the parameter list.

The Method Body

The method header is always followed by the method's body, which is delimited by left and right braces, as in lines 29 and 41. A method's body contains one or more statements that perform the method's task. To determine the maximum value, we begin with the as-

assumption that parameter `x` contains the largest value, so line 30 declares local variable `maximumValue` and initializes it with the value of parameter `x`. Of course, it's possible that parameter `y` or `z` contains the actual largest value, so we must compare each of these values with `maximumValue`. The `if` statement at lines 33–34 determines whether `y` is greater than `maximumValue`. If so, line 34 assigns `y` to `maximumValue`. The `if` statement at lines 37–38 determines whether `z` is greater than `maximumValue`. If so, line 38 assigns `z` to `maximumValue`. At this point the largest of the three values resides in `maximumValue`, so line 40 uses the **return** statement to return that value to the point in the program from which `maximum` was called (line 21). When program control returns to that point, `maximum`'s parameters `x`, `y` and `z` no longer exist in memory.

Method `main` and Calling Method `maximum`

Lines 14–18 in `main` prompt the user to enter three `double` values, then read them from the user via Scanner method `nextDouble`, which returns the user input as a `double` value.

A method call supplies values—called arguments—for each of the method's parameters. For example, the argument to method `System.out.println` specifies the data to display in a command window. When `maximum` is called from line 21 in `main`, its parameters `x`, `y` and `z` (line 28) are initialized with the values of arguments `number1`, `number2` and `number3`, respectively. There must be one argument in the method call for each parameter in the method declaration. Also, each argument must be *consistent* with the type of the corresponding parameter. For example, a parameter of type `double` can receive values like 7.35, 22 or -0.03456, but not Strings like "hello" nor the boolean values `true` or `false`. Section 5.7 discusses the argument types that can be provided in a method call for each parameter of a primitive type.

When method `maximum` returns the result to line 21, the program assigns `maximum`'s return value to `main`'s local variable `result`. Then line 24 outputs the maximum value.



Common Programming Error 5.2

A compilation error occurs if the number of arguments in a method call does not match the number of parameters in the method declaration.

Assembling Strings with String Concatenation

Java allows you to assemble `String` objects into larger strings by using operators `+` or `+=`. This is known as **string concatenation**. When both operands of operator `+` are `String` objects, operator `+` creates a new `String` object in which the characters of the right operand are placed at the end of those in the left operand—e.g., the expression `"hello " + "there"` creates the `String` `"hello there"`.

In line 24 of Fig. 5.3, the expression `"Maximum is: " + result` uses operator `+` with operands of types `String` and `double`. *Every primitive value and object in Java can be represented as a String*. When one of the `+` operator's operands is a `String`, the other is converted to a `String`, then the two are *concatenated*. In line 24, the `double` value is converted to its `String` representation and placed at the end of the `String` `"Maximum is: "`. If there are any *trailing zeros* in a `double` value, these will be *discarded* when the number is converted to a `String`—for example 9.3500 would be represented as 9.35.

Primitive values used in `String` concatenation are converted to `Strings`. A boolean concatenated with a `String` is converted to the `String` `"true"` or `"false"`. In Chapter 7, you'll learn that *all objects have a toString method that returns a String representation of*

the object. When an object is concatenated with a `String`, the object's `toString` method is implicitly called to obtain the `String` representation of the object.

You can break large `String` literals into several smaller `Strings` and place them on multiple lines of code for readability. In this case, the `Strings` can be reassembled using concatenation. We discuss the details of `Strings` in Chapter 14.



Common Programming Error 5.3

It's a syntax error to break a `String` literal across lines. If necessary, you can split a `String` into several smaller `Strings` and use concatenation to form the desired `String`.



Common Programming Error 5.4

Confusing the `+` operator used for string concatenation with the `+` operator used for addition can lead to strange results. Java evaluates the operands of an operator from left to right. For example, if integer variable `y` has the value 5, the expression "`y + 2 =` " + `y + 2` results in the string "`y + 2 = 52`", not "`y + 2 = 7`", because first the value of `y` (5) is concatenated to the string "`y + 2 =` ", then the value 2 is concatenated to the new larger string "`y + 2 = 5`". The expression "`y + 2 =` " + (`y + 2`) produces the desired result "`y + 2 = 7`".

Implementing Method `maximum` by Reusing Method `Math.max`

The entire body of our `maximum` method could also be implemented with two calls to `Math.max`, as follows:

```
return Math.max(x, Math.max(y, z));
```

The outer call to `Math.max` specifies arguments `x` and `Math.max(y, z)`. Before any method can be called, its arguments must be evaluated to determine their values. If an argument is a method call, the method call must be performed to determine its return value. So, in the preceding statement, `Math.max(y, z)` is evaluated to determine the maximum of `y` and `z`. Then the result is passed as the second argument to the other call to `Math.max`, which returns the larger of its two arguments. This is a good example of *software reuse*—we find the largest of three values by reusing `Math.max`, which finds the larger of two values. Notice how concise this code is compared to lines 30–38 of Fig. 5.3.

5.5 Notes on Declaring and Using Methods

There are three ways to call a method:

1. Using a method name by itself to call another method of the *same* class—such as `maximum(number1, number2, number3)` in line 21 of Fig. 5.3.
2. Using an object's variable name followed by a dot (`.`) and the method name to call a non-static method of the object—such as the method call in line 16 of Fig. 5.3, `input.nextDouble()`, which calls a method of class `Scanner`. Non-static methods are typically called **instance methods**.
3. Using the class name and a dot (`.`) to call a static method of a class—such as `Math.sqrt(900.0)` in Section 5.3.

There are three ways to return control to the statement that calls a method. If the method does not return a result, control returns when the program flow reaches the method-ending right brace or when the statement

```
return;
```

is executed. If the method returns a result, the statement

```
return expression;
```

evaluates the *expression*, then returns the result to the caller.



Common Programming Error 5.5

Declaring a method outside the body of a class declaration or inside the body of another method is a syntax error.



Common Programming Error 5.6

Redeclaring a parameter as a local variable in the method's body is a compilation error.



Common Programming Error 5.7

Forgetting to return a value from a method that should return a value is a compilation error. If a return type other than void is specified, the method must contain a return statement that returns a value consistent with the method's return type. Returning a value from a method whose return type is void is a compilation error.

5.6 Method-Call Stack and Stack Frames

To understand how Java performs method calls, we first need to consider a data structure (i.e., collection of related data items) known as a **stack**. You can think of a stack as analogous to a pile of dishes. When a dish is placed on the pile, it's normally placed at the top (referred to as **pushing** the dish onto the stack). Similarly, when a dish is removed from the pile, it's normally removed from the top (referred to as **popping** the dish off the stack). Stacks are known as **last-in, first-out (LIFO) data structures**—the *last* item pushed onto the stack is the *first* item popped from the stack.

When a program *calls* a method, the called method must know how to *return* to its caller, so the *return address* of the calling method is *pushed* onto the **method-call stack**. If a series of method calls occurs, the successive return addresses are pushed onto the stack in last-in, first-out order so that each method can return to its caller.

The method-call stack also contains the memory for the *local variables* (including the method parameters) used in each invocation of a method during a program's execution. This data, stored as a portion of the method-call stack, is known as the **stack frame** (or **activation record**) of the method call. When a method call is made, the stack frame for that method call is *pushed* onto the method-call stack. When the method returns to its caller, the stack frame for this method call is *popped* off the stack and those local variables are no longer known to the program.

Of course, a computer's memory is finite, so only a certain amount can be used to store stack frames on the method-call stack. If more method calls occur than can have their stack frames stored, an error known as a **stack overflow** occurs—we'll talk more about this in Chapter 11, Exception Handling: A Deeper Look.

5.7 Argument Promotion and Casting

Another important feature of method calls is **argument promotion**—converting an *argument's value*, if possible, to the type that the method expects to receive in its corresponding *parameter*. For example, a program can call `Math` method `sqrt` with an `int` argument even though a `double` argument is expected. The statement

```
System.out.println(Math.sqrt(4));
```

correctly evaluates `Math.sqrt(4)` and prints the value `2.0`. The method declaration's parameter list causes Java to convert the `int` value `4` to the `double` value `4.0` *before* passing the value to method `sqrt`. Such conversions may lead to compilation errors if Java's **promotion rules** are not satisfied. These rules specify which conversions are allowed—that is, which ones can be performed *without losing data*. In the `sqrt` example above, an `int` is converted to a `double` without changing its value. However, converting a `double` to an `int` *truncates* the fractional part of the `double` value—thus, part of the value is lost. Converting large integer types to small integer types (e.g., `long` to `int`, or `int` to `short`) may also result in changed values.

The promotion rules apply to expressions containing values of two or more primitive types and to primitive-type values passed as arguments to methods. Each value is promoted to the “highest” type in the expression. Actually, the expression uses a *temporary copy* of each value—the types of the original values remain unchanged. Figure 5.4 lists the primitive types and the types to which each can be promoted. The valid promotions for a given type are always to a type higher in the table. For example, an `int` can be promoted to the higher types `long`, `float` and `double`.

Converting values to types lower in the table of Fig. 5.4 will result in different values if the lower type cannot represent the value of the higher type (e.g., the `int` value `2000000` cannot be represented as a `short`, and any floating-point number with digits after its decimal point cannot be represented in an integer type such as `long`, `int` or `short`). Therefore, in cases where information may be lost due to conversion, the Java compiler requires you to use a *cast operator* (introduced in Section 3.9) to explicitly force the conversion to occur—otherwise a compilation error occurs. This enables you to “take control” from the compiler. You essentially say, “I know this conversion might cause loss of information, but

Type	Valid promotions
<code>double</code>	None
<code>float</code>	<code>double</code>
<code>long</code>	<code>float</code> or <code>double</code>
<code>int</code>	<code>long</code> , <code>float</code> or <code>double</code>
<code>char</code>	<code>int</code> , <code>long</code> , <code>float</code> or <code>double</code>
<code>short</code>	<code>int</code> , <code>long</code> , <code>float</code> or <code>double</code> (but not <code>char</code>)
<code>byte</code>	<code>short</code> , <code>int</code> , <code>long</code> , <code>float</code> or <code>double</code> (but not <code>char</code>)
<code>boolean</code>	None (<code>boolean</code> values are not considered to be numbers in Java)

Fig. 5.4 | Promotions allowed for primitive types.

for my purposes here, that’s fine.” Suppose method `square` calculates the square of an integer and thus requires an `int` argument. To call `square` with a `double` argument named `doubleValue`, we would be required to write the method call as

```
square((int) doubleValue)
```

This method call explicitly casts (converts) `doubleValue`’s value to a temporary integer for use in method `square`. Thus, if `doubleValue`’s value is 4.5, the method receives the value 4 and returns 16, not 20.25.



Common Programming Error 5.8

Casting a primitive-type value to another primitive type may change the value if the new type is not a valid promotion. For example, casting a floating-point value to an integer value may introduce truncation errors (loss of the fractional part) into the result.

5.8 Java API Packages

As you’ve seen, Java contains many *predefined* classes that are grouped into categories of related classes called *packages*. Together, these are known as the Java Application Programming Interface (Java API), or the Java class library. A great strength of Java is the Java API’s thousands of classes. Some key Java API packages that we use in this book are described in Fig. 5.5, which represents only a small portion of the *reusable components* in the Java API.

Package	Description
java.awt.event	The Java Abstract Window Toolkit Event Package contains classes and interfaces that enable event handling for GUI components in both the <code>java.awt</code> and <code>javax.swing</code> packages. (See Chapter 12, GUI Components: Part 1, and Chapter 22, GUI Components: Part 2.)
java.awt.geom	The Java 2D Shapes Package contains classes and interfaces for working with Java’s advanced two-dimensional graphics capabilities. (See Chapter 13, Graphics and Java 2D.)
java.io	The Java Input/Output Package contains classes and interfaces that enable programs to input and output data. (See Chapter 15, Files, Streams and Object Serialization.)
java.lang	The Java Language Package contains classes and interfaces (discussed throughout the book) that are required by many Java programs. This package is imported by the compiler into all programs.
java.net	The Java Networking Package contains classes and interfaces that enable programs to communicate via computer networks like the Internet. (See online Chapter 28, Networking.)
java.security	The Java Security Package contains classes and interfaces for enhancing application security.
java.sql	The JDBC Package contains classes and interfaces for working with databases. (See Chapter 24, Accessing Databases with JDBC.)

Fig. 5.5 | Java API packages (a subset). (Part 1 of 2.)

Package	Description
<code>java.util</code>	The Java Utilities Package contains utility classes and interfaces that enable storing and processing of large amounts of data. Many of these classes and interfaces have been updated to support Java SE 8's new lambda capabilities. (See Chapter 16, Generic Collections.)
<code>java.util.concurrent</code>	The Java Concurrency Package contains utility classes and interfaces for implementing programs that can perform multiple tasks in parallel. (See Chapter 23, Concurrency.)
<code>javax.swing</code>	The Java Swing GUI Components Package contains classes and interfaces for Java's Swing GUI components that provide support for portable GUIs. This package still uses some elements of the older <code>java.awt</code> package. (See Chapter 12, GUI Components: Part 1, and Chapter 22, GUI Components: Part 2.)
<code>javax.swing.event</code>	The Java Swing Event Package contains classes and interfaces that enable event handling (e.g., responding to button clicks) for GUI components in package <code>javax.swing</code> . (See Chapter 12, GUI Components: Part 1, and Chapter 22, GUI Components: Part 2.)
<code>javax.xml.ws</code>	The JAX-WS Package contains classes and interfaces for working with web services in Java. (See online Chapter 32, REST-Based Web Services.)
javafx packages	JavaFX is the preferred GUI technology for the future. We discuss these packages in Chapter 25, JavaFX GUI: Part 1 and in the online JavaFX GUI and multimedia chapters.
<i>Some Java SE 8 Packages Used in This Book</i>	
<code>java.time</code>	The new Java SE 8 Date/Time API Package contains classes and interfaces for working with dates and times. These features are designed to replace the older date and time capabilities of package <code>java.util</code> . (See Chapter 23, Concurrency.)
<code>java.util.function</code> and <code>java.util.stream</code>	These packages contain classes and interfaces for working with Java SE 8's functional programming capabilities. (See Chapter 17, Java SE 8 Lambdas and Streams.)

Fig. 5.5 | Java API packages (a subset). (Part 2 of 2.)

The set of packages available in Java is quite large. In addition to those summarized in Fig. 5.5, Java includes packages for complex graphics, advanced graphical user interfaces, printing, advanced networking, security, database processing, multimedia, accessibility (for people with disabilities), concurrent programming, cryptography, XML processing and many other capabilities. For an overview of the packages in Java, visit

<http://docs.oracle.com/javase/7/docs/api/overview-summary.html>
<http://download.java.net/jdk8/docs/api/overview-summary.html>

You can locate additional information about a predefined Java class's methods in the Java API documentation at

<http://docs.oracle.com/javase/7/docs/api/>

When you visit this site, click the **Index** link to see an alphabetical listing of all the classes and methods in the Java API. Locate the class name and click its link to see the online description of the class. Click the **METHOD** link to see a table of the class's methods. Each static method will be listed with the word “static” preceding its return type.

5.9 Case Study: Secure Random-Number Generation

We now take a brief diversion into a popular type of programming application—simulation and game playing. In this and the next section, we develop a game-playing program with multiple methods. The program uses most of the control statements presented thus far in the book and introduces several new programming concepts.

The **element of chance** can be introduced in a program via an object of class **SecureRandom** (package `java.security`). Such objects can produce random `boolean`, `byte`, `float`, `double`, `int`, `long` and Gaussian values. In the next several examples, we use objects of class `SecureRandom` to produce random values.

Moving to Secure Random Numbers

Recent editions of this book used Java's `Random` class to obtain “random” values. This class produced *deterministic* values that could be *predicted* by malicious programmers. `SecureRandom` objects produce **nondeterministic random numbers** that *cannot* be predicted.

Deterministic random numbers have been the source of many software security breaches. Most programming languages now have library features similar to Java's `SecureRandom` class for producing nondeterministic random numbers to help prevent such problems. From this point forward in the text, when we refer to “random numbers” we mean “secure random numbers.”

Creating a SecureRandom Object

A new secure random-number generator object can be created as follows:

```
SecureRandom randomNumbers = new SecureRandom();
```

It can then be used to generate random values—we discuss only random `int` values here. For more information on the `SecureRandom` class, see docs.oracle.com/javase/7/docs/api/java/security/SecureRandom.html.

Obtaining a Random int Value

Consider the following statement:

```
int randomValue = randomNumbers.nextInt();
```

`SecureRandom` method **nextInt** generates a random `int` value. If it truly produces values *at random*, then every value in the range should have an *equal chance* (or probability) of being chosen each time `nextInt` is called.

Changing the Range of Values Produced By nextInt

The range of values produced by method `nextInt` generally differs from the range of values required in a particular Java application. For example, a program that simulates coin tossing might require only 0 for “heads” and 1 for “tails.” A program that simulates the rolling of a six-sided die might require random integers in the range 1–6. A program that randomly predicts the next type of spaceship (out of four possibilities) that will fly across

the horizon in a video game might require random integers in the range 1–4. For cases like these, class `SecureRandom` provides another version of method `nextInt` that receives an `int` argument and returns a value from 0 up to, but not including, the argument's value. For example, for coin tossing, the following statement returns 0 or 1.

```
int randomValue = randomNumbers.nextInt(2);
```

Rolling a Six-Sided Die

To demonstrate random numbers, let's develop a program that simulates 20 rolls of a six-sided die and displays the value of each roll. We begin by using `nextInt` to produce random values in the range 0–5, as follows:

```
int face = randomNumbers.nextInt(6);
```

The argument 6—called the **scaling factor**—represents the number of unique values that `nextInt` should produce (in this case six—0, 1, 2, 3, 4 and 5). This manipulation is called **scaling** the range of values produced by `SecureRandom` method `nextInt`.

A six-sided die has the numbers 1–6 on its faces, not 0–5. So we **shift** the range of numbers produced by adding a **shifting value**—in this case 1—to our previous result, as in

```
int face = 1 + randomNumbers.nextInt(6);
```

The shifting value (1) specifies the *first* value in the desired range of random integers. The preceding statement assigns `face` a random integer in the range 1–6.

Rolling a Six-Sided Die 20 Times

Figure 5.6 shows two sample outputs which confirm that the results of the preceding calculation are integers in the range 1–6, and that each run of the program can produce a *different* sequence of random numbers. Line 3 imports class `SecureRandom` from the `java.security` package. Line 10 creates the `SecureRandom` object `randomNumbers` to produce random values. Line 16 executes 20 times in a loop to roll the die. The `if` statement (lines 21–22) in the loop starts a new line of output after every five numbers to create a neat, five-column format.

```

1 // Fig. 5.6: RandomIntegers.java
2 // Shifted and scaled random integers.
3 import java.security.SecureRandom; // program uses class SecureRandom
4
5 public class RandomIntegers
6 {
7     public static void main(String[] args)
8     {
9         // randomNumbers object will produce secure random numbers
10        SecureRandom randomNumbers = new SecureRandom();
11
12        // loop 20 times
13        for (int counter = 1; counter <= 20; counter++)
14        {
15            // pick random integer from 1 to 6
16            int face = 1 + randomNumbers.nextInt(6);

```

Fig. 5.6 | Shifted and scaled random integers. (Part 1 of 2.)

```

17
18         System.out.printf("%d ", face); // display generated value
19
20         // if counter is divisible by 5, start a new line of output
21         if (counter % 5 == 0)
22             System.out.println();
23     }
24 }
25 } // end class RandomIntegers

```

```

1 5 3 6 2
5 2 6 5 2
4 4 4 2 6
3 1 6 2 2

```

```

6 5 4 2 6
1 2 5 1 3
6 3 2 2 1
6 4 2 6 4

```

Fig. 5.6 | Shifted and scaled random integers. (Part 2 of 2.)

Rolling a Six-Sided Die 6,000,000 Times

To show that the numbers produced by `nextInt` occur with approximately equal likelihood, let's simulate 6,000,000 rolls of a die with the application in Fig. 5.7. Each integer from 1 to 6 should appear approximately 1,000,000 times.

```

1 // Fig. 5.7: RollDie.java
2 // Roll a six-sided die 6,000,000 times.
3 import java.security.SecureRandom;
4
5 public class RollDie
6 {
7     public static void main(String[] args)
8     {
9         // randomNumbers object will produce secure random numbers
10        SecureRandom randomNumbers = new SecureRandom();
11
12        int frequency1 = 0; // count of 1s rolled
13        int frequency2 = 0; // count of 2s rolled
14        int frequency3 = 0; // count of 3s rolled
15        int frequency4 = 0; // count of 4s rolled
16        int frequency5 = 0; // count of 5s rolled
17        int frequency6 = 0; // count of 6s rolled
18
19        // tally counts for 6,000,000 rolls of a die
20        for (int roll = 1; roll <= 6000000; roll++)
21        {
22            int face = 1 + randomNumbers.nextInt(6); // number from 1 to 6

```

Fig. 5.7 | Roll a six-sided die 6,000,000 times. (Part 1 of 2.)

```

23
24     // use face value 1-6 to determine which counter to increment
25     switch (face)
26     {
27         case 1:
28             ++frequency1; // increment the 1s counter
29             break;
30         case 2:
31             ++frequency2; // increment the 2s counter
32             break;
33         case 3:
34             ++frequency3; // increment the 3s counter
35             break;
36         case 4:
37             ++frequency4; // increment the 4s counter
38             break;
39         case 5:
40             ++frequency5; // increment the 5s counter
41             break;
42         case 6:
43             ++frequency6; // increment the 6s counter
44             break;
45     }
46 }
47
48 System.out.println("Face\tFrequency"); // output headers
49 System.out.printf("1\t%d%n2\t%d%n3\t%d%n4\t%d%n5\t%d%n6\t%d%n",
50     frequency1, frequency2, frequency3, frequency4,
51     frequency5, frequency6);
52 }
53 } // end class RollDie

```

Face	Frequency
1	999501
2	1000412
3	998262
4	1000820
5	1002245
6	998760

Face	Frequency
1	999647
2	999557
3	999571
4	1000376
5	1000701
6	1000148

Fig. 5.7 | Roll a six-sided die 6,000,000 times. (Part 2 of 2.)

As the sample outputs show, scaling and shifting the values produced by `nextInt` enables the program to simulate rolling a six-sided die. The application uses nested control

statements (the `switch` is nested inside the `for`) to determine the number of times each side of the die appears. The `for` statement (lines 20–46) iterates 6,000,000 times. During each iteration, line 22 produces a random value from 1 to 6. That value is then used as the controlling expression (line 25) of the `switch` statement (lines 25–45). Based on the face value, the `switch` statement increments one of the six counter variables during each iteration of the loop. This `switch` statement has no default case, because we have a case for every possible die value that the expression in line 22 could produce. Run the program, and observe the results. As you'll see, every time you run this program, it produces *different* results.

When we study arrays in Chapter 6, we'll show an elegant way to replace the entire `switch` statement in this program with a *single* statement. Then, when we study Java SE 8's new functional programming capabilities in Chapter 17, we'll show how to replace the loop that rolls the dice, the `switch` statement *and* the statement that displays the results with a *single* statement!

Generalized Scaling and Shifting of Random Numbers

Previously, we simulated the rolling of a six-sided die with the statement

```
int face = 1 + randomNumbers.nextInt(6);
```

This statement always assigns to variable `face` an integer in the range $1 \leq \text{face} \leq 6$. The *width* of this range (i.e., the number of consecutive integers in the range) is 6, and the *starting number* in the range is 1. In the preceding statement, the width of the range is determined by the number 6 that's passed as an argument to `SecureRandom` method `nextInt`, and the starting number of the range is the number 1 that's added to `randomNumbers.nextInt(6)`. We can generalize this result as

```
int number = shiftingValue + randomNumbers.nextInt(scalingFactor);
```

where *shiftingValue* specifies the *first number* in the desired range of consecutive integers and *scalingFactor* specifies *how many numbers* are in the range.

It's also possible to choose integers at random from sets of values other than ranges of consecutive integers. For example, to obtain a random value from the sequence 2, 5, 8, 11 and 14, you could use the statement

```
int number = 2 + 3 * randomNumbers.nextInt(5);
```

In this case, `randomNumbers.nextInt(5)` produces values in the range 0–4. Each value produced is multiplied by 3 to produce a number in the sequence 0, 3, 6, 9 and 12. We add 2 to that value to *shift* the range of values and obtain a value from the sequence 2, 5, 8, 11 and 14. We can generalize this result as

```
int number = shiftingValue +  
differenceBetweenValues * randomNumbers.nextInt(scalingFactor);
```

where *shiftingValue* specifies the first number in the desired range of values, *differenceBetweenValues* represents the *constant difference* between consecutive numbers in the sequence and *scalingFactor* specifies how many numbers are in the range.

A Note About Performance

Using `SecureRandom` instead of `Random` to achieve higher levels of security incurs a significant performance penalty. For “casual” applications, you might want to use class `Random` from package `java.util`—simply replace `SecureRandom` with `Random`.

5.10 Case Study: A Game of Chance; Introducing enum Types

A popular game of chance is a dice game known as craps, which is played in casinos and back alleys throughout the world. The rules of the game are straightforward:

You roll two dice. Each die has six faces, which contain one, two, three, four, five and six spots, respectively. After the dice have come to rest, the sum of the spots on the two upward faces is calculated. If the sum is 7 or 11 on the first throw, you win. If the sum is 2, 3 or 12 on the first throw (called “craps”), you lose (i.e., the “house” wins). If the sum is 4, 5, 6, 8, 9 or 10 on the first throw, that sum becomes your “point.” To win, you must continue rolling the dice until you “make your point” (i.e., roll that same point value). You lose by rolling a 7 before making your point.

Figure 5.8 simulates the game of craps, using methods to implement the game’s logic. The main method (lines 21–65) calls the rollDice method (lines 68–81) as necessary to roll the dice and compute their sum. The sample outputs show winning and losing on the first roll, and winning and losing on a subsequent roll.

```

1  // Fig. 5.8: Craps.java
2  // Craps class simulates the dice game craps.
3  import java.security.SecureRandom;
4
5  public class Craps
6  {
7      // create secure random number generator for use in method rollDice
8      private static final SecureRandom randomNumbers = new SecureRandom();
9
10     // enum type with constants that represent the game status
11     private enum Status { CONTINUE, WON, LOST };
12
13     // constants that represent common rolls of the dice
14     private static final int SNAKE_EYES = 2;
15     private static final int TREY = 3;
16     private static final int SEVEN = 7;
17     private static final int YO_LEVEN = 11;
18     private static final int BOX_CARS = 12;
19
20     // plays one game of craps
21     public static void main(String[] args)
22     {
23         int myPoint = 0; // point if no win or loss on first roll
24         Status gameStatus; // can contain CONTINUE, WON or LOST
25
26         int sumOfDice = rollDice(); // first roll of the dice
27
28         // determine game status and point based on first roll
29         switch (sumOfDice)
30         {

```

Fig. 5.8 | Craps class simulates the dice game craps. (Part I of 3.)

```

31     case SEVEN: // win with 7 on first roll
32     case YO_LEVEN: // win with 11 on first roll
33         gameStatus = Status.WON;
34         break;
35     case SNAKE_EYES: // lose with 2 on first roll
36     case TREY: // lose with 3 on first roll
37     case BOX_CARS: // lose with 12 on first roll
38         gameStatus = Status.LOST;
39         break;
40     default: // did not win or lose, so remember point
41         gameStatus = Status.CONTINUE; // game is not over
42         myPoint = sumOfDice; // remember the point
43         System.out.printf("Point is %d\n", myPoint);
44         break;
45 }
46
47 // while game is not complete
48 while (gameStatus == Status.CONTINUE) // not WON or LOST
49 {
50     sumOfDice = rollDice(); // roll dice again
51
52     // determine game status
53     if (sumOfDice == myPoint) // win by making point
54         gameStatus = Status.WON;
55     else
56         if (sumOfDice == SEVEN) // lose by rolling 7 before point
57             gameStatus = Status.LOST;
58 }
59
60 // display won or lost message
61 if (gameStatus == Status.WON)
62     System.out.println("Player wins");
63 else
64     System.out.println("Player loses");
65 }
66
67 // roll dice, calculate sum and display results
68 public static int rollDice()
69 {
70     // pick random die values
71     int die1 = 1 + randomNumbers.nextInt(6); // first die roll
72     int die2 = 1 + randomNumbers.nextInt(6); // second die roll
73
74     int sum = die1 + die2; // sum of die values
75
76     // display results of this roll
77     System.out.printf("Player rolled %d + %d = %d\n",
78         die1, die2, sum);
79
80     return sum;
81 }
82 } // end class Craps

```

Fig. 5.8 | Craps class simulates the dice game craps. (Part 2 of 3.)


```
Player rolled 5 + 6 = 11  
Player wins
```

```
Player rolled 5 + 4 = 9  
Point is 9  
Player rolled 4 + 2 = 6  
Player rolled 3 + 6 = 9  
Player wins
```

```
Player rolled 1 + 2 = 3  
Player loses
```

```
Player rolled 2 + 6 = 8  
Point is 8  
Player rolled 5 + 1 = 6  
Player rolled 2 + 1 = 3  
Player rolled 1 + 6 = 7  
Player loses
```

Fig. 5.8 | Craps class simulates the dice game craps. (Part 3 of 3.)

Method rollDice

In the rules of the game, the player must roll *two* dice on the first and all subsequent rolls. We declare method `rollDice` (lines 68–81) to roll the dice and compute and print their sum. Method `rollDice` is declared once, but it's called from two places (lines 26 and 50) in `main`, which contains the logic for one complete game of craps. Method `rollDice` takes no arguments, so it has an empty parameter list. Each time it's called, `rollDice` returns the sum of the dice, so the return type `int` is indicated in the method header (line 68). Although lines 71 and 72 look the same (except for the die names), they do not necessarily produce the same result. Each of these statements produces a *random* value in the range 1–6. Variable `randomNumbers` (used in lines 71–72) is *not* declared in the method. Instead it's declared as a `private static final` variable of the class and initialized in line 8. This enables us to create one `SecureRandom` object that's reused in each call to `rollDice`.

Method main's Local Variables

The game is reasonably involved. The player may win or lose on the first roll, or may win or lose on any subsequent roll. Method `main` (lines 21–65) uses local variable `myPoint` (line 23) to store the “point” if the player doesn't win or lose on the first roll, local variable `gameStatus` (line 24) to keep track of the overall game status and local variable `sumOfDice` (line 26) to hold the sum of the dice for the most recent roll. Variable `myPoint` is initialized to 0 to ensure that the application will compile. If you do not initialize `myPoint`, the compiler issues an error, because `myPoint` is not assigned a value in *every* case of the `switch` statement, and thus the program could try to use `myPoint` before it's assigned a value. By contrast, `gameStatus` *is* assigned a value in *every* case of the `switch` statement (including

the default case)—thus, it’s guaranteed to be initialized before it’s used, so we do not need to initialize it in line 24.

enum Type Status

Local variable `gameStatus` (line 24) is declared to be of a new type called `Status` (declared at line 11). Type `Status` is a private member of class `Craps`, because `Status` will be used only in that class. `Status` is a type called an **enum type**, which, in its simplest form, declares a set of constants represented by identifiers. An enum type is a special kind of class that’s introduced by the keyword `enum` and a type name (in this case, `Status`). As with classes, braces delimit an enum declaration’s body. Inside the braces is a comma-separated list of **enum constants**, each representing a unique value. The identifiers in an enum must be *unique*. You’ll learn more about enum types in Chapter 8.



Good Programming Practice 5.1

Use only uppercase letters in the names of enum constants to make them stand out and remind you that they’re not variables.

Variables of type `Status` can be assigned only the three constants declared in the enum (line 11) or a compilation error will occur. When the game is won, the program sets local variable `gameStatus` to `Status.WON` (lines 33 and 54). When the game is lost, the program sets local variable `gameStatus` to `Status.LOST` (lines 38 and 57). Otherwise, the program sets local variable `gameStatus` to `Status.CONTINUE` (line 41) to indicate that the game is not over and the dice must be rolled again.



Good Programming Practice 5.2

Using enum constants (like `Status.WON`, `Status.LOST` and `Status.CONTINUE`) rather than literal values (such as 0, 1 and 2) makes programs easier to read and maintain.

Logic of the main Method

Line 26 in `main` calls `rollDice`, which picks two random values from 1 to 6, displays the values of the first die, the second die and their sum, and returns the sum. Method `main` next enters the switch statement (lines 29–45), which uses the `sumOfDice` value from line 26 to determine whether the game has been won or lost, or should continue with another roll. The values that result in a win or loss on the first roll are declared as `private static final int` constants in lines 14–18. The identifier names use casino parlance for these sums. These constants, like enum constants, are declared by convention with all capital letters, to make them stand out in the program. Lines 31–34 determine whether the player won on the first roll with `SEVEN` (7) or `YO_LEVEN` (11). Lines 35–39 determine whether the player lost on the first roll with `SNAKE_EYES` (2), `TREY` (3), or `BOX_CARS` (12). After the first roll, if the game is not over, the default case (lines 40–44) sets `gameStatus` to `Status.CONTINUE`, saves `sumOfDice` in `myPoint` and displays the point.

If we’re still trying to “make our point” (i.e., the game is continuing from a prior roll), lines 48–58 execute. Line 50 rolls the dice again. If `sumOfDice` matches `myPoint` (line 53), line 54 sets `gameStatus` to `Status.WON`, then the loop terminates because the game is complete. If `sumOfDice` is `SEVEN` (line 56), line 57 sets `gameStatus` to `Status.LOST`, and the loop terminates because the game is complete. When the game completes, lines 61–64 display a message indicating whether the player won or lost, and the program terminates.

The program uses the various program-control mechanisms we've discussed. The `Craps` class uses two methods—`main` and `rollDice` (called twice from `main`)—and the `switch`, `while`, `if...else` and nested `if` control statements. Note also the use of multiple case labels in the `switch` statement to execute the same statements for sums of `SEVEN` and `YO_LEVEN` (lines 31–32) and for sums of `SNAKE_EYES`, `TREY` and `BOX_CARS` (lines 35–37).

Why Some Constants Are Not Defined as `enum` Constants

You might be wondering why we declared the sums of the dice as `private static final int` constants rather than as `enum` constants. The reason is that the program must compare the `int` variable `sumOfDice` (line 26) to these constants to determine the outcome of each roll. Suppose we declared `enum Sum` containing constants (e.g., `Sum.SNAKE_EYES`) representing the five sums used in the game, then used these constants in the `switch` statement (lines 29–45). Doing so would prevent us from using `sumOfDice` as the `switch` statement's controlling expression, because Java does *not* allow an `int` to be compared to an `enum` constant. To achieve the same functionality as the current program, we would have to use a variable `currentSum` of type `Sum` as the `switch`'s controlling expression. Unfortunately, Java does not provide an easy way to convert an `int` value to a particular `enum` constant. This could be done with a separate `switch` statement. This would be cumbersome and would not improve the program's readability (thus defeating the purpose of using an `enum`).

5.11 Scope of Declarations

You've seen declarations of various Java entities, such as classes, methods, variables and parameters. Declarations introduce names that can be used to refer to such Java entities. The **scope** of a declaration is the portion of the program that can refer to the declared entity by its name. Such an entity is said to be “in scope” for that portion of the program. This section introduces several important scope issues.

The basic scope rules are as follows:

1. The scope of a parameter declaration is the body of the method in which the declaration appears.
2. The scope of a local-variable declaration is from the point at which the declaration appears to the end of that block.
3. The scope of a local-variable declaration that appears in the initialization section of a `for` statement's header is the body of the `for` statement and the other expressions in the header.
4. A method or field's scope is the entire body of the class.

Any block may contain variable declarations. If a local variable or parameter in a method has the same name as a field of the class, the field is *hidden* until the block terminates execution—this is called **shadowing**. You can access a shadowed `static` variable of a class by preceding its name with the class's name and a dot (`.`), as in `ClassName.x`. (Section 7.2.1 discusses shadowing of so-called instance variables.)

Figure 5.9 demonstrates scoping issues with `static` and local variables. Line 7 declares and initializes the `static` variable `x` to 1. This variable is *shadowed* in any block (or method) that declares a local variable named `x`. Method `main` (lines 11–23) declares a local variable

x (line 13) and initializes it to 5. This local variable's value is output to show that the static variable x (whose value is 1) is *shadowed* in main. The program declares two other methods—`useLocalVariable` (lines 26–35) and `useField` (lines 38–45)—that each take no arguments and return no results. Method `main` calls each method twice (lines 17–20). Method `useLocalVariable` declares local variable x (line 28). When `useLocalVariable` is first called (line 17), it creates local variable x and initializes it to 25 (line 28), outputs the value of x (lines 30–31), increments x (line 32) and outputs the value of x again (lines 33–34). When `useLocalVariable` is called a second time (line 19), it *recreates* local variable x and *reinitializes* it to 25, so the output of each `useLocalVariable` call is identical.

```

1 // Fig. 5.9: Scope.java
2 // Scope class demonstrates field and local variable scopes.
3
4 public class Scope
5 {
6     // field that is accessible to all methods of this class
7     private static int x = 1;
8
9     // method main creates and initializes local variable x
10    // and calls methods useLocalVariable and useField
11    public static void main(String[] args)
12    {
13        int x = 5; // method's local variable x shadows field x
14
15        System.out.printf("local x in main is %d\n", x);
16
17        useLocalVariable(); // useLocalVariable has local x
18        useField(); // useField uses class Scope's field x
19        useLocalVariable(); // useLocalVariable reinitializes local x
20        useField(); // class Scope's field x retains its value
21
22        System.out.printf("\nlocal x in main is %d\n", x);
23    }
24
25    // create and initialize local variable x during each call
26    public static void useLocalVariable()
27    {
28        int x = 25; // initialized each time useLocalVariable is called
29
30        System.out.printf(
31            "%nlocal x on entering method useLocalVariable is %d\n", x);
32        ++x; // modifies this method's local variable x
33        System.out.printf(
34            "local x before exiting method useLocalVariable is %d\n", x);
35    }
36
37    // modify class Scope's field x during each call
38    public static void useField()
39    {
40        System.out.printf(
41            "%nfield x on entering method useField is %d\n", x);

```

Fig. 5.9 | Scope class demonstrates field and local-variable scopes. (Part 1 of 2.)

```

42     x *= 10; // modifies class Scope's field x
43     System.out.printf(
44         "field x before exiting method useField is %d\n", x);
45     }
46 } // end class Scope

```

```

local x in main is 5

local x on entering method useLocalVariable is 25
local x before exiting method useLocalVariable is 26

field x on entering method useField is 1
field x before exiting method useField is 10

local x on entering method useLocalVariable is 25
local x before exiting method useLocalVariable is 26

field x on entering method useField is 10
field x before exiting method useField is 100

local x in main is 5

```

Fig. 5.9 | Scope class demonstrates field and local-variable scopes. (Part 2 of 2.)

Method `useField` does not declare any local variables. Therefore, when it refers to `x`, the static variable `x` (line 7) of the class is used. When method `useField` is first called (line 18), it outputs the value (1) of static variable `x` (lines 40–41), multiplies it by 10 (line 42) and outputs its value (10) again (lines 43–44) before returning. The next time method `useField` is called (line 20), the static variable has its modified value (10), so the method outputs 10, then 100. Finally, in method `main`, the program outputs the value of local variable `x` again (line 22) to show that none of the method calls modified `main`'s local variable `x`, because the methods all referred to variables named `x` in other scopes.

Principle of Least Privilege

In a general sense, “things” should have the capabilities they need to get their job done, but no more. An example is the scope of a variable. A variable should not be visible when it's not needed.



Good Programming Practice 5.3

Declare local variables as close to where they're first used as possible.

5.12 Method Overloading

Methods of the *same* name can be declared in the same class, as long as they have *different* sets of parameters (determined by the number, types and order of the parameters)—this is called **method overloading**. When an overloaded method is called, the compiler selects the appropriate method by examining the number, types and order of the arguments in the call. Method overloading is commonly used to create several methods with the *same* name that perform the *same* or *similar* tasks, but on *different* types or *different* numbers of

arguments. For example, Math methods `abs`, `min` and `max` (summarized in Section 5.3) are overloaded with four versions each:

1. One with two `double` parameters.
2. One with two `float` parameters.
3. One with two `int` parameters.
4. One with two `long` parameters.

Our next example demonstrates declaring and invoking overloaded methods. We demonstrate overloaded constructors in Chapter 8.

Declaring Overloaded Methods

Class `MethodOverload` (Fig. 5.10) includes two overloaded versions of method `square`—one that calculates the square of an `int` (and returns an `int`) and one that calculates the square of a `double` (and returns a `double`). Although these methods have the same name and similar parameter lists and bodies, think of them simply as *different* methods. It may help to think of the method names as “square of `int`” and “square of `double`,” respectively.

Line 9 invokes method `square` with the argument 7. Literal integer values are treated as type `int`, so the method call in line 9 invokes the version of `square` at lines 14–19 that specifies an `int` parameter. Similarly, line 10 invokes method `square` with the argument

```

1 // Fig. 5.10: MethodOverload.java
2 // Overloaded method declarations.
3
4 public class MethodOverload
5 {
6     // test overloaded square methods
7     public static void main(String[] args)
8     {
9         System.out.printf("Square of integer 7 is %d\n", square(7));
10        System.out.printf("Square of double 7.5 is %f\n", square(7.5));
11    }
12
13    // square method with int argument
14    public static int square(int intValue)
15    {
16        System.out.printf("%nCalled square with int argument: %d\n",
17                           intValue);
18        return intValue * intValue;
19    }
20
21    // square method with double argument
22    public static double square(double doubleValue)
23    {
24        System.out.printf("%nCalled square with double argument: %f\n",
25                           doubleValue);
26        return doubleValue * doubleValue;
27    }
28 } // end class MethodOverload

```

Fig. 5.10 | Overloaded method declarations. (Part 1 of 2.)

```

Called square with int argument: 7
Square of integer 7 is 49

Called square with double argument: 7.500000
Square of double 7.5 is 56.250000

```

Fig. 5.10 | Overloaded method declarations. (Part 2 of 2.)

7.5. Literal floating-point values are treated as type `double`, so the method call in line 10 invokes the version of `square` at lines 22–27 that specifies a `double` parameter. Each method first outputs a line of text to prove that the proper method was called in each case. The values in lines 10 and 24 are displayed with the format specifier `%f`. We did not specify a precision in either case. By default, floating-point values are displayed with six digits of precision if the precision is *not* specified in the format specifier.

Distinguishing Between Overloaded Methods

The compiler distinguishes overloaded methods by their **signatures**—a combination of the method’s *name* and the *number, types and order* of its parameters, but *not* its return type. If the compiler looked only at method names during compilation, the code in Fig. 5.10 would be ambiguous—the compiler would not know how to distinguish between the two `square` methods (lines 14–19 and 22–27). Internally, the compiler uses longer method names that include the original method name, the types of each parameter and the exact order of the parameters to determine whether the methods in a class are *unique* in that class.

For example, in Fig. 5.10, the compiler might (internally) use the logical name “square of `int`” for the `square` method that specifies an `int` parameter and “square of `double`” for the `square` method that specifies a `double` parameter (the actual names the compiler uses are messier). If `method1`’s declaration begins as

```
void method1(int a, float b)
```

then the compiler might use the logical name “method1 of `int` and `float`.” If the parameters are specified as

```
void method1(float a, int b)
```

then the compiler might use the logical name “method1 of `float` and `int`.” The *order* of the parameter types is important—the compiler considers the preceding two `method1` headers to be *distinct*.

Return Types of Overloaded Methods

In discussing the logical names of methods used by the compiler, we did not mention the return types of the methods. *Method calls cannot be distinguished only by return type*. If you had overloaded methods that differed *only* by their return types and you called one of the methods in a standalone statement as in:

```
square(2);
```

the compiler would *not* be able to determine the version of the method to call, because the return value is *ignored*. When two methods have the *same* signature and *different* return types,

the compiler issues an error message indicating that the method is already defined in the class. Overloaded methods *can* have *different* return types if the methods have *different* parameter lists. Also, overloaded methods need *not* have the same number of parameters.



Common Programming Error 5.9

Declaring overloaded methods with identical parameter lists is a compilation error regardless of whether the return types are different.

5.13 (Optional) GUI and Graphics Case Study: Colors and Filled Shapes

Although you can create many interesting designs with just lines and basic shapes, class `Graphics` provides many more capabilities. The next two features we introduce are colors and filled shapes. Adding color enriches the drawings a user sees on the computer screen. Shapes can be filled with solid colors.

Colors displayed on computer screens are defined by their *red*, *green*, and *blue* components (called **RGB values**) that have integer values from 0 to 255. The higher the value of a component color, the richer that color's shade will be. Java uses class `Color` (package `java.awt`) to represent colors using their RGB values. For convenience, class `Color` contains various predefined static `Color` objects—`BLACK`, `BLUE`, `CYAN`, `DARK_GRAY`, `GRAY`, `GREEN`, `LIGHT_GRAY`, `MAGENTA`, `ORANGE`, `PINK`, `RED`, `WHITE` and `YELLOW`. Each can be accessed via the class name and a dot (`.`) as in `Color.RED`. You can create custom colors by passing the red-, green- and blue-component values to class `Color`'s constructor:

```
public Color(int r, int g, int b)
```

Graphics methods `fillRect` and `fillOval` draw filled rectangles and ovals, respectively. These have the same parameters as `drawRect` and `drawOval`; the first two are the coordinates for the *upper-left corner* of the shape, while the next two determine the *width* and *height*. The example in Fig. 5.11 demonstrates colors and filled shapes by drawing and displaying a yellow smiley face on the screen.

```
1 // Fig. 5.11: DrawSmiley.java
2 // Drawing a smiley face using colors and filled shapes.
3 import java.awt.Color;
4 import java.awt.Graphics;
5 import javax.swing.JPanel;
6
7 public class DrawSmiley extends JPanel
8 {
9     public void paintComponent(Graphics g)
10    {
11        super.paintComponent(g);
12
13        // draw the face
14        g.setColor(Color.YELLOW);
15        g.fillOval(10, 10, 200, 200);
16    }
```

Fig. 5.11 | Drawing a smiley face using colors and filled shapes. (Part 1 of 2.)


```
17      // draw the eyes
18      g.setColor(Color.BLACK);
19      g.fillOval(55, 65, 30, 30);
20      g.fillOval(135, 65, 30, 30);
21
22      // draw the mouth
23      g.fillOval(50, 110, 120, 60);
24
25      // "touch up" the mouth into a smile
26      g.setColor(Color.YELLOW);
27      g.fillRect(50, 110, 120, 30);
28      g.fillOval(50, 120, 120, 40);
29  }
30
31  public static void main(String[] args)
32  {
33      DrawSmiley panel = new DrawSmiley();
34      JFrame application = new JFrame();
35
36      application.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
37      application.add(panel);
38      application.setSize(230, 250);
39      application.setVisible(true);
40  }
41  } // end class DrawSmiley
```




Fig. 5.11 | Drawing a smiley face using colors and filled shapes. (Part 2 of 2.)

The import statements in lines 3–5 import classes `Color`, `Graphics` and `JPanel`. Class `DrawSmiley` uses class `Color` to specify drawing colors, and uses class `Graphics` to draw.

Class `JPanel` again provides the area in which we draw. Line 14 in method `paintComponent` uses `Graphics` method `setColor` to set the current drawing color to `Color.YELLOW`. Method `setColor` requires one argument, the `Color` to set as the drawing color. In this case, we use the predefined object `Color.YELLOW`.

Line 15 draws a circle with diameter 200 to represent the face—when the width and height arguments are identical, method `fillOval` draws a circle. Next, line 18 sets the color to `Color.Black`, and lines 19–20 draw the eyes. Line 23 draws the mouth as an oval, but this is not quite what we want.

To create a happy face, we'll touch up the mouth. Line 26 sets the color to `Color.YELLOW`, so any shapes we draw will blend in with the face. Line 27 draws a rectangle that's half the mouth's height. This erases the top half of the mouth, leaving just the bottom half. To create a better smile, line 28 draws another oval to slightly cover the upper portion of the mouth. Method `main` (lines 31–40) creates and displays a `JFrame` containing the drawing. When the `JFrame` is displayed, the system calls method `paintComponent` to draw the smiley face.

GUI and Graphics Case Study Exercises

5.1 Using method `fillOval`, draw a bull's-eye that alternates between two random colors, as in Fig. 5.12. Use the constructor `Color(int r, int g, int b)` with random arguments to generate random colors.

5.2 Create a program that draws 10 random filled shapes in random colors, positions and sizes (Fig. 5.13). Method `paintComponent` should contain a loop that iterates 10 times. In each iteration, the loop should determine whether to draw a filled rectangle or an oval, create a random color and choose coordinates and dimensions at random. The coordinates should be chosen based on the panel's width and height. Lengths of sides should be limited to half the width or height of the window.




Fig. 5.12 | A bulls-eye with two alternating, random colors.




Fig. 5.13 | Randomly generated shapes.

5.14 Wrap-Up

In this chapter, you learned about method declarations and how to call `static` methods. You learned how to use operators `+` and `+=` to perform string concatenations. We discussed how the method-call stack and stack frames keep track of the methods that have been called and where each method must return to when it completes its task. We also discussed Java's promotion rules for converting implicitly between primitive types and how to perform explicit conversions with cast operators. Next, you learned about some of the commonly used packages in the Java API.

You saw how to declare named constants using both `enum` types and `private static final` variables. You used class `SecureRandom` to generate random numbers for simulations. You also learned about the scope of fields and local variables in a class. Finally, you learned that multiple methods in one class can be overloaded by providing methods with the same name and different signatures. Such methods can be used to perform the same or similar tasks using different types or different numbers of parameters.

In Chapter 6, you'll learn how to maintain lists and tables of data in arrays. You'll see a more elegant implementation of the application that rolls a die 6,000,000 times. You'll also learn how to access an application's command-line arguments that are passed to method `main` when an application begins execution.

Summary

Section 5.1 Introduction

- Experience has shown that the best way to develop and maintain a large program is to construct it from small, simple pieces, or modules. This technique is called divide and conquer (p. 165).

Section 5.2 Program Modules in Java

- Methods are declared within classes. Classes are typically grouped into packages so they can be imported and reused.
- Methods allow you to modularize a program by separating its tasks into self-contained units. The statements in a method are written only once and hidden from other methods.
- Using existing methods as building blocks to create new programs is a form of software reusability (p. 166) that allows you to avoid repeating code within a program.

Section 5.3 static Methods, static Fields and Class Math

- A method call specifies the name of the method to call and provides the arguments that the called method requires to perform its task. When the method call completes, the method returns either a result, or simply control, to its caller.
- A class may contain `static` methods to perform common tasks that do not require an object of the class. Any data a `static` method might require to perform its tasks can be sent to the method as arguments in a method call. A `static` method is called by specifying the name of the class in which the method is declared followed by a dot (`.`) and the method name, as in

ClassName.methodName(arguments)

- Class `Math` provides `static` methods for performing common mathematical calculations.
- `Math.PI` (3.141592653589793; p. 169) is the ratio of a circle's circumference to its diameter. `Math.E` (2.718281828459045; p. 169) is the base value for natural logarithms.

- `Math.PI` and `Math.E` are declared `public`, `static` and `final`. Making them `public` allows you to use these fields in your own classes. Making them `static` allows them to be accessed via the class name `Math` and a dot (`.`) separator, just like class `Math`'s methods. Making them `final` (p. 169) indicates that they are constants—their values cannot be changed after they're initialized.
- When you execute the Java Virtual Machine (JVM) with the `java` command, the JVM loads the class you specify and uses that class name to invoke method `main`. You can specify additional command-line arguments (p. 169) that the JVM will pass to your application.
- You can place a `main` method in every class you declare—only the `main` method in the class you use to execute the application will be called by the `java` command.

Section 5.4 Declaring Methods

- Class, method and variable names are identifiers. By convention all use camel case names. Class names begin with an uppercase letter, and method and variable names begin with a lowercase letter.
- Parameters are declared in a comma-separated parameter list (p. 171), which is located inside the parentheses that follow the method name in the method declaration. Multiple parameters are separated by commas. Each parameter must specify a type followed by a variable name.
- Every method's body is delimited by left and right braces (`{` and `}`).
- Each method's body contains one or more statements that perform the method's task(s).
- The method's return type specifies the type of data returned to a method's caller. Keyword `void` indicates that a method will perform a task but will not return any information.
- Empty parentheses following a method name indicate that the method does not require any parameters to perform its task.
- When a method that specifies a return type (p. 171) other than `void` is called and completes its task, the method must return a result to its calling method.
- The `return` statement (p. 172) passes a value from a called method back to its caller.
- When a method is called, the program makes a copy of the method's argument values and assigns them to the method's corresponding parameters. When program control returns to the point in the program where the method was called, the method's parameters are removed from memory.
- Strings can be concatenated (p. 172) using operator `+`, which places the characters of the right operand at the end of those in the left operand.
- Every primitive value and object in Java can be represented as a `String`.
- If a `boolean` is concatenated with a `String`, the word `"true"` or the word `"false"` is used to represent the `boolean` value.
- All objects in Java have a special method named `toString` that returns a `String` representation of the object's contents. When an object is concatenated with a `String`, the JVM implicitly calls the object's `toString` method to obtain the string representation of the object.
- You can break large `String` literals into several smaller `Strings` and place them on multiple lines of code for readability, then reassemble the `Strings` using concatenation.

Section 5.5 Notes on Declaring and Using Methods

- There are three ways to call a method—using a method name by itself to call another method of the same class; using an object's variable name followed by a dot (`.`) and the method name to call a method of the object; and using the class name and a dot (`.`) to call a `static` method of a class.
- There are three ways to return control to a statement that calls a method. If the method does not return a result, control returns when the program flow reaches the method-ending right brace or when the statement

return;

is executed. If the method returns a result, the statement

```
return expression;
```

evaluates the *expression*, then immediately returns the resulting value to the caller.

Section 5.6 Method-Call Stack and Stack Frames

- Stacks (p. 174) are known as last-in, first-out (LIFO) data structures—the last item pushed (inserted) onto the stack is the first item popped (removed) from the stack.
- A called method must know how to return to its caller, so the return address of the calling method is pushed onto the method-call stack when the method is called. If a series of method calls occurs, the successive return addresses are pushed onto the stack in last-in, first-out order so that the last method to execute will be the first to return to its caller.
- The method-call stack (p. 174) contains the memory for the local variables used in each invocation of a method during a program's execution. This data is known as the method call's stack frame or activation record. When a method call is made, the stack frame for that method call is pushed onto the method-call stack. When the method returns to its caller, its stack frame call is popped off the stack and the local variables are no longer known to the program.
- If there are more method calls than can have their stack frames stored on the method-call stack, an error known as a stack overflow (p. 174) occurs. The application will compile correctly, but its execution causes a stack overflow.

Section 5.7 Argument Promotion and Casting

- Argument promotion (p. 175) converts an argument's value to the type that the method expects to receive in its corresponding parameter.
- Promotion rules (p. 175) apply to expressions containing values of two or more primitive types and to primitive-type values passed as arguments to methods. Each value is promoted to the "highest" type in the expression. In cases where information may be lost due to conversion, the Java compiler requires you to use a cast operator to explicitly force the conversion to occur.

Section 5.9 Case Study: Secure Random-Number Generation

- SecureRandom objects can produce nondeterministic random values.
- SecureRandom method `nextInt` (p. 178) generates a random `int` value.
- Class SecureRandom provides another version of method `nextInt` that receives an `int` argument and returns a value from 0 up to, but not including, the argument's value.
- Random numbers in a range (p. 179) can be generated with

```
int number = shiftingValue + randomNumbers.nextInt(scalingFactor);
```

where *shiftingValue* specifies the first number in the desired range of consecutive integers, and *scalingFactor* specifies how many numbers are in the range.

- Random numbers can be chosen from nonconsecutive integer ranges, as in

```
int number = shiftingValue +  
             differenceBetweenValues * randomNumbers.nextInt(scalingFactor);
```

where *shiftingValue* specifies the first number in the range of values, *differenceBetweenValues* represents the difference between consecutive numbers in the sequence and *scalingFactor* specifies how many numbers are in the range.

Section 5.10 Case Study: A Game of Chance; Introducing `enum` Types

- An `enum` type (p. 186) is introduced by the keyword `enum` and a type name. As with any class, braces (`{` and `}`) delimit the body of an `enum` declaration. Inside the braces is a comma-separated

list of enum constants, each representing a unique value. The identifiers in an enum must be unique. Variables of an enum type can be assigned only constants of that enum type.

- Constants can also be declared as `private static final` variables. Such constants are declared by convention with all capital letters to make them stand out in the program.

Section 5.11 Scope of Declarations

- Scope (p. 187) is the portion of the program in which an entity, such as a variable or a method, can be referred to by its name. Such an entity is said to be “in scope” for that portion of the program.
- The scope of a parameter declaration is the body of the method in which the declaration appears.
- The scope of a local-variable declaration is from the point at which the declaration appears to the end of that block.
- The scope of a local-variable declaration that appears in the initialization section of a `for` statement’s header is the body of the `for` statement and the other expressions in the header.
- The scope of a method or field of a class is the entire body of the class. This enables a class’s methods to use simple names to call the class’s other methods and to access the class’s fields.
- Any block may contain variable declarations. If a local variable or parameter in a method has the same name as a variable of the class, the class’s variable is shadowed (p. 187) until the block terminates execution.

Section 5.12 Method Overloading

- Java allows overloaded methods (p. 189) in a class, as long as the methods have different sets of parameters (determined by the number, order and types of the parameters).
- Overloaded methods are distinguished by their signatures (p. 191)—combinations of the methods’ names and the number, types and order of their parameters, but not their return types.

Self-Review Exercises

5.1 Fill in the blanks in each of the following statements:

- A method is invoked with a(n) _____.
- A variable known only within the method in which it’s declared is called a(n) _____.
- The _____ statement in a called method can be used to pass the value of an expression back to the calling method.
- The keyword _____ indicates that a method does not return a value.
- Data can be added or removed only from the _____ of a stack.
- Stacks are known as _____ data structures; the last item pushed (inserted) onto the stack is the first item popped (removed) from the stack.
- The three ways to return control from a called method to a caller are _____, _____ and _____.
- An object of class _____ produces truly random numbers.
- The method-call stack contains the memory for local variables on each invocation of a method during a program’s execution. This data, stored as a portion of the method-call stack, is known as the _____ or _____ of the method call.
- If there are more method calls than can be stored on the method-call stack, an error known as a(n) _____ occurs.
- The _____ of a declaration is the portion of a program that can refer to the entity in the declaration by name.
- It’s possible to have several methods with the same name that each operate on different types or numbers of arguments. This feature is called method _____.

- 5.2** For the class `Craps` in Fig. 5.8, state the scope of each of the following entities:
- the variable `randomNumbers`.
 - the variable `die1`.
 - the method `rollDice`.
 - the method `main`.
 - the variable `sumOfDice`.
- 5.3** Write an application that tests whether the examples of the `Math` class method calls shown in Fig. 5.2 actually produce the indicated results.

- 5.4** Give the method header for each of the following methods:
- Method `hypotenuse`, which takes two double-precision, floating-point arguments `side1` and `side2` and returns a double-precision, floating-point result.
 - Method `smallest`, which takes three integers `x`, `y` and `z` and returns an integer.
 - Method `instructions`, which does not take any arguments and does not return a value. [Note: Such methods are commonly used to display instructions to a user.]
 - Method `intToFloat`, which takes integer argument `number` and returns a `float`.

- 5.5** Find the error in each of the following program segments. Explain how to correct the error.

- ```

void g()
{
 System.out.println("Inside method g");

 void h()
 {
 System.out.println("Inside method h");
 }
}

```
- ```

int sum(int x, int y)
{
    int result;
    result = x + y;
}

```
- ```

void f(float a);
{
 float a;
 System.out.println(a);
}

```
- ```

void product()
{
    int a = 6, b = 5, c = 4, result;
    result = a * b * c;
    System.out.printf("Result is %d\n", result);
    return result;
}

```

- 5.6** Declare method `sphereVolume` to calculate and return the volume of the sphere. Use the following statement to calculate the volume:

```
double volume = (4.0 / 3.0) * Math.PI * Math.pow(radius, 3)
```

Write a Java application that prompts the user for the `double` radius of a sphere, calls `sphereVolume` to calculate the volume and displays the result.

Answers to Self-Review Exercises

5.1 a) method call. b) local variable. c) return. d) void. e) top. f) last-in, first-out (LIFO). g) return; or return *expression*; or encountering the closing right brace of a method. h) SecureRandom. i) stack frame, activation record. j) stack overflow. k) scope. l) method overloading.

5.2 a) class body. b) block that defines method `rollDice`'s body. c) class body. d) class body. e) block that defines method `main`'s body.

5.3 The following solution demonstrates the `Math` class methods in Fig. 5.2:

```

1 // Exercise 5.3: MathTest.java
2 // Testing the Math class methods.
3 public class MathTest
4 {
5     public static void main(String[] args)
6     {
7         System.out.printf("Math.abs(23.7) = %f\n", Math.abs(23.7));
8         System.out.printf("Math.abs(0.0) = %f\n", Math.abs(0.0));
9         System.out.printf("Math.abs(-23.7) = %f\n", Math.abs(-23.7));
10        System.out.printf("Math.ceil(9.2) = %f\n", Math.ceil(9.2));
11        System.out.printf("Math.ceil(-9.8) = %f\n", Math.ceil(-9.8));
12        System.out.printf("Math.cos(0.0) = %f\n", Math.cos(0.0));
13        System.out.printf("Math.exp(1.0) = %f\n", Math.exp(1.0));
14        System.out.printf("Math.exp(2.0) = %f\n", Math.exp(2.0));
15        System.out.printf("Math.floor(9.2) = %f\n", Math.floor(9.2));
16        System.out.printf("Math.floor(-9.8) = %f\n", Math.floor(-9.8));
17        System.out.printf("Math.log(Math.E) = %f\n", Math.log(Math.E));
18        System.out.printf("Math.log(Math.E * Math.E) = %f\n",
19            Math.log(Math.E * Math.E));
20        System.out.printf("Math.max(2.3, 12.7) = %f\n", Math.max(2.3, 12.7));
21        System.out.printf("Math.max(-2.3, -12.7) = %f\n",
22            Math.max(-2.3, -12.7));
23        System.out.printf("Math.min(2.3, 12.7) = %f\n", Math.min(2.3, 12.7));
24        System.out.printf("Math.min(-2.3, -12.7) = %f\n",
25            Math.min(-2.3, -12.7));
26        System.out.printf("Math.pow(2.0, 7.0) = %f\n", Math.pow(2.0, 7.0));
27        System.out.printf("Math.pow(9.0, 0.5) = %f\n", Math.pow(9.0, 0.5));
28        System.out.printf("Math.sin(0.0) = %f\n", Math.sin(0.0));
29        System.out.printf("Math.sqrt(900.0) = %f\n", Math.sqrt(900.0));
30        System.out.printf("Math.tan(0.0) = %f\n", Math.tan(0.0));
31    } // end main
32 } // end class MathTest

```

```

Math.abs(23.7) = 23.700000
Math.abs(0.0) = 0.000000
Math.abs(-23.7) = 23.700000
Math.ceil(9.2) = 10.000000
Math.ceil(-9.8) = -9.000000
Math.cos(0.0) = 1.000000
Math.exp(1.0) = 2.718282
Math.exp(2.0) = 7.389056
Math.floor(9.2) = 9.000000
Math.floor(-9.8) = -10.000000
Math.log(Math.E) = 1.000000
Math.log(Math.E * Math.E) = 2.000000
Math.max(2.3, 12.7) = 12.700000
Math.max(-2.3, -12.7) = -2.300000
Math.min(2.3, 12.7) = 2.300000
Math.min(-2.3, -12.7) = -12.700000

```



```

Math.pow(2.0, 7.0) = 128.000000
Math.pow(9.0, 0.5) = 3.000000
Math.sin(0.0) = 0.000000
Math.sqrt(900.0) = 30.000000
Math.tan(0.0) = 0.000000

```

- 5.4**
- a) **double** hypotenuse(**double** side1, **double** side2)
 - b) **int** smallest(**int** x, **int** y, **int** z)
 - c) **void** instructions()
 - d) **float** intToFloat(**int** number)
- 5.5**
- a) Error: Method h is declared within method g.
Correction: Move the declaration of h outside the declaration of g.
 - b) Error: The method is supposed to return an integer, but does not.
Correction: Delete the variable result, and place the statement

```
return x + y;
```

in the method, or add the following statement at the end of the method body:

```
return result;
```
 - c) Error: The semicolon after the right parenthesis of the parameter list is incorrect, and the parameter a should not be redeclared in the method.
Correction: Delete the semicolon after the right parenthesis of the parameter list, and delete the declaration `float a;`.
 - d) Error: The method returns a value when it's not supposed to.
Correction: Change the return type from `void` to `int`.
- 5.6** The following solution calculates the volume of a sphere, using the radius entered by the user:

```

1 // Exercise 5.6: Sphere.java
2 // Calculate the volume of a sphere.
3 import java.util.Scanner;
4
5 public class Sphere
6 {
7     // obtain radius from user and display volume of sphere
8     public static void main(String[] args)
9     {
10         Scanner input = new Scanner(System.in);
11
12         System.out.print("Enter radius of sphere: ");
13         double radius = input.nextDouble();
14
15         System.out.printf("Volume is %f\n", sphereVolume(radius));
16     } // end method determineSphereVolume
17
18     // calculate and return sphere volume
19     public static double sphereVolume(double radius)
20     {
21         double volume = (4.0 / 3.0) * Math.PI * Math.pow(radius, 3);
22         return volume;
23     } // end method sphereVolume
24 } // end class Sphere

```

```

Enter radius of sphere: 4
Volume is 268.082573

```

Exercises

5.7 What is the value of x after each of the following statements is executed?

- a) `x = Math.abs(7.5);`
- b) `x = Math.floor(7.5);`
- c) `x = Math.abs(0.0);`
- d) `x = Math.ceil(0.0);`
- e) `x = Math.abs(-6.4);`
- f) `x = Math.ceil(-6.4);`
- g) `x = Math.ceil(-Math.abs(-8 + Math.floor(-5.5)));`

5.8 (*Parking Charges*) A parking garage charges a \$2.00 minimum fee to park for up to three hours. The garage charges an additional \$0.50 per hour for each hour *or part thereof* in excess of three hours. The maximum charge for any given 24-hour period is \$10.00. Assume that no car parks for longer than 24 hours at a time. Write an application that calculates and displays the parking charges for each customer who parked in the garage yesterday. You should enter the hours parked for each customer. The program should display the charge for the current customer and should calculate and display the running total of yesterday's receipts. It should use the method `calculateCharges` to determine the charge for each customer.

5.9 (*Rounding Numbers*) `Math.floor` can be used to round values to the nearest integer—e.g.,

```
y = Math.floor(x + 0.5);
```

will round the number x to the nearest integer and assign the result to y . Write an application that reads `double` values and uses the preceding statement to round each of the numbers to the nearest integer. For each number processed, display both the original number and the rounded number.

5.10 (*Rounding Numbers*) To round numbers to specific decimal places, use a statement like

```
y = Math.floor(x * 10 + 0.5) / 10;
```

which rounds x to the tenths position (i.e., the first position to the right of the decimal point), or

```
y = Math.floor(x * 100 + 0.5) / 100;
```

which rounds x to the hundredths position (i.e., the second position to the right of the decimal point). Write an application that defines four methods for rounding a number x in various ways:

- a) `roundToInteger(number)`
- b) `roundToTenths(number)`
- c) `roundToHundredths(number)`
- d) `roundToThousandths(number)`

For each value read, your program should display the original value, the number rounded to the nearest integer, the number rounded to the nearest tenth, the number rounded to the nearest hundredth and the number rounded to the nearest thousandth.

5.11 Answer each of the following questions:

- a) What does it mean to choose numbers “at random”?
- b) Why is the `nextInt` method of class `SecureRandom` useful for simulating games of chance?
- c) Why is it often necessary to scale or shift the values produced by a `SecureRandom` object?
- d) Why is computerized simulation of real-world situations a useful technique?

5.12 Write statements that assign random integers to the variable n in the following ranges:

- a) $1 \leq n \leq 2$.
- b) $1 \leq n \leq 100$.
- c) $0 \leq n \leq 9$.
- d) $1000 \leq n \leq 1112$.

- e) $-1 \leq n \leq 1$.
- f) $-3 \leq n \leq 11$.

5.13 Write statements that will display a random number from each of the following sets:

- a) 2, 4, 6, 8, 10.
- b) 3, 5, 7, 9, 11.
- c) 6, 10, 14, 18, 22.

5.14 (*Exponentiation*) Write a method `integerPower(base, exponent)` that returns the value of $\text{base}^{\text{exponent}}$

For example, `integerPower(3, 4)` calculates 3^4 (or $3 * 3 * 3 * 3$). Assume that `exponent` is a positive, nonzero integer and that `base` is an integer. Use a `for` or `while` statement to control the calculation. Do not use any `Math` class methods. Incorporate this method into an application that reads integer values for `base` and `exponent` and performs the calculation with the `integerPower` method.

5.15 (*Hypotenuse Calculations*) Define a method `hypotenuse` that calculates the hypotenuse of a right triangle when the lengths of the other two sides are given. The method should take two arguments of type `double` and return the hypotenuse as a `double`. Incorporate this method into an application that reads values for `side1` and `side2` and performs the calculation with the `hypotenuse` method. Use `Math` methods `pow` and `sqrt` to determine the length of the hypotenuse for each of the triangles in Fig. 5.14. [Note: Class `Math` also provides method `hypot` to perform this calculation.]

Triangle	Side 1	Side 2
1	3.0	4.0
2	5.0	12.0
3	8.0	15.0

Fig. 5.14 | Values for the sides of triangles in Exercise 5.15.

5.16 (*Multiples*) Write a method `isMultiple` that determines, for a pair of integers, whether the second integer is a multiple of the first. The method should take two integer arguments and return `true` if the second is a multiple of the first and `false` otherwise. [Hint: Use the remainder operator.] Incorporate this method into an application that inputs a series of pairs of integers (one pair at a time) and determines whether the second value in each pair is a multiple of the first.

5.17 (*Even or Odd*) Write a method `isEven` that uses the remainder operator (%) to determine whether an integer is even. The method should take an integer argument and return `true` if the integer is even and `false` otherwise. Incorporate this method into an application that inputs a sequence of integers (one at a time) and determines whether each is even or odd.

5.18 (*Displaying a Square of Asterisks*) Write a method `squareOfAsterisks` that displays a solid square (the same number of rows and columns) of asterisks whose side is specified in integer parameter `side`. For example, if `side` is 4, the method should display

```
****
****
****
****
```

Incorporate this method into an application that reads an integer value for `side` from the user and outputs the asterisks with the `squareOfAsterisks` method.

5.19 (*Displaying a Square of Any Character*) Modify the method created in Exercise 5.18 to receive a second parameter of type `char` called `fillCharacter`. Form the square using the `char` provided as an argument. Thus, if `side` is 5 and `fillCharacter` is `#`, the method should display

```
#####
#####
#####
#####
#####
```

Use the following statement (in which `input` is a `Scanner` object) to read a character from the user at the keyboard:

```
char fill = input.next().charAt(0);
```

5.20 (*Circle Area*) Write an application that prompts the user for the radius of a circle and uses a method called `circleArea` to calculate the area of the circle.

5.21 (*Separating Digits*) Write methods that accomplish each of the following tasks:

- Calculate the integer part of the quotient when integer `a` is divided by integer `b`.
- Calculate the integer remainder when integer `a` is divided by integer `b`.
- Use the methods developed in parts (a) and (b) to write a method `displayDigits` that receives an integer between 1 and 99999 and displays it as a sequence of digits, separating each pair of digits by two spaces. For example, the integer 4562 should appear as

```
4 5 6 2
```

Incorporate the methods into an application that inputs an integer and calls `displayDigits` by passing the method the integer entered. Display the results.

5.22 (*Temperature Conversions*) Implement the following integer methods:

- Method `celsius` returns the Celsius equivalent of a Fahrenheit temperature, using the calculation

```
celsius = 5.0 / 9.0 * (fahrenheit - 32);
```

- Method `fahrenheit` returns the Fahrenheit equivalent of a Celsius temperature, using the calculation

```
fahrenheit = 9.0 / 5.0 * celsius + 32;
```

- Use the methods from parts (a) and (b) to write an application that enables the user either to enter a Fahrenheit temperature and display the Celsius equivalent or to enter a Celsius temperature and display the Fahrenheit equivalent.

5.23 (*Find the Minimum*) Write a method `minimum3` that returns the smallest of three floating-point numbers. Use the `Math.min` method to implement `minimum3`. Incorporate the method into an application that reads three values from the user, determines the smallest value and displays the result.

5.24 (*Perfect Numbers*) An integer number is said to be a *perfect number* if its factors, including 1 (but not the number itself), sum to the number. For example, 6 is a perfect number, because $6 = 1 + 2 + 3$. Write a method `isPerfect` that determines whether parameter `number` is a perfect number. Use this method in an application that displays all the perfect numbers between 1 and 1000. Display the factors of each perfect number to confirm that the number is indeed perfect. Challenge the computing power of your computer by testing numbers much larger than 1000. Display the results.

5.25 (*Prime Numbers*) A positive integer is *prime* if it's divisible by only 1 and itself. For example, 2, 3, 5 and 7 are prime, but 4, 6, 8 and 9 are not. The number 1, by definition, is not prime.

- Write a method that determines whether a number is prime.

- b) Use this method in an application that determines and displays all the prime numbers less than 10,000. How many numbers up to 10,000 do you have to test to ensure that you've found all the primes?
- c) Initially, you might think that $n/2$ is the upper limit for which you must test to see whether a number n is prime, but you need only go as high as the square root of n . Rewrite the program, and run it both ways.

5.26 (Reversing Digits) Write a method that takes an integer value and returns the number with its digits reversed. For example, given the number 7631, the method should return 1367. Incorporate the method into an application that reads a value from the user and displays the result.

5.27 (Greatest Common Divisor) The *greatest common divisor (GCD)* of two integers is the largest integer that evenly divides each of the two numbers. Write a method `gcd` that returns the greatest common divisor of two integers. [Hint: You might want to use Euclid's algorithm. You can find information about it at en.wikipedia.org/wiki/Euclidean_algorithm.] Incorporate the method into an application that reads two values from the user and displays the result.

5.28 Write a method `qualityPoints` that inputs a student's average and returns 4 if it's 90–100, 3 if 80–89, 2 if 70–79, 1 if 60–69 and 0 if lower than 60. Incorporate the method into an application that reads a value from the user and displays the result.

5.29 (Coin Tossing) Write an application that simulates coin tossing. Let the program toss a coin each time the user chooses the "Toss Coin" menu option. Count the number of times each side of the coin appears. Display the results. The program should call a separate method `flip` that takes no arguments and returns a value from a `Coin` enum (HEADS and TAILS). [Note: If the program realistically simulates coin tossing, each side of the coin should appear approximately half the time.]

5.30 (Guess the Number) Write an application that plays "guess the number" as follows: Your program chooses the number to be guessed by selecting a random integer in the range 1 to 1000. The application displays the prompt `Guess a number between 1 and 1000`. The player inputs a first guess. If the player's guess is incorrect, your program should display `Too high. Try again.` or `Too low. Try again.` to help the player "zero in" on the correct answer. The program should prompt the user for the next guess. When the user enters the correct answer, display `Congratulations. You guessed the number!`, and allow the user to choose whether to play again. [Note: The guessing technique employed in this problem is similar to a binary search, which is discussed in Chapter 19, Searching, Sorting and Big O.]

5.31 (Guess the Number Modification) Modify the program of Exercise 5.30 to count the number of guesses the player makes. If the number is 10 or fewer, display `Either you know the secret or you got lucky!` If the player guesses the number in 10 tries, display `Aha! You know the secret!` If the player makes more than 10 guesses, display `You should be able to do better!` Why should it take no more than 10 guesses? Well, with each "good guess," the player should be able to eliminate half of the numbers, then half of the remaining numbers, and so on.

5.32 (Distance Between Points) Write method `distance` to calculate the distance between two points $(x1, y1)$ and $(x2, y2)$. All numbers and return values should be of type `double`. Incorporate this method into an application that enables the user to enter the coordinates of the points.

5.33 (Craps Game Modification) Modify the craps program of Fig. 5.8 to allow wagering. Initialize variable `bankBalance` to 1000 dollars. Prompt the player to enter a wager. Check that wager is less than or equal to `bankBalance`, and if it's not, have the user reenter wager until a valid wager is entered. Then, run one game of craps. If the player wins, increase `bankBalance` by wager and display the new `bankBalance`. If the player loses, decrease `bankBalance` by wager, display the new `bankBalance`, check whether `bankBalance` has become zero and, if so, display the message "Sorry. You busted!" As the game progresses, display various messages to create some "chatter," such as "Oh, you're going for broke, huh?" or "Aw c'mon, take a chance!" or "You're up big. Now's the time

to cash in your chips!". Implement the "chatter" as a separate method that randomly chooses the string to display.

5.34 (*Table of Binary, Octal and Hexadecimal Numbers*) Write an application that displays a table of the binary, octal and hexadecimal equivalents of the decimal numbers in the range 1 through 256. If you aren't familiar with these number systems, read online Appendix J first.

Making a Difference

As computer costs decline, it becomes feasible for every student, regardless of economic circumstance, to have a computer and use it in school. This creates exciting possibilities for improving the educational experience of all students worldwide, as suggested by the next five exercises. [Note: Check out initiatives such as the One Laptop Per Child Project (www.1laptop.org). Also, research "green" laptops—what are some key "going green" characteristics of these devices? Look into the Electronic Product Environmental Assessment Tool (www.epeat.net), which can help you assess the "greenness" of desktops, notebooks and monitors to help you decide which products to purchase.]

5.35 (*Computer-Assisted Instruction*) The use of computers in education is referred to as *computer-assisted instruction (CAI)*. Write a program that will help an elementary school student learn multiplication. Use a `SecureRandom` object to produce two positive one-digit integers. The program should then prompt the user with a question, such as

How much is 6 times 7?

The student then inputs the answer. Next, the program checks the student's answer. If it's correct, display the message "Very good!" and ask another multiplication question. If the answer is wrong, display the message "No. Please try again." and let the student try the same question repeatedly until the student finally gets it right. A separate method should be used to generate each new question. This method should be called once when the application begins execution and each time the user answers the question correctly.

5.36 (*Computer-Assisted Instruction: Reducing Student Fatigue*) One problem in CAI environments is student fatigue. This can be reduced by varying the computer's responses to hold the student's attention. Modify the program of Exercise 5.35 so that various comments are displayed for each answer as follows:

Possible responses to a correct answer:

Very good!
Excellent!
Nice work!
Keep up the good work!

Possible responses to an incorrect answer:

No. Please try again.
Wrong. Try once more.
Don't give up!
No. Keep trying.

Use random-number generation to choose a number from 1 to 4 that will be used to select one of the four appropriate responses to each correct or incorrect answer. Use a `switch` statement to issue the responses.

5.37 (*Computer-Assisted Instruction: Monitoring Student Performance*) More sophisticated computer-assisted instruction systems monitor the student's performance over a period of time. The decision to begin a new topic is often based on the student's success with previous topics. Modify the program of Exercise 5.36 to count the number of correct and incorrect responses typed by the

student. After the student types 10 answers, your program should calculate the percentage that are correct. If the percentage is lower than 75%, display "Please ask your teacher for extra help.", then reset the program so another student can try it. If the percentage is 75% or higher, display "Congratulations, you are ready to go to the next level!", then reset the program so another student can try it.

5.38 (*Computer-Assisted Instruction: Difficulty Levels*) Exercises 5.35–5.37 developed a computer-assisted instruction program to help teach an elementary school student multiplication. Modify the program to allow the user to enter a difficulty level. At a difficulty level of 1, the program should use only single-digit numbers in the problems; at a difficulty level of 2, numbers as large as two digits, and so on.

5.39 (*Computer-Assisted Instruction: Varying the Types of Problems*) Modify the program of Exercise 5.38 to allow the user to pick a type of arithmetic problem to study. An option of 1 means addition problems only, 2 means subtraction problems only, 3 means multiplication problems only, 4 means division problems only and 5 means a random mixture of all these types.

6

Arrays and ArrayLists

*Begin at the beginning, ... and
go on till you come to the end:
then stop.*

—Lewis Carroll

*To go beyond is as wrong as to
fall short.*

—Confucius

Objectives

In this chapter you'll:

- Learn what primitive types and reference types are.
- Learn what arrays are.
- Use arrays to store data in and retrieve data from lists and tables of values.
- Declare arrays, initialize arrays and refer to individual elements of arrays.
- Iterate through arrays with the enhanced `for` statement.
- Pass arrays to methods.
- Declare and manipulate multidimensional arrays.
- Use variable-length argument lists.
- Read command-line arguments into a program.
- Search, sort and fill arrays with the methods of class `Arrays`, which contains methods for common array manipulations.
- Use class `ArrayList` to manipulate a dynamically resizable arraylike data structure.



- 6.1 Introduction
- 6.2 Primitive Types vs. Reference Types
- 6.3 Arrays
- 6.4 Declaring and Creating Arrays
- 6.5 Examples Using Arrays
 - 6.5.1 Creating and Initializing an Array
 - 6.5.2 Using an Array Initializer
 - 6.5.3 Calculating the Values to Store in an Array
 - 6.5.4 Summing the Elements of an Array
 - 6.5.5 Using Bar Charts to Display Array Data Graphically
 - 6.5.6 Using the Elements of an Array as Counters
 - 6.5.7 Using Arrays to Analyze Survey Results
- 6.6 Exception Handling: Processing the Incorrect Response
 - 6.6.1 The try Statement
 - 6.6.2 Executing the catch Block
 - 6.6.3 toString Method of the Exception Parameter
- 6.7 Enhanced for Statement
- 6.8 Passing Arrays to Methods
- 6.9 Pass-By-Value vs. Pass-By-Reference
- 6.10 Multidimensional Arrays
- 6.11 Variable-Length Argument Lists
- 6.12 Using Command-Line Arguments
- 6.13 Class Arrays
- 6.14 Introduction to Collections and Class ArrayList
- 6.15 (Optional) GUI and Graphics Case Study: Drawing Arcs
- 6.16 Wrap-Up

Summary | Self-Review Exercises | Answers to Self-Review Exercises | Exercises |
 Special Section: Building Your Own Computer | Making a Difference

6.1 Introduction

This chapter introduces **data structures**—collections of related data items. **Array** objects are data structures consisting of related data items of the same type. Arrays make it convenient to process related groups of values. Arrays remain the same length once they're created. We study data structures in depth in Chapters 16–21.

After discussing how arrays are declared, created and initialized, we present practical examples that demonstrate common array manipulations. We introduce Java's *exception-handling* mechanism and use it to allow a program to continue executing when it attempts to access an array element that does not exist. We introduce Java's *enhanced for statement*, which allows a program to access the data in an array more easily than does the counter-controlled for statement presented in Section 4.3. We show how to use *variable-length argument lists* to create methods that can be called with varying numbers of arguments, and we demonstrate how to process *command-line arguments* in method `main`. Next, we present some common array manipulations with `static` methods of class `Arrays` from the `java.util` package.

Although commonly used, arrays have limited capabilities. For instance, you must specify an array's size, and if at execution time you wish to modify the size, you must do so by creating a new array. At the end of this chapter, we introduce one of Java's prebuilt data structures from the Java API's *collection classes*. These offer greater capabilities than traditional arrays. They're reusable, reliable, powerful and efficient. We focus on the `ArrayList` collection. `ArrayLists` are similar to arrays but provide additional functionality, such as **dynamic resizing** as necessary to accommodate more or fewer elements.

Java SE 8

After reading Chapter 17, Java SE 8 Lambdas and Streams, you'll be able to reimplement many of Chapter 6's examples in a more concise and elegant manner, and in a way that makes them easier to parallelize to improve performance on today's multi-core systems.

6.2 Primitive Types vs. Reference Types

Java's types are divided into primitive types and **reference types**. In Chapters 2–5, you worked primarily with variables of types `int` and `double`—two of the primitive types. The other six primitive types are `boolean`, `byte`, `char`, `short`, `long` and `float`—these are summarized in Appendix D. All nonprimitive types are *reference types*, so classes, which specify the types of objects, are reference types. In earlier chapters, you used variables of the *reference types* `Scanner` (Chapters 2–4) and `SecureRandom` (Chapter 5).



Software Engineering Observation 6.1

A variable's declared type (e.g., `int`, `double` or `Scanner`) indicates whether the variable is of a primitive or a reference type. If a variable's type is not one of the eight primitive types, then it's a reference type.

A primitive-type variable can hold exactly *one* value of its declared type at a time. For example, an `int` variable can store one integer at a time. When another value is assigned to that variable, the new value replaces the previous one—which is *lost*.

Programs use variables of reference types (normally called **references**) to store the *addresses* of objects in the computer's memory. Such a variable is said to **refer to an object** in the program. For example, the statement:

```
Scanner input = new Scanner(System.in);
```

which you've used in many programs, creates a `Scanner` object, then assigns to the variable `input` a *reference* to that `Scanner` object.

To call an object's methods, you need a reference to the object. For example, the statement

```
int number = input.nextInt();
```

uses the variable `input`, which refers to a `Scanner` object, to call the `Scanner` object's method `nextInt`.

If an object's method requires additional data to perform its task, then you'd pass arguments in the method call. For example, the statement

```
int face = 1 + randomNumbers.nextInt(6);
```

from line 16 of Fig. 5.6 uses the variable `randomNumbers`, which refers to a `SecureRandom` object, to call the object's `nextInt` method and pass it the argument 6. Note that primitive-type variables do *not* refer to objects, so such variables cannot be used to invoke methods.

6.3 Arrays

An array is a group of variables (called **elements** or **components**) containing values that all have the *same* type. Arrays are *objects*, so they're considered *reference types*. As you'll soon see, what we typically think of as an array is actually a *reference* to an array object in mem-

ory. The *elements* of an array can be either *primitive types* or *reference types* (including arrays, as we'll see in Section 6.10). To refer to a particular element in an array, we specify the *name* of the reference to the array and the *position number* of the element in the array. The position number of the element is called the element's **index** or **subscript**.

Logical Array Representation

Figure 6.1 shows a logical representation of an integer array called *c*. This array contains 12 *elements*. A program refers to any one of these elements with an **array-access expression** that includes the *name* of the array followed by the *index* of the particular element in **square brackets** (`[]`). The first element in every array has **index zero** and is sometimes called the **zeroth element**. Thus, the elements of array *c* are `c[0]`, `c[1]`, `c[2]` and so on. The highest index in array *c* is 11, which is 1 less than 12—the number of elements in the array. Array names follow the same conventions as other variable names.

Name of array (c) →	<code>c[0]</code>	-45
	<code>c[1]</code>	6
	<code>c[2]</code>	0
	<code>c[3]</code>	72
	<code>c[4]</code>	1543
	<code>c[5]</code>	-89
	<code>c[6]</code>	0
	<code>c[7]</code>	62
	<code>c[8]</code>	-3
	<code>c[9]</code>	1
	<code>c[10]</code>	6453
Index (or subscript) of the element in array c →	<code>c[11]</code>	78

Fig. 6.1 | A 12-element array.

An index must be a *nonnegative integer*. A program can use an expression as an index. For example, if we assume that variable *a* is 5 and variable *b* is 6, then the statement

```
c[a + b] += 2;
```

adds 2 to array element `c[11]`. An indexed array name is an *array-access expression*, which can be used on the left side of an assignment to place a new value into an array element.



Common Programming Error 6.1

An index must be an int value or a value of a type that can be promoted to int—namely, byte, short or char, but not long; otherwise, a compilation error occurs.

Let's examine array *c* in Fig. 6.1 more closely. The **name** of the array is *c*. Every array object knows its own length and stores it in a **length instance variable**. The expression `c.length` returns array *c*'s length. Even though the **length instance variable** of an array is

`public`, it cannot be changed because it's a `final` variable. This array's 12 elements are referred to as `c[0]`, `c[1]`, `c[2]`, ..., `c[11]`. The value of `c[0]` is -45, the value of `c[1]` is 6, the value of `c[2]` is 0, the value of `c[7]` is 62 and the value of `c[11]` is 78. To calculate the sum of the values contained in the first three elements of array `c` and store the result in variable `sum`, we would write

```
sum = c[0] + c[1] + c[2];
```

To divide the value of `c[6]` by 2 and assign the result to the variable `x`, we would write

```
x = c[6] / 2;
```

6.4 Declaring and Creating Arrays

Array objects occupy space in memory. Like other objects, arrays are created with keyword `new`. To create an array object, you specify the type of the array elements and the number of elements as part of an **array-creation expression** that uses keyword `new`. Such an expression returns a *reference* that can be stored in an array variable. The following declaration and array-creation expression create an array object containing 12 `int` elements and store the array's reference in the array variable named `c`:

```
int[] c = new int[12];
```

This expression can be used to create the array in Fig. 6.1. When an array is created, each of its elements receives a default value—zero for the numeric primitive-type elements, `false` for `boolean` elements and `null` for references. As you'll soon see, you can provide nondefault element values when you create an array.

Creating the array in Fig. 6.1 can also be performed in two steps as follows:

```
int[] c; // declare the array variable
c = new int[12]; // create the array; assign to array variable
```

In the declaration, the *square brackets* following the type indicate that `c` is a variable that will refer to an array (i.e., the variable will store an array *reference*). In the assignment statement, the array variable `c` receives the reference to a new array of 12 `int` elements.



Common Programming Error 6.2

In an array declaration, specifying the number of elements in the square brackets of the declaration (e.g., `int[12] c;`) is a syntax error.

A program can create several arrays in a single declaration. The following declaration reserves 100 elements for `b` and 27 elements for `x`:

```
String[] b = new String[100], x = new String[27];
```

When the type of the array and the square brackets are combined at the beginning of the declaration, all the identifiers in the declaration are array variables. In this case, variables `b` and `x` refer to `String` arrays. For readability, we prefer to declare only *one* variable per declaration. The preceding declaration is equivalent to:

```
String[] b = new String[100]; // create array b
String[] x = new String[27]; // create array x
```



Good Programming Practice 6.1

For readability, declare only one variable per declaration. Keep each declaration on a separate line, and include a comment describing the variable being declared.

When only one variable is declared in each declaration, the square brackets can be placed either after the type or after the array variable name, as in:

```
String b[] = new String[100]; // create array b
String x[] = new String[27]; // create array x
```

but placing the square brackets after the type is preferred.



Common Programming Error 6.3

Declaring multiple array variables in a single declaration can lead to subtle errors. Consider the declaration `int[] a, b, c;`. If `a`, `b` and `c` should be declared as array variables, then this declaration is correct—placing square brackets directly following the type indicates that all the identifiers in the declaration are array variables. However, if only `a` is intended to be an array variable, and `b` and `c` are intended to be individual `int` variables, then this declaration is incorrect—the declaration `int a[], b, c;` would achieve the desired result.

A program can declare arrays of any type. Every element of a primitive-type array contains a value of the array's declared element type. Similarly, in an array of a reference type, every element is a reference to an object of the array's declared element type. For example, every element of an `int` array is an `int` value, and every element of a `String` array is a reference to a `String` object.

6.5 Examples Using Arrays

This section presents several examples that demonstrate declaring arrays, creating arrays, initializing arrays and manipulating array elements.

6.5.1 Creating and Initializing an Array

The application of Fig. 6.2 uses keyword `new` to create an array of 10 `int` elements, which are initially zero (the default initial value for `int` variables). Line 9 declares `array`—a reference capable of referring to an array of `int` elements—then initializes the variable with a reference to an array object containing 10 `int` elements. Line 11 outputs the column headings. The first column contains the index (0–9) of each array element, and the second column contains the default initial value (0) of each array element.

```
1 // Fig. 6.2: InitArray.java
2 // Initializing the elements of an array to default values of zero.
3
4 public class InitArray
5 {
6     public static void main(String[] args)
7     {
```

Fig. 6.2 | Initializing the elements of an array to default values of zero. (Part 1 of 2.)

```

8      // declare variable array and initialize it with an array object
9      int[] array = new int[10]; // create the array object
10
11     System.out.printf("%s%s%n", "Index", "Value"); // column headings
12
13     // output each array element's value
14     for (int counter = 0; counter < array.length; counter++)
15         System.out.printf("%5d%8d%n", counter, array[counter]);
16     }
17 } // end class InitArray

```

Index	Value
0	0
1	0
2	0
3	0
4	0
5	0
6	0
7	0
8	0
9	0

Fig. 6.2 | Initializing the elements of an array to default values of zero. (Part 2 of 2.)

The `for` statement (lines 14–15) outputs the index (represented by `counter`) and value of each array element (represented by `array[counter]`). Control variable `counter` is initially 0—index values start at 0, so using **zero-based counting** allows the loop to access every element of the array. The `for`’s loop-continuation condition uses the expression `array.length` (line 14) to determine the length of the array. In this example, the length of the array is 10, so the loop continues executing as long as the value of control variable `counter` is less than 10. The highest index value of a 10-element array is 9, so using the less-than operator in the loop-continuation condition guarantees that the loop does not attempt to access an element *beyond* the end of the array (i.e., during the final iteration of the loop, `counter` is 9). We’ll soon see what Java does when it encounters such an *out-of-range index* at execution time.

6.5.2 Using an Array Initializer

You can create an array and initialize its elements with an **array initializer**—a comma-separated list of expressions (called an **initializer list**) enclosed in braces. In this case, the array length is determined by the number of elements in the initializer list. For example,

```
int[] n = { 10, 20, 30, 40, 50 };
```

creates a *five*-element array with index values 0–4. Element `n[0]` is initialized to 10, `n[1]` is initialized to 20, and so on. When the compiler encounters an array declaration that includes an initializer list, it *counts* the number of initializers in the list to determine the size of the array, then sets up the appropriate new operation “behind the scenes.”

The application in Fig. 6.3 initializes an integer array with 10 values (line 9) and displays the array in tabular format. The code for displaying the array elements (lines 14–15) is identical to that in Fig. 6.2 (lines 15–16).

```

1 // Fig. 6.3: InitArray.java
2 // Initializing the elements of an array with an array initializer.
3
4 public class InitArray
5 {
6     public static void main(String[] args)
7     {
8         // initializer list specifies the initial value for each element
9         int[] array = { 32, 27, 64, 18, 95, 14, 90, 70, 60, 37 };
10
11         System.out.printf("%s%8s%n", "Index", "Value"); // column headings
12
13         // output each array element's value
14         for (int counter = 0; counter < array.length; counter++)
15             System.out.printf("%5d%8d%n", counter, array[counter]);
16
17     } // end class InitArray

```

Index	Value
0	32
1	27
2	64
3	18
4	95
5	14
6	90
7	70
8	60
9	37

Fig. 6.3 | Initializing the elements of an array with an array initializer.

6.5.3 Calculating the Values to Store in an Array

The application in Fig. 6.4 creates a 10-element array and assigns to each element one of the even integers from 2 to 20 (2, 4, 6, ..., 20). Then the application displays the array in tabular format. The `for` statement at lines 12–13 calculates an array element's value by multiplying the current value of the control variable `counter` by 2, then adding 2.

```

1 // Fig. 6.4: InitArray.java
2 // Calculating the values to be placed into the elements of an array.
3
4 public class InitArray
5 {
6     public static void main(String[] args)
7     {
8         final int ARRAY_LENGTH = 10; // declare constant
9         int[] array = new int[ARRAY_LENGTH]; // create array
10

```

Fig. 6.4 | Calculating the values to be placed into the elements of an array. (Part I of 2.)

```

11      // calculate value for each array element
12      for (int counter = 0; counter < array.length; counter++)
13          array[counter] = 2 + 2 * counter;
14
15      System.out.printf("%s%8s%n", "Index", "Value"); // column headings
16
17      // output each array element's value
18      for (int counter = 0; counter < array.length; counter++)
19          System.out.printf("%5d%8d%n", counter, array[counter]);
20  }
21  } // end class InitArray

```

Index	Value
0	2
1	4
2	6
3	8
4	10
5	12
6	14
7	16
8	18
9	20

Fig. 6.4 | Calculating the values to be placed into the elements of an array. (Part 2 of 2.)

Line 8 uses the modifier `final` to declare the constant variable `ARRAY_LENGTH` with the value 10. Constant variables must be initialized *before* they're used and *cannot* be modified thereafter. If you attempt to *modify* a `final` variable after it's initialized in its declaration, the compiler issues an error message like

cannot assign a value to final variable *variableName*



Good Programming Practice 6.2

Constant variables also are called *named constants*. They often make programs more readable than programs that use literal values (e.g., 10)—a named constant such as `ARRAY_LENGTH` clearly indicates its purpose, whereas a literal value could have different meanings based on its context.



Good Programming Practice 6.3

Multiword named constants should have each word separated from the next with an underscore (`_`) as in `ARRAY_LENGTH`.



Common Programming Error 6.4

Assigning a value to a `final` variable after it has been initialized is a compilation error. Similarly, attempting to access the value of a `final` variable before it's initialized results in a compilation error like, “variable *variableName* might not have been initialized.”

6.5.4 Summing the Elements of an Array

Often, the elements of an array represent a series of values to be used in a calculation. If, for example, they represent exam grades, a professor may wish to total the elements of the array and use that sum to calculate the class average for the exam.

Figure 6.5 sums the values contained in a 10-element integer array. The program declares, creates and initializes the array at line 8. The `for` statement performs the calculations. [Note: The values supplied as array initializers are often read into a program rather than specified in an initializer list. For example, an application could input the values from a user or from a file on disk (as discussed in Chapter 15, Files, Streams and Object Serialization). Reading the data into a program (rather than “hand coding” it into the program) makes the program more reusable, because it can be used with *different* sets of data.]

```

1  // Fig. 6.5: SumArray.java
2  // Computing the sum of the elements of an array.
3
4  public class SumArray
5  {
6      public static void main(String[] args)
7      {
8          int[] array = { 87, 68, 94, 100, 83, 78, 85, 91, 76, 87 };
9          int total = 0;
10
11          // add each element's value to total
12          for (int counter = 0; counter < array.length; counter++)
13              total += array[counter];
14
15          System.out.printf("Total of array elements: %d\n", total);
16      }
17  } // end class SumArray

```

Total of array elements: 849

Fig. 6.5 | Computing the sum of the elements of an array.

6.5.5 Using Bar Charts to Display Array Data Graphically

Many programs present data to users in a graphical manner. For example, numeric values are often displayed as bars in a bar chart. In such a chart, longer bars represent proportionally larger numeric values. One simple way to display numeric data graphically is with a bar chart that shows each numeric value as a bar of asterisks (*).

Professors often like to examine the distribution of grades on an exam. A professor might graph the number of grades in each of several categories to visualize the grade distribution. Suppose the grades on an exam were 87, 68, 94, 100, 83, 78, 85, 91, 76 and 87. They include one grade of 100, two grades in the 90s, four grades in the 80s, two grades in the 70s, one grade in the 60s and no grades below 60. Our next application (Fig. 6.6) stores this grade distribution data in an array of 11 elements, each corresponding to a category of grades. For example, `array[0]` indicates the number of grades in the range 0–9, `array[7]` the number of grades in the range 70–79 and `array[10]` the number of 100 grades. The GradeBook case studies in Chapter 7 contain code that calculates these grade

frequencies based on a set of grades. For now, we manually create the array with the given grade frequencies.

```

1 // Fig. 6.6: BarChart.java
2 // Bar chart printing program.
3
4 public class BarChart
5 {
6     public static void main(String[] args)
7     {
8         int[] array = {0, 0, 0, 0, 0, 0, 1, 2, 4, 2, 1};
9
10        System.out.println("Grade distribution:");
11
12        // for each array element, output a bar of the chart
13        for (int counter = 0; counter < array.length; counter++)
14        {
15            // output bar label ("00-09: ", ..., "90-99: ", "100: ")
16            if (counter == 10)
17                System.out.printf("%5d: ", 100);
18            else
19                System.out.printf("%02d-%02d: ",
20                                counter * 10, counter * 10 + 9);
21
22            // print bar of asterisks
23            for (int stars = 0; stars < array[counter]; stars++)
24                System.out.print("*");
25
26            System.out.println();
27        }
28    }
29 } // end class BarChart

```

```

Grade distribution:
00-09:
10-19:
20-29:
30-39:
40-49:
50-59:
60-69: *
70-79: **
80-89: ****
90-99: **
100: *

```

Fig. 6.6 | Bar chart printing program.

The application reads the numbers from the array and graphs the information as a bar chart. It displays each grade range followed by a bar of asterisks indicating the number of grades in that range. To label each bar, lines 16–20 output a grade range (e.g., "70–79: ") based on the current value of counter. When counter is 10, line 17 outputs 100 with a field width of 5, followed by a colon and a space, to align the label "100: " with the other

bar labels. The nested `for` statement (lines 23–24) outputs the bars. Note the loop-continuation condition at line 23 (`stars < array[counter]`). Each time the program reaches the inner `for`, the loop counts from 0 up to `array[counter]`, thus using a value in `array` to determine the number of asterisks to display. In this example, *no* students received a grade below 60, so `array[0]–array[5]` contain zeroes, and *no* asterisks are displayed next to the first six grade ranges. In line 19, the format specifier `%02d` indicates that an `int` value should be formatted as a field of two digits. The **0 flag** in the format specifier displays a leading 0 for values with fewer digits than the field width (2).

6.5.6 Using the Elements of an Array as Counters

Sometimes, programs use counter variables to summarize data, such as the results of a survey. In Fig. 5.7, we used separate counters in our die-rolling program to track the number of occurrences of each side of a six-sided die as the program rolled the die 6,000,000 times. An array version of this application is shown in Fig. 6.7.

```

1  // Fig. 6.7: RollDie.java
2  // Die-rolling program using arrays instead of switch.
3  import java.security.SecureRandom;
4
5  public class RollDie
6  {
7      public static void main(String[] args)
8      {
9          SecureRandom randomNumbers = new SecureRandom();
10         int[] frequency = new int[7]; // array of frequency counters
11
12         // roll die 6,000,000 times; use die value as frequency index
13         for (int roll = 1; roll <= 6000000; roll++)
14             ++frequency[1 + randomNumbers.nextInt(6)];
15
16         System.out.printf("%s%10s\n", "Face", "Frequency");
17
18         // output each array element's value
19         for (int face = 1; face < frequency.length; face++)
20             System.out.printf("%4d%10d\n", face, frequency[face]);
21     }
22 } // end class RollDie

```

Face	Frequency
1	999690
2	999512
3	1000575
4	999815
5	999781
6	1000627

Fig. 6.7 | Die-rolling program using arrays instead of `switch`.

Figure 6.7 uses the array `frequency` (line 10) to count the occurrences of each side of the die. *The single statement in line 14 of this program replaces lines 22–45 of Fig. 5.7.* Line

14 uses the random value to determine which frequency element to increment during each iteration of the loop. The calculation in line 14 produces random numbers from 1 to 6, so the array frequency must be large enough to store six counters. However, we use a seven-element array in which we ignore frequency[0]—it’s more logical to have the face value 1 increment frequency[1] than frequency[0]. Thus, each face value is used as an index for array frequency. In line 14, the calculation inside the square brackets evaluates first to determine which element of the array to increment, then the ++ operator adds one to that element. We also replaced lines 49–51 from Fig. 5.7 by looping through array frequency to output the results (lines 19–20). When we study Java SE 8’s new functional programming capabilities in Chapter 17, we’ll show how to replace lines 13–14 and 19–20 with a *single* statement!

6.5.7 Using Arrays to Analyze Survey Results

Our next example uses arrays to summarize data collected in a survey. Consider the following problem statement:

Twenty students were asked to rate on a scale of 1 to 5 the quality of the food in the student cafeteria, with 1 being “awful” and 5 being “excellent.” Place the 20 responses in an integer array and determine the frequency of each rating.

This is a typical array-processing application (Fig. 6.8). We wish to summarize the number of responses of each type (that is, 1–5). Array responses (lines 9–10) is a 20-element integer array containing the students’ survey responses. The last value in the array *is intentionally* an incorrect response (14). When a Java program executes, array element indices are checked for validity—all indices must be greater than or equal to 0 and less than the length of the array. Any attempt to access an element outside that range of indices results in a runtime error that’s known as an `ArrayIndexOutOfBoundsException`. At the end of this section, we’ll discuss the invalid response value, demonstrate array **bounds checking** and introduce Java’s *exception-handling* mechanism, which can be used to detect and handle an `ArrayIndexOutOfBoundsException`.

```

1 // Fig. 6.8: StudentPoll.java
2 // Poll analysis program.
3
4 public class StudentPoll
5 {
6     public static void main(String[] args)
7     {
8         // student response array (more typically, input at runtime)
9         int[] responses = { 1, 2, 5, 4, 3, 5, 2, 1, 3, 3, 1, 4, 3, 3, 3,
10                          2, 3, 3, 2, 14 };
11         int[] frequency = new int[6]; // array of frequency counters
12
13         // for each answer, select responses element and use that value
14         // as frequency index to determine element to increment
15         for (int answer = 0; answer < responses.length; answer++)
16         {

```

Fig. 6.8 | Poll analysis program. (Part I of 2.)

```

17     try
18     {
19         ++frequency[responses[answer]];
20     }
21     catch (ArrayIndexOutOfBoundsException e)
22     {
23         System.out.println(e); // invokes toString method
24         System.out.printf("    responses[%d] = %d\n\n",
25             answer, responses[answer]);
26     }
27 }
28
29 System.out.printf("%s%10s\n", "Rating", "Frequency");
30
31 // output each array element's value
32 for (int rating = 1; rating < frequency.length; rating++)
33     System.out.printf("%6d%10d\n", rating, frequency[rating]);
34 }
35 } // end class StudentPoll

```

```

java.lang.ArrayIndexOutOfBoundsException: 14
    responses[19] = 14

```

Rating	Frequency
1	3
2	4
3	8
4	2
5	2

Fig. 6.8 | Poll analysis program. (Part 2 of 2.)

The frequency Array

We use the *six-element* array `frequency` (line 11) to count the number of occurrences of each response. Each element is used as a *counter* for one of the possible types of survey responses—`frequency[1]` counts the number of students who rated the food as 1, `frequency[2]` counts the number of students who rated the food as 2, and so on.

Summarizing the Results

The `for` statement (lines 15–27) reads the responses from the array `responses` one at a time and increments one of the counters `frequency[1]` to `frequency[5]`; we ignore `frequency[0]` because the survey responses are limited to the range 1–5. The key statement in the loop appears in line 19. This statement increments the appropriate frequency counter as determined by the value of `responses[answer]`.

Let's step through the first few iterations of the `for` statement:

- When the counter `answer` is 0, `responses[answer]` is the value of `responses[0]` (that is, 1—see line 9). In this case, `frequency[responses[answer]]` is interpreted as `frequency[1]`, and the counter `frequency[1]` is incremented by one. To evaluate the expression, we begin with the value in the *innermost* set of brackets (`answer`, currently 0). The value of `answer` is plugged into the expression, and the

next set of brackets (`responses[answer]`) is evaluated. That value is used as the index for the frequency array to determine which counter to increment (in this case, `frequency[1]`).

- The next time through the loop `answer` is 1, `responses[answer]` is the value of `responses[1]` (that is, 2—see line 9), so `frequency[responses[answer]]` is interpreted as `frequency[2]`, causing `frequency[2]` to be incremented.
- When `answer` is 2, `responses[answer]` is the value of `responses[2]` (that is, 5—see line 9), so `frequency[responses[answer]]` is interpreted as `frequency[5]`, causing `frequency[5]` to be incremented, and so on.

Regardless of the number of responses processed, only a six-element array (in which we ignore element zero) is required to summarize the results, because all the correct response values are values from 1 to 5, and the index values for a six-element array are 0–5. In the program’s output, the Frequency column summarizes only 19 of the 20 values in the `responses` array—the last element of the array `responses` contains an (intentionally) incorrect response that was not counted. Section 6.6 discusses what happens when the program in Fig. 6.8 encounters the invalid response (14) in the last element of array `responses`.

6.6 Exception Handling: Processing the Incorrect Response

An **exception** indicates a problem that occurs while a program executes. The name “exception” suggests that the problem occurs infrequently—if the “rule” is that a statement normally executes correctly, then the problem represents the “exception to the rule.” **Exception handling** helps you create **fault-tolerant programs** that can resolve (or handle) exceptions. In many cases, this allows a program to continue executing as if no problems were encountered. For example, the `StudentPoll` application still displays results (Fig. 6.8), even though one of the responses was out of range. More severe problems might prevent a program from continuing normal execution, instead requiring the program to notify the user of the problem, then terminate. When the JVM or a method detects a problem, such as an invalid array index or an invalid method argument, it **throws** an exception—that is, an exception occurs. Methods in your own classes can also throw exceptions, as you’ll learn in Chapter 8.

6.6.1 The try Statement

To handle an exception, place any code that might throw an exception in a **try statement** (lines 17–26). The **try block** (lines 17–20) contains the code that might *throw* an exception, and the **catch block** (lines 21–26) contains the code that *handles* the exception if one occurs. You can have *many* catch blocks to handle different *types* of exceptions that might be thrown in the corresponding try block. When line 19 correctly increments an element of the frequency array, lines 21–26 are ignored. The braces that delimit the bodies of the try and catch blocks are required.

6.6.2 Executing the catch Block

When the program encounters the invalid value 14 in the `responses` array, it attempts to add 1 to `frequency[14]`, which is *outside* the bounds of the array—the frequency array has only six elements (with indexes 0–5). Because array bounds checking is performed at execu-

tion time, the JVM generates an *exception*—specifically line 19 throws an **ArrayIndexOutOfBoundsException** to notify the program of this problem. At this point the try block terminates and the catch block begins executing—any local variables declared in the try block are now *out of scope* (and no longer exist), so they’re not accessible in the catch block.

The catch block declares an exception parameter (e) of type (IndexOutOfRangeException). The catch block can handle exceptions of the specified type. Inside the catch block, you can use the parameter’s identifier to interact with a caught exception object.



Error-Prevention Tip 6.1

When writing code to access an array element, ensure that the array index remains greater than or equal to 0 and less than the length of the array. This would prevent ArrayIndexOutOfBoundsException if your program is correct.

6.6.3 toString Method of the Exception Parameter

When lines 21–26 *catch* the exception, the program displays a message indicating the problem that occurred. Line 23 *implicitly* calls the exception object’s toString method to get the error message that’s implicitly stored in the exception object and display it. Once the message is displayed in this example, the exception is considered *handled* and the program continues with the next statement after the catch block’s closing brace. In this example, the end of the for statement is reached (line 27), so the program continues with the increment of the control variable in line 15. We discuss exception handling again in Chapter 8, and more deeply in Chapter 11.

6.7 Enhanced for Statement

The **enhanced for** statement iterates through the elements of an array *without* using a counter, thus avoiding the possibility of “stepping outside” the array. We show how to use the enhanced for statement with the Java API’s prebuilt data structures (called collections) in Section 6.14. The syntax of an enhanced for statement is:

```
for (parameter : arrayName)  
    statement
```

where *parameter* has a *type* and an *identifier* (e.g., int number), and *arrayName* is the array through which to iterate. The type of the parameter must be *consistent* with the type of the elements in the array. As the next example illustrates, the identifier represents successive element values in the array on successive iterations of the loop.

Figure 6.9 uses the enhanced for statement (lines 12–13) to sum the integers in an array of student grades. The enhanced for’s parameter is of type int, because array contains int values—the loop selects one int value from the array during each iteration. The enhanced for statement iterates through successive values in the array one by one. The statement’s header can be read as “for each iteration, assign the next element of array to int variable number, then execute the following statement.” Thus, for each iteration, identifier number represents an int value in array. Lines 12–13 are equivalent to the following counter-controlled repetition used in lines 12–13 of Fig. 6.5 to total the integers in array, except that counter *cannot be accessed* in the enhanced for statement:

```
for (int counter = 0; counter < array.length; counter++)  
    total += array[counter];
```

```

1 // Fig. 6.9: EnhancedForTest.java
2 // Using the enhanced for statement to total integers in an array.
3
4 public class EnhancedForTest
5 {
6     public static void main(String[] args)
7     {
8         int[] array = { 87, 68, 94, 100, 83, 78, 85, 91, 76, 87 };
9         int total = 0;
10
11         // add each element's value to total
12         for (int number : array)
13             total += number;
14
15         System.out.printf("Total of array elements: %d\n", total);
16     }
17 } // end class EnhancedForTest

```

```
Total of array elements: 849
```

Fig. 6.9 | Using the enhanced for statement to total integers in an array.

The enhanced for statement can be used *only* to obtain array elements—it *cannot* be used to *modify* elements. If your program needs to modify elements, use the traditional counter-controlled for statement.

The enhanced for statement can be used in place of the counter-controlled for statement whenever code looping through an array does *not* require access to the counter indicating the index of the current array element. For example, totaling the integers in an array requires access only to the element values—the index of each element is irrelevant. However, if a program must use a counter for some reason other than simply to loop through an array (e.g., to print an index number next to each array element value, as in the examples earlier in this chapter), use the counter-controlled for statement.



Error-Prevention Tip 6.2

The enhanced for statement simplifies the code for iterating through an array making the code more readable and eliminating several error possibilities, such as improperly specifying the control variable's initial value, the loop-continuation test and the increment expression.

Java SE 8

The for statement and the enhanced for statement each iterate sequentially from a starting value to an ending value. In Chapter 17, Java SE 8 Lambdas and Streams, you'll learn about class Stream and its forEach method. Working together, these provide an elegant, more concise and less error prone means for iterating through collections so that some of the iterations may occur in parallel with others to achieve better multi-core system performance.

6.8 Passing Arrays to Methods

This section demonstrates how to pass arrays and individual array elements as arguments to methods. To pass an array argument to a method, specify the name of the array *without any brackets*. For example, if array `hourlyTemperatures` is declared as


```
double[] hourlyTemperatures = new double[24];
```

then the method call

```
modifyArray(hourlyTemperatures);
```

passes the reference of array `hourlyTemperatures` to method `modifyArray`. Every array object “knows” its own length. Thus, when we pass an array object’s reference into a method, we need not pass the array length as an additional argument.

For a method to receive an array reference through a method call, the method’s parameter list must specify an *array parameter*. For example, the method header for method `modifyArray` might be written as

```
void modifyArray(double[] b)
```

indicating that `modifyArray` receives the reference of a `double` array in parameter `b`. The method call passes array `hourlyTemperature`’s reference, so when the called method uses the array variable `b`, it *refers to* the same array object as `hourlyTemperatures` in the caller.

When an argument to a method is an entire array or an individual array element of a reference type, the called method receives a *copy* of the reference. However, when an argument to a method is an individual array element of a primitive type, the called method receives a copy of the element’s *value*. Such primitive values are called **scalars** or **scalar quantities**. To pass an individual array element to a method, use the indexed name of the array element as an argument in the method call.

Figure 6.10 demonstrates the difference between passing an entire array and passing a primitive-type array element to a method. Notice that `main` invokes static methods `modifyArray` (line 19) and `modifyElement` (line 30) directly. Recall from Section 5.4 that a static method of a class can invoke other static methods of the same class directly.

```

1  // Fig. 6.10: PassArray.java
2  // Passing arrays and individual array elements to methods.
3
4  public class PassArray
5  {
6      // main creates array and calls modifyArray and modifyElement
7      public static void main(String[] args)
8      {
9          int[] array = { 1, 2, 3, 4, 5 };
10
11         System.out.printf(
12             "Effects of passing reference to entire array:%n" +
13             "The values of the original array are:%n");
14
15         // output original array elements
16         for (int value : array)
17             System.out.printf("  %d", value);
18
19         modifyArray(array); // pass array reference
20         System.out.printf("%n%nThe values of the modified array are:%n");
21

```

Fig. 6.10 | Passing arrays and individual array elements to methods. (Part I of 2.)

```

22      // output modified array elements
23      for (int value : array)
24          System.out.printf("    %d", value);
25
26      System.out.printf(
27          "%n\nEffects of passing array element value:%n" +
28          "array[3] before modifyElement: %d\n", array[3]);
29
30      modifyElement(array[3]); // attempt to modify array[3]
31      System.out.printf(
32          "array[3] after modifyElement: %d\n", array[3]);
33  }
34
35  // multiply each element of an array by 2
36  public static void modifyArray(int[] array2)
37  {
38      for (int counter = 0; counter < array2.length; counter++)
39          array2[counter] *= 2;
40  }
41
42  // multiply argument by 2
43  public static void modifyElement(int element)
44  {
45      element *= 2;
46      System.out.printf(
47          "Value of element in modifyElement: %d\n", element);
48  }
49  } // end class PassArray

```

Effects of passing reference to entire array:

The values of the original array are:

1 2 3 4 5

The values of the modified array are:

2 4 6 8 10

Effects of passing array element value:

array[3] before modifyElement: 8

Value of element in modifyElement: 16

array[3] after modifyElement: 8

Fig. 6.10 | Passing arrays and individual array elements to methods. (Part 2 of 2.)

The enhanced for statement at lines 16–17 outputs the elements of array. Line 19 invokes method `modifyArray`, passing array as an argument. The method (lines 36–40) receives a copy of array's reference and uses it to multiply each of array's elements by 2. To prove that array's elements were modified, lines 23–24 output array's elements again. As the output shows, method `modifyArray` doubled the value of each element. We could *not* use the enhanced for statement in lines 38–39 because we're modifying the array's elements.

Figure 6.10 next demonstrates that when a copy of an individual primitive-type array element is passed to a method, modifying the *copy* in the called method does *not* affect the

original value of that element in the calling method's array. Lines 26–28 output the value of `array[3]` *before* invoking method `modifyElement`. Remember that the value of this element is now 8 after it was modified in the call to `modifyArray`. Line 30 calls method `modifyElement` and passes `array[3]` as an argument. Remember that `array[3]` is actually one `int` value (8) in `array`. Therefore, the program passes a copy of the value of `array[3]`. Method `modifyElement` (lines 43–48) multiplies the value received as an argument by 2, stores the result in its parameter `element`, then outputs the value of `element` (16). Since method parameters, like local variables, cease to exist when the method in which they're declared completes execution, the method parameter `element` is destroyed when method `modifyElement` terminates. When the program returns control to `main`, lines 31–32 output the *unmodified* value of `array[3]` (i.e., 8).

6.9 Pass-By-Value vs. Pass-By-Reference

The preceding example demonstrated how arrays and primitive-type array elements are passed as arguments to methods. We now take a closer look at how arguments in general are passed to methods. Two ways to pass arguments in method calls in many programming languages are **pass-by-value** and **pass-by-reference** (sometimes called **call-by-value** and **call-by-reference**). When an argument is passed by value, a *copy* of the argument's *value* is passed to the called method. The called method works exclusively with the copy. Changes to the called method's copy do *not* affect the original variable's value in the caller.

When an argument is passed by reference, the called method can access the argument's value in the caller directly and modify that data, if necessary. Pass-by-reference improves performance by eliminating the need to copy possibly large amounts of data.

Unlike some other languages, Java does *not* allow you to choose pass-by-value or pass-by-reference—*all arguments are passed by value*. A method call can pass two types of values to a method—copies of primitive values (e.g., values of type `int` and `double`) and copies of references to objects. Objects themselves cannot be passed to methods. When a method modifies a primitive-type parameter, changes to the parameter have no effect on the original argument value in the calling method. For example, when line 30 in `main` of Fig. 6.10 passes `array[3]` to method `modifyElement`, the statement in line 45 that doubles the value of parameter `element` has *no* effect on the value of `array[3]` in `main`. This is also true for reference-type parameters. If you modify a reference-type parameter so that it refers to another object, only the parameter refers to the new object—the reference stored in the caller's variable still refers to the original object.

Although an object's reference is passed by value, a method can still interact with the referenced object by calling its `public` methods using the copy of the object's reference. Since the reference stored in the parameter is a copy of the reference that was passed as an argument, the parameter in the called method and the argument in the calling method refer to the *same* object in memory. For example, in Fig. 6.10, both parameter `array2` in method `modifyArray` and variable `array` in `main` refer to the *same* array object in memory. Any changes made using the parameter `array2` are carried out on the object that `array` references in the calling method. In Fig. 6.10, the changes made in `modifyArray` using `array2` affect the contents of the array object referenced by `array` in `main`. Thus, with a reference to an object, the called method *can* manipulate the caller's object directly.

**Performance Tip 6.1**

Passing references to arrays, instead of the array objects themselves, makes sense for performance reasons. Because everything in Java is passed by value, if array objects were passed, a copy of each element would be passed. For large arrays, this would waste time and consume considerable storage for the copies of the elements.

6.10 Multidimensional Arrays

Multidimensional arrays with two dimensions are often used to represent *tables* of values with data arranged in *rows* and *columns*. To identify a particular table element, you specify *two* indices. *By convention*, the first identifies the element's row and the second its column. Arrays that require two indices to identify each element are called **two-dimensional arrays**. (Multidimensional arrays can have more than two dimensions.) Java does not support multidimensional arrays directly, but it allows you to specify one-dimensional arrays whose elements are also one-dimensional arrays, thus achieving the same effect. Figure 6.11 illustrates a two-dimensional array named *a* with three rows and four columns (i.e., a three-by-four array). In general, an array with *m* rows and *n* columns is called an *m-by-n* array.

	Column 0	Column 1	Column 2	Column 3
Row 0	a[0][0]	a[0][1]	a[0][2]	a[0][3]
Row 1	a[1][0]	a[1][1]	a[1][2]	a[1][3]
Row 2	a[2][0]	a[2][1]	a[2][2]	a[2][3]

Column index
Row index
Array name

Fig. 6.11 | Two-dimensional array with three rows and four columns.

Every element in array *a* is identified in Fig. 6.11 by an *array-access expression* of the form *a*[*row*][*column*]; *a* is the name of the array, and *row* and *column* are the indices that uniquely identify each element by row and column index. The names of the elements in *row* 0 all have a *first* index of 0, and the names of the elements in *column* 3 all have a *second* index of 3.

Arrays of One-Dimensional Arrays

Like one-dimensional arrays, multidimensional arrays can be initialized with array initializers in declarations. A two-dimensional array *b* with two rows and two columns could be declared and initialized with **nested array initializers** as follows:

```
int[][] b = {{1, 2}, {3, 4}};
```

The initial values are *grouped by row* in braces. So 1 and 2 initialize *b*[0][0] and *b*[0][1], respectively, and 3 and 4 initialize *b*[1][0] and *b*[1][1], respectively. The compiler counts the number of nested array initializers (represented by sets of braces within the out-

er braces) to determine the number of *rows* in array *b*. The compiler counts the initializer values in the nested array initializer for a row to determine the number of *columns* in that row. As we'll see momentarily, this means that *rows can have different lengths*.

Multidimensional arrays are maintained as *arrays of one-dimensional arrays*. Therefore array *b* in the preceding declaration is actually composed of two separate one-dimensional arrays—one containing the values in the first nested initializer list {1, 2} and one containing the values in the second nested initializer list {3, 4}. Thus, array *b* itself is an array of two elements, each a one-dimensional array of *int* values.

Two-Dimensional Arrays with Rows of Different Lengths

The manner in which multidimensional arrays are represented makes them quite flexible. In fact, the lengths of the rows in array *b* are *not* required to be the same. For example,

```
int[][] b = {{1, 2}, {3, 4, 5}};
```

creates integer array *b* with two elements (determined by the number of nested array initializers) that represent the rows of the two-dimensional array. Each element of *b* is a *reference* to a one-dimensional array of *int* variables. The *int* array for row 0 is a one-dimensional array with *two* elements (1 and 2), and the *int* array for row 1 is a one-dimensional array with *three* elements (3, 4 and 5).

Creating Two-Dimensional Arrays with Array-Creation Expressions

A multidimensional array with the *same* number of columns in every row can be created with an array-creation expression. For example, the following line declares array *b* and assign it a reference to a three-by-four array:

```
int[][] b = new int[3][4];
```

In this case, we use the literal values 3 and 4 to specify the number of rows and number of columns, respectively, but this is *not* required. Programs can also use variables to specify array dimensions, because *new creates arrays at execution time—not at compile time*. The elements of a multidimensional array are initialized when the array object is created.

A multidimensional array in which each row has a *different* number of columns can be created as follows:

```
int[][] b = new int[2][]; // create 2 rows
b[0] = new int[5]; // create 5 columns for row 0
b[1] = new int[3]; // create 3 columns for row 1
```

The preceding statements create a two-dimensional array with two rows. Row 0 has *five* columns, and row 1 has *three* columns.

Two-Dimensional Array Example: Displaying Element Values

Figure 6.12 demonstrates initializing two-dimensional arrays with array initializers, and using nested for loops to **traverse** the arrays—that is, manipulate *every* element of each array. (In Chapter 7, we'll show a GradeBook case study in which we use a two-dimensional array to store student grades on multiple exams.) Class `InitArray`'s `main` declares two arrays. The declaration of `array1` (line 9) uses nested array initializers of the *same* length to initialize the first row to the values 1, 2 and 3, and the second row to the values 4, 5 and 6. The declaration of `array2` (line 10) uses nested initializers of *different* lengths. In this case, the first row is initialized to two elements with the values 1 and 2, respectively. The

second row is initialized to one element with the value 3. The third row is initialized to three elements with the values 4, 5 and 6, respectively.

```

1  // Fig. 6.12: InitArray.java
2  // Initializing two-dimensional arrays.
3
4  public class InitArray
5  {
6      // create and output two-dimensional arrays
7      public static void main(String[] args)
8      {
9          int[][] array1 = {{1, 2, 3}, {4, 5, 6}};
10         int[][] array2 = {{1, 2}, {3}, {4, 5, 6}};
11
12         System.out.println("Values in array1 by row are");
13         outputArray(array1); // displays array1 by row
14
15         System.out.printf("\nValues in array2 by row are\n");
16         outputArray(array2); // displays array2 by row
17     }
18
19     // output rows and columns of a two-dimensional array
20     public static void outputArray(int[][] array)
21     {
22         // loop through array's rows
23         for (int row = 0; row < array.length; row++)
24         {
25             // loop through columns of current row
26             for (int column = 0; column < array[row].length; column++)
27                 System.out.printf("%d ", array[row][column]);
28
29             System.out.println();
30         }
31     }
32 } // end class InitArray

```

```

Values in array1 by row are
1 2 3
4 5 6

Values in array2 by row are
1 2
3
4 5 6

```

Fig. 6.12 | Initializing two-dimensional arrays.

Lines 13 and 16 call method `outputArray` (lines 20–31) to output the elements of `array1` and `array2`, respectively. Method `outputArray`'s parameter—`int[][] array`—indicates that the method receives a two-dimensional array. The nested `for` statement (lines 23–30) outputs the rows of a two-dimensional array. In the loop-continuation condition of the outer `for` statement, the expression `array.length` determines the number of rows in the array. In the inner `for` statement, the expression `array[row].length` deter-

mines the number of columns in the current row of the array. The inner `for` statement's condition enables the loop to determine the exact number of columns in each row.

Nested Enhanced-`for` Statements

The nested loop in method `outputArray` may also be implemented with nested enhanced-`for` statements as follows:

```
// loop through array's rows
for (int[] row : array)
{
    // loop through columns of current row
    for (int column : row)
        System.out.printf("%d ", column);

    System.out.println();
}
```

Common Multidimensional-Array Manipulations Performed with `for` Statements

Many common array manipulations use `for` statements. As an example, the following `for` statement sets all the elements in row 2 of array `a` in Fig. 6.11 to zero:

```
for (int column = 0; column < a[2].length; column++)
    a[2][column] = 0;
```

We specified row 2; therefore, we know that the *first* index is always 2 (0 is the first row, and 1 is the second row). This `for` loop varies only the *second* index (i.e., the column index). If row 2 of array `a` contains four elements, then the preceding `for` statement is equivalent to the assignment statements

```
a[2][0] = 0;
a[2][1] = 0;
a[2][2] = 0;
a[2][3] = 0;
```

The following nested `for` statement totals the values of all the elements in array `a`:

```
int total = 0;
for (int row = 0; row < a.length; row++)
{
    for (int column = 0; column < a[row].length; column++)
        total += a[row][column];
}
```

These nested `for` statements total the array elements *one row at a time*. The outer `for` statement begins by setting the row index to 0 so that the first row's elements can be totaled by the inner `for` statement. The outer `for` then increments row to 1 so that the second row can be totaled. Then, the outer `for` increments row to 2 so that the third row can be totaled.

6.11 Variable-Length Argument Lists

With **variable-length argument lists**, you can create methods that receive an unspecified number of arguments. A type followed by an **ellipsis** (`...`) in a method's parameter list indicates that the method receives a variable number of arguments of that particular type. This use of the ellipsis can occur only *once* in a parameter list, and the ellipsis, together with its

type and the parameter name, must be placed at the *end* of the parameter list. While you can use method overloading and array passing to accomplish much of what is accomplished with variable-length argument lists, using an ellipsis in a method's parameter list is more concise.

Figure 6.13 demonstrates method `average` (lines 7–16), which receives a variable-length sequence of `doubles`. Java treats the variable-length argument list as an array whose elements are all of the same type. So, the method body can manipulate the parameter numbers as an array of `doubles`. Lines 12–13 use the enhanced `for` loop to walk through the array and calculate the total of the `doubles` in the array. Line 15 accesses `numbers.length` to obtain the size of the `numbers` array for use in the averaging calculation. Lines 29, 31 and 33 in `main` call method `average` with two, three and four arguments, respectively. Method `average` has a variable-length argument list (line 7), so it can average as many `double` arguments as the caller passes. The output shows that each call to method `average` returns the correct value.



Common Programming Error 6.5

Placing an ellipsis indicating a variable-length argument list in the middle of a parameter list is a syntax error. An ellipsis may be placed only at the end of the parameter list.

```

1 // Fig. 6.13: VarargsTest.java
2 // Using variable-length argument lists.
3
4 public class VarargsTest
5 {
6     // calculate average
7     public static double average(double... numbers)
8     {
9         double total = 0.0;
10
11         // calculate total using the enhanced for statement
12         for (double d : numbers)
13             total += d;
14
15         return total / numbers.length;
16     }
17
18     public static void main(String[] args)
19     {
20         double d1 = 10.0;
21         double d2 = 20.0;
22         double d3 = 30.0;
23         double d4 = 40.0;
24
25         System.out.printf("d1 = %.1f%d2 = %.1f%d3 = %.1f%d4 = %.1f%n",
26                             d1, d2, d3, d4);
27
28         System.out.printf("Average of d1 and d2 is %.1f",
29                             average(d1, d2) );
30         System.out.printf("Average of d1, d2 and d3 is %.1f",
31                             average(d1, d2, d3) );

```

Fig. 6.13 | Using variable-length argument lists. (Part 1 of 2.)


```

32         System.out.printf("Average of d1, d2, d3 and d4 is %.1f%n",
33             average(d1, d2, d3, d4) );
34     }
35 } // end class VarargsTest

```

```

d1 = 10.0
d2 = 20.0
d3 = 30.0
d4 = 40.0

```

```

Average of d1 and d2 is 15.0
Average of d1, d2 and d3 is 20.0
Average of d1, d2, d3 and d4 is 25.0

```

Fig. 6.13 | Using variable-length argument lists. (Part 2 of 2.)

6.12 Using Command-Line Arguments

It's possible to pass arguments from the command line to an application via method `main`'s `String[]` parameter, which receives an array of `Strings`. By convention, this parameter is named `args`. When an application is executed using the `java` command, Java passes the **command-line arguments** that appear after the class name in the `java` command to the application's `main` method as `Strings` in the array `args`. The number of command-line arguments is obtained by accessing the array's `length` attribute. Common uses of command-line arguments include passing options and filenames to applications.

Our next example uses command-line arguments to determine the size of an array, the value of its first element and the increment used to calculate the values of the array's remaining elements. The command

```
java InitArray 5 0 4
```

passes three arguments, 5, 0 and 4, to the application `InitArray`. Command-line arguments are separated by white space, *not* commas. When this command executes, `InitArray`'s `main` method receives the three-element array `args` (i.e., `args.length` is 3) in which `args[0]` contains the `String` "5", `args[1]` contains the `String` "0" and `args[2]` contains the `String` "4". The program determines how to use these arguments—in Fig. 6.14 we convert the three command-line arguments to `int` values and use them to initialize an array. When the program executes, if `args.length` is not 3, the program prints an error message and terminates (lines 9–12). Otherwise, lines 14–32 initialize and display the array based on the values of the command-line arguments.

```

1  // Fig. 6.14: InitArray.java
2  // Initializing an array using command-line arguments.
3
4  public class InitArray
5  {
6      public static void main(String[] args)
7      {

```

Fig. 6.14 | Initializing an array using command-line arguments. (Part 1 of 2.)

```

8      // check number of command-line arguments
9      if (args.length != 3)
10         System.out.printf(
11             "Error: Please re-enter the entire command, including%n" +
12             "an array size, initial value and increment.%n");
13     else
14     {
15         // get array size from first command-line argument
16         int arrayLength = Integer.parseInt(args[0]);
17         int[] array = new int[arrayLength];
18
19         // get initial value and increment from command-line arguments
20         int initialValue = Integer.parseInt(args[1]);
21         int increment = Integer.parseInt(args[2]);
22
23         // calculate value for each array element
24         for (int counter = 0; counter < array.length; counter++)
25             array[counter] = initialValue + increment * counter;
26
27         System.out.printf("%s%8s%n", "Index", "Value");
28
29         // display array index and value
30         for (int counter = 0; counter < array.length; counter++)
31             System.out.printf("%5d%8d%n", counter, array[counter]);
32     }
33 }
34 } // end class InitArray

```

```
java InitArray
```

Error: Please re-enter the entire command, including
an array size, initial value and increment.

```
java InitArray 5 0 4
```

Index	Value
0	0
1	4
2	8
3	12
4	16

```
java InitArray 8 1 2
```

Index	Value
0	1
1	3
2	5
3	7
4	9
5	11
6	13
7	15

Fig. 6.14 | Initializing an array using command-line arguments. (Part 2 of 2.)

Line 16 gets `args[0]`—a `String` that specifies the array size—and converts it to an `int` value that the program uses to create the array in line 17. The static method `parseInt` of class `Integer` converts its `String` argument to an `int`.

Lines 20–21 convert the `args[1]` and `args[2]` command-line arguments to `int` values and store them in `initialValue` and `increment`, respectively. Lines 24–25 calculate the value for each array element.

The output of the first execution shows that the application received an insufficient number of command-line arguments. The second execution uses command-line arguments 5, 0 and 4 to specify the size of the array (5), the value of the first element (0) and the increment of each value in the array (4), respectively. The corresponding output shows that these values create an array containing the integers 0, 4, 8, 12 and 16. The output from the third execution shows that the command-line arguments 8, 1 and 2 produce an array whose 8 elements are the nonnegative odd integers from 1 to 15.

6.13 Class Arrays

Class **Arrays** helps you avoid reinventing the wheel by providing static methods for common array manipulations. These methods include **sort** for *sorting* an array (i.e., arranging elements into ascending order), **binarySearch** for *searching* a *sorted* array (i.e., determining whether an array contains a specific value and, if so, where the value is located), **equals** for *comparing* arrays and **fill** for *placing values into an array*. These methods are overloaded for primitive-type arrays and for arrays of objects. Our focus in this section is on using the built-in capabilities provided by the Java API. Chapter 19, Searching, Sorting and Big O, shows how to implement your own sorting and searching algorithms, a subject of great interest to computer-science researchers and students.

Figure 6.15 uses `Arrays` methods `sort`, `binarySearch`, `equals` and `fill`, and shows how to *copy* arrays with class `System`'s static **arraycopy** method. In `main`, line 11 sorts the elements of array `doubleArray`. The static method `sort` of class `Arrays` orders the array's elements in *ascending* order by default. We discuss how to sort in *descending* order later in the chapter. Overloaded versions of `sort` allow you to sort a specific range of elements within the array. Lines 12–15 output the sorted array.

```

1 // Fig. 6.15: ArrayManipulations.java
2 // Arrays class methods and System.arraycopy.
3 import java.util.Arrays;
4
5 public class ArrayManipulations
6 {
7     public static void main(String[] args)
8     {
9         // sort doubleArray into ascending order
10        double[] doubleArray = { 8.4, 9.3, 0.2, 7.9, 3.4 };
11        Arrays.sort(doubleArray);
12        System.out.printf("%ndoubleArray: ");
13
14        for (double value : doubleArray)
15            System.out.printf("%.1f ", value);

```

Fig. 6.15 | Arrays class methods and `System.arraycopy`. (Part 1 of 3.)

```

16
17 // fill 10-element array with 7s
18 int[] filledIntArray = new int[10];
19 Arrays.fill(filledIntArray, 7);
20 displayArray(filledIntArray, "filledIntArray");
21
22 // copy array intArray into array intArrayCopy
23 int[] intArray = { 1, 2, 3, 4, 5, 6 };
24 int[] intArrayCopy = new int[intArray.length];
25 System.arraycopy(intArray, 0, intArrayCopy, 0, intArray.length);
26 displayArray(intArray, "intArray");
27 displayArray(intArrayCopy, "intArrayCopy");
28
29 // compare intArray and intArrayCopy for equality
30 boolean b = Arrays.equals(intArray, intArrayCopy);
31 System.out.printf("%n\nintArray %s intArrayCopy%n",
32     (b ? "==" : "!="));
33
34 // compare intArray and filledIntArray for equality
35 b = Arrays.equals(intArray, filledIntArray);
36 System.out.printf("intArray %s filledIntArray%n",
37     (b ? "==" : "!="));
38
39 // search intArray for the value 5
40 int location = Arrays.binarySearch(intArray, 5);
41
42 if (location >= 0)
43     System.out.printf(
44         "Found 5 at element %d in intArray%n", location);
45 else
46     System.out.println("5 not found in intArray");
47
48 // search intArray for the value 8763
49 location = Arrays.binarySearch(intArray, 8763);
50
51 if (location >= 0)
52     System.out.printf(
53         "Found 8763 at element %d in intArray%n", location);
54 else
55     System.out.println("8763 not found in intArray");
56 }
57
58 // output values in each array
59 public static void displayArray(int[] array, String description)
60 {
61     System.out.printf("%n%s: ", description);
62
63     for (int value : array)
64         System.out.printf("%d ", value);
65 }
66 } // end class ArrayManipulations

```

Fig. 6.15 | Arrays class methods and System.arraycopy. (Part 2 of 3.)

```
doubleArray: 0.2 3.4 7.9 8.4 9.3
filledIntArray: 7 7 7 7 7 7 7 7 7
intArray: 1 2 3 4 5 6
intArrayCopy: 1 2 3 4 5 6

intArray == intArrayCopy
intArray != filledIntArray
Found 5 at element 4 in intArray
8763 not found in intArray
```

Fig. 6.15 | Arrays class methods and System.arraycopy. (Part 3 of 3.)

Line 19 calls static method `fill` of class `Arrays` to populate all 10 elements of `filledIntArray` with 7s. Overloaded versions of `fill` allow you to populate a specific range of elements with the same value. Line 20 calls our class's `displayArray` method (declared at lines 59–65) to output the contents of `filledIntArray`.

Line 25 copies the elements of `intArray` into `intArrayCopy`. The first argument (`intArray`) passed to `System` method `arraycopy` is the array from which elements are to be copied. The second argument (0) is the index that specifies the *starting point* in the range of elements to copy from the array. This value can be any valid array index. The third argument (`intArrayCopy`) specifies the *destination array* that will store the copy. The fourth argument (0) specifies the index in the destination array *where the first copied element should be stored*. The last argument specifies the *number of elements to copy* from the array in the first argument. In this case, we copy all the elements in the array.

Lines 30 and 35 call static method `equals` of class `Arrays` to determine whether all the elements of two arrays are equivalent. If the arrays contain the same elements in the same order, the method returns `true`; otherwise, it returns `false`.



Error-Prevention Tip 6.3

When comparing array contents, always use `Arrays.equals(array1, array2)`, which compares the two arrays' contents, rather than `array1.equals(array2)`, which compares whether `array1` and `array2` refer to the same array object.

Lines 40 and 49 call static method `binarySearch` of class `Arrays` to perform a binary search on `intArray`, using the second argument (5 and 8763, respectively) as the key. If value is found, `binarySearch` returns the index of the element; otherwise, `binarySearch` returns a negative value. The negative value returned is based on the search key's *insertion point*—the index where the key would be inserted in the array if we were performing an insert operation. After `binarySearch` determines the insertion point, it changes its sign to negative and subtracts 1 to obtain the return value. For example, in Fig. 6.15, the insertion point for the value 8763 is the element with index 6 in the array. Method `binarySearch` changes the insertion point to -6, subtracts 1 from it and returns the value -7. Subtracting 1 from the insertion point guarantees that method `binarySearch` returns positive values (≥ 0) if and only if the key is found. This return value is useful for inserting elements in a sorted array. Chapter 19 discusses binary searching in detail.



Common Programming Error 6.6

Passing an unsorted array to `binarySearch` is a logic error—the value returned is undefined.

Java SE 8—Class Arrays Method `parallelSort`

The `Arrays` class now has several new “parallel” methods that take advantage of multi-core hardware. `Arrays` method `parallelSort` can sort large arrays more efficiently on multi-core systems. In Section 23.12, we create a very large array and use features of the Java SE 8 Date/Time API to compare how long it takes to sort the array with methods `sort` and `parallelSort`.

6.14 Introduction to Collections and Class `ArrayList`

The Java API provides several predefined data structures, called **collections**, used to store groups of related objects in memory. These classes provide efficient methods that organize, store and retrieve your data *without* requiring knowledge of how the data is being *stored*. This reduces application-development time.

You’ve used arrays to store sequences of objects. Arrays do not automatically change their size at execution time to accommodate additional elements. The collection class `ArrayList<T>` (package `java.util`) provides a convenient solution to this problem—it can *dynamically* change its size to accommodate more elements. The `T` (by convention) is a *placeholder*—when declaring a new `ArrayList`, replace it with the type of elements that you want the `ArrayList` to hold. For example,

```
ArrayList<String> list;
```

declares `list` as an `ArrayList` collection that can store only `Strings`. Classes with this kind of placeholder that can be used with any type are called **generic classes**. *Only nonprimitive types can be used to declare variables and create objects of generic classes.* However, Java provides a mechanism—known as *boxing*—that allows primitive values to be wrapped as objects for use with generic classes. So, for example,

```
ArrayList<Integer> integers;
```

declares `integers` as an `ArrayList` that can store only `Integers`. When you place an `int` value into an `ArrayList<Integer>`, the `int` value is *boxed* (wrapped) as an `Integer` object, and when you get an `Integer` object from an `ArrayList<Integer>`, then assign the object to an `int` variable, the `int` value inside the object is *unboxed* (unwrapped).

Additional generic collection classes and generics are discussed in Chapters 16 and 20, respectively. Figure 6.16 shows some common methods of class `ArrayList<T>`.

Method	Description
<code>add</code>	Adds an element to the <i>end</i> of the <code>ArrayList</code> .
<code>clear</code>	Removes all the elements from the <code>ArrayList</code> .
<code>contains</code>	Returns <code>true</code> if the <code>ArrayList</code> contains the specified element; otherwise, returns <code>false</code> .
<code>get</code>	Returns the element at the specified index.
<code>indexOf</code>	Returns the index of the first occurrence of the specified element in the <code>ArrayList</code> .

Fig. 6.16 | Some methods and properties of class `ArrayList<T>`. (Part 1 of 2.)

Method	Description
<code>remove</code>	Overloaded. Removes the first occurrence of the specified value or the element at the specified index.
<code>size</code>	Returns the number of elements stored in the ArrayList.
<code>trimToSize</code>	Trims the capacity of the ArrayList to the current number of elements.

Fig. 6.16 | Some methods and properties of class `ArrayList<T>`. (Part 2 of 2.)

Demonstrating an `ArrayList<String>`

Figure 6.17 demonstrates some common `ArrayList` capabilities. Line 10 creates a new empty `ArrayList` of `Strings` with a default initial capacity of 10 elements. The capacity indicates how many items the `ArrayList` can hold *without growing*. `ArrayList` is implemented using a conventional array behind the scenes. When the `ArrayList` grows, it must create a larger internal array and *copy* each element to the new array. This is a time-consuming operation. It would be inefficient for the `ArrayList` to grow each time an element is added. Instead, it grows only when an element is added *and* the number of elements is equal to the capacity—i.e., there's no space for the new element.

```

1  // Fig. 6.17: ArrayListCollection.java
2  // Generic ArrayList<T> collection demonstration.
3  import java.util.ArrayList;
4
5  public class ArrayListCollection
6  {
7      public static void main(String[] args)
8      {
9          // create a new ArrayList of Strings with an initial capacity of 10
10         ArrayList<String> items = new ArrayList<String>();
11
12         items.add("red"); // append an item to the list
13         items.add(0, "yellow"); // insert "yellow" at index 0
14
15         // header
16         System.out.print(
17             "Display list contents with counter-controlled loop:");
18
19         // display the colors in the list
20         for (int i = 0; i < items.size(); i++)
21             System.out.printf(" %s", items.get(i));
22
23         // display colors using enhanced for in the display method
24         display(items,
25             "%nDisplay list contents with enhanced for statement:");
26
27         items.add("green"); // add "green" to the end of the list
28         items.add("yellow"); // add "yellow" to the end of the list

```

Fig. 6.17 | Generic `ArrayList<T>` collection demonstration. (Part 1 of 2.)

```

29     display(items, "List with two new elements:");
30
31     items.remove("yellow"); // remove the first "yellow"
32     display(items, "Remove first instance of yellow:");
33
34     items.remove(1); // remove item at index 1
35     display(items, "Remove second list element (green):");
36
37     // check if a value is in the List
38     System.out.printf("\nred is %sin the list\n",
39         items.contains("red") ? "" : "not ");
40
41     // display number of elements in the List
42     System.out.printf("Size: %s\n", items.size());
43 }
44
45 // display the ArrayList's elements on the console
46 public static void display(ArrayList<String> items, String header)
47 {
48     System.out.printf(header); // display header
49
50     // display each element in items
51     for (String item : items)
52         System.out.printf(" %s", item);
53
54     System.out.println();
55 }
56 } // end class ArrayListCollection

```

```

Display list contents with counter-controlled loop: yellow red
Display list contents with enhanced for statement: yellow red
List with two new elements: yellow red green yellow
Remove first instance of yellow: red green yellow
Remove second list element (green): red yellow
"red" is in the list
Size: 2

```

Fig. 6.17 | Generic `ArrayList<T>` collection demonstration. (Part 2 of 2.)

The **add** method adds elements to the `ArrayList` (lines 12–13). The add method with *one* argument *appends* its argument to the *end* of the `ArrayList`. The add method with *two* arguments *inserts* a new element at the specified *position*. The first argument is an index. As with arrays, collection indices start at zero. The second argument is the *value* to insert at that *index*. The indices of all subsequent elements are incremented by one. Inserting an element is usually slower than adding an element to the end of the `ArrayList`.

Lines 20–21 display the items in the `ArrayList`. Method **size** returns the number of elements currently in the `ArrayList`. Method **get** (line 21) obtains the element at a specified index. Lines 24–25 display the elements again by invoking method `display` (defined at lines 46–55). Lines 27–28 add two more elements to the `ArrayList`, then line 29 displays the elements again to confirm that the two elements were added to the *end* of the collection.

The **remove** method is used to remove an element with a specific value (line 31). It removes only the first such element. If no such element is in the `ArrayList`, remove does

nothing. An overloaded version of the method removes the element at the specified index (line 34). When an element is removed, the indices of any elements after the removed element decrease by one.

Line 39 uses the **contains** method to check if an item is in the `ArrayList`. The `contains` method returns true if the element is found in the `ArrayList`, and false otherwise. The method compares its argument to each element of the `ArrayList` in order, so using `contains` on a large `ArrayList` can be *inefficient*. Line 42 displays the `ArrayList`'s size.

Java SE 7—Diamond (<>) Notation for Creating an Object of a Generic Class

Consider line 10 of Fig. 6.17:

```
ArrayList<String> items = new ArrayList<String>();
```

Notice that `ArrayList<String>` appears in the variable declaration *and* in the class instance creation expression. Java SE 7 introduced the **diamond (<>)** notation to simplify statements like this. Using `<>` in a class instance creation expression for an object of a *generic* class tells the compiler to determine what belongs in the angle brackets. In Java SE 7 and higher, the preceding statement can be written as:

```
ArrayList<String> items = new ArrayList<>();
```

When the compiler encounters the diamond (`<>`) in the class instance creation expression, it uses the declaration of variable `items` to determine the `ArrayList`'s element type (`String`)—this is known as *inferring the element type*.

6.15 (Optional) GUI and Graphics Case Study: Drawing Arcs

Using Java's graphics features, we can create complex drawings that would be more tedious to code line by line. In Figs. 6.18–6.19, we use arrays and repetition statements to draw a rainbow by using Graphics method `fillArc`. Drawing arcs in Java is similar to drawing ovals—an arc is simply a section of an oval.

In Fig. 6.18, lines 10–11 declare and create two new color constants—`VIOLET` and `INDIGO`. As you may know, the colors of a rainbow are red, orange, yellow, green, blue, indigo and violet. Java has predefined constants only for the first five colors. Lines 15–17 initialize an array with the colors of the rainbow, starting with the innermost arcs first. The array begins with two `Color.WHITE` elements, which, as you'll soon see, are for drawing the empty arcs at the center of the rainbow. The instance variables can be initialized when they're declared, as shown in lines 10–17. The constructor (lines 20–23) contains a single statement that calls method **setBackground** (which is inherited from class `JPanel`) with the parameter `Color.WHITE`. Method `setBackground` takes a single `Color` argument and sets the background of the component to that color.

Line 30 in `paintComponent` declares local variable `radius`, which determines the radius of each arc. Local variables `centerX` and `centerY` (lines 33–34) determine the location of the midpoint on the base of the rainbow. The loop at lines 37–46 uses control variable `counter` to count backward from the end of the array, drawing the largest arcs first and placing each successive smaller arc on top of the previous one. Line 40 sets the color to draw the current arc from the array. The reason we have `Color.WHITE` entries at the beginning of the array is to create the empty arc in the center. Otherwise, the center of the

rainbow would just be a solid violet semicircle. You can change the individual colors and the number of entries in the array to create new designs.

```

1  // Fig. 6.18: DrawRainbow.java
2  // Drawing a rainbow using arcs and an array of colors.
3  import java.awt.Color;
4  import java.awt.Graphics;
5  import javax.swing.JPanel;
6
7  public class DrawRainbow extends JPanel
8  {
9      // define indigo and violet
10     private final static Color VIOLET = new Color(128, 0, 128);
11     private final static Color INDIGO = new Color(75, 0, 130);
12
13     // colors to use in the rainbow, starting from the innermost
14     // The two white entries result in an empty arc in the center
15     private Color[] colors =
16     { Color.WHITE, Color.WHITE, VIOLET, INDIGO, Color.BLUE,
17       Color.GREEN, Color.YELLOW, Color.ORANGE, Color.RED };
18
19     // constructor
20     public DrawRainbow()
21     {
22         setBackground(Color.WHITE); // set the background to white
23     }
24
25     // draws a rainbow using concentric arcs
26     public void paintComponent(Graphics g)
27     {
28         super.paintComponent(g);
29
30         int radius = 20; // radius of an arc
31
32         // draw the rainbow near the bottom-center
33         int centerX = getWidth() / 2;
34         int centerY = getHeight() - 10;
35
36         // draws filled arcs starting with the outermost
37         for (int counter = colors.length; counter > 0; counter--)
38         {
39             // set the color for the current arc
40             g.setColor(colors[counter - 1]);
41
42             // fill the arc from 0 to 180 degrees
43             g.fillArc(centerX - counter * radius,
44                     centerY - counter * radius,
45                     counter * radius * 2, counter * radius * 2, 0, 180);
46         }
47     }
48 } // end class DrawRainbow

```

Fig. 6.18 | Drawing a rainbow using arcs and an array of colors.

The **fillArc** method call at lines 43–45 draws a filled semicircle. Method **fillArc** requires six parameters. The first four represent the bounding rectangle in which the arc will be drawn. The first two of these specify the coordinates for the *upper-left* corner of the bounding rectangle, and the next two specify its width and height. The fifth parameter is the starting angle on the oval, and the sixth specifies the **sweep**, or the amount of arc to cover. The starting angle and sweep are measured in degrees, with zero degrees pointing right. A *positive* sweep draws the arc *counterclockwise*, while a *negative* sweep draws the arc *clockwise*. A method similar to **fillArc** is **drawArc**—it requires the same parameters as **fillArc**, but draws the edge of the arc rather than filling it.

Class **DrawRainbowTest** (Fig. 6.19) creates and sets up a **JFrame** to display the rainbow. Once the program makes the **JFrame** visible, the system calls the **paintComponent** method in class **DrawRainbow** to draw the rainbow on the screen.

```

1  // Fig. 6.19: DrawRainbowTest.java
2  // Test application to display a rainbow.
3  import javax.swing.JFrame;
4
5  public class DrawRainbowTest
6  {
7      public static void main(String[] args)
8      {
9          DrawRainbow panel = new DrawRainbow();
10         JFrame application = new JFrame();
11
12         application.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
13         application.add(panel);
14         application.setSize(400, 250);
15         application.setVisible(true);
16     }
17 } // end class DrawRainbowTest

```




Fig. 6.19 | Test application to display a rainbow.

GUI and Graphics Case Study Exercise

- 6.1** (*Drawing Spirals*) In this exercise, you'll draw spirals with methods **drawLine** and **drawArc**.
- Draw a square-shaped spiral (as in the left screen capture of Fig. 6.20), centered on the panel, using method **drawLine**. One technique is to use a loop that increases the line

- length after drawing every second line. The direction in which to draw the next line should follow a distinct pattern, such as down, left, up, right.
- b) Draw a circular spiral (as in the right screen capture of Fig. 6.20), using method `drawArc` to draw one semicircle at a time. Each successive semicircle should have a larger radius (as specified by the bounding rectangle's width) and should continue drawing where the previous semicircle finished.




Fig. 6.20 | Drawing a spiral using `drawLine` (left) and `drawArc` (right).

6.16 Wrap-Up

This chapter began our introduction to data structures, exploring the use of arrays to store data in and retrieve data from lists and tables of values. The chapter examples demonstrated how to declare an array, initialize an array and refer to individual elements of an array. The chapter introduced the enhanced `for` statement to iterate through arrays. We used exception handling to test for `ArrayIndexOutOfBoundsExceptions` that occur when a program attempts to access an array element outside the bounds of an array. We also illustrated how to pass arrays to methods and how to declare and manipulate multidimensional arrays. Finally, the chapter showed how to write methods that use variable-length argument lists and how to read arguments passed to a program from the command line.

We introduced the `ArrayList<T>` generic collection, which provides all the functionality and performance of arrays, along with other useful capabilities such as dynamic resizing. We used the `add` methods to add new items to the end of an `ArrayList` and to insert items in an `ArrayList`. The `remove` method was used to remove the first occurrence of a specified item, and an overloaded version of `remove` was used to remove an item at a specified index. We used the `size` method to obtain the number of items in the `ArrayList`.

We continue our coverage of data structures in Chapter 16, *Generic Collections*, which introduces the Java Collections Framework and Java's other predefined data structures. Like `ArrayList`, the other predefined data structures use generics to allow you to specify the exact types of objects that a particular data structure will store. Chapter 16 also covers additional methods of class `Arrays`—you'll be able to use some of these after reading the Chapter 6, but others require knowledge of concepts presented later in the book. Chapter 20 discusses generics, which enable you to create general models of methods and classes that can be declared once, but used with many different data types. Chapter 21, *Custom Generic Data Structures*, shows how to build dynamic data structures, such as lists, queues, stacks and trees, that can grow and shrink as programs execute.

We've now introduced the basic concepts of control statements, methods, arrays and collections. As you'll see in Chapter 7, Java applications typically contain just a few lines of code in method `main`—these statements normally create the objects that perform the work of the application. In Chapter 7, you'll learn how to implement your own classes and use objects of those classes in applications.

Summary

Section 6.1 Introduction

- Arrays (p. 209) are fixed-length data structures consisting of related data items of the same type.

Section 6.2 Primitive Types vs. Reference Types

- Types in Java are divided into two categories—primitive types and reference types. The primitive types are `boolean`, `byte`, `char`, `short`, `int`, `long`, `float` and `double`. All other types are reference types, so classes, which specify the types of objects, are reference types.
- A primitive-type variable can store exactly one value of its declared type at a time.
- Reference-type variables (called references; p. 210) store the location of an object in the computer's memory. Such variables refer to objects in the program.
- A reference to an object (p. 210) is required to invoke an object's methods. A primitive-type variable does not refer to an object and therefore cannot be used to invoke a method.

Section 6.3 Arrays

- An array is a group of variables (called elements or components; p. 210) containing values that all have the same type. Arrays are objects, so they're considered reference types.
- A program refers to any one of an array's elements with an array-access expression (p. 211) that includes the name of the array followed by the index of the particular element in square brackets (`[]`; p. 211).
- The first element in every array has index zero (p. 211) and is sometimes called the zeroth element.
- An index must be a nonnegative integer. A program can use an expression as an index.
- An array object's `length` instance variable (p. 211) stores the array's length.

Section 6.4 Declaring and Creating Arrays

- To create an array object, specify the array's element type and the number of elements as part of an array-creation expression (p. 212) that uses keyword `new`.
- When an array is created, each element receives a default value—zero for numeric primitive-type elements, `false` for boolean elements and `null` for references.
- In an array declaration, the type and the square brackets can be combined at the beginning of the declaration to indicate that all the identifiers in the declaration are array variables.
- Every element of a primitive-type array contains a variable of the array's declared type. Every element of a reference-type array is a reference to an object of the array's declared type.

Section 6.5 Examples Using Arrays

- A program can create an array and initialize its elements with an array initializer (p. 214).
- Constant variables (p. 216) are declared with keyword `final`, must be initialized before they're used and cannot be modified thereafter.

Section 6.6 Exception Handling: Processing the Incorrect Response

- An exception indicates a problem that occurs while a program executes. The name “exception” suggests that the problem occurs infrequently—if the “rule” is that a statement normally executes correctly, then the problem represents the “exception to the rule.”
- Exception handling (p. 222) enables you to create fault-tolerant programs.
- When a Java program executes, the JVM checks array indices to ensure that they’re greater than or equal to 0 and less than the array’s length. If a program uses an invalid index, Java generates an exception (p. 222) to indicate that an error occurred in the program at execution time.
- To handle an exception, place any code that might throw an exception (p. 222) in a try statement.
- The try block (p. 222) contains the code that might throw an exception, and the catch block (p. 222) contains the code that handles the exception if one occurs.
- You can have many catch blocks to handle different types of exceptions that might be thrown in the corresponding try block.
- When a try block terminates, any variables declared in the try block go out of scope.
- A catch block declares a type and an exception parameter. Inside the catch block, you can use the parameter’s identifier to interact with a caught exception object.
- When a program is executed, array element indices are checked for validity—all indices must be greater than or equal to 0 and less than the length of the array. If an attempt is made to use an invalid index to access an element, an `ArrayIndexOutOfBoundsException` (p. 223) exception occurs.
- An exception object’s `toString` method returns the exception’s error message.

Section 6.7 Enhanced for Statement

- The enhanced for statement (p. 223) allows you to iterate through the elements of an array or a collection without using a counter. The syntax of an enhanced for statement is:

```
for (parameter : arrayName)
    statement
```

where *parameter* has a type and an identifier, and *arrayName* is the array through which to iterate.

- The enhanced for statement cannot be used to modify elements in an array. If a program needs to modify elements, use the traditional counter-controlled for statement.

Section 6.8 Passing Arrays to Methods

- When an argument is passed by value, a copy of the argument’s value is made and passed to the called method. The called method works exclusively with the copy.

Section 6.9 Pass-By-Value vs. Pass-By-Reference

- When an argument is passed by reference (p. 227), the called method can access the argument’s value in the caller directly and possibly modify it.
- All arguments in Java are passed by value. A method call can pass two types of values to a method—copies of primitive values and copies of references to objects. Although an object’s reference is passed by value (p. 227), a method can still interact with the referenced object by calling its `public` methods using the copy of the object’s reference.
- To pass an object reference to a method, simply specify in the method call the name of the variable that refers to the object.
- When you pass an array or an individual array element of a reference type to a method, the called method receives a copy of the array or element’s reference. When you pass an individual element of a primitive type, the called method receives a copy of the element’s value.
- To pass an individual array element to a method, use the indexed name of the array.

Section 6.10 Multidimensional Arrays

- Multidimensional arrays with two dimensions are often used to represent tables of values consisting of information arranged in rows and columns.
- A two-dimensional array (p. 228) with m rows and n columns is called an m -by- n array. Such an array can be initialized with an array initializer of the form

```
arrayType[][] arrayName = {{row1 initializer}, {row2 initializer}, ...};
```

- Multidimensional arrays are maintained as arrays of separate one-dimensional arrays. As a result, the lengths of the rows in a two-dimensional array are not required to be the same.
- A multidimensional array with the same number of columns in every row can be created with an array-creation expression of the form

```
arrayType[][] arrayName = new arrayType[numRows][numColumns];
```

Section 6.11 Variable-Length Argument Lists

- An argument type followed by an ellipsis (`...`; p. 231) in a method's parameter list indicates that the method receives a variable number of arguments of that particular type. The ellipsis can occur only once in a method's parameter list. It must be at the end of the parameter list.
- A variable-length argument list (p. 231) is treated as an array within the method body. The number of arguments in the array can be obtained using the array's `length` field.

Section 6.12 Using Command-Line Arguments

- Passing arguments to `main` (p. 233) from the command line is achieved by including a parameter of type `String[]` in the parameter list of `main`. By convention, `main`'s parameter is named `args`.
- Java passes command-line arguments that appear after the class name in the `java` command to the application's `main` method as `Strings` in the array `args`.

Section 6.13 Class Arrays

- Class `Arrays`' (p. 235) static methods perform common array manipulations, including `sort`, `binarySearch`, `equals` and `fill`.
- Class `System`'s `arraycopy` method (p. 235) enables you to copy the elements of one array into another.

Section 6.14 Introduction to Collections and Class `ArrayList`

- The Java API's collection classes provide efficient methods that organize, store and retrieve data without requiring knowledge of how the data is being stored.
- An `ArrayList<T>` (p. 238) is similar to an array but can be dynamically resized.
- The `add` method (p. 240) with one argument appends an element to the end of an `ArrayList`.
- The `add` method with two arguments inserts a new element at a specified position in an `ArrayList`.
- The `size` method (p. 240) returns the number of elements currently in an `ArrayList`.
- The `remove` method with a reference to an object as an argument removes the first element that matches the argument's value.
- The `remove` method with an integer argument removes the element at the specified index, and all elements above that index are shifted down by one.
- The `contains` method returns `true` if the element is found in the `ArrayList`, and `false` otherwise.

Self-Review Exercises

- 6.1** Fill in the blank(s) in each of the following statements:
- Lists and tables of values can be stored in _____ and _____.
 - An array is a group of _____ (called elements or components) containing values that all have the same _____.
 - The _____ allows you to iterate through an array's elements without using a counter.
 - The number used to refer to a particular array element is called the element's _____.
 - An array that uses two indices is referred to as a(n) _____ array.
 - Use the enhanced for statement _____ to walk through double array numbers.
 - Command-line arguments are stored in _____.
 - Use the expression _____ to receive the total number of arguments in a command line. Assume that command-line arguments are stored in `String[] args`.
 - Given the command `java MyClass test`, the first command-line argument is _____.
 - A(n) _____ in the parameter list of a method indicates that the method can receive a variable number of arguments.
- 6.2** Determine whether each of the following is *true* or *false*. If *false*, explain why.
- An array can store many different types of values.
 - An array index should normally be of type `float`.
 - An individual array element that's passed to a method and modified in that method will contain the modified value when the called method completes execution.
 - Command-line arguments are separated by commas.
- 6.3** Perform the following tasks for an array called `fractions`:
- Declare a constant `ARRAY_SIZE` that's initialized to 10.
 - Declare an array with `ARRAY_SIZE` elements of type `double`, and initialize the elements to 0.
 - Refer to array element 4.
 - Assign the value 1.667 to array element 9.
 - Assign the value 3.333 to array element 6.
 - Sum all the elements of the array, using a `for` statement. Declare the integer variable `x` as a control variable for the loop.
- 6.4** Perform the following tasks for an array called `table`:
- Declare and create the array as an integer array that has three rows and three columns. Assume that the constant `ARRAY_SIZE` has been declared to be 3.
 - How many elements does the array contain?
 - Use a `for` statement to initialize each element of the array to the sum of its indices. Assume that the integer variables `x` and `y` are declared as control variables.
- 6.5** Find and correct the error in each of the following program segments:
- ```
final int ARRAY_SIZE = 5;
ARRAY_SIZE = 10;
```
  - ```
int[] b = new int[10];
for (int i = 0; i <= b.length; i++)
    b[i] = 1;
```
 - ```
int[][] a = {{1, 2}, {3, 4}};
a[1, 1] = 5;
```

## Answers to Self-Review Exercises

- 6.1** a) arrays, collections. b) variables, type. c) enhanced for statement. d) index (or subscript or position number). e) two-dimensional. f) `for (double d : numbers)`. g) an array of `Strings`, called `args` by convention. h) `args.length`. i) `test`. j) ellipsis (`...`).



- 6.2
- a) False. An array can store only values of the same type.
  - b) False. An array index must be an integer or an integer expression.
  - c) For individual primitive-type elements of an array: False. A called method receives and manipulates a copy of the element value, so modifications do not affect the original. If the reference of an array is passed to a method, however, modifications to the array elements made in the called method *are* reflected in the original. For individual elements of a reference type: True. A called method receives a copy of the element's reference, and changes to the referenced object will be reflected in the original array element.
  - d) False. Command-line arguments are separated by white space.
- 6.3
- a) `final int ARRAY_SIZE = 10;`
  - b) `double[] fractions = new double[ARRAY_SIZE];`
  - c) `fractions[4]`
  - d) `fractions[9] = 1.667;`
  - e) `fractions[6] = 3.333;`
  - f) `double total = 0.0;`  
`for (int x = 0; x < fractions.length; x++)`  
`total += fractions[x];`
- 6.4
- a) `int[][] table = new int[ARRAY_SIZE][ARRAY_SIZE];`
  - b) Nine.
  - c) `for (int x = 0; x < table.length; x++)`  
`for (int y = 0; y < table[x].length; y++)`  
`table[x][y] = x + y;`
- 6.5
- a) Error: Assigning a value to a constant after it has been initialized.  
Correction: Assign the correct value to the constant in a `final int ARRAY_SIZE` declaration or declare another variable.
  - b) Error: Referencing an array element outside the bounds of the array (`b[10]`).  
Correction: Change the `<=` operator to `<`.
  - c) Error: Array indexing is performed incorrectly.  
Correction: Change the statement to `a[1][1] = 5;`.

## Exercises

- 6.6 Fill in the blanks in each of the following statements:
- a) One-dimensional array `p` contains four elements. The names of those elements are \_\_\_\_\_, \_\_\_\_\_, \_\_\_\_\_ and \_\_\_\_\_.
  - b) Naming an array, stating its type and specifying the number of dimensions in the array is called \_\_\_\_\_ the array.
  - c) In a two-dimensional array, the first index identifies the \_\_\_\_\_ of an element and the second index identifies the \_\_\_\_\_ of an element.
  - d) An  $m$ -by- $n$  array contains \_\_\_\_\_ rows, \_\_\_\_\_ columns and \_\_\_\_\_ elements.
  - e) The name of the element in row 3 and column 5 of array `d` is \_\_\_\_\_.
- 6.7 Determine whether each of the following is *true* or *false*. If *false*, explain why.
- a) To refer to a particular location or element within an array, we specify the name of the array and the value of the particular element.
  - b) An array declaration reserves space for the array.
  - c) To indicate that 100 locations should be reserved for integer array `p`, you write the declaration  
`p[100];`

- d) An application that initializes the elements of a 15-element array to zero must contain at least one `for` statement.
- e) An application that totals the elements of a two-dimensional array must contain nested `for` statements.

**6.8** Write Java statements to accomplish each of the following tasks:

- a) Display the value of element 6 of array `f`.
- b) Initialize each of the five elements of one-dimensional integer array `g` to 8.
- c) Total the 100 elements of floating-point array `c`.
- d) Copy 11-element array `a` into the first portion of array `b`, which contains 34 elements.
- e) Determine and display the smallest and largest values contained in 99-element floating-point array `w`.

**6.9** Consider a two-by-three integer array `t`.

- a) Write a statement that declares and creates `t`.
- b) How many rows does `t` have?
- c) How many columns does `t` have?
- d) How many elements does `t` have?
- e) Write access expressions for all the elements in row 1 of `t`.
- f) Write access expressions for all the elements in column 2 of `t`.
- g) Write a single statement that sets the element of `t` in row 0 and column 1 to zero.
- h) Write individual statements to initialize each element of `t` to zero.
- i) Write a nested `for` statement that initializes each element of `t` to zero.
- j) Write a nested `for` statement that inputs the values for the elements of `t` from the user.
- k) Write a series of statements that determines and displays the smallest value in `t`.
- l) Write a single `printf` statement that displays the elements of the first row of `t`.
- m) Write a statement that totals the elements of the third column of `t`. Do not use repetition.
- n) Write a series of statements that displays the contents of `t` in tabular format. List the column indices as headings across the top, and list the row indices at the left of each row.

**6.10** (*Sales Commissions*) Use a one-dimensional array to solve the following problem: A company pays its salespeople on a commission basis. The salespeople receive \$200 per week plus 9% of their gross sales for that week. For example, a salesperson who grosses \$5,000 in sales in a week receives \$200 plus 9% of \$5,000, or a total of \$650. Write an application (using an array of counters) that determines how many of the salespeople earned salaries in each of the following ranges (assume that each salesperson's salary is truncated to an integer amount):

- a) \$200–299
- b) \$300–399
- c) \$400–499
- d) \$500–599
- e) \$600–699
- f) \$700–799
- g) \$800–899
- h) \$900–999
- i) \$1,000 and over

Summarize the results in tabular format.

**6.11** Write statements that perform the following one-dimensional-array operations:

- a) Set the 10 elements of integer array `counts` to zero.
- b) Add one to each of the 15 elements of integer array `bonus`.
- c) Display the five values of integer array `bestScores` in column format.

**6.12** (*Duplicate Elimination*) Use a one-dimensional array to solve the following problem: Write an application that inputs five numbers, each between 10 and 100, inclusive. As each number

is read, display it only if it's not a duplicate of a number already read. Provide for the "worst case," in which all five numbers are different. Use the smallest possible array to solve this problem. Display the complete set of unique values input after the user enters each new value.

**6.13** Label the elements of three-by-five two-dimensional array `sales` to indicate the order in which they're set to zero by the following program segment:

```
for (int row = 0; row < sales.length; row++)
{
 for (int col = 0; col < sales[row].length; col++)
 {
 sales[row][col] = 0;
 }
}
```

**6.14** (*Variable-Length Argument List*) Write an application that calculates the product of a series of integers that are passed to method `product` using a variable-length argument list. Test your method with several calls, each with a different number of arguments.

**6.15** (*Command-Line Arguments*) Rewrite Fig. 6.2 so that the size of the array is specified by the first command-line argument. If no command-line argument is supplied, use 10 as the default size of the array.

**6.16** (*Using the Enhanced for Statement*) Write an application that uses an enhanced for statement to sum the double values passed by the command-line arguments. [Hint: Use the static method `parseDouble` of class `Double` to convert a `String` to a double value.]

**6.17** (*Dice Rolling*) Write an application to simulate the rolling of two dice. The application should use an object of class `Random` once to roll the first die and again to roll the second die. The sum of the two values should then be calculated. Each die can show an integer value from 1 to 6, so the sum of the values will vary from 2 to 12, with 7 being the most frequent sum, and 2 and 12 the least frequent. Figure 6.21 shows the 36 possible combinations of the two dice. Your application should roll the dice 36,000,000 times. Use a one-dimensional array to tally the number of times each possible sum appears. Display the results in tabular format.

|   | 1 | 2 | 3 | 4  | 5  | 6  |
|---|---|---|---|----|----|----|
| 1 | 2 | 3 | 4 | 5  | 6  | 7  |
| 2 | 3 | 4 | 5 | 6  | 7  | 8  |
| 3 | 4 | 5 | 6 | 7  | 8  | 9  |
| 4 | 5 | 6 | 7 | 8  | 9  | 10 |
| 5 | 6 | 7 | 8 | 9  | 10 | 11 |
| 6 | 7 | 8 | 9 | 10 | 11 | 12 |

**Fig. 6.21** | The 36 possible sums of two dice.

**6.18** (*Game of Craps*) Write an application that runs 1,000,000 games of craps (Fig. 5.8) and answers the following questions:

- How many games are won on the first roll, second roll, ..., twentieth roll and after the twentieth roll?
- How many games are lost on the first roll, second roll, ..., twentieth roll and after the twentieth roll?
- What are the chances of winning at craps? [Note: You should discover that craps is one of the fairest casino games. What do you suppose this means?]

- d) What is the average length of a game of craps?
- e) Do the chances of winning improve with the length of the game?

**6.19 (Airline Reservations System)** A small airline has just purchased a computer for its new automated reservations system. You've been asked to develop the new system. You're to write an application to assign seats on each flight of the airline's only plane (capacity: 10 seats).

Your application should display the following alternatives: Please type 1 for First Class and Please type 2 for Economy. If the user types 1, your application should assign a seat in the first-class section (seats 1–5). If the user types 2, your application should assign a seat in the economy section (seats 6–10). Your application should then display a boarding pass indicating the person's seat number and whether it's in the first-class or economy section of the plane.

Use a one-dimensional array of primitive type `boolean` to represent the seating chart of the plane. Initialize all the elements of the array to `false` to indicate that all the seats are empty. As each seat is assigned, set the corresponding element of the array to `true` to indicate that the seat is no longer available.

Your application should never assign a seat that has already been assigned. When the economy section is full, your application should ask the person if it's acceptable to be placed in the first-class section (and vice versa). If yes, make the appropriate seat assignment. If no, display the message "Next flight leaves in 3 hours."

**6.20 (Total Sales)** Use a two-dimensional array to solve the following problem: A company has four salespeople (1 to 4) who sell five different products (1 to 5). Once a day, each salesperson passes in a slip for each type of product sold. Each slip contains the following:

- a) The salesperson number
- b) The product number
- c) The total dollar value of that product sold that day

Thus, each salesperson passes in between 0 and 5 sales slips per day. Assume that the information from all the slips for last month is available. Write an application that will read all this information for last month's sales and summarize the total sales by salesperson and by product. All totals should be stored in the two-dimensional array `sales`. After processing all the information for last month, display the results in tabular format, with each column representing a salesperson and each row representing a particular product. Cross-total each row to get the total sales of each product for last month. Cross-total each column to get the total sales by salesperson for last month. Your output should include these cross-totals to the right of the totaled rows and to the bottom of the totaled columns.

**6.21 (Turtle Graphics)** The Logo language made the concept of *turtle graphics* famous. Imagine a mechanical turtle that walks around the room under the control of a Java application. The turtle holds a pen in one of two positions, up or down. While the pen is down, the turtle traces out shapes as it moves, and while the pen is up, the turtle moves about freely without writing anything. In this problem, you'll simulate the operation of the turtle and create a computerized sketchpad.

Use a 20-by-20 array `floor` that's initialized to zeros. Read commands from an array that contains them. Keep track of the current position of the turtle at all times and whether the pen is currently up or down. Assume that the turtle always starts at position (0, 0) of the floor with its pen up. The set of turtle commands your application must process are shown in Fig. 6.22.

| Command | Meaning  |
|---------|----------|
| 1       | Pen up   |
| 2       | Pen down |

**Fig. 6.22** | Turtle graphics commands. (Part 1 of 2.)

| Command | Meaning                                                              |
|---------|----------------------------------------------------------------------|
| 3       | Turn right                                                           |
| 4       | Turn left                                                            |
| 5,10    | Move forward 10 spaces (replace 10 for a different number of spaces) |
| 6       | Display the 20-by-20 array                                           |
| 9       | End of data (sentinel)                                               |

**Fig. 6.22** | Turtle graphics commands. (Part 2 of 2.)

Suppose that the turtle is somewhere near the center of the floor. The following “program” would draw and display a 12-by-12 square, leaving the pen in the up position:

```

2
5,12
3
5,12
3
5,12
3
5,12
1
6
9

```


As the turtle moves with the pen down, set the appropriate elements of array `floor` to 1s. When the 6 command (display the array) is given, wherever there's a 1 in the array, display an asterisk or any character you choose. Wherever there's a 0, display a blank.

Write an application to implement the turtle graphics capabilities discussed here. Write several turtle graphics programs to draw interesting shapes. Add other commands to increase the power of your turtle graphics language.

**6.22** (*Knight's Tour*) An interesting puzzler for chess buffs is the Knight's Tour problem, originally proposed by the mathematician Euler. Can the knight piece move around an empty chessboard and touch each of the 64 squares once and only once? We study this intriguing problem in depth here.

The knight makes only L-shaped moves (two spaces in one direction and one space in a perpendicular direction). Thus, as shown in Fig. 6.23, from a square near the middle of an empty chessboard, the knight (labeled K) can make eight different moves (numbered 0 through 7).

- Draw an eight-by-eight chessboard on a sheet of paper, and attempt a Knight's Tour by hand. Put a 1 in the starting square, a 2 in the second square, a 3 in the third, and so on. Before starting the tour, estimate how far you think you'll get, remembering that a full tour consists of 64 moves. How far did you get? Was this close to your estimate?
- Now let's develop an application that will move the knight around a chessboard. The board is represented by an eight-by-eight two-dimensional array board. Each square is initialized to zero. We describe each of the eight possible moves in terms of its horizontal and vertical components. For example, a move of type 0, as shown in Fig. 6.23, consists of moving two squares horizontally to the right and one square vertically upward. A move of type 2 consists of moving one square horizontally to the left and two squares vertically upward. Horizontal moves to the left and vertical moves upward are indicated with negative numbers. The eight moves may be described by two one-dimensional arrays, `horizontal` and `vertical`, as follows:



**Fig. 6.23** | The eight possible moves of the knight.

```
horizontal[0] = 2 vertical[0] = -1
horizontal[1] = 1 vertical[1] = -2
horizontal[2] = -1 vertical[2] = -2
horizontal[3] = -2 vertical[3] = -1
horizontal[4] = -2 vertical[4] = 1
horizontal[5] = -1 vertical[5] = 2
horizontal[6] = 1 vertical[6] = 2
horizontal[7] = 2 vertical[7] = 1
```

Let the variables `currentRow` and `currentColumn` indicate the row and column, respectively, of the knight's current position. To make a move of type `moveNumber`, where `moveNumber` is between 0 and 7, your application should use the statements

```
currentRow += vertical[moveNumber];
currentColumn += horizontal[moveNumber];
```

Write an application to move the knight around the chessboard. Keep a counter that varies from 1 to 64. Record the latest count in each square the knight moves to. Test each potential move to see if the knight has already visited that square. Test every potential move to ensure that the knight does not land off the chessboard. Run the application. How many moves did the knight make?

- c) After attempting to write and run a Knight's Tour application, you've probably developed some valuable insights. We'll use these insights to develop a *heuristic* (i.e., a common-sense rule) for moving the knight. Heuristics do not guarantee success, but a carefully developed heuristic greatly improves the chance of success. You may have observed that the outer squares are more troublesome than the squares nearer the center of the board. In fact, the most troublesome or inaccessible squares are the four corners.

Intuition may suggest that you should attempt to move the knight to the most troublesome squares first and leave open those that are easiest to get to, so that when the board gets congested near the end of the tour, there will be a greater chance of success.

We could develop an "accessibility heuristic" by classifying each of the squares according to how accessible it is and always moving the knight (using the knight's L-shaped moves) to the most inaccessible square. We label a two-dimensional array `accessibility` with numbers indicating from how many squares each particular square is accessible. On a blank chessboard, each of the 16 squares nearest the center is rated as 8, each corner square is rated as 2, and the other squares have accessibility numbers of 3, 4 or 6 as follows:

|   |   |   |   |   |   |   |   |
|---|---|---|---|---|---|---|---|
| 2 | 3 | 4 | 4 | 4 | 4 | 3 | 2 |
| 3 | 4 | 6 | 6 | 6 | 6 | 4 | 3 |
| 4 | 6 | 8 | 8 | 8 | 8 | 6 | 4 |
| 4 | 6 | 8 | 8 | 8 | 8 | 6 | 4 |
| 4 | 6 | 8 | 8 | 8 | 8 | 6 | 4 |
| 4 | 6 | 8 | 8 | 8 | 8 | 6 | 4 |
| 3 | 4 | 6 | 6 | 6 | 6 | 4 | 3 |
| 2 | 3 | 4 | 4 | 4 | 4 | 3 | 2 |

Write a new version of the Knight's Tour, using the accessibility heuristic. The knight should always move to the square with the lowest accessibility number. In case of a tie, the knight may move to any of the tied squares. Therefore, the tour may begin in any of the four corners. [Note: As the knight moves around the chessboard, your application should reduce the accessibility numbers as more squares become occupied. In this way, at any given time during the tour, each available square's accessibility number will remain equal to precisely the number of squares from which that square may be reached.] Run this version of your application. Did you get a full tour? Modify the application to run 64 tours, one starting from each square of the chessboard. How many full tours did you get?

- d) Write a version of the Knight's Tour application that, when encountering a tie between two or more squares, decides what square to choose by looking ahead to those squares reachable from the "tied" squares. Your application should move to the tied square for which the next move would arrive at a square with the lowest accessibility number.


**6.23 (Knight's Tour: Brute-Force Approaches)** In part (c) of Exercise 6.22, we developed a solution to the Knight's Tour problem. The approach used, called the "accessibility heuristic," generates many solutions and executes efficiently.

As computers continue to increase in power, we'll be able to solve more problems with sheer computer power and relatively unsophisticated algorithms. Let's call this approach "brute-force" problem solving.

- Use random-number generation to enable the knight to walk around the chessboard (in its legitimate L-shaped moves) at random. Your application should run one tour and display the final chessboard. How far did the knight get?
- Most likely, the application in part (a) produced a relatively short tour. Now modify your application to attempt 1,000 tours. Use a one-dimensional array to keep track of the number of tours of each length. When your application finishes attempting the 1,000 tours, it should display this information in neat tabular format. What was the best result?
- Most likely, the application in part (b) gave you some "respectable" tours, but no full tours. Now let your application run until it produces a full tour. [Caution: This version of the application could run for hours on a powerful computer.] Once again, keep a table of the number of tours of each length, and display this table when the first full tour is found. How many tours did your application attempt before producing a full tour? How much time did it take?
- Compare the brute-force version of the Knight's Tour with the accessibility-heuristic version. Which required a more careful study of the problem? Which algorithm was more difficult to develop? Which required more computer power? Could we be certain (in advance) of obtaining a full tour with the accessibility-heuristic approach? Could we be certain (in advance) of obtaining a full tour with the brute-force approach? Argue the pros and cons of brute-force problem solving in general.

**6.24 (Eight Queens)** Another puzzler for chess buffs is the Eight Queens problem, which asks the following: Is it possible to place eight queens on an empty chessboard so that no queen is "attacking" any other (i.e., no two queens are in the same row, in the same column or along the same diagonal)?

Use the thinking developed in Exercise 6.22 to formulate a heuristic for solving the Eight Queens problem. Run your application. [Hint: It's possible to assign a value to each square of the chessboard to indicate how many squares of an empty chessboard are "eliminated" if a queen is placed in that square. Each of the corners would be assigned the value 22, as demonstrated by Fig. 6.24. Once these "elimination numbers" are placed in all 64 squares, an appropriate heuristic might be as follows: Place the next queen in the square with the smallest elimination number. Why is this strategy intuitively appealing?]



**Fig. 6.24** | The 22 squares eliminated by placing a queen in the upper left corner.

**6.25** (*Eight Queens: Brute-Force Approaches*) In this exercise, you'll develop several brute-force approaches to solving the Eight Queens problem introduced in Exercise 6.24.

- Use the random brute-force technique developed in Exercise 6.23 to solve the Eight Queens problem.
- Use an exhaustive technique (i.e., try all possible combinations of eight queens on the chessboard) to solve the Eight Queens problem.
- Why might the exhaustive brute-force approach not be appropriate for solving the Knight's Tour problem?
- Compare and contrast the random brute-force and exhaustive brute-force approaches.

**6.26** (*Knight's Tour: Closed-Tour Test*) In the Knight's Tour (Exercise 6.22), a full tour occurs when the knight makes 64 moves, touching each square of the chessboard once and only once. A closed tour occurs when the 64th move is one move away from the square in which the knight started the tour. Modify the application you wrote in Exercise 6.22 to test for a closed tour if a full tour has occurred.

**6.27** (*Sieve of Eratosthenes*) A prime number is any integer greater than 1 that's evenly divisible only by itself and 1. The Sieve of Eratosthenes is a method of finding prime numbers. It operates as follows:

- Create a primitive-type `boolean` array with all elements initialized to `true`. Array elements with prime indices will remain `true`. All other array elements will eventually be set to `false`.
- Starting with array index 2, determine whether a given element is `true`. If so, loop through the remainder of the array and set to `false` every element whose index is a multiple of the index for the element with value `true`. Then continue the process with the next element with value `true`. For array index 2, all elements beyond element 2 in the array that have indices which are multiples of 2 (indices 4, 6, 8, 10, etc.) will be set to `false`; for array index 3, all elements beyond element 3 in the array that have indices which are multiples of 3 (indices 6, 9, 12, 15, etc.) will be set to `false`; and so on.



When this process completes, the array elements that are still `true` indicate that the index is a prime number. These indices can be displayed. Write an application that uses an array of 1,000 elements to determine and display the prime numbers between 2 and 999. Ignore array elements 0 and 1.

**6.28** (*Simulation: The Tortoise and the Hare*) In this problem, you'll re-create the classic race of the tortoise and the hare. You'll use random-number generation to develop a simulation of this memorable event.

Our contenders begin the race at square 1 of 70 squares. Each square represents a possible position along the race course. The finish line is at square 70. The first contender to reach or pass square 70 is rewarded with a pail of fresh carrots and lettuce. The course weaves its way up the side of a slippery mountain, so occasionally the contenders lose ground.

A clock ticks once per second. With each tick of the clock, your application should adjust the position of the animals according to the rules in Fig. 6.25. Use variables to keep track of the positions of the animals (i.e., position numbers are 1–70). Start each animal at position 1 (the “starting gate”). If an animal slips left before square 1, move it back to square 1.

| Animal   | Move type  | Percentage of the time | Actual move            |
|----------|------------|------------------------|------------------------|
| Tortoise | Fast plod  | 50%                    | 3 squares to the right |
|          | Slip       | 20%                    | 6 squares to the left  |
|          | Slow plod  | 30%                    | 1 square to the right  |
| Hare     | Sleep      | 20%                    | No move at all         |
|          | Big hop    | 20%                    | 9 squares to the right |
|          | Big slip   | 10%                    | 12 squares to the left |
|          | Small hop  | 30%                    | 1 square to the right  |
|          | Small slip | 20%                    | 2 squares to the left  |

**Fig. 6.25** | Rules for adjusting the positions of the tortoise and the hare.

Generate the percentages in Fig. 6.25 by producing a random integer  $i$  in the range  $1 \leq i \leq 10$ . For the tortoise, perform a “fast plod” when  $1 \leq i \leq 5$ , a “slip” when  $6 \leq i \leq 7$  or a “slow plod” when  $8 \leq i \leq 10$ . Use a similar technique to move the hare.

Begin the race by displaying

```
BANG !!!!!
AND THEY'RE OFF !!!!!
```

Then, for each tick of the clock (i.e., each repetition of a loop), display a 70-position line showing the letter `T` in the position of the tortoise and the letter `H` in the position of the hare. Occasionally, the contenders will land on the same square. In this case, the tortoise bites the hare, and your application should display `OUCH!!!` beginning at that position. All output positions other than the `T`, the `H` or the `OUCH!!!` (in case of a tie) should be blank.

After each line is displayed, test for whether either animal has reached or passed square 70. If so, display the winner and terminate the simulation. If the tortoise wins, display `TORTOISE WINS!!! YAY!!!`. If the hare wins, display `Hare wins. Yuch.` If both animals win on the same tick of the clock, you may want to favor the tortoise (the “underdog”), or you may want to display `It's a tie.` If neither animal wins, perform the loop again to simulate the next tick of the clock. When you're ready to run your application, assemble a group of fans to watch the race. You'll be amazed at how involved your audience gets!

Later in the book, we introduce a number of Java capabilities, such as graphics, images, animation, sound and multithreading. As you study those features, you might enjoy enhancing your tortoise-and-hare contest simulation.

**6.29 (Fibonacci Series)** The Fibonacci series

0, 1, 1, 2, 3, 5, 8, 13, 21, ...

begins with the terms 0 and 1 and has the property that each succeeding term is the sum of the two preceding terms.

- a) Write a method `fibonacci(n)` that calculates the  $n$ th Fibonacci number. Incorporate this method into an application that enables the user to enter the value of  $n$ .
- b) Determine the largest Fibonacci number that can be displayed on your system.
- c) Modify the application you wrote in part (a) to use `double` instead of `int` to calculate and return Fibonacci numbers, and use this modified application to repeat part (b).

**Special Section: Building Your Own Computer**

In the next several problems, we take a temporary diversion from the world of high-level language programming to “peel open” a computer and look at its internal structure. We introduce machine-language programming and write several machine-language programs. To make this an especially valuable experience, we then build a computer (through the technique of software-based *simulation*) on which you can execute your machine-language programs.

**6.30 (Machine-Language Programming)** Let’s create a computer called the Simpletron. As its name implies, it’s a simple machine, but powerful. The Simpletron runs programs written in the only language it directly understands: Simpletron Machine Language (SML).

The Simpletron contains an *accumulator*—a special register in which information is put before the Simpletron uses that information in calculations or examines it in various ways. All the information in the Simpletron is handled in terms of *words*. A word is a signed four-digit decimal number, such as +3364, -1293, +0007 and -0001. The Simpletron is equipped with a 100-word memory, and these words are referenced by their location numbers 00, 01, ..., 99.

Before running an SML program, we must *load*, or place, the program into memory. The first instruction (or statement) of every SML program is always placed in location 00. The simulator will start executing at this location.

Each instruction written in SML occupies one word of the Simpletron’s memory (so instructions are signed four-digit decimal numbers). We shall assume that the sign of an SML instruction is always plus, but the sign of a data word may be either plus or minus. Each location in the Simpletron’s memory may contain an instruction, a data value used by a program or an unused (and so undefined) area of memory. The first two digits of each SML instruction are the *operation code* specifying the operation to be performed. SML operation codes are summarized in Fig. 6.26.

The last two digits of an SML instruction are the *operand*—the address of the memory location containing the word to which the operation applies. Let’s consider several simple SML programs.

| Operation code                    | Meaning                                                           |
|-----------------------------------|-------------------------------------------------------------------|
| <i>Input/output operations:</i>   |                                                                   |
| <code>final int READ = 10;</code> | Read a word from the keyboard into a specific location in memory. |

**Fig. 6.26** | Simpletron Machine Language (SML) operation codes. (Part I of 2.)

| Operation code                         | Meaning                                                                                                                    |
|----------------------------------------|----------------------------------------------------------------------------------------------------------------------------|
| <b>final int</b> WRITE = 11;           | Write a word from a specific location in memory to the screen.                                                             |
| <i>Load/store operations:</i>          |                                                                                                                            |
| <b>final int</b> LOAD = 20;            | Load a word from a specific location in memory into the accumulator.                                                       |
| <b>final int</b> STORE = 21;           | Store a word from the accumulator into a specific location in memory.                                                      |
| <i>Arithmetic operations:</i>          |                                                                                                                            |
| <b>final int</b> ADD = 30;             | Add a word from a specific location in memory to the word in the accumulator (leave the result in the accumulator).        |
| <b>final int</b> SUBTRACT = 31;        | Subtract a word from a specific location in memory from the word in the accumulator (leave the result in the accumulator). |
| <b>final int</b> DIVIDE = 32;          | Divide a word from a specific location in memory into the word in the accumulator (leave result in the accumulator).       |
| <b>final int</b> MULTIPLY = 33;        | Multiply a word from a specific location in memory by the word in the accumulator (leave the result in the accumulator).   |
| <i>Transfer-of-control operations:</i> |                                                                                                                            |
| <b>final int</b> BRANCH = 40;          | Branch to a specific location in memory.                                                                                   |
| <b>final int</b> BRANCHNEG = 41;       | Branch to a specific location in memory if the accumulator is negative.                                                    |
| <b>final int</b> BRANCHZERO = 42;      | Branch to a specific location in memory if the accumulator is zero.                                                        |
| <b>final int</b> HALT = 43;            | Halt. The program has completed its task.                                                                                  |

**Fig. 6.26** | Simpletron Machine Language (SML) operation codes. (Part 2 of 2.)

The first SML program (Fig. 6.27) reads two numbers from the keyboard and computes and displays their sum. The instruction +1007 reads the first number from the keyboard and places it into location 07 (which has been initialized to 0). Then instruction +1008 reads the next number into location 08. The *load* instruction, +2007, puts the first number into the accumulator, and the *add* instruction, +3008, adds the second number to the number in the accumulator. *All SML arithmetic instructions leave their results in the accumulator.* The *store* instruction, +2109, places the result back into memory location 09, from which the *write* instruction, +1109, takes the number and displays it (as a signed four-digit decimal number). The *halt* instruction, +4300, terminates execution.

| Location | Number | Instruction |
|----------|--------|-------------|
| 00       | +1007  | (Read A)    |
| 01       | +1008  | (Read B)    |
| 02       | +2007  | (Load A)    |
| 03       | +3008  | (Add B)     |

**Fig. 6.27** | SML program that reads two integers and computes their sum. (Part 1 of 2.)

| Location | Number | Instruction  |
|----------|--------|--------------|
| 04       | +2109  | (Store C)    |
| 05       | +1109  | (Write C)    |
| 06       | +4300  | (Halt)       |
| 07       | +0000  | (Variable A) |
| 08       | +0000  | (Variable B) |
| 09       | +0000  | (Result C)   |

**Fig. 6.27** | SML program that reads two integers and computes their sum. (Part 2 of 2.)

The second SML program (Fig. 6.28) reads two numbers from the keyboard and determines and displays the larger value. Note the use of the instruction +4107 as a conditional transfer of control, much the same as Java's `if` statement.

| Location | Number | Instruction             |
|----------|--------|-------------------------|
| 00       | +1009  | (Read A)                |
| 01       | +1010  | (Read B)                |
| 02       | +2009  | (Load A)                |
| 03       | +3110  | (Subtract B)            |
| 04       | +4107  | (Branch negative to 07) |
| 05       | +1109  | (Write A)               |
| 06       | +4300  | (Halt)                  |
| 07       | +1110  | (Write B)               |
| 08       | +4300  | (Halt)                  |
| 09       | +0000  | (Variable A)            |
| 10       | +0000  | (Variable B)            |

**Fig. 6.28** | SML program that reads two integers and determines the larger.

Now write SML programs to accomplish each of the following tasks:

- Use a sentinel-controlled loop to read 10 positive numbers. Compute and display their sum.
- Use a counter-controlled loop to read seven numbers, some positive and some negative, and compute and display their average.
- Read a series of numbers, and determine and display the largest number. The first number read indicates how many numbers should be processed.

**6.31 (Computer Simulator)** In this problem, you're going to build your own computer. No, you'll not be soldering components together. Rather, you'll use the powerful technique of *software-based simulation* to create an object-oriented *software model* of the Simpletron of Exercise 6.30. Your Simpletron simulator will turn the computer you're using into a Simpletron, and you'll actually be able to run, test and debug the SML programs you wrote in Exercise 6.30.

When you run your Simpletron simulator, it should begin by displaying:

```
*** Welcome to Simpletron! ***
*** Please enter your program one instruction ***
*** (or data word) at a time. I will display ***
*** the location number and a question mark (?). ***
*** You then type the word for that location. ***
*** Type -99999 to stop entering your program. ***
```

Your application should simulate the memory of the Simpletron with a one-dimensional array memory that has 100 elements. Now assume that the simulator is running, and let's examine the dialog as we enter the program of Fig. 6.28 (Exercise 6.30):

```
00 ? +1009
01 ? +1010
02 ? +2009
03 ? +3110
04 ? +4107
05 ? +1109
06 ? +4300
07 ? +1110
08 ? +4300
09 ? +0000
10 ? +0000
11 ? -99999
```

Your program should display the memory location followed by a question mark. Each value to the right of a question mark is input by the user. When the sentinel value -99999 is input, the program should display the following:

```
*** Program loading completed ***
*** Program execution begins ***
```

The SML program has now been placed (or loaded) in array memory. Now the Simpletron executes the SML program. Execution begins with the instruction in location 00 and, as in Java, continues sequentially, unless directed to some other part of the program by a transfer of control.

Use the variable `accumulator` to represent the accumulator register. Use the variable `instructionCounter` to keep track of the location in memory that contains the instruction being performed. Use the variable `operationCode` to indicate the operation currently being performed (i.e., the left two digits of the instruction word). Use the variable `operand` to indicate the memory location on which the current instruction operates. Thus, `operand` is the rightmost two digits of the instruction currently being performed. Do not execute instructions directly from memory. Rather, transfer the next instruction to be performed from memory to a variable called `instructionRegister`. Then pick off the left two digits and place them in `operationCode`, and pick off the right two digits and place them in `operand`. When the Simpletron begins execution, the special registers are all initialized to zero.

Now, let's walk through execution of the first SML instruction, +1009 in memory location 00. This procedure is called an *instruction-execution cycle*.

The `instructionCounter` tells us the location of the next instruction to be performed. We *fetch* the contents of that location from memory by using the Java statement

```
instructionRegister = memory[instructionCounter];
```

The operation code and the operand are extracted from the instruction register by the statements

```
operationCode = instructionRegister / 100;
operand = instructionRegister % 100;
```

Now the Simpletron must determine that the operation code is actually a *read* (versus a *write*, a *load*, and so on). A switch differentiates among the 12 operations of SML. In the switch state-

ment, the behavior of various SML instructions is simulated as shown in Fig. 6.29. We discuss branch instructions shortly and leave the others to you.

When the SML program completes execution, the name and contents of each register as well as the complete contents of memory should be displayed. Such a printout is often called a computer dump (no, a computer dump is not a place where old computers go). To help you program your dump method, a sample dump format is shown in Fig. 6.30. A dump after executing a Simpletron program would show the actual values of instructions and data values at the moment execution terminated.

| Instruction  | Description                                                                                             |
|--------------|---------------------------------------------------------------------------------------------------------|
| <i>read:</i> | Display the prompt "Enter an integer", then input the integer and store it in location memory[operand]. |
| <i>load:</i> | accumulator = memory[operand];                                                                          |
| <i>add:</i>  | accumulator += memory[operand];                                                                         |
| <i>halt:</i> | This instruction displays the message<br>*** Simpletron execution terminated ***                        |

**Fig. 6.29** | Behavior of several SML instructions in the Simpletron.

```

REGISTERS:
accumulator +0000
instructionCounter 00
instructionRegister +0000
operationCode 00
operand 00

MEMORY:
 0 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000
 10 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000
 20 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000
 30 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000
 40 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000
 50 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000
 60 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000
 70 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000
 80 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000
 90 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000

```

**Fig. 6.30** | A sample dump.

Let's proceed with the execution of our program's first instruction—namely, the +1009 in location 00. As we've indicated, the switch statement simulates this task by prompting the user to enter a value, reading the value and storing it in memory location memory[operand]. The value is then read into location 09.

At this point, simulation of the first instruction is completed. All that remains is to prepare the Simpletron to execute the next instruction. Since the instruction just performed was not a transfer of control, we need merely increment the instruction-counter register as follows:

```
instructionCounter++;
```

This action completes the simulated execution of the first instruction. The entire process (i.e., the instruction-execution cycle) begins anew with the fetch of the next instruction to execute.

Now let's consider how the branching instructions—the transfers of control—are simulated. All we need to do is adjust the value in the instruction counter appropriately. Therefore, the unconditional branch instruction (40) is simulated within the switch as

```
instructionCounter = operand;
```

The conditional “branch if accumulator is zero” instruction is simulated as

```
if (accumulator == 0)
 instructionCounter = operand;
```

At this point, you should implement your Simpletron simulator and run each of the SML programs you wrote in Exercise 6.30. If you desire, you may embellish SML with additional features and provide for these features in your simulator.

Your simulator should check for various types of errors. During the program-loading phase, for example, each number the user types into the Simpletron's memory must be in the range -9999 to +9999. Your simulator should test that each number entered is in this range and, if not, keep prompting the user to re-enter the number until the user enters a correct number.

During the execution phase, your simulator should check for various serious errors, such as attempts to divide by zero, attempts to execute invalid operation codes, and accumulator overflows (i.e., arithmetic operations resulting in values larger than +9999 or smaller than -9999). Such serious errors are called *fatal errors*. When a fatal error is detected, your simulator should display an error message, such as

```
*** Attempt to divide by zero ***
*** Simpletron execution abnormally terminated ***
```

and should display a full computer dump in the format we discussed previously. This treatment will help the user locate the error in the program.

**6.32 (Simpletron Simulator Modifications)** In Exercise 6.31, you wrote a software simulation of a computer that executes programs written in Simpletron Machine Language (SML). In this exercise, we propose several modifications and enhancements to the Simpletron Simulator. In the exercises of Chapter 21, we propose building a compiler that converts programs written in a high-level programming language (a variation of Basic) to Simpletron Machine Language. Some of the following modifications and enhancements may be required to execute the programs produced by the compiler:

- Extend the Simpletron Simulator's memory to contain 1,000 memory locations to enable the Simpletron to handle larger programs.
- Allow the simulator to perform remainder calculations. This modification requires an additional SML instruction.
- Allow the simulator to perform exponentiation calculations. This modification requires an additional SML instruction.
- Modify the simulator to use hexadecimal rather than integer values to represent SML instructions.
- Modify the simulator to allow output of a newline. This modification requires an additional SML instruction.
- Modify the simulator to process floating-point values in addition to integer values.
- Modify the simulator to handle string input. [*Hint:* Each Simpletron word can be divided into two groups, each holding a two-digit integer. Each two-digit integer represents the ASCII (see Appendix B) decimal equivalent of a character. Add a machine-language instruction that will input a string and store the string, beginning at a specific Simpletron memory location. The first half of the word at that location will be a count of the number of characters in the string (i.e., the length of the string). Each succeeding half-word contains one ASCII character expressed as two decimal digits. The machine-

language instruction converts each character into its ASCII equivalent and assigns it to a half-word.]

- h) Modify the simulator to handle output of strings stored in the format of part (g). [*Hint:* Add a machine-language instruction that will display a string, beginning at a certain Simpletron memory location. The first half of the word at that location is a count of the number of characters in the string (i.e., the length of the string). Each succeeding half-word contains one ASCII character expressed as two decimal digits. The machine-language instruction checks the length and displays the string by translating each two-digit number into its equivalent character.]

## Making a Difference

**6.33** (*Polling*) The Internet and the web are enabling more people to network, join a cause, voice opinions, and so on. Recent presidential candidates have used the Internet intensively to get out their messages and raise money for their campaigns. In this exercise, you'll write a simple polling program that allows users to rate five social-consciousness issues from 1 (least important) to 10 (most important). Pick five causes that are important to you (e.g., political issues, global environmental issues). Use a one-dimensional array `topics` (of type `String`) to store the five causes. To summarize the survey responses, use a 5-row, 10-column two-dimensional array `responses` (of type `int`), each row corresponding to an element in the `topics` array. When the program runs, it should ask the user to rate each issue. Have your friends and family respond to the survey. Then have the program display a summary of the results, including:

- a) A tabular report with the five topics down the left side and the 10 ratings across the top, listing in each column the number of ratings received for each topic.
- b) To the right of each row, show the average of the ratings for that issue.
- c) Which issue received the highest point total? Display both the issue and the point total.
- d) Which issue received the lowest point total? Display both the issue and the point total.



# Introduction to Classes and Objects

# 7



*Your public servants serve you right.*

—Adlai E. Stevenson

*Nothing can have value without being an object of utility.*

—Karl Marx

## Objectives

In this chapter you'll learn:

- How to declare a class and use it to create an object.
- How to implement a class's behaviors as methods.
- How to implement a class's attributes as instance variables.
- How to call an object's methods to make them perform their tasks.
- What local variables of a method are and how they differ from instance variables.
- How to use a constructor to initialize an object's data.
- How to represent and use numbers containing decimal points.

- 7.1 Introduction
- 7.2 Instance Variables, *set* Methods and *get* Methods
  - 7.2.1 Account Class with an Instance Variable, a *set* Method and a *get* Method
  - 7.2.2 AccountTest Class That Creates and Uses an Object of Class Account
  - 7.2.3 Compiling and Executing an App with Multiple Classes
  - 7.2.4 Account UML Class Diagram with an Instance Variable and *set* and *get* Methods
  - 7.2.5 Additional Notes on This Example
  - 7.2.6 Software Engineering with *private* Instance Variables and *public set* and *get* Methods
- 7.3 Default and Explicit Initialization for Instance Variables
- 7.4 Account Class: Initializing Objects with Constructors
  - 7.4.1 Declaring an Account Constructor for Custom Object Initialization
  - 7.4.2 Class AccountTest: Initializing Account Objects When They're Created
- 7.5 Account Class with a Balance; Floating-Point Numbers
  - 7.5.1 Account Class with a balance Instance Variable of Type *double*
  - 7.5.2 AccountTest Class to Use Class Account
- 7.6 Case Study: Card Shuffling and Dealing Simulation
- 7.7 Case Study: Class GradeBook Using an Array to Store Grades
- 7.8 Case Study: Class GradeBook Using a Two-Dimensional Array
- 7.9 Wrap-Up

Summary | Self-Review Exercises | Answers to Self-Review Exercises | Exercises | Making a Difference

## 7.1 Introduction

[*Note:* This chapter depends on the terminology and concepts of object-oriented programming introduced in Section 1.5, Introduction to Object Technology.]

In the preceding chapters, you worked with *existing* classes, objects and methods. For example, you used the predefined standard output object `System.out`, invoking its methods `print`, `println` and `printf` to display information on the screen, and you used the existing `Scanner` class to create an object that reads into memory integer data typed by the user at the keyboard. Throughout the book, you'll use many more preexisting classes and objects—this is one of the great strengths of Java as an object-oriented programming language.

In this chapter, you'll learn how to create your own classes. Each new *class* you create becomes a new *type* that can be used to declare variables and create objects. You can declare new classes as needed; this is one reason why Java is known as an *extensible* language.

In this chapter, Sections 7.2–7.5 present a case study on creating and using a simple, real-world bank account class—`Account`. Such a class should maintain as *instance variables* attributes such as its name and balance, and provide *methods* for tasks such as querying the balance (`getBalance`), making deposits that increase the balance (`deposit`) and making withdrawals that decrease the balance (`withdraw`). We'll build the `getBalance` and `deposit` methods into the class in the chapter's examples and you'll add the `withdraw` method in the exercises.

Next, we present additional case studies, including a card shuffling and dealing simulation and two `GradeBook` case studies that use arrays to store and manipulate student grades. The first `GradeBook` case study uses a one-dimensional array to represent grades for

ten students on a single exam. The second uses a two-dimensional array to represent the grades for ten students on each of three exams.

Typically, the apps you develop in this chapter and later will consist of two or more classes. If you become part of a development team in industry, you might work on apps that contain hundreds, or even thousands, of classes.

## 7.2 Instance Variables, set Methods and get Methods

In this section, you'll create two classes—Account (Fig. 7.1) and AccountTest (Fig. 7.2). Class AccountTest is an *application class* in which the main method will create and use an Account object to demonstrate class Account's capabilities.

### 7.2.1 Account Class with an Instance Variable, a set Method and a get Method

Different accounts typically have different names. For this reason, class Account (Fig. 7.1) contains a name *instance variable*. A class's instance variables maintain data for each object (that is, each instance) of the class. Later in the chapter we'll add an instance variable named balance so we can keep track of how much money is in the account. Class Account contains two methods—method setName stores a name in an Account object and method getName obtains a name from an Account object.

---

```

1 // Fig. 7.1: Account.java
2 // Account class that contains a name instance variable
3 // and methods to set and get its value.
4
5 public class Account
6 {
7 private String name; // instance variable
8
9 // method to set the name in the object
10 public void setName(String name)
11 {
12 this.name = name; // store the name
13 }
14
15 // method to retrieve the name from the object
16 public String getName()
17 {
18 return name; // return value of name to caller
19 }
20 } // end class Account

```

---

**Fig. 7.1** | Account class that contains a name instance variable and methods to *set* and *get* its value.

#### *Class Declaration*

The *class declaration* begins in line 5:

```
public class Account
```

The keyword `public` (which Chapter 8 explains in detail) is an **access modifier**. For now, we'll simply declare every class `public`. Each `public` class declaration must be stored in a file having the *same* name as the class and ending with the `.java` filename extension; otherwise, a compilation error will occur. Thus, `public` classes `Account` and `AccountTest` (Fig. 7.2) *must* be declared in the *separate* files `Account.java` and `AccountTest.java`, respectively.

Every class declaration contains the keyword `class` followed immediately by the class's name—in this case, `Account`. Every class's body is enclosed in a pair of left and right braces as in lines 6 and 20 of Fig. 7.1.

### *Identifiers and Camel Case Naming*

Class names, method names and variable names are all *identifiers* and by convention all use the same *camel case* naming scheme we discussed in Chapter 2. Also by convention, class names begin with an initial *uppercase* letter, and method names and variable names begin with an initial *lowercase* letter.

### *Instance Variable name*

Recall from Section 1.5 that an object has attributes, implemented as instance variables and carried with it throughout its lifetime. Instance variables exist before methods are called on an object, while the methods are executing and after the methods complete execution. Each object (instance) of the class has its *own* copy of the class's instance variables. A class normally contains one or more methods that manipulate the instance variables belonging to particular objects of the class.

Instance variables are declared *inside* a class declaration but *outside* the bodies of the class's methods. Line 7

```
private String name; // instance variable
```

declares instance variable `name` of type `String` *outside* the bodies of methods `setName` (lines 10–13) and `getName` (lines 16–19). `String` variables can hold character string values such as "Jane Green". If there are many `Account` objects, each has its own name. Because `name` is an instance variable, it can be manipulated by each of the class's methods.



### **Good Programming Practice 7.1**

*We prefer to list a class's instance variables first in the class's body, so that you see the names and types of the variables before they're used in the class's methods. You can list the class's instance variables anywhere in the class outside its method declarations, but scattering the instance variables can lead to hard-to-read code.*

### *Access Modifiers **public** and **private***

Most instance-variable declarations are preceded with the keyword `private` (as in line 7). Like `public`, **`private`** is an *access modifier*. Variables or methods declared with access modifier `private` are accessible only to methods of the class in which they're declared. So, the variable name can be used only in each `Account` object's methods (`setName` and `getName` in this case). You'll soon see that this presents powerful software engineering opportunities.

### *Instance Method **setName** of Class **Account***

In the preceding chapters, you've declared only **static** methods in each class. A class's non-static methods are known as **instance methods**. Method `setName`'s declaration

(lines 10–13) indicates that `setName` receives parameter `name` of type `String`—which represents the name that will be passed to the method as an argument.

Recall that variables declared in a particular method's body (such as `main`) are local variables which can be used only in that method and that a method's parameters also are local variables of the method.

Method `setName`'s body contains a single statement (line 12) that assigns the value of the name *parameter* (a `String`) to the class's name *instance variable*, thus storing the account name in the object. If a method contains a local variable with the *same* name as an instance variable (as in lines 10 and 7, respectively), that method's body will refer to the local variable rather than the instance variable. In this case, the local variable is said to *shadow* the instance variable in the method's body. The method's body can use the keyword **this** to refer to the shadowed instance variable explicitly, as shown on the left side of the assignment in line 12.



### Good Programming Practice 7.2

*We could have avoided the need for keyword `this` here by choosing a different name for the parameter in line 10, but using the `this` keyword as shown in line 12 is a widely accepted practice to minimize the proliferation of identifier names.*

After line 12 executes, the method has completed its task, so it returns to its *caller*. As you'll soon see, the statement in line 21 of `main` (Fig. 7.2) calls method `setName`.

### **getName Method of Class Account**

Method `getName` (lines 16–19 of Fig. 7.1) returns a particular `Account` object's name to the caller. The method has an empty parameter list, so it does *not* require additional information to perform its task.

## 7.2.2 AccountTest Class That Creates and Uses an Object of Class Account

Next, we'd like to use class `Account` in an app and *call* each of its methods. A class that contains a `main` method begins the execution of a Java app. Class `Account` *cannot* execute by itself because it does *not* contain a `main` method—if you type `java Account` in the command window, you'll get an error indicating “Main method not found in class `Account`.” To fix this problem, you must either declare a *separate* class that contains a `main` method or place a `main` method in class `Account`.

### **Driver Class AccountTest**

To help you prepare for the larger programs you'll encounter later in this book and in industry, we use a separate class `AccountTest` (Fig. 7.2) containing method `main` to test class `Account`. Once `main` begins executing, it may call other methods in this and other classes; those may, in turn, call other methods, and so on. Class `AccountTest`'s `main` method creates one `Account` object and calls its `getName` and `setName` methods. Such a class is sometimes called a *driver class*—just as a `Person` object drives a `Car` object by telling it what to do (go faster, go slower, turn left, turn right, etc.), class `AccountTest` drives an `Account` object, telling it what to do by calling its methods.

```

1 // Fig. 7.2: AccountTest.java
2 // Creating and manipulating an Account object.
3 import java.util.Scanner;
4
5 public class AccountTest
6 {
7 public static void main(String[] args)
8 {
9 // create a Scanner object to obtain input from the command window
10 Scanner input = new Scanner(System.in);
11
12 // create an Account object and assign it to myAccount
13 Account myAccount = new Account();
14
15 // display initial value of name (null)
16 System.out.printf("Initial name is: %s%n%n", myAccount.getName());
17
18 // prompt for and read name
19 System.out.println("Please enter the name:");
20 String theName = input.nextLine(); // read a line of text
21 myAccount.setName(theName); // put theName in myAccount
22 System.out.println(); // outputs a blank line
23
24 // display the name stored in object myAccount
25 System.out.printf("Name in object myAccount is:%n%s%n",
26 myAccount.getName());
27 }
28 } // end class AccountTest

```

```

Initial name is: null

Please enter the name:
Jane Green

Name in object myAccount is:
Jane Green

```

**Fig. 7.2** | Creating and manipulating an Account object.

### *Scanner Object for Receiving Input from the User*

Line 10 creates a Scanner object named `input` for inputting the name from the user. Line 19 prompts the user to enter a name. Line 20 uses the Scanner object's `nextLine` method to read the name from the user and assign it to the local variable `theName`. You type the name and press *Enter* to submit it to the program. Pressing *Enter* inserts a newline character after the characters you typed. Method `nextLine` reads characters (including white-space characters, such as the blank in "Jane Green") until it encounters the newline, then returns a String containing the characters up to, but *not* including, the newline, which is *discarded*.

As you've seen, class Scanner provides various other input methods. A Scanner method similar to `nextLine`—named `next`—reads the *next word*. When you press *Enter* after typing some text, method `next` reads characters until it encounters a *white-space character* (such as a space, tab or newline), then returns a String containing the characters up

to, but *not* including, the white-space character, which is *discarded*. All information after the first white-space character is *not lost*—it can be read by subsequent statements that call the Scanner’s methods later in the program.

### *Instantiating an Object—Keyword **new** and Constructors*

Line 13 creates an Account object and assigns it to variable `myAccount` of type Account. Variable `myAccount` is initialized with the result of the **class instance creation expression** `new Account()`. Keyword **new** creates a new object of the specified class—in this case, Account. The parentheses to the right of Account are *required*. As you’ll learn in Section 7.4, those parentheses in combination with a class name represent a call to a **constructor**, which is *similar* to a method but is called implicitly by the new operator to *initialize* an object’s instance variables when the object is *created*. In Section 7.4, you’ll see how to place an *argument* in the parentheses to specify an *initial value* for an Account object’s name instance variable—you’ll enhance class Account to enable this. For now, we simply leave the parentheses *empty*. Line 10 contains a class instance creation expression for a Scanner object—the expression initializes the Scanner with `System.in`, which tells the Scanner where to read the input from (i.e., the keyboard).

### *Calling Class Account’s **getName** Method*

Line 16 displays the *initial* name, which is obtained by calling the object’s `getName` method. Just as we can use object `System.out` to call its methods `print`, `printf` and `println`, we can use object `myAccount` to call its methods `getName` and `setName`. Line 16 calls `getName` using the `myAccount` object created in line 13, followed by a dot separator (`.`), then the method name `getName` and an *empty* set of parentheses because no arguments are being passed. When `getName` is called:

1. The app transfers program execution from the call (line 16 in `main`) to method `getName`’s declaration (lines 16–19 of Fig. 7.1). Because `getName` was called via the `myAccount` object, `getName` “knows” which object’s instance variable to manipulate.
2. Next, method `getName` performs its task—that is, it *returns* the name (line 18 of Fig. 7.1). When the return statement executes, program execution continues where `getName` was called (line 16 in Fig. 7.2).
3. `System.out.printf` displays the String returned by method `getName`, then the program continues executing at line 19 in `main`.



### **Error-Prevention Tip 7.1**

*Never use as a format-control a string that was input from the user. When method `System.out.printf` evaluates the format-control string in its first argument, the method performs tasks based on the conversion specifier(s) in that string. If the format-control string were obtained from the user, a malicious user could supply conversion specifiers that would be executed by `System.out.printf`, possibly causing a security breach.*

### **null—the Default Initial Value for String Variables**

The first line of the output shows the name “`null`.” Unlike local variables, which are *not* automatically initialized, *every instance variable has a default initial value*—a value provided by Java when you do *not* specify the instance variable’s initial value. Thus, *instance variables* are *not* required to be explicitly initialized before they’re used in a program—unless they

must be initialized to values *other than* their default values. The default value for an instance variable of type `String` (like `name` in this example) is `null`, which we discuss further in Section 7.3.

### *Calling Class `Account`'s `setName` Method*

Line 21 calls `myAccounts`'s `setName` method. Recall that a method call can supply arguments whose values are assigned to the corresponding method parameters. In this case, the value of `main`'s local variable `theName` in parentheses is the argument that's passed to `setName` so that the method can perform its task. When `setName` is called:

1. The app transfers program execution from line 21 in `main` to `setName` method's declaration (lines 10–13 of Fig. 7.1), and the argument value in the call's parentheses (`theName`) is assigned to the corresponding parameter (`name`) in the method header (line 10 of Fig. 7.1). Because `setName` was called via the `myAccount` object, `setName` “knows” which object's instance variable to manipulate.
2. Next, method `setName` performs its task—that is, it assigns the `name` parameter's value to instance variable `name` (line 12 of Fig. 7.1).
3. When program execution reaches `setName`'s closing right brace, it returns to where `setName` was called in line 21 of Fig. 7.2, then continues at line 22.

### *Displaying the Name That Was Entered by the User*

When the second call to method `getName` (line 26) executes, the name entered by the user in line 20 is displayed. When the statement at lines 25–26 completes execution, the end of method `main` is reached, so the program terminates.

## 7.2.3 Compiling and Executing an App with Multiple Classes

You must compile the classes in Figs. 7.1 and 7.2 before you can *execute* the app. This is the first time you've created an app with *multiple* classes. Class `AccountTest` has a `main` method; class `Account` does not. To compile this app, first change to the directory that contains the app's source-code files. Next, type the command

```
javac Account.java AccountTest.java
```

to compile *both* classes at once. If the directory containing the app includes *only* this app's files, you can compile both classes with the command

```
javac *.java
```

The asterisk (\*) in `*.java` indicates that *all* files in the *current* directory ending with the filename extension “`.java`” should be compiled. If both classes compile correctly—that is, no compilation errors are displayed—you can then run the app with the command


```
java AccountTest
```

## 7.2.4 Account UML Class Diagram with an Instance Variable and `set` and `get` Methods

We'll often use UML class diagrams to summarize a class's *attributes* and *operations*. In industry, UML diagrams help systems designers specify a system in a concise, graphical, programming-language-independent manner, before programmers implement the system in



a specific programming language. Figure 7.3 presents a **UML class diagram** for class Account of Fig. 7.1.



**Fig. 7.3** | UML class diagram for class Account of Fig. 7.1.

### *Top Compartment*

In the UML, each class is modeled in a class diagram as a rectangle with three compartments. In this diagram the *top* compartment contains the *class name* Account centered horizontally in boldface type.

### *Middle Compartment*

The *middle* compartment contains the *class's attribute* name, which corresponds to the instance variable of the same name in Java. Instance variable name is private in Java, so the UML class diagram lists a *minus sign* (–) *access modifier* before the attribute name. Following the attribute name are a *colon* and the *attribute type*, in this case String.

### *Bottom Compartment*

The *bottom* compartment contains the class's **operations**, setName and getName, which correspond to the methods of the same names in Java. The UML models operations by listing the operation name preceded by an *access modifier*, in this case + getName. This plus sign (+) indicates that getName is a *public* operation in the UML (because it's a public method in Java). Operation getName does *not* have any parameters, so the parentheses following the operation name in the class diagram are *empty*, just as they are in the method's declaration in line 16 of Fig. 7.1. Operation setName, also a public operation, has a String parameter called name.

### *Return Types*

The UML indicates the *return type* of an operation by placing a colon and the return type *after* the parentheses following the operation name. Account method getName (Fig. 7.1) has a String return type. Method setName *does not* return a value (because it returns void in Java), so the UML class diagram *does not* specify a return type after the parentheses of this operation.

### *Parameters*

The UML models a parameter a bit differently from Java by listing the parameter name, followed by a colon and the parameter type in the parentheses after the operation name. The UML has its own data types similar to those of Java, but for simplicity, we'll use the Java data types. Account method setName (Fig. 7.1) has a String parameter named name, so Fig. 7.3 lists name : String between the parentheses following the method name.

### 7.2.5 Additional Notes on This Example

#### Notes on *static* Methods

A *static* method can call other *static* methods of the same class directly (i.e., using the method name by itself) and can manipulate *static* variables in the same class directly. To access the class's instance variables and instance methods, a *static* method must use a reference to an object of the class. Instance methods can access all fields (*static* variables and instance variables) and methods of the class.

Recall that *static* methods relate to a class as a whole, whereas instance methods are associated with a specific instance (object) of the class and may manipulate the instance variables of that object. Many objects of a class, each with its *own* copies of the instance variables, may exist at the same time. Suppose a *static* method were to invoke an instance method directly. How would the *static* method know which object's instance variables to manipulate? What would happen if *no* objects of the class existed at the time the instance method was invoked? Thus, Java does *not* allow a *static* method to directly access instance variables and instance methods of the same class.

#### Notes on *import* Declarations

Notice the *import* declaration in Fig. 7.2 (line 3), which indicates to the compiler that the program uses class `Scanner`. As you learned in Chapter 2, classes `System` and `String` are in package `java.lang`, which is *implicitly* imported into *every* Java program, so all programs can use that package's classes *without* explicitly importing them. *Most* other classes you'll use in Java programs *must* be imported *explicitly*.

There's a special relationship between classes that are compiled in the *same* directory, like classes `Account` and `AccountTest`. By default, such classes are considered to be in the *same* package—known as the **default package**. Classes in the *same* package are *implicitly imported* into the source-code files of other classes in that package. Thus, an *import* declaration is *not* required when one class in a package uses another in the *same* package—such as when class `AccountTest` uses class `Account`.

The *import* declaration in line 3 is *not* required if we refer to class `Scanner` throughout this file as `java.util.Scanner`, which includes the *full package name and class name*. This is known as the class's **fully qualified class name**. For example, line 10 of Fig. 7.2 also could be written as

```
java.util.Scanner input = new java.util.Scanner(System.in);
```



#### Software Engineering Observation 7.1

*The Java compiler does not require import declarations in a Java source-code file if the fully qualified class name is specified every time a class name is used. Most Java programmers prefer the more concise programming style enabled by import declarations.*

### 7.2.6 Software Engineering with *private* Instance Variables and *public set* and *get* Methods

As you'll see, through the use of *set* and *get* methods, you can *validate* attempted modifications to private data and control how that data is presented to the caller—these are compelling software engineering benefits. We'll discuss this in more detail in Section 7.5.

If the instance variable were `public`, any **client** of the class—that is, any other class that calls the class's methods—could see the data and do whatever it wanted with it, including setting it to an *invalid* value.

You might think that even though a client of the class cannot directly access a `private` instance variable, the client can do whatever it wants with the variable through `public` *set* and *get* methods. You would think that you could peek at the `private` data any time with the `public` *get* method and that you could modify the `private` data at will through the `public` *set* method. But *set* methods can be programmed to *validate* their arguments and reject any attempts to *set* the data to bad values, such as a negative body temperature, a day in March out of the range 1 through 31, a product code not in the company's product catalog, etc. And a *get* method can present the data in a different form. For example, a `Grade` class might store a grade as an `int` between 0 and 100, but a `getGrade` method might return a letter grade as a `String`, such as "A" for grades between 90 and 100, "B" for grades between 80 and 89, etc. Tightly controlling the access to and presentation of `private` data can greatly reduce errors, while increasing the robustness and security of your programs.

Declaring instance variables with access modifier `private` is known as *data hiding* or *information hiding*. When a program creates (instantiates) an object of class `Account`, variable name is *encapsulated* (hidden) in the object and can be accessed only by methods of the object's class.




### Software Engineering Observation 7.2

*Precede each instance variable and method declaration with an access modifier. Generally, instance variables should be declared `private` and methods `public`. Later in the book, we'll discuss why you might want to declare a method `private`.*

### Conceptual View of an `Account` Object with Encapsulated Data

You can think of an `Account` object as shown in Fig. 7.4. The `private` instance variable name is *hidden inside* the object (represented by the inner circle containing name) and *protected by an outer layer* of `public` methods (represented by the outer circle containing `getName` and `setName`). Any client code that needs to interact with the `Account` object can do *only* by calling the `public` methods of the protective outer layer.



**Fig. 7.4** | Conceptual view of an `Account` object with its encapsulated `private` instance variable `name` and protective layer of `public` methods.

### 7.3 Default and Explicit Initialization for Instance Variables

Recall that local variables are *not* initialized by default. Primitive-type instance variables *are* initialized by default—instance variables of types `byte`, `char`, `short`, `int`, `long`, `float` and `double` are initialized to 0, and variables of type `boolean` are initialized to `false`.

You can specify your own initial value for a primitive-type instance variable by assigning the variable a value in its declaration, as in

```
private int numberOfStudents = 10;
```

Reference-type instance variables (such as those of type `String`), if not explicitly initialized, are initialized by default to the value `null`—which represents a “reference to nothing.” That’s why the first call to `getName` in line 16 of Fig. 7.2 returns `null`—the value of `name` has *not* yet been set, so the *default initial value* `null` is returned.

### 7.4 Account Class: Initializing Objects with Constructors

As mentioned in Section 7.2, when an object of class `Account` (Fig. 7.1) is created, its `String` instance variable `name` is initialized to `null` by *default*. But what if you want to provide a name when you *create* an `Account` object?

Each class you declare can optionally provide a *constructor* with parameters that can be used to initialize an object of a class when the object is created. Java *requires* a constructor call for *every* object that’s created, so this is the ideal point to initialize an object’s instance variables. The next example enhances class `Account` (Fig. 7.5) with a constructor that can receive a name and use it to initialize instance variable `name` when an `Account` object is created (Fig. 7.6).

#### 7.4.1 Declaring an Account Constructor for Custom Object Initialization

When you declare a class, you can provide your own constructor to specify *custom initialization* for objects of your class. For example, you might want to specify a name for an `Account` object when the object is created, as in line 10 of Fig. 7.6:

```
Account account1 = new Account("Jane Green");
```

In this case, the `String` argument “Jane Green” is passed to the `Account` object’s constructor and used to initialize the `name` instance variable. The preceding statement requires that the class provide a constructor that takes only a `String` parameter. Figure 7.5 contains a modified `Account` class with such a constructor.

---

```

1 // Fig. 7.5: Account.java
2 // Account class with a constructor that initializes the name.
3
4 public class Account
5 {
6 private String name; // instance variable
7
8 // constructor initializes name with parameter name
9 public Account(String name) // constructor name is class name
10 {

```

---

**Fig. 7.5** | Account class with a constructor that initializes the name. (Part 1 of 2.)

```
11 this.name = name;
12 }
13
14 // method to set the name
15 public void setName(String name)
16 {
17 this.name = name;
18 }
19
20 // method to retrieve the name
21 public String getName()
22 {
23 return name;
24 }
25 } // end class Account
```

**Fig. 7.5** | Account class with a constructor that initializes the name. (Part 2 of 2.)

#### **Account Constructor Declaration**

Lines 9–12 of Fig. 7.5 declare `Account`'s constructor. A constructor *must* have the *same name* as the class. A constructor's *parameter list* specifies that the constructor requires one or more pieces of data to perform its task. Line 9 indicates that the constructor has a `String` parameter called `name`. When you create a new `Account` object (as you'll see in Fig. 7.6), you'll pass a person's name to the constructor, which will receive that name in the parameter `name`. The constructor will then assign `name` to *instance variable* `name` in line 11.



#### **Error-Prevention Tip 7.2**

*Even though it's possible to do so, do not call methods from constructors. We'll explain this in Chapter 10, *Object-Oriented Programming: Polymorphism and Interfaces*.*

#### **Parameter name of Class `Account`'s Constructor and Method `setName`**

Recall from Section 7.2.1 that method parameters are local variables. In Fig. 7.5, the constructor and method `setName` both have a parameter called `name`. Although these parameters have the same identifier (`name`), the parameter in line 9 is a local variable of the constructor that's *not* visible to method `setName`, and the one in line 15 is a local variable of `setName` that's *not* visible to the constructor.

### **7.4.2 Class `AccountTest`: Initializing Account Objects When They're Created**

The `AccountTest` program (Fig. 7.6) initializes two `Account` objects using the constructor. Line 10 creates and initializes the `Account` object `account1`. Keyword `new` requests memory from the system to store the `Account` object, then implicitly calls the class's constructor to *initialize* the object. The call is indicated by the parentheses after the class name, which contain the *argument* "Jane Green" that's used to initialize the new object's name. The class instance creation expression in line 10 returns a *reference* to the new object, which is assigned to the variable `account1`. Line 11 repeats this process, passing the argument "John Blue" to initialize the name for `account2`. Lines 14–15 use each object's

`getName` method to obtain the names and show that they were indeed initialized when the objects were *created*. The output shows *different* names, confirming that each `Account` maintains its *own copy* of instance variable `name`.

---

```

1 // Fig. 7.6: AccountTest.java
2 // Using the Account constructor to initialize the name instance
3 // variable at the time each Account object is created.
4
5 public class AccountTest
6 {
7 public static void main(String[] args)
8 {
9 // create two Account objects
10 Account account1 = new Account("Jane Green");
11 Account account2 = new Account("John Blue");
12
13 // display initial value of name for each Account
14 System.out.printf("account1 name is: %s\n", account1.getName());
15 System.out.printf("account2 name is: %s\n", account2.getName());
16 }
17 } // end class AccountTest

```

```

account1 name is: Jane Green
account2 name is: John Blue

```

**Fig. 7.6** | Using the `Account` constructor to initialize the `name` instance variable at the time each `Account` object is created.

### *Constructors Cannot Return Values*

An important difference between constructors and methods is that *constructors cannot return values*, so they *cannot* specify a return type (not even `void`). Normally, constructors are declared `public`—later in the book we’ll explain when to use private constructors.

### *Default Constructor*

Recall that line 13 of Fig. 7.2

```
Account myAccount = new Account();
```

used `new` to create an `Account` object. The *empty* parentheses after “`new Account`” indicate a call to the class’s **default constructor**—in any class that does *not* explicitly declare a constructor, the compiler provides a default constructor (which always has no parameters). When a class has only the default constructor, the class’s instance variables are initialized to their *default values*. In Section 8.5, you’ll learn that classes can have multiple constructors.

### *There’s No Default Constructor in a Class That Declares a Constructor*

If you declare a constructor for a class, the compiler will *not* create a *default constructor* for that class. In that case, you will not be able to create an `Account` object with the class instance creation expression `new Account()` as we did in Fig. 7.2—unless the custom constructor you declare takes *no* parameters.




### Software Engineering Observation 7.3

*Unless default initialization of your class's instance variables is acceptable, provide a custom constructor to ensure that your instance variables are properly initialized with meaningful values when each new object of your class is created.*

#### Adding the Constructor to Class **Account**'s UML Class Diagram

The UML class diagram of Fig. 7.7 models class **Account** of Fig. 7.5, which has a constructor with a `String` name parameter. Like operations, the UML models constructors in the *third* compartment of a class diagram. To distinguish a constructor from the class's operations, the UML requires that the word “constructor” be enclosed in **guillemets** (« and ») and placed before the constructor's name. It's customary to list constructors *before* other operations in the third compartment.



**Fig. 7.7** | UML class diagram for **Account** class of Fig. 7.5.

## 7.5 Account Class with a Balance; Floating-Point Numbers

We now declare an **Account** class that maintains the *balance* of a bank account in addition to the name. Most account balances are not integers. So, class **Account** represents the account balance as a `double`. [In Section 8.15, as we study object-oriented programming in more depth, we'll begin representing monetary amounts precisely with class `BigDecimal` as you should do when writing industrial-strength monetary applications.]

### 7.5.1 Account Class with a `balance` Instance Variable of Type `double`

Our next app contains a version of class **Account** (Fig. 7.8) that maintains as instance variables the name *and* the balance of a bank account. A typical bank services *many* accounts, each with its *own* balance, so line 8 declares an instance variable `balance` of type `double`. Every instance (i.e., object) of class **Account** contains its *own* copies of *both* the name and the balance.

```

1 // Fig. 7.8: Account.java
2 // Account class with a double instance variable balance and a constructor
3 // and deposit method that perform validation.
4

```

**Fig. 7.8** | Account class with a `double` instance variable `balance` and a constructor and deposit method that perform validation. (Part 1 of 2.)

---

```

5 public class Account
6 {
7 private String name; // instance variable
8 private double balance; // instance variable
9
10 // Account constructor that receives two parameters
11 public Account(String name, double balance)
12 {
13 this.name = name; // assign name to instance variable name
14
15 // validate that the balance is greater than 0.0; if it's not,
16 // instance variable balance keeps its default initial value of 0.0
17 if (balance > 0.0) // if the balance is valid
18 this.balance = balance; // assign it to instance variable balance
19 }
20
21 // method that deposits (adds) only a valid amount to the balance
22 public void deposit(double depositAmount)
23 {
24 if (depositAmount > 0.0) // if the depositAmount is valid
25 balance += depositAmount; // add it to the balance
26 }
27
28 // method returns the account balance
29 public double getBalance()
30 {
31 return balance;
32 }
33
34 // method that sets the name
35 public void setName(String name)
36 {
37 this.name = name;
38 }
39
40 // method that returns the name
41 public String getName()
42 {
43 return name; // give value of name back to caller
44 } // end method getName
45 } // end class Account

```

---

**Fig. 7.8** | Account class with a double instance variable balance and a constructor and deposit method that perform validation. (Part 2 of 2.)

### **Account Class Two-Parameter Constructor**

The class has a *constructor* and four *methods*. It's common for someone opening an account to deposit money immediately, so the constructor (lines 11–19) now receives a second parameter—initialBalance of type double that represents the *starting balance*. Lines 17–18 ensure that initialBalance is greater than 0.0. If so, initialBalance's value is assigned to instance variable balance. Otherwise, balance remains at 0.0—its *default initial value*.



**Account Class deposit Method**

Method `deposit` (lines 22–26) does *not* return any data when it completes its task, so its return type is `void`. The method receives one parameter named `depositAmount`—a `double` value that's added to the balance *only* if the parameter value is *valid* (i.e., greater than zero). Line 25 adds the `depositAmount` to the current balance.

**Account Class getBalance Method**

Method `getBalance` (lines 29–32) allows *clients* of the class (i.e., other classes whose methods call the methods of this class) to obtain the value of a particular `Account` object's balance. The method specifies return type `double` and an *empty* parameter list.

**Account's Methods Can All Use balance**

Once again, the statements in lines 18, 25 and 31 use the variable `balance` even though it was *not* declared in *any* of the methods. We can use `balance` in these methods because it's an *instance variable* of the class.

**7.5.2 AccountTest Class to Use Class Account**

Class `AccountTest` (Fig. 7.9) creates two `Account` objects (lines 9–10) and initializes them with a *valid* balance of 50.00 and an *invalid* balance of -7.53, respectively—for the purpose of our examples, we assume that balances must be greater than or equal to zero. The calls to method `System.out.printf` in lines 13–16 output the account names and balances, which are obtained by calling each `Account`'s `getName` and `getBalance` methods.

---

```

1 // Fig. 7.9: AccountTest.java
2 // Inputting and outputting floating-point numbers with Account objects.
3 import java.util.Scanner;
4
5 public class AccountTest
6 {
7 public static void main(String[] args)
8 {
9 Account account1 = new Account("Jane Green", 50.00);
10 Account account2 = new Account("John Blue", -7.53);
11
12 // display initial balance of each object
13 System.out.printf("%s balance: %.2f%n",
14 account1.getName(), account1.getBalance());
15 System.out.printf("%s balance: %.2f%n%n",
16 account2.getName(), account2.getBalance());
17
18 // create a Scanner to obtain input from the command window
19 Scanner input = new Scanner(System.in);
20
21 System.out.print("Enter deposit amount for account1: "); // prompt
22 double depositAmount = input.nextDouble(); // obtain user input
23 System.out.printf("%nadding %.2f to account1 balance%n%n",
24 depositAmount);
25 account1.deposit(depositAmount); // add to account1's balance

```

---

**Fig. 7.9** | Inputting and outputting floating-point numbers with `Account` objects. (Part 1 of 2.)

```

26
27 // display balances
28 System.out.printf("%s balance: $%.2f%n",
29 account1.getName(), account1.getBalance());
30 System.out.printf("%s balance: $%.2f%n%n",
31 account2.getName(), account2.getBalance());
32
33 System.out.print("Enter deposit amount for account2: "); // prompt
34 depositAmount = input.nextDouble(); // obtain user input
35 System.out.printf("%nadding %.2f to account2 balance%n%n",
36 depositAmount);
37 account2.deposit(depositAmount); // add to account2 balance
38
39 // display balances
40 System.out.printf("%s balance: $%.2f%n",
41 account1.getName(), account1.getBalance());
42 System.out.printf("%s balance: $%.2f%n%n",
43 account2.getName(), account2.getBalance());
44 } // end main
45 } // end class AccountTest

```

```

Jane Green balance: $50.00
John Blue balance: $0.00

Enter deposit amount for account1: 25.53

adding 25.53 to account1 balance

Jane Green balance: $75.53
John Blue balance: $0.00

```

```

Enter deposit amount for account2: 123.45

adding 123.45 to account2 balance

Jane Green balance: $75.53
John Blue balance: $123.45

```

**Fig. 7.9** | Inputting and outputting floating-point numbers with Account objects. (Part 2 of 2.)

### *Displaying the Account Objects' Initial Balances*

When method `getBalance` is called for `account1` from line 14, the value of `account1`'s balance is returned from line 31 of Fig. 7.8 and displayed by the `System.out.printf` statement (Fig. 7.9, lines 13–14). Similarly, when method `getBalance` is called for `account2` from line 16, the value of the `account2`'s balance is returned from line 31 of Fig. 7.8 and displayed by the `System.out.printf` statement (Fig. 7.9, lines 15–16). The balance of `account2` is initially 0.00, because the constructor rejected the attempt to start `account2` with a *negative* balance, so the balance retains its default initial value.

### *Formatting Floating-Point Numbers for Display*

Each of the balances is output by `printf` with the format specifier `%.2f`. The **%f format specifier** is used to output values of type `float` or `double`. The `.2` between `%` and `f` repre-

sents the number of *decimal places* (2) that should be output to the *right* of the decimal point in the floating-point number—also known as the number’s **precision**. Any floating-point value output with `%.2f` will be *rounded* to the *hundredths position*—for example, 123.457 would be rounded to 123.46 and 27.33379 would be rounded to 27.33.

### *Reading a Floating-Point Value from the User and Making a Deposit*

Line 21 (Fig. 7.9) prompts the user to enter a deposit amount for `account1`. Line 22 declares *local* variable `depositAmount` to store each deposit amount entered by the user. Unlike *instance* variables (such as `name` and `balance` in class `Account`), *local* variables (like `depositAmount` in `main`) are *not* initialized by default, so they normally must be initialized explicitly. As you’ll learn momentarily, variable `depositAmount`’s initial value will be determined by the user’s input.



#### **Common Programming Error 7.1**

*The Java compiler will issue a compilation error if you attempt to use the value of an uninitialized local variable. This helps you avoid dangerous execution-time logic errors. It’s always better to get the errors out of your programs at compilation time rather than execution time.*

Line 22 obtains the input from the user by calling `Scanner` object `input`’s `nextDouble` method. Lines 23–24 display the `depositAmount`. Line 25 calls object `account1`’s `deposit` method with the `depositAmount` as the method’s argument. When the method is called, the argument’s value is assigned to the parameter `depositAmount` of method `deposit` (line 22 of Fig. 7.8); then method `deposit` adds that value to the `balance`. Lines 28–31 (Fig. 7.9) output the names and balances of both `Accounts` *again* to show that *only* `account1`’s `balance` has changed.

Line 33 prompts the user to enter a deposit amount for `account2`. Line 34 obtains the input from the user by calling `Scanner` object `input`’s `nextDouble` method. Lines 35–36 display the `depositAmount`. Line 37 calls object `account2`’s `deposit` method with `depositAmount` as the method’s *argument*; then method `deposit` adds that value to the `balance`. Finally, lines 40–43 output the names and balances of both `Accounts` *again* to show that *only* `account2`’s `balance` has changed.

### *Duplicated Code in Method main*

The six statements at lines 13–14, 15–16, 28–29, 30–31, 40–41 and 42–43 are almost *identical*—they each output an `Account`’s name and `balance`. They differ only in the name of the `Account` object—`account1` or `account2`. Duplicate code like this can create *code maintenance problems* when that code needs to be updated—if *six* copies of the same code all have the same error or update to be made, you must make that change *six* times, *without making errors*. Exercise 7.14 asks you to modify Fig. 7.9 to include a `displayAccount` method that takes as a parameter an `Account` object and outputs the object’s name and `balance`. You’ll then replace `main`’s duplicated statements with six calls to `displayAccount`, thus reducing the size of your program and improving its maintainability by having *one* copy of the code that displays an `Account`’s name and `balance`.




#### **Software Engineering Observation 7.4**

*Replacing duplicated code with calls to a method that contains one copy of that code can reduce the size of your program and improve its maintainability.*

**UML Class Diagram for Class Account**

The UML class diagram in Fig. 7.10 concisely models class `Account` of Fig. 7.8. The diagram models in its *second* compartment the private attributes `name` of type `String` and `balance` of type `double`.



**Fig. 7.10** | UML class diagram for `Account` class of Fig. 7.8.

Class `Account`'s *constructor* is modeled in the *third* compartment with parameters `name` of type `String` and `initialBalance` of type `double`. The class's four public methods also are modeled in the *third* compartment—operation `deposit` with a `depositAmount` parameter of type `double`, operation `getBalance` with a return type of `double`, operation `setName` with a `name` parameter of type `String` and operation `getName` with a return type of `String`.

## 7.6 Case Study: Card Shuffling and Dealing Simulation

The examples in Chapter 6 demonstrated arrays containing only elements of primitive types. The elements of an array can be either primitive types or reference types. This section uses random-number generation and an array of reference-type elements—namely objects representing playing cards—to develop a class that simulates card shuffling and dealing. This class can then be used to implement applications that play specific card games. The exercises at the end of the chapter use the classes developed here to build a simple poker application.

We first develop class `Card` (Fig. 7.11), which represents a playing card that has a face (e.g., "Ace", "Deuce", "Three", ..., "Jack", "Queen", "King") and a suit (e.g., "Hearts", "Diamonds", "Clubs", "Spades"). Next, we develop the `DeckOfCards` class (Fig. 7.12), which creates a deck of 52 playing cards in which each element is a `Card` object. We then build a test application (Fig. 7.13) that demonstrates class `DeckOfCards`'s card shuffling and dealing capabilities.

### Class Card

Class `Card` (Fig. 7.11) contains two `String` instance variables—`face` and `suit`—that are used to store references to the face name and suit name for a specific `Card`. The constructor for the class (lines 10–14) receives two `Strings` that it uses to initialize `face` and `suit`. Method `toString` (lines 17–20) creates a `String` consisting of the face of the card, the `String` " of " and the suit of the card. `Card`'s `toString` method can be invoked *explicitly*

to obtain a string representation of a Card object (e.g., "Ace of Spades"). The `toString` method of an object is called *implicitly* when the object is used where a `String` is expected (e.g., when `printf` outputs the object as a `String` using the `%s` format specifier or when the object is concatenated to a `String` using the `+` operator). For this behavior to occur, `toString` must be declared with the header shown in Fig. 7.11.

---

```

1 // Fig. 7.11: Card.java
2 // Card class represents a playing card.
3
4 public class Card
5 {
6 private final String face; // face of card ("Ace", "Deuce", ...)
7 private final String suit; // suit of card ("Hearts", "Diamonds", ...)
8
9 // two-argument constructor initializes card's face and suit
10 public Card(String cardFace, String cardSuit)
11 {
12 this.face = cardFace; // initialize face of card
13 this.suit = cardSuit; // initialize suit of card
14 }
15
16 // return String representation of Card
17 public String toString()
18 {
19 return face + " of " + suit;
20 }
21 } // end class Card

```

---

**Fig. 7.11** | Card class represents a playing card.

### *Class DeckOfCards*

Class `DeckOfCards` (Fig. 7.12) declares as an instance variable a `Card` array named `deck` (line 7). An array of a *reference* type is declared like any other array. Class `DeckOfCards` also declares an integer instance variable `currentCard` (line 8) representing the sequence number (0–51) of the next `Card` to be dealt from the `deck` array, and a named constant `NUMBER_OF_CARDS` (line 9) indicating the number of Cards in the deck (52).

---

```

1 // Fig. 7.12: DeckOfCards.java
2 // DeckOfCards class represents a deck of playing cards.
3 import java.security.SecureRandom;
4
5 public class DeckOfCards
6 {
7 private Card[] deck; // array of Card objects
8 private int currentCard; // index of next Card to be dealt (0-51)
9 private static final int NUMBER_OF_CARDS = 52; // constant # of Cards
10 // random number generator
11 private static final SecureRandom randomNumbers = new SecureRandom();
12

```

---

**Fig. 7.12** | `DeckOfCards` class represents a deck of playing cards. (Part I of 2.)

---

```

13 // constructor fills deck of Cards
14 public DeckOfCards()
15 {
16 String[] faces = { "Ace", "Deuce", "Three", "Four", "Five", "Six",
17 "Seven", "Eight", "Nine", "Ten", "Jack", "Queen", "King" };
18 String[] suits = { "Hearts", "Diamonds", "Clubs", "Spades" };
19
20 deck = new Card[NUMBER_OF_CARDS]; // create array of Card objects
21 currentCard = 0; // first Card dealt will be deck[0]
22
23 // populate deck with Card objects
24 for (int count = 0; count < deck.length; count++)
25 deck[count] =
26 new Card(faces[count % 13], suits[count / 13]);
27 }
28
29 // shuffle deck of Cards with one-pass algorithm
30 public void shuffle()
31 {
32 // next call to method dealCard should start at deck[0] again
33 currentCard = 0;
34
35 // for each Card, pick another random Card (0-51) and swap them
36 for (int first = 0; first < deck.length; first++)
37 {
38 // select a random number between 0 and 51
39 int second = randomNumbers.nextInt(NUMBER_OF_CARDS);
40
41 // swap current Card with randomly selected Card
42 Card temp = deck[first];
43 deck[first] = deck[second];
44 deck[second] = temp;
45 }
46 }
47
48 // deal one Card
49 public Card dealCard()
50 {
51 // determine whether Cards remain to be dealt
52 if (currentCard < deck.length)
53 return deck[currentCard++]; // return current Card in array
54 else
55 return null; // return null to indicate that all Cards were dealt
56 }
57 } // end class DeckOfCards

```

---

**Fig. 7.12** | DeckOfCards class represents a deck of playing cards. (Part 2 of 2.)

### *DeckOfCards Constructor*

The class's constructor instantiates the deck array (line 20) with `NUMBER_OF_CARDS` (52) elements. The elements of `deck` are `null` by default, so the constructor uses a `for` statement (lines 24–26) to fill the deck with `Cards`. The loop initializes control variable `count`

to 0 and loops while count is less than `deck.length`, causing count to take on each integer value from 0 to 51 (the indices of the deck array). Each `Card` is instantiated and initialized with two `Strings`—one from the faces array (which contains the `Strings` "Ace" through "King") and one from the suits array (which contains the `Strings` "Hearts", "Diamonds", "Clubs" and "Spades"). The calculation `count % 13` always results in a value from 0 to 12 (the 13 indices of the faces array in lines 16–17), and the calculation `count / 13` always results in a value from 0 to 3 (the four indices of the suits array in line 18). When the deck array is initialized, it contains the `Cards` with faces "Ace" through "King" in order for each suit (all 13 "Hearts", then all the "Diamonds", then the "Clubs", then the "Spades"). We use arrays of `Strings` to represent the faces and suits in this example. In Exercise 7.20, we ask you to modify this example to use arrays of `enum` constants to represent the faces and suits.

### ***DeckOfCards Method shuffle***

Method `shuffle` (lines 30–46) shuffles the `Cards` in the deck. The method loops through all 52 `Cards` (array indices 0 to 51). For each `Card`, a number between 0 and 51 is picked randomly to select another `Card`. Next, the current `Card` object and the randomly selected `Card` object are swapped in the array. This exchange is performed by the three assignments in lines 42–44. The extra variable `temp` temporarily stores one of the two `Card` objects being swapped. The swap cannot be performed with only the two statements

```
deck[first] = deck[second];
deck[second] = deck[first];
```

If `deck[first]` is the "Ace" of "Spades" and `deck[second]` is the "Queen" of "Hearts", after the first assignment, both array elements contain the "Queen" of "Hearts" and the "Ace" of "Spades" is lost—so, the extra variable `temp` is needed. After the for loop terminates, the `Card` objects are randomly ordered. A total of only 52 swaps are made in a single pass of the entire array, and the array of `Card` objects is shuffled!

[*Note:* It's recommended that you use a so-called *unbiased* shuffling algorithm for real card games. Such an algorithm ensures that all possible shuffled card sequences are equally likely to occur. Exercise 7.21 asks you to research the popular unbiased Fisher-Yates shuffling algorithm and use it to reimplement the `DeckOfCards` method `shuffle`.]

### ***DeckOfCards Method dealCard***

Method `dealCard` (lines 49–56) deals one `Card` in the array. Recall that `currentCard` indicates the index of the next `Card` to be dealt (i.e., the `Card` at the *top* of the deck). Thus, line 52 compares `currentCard` to the length of the deck array. If the deck is not empty (i.e., `currentCard` is less than 52), line 53 returns the "top" `Card` and postincrements `currentCard` to prepare for the next call to `dealCard`—otherwise, `null` is returned. Recall that `null` represents a "reference to nothing."

### ***Shuffling and Dealing Cards***

Figure 7.13 demonstrates class `DeckOfCards`. Line 9 creates a `DeckOfCards` object named `myDeckOfCards`. The `DeckOfCards` constructor creates the deck with the 52 `Card` objects in order by suit and face. Line 10 invokes `myDeckOfCards`'s `shuffle` method to rearrange

the Card objects. Lines 13–20 deal all 52 Cards and print them in four columns of 13 Cards each. Line 16 deals one Card object by invoking `myDeckOfCards`'s `dealCard` method, then displays the Card left justified in a field of 19 characters. When a Card is output as a String, the Card's `toString` method (lines 17–20 of Fig. 7.11) is implicitly invoked. Lines 18–19 start a new line after every four Cards.

---

```

1 // Fig. 7.13: DeckOfCardsTest.java
2 // Card shuffling and dealing.
3
4 public class DeckOfCardsTest
5 {
6 // execute application
7 public static void main(String[] args)
8 {
9 DeckOfCards myDeckOfCards = new DeckOfCards();
10 myDeckOfCards.shuffle(); // place Cards in random order
11
12 // print all 52 Cards in the order in which they are dealt
13 for (int i = 1; i <= 52; i++)
14 {
15 // deal and display a Card
16 System.out.printf("%-19s", myDeckOfCards.dealCard());
17
18 if (i % 4 == 0) // output a newline after every fourth card
19 System.out.println();
20 }
21 }
22 } // end class DeckOfCardsTest

```

---

|                   |                   |                   |                  |
|-------------------|-------------------|-------------------|------------------|
| Six of Spades     | Eight of Spades   | Six of Clubs      | Nine of Hearts   |
| Queen of Hearts   | Seven of Clubs    | Nine of Spades    | King of Hearts   |
| Three of Diamonds | Deuce of Clubs    | Ace of Hearts     | Ten of Spades    |
| Four of Spades    | Ace of Clubs      | Seven of Diamonds | Four of Hearts   |
| Three of Clubs    | Deuce of Hearts   | Five of Spades    | Jack of Diamonds |
| King of Clubs     | Ten of Hearts     | Three of Hearts   | Six of Diamonds  |
| Queen of Clubs    | Eight of Diamonds | Deuce of Diamonds | Ten of Diamonds  |
| Three of Spades   | King of Diamonds  | Nine of Clubs     | Six of Hearts    |
| Ace of Spades     | Four of Diamonds  | Seven of Hearts   | Eight of Clubs   |
| Deuce of Spades   | Eight of Hearts   | Five of Hearts    | Queen of Spades  |
| Jack of Hearts    | Seven of Spades   | Four of Clubs     | Nine of Diamonds |
| Ace of Diamonds   | Queen of Diamonds | Five of Clubs     | King of Spades   |
| Five of Diamonds  | Ten of Clubs      | Jack of Spades    | Jack of Clubs    |

**Fig. 7.13** | Card shuffling and dealing.

### *Preventing NullPointerExceptions*

In Fig. 7.12, we created a deck array of 52 Card references—each element of every reference-type array created with `new` is default initialized to `null`. Reference-type variables which are fields of a class are also initialized to `null` by default. A `NullPointerException` occurs when you try to call a method on a `null` reference. In industrial-strength code, en-



ensuring that references are not null before you use them to call methods prevents `NullPointerException`s.

## 7.7 Case Study: Class GradeBook Using an Array to Store Grades

We now present the first part of our case study on developing a `GradeBook` class that instructors can use to maintain students' grades on an exam and display a grade report that includes the grades, class average, lowest grade, highest grade and a grade distribution bar chart. The version of class `GradeBook` presented in this section stores the grades for one exam in a one-dimensional array. In Section 7.8, we present a version of class `GradeBook` that uses a two-dimensional array to store students' grades for *several* exams.

### *Storing Student Grades in an Array in Class GradeBook*

Class `GradeBook` (Fig. 7.14) uses an array of `ints` to store several students' grades on a single exam. Array `grades` is declared as an instance variable (line 7), so each `GradeBook` object maintains its *own* set of grades. The constructor (lines 10–14) has two parameters—the name of the course and an array of grades. When an application (e.g., class `GradeBookTest` in Fig. 7.15) creates a `GradeBook` object, the application passes an existing `int` array to the constructor, which assigns the array's reference to instance variable `grades` (line 13). The `grades` array's *size* is determined by the `length` instance variable of the constructor's array parameter. Thus, a `GradeBook` object can process a *variable* number of grades. The grade values in the argument could have been input from a user, read from a file on disk (as discussed in Chapter 15) or come from a variety of other sources. In class `GradeBookTest`, we initialize an array with grade values (Fig. 7.15, line 10). Once the grades are stored in *instance variable* `grades` of class `GradeBook`, all the class's methods can access the elements of `grades`.

---

```

1 // Fig. 7.14: GradeBook.java
2 // GradeBook class using an array to store test grades.
3
4 public class GradeBook
5 {
6 private String courseName; // name of course this GradeBook represents
7 private int[] grades; // array of student grades
8
9 // constructor
10 public GradeBook(String courseName, int[] grades)
11 {
12 this.courseName = courseName;
13 this.grades = grades;
14 }
15
16 // method to set the course name
17 public void setCourseName(String courseName)
18 {
19 this.courseName = courseName;
20 }

```

---

**Fig. 7.14** | `GradeBook` class using an array to store test grades. (Part 1 of 4.)

---

```

21
22 // method to retrieve the course name
23 public String getCourseName()
24 {
25 return courseName;
26 }
27
28 // perform various operations on the data
29 public void processGrades()
30 {
31 // output grades array
32 outputGrades();
33
34 // call method getAverage to calculate the average grade
35 System.out.printf("\nClass average is %.2f\n", getAverage());
36
37 // call methods getMinimum and getMaximum
38 System.out.printf("Lowest grade is %d\nHighest grade is %d\n\n",
39 getMinimum(), getMaximum());
40
41 // call outputBarChart to print grade distribution chart
42 outputBarChart();
43 }
44
45 // find minimum grade
46 public int getMinimum()
47 {
48 int lowGrade = grades[0]; // assume grades[0] is smallest
49
50 // loop through grades array
51 for (int grade : grades)
52 {
53 // if grade lower than lowGrade, assign it to lowGrade
54 if (grade < lowGrade)
55 lowGrade = grade; // new lowest grade
56 }
57
58 return lowGrade;
59 }
60
61 // find maximum grade
62 public int getMaximum()
63 {
64 int highGrade = grades[0]; // assume grades[0] is largest
65
66 // loop through grades array
67 for (int grade : grades)
68 {
69 // if grade greater than highGrade, assign it to highGrade
70 if (grade > highGrade)
71 highGrade = grade; // new highest grade
72 }

```

---

**Fig. 7.14** | GradeBook class using an array to store test grades. (Part 2 of 4.)

```
73
74 return highGrade;
75 }
76
77 // determine average grade for test
78 public double getAverage()
79 {
80 int total = 0;
81
82 // sum grades for one student
83 for (int grade : grades)
84 total += grade;
85
86 // return average of grades
87 return (double) total / grades.length;
88 }
89
90 // output bar chart displaying grade distribution
91 public void outputBarChart()
92 {
93 System.out.println("Grade distribution:");
94
95 // stores frequency of grades in each range of 10 grades
96 int[] frequency = new int[11];
97
98 // for each grade, increment the appropriate frequency
99 for (int grade : grades)
100 ++frequency[grade / 10];
101
102 // for each grade frequency, print bar in chart
103 for (int count = 0; count < frequency.length; count++)
104 {
105 // output bar label ("00-09: ", ..., "90-99: ", "100: ")
106 if (count == 10)
107 System.out.printf("%5d: ", 100);
108 else
109 System.out.printf("%02d-%02d: ",
110 count * 10, count * 10 + 9);
111
112 // print bar of asterisks
113 for (int stars = 0; stars < frequency[count]; stars++)
114 System.out.print("*");
115
116 System.out.println();
117 }
118 }
119
120 // output the contents of the grades array
121 public void outputGrades()
122 {
123 System.out.printf("The grades are:%n%n");
124 }
```

**Fig. 7.14** | GradeBook class using an array to store test grades. (Part 3 of 4.)

---

```

125 // output each student's grade
126 for (int student = 0; student < grades.length; student++)
127 System.out.printf("Student %2d: %3d%n",
128 student + 1, grades[student]);
129 }
130 } // end class GradeBook

```

---

**Fig. 7.14** | GradeBook class using an array to store test grades. (Part 4 of 4.)

Method `processGrades` (lines 29–43) contains a series of method calls that output a report summarizing the grades. Line 32 calls method `outputGrades` to print the contents of the array `grades`. Lines 126–128 in method `outputGrades` output the students' grades. A counter-controlled *for* statement *must* be used in this case, because lines 127–128 use counter variable `student`'s value to output each grade next to a particular student number (see the output in Fig. 7.15). Although array indices start at 0, a professor might typically number students starting at 1. Thus, lines 127–128 output `student + 1` as the student number to produce grade labels "Student 1: ", "Student 2: ", and so on.

Method `processGrades` next calls method `getAverage` (line 35) to obtain the average of the grades in the array. Method `getAverage` (lines 78–88) uses an enhanced *for* statement to total the values in array `grades` before calculating the average. The parameter in the enhanced *for*'s header (e.g., `int grade`) indicates that for each iteration, the `int` variable `grade` takes on a value in the array `grades`. The averaging calculation in line 87 uses `grades.length` to determine the number of grades being averaged.

Lines 38–39 in method `processGrades` call methods `getMinimum` and `getMaximum` to determine the lowest and highest grades of any student on the exam, respectively. Each of these methods uses an enhanced *for* statement to loop through array `grades`. Lines 51–56 in method `getMinimum` loop through the array. Lines 54–55 compare each grade to `lowGrade`; if a grade is less than `lowGrade`, `lowGrade` is set to that grade. When line 58 executes, `lowGrade` contains the lowest grade in the array. Method `getMaximum` (lines 62–75) works similarly to method `getMinimum`.

Finally, line 42 in method `processGrades` calls `outputBarChart` to print a grade distribution chart using a technique similar to that in Fig. 6.6. In that example, we manually calculated the number of grades in each category (i.e., 0–9, 10–19, ..., 90–99 and 100) by simply looking at a set of grades. Here, lines 99–100 use a technique similar to that in Fig. 6.8 to calculate the frequency of grades in each category. Line 96 declares and creates array `frequency` of 11 `ints` to store the frequency of grades in each category. For each grade in array `grades`, lines 99–100 increment the appropriate frequency array element. To determine which one to increment, line 100 divides the current grade by 10 using *integer division*—e.g., if grade is 85, line 100 increments `frequency[8]` to update the count of grades in the range 80–89. Lines 103–117 print the bar chart (as shown in Fig. 7.15) based on the values in array `frequency`. Like lines 23–24 of Fig. 6.6, lines 113–116 of Fig. 7.14 use a value in array `frequency` to determine the number of asterisks to display in each bar.

### ***Class GradeBookTest That Demonstrates Class GradeBook***

The application of Fig. 7.15 creates an object of class `GradeBook` (Fig. 7.14) using the `int` array `gradesArray` (declared and initialized in line 10). Lines 12–13 pass a course name and `gradesArray` to the `GradeBook` constructor. Lines 14–15 display a welcome message that in-

cludes the course name stored in the GradeBook object. Line 16 invokes the GradeBook object's processGrades method. The output summarizes the 10 grades in myGradeBook.



### Software Engineering Observation 7.5

*A test harness (or test application) is responsible for creating an object of the class being tested and providing it with data. This data could come from any of several sources. Test data can be placed directly into an array with an array initializer, it can come from the user at the keyboard, from a file (as you'll see in Chapter 15), from a database (as you'll see in Chapter 24) or from a network (as you'll see in online Chapter 28). After passing this data to the class's constructor to instantiate the object, the test harness should call upon the object to test its methods and manipulate its data. Gathering data in the test harness like this allows the class to be more reusable, able to manipulate data from several sources.*

```

1 // Fig. 7.15: GradeBookTest.java
2 // GradeBookTest creates a GradeBook object using an array of grades,
3 // then invokes method processGrades to analyze them.
4 public class GradeBookTest
5 {
6 // main method begins program execution
7 public static void main(String[] args)
8 {
9 // array of student grades
10 int[] gradesArray = { 87, 68, 94, 100, 83, 78, 85, 91, 76, 87 };
11
12 GradeBook myGradeBook = new GradeBook(
13 "CS101 Introduction to Java Programming", gradesArray);
14 System.out.printf("Welcome to the grade book for%n%s%n",
15 myGradeBook.getCourseName());
16 myGradeBook.processGrades();
17 }
18 } // end class GradeBookTest

```

```

Welcome to the grade book for
CS101 Introduction to Java Programming

```

The grades are:

```

Student 1: 87
Student 2: 68
Student 3: 94
Student 4: 100
Student 5: 83
Student 6: 78
Student 7: 85
Student 8: 91
Student 9: 76
Student 10: 87

```

```

Class average is 84.90
Lowest grade is 68
Highest grade is 100

```

**Fig. 7.15** | GradeBookTest creates a GradeBook object using an array of grades, then invokes method processGrades to analyze them. (Part 1 of 2.)

```

Grade distribution:
00-09:
10-19:
20-29:
30-39:
40-49:
50-59:
60-69: *
70-79: **
80-89: ****
90-99: **
100: *

```

**Fig. 7.15** | GradeBookTest creates a GradeBook object using an array of grades, then invokes method processGrades to analyze them. (Part 2 of 2.)

### Java SE 8

In Chapter 17, Java SE 8 Lambdas and Streams, the example of Fig. 17.5 uses stream methods min, max, count and average to process the elements of an int array elegantly and concisely without having to write repetition statements. In Chapter 23, Concurrency, the example of Fig. 23.29 uses stream method summaryStatistics to perform all of these operations in one method call.

## 7.8 Case Study: Class GradeBook Using a Two-Dimensional Array

In Section 7.7, we presented class GradeBook (Fig. 7.14), which used a one-dimensional array to store student grades on a single exam. In most semesters, students take several exams. Professors are likely to want to analyze grades across the entire semester, both for a single student and for the class as a whole.

### Storing Student Grades in a Two-Dimensional Array in Class GradeBook

Figure 7.16 contains a GradeBook class that uses a two-dimensional array grades to store the grades of *several* students on *multiple* exams. Each *row* of the array represents a *single* student's grades for the entire course, and each *column* represents the grades of *all* the students who took a particular exam. Class GradeBookTest (Fig. 7.17) passes the array as an argument to the GradeBook constructor. In this example, we use a ten-by-three array for ten students' grades on three exams. Five methods perform array manipulations to process the grades. Each method is similar to its counterpart in the earlier one-dimensional array version of GradeBook (Fig. 7.14). Method getMinimum (lines 46–62) determines the lowest grade of any student for the semester. Method getMaximum (lines 65–83) determines the highest grade of any student for the semester. Method getAverage (lines 86–96) determines a particular student's semester average. Method outputBarChart (lines 99–129) outputs a grade bar chart for the entire semester's student grades. Method outputGrades (lines 132–156) outputs the array in a tabular format, along with each student's semester average.

---

```

1 // Fig. 7.16: GradeBook.java
2 // GradeBook class using a two-dimensional array to store grades.
3
4 public class GradeBook
5 {
6 private String courseName; // name of course this grade book represents
7 private int[][] grades; // two-dimensional array of student grades
8
9 // two-argument constructor initializes courseName and grades array
10 public GradeBook(String courseName, int[][] grades)
11 {
12 this.courseName = courseName;
13 this.grades = grades;
14 }
15
16 // method to set the course name
17 public void setCourseName(String courseName)
18 {
19 this.courseName = courseName;
20 }
21
22 // method to retrieve the course name
23 public String getCourseName()
24 {
25 return courseName;
26 }
27
28 // perform various operations on the data
29 public void processGrades()
30 {
31 // output grades array
32 outputGrades();
33
34 // call methods getMinimum and getMaximum
35 System.out.printf("%n%s %d%n%s %d%n%n",
36 "Lowest grade in the grade book is", getMinimum(),
37 "Highest grade in the grade book is", getMaximum());
38
39 // output grade distribution chart of all grades on all tests
40 outputBarChart();
41 }
42
43 // find minimum grade
44 public int getMinimum()
45 {
46 // assume first element of grades array is smallest
47 int lowGrade = grades[0][0];
48
49 // loop through rows of grades array
50 for (int[] studentGrades : grades)
51 {

```

---

**Fig. 7.16** | GradeBook class using a two-dimensional array to store grades. (Part I of 4.)

```

52 // loop through columns of current row
53 for (int grade : studentGrades)
54 {
55 // if grade less than lowGrade, assign it to lowGrade
56 if (grade < lowGrade)
57 lowGrade = grade;
58 }
59 }
60
61 return lowGrade;
62 }
63
64 // find maximum grade
65 public int getMaximum()
66 {
67 // assume first element of grades array is largest
68 int highGrade = grades[0][0];
69
70 // loop through rows of grades array
71 for (int[] studentGrades : grades)
72 {
73 // loop through columns of current row
74 for (int grade : studentGrades)
75 {
76 // if grade greater than highGrade, assign it to highGrade
77 if (grade > highGrade)
78 highGrade = grade;
79 }
80 }
81
82 return highGrade;
83 }
84
85 // determine average grade for particular set of grades
86 public double getAverage(int[] setOfGrades)
87 {
88 int total = 0;
89
90 // sum grades for one student
91 for (int grade : setOfGrades)
92 total += grade;
93
94 // return average of grades
95 return (double) total / setOfGrades.length;
96 }
97
98 // output bar chart displaying overall grade distribution
99 public void outputBarChart()
100 {
101 System.out.println("Overall grade distribution:");
102

```

**Fig. 7.16** | GradeBook class using a two-dimensional array to store grades. (Part 2 of 4.)



```

103 // stores frequency of grades in each range of 10 grades
104 int[] frequency = new int[11];
105
106 // for each grade in GradeBook, increment the appropriate frequency
107 for (int[] studentGrades : grades)
108 {
109 for (int grade : studentGrades)
110 ++frequency[grade / 10];
111 }
112
113 // for each grade frequency, print bar in chart
114 for (int count = 0; count < frequency.length; count++)
115 {
116 // output bar label ("00-09: ", ..., "90-99: ", "100: ")
117 if (count == 10)
118 System.out.printf("%5d: ", 100);
119 else
120 System.out.printf("%02d-%02d: ",
121 count * 10, count * 10 + 9);
122
123 // print bar of asterisks
124 for (int stars = 0; stars < frequency[count]; stars++)
125 System.out.print("*");
126
127 System.out.println();
128 }
129 }
130
131 // output the contents of the grades array
132 public void outputGrades()
133 {
134 System.out.printf("The grades are:%n%n");
135 System.out.print(" "); // align column heads
136
137 // create a column heading for each of the tests
138 for (int test = 0; test < grades[0].length; test++)
139 System.out.printf("Test %d ", test + 1);
140
141 System.out.println("Average"); // student average column heading
142
143 // create rows/columns of text representing array grades
144 for (int student = 0; student < grades.length; student++)
145 {
146 System.out.printf("Student %2d", student + 1);
147
148 for (int test : grades[student]) // output student's grades
149 System.out.printf("%8d", test);
150
151 // call method getAverage to calculate student's average grade;
152 // pass row of grades as the argument to getAverage
153 double average = getAverage(grades[student]);

```

**Fig. 7.16** | GradeBook class using a two-dimensional array to store grades. (Part 3 of 4.)

---

```

154 System.out.printf("%9.2f%n", average);
155 }
156 }
157 } // end class GradeBook

```

---

**Fig. 7.16** | GradeBook class using a two-dimensional array to store grades. (Part 4 of 4.)

### ***Methods `getMinimum` and `getMaximum`***

Methods `getMinimum`, `getMaximum`, `outputBarChart` and `outputGrades` each loop through array `grades` by using nested `for` statements—for example, the nested enhanced `for` statement (lines 50–59) from the declaration of method `getMinimum`. The outer enhanced `for` statement iterates through the two-dimensional array `grades`, assigning successive rows to parameter `studentGrades` on successive iterations. The square brackets following the parameter name indicate that `studentGrades` refers to a one-dimensional `int` array—namely, a row in array `grades` containing one student’s grades. To find the lowest overall grade, the inner `for` statement compares the elements of the current one-dimensional array `studentGrades` to variable `lowGrade`. For example, on the first iteration of the outer `for`, row 0 of `grades` is assigned to parameter `studentGrades`. The inner enhanced `for` statement then loops through `studentGrades` and compares each grade value with `lowGrade`. If a grade is less than `lowGrade`, `lowGrade` is set to that grade. On the second iteration of the outer enhanced `for` statement, row 1 of `grades` is assigned to `studentGrades`, and the elements of this row are compared with variable `lowGrade`. This repeats until all rows of `grades` have been traversed. When execution of the nested statement is complete, `lowGrade` contains the lowest grade in the two-dimensional array. Method `getMaximum` works similarly to method `getMinimum`.

### ***Method `outputBarChart`***

Method `outputBarChart` in Fig. 7.16 is nearly identical to the one in Fig. 7.14. However, to output the overall grade distribution for a whole semester, the method here uses nested enhanced `for` statements (lines 107–111) to create the one-dimensional array `frequency` based on all the grades in the two-dimensional array. The rest of the code in each of the two `outputBarChart` methods that displays the chart is identical.

### ***Method `outputGrades`***

Method `outputGrades` (lines 132–156) uses nested `for` statements to output values of the array `grades` and each student’s semester average. The output (Fig. 7.17) shows the result, which resembles the tabular format of a professor’s physical grade book. Lines 138–139 print the column headings for each test. We use a counter-controlled `for` statement here so that we can identify each test with a number. Similarly, the `for` statement in lines 144–155 first outputs a row label using a counter variable to identify each student (line 146). Although array indices start at 0, lines 139 and 146 output `test + 1` and `student + 1`, respectively, to produce test and student numbers starting at 1 (see the output in Fig. 7.17). The inner `for` statement (lines 148–149) uses the outer `for` statement’s counter variable `student` to loop through a specific row of array `grades` and output each student’s test grade. An enhanced `for` statement can be nested in a counter-controlled `for` statement, and vice versa. Finally, line 153 obtains each student’s semester average by passing the current row of `grades` (i.e., `grades[student]`) to method `getAverage`.

**Method `getAverage`**

Method `getAverage` (lines 86–96) takes one argument—a one-dimensional array of test results for a particular student. When line 153 calls `getAverage`, the argument is `grades[student]`, which specifies that a particular row of the two-dimensional array `grades` should be passed to `getAverage`. For example, based on the array created in Fig. 7.17, the argument `grades[1]` represents the three values (a one-dimensional array of grades) stored in row 1 of the two-dimensional array `grades`. Recall that a two-dimensional array is one whose elements are one-dimensional arrays. Method `getAverage` calculates the sum of the array elements, divides the total by the number of test results and returns the floating-point result as a `double` value (line 95).

**Class `GradeBookTest` That Demonstrates Class `GradeBook`**

Figure 7.17 creates an object of class `GradeBook` (Fig. 7.16) using the two-dimensional array of ints named `gradesArray` (declared and initialized in lines 10–19). Lines 21–22 pass a course name and `gradesArray` to the `GradeBook` constructor. Lines 23–24 display a welcome message containing the course name, then line 25 invokes `myGradeBook`'s `processGrades` method to display a report summarizing the students' grades for the semester.

---

```

1 // Fig. 7.17: GradeBookTest.java
2 // GradeBookTest creates GradeBook object using a two-dimensional array
3 // of grades, then invokes method processGrades to analyze them.
4 public class GradeBookTest
5 {
6 // main method begins program execution
7 public static void main(String[] args)
8 {
9 // two-dimensional array of student grades
10 int[][] gradesArray = {{87, 96, 70},
11 {68, 87, 90},
12 {94, 100, 90},
13 {100, 81, 82},
14 {83, 65, 85},
15 {78, 87, 65},
16 {85, 75, 83},
17 {91, 94, 100},
18 {76, 72, 84},
19 {87, 93, 73}};
20
21 GradeBook myGradeBook = new GradeBook(
22 "CS101 Introduction to Java Programming", gradesArray);
23 System.out.printf("Welcome to the grade book for%n%s%n",
24 myGradeBook.getCourseName());
25 myGradeBook.processGrades();
26 }
27 } // end class GradeBookTest

```

---

**Fig. 7.17** | `GradeBookTest` creates `GradeBook` object using a two-dimensional array of grades, then invokes method `processGrades` to analyze them. (Part 1 of 2.)

```

Welcome to the grade book for
CS101 Introduction to Java Programming

The grades are:

 Test 1 Test 2 Test 3 Average
Student 1 87 96 70 84.33
Student 2 68 87 90 81.67
Student 3 94 100 90 94.67
Student 4 100 81 82 87.67
Student 5 83 65 85 77.67
Student 6 78 87 65 76.67
Student 7 85 75 83 81.00
Student 8 91 94 100 95.00
Student 9 76 72 84 77.33
Student 10 87 93 73 84.33

Lowest grade in the grade book is 65
Highest grade in the grade book is 100

Overall grade distribution:
00-09:
10-19:
20-29:
30-39:
40-49:
50-59:
60-69: ***
70-79: *****
80-89: *****
90-99: *****
100: ***

```

**Fig. 7.17** | GradeBookTest creates GradeBook object using a two-dimensional array of grades, then invokes method processGrades to analyze them. (Part 2 of 2.)

## 7.9 Wrap-Up

In this chapter, you learned how to create your own classes, create objects of those classes and call methods of those objects to perform useful actions. You declared instance variables maintain data for each object of the class, and you declared your own methods to operate on that data. You learned the difference between a local variable of a method and an instance variable of a class, and that only instance variables are initialized automatically. You used a class's constructor to specify the initial values for an object's instance variables. You studied an Account class, then three substantial object-oriented case studies—one card shuffling and dealing and two variations of a GradeBook class. The first used a one-dimensional array of grades for 10 students on a single exam. The second used a two-dimensional array of grades for 10 students on three exams. In Chapter 8, we take a deeper look at classes and objects.

## Summary

### Section 7.2 Instance Variables, set Methods and get Methods

- Each class you create becomes a new type that can be used to declare variables and create objects.
- You can declare new classes as needed; this is one reason Java is known as an extensible language.

### **Section 7.2.1 Account Class with an Instance Variable, a set Method and a get Method**

- Each class declaration that begins with the access modifier (p. 268) `public` must be stored in a file that has the same name as the class and ends with the `.java` filename extension.
- Every class declaration contains keyword `class` followed immediately by the class's name.
- Class, method and variable names are identifiers. By convention all use camel case names. Class names begin with an uppercase letter, and method and variable names begin with a lowercase letter.
- An object has attributes that are implemented as instance variables (p. 268) and carried with it throughout its lifetime.
- Instance variables exist before methods are called on an object, while the methods are executing and after the methods complete execution.
- A class normally contains one or more methods that manipulate the instance variables that belong to particular objects of the class.
- Instance variables are declared inside a class declaration but outside the bodies of the class's method declarations.
- Each object (instance) of the class has its own copy of each of the class's instance variables.
- Most instance-variable declarations are preceded with the keyword `private` (p. 268), which is an access modifier. Variables or methods declared with access modifier `private` are accessible only to methods of the class in which they're declared.
- Classes often provide `public` methods to allow the class's clients to *set* or *get* `private` instance variables. The names of these methods need not begin with *set* or *get*, but this naming convention is recommended.

### **Section 7.2.2 AccountTest Class That Creates and Uses an Object of Class Account**

- A class that creates an object of another class, then calls the object's methods, is a driver class.
- Scanner method `nextLine` (p. 270) reads characters until a newline character is encountered, then returns the characters as a `String`.
- Scanner method `next` (p. 270) reads characters until any white-space character is encountered, then returns the characters as a `String`.
- A class instance creation expression (p. 271) begins with keyword `new` and creates a new object.
- A constructor is similar to a method but is called implicitly by the `new` operator to initialize an object's instance variables at the time the object is created.
- To call a method of an object, follow the object name with a dot separator (p. 271), the method name and a set of parentheses containing the method's arguments.
- Local variables are not automatically initialized. Every instance variable has a default initial value—a value provided by Java when you do not specify the instance variable's initial value.
- The default value for an instance variable of type `String` is `null`.
- A method call supplies values—known as arguments—for each of the method's parameters. Each argument's value is assigned to the corresponding parameter in the method header.
- The number of arguments in a method call must match the number of parameters in the method declaration's parameter list.
- The argument types in the method call must be consistent with the types of the corresponding parameters in the method's declaration.

### **Section 7.2.3 Compiling and Executing an App with Multiple Classes**

- The `javac` command can compile multiple classes at once. Simply list the source-code filenames after the command with each filename separated by a space from the next. If the directory con-

taining the app includes only one app's files, you can compile all of its classes with the command `javac *.java`. The asterisk (\*) in `*.java` indicates that all files in the current directory ending with the filename extension `".java"` should be compiled.

#### *Section 7.2.4 Account UML Class Diagram with an Instance Variable and set and get Methods*

- In the UML, each class is modeled in a class diagram (p. 273) as a rectangle with three compartments. The top one contains the class's name centered horizontally in boldface. The middle one contains the class's attributes, which correspond to instance variables in Java. The bottom one contains the class's operations (p. 273), which correspond to methods and constructors in Java.
- The UML represents instance variables as an attribute name, followed by a colon and the type.
- Private attributes are preceded by a minus sign (–) in the UML.
- The UML models operations by listing the operation name followed by a set of parentheses. A plus sign (+) in front of the operation name indicates that the operation is a public one in the UML (i.e., a `public` method in Java).
- The UML models a parameter of an operation by listing the parameter name, followed by a colon and the parameter type between the parentheses after the operation name.
- The UML indicates an operation's return type by placing a colon and the return type after the parentheses following the operation name.
- UML class diagrams do not specify return types for operations that do not return values.
- Declaring instance variables private is known as data hiding or information hiding.

#### *Section 7.2.5 Additional Notes on This Example*

- Most classes you'll use in Java programs must be imported explicitly. There's a special relationship between classes that are compiled in the same directory. By default, such classes are considered to be in the same package—known as the default package. Classes in the same package are implicitly imported into the source-code files of other classes in that package. An `import` declaration is not required when one class in a package uses another in the same package.
- An `import` declaration is not required if you always refer to a class with its fully qualified class name, which includes its package name and class name.

#### *Section 7.2.6 Software Engineering with **private** Instance Variables and **public** set and get Methods*

- Declaring instance variables private is known as data hiding or information hiding.

#### *Section 7.3 Default and Explicit Initialization for Instance Variables*

- Primitive-type instance variables are initialized by default. Variables of types `byte`, `char`, `short`, `int`, `long`, `float` and `double` are initialized to 0. Variables of type `boolean` are initialized to `false`.
- Reference-type instance variables are initialized by default to the value `null`.

#### *Section 7.4 Account Class: Initializing Objects with Constructors*

- Each class you declare can optionally provide a constructor with parameters that can be used to initialize an object of a class when the object is created.
- Java requires a constructor call for every object that's created.
- Constructors can specify parameters but not return types.
- If a class does not define constructors, the compiler provides a default constructor (p. 278) with no parameters, and the class's instance variables are initialized to their default values.
- If you declare a constructor for a class, the compiler will *not* create a *default constructor* for that class.

- The UML models constructors in the third compartment of a class diagram. To distinguish a constructor from a class's operations, the UML places the word "constructor" between guillemets (« and »; p. 279) before the constructor's name.

### Section 7.5 Account Class with a Balance; Floating-Point Numbers

- Scanner method `nextDouble` returns a `double` value.
- The format specifier `%f` (p. 282) is used to output values of type `float` or `double`. The format specifier `%.2f` specifies that two digits of precision (p. 283) should be output to the right of the decimal point in the floating-point number.
- The default value for an instance variable of type `double` is 0.0, and the default value for an instance variable of type `int` is 0.

### Section 7.6 Case Study: Card Shuffling and Dealing Simulation

- The `toString` method of an object is called implicitly when the object is used where a `String` is expected (e.g., when `printf` outputs the object as a `String` using the `%s` format specifier or when the object is concatenated to a `String` using the `+` operator).

## Self-Review Exercises

- 7.1** Fill in the blanks in each of the following:
- Each class declaration that begins with keyword \_\_\_\_\_ must be stored in a file that has exactly the same name as the class and ends with the `.java` filename extension.
  - Keyword \_\_\_\_\_ in a class declaration is followed immediately by the class's name.
  - Keyword \_\_\_\_\_ requests memory from the system to store an object, then calls the corresponding class's constructor to initialize the object.
  - Each parameter must specify both a(n) \_\_\_\_\_ and a(n) \_\_\_\_\_.
  - By default, classes that are compiled in the same directory are considered to be in the same package, known as the \_\_\_\_\_.
  - Variables of type `double` represent \_\_\_\_\_ floating-point numbers.
  - Scanner method \_\_\_\_\_ returns a `double` value.
  - Keyword `public` is an access \_\_\_\_\_.
  - Scanner method \_\_\_\_\_ reads characters until it encounters a newline character, then returns those characters as a `String`.
  - Class `String` is in package \_\_\_\_\_.
  - A(n) \_\_\_\_\_ is not required if you always refer to a class with its fully qualified class name.
- 7.2** State whether each of the following is *true* or *false*. If *false*, explain why.
- An `import` declaration is not required when one class in a package uses another in the same package.
  - Variables declared in the body of a particular method are known as instance variables and can be used in all methods of the class.
  - Primitive-type local variables are initialized by default.
  - Reference-type instance variables are initialized by default to the value `null`.
- 7.3** What is the difference between a local variable and an instance variable?

## Answers to Self-Review Exercises

- 7.1** a) `public`. b) `class`. c) `new`. d) type, name. e) default package. f) double-precision. g) `nextDouble`. h) modifier. i) `nextLine`. j) `java.lang`. k) `import` declaration.

**7.2** a) True. b) False. Such variables are called local variables and can be used only in the method in which they're declared. c) False. Primitive-type instance variables are initialized by default. Each local variable must explicitly be assigned a value. d) True.

**7.3** A local variable is declared in the body of a method and can be used only from the point at which it's declared through the end of the method declaration. An instance variable is declared in a class, but not in the body of any of the class's methods. Also, instance variables are accessible to all methods of the class. (We'll see an exception to this in Chapter 8.)

## Exercises

**7.4** (*Keyword new*) What's the purpose of keyword `new`? Explain what happens when you use it.

**7.5** (*Default Constructors*) What is a default constructor? How are an object's instance variables initialized if a class has only a default constructor?

**7.6** (*Instance Variables*) Explain the purpose of an instance variable.

**7.7** (*Using Classes without Importing Them*) Most classes need to be imported before they can be used in an app. Why is every app allowed to use classes `System` and `String` without first importing them?

**7.8** (*Using a Class without Importing It*) Explain how a program could use class `Scanner` without importing it.

**7.9** (*set and get Methods*) Explain why a class might provide a *set* method and a *get* method for an instance variable.

**7.10** (*Modified Account Class*) Modify class `Account` (Fig. 7.8) to provide a method called `withdraw` that withdraws money from an `Account`. Ensure that the withdrawal amount does not exceed the `Account`'s balance. If it does, the balance should be left unchanged and the method should print a message indicating "Withdrawal amount exceeded account balance." Modify class `AccountTest` (Fig. 7.9) to test method `withdraw`.

**7.11** (*Invoice Class*) Create a class called `Invoice` that a hardware store might use to represent an invoice for an item sold at the store. An `Invoice` should include four pieces of information as instance variables—a part number (type `String`), a part description (type `String`), a quantity of the item being purchased (type `int`) and a price per item (type `double`). Your class should have a constructor that initializes the four instance variables. Provide a *set* and a *get* method for each instance variable. In addition, provide a method named `getInvoiceAmount` that calculates the invoice amount (i.e., multiplies the quantity by the price per item), then returns the amount as a `double` value. If the quantity is not positive, it should be set to 0. If the price per item is not positive, it should be set to 0.0. Write a test app named `InvoiceTest` that demonstrates class `Invoice`'s capabilities.

**7.12** (*Employee Class*) Create a class called `Employee` that includes three instance variables—a first name (type `String`), a last name (type `String`) and a monthly salary (type `double`). Provide a constructor that initializes the three instance variables. Provide a *set* and a *get* method for each instance variable. If the monthly salary is not positive, do not set its value. Write a test app named `EmployeeTest` that demonstrates class `Employee`'s capabilities. Create two `Employee` objects and display each object's *yearly* salary. Then give each `Employee` a 10% raise and display each `Employee`'s *yearly* salary again.

**7.13** (*Date Class*) Create a class called `Date` that includes three instance variables—a month (type `int`), a day (type `int`) and a year (type `int`). Provide a constructor that initializes the three instance variables and assumes that the values provided are correct. Provide a *set* and a *get* method for each instance variable. Provide a method `displayDate` that displays the month, day and year separated by forward slashes (/). Write a test app named `DateTest` that demonstrates class `Date`'s capabilities.



**7.14 (Removing Duplicated Code in Method *main*)** In the `AccountTest` class of Fig. 7.9, method `main` contains six statements (lines 13–14, 15–16, 28–29, 30–31, 40–41 and 42–43) that each display an `Account` object's name and balance. Study these statements and you'll notice that they differ only in the `Account` object being manipulated—`account1` or `account2`. In this exercise, you'll define a new `displayAccount` method that contains *one* copy of that output statement. The method's parameter will be an `Account` object and the method will output the object's name and balance. You'll then replace the six duplicated statements in `main` with calls to `displayAccount`, passing as an argument the specific `Account` object to output.

Modify class `AccountTest` class of Fig. 7.9 to declare the following `displayAccount` method *after* the closing right brace of `main` and *before* the closing right brace of class `AccountTest`:

```
public static void displayAccount(Account accountToDisplay)
{
 // place the statement that displays
 // accountToDisplay's name and balance here
}
```

Replace the comment in the method's body with a statement that displays `accountToDisplay`'s name and balance.

Recall that `main` is a static method, so it can be called without first creating an object of the class in which `main` is declared. We also declared method `displayAccount` as a static method. When `main` needs to call another method in the same class without first creating an object of that class, the other method *also* must be declared static.

Once you've completed `displayAccount`'s declaration, modify `main` to replace the statements that display each `Account`'s name and balance with calls to `displayAccount`—each receiving as its argument the `account1` or `account2` object, as appropriate. Then, test the updated `AccountTest` class to ensure that it produces the same output as shown in Fig. 7.9.

**7.15 (Enhanced *GradeBook*)** Modify the `GradeBook` class of Fig. 7.16 so that the constructor accepts as parameters the number of students and the number of exams, then builds an appropriately sized two-dimensional array, rather than receiving a preinitialized two-dimensional array as it does now. Set each element of the new two-dimensional array to -1 to indicate that no grade has been entered for that element. Add a `setGrade` method that sets one grade for a particular student on a particular exam. Modify class `GradeBookTest` of Fig. 7.17 to input the number of students and number of exams for the `GradeBook` and to allow the instructor to enter one grade at a time.

*Exercises 7.16–7.20 are reasonably challenging. Once you've done them, you ought to be able to implement most popular card games easily.*

**7.16 (Card Shuffling and Dealing)** Modify the application of Fig. 7.13 to deal a five-card poker hand. Then modify class `DeckOfCards` of Fig. 7.12 to include methods that determine whether a hand contains

- a) a pair
- b) two pairs
- c) three of a kind (e.g., three jacks)
- d) four of a kind (e.g., four aces)
- e) a flush (i.e., all five cards of the same suit)
- f) a straight (i.e., five cards of consecutive face values)
- g) a full house (i.e., two cards of one face value and three cards of another face value)

[Hint: Add methods `getFace` and `getSuit` to class `Card` of Fig. 7.11.]

**7.17 (Card Shuffling and Dealing)** Use the methods developed in Exercise 7.16 to write an application that deals two five-card poker hands, evaluates each hand and determines which is better.

**7.18** (*Project: Card Shuffling and Dealing*) Modify the application developed in Exercise 7.17 so that it can simulate the dealer. The dealer's five-card hand is dealt "face down," so the player cannot see it. The application should then evaluate the dealer's hand, and, based on the quality of the hand, the dealer should draw one, two or three more cards to replace the corresponding number of unneeded cards in the original hand. The application should then reevaluate the dealer's hand. [*Caution:* This is a difficult problem!]

**7.19** (*Project: Card Shuffling and Dealing*) Modify the application developed in Exercise 7.18 so that it can handle the dealer's hand automatically, but the player is allowed to decide which cards of the player's hand to replace. The application should then evaluate both hands and determine who wins. Now use this new application to play 20 games against the computer. Who wins more games, you or the computer? Have a friend play 20 games against the computer. Who wins more games? Based on the results of these games, refine your poker-playing application. (This, too, is a difficult problem.) Play 20 more games. Does your modified application play a better game?

**7.20** (*Project: Card Shuffling and Dealing*) Modify the application of Figs. 7.11–7.13 to use `Face` and `Suit` enum types to represent the faces and suits of the cards. Declare each of these enum types as a `public` type in its own source-code file. Each `Card` should have a `Face` and a `Suit` instance variable. These should be initialized by the `Card` constructor. In class `DeckOfCards`, create an array of `Faces` that's initialized with the names of the constants in the `Face` enum type and an array of `Suits` that's initialized with the names of the constants in the `Suit` enum type. [*Note:* When you output an enum constant as a `String`, the name of the constant is displayed.]

**7.21** (*Fisher-Yates Shuffling Algorithm*) Research the Fisher-Yates shuffling algorithm online, then use it to reimplement the `shuffle` method in Fig. 7.12.

## Making a Difference

**7.22** (*Target-Heart-Rate Calculator*) While exercising, you can use a heart-rate monitor to see that your heart rate stays within a safe range suggested by your trainers and doctors. According to the American Heart Association (AHA) ([www.americanheart.org/presenter.jhtml?identifier=4736](http://www.americanheart.org/presenter.jhtml?identifier=4736)), the formula for calculating your *maximum heart rate* in beats per minute is 220 minus your age in years. Your *target heart rate* is a range that's 50–85% of your maximum heart rate. [*Note:* These formulas are estimates provided by the AHA. Maximum and target heart rates may vary based on the health, fitness and gender of the individual. **Always consult a physician or qualified health-care professional before beginning or modifying an exercise program.**] Create a class called `HeartRates`. The class attributes should include the person's first name, last name and date of birth (consisting of separate attributes for the month, day and year of birth). Your class should have a constructor that receives this data as parameters. For each attribute provide *set* and *get* methods. The class also should include a method that calculates and returns the person's age (in years), a method that calculates and returns the person's maximum heart rate and a method that calculates and returns the person's target heart rate. Write a Java app that prompts for the person's information, instantiates an object of class `HeartRates` and prints the information from that object—including the person's first name, last name and date of birth—then calculates and prints the person's age in (years), maximum heart rate and target-heart-rate range.

# Classes and Objects: A Deeper Look

# 8



*Is it a world to hide virtues in?*

—William Shakespeare

*But what, to serve  
our private ends,  
Forbids the cheating  
of our friends?*

—Charles Churchill

*This above all: to thine own self  
be true.*

—William Shakespeare.

## Objectives

In this chapter you'll:

- Use the `throw` statement to indicate that a problem has occurred.
- Use keyword `this` in a constructor to call another constructor in the same class.
- Use `static` variables and methods.
- Import `static` members of a class.
- Use the `enum` type to create sets of constants with unique identifiers.
- Declare `enum` constants with parameters.
- Use `BigDecimal` for precise monetary calculations.

- |                                                                                    |                                                                          |
|------------------------------------------------------------------------------------|--------------------------------------------------------------------------|
| 8.1 Introduction                                                                   | 8.11 <code>static</code> Class Members                                   |
| 8.2 Time Class Case Study                                                          | 8.12 <code>static</code> Import                                          |
| 8.3 Controlling Access to Members                                                  | 8.13 <code>final</code> Instance Variables                               |
| 8.4 Referring to the Current Object's Members with the <code>this</code> Reference | 8.14 Package Access                                                      |
| 8.5 Time Class Case Study: Overloaded Constructors                                 | 8.15 Using <code>BigDecimal</code> for Precise Monetary Calculations     |
| 8.6 Default and No-Argument Constructors                                           | 8.16 (Optional) GUI and Graphics Case Study: Using Objects with Graphics |
| 8.7 Notes on <code>Set</code> and <code>Get</code> Methods                         | 8.17 Wrap-Up                                                             |
| 8.8 Composition                                                                    |                                                                          |
| 8.9 <code>enum</code> Types                                                        |                                                                          |
| 8.10 Garbage Collection                                                            |                                                                          |

Summary | Self-Review Exercise | Answers to Self-Review Exercise | Exercises | Making a Difference

## 8.1 Introduction

We now take a deeper look at building classes, controlling access to members of a class and creating constructors. We show how to throw an exception to indicate that a problem has occurred (Section 6.5 discussed catching exceptions). We use the `this` keyword to enable one constructor to conveniently call another constructor of the same class. We discuss *composition*—a capability that allows a class to have references to objects of other classes as members. We reexamine the use of *set* and *get* methods. Recall that Section 5.10 introduced the basic `enum` type to declare a set of constants. In this chapter, we discuss the relationship between `enum` types and classes, demonstrating that an `enum` type, like a class, can be declared in its own file with constructors, methods and fields. The chapter also discusses static class members and `final` instance variables in detail. We show a special relationship between classes in the same package. Finally, we demonstrate how to use class `BigDecimal` to perform precise monetary calculations. Two additional types of classes—nested classes and anonymous inner classes—are discussed in Chapter 12.

## 8.2 Time Class Case Study

Our first example consists of two classes—`Time1` (Fig. 8.1) and `Time1Test` (Fig. 8.2). Class `Time1` represents the time of day. Class `Time1Test`'s `main` method creates one object of class `Time1` and invokes its methods. The output of this program appears in Fig. 8.2.

### *Time1 Class Declaration*

Class `Time1`'s private `int` instance variables `hour`, `minute` and `second` (lines 6–8) represent the time in universal-time format (24-hour clock format in which hours are in the range 0–23, and minutes and seconds are each in the range 0–59). `Time1` contains public methods `setTime` (lines 12–25), `toUniversalString` (lines 28–31) and `toString` (lines 34–39). These methods are also called the **public services** or the **public interface** that the class provides to its clients.

---

```

1 // Fig. 8.1: Time1.java
2 // Time1 class declaration maintains the time in 24-hour format.
3
4 public class Time1
5 {
6 private int hour; // 0 - 23
7 private int minute; // 0 - 59
8 private int second; // 0 - 59
9
10 // set a new time value using universal time; throw an
11 // exception if the hour, minute or second is invalid
12 public void setTime(int hour, int minute, int second)
13 {
14 // validate hour, minute and second
15 if (hour < 0 || hour >= 24 || minute < 0 || minute >= 60 ||
16 second < 0 || second >= 60)
17 {
18 throw new IllegalArgumentException(
19 "hour, minute and/or second was out of range");
20 }
21
22 this.hour = hour;
23 this.minute = minute;
24 this.second = second;
25 }
26
27 // convert to String in universal-time format (HH:MM:SS)
28 public String toUniversalString()
29 {
30 return String.format("%02d:%02d:%02d", hour, minute, second);
31 }
32
33 // convert to String in standard-time format (H:MM:SS AM or PM)
34 public String toString()
35 {
36 return String.format("%d:%02d:%02d %s",
37 ((hour == 0 || hour == 12) ? 12 : hour % 12),
38 minute, second, (hour < 12 ? "AM" : "PM"));
39 }
40 } // end class Time1

```

---

**Fig. 8.1** | Time1 class declaration maintains the time in 24-hour format.

### *Default Constructor*

In this example, class `Time1` does *not* declare a constructor, so the compiler supplies a default constructor. Each instance variable implicitly receives the default `int` value. Instance variables also can be initialized when they're declared in the class body, using the same initialization syntax as with a local variable.

### *Method `setTime` and Throwing Exceptions*

Method `setTime` (lines 12–25) is a public method that declares three `int` parameters and uses them to set the time. Lines 15–16 test each argument to determine whether the value is outside the proper range. The hour value must be greater than or equal to 0 and less than

24, because universal-time format represents hours as integers from 0 to 23 (e.g., 1 PM is hour 13 and 11 PM is hour 23; midnight is hour 0 and noon is hour 12). Similarly, both minute and second values must be greater than or equal to 0 and less than 60. For values outside these ranges, `setTime` **throws an exception** of type `IllegalArgumentException` (lines 18–19), which notifies the client code that an invalid argument was passed to the method. As you learned in Section 6.5, you can use `try...catch` to catch exceptions and attempt to recover from them, which we'll do in Fig. 8.2. The class instance creation expression in the **throw statement** (Fig. 8.1; line 18) creates a new object of type `IllegalArgumentException`. The parentheses following the class name indicate a call to the `IllegalArgumentException` constructor. In this case, we call the constructor that allows us to specify a custom error message. After the exception object is created, the `throw` statement immediately terminates method `setTime` and the exception is returned to the calling method that attempted to set the time. If the argument values are all valid, lines 22–24 assign them to the `hour`, `minute` and `second` instance variables.



### Software Engineering Observation 8.1

*For a method like `setTime` in Fig. 8.1, validate all of the method's arguments before using them to set instance variable values to ensure that the object's data is modified only if all the arguments are valid.*

#### Method `toUniversalString`

Method `toUniversalString` (lines 28–31) takes no arguments and returns a `String` in *universal-time format*, consisting of two digits each for the hour, minute and second—recall that you can use the `0` flag in a `printf` format specification (e.g., `%02d`) to display leading zeros for a value that doesn't use all the character positions in the specified field width. For example, if the time were 1:30:07 PM, the method would return `13:30:07`. Line 30 uses static method `format` of class `String` to return a `String` containing the formatted hour, minute and second values, each with two digits and possibly a leading `0` (specified with the `0` flag). Method `format` is similar to method `System.out.printf` except that `format` *returns* a formatted `String` rather than displaying it in a command window. The formatted `String` is returned by method `toUniversalString`.

#### Method `toString`

Method `toString` (lines 34–39) takes no arguments and returns a `String` in *standard-time format*, consisting of the hour, minute and second values separated by colons and followed by AM or PM (e.g., `11:30:17 AM` or `1:27:06 PM`). Like method `toUniversalString`, method `toString` uses static `String` method `format` to format the minute and second as two-digit values, with leading zeros if necessary. Line 37 uses a conditional operator (`?:`) to determine the value for hour in the `String`—if the hour is 0 or 12 (AM or PM), it appears as 12; otherwise, it appears as a value from 1 to 11. The conditional operator in line 30 determines whether AM or PM will be returned as part of the `String`.

Recall all objects in Java have a `toString` method that returns a `String` representation of the object. We chose to return a `String` containing the time in standard-time format. Method `toString` is called *implicitly* whenever a `Time1` object appears in the code where a `String` is needed, such as the value to output with a `%s` format specifier in a call to `System.out.printf`. You may also call `toString` *explicitly* to obtain a `String` representation of a `Time` object.

*Using Class Time1*

Class `Time1Test` (Fig. 8.2) uses class `Time1`. Line 9 declares and creates a `Time1` object `time`. Operator `new` implicitly invokes class `Time1`'s default constructor, because `Time1` does not declare any constructors. To confirm that the `Time1` object was initialized properly, line 12 calls the private method `displayTime` (lines 35–39), which, in turn, calls the `Time1` object's `toUniversalString` and `toString` methods to output the time in universal-time format and standard-time format, respectively. Note that `toString` could have been called implicitly here rather than explicitly. Next, line 16 invokes method `setTime` of the time object to change the time. Then line 17 calls `displayTime` again to output the time in both formats to confirm that it was set correctly.

**Software Engineering Observation 8.2**

*Recall from Chapter 7 that methods declared with access modifier `private` can be called only by other methods of the class in which the private methods are declared. Such methods are commonly referred to as **utility methods** or **helper methods** because they're typically used to support the operation of the class's other methods.*

---

```

1 // Fig. 8.2: Time1Test.java
2 // Time1 object used in an app.
3
4 public class Time1Test
5 {
6 public static void main(String[] args)
7 {
8 // create and initialize a Time1 object
9 Time1 time = new Time1(); // invokes Time1 constructor
10
11 // output string representations of the time
12 displayTime("After time object is created", time);
13 System.out.println();
14
15 // change time and output updated time
16 time.setTime(13, 27, 6);
17 displayTime("After calling setTime", time);
18 System.out.println();
19
20 // attempt to set time with invalid values
21 try
22 {
23 time.setTime(99, 99, 99); // all values out of range
24 }
25 catch (IllegalArgumentException e)
26 {
27 System.out.printf("Exception: %s%n%n", e.getMessage());
28 }
29
30 // display time after attempt to set invalid values
31 displayTime("After calling setTime with invalid values", time);
32 }

```

---

**Fig. 8.2** | Time1 object used in an app. (Part I of 2.)

```

33
34 // displays a Time1 object in 24-hour and 12-hour formats
35 private static void displayTime(String header, Time1 t)
36 {
37 System.out.printf("%s\nUniversal time: %s\nStandard time: %s\n",
38 header, t.toUniversalString(), t.toString());
39 }
40 } // end class Time1Test

```

After time object is created  
 Universal time: 00:00:00  
 Standard time: 12:00:00 AM

After calling setTime  
 Universal time: 13:27:06  
 Standard time: 1:27:06 PM

Exception: hour, minute and/or second was out of range

After calling setTime with invalid values  
 Universal time: 13:27:06  
 Standard time: 1:27:06 PM

**Fig. 8.2** | Time1 object used in an app. (Part 2 of 2.)

### *Calling Time1 Method setTime with Invalid Values*

To illustrate that method `setTime` *validates* its arguments, line 23 calls method `setTime` with *invalid* arguments of 99 for the hour, minute and second. This statement is placed in a try block (lines 21–24) in case `setTime` throws an `IllegalArgumentException`, which it will do since the arguments are all invalid. When this occurs, the exception is caught at lines 25–28, and line 27 displays the exception's error message by calling its `getMessage` method. Line 31 outputs the time again in both formats to confirm that `setTime` did *not* change the time when invalid arguments were supplied.

### *Software Engineering of the Time1 Class Declaration*

Consider several issues of class design with respect to class `Time1`. The instance variables `hour`, `minute` and `second` are each declared `private`. The actual data representation used within the class is of no concern to the class's clients. For example, it would be perfectly reasonable for `Time1` to represent the time internally as the number of seconds since midnight or the number of minutes and seconds since midnight. Clients could use the same `public` methods and get the same results without being aware of this. (Exercise 8.5 asks you to represent the time in class `Time2` of Fig. 8.5 as the number of seconds since midnight and show that indeed no change is visible to the clients of the class.)



### **Software Engineering Observation 8.3**

*Classes simplify programming, because the client can use only a class's public methods. Such methods are usually client oriented rather than implementation oriented. Clients are neither aware of, nor involved in, a class's implementation. Clients generally care about what the class does but not how the class does it.*





#### Software Engineering Observation 8.4

*Interfaces change less frequently than implementations. When an implementation changes, implementation-dependent code must change accordingly. Hiding the implementation reduces the possibility that other program parts will become dependent on class implementation details.*

#### Java SE 8—Date/Time API

This section's example and several of this chapter's later examples demonstrate various class-implementation concepts in classes that represent dates and times. In professional Java development, rather than building your own date and time classes, you'll typically reuse the ones provided by the Java API. Though Java has always had classes for manipulating dates and times, Java SE 8 introduces a new **Date/Time API**—defined by the classes in the package `java.time`—applications built with Java SE 8 should use the Date/Time API's capabilities, rather than those in earlier Java versions. The new API fixes various issues with the older classes and provides more robust, easier-to-use capabilities for manipulating dates, times, time zones, calendars and more. We use some Date/Time API features in Chapter 23. You can learn more about the Date/Time API's classes at:

[download.java.net/jdk8/docs/api/java/time/package-summary.html](http://download.java.net/jdk8/docs/api/java/time/package-summary.html)

## 8.3 Controlling Access to Members

The access modifiers `public` and `private` control access to a class's variables and methods. In Chapter 9, we'll introduce the additional access modifier `protected`. The primary purpose of `public` methods is to present to the class's clients a view of the services the class provides (i.e., the class's **public interface**). Clients need not be concerned with how the class accomplishes its tasks. For this reason, the class's **private variables and private methods** (i.e., its *implementation details*) are *not* accessible to its clients.

Figure 8.3 demonstrates that **private class members** are *not* accessible outside the class. Lines 9–11 attempt to access the private instance variables `hour`, `minute` and `second` of the `Time1` object `time`. When this program is compiled, the compiler generates error messages that these private members are not accessible. This program assumes that the `Time1` class from Fig. 8.1 is used.

---

```

1 // Fig. 8.3: MemberAccessTest.java
2 // Private members of class Time1 are not accessible.
3 public class MemberAccessTest
4 {
5 public static void main(String[] args)
6 {
7 Time1 time = new Time1(); // create and initialize Time1 object
8
9 time.hour = 7; // error: hour has private access in Time1
10 time.minute = 15; // error: minute has private access in Time1
11 time.second = 30; // error: second has private access in Time1
12 }
13 } // end class MemberAccessTest

```

---

**Fig. 8.3** | Private members of class `Time1` are not accessible. (Part 1 of 2.)

```

MemberAccessTest.java:9: hour has private access in Time1
 time.hour = 7; // error: hour has private access in Time1
 ^
MemberAccessTest.java:10: minute has private access in Time1
 time.minute = 15; // error: minute has private access in Time1
 ^
MemberAccessTest.java:11: second has private access in Time1
 time.second = 30; // error: second has private access in Time1
 ^
3 errors

```

**Fig. 8.3** | Private members of class `Time1` are not accessible. (Part 2 of 2.)



### Common Programming Error 8.1

*An attempt by a method that's not a member of a class to access a private member of that class generates a compilation error.*

## 8.4 Referring to the Current Object's Members with the `this` Reference

Every object can access a *reference to itself* with keyword **this** (sometimes called the **this reference**). When an instance method is called for a particular object, the method's body *implicitly* uses keyword `this` to refer to the object's instance variables and other methods. This enables the class's code to know which object should be manipulated. As you'll see in Fig. 8.4, you can also use keyword `this` *explicitly* in an instance method's body. Section 8.5 shows another interesting use of keyword `this`. Section 8.11 explains why keyword `this` cannot be used in a static method.

We now demonstrate implicit and explicit use of the `this` reference (Fig. 8.4). This example is the first in which we declare *two* classes in one file—class `ThisTest` is declared in lines 4–11, and class `SimpleTime` in lines 14–47. We do this to demonstrate that when you compile a `.java` file containing more than one class, the compiler produces a separate class file with the `.class` extension for every compiled class. In this case, two separate files are produced—`SimpleTime.class` and `ThisTest.class`. When one source-code (`.java`) file contains multiple class declarations, the compiler places both class files for those classes in the *same* directory. Note also in Fig. 8.4 that only class `ThisTest` is declared `public`. A source-code file can contain only *one* `public` class—otherwise, a compilation error occurs. *Non-public classes* can be used only by other classes in the *same package*. So, in this example, class `SimpleTime` can be used only by class `ThisTest`.

```

1 // Fig. 8.4: ThisTest.java
2 // this used implicitly and explicitly to refer to members of an object.
3
4 public class ThisTest
5 {
6 public static void main(String[] args)
7 {

```

**Fig. 8.4** | `this` used implicitly and explicitly to refer to members of an object. (Part 1 of 2.)

```

8 SimpleTime time = new SimpleTime(15, 30, 19);
9 System.out.println(time.buildString());
10 }
11 } // end class ThisTest
12
13 // class SimpleTime demonstrates the "this" reference
14 class SimpleTime
15 {
16 private int hour; // 0-23
17 private int minute; // 0-59
18 private int second; // 0-59
19
20 // if the constructor uses parameter names identical to
21 // instance variable names the "this" reference is
22 // required to distinguish between the names
23 public SimpleTime(int hour, int minute, int second)
24 {
25 this.hour = hour; // set "this" object's hour
26 this.minute = minute; // set "this" object's minute
27 this.second = second; // set "this" object's second
28 }
29
30 // use explicit and implicit "this" to call toUniversalString
31 public String buildString()
32 {
33 return String.format("%24s: %s%n%24s: %s",
34 "this.toUniversalString()", this.toUniversalString(),
35 "toUniversalString()", toUniversalString());
36 }
37
38 // convert to String in universal-time format (HH:MM:SS)
39 public String toUniversalString()
40 {
41 // "this" is not required here to access instance variables,
42 // because method does not have local variables with same
43 // names as instance variables
44 return String.format("%02d:%02d:%02d",
45 this.hour, this.minute, this.second);
46 }
47 } // end class SimpleTime

```

```

this.toUniversalString(): 15:30:19
toUniversalString(): 15:30:19

```

**Fig. 8.4** | `this` used implicitly and explicitly to refer to members of an object. (Part 2 of 2.)

Class `SimpleTime` (lines 14–47) declares three private instance variables—`hour`, `minute` and `second` (lines 16–18). The class's constructor (lines 23–28) receives three `int` arguments to initialize a `SimpleTime` object. Once again, we used parameter names for the constructor (line 23) that are *identical* to the class's instance-variable names (lines 16–18), so we use the `this` reference to refer to the instance variables in lines 25–27.

**Error-Prevention Tip 8.1**

*Most IDEs will issue a warning if you say `x = x`; instead of `this.x = x`. The statement `x = x`; is often called a no-op (no operation).*

Method `buildString` (lines 31–36) returns a `String` created by a statement that uses the `this` reference explicitly and implicitly. Line 34 uses it *explicitly* to call method `toUniversalString`. Line 35 uses it *implicitly* to call the same method. Both lines perform the same task. You typically will not use `this` explicitly to reference other methods within the current object. Also, line 45 in method `toUniversalString` explicitly uses the `this` reference to access each instance variable. This is *not* necessary here, because the method does *not* have any local variables that shadow the instance variables of the class.

**Performance Tip 8.1**

*Java conserves storage by maintaining only one copy of each method per class—this method is invoked by every object of the class. Each object, on the other hand, has its own copy of the class's instance variables. Each method of the class implicitly uses `this` to determine the specific object of the class to manipulate.*

Class `ThisTest`'s main method (lines 6–10) demonstrates class `SimpleTime`. Line 8 creates an instance of class `SimpleTime` and invokes its constructor. Line 9 invokes the object's `buildString` method, then displays the results.

## 8.5 Time Class Case Study: Overloaded Constructors

As you know, you can declare your own constructor to specify how objects of a class should be initialized. Next, we demonstrate a class with several **overloaded constructors** that enable objects of that class to be initialized in different ways. To overload constructors, simply provide multiple constructor declarations with different signatures.

### *Class Time2 with Overloaded Constructors*

The `Time1` class's default constructor in Fig. 8.1 initialized `hour`, `minute` and `second` to their default 0 values (i.e., midnight in universal time). The default constructor does not enable the class's clients to initialize the time with nonzero values. Class `Time2` (Fig. 8.5) contains five overloaded constructors that provide convenient ways to initialize objects. In this program, four of the constructors invoke a fifth, which in turn ensures that the value supplied for `hour` is in the range 0 to 23, and the values for `minute` and `second` are each in the range 0 to 59. The compiler invokes the appropriate constructor by matching the number, types and order of the types of the arguments specified in the constructor call with the number, types and order of the types of the parameters specified in each constructor declaration. Class `Time2` also provides *set* and *get* methods for each instance variable.

---

```

1 // Fig. 8.5: Time2.java
2 // Time2 class declaration with overloaded constructors.
3
4 public class Time2
5 {

```

---

**Fig. 8.5** | `Time2` class with overloaded constructors. (Part 1 of 4.)

```
6 private int hour; // 0 - 23
7 private int minute; // 0 - 59
8 private int second; // 0 - 59
9
10 // Time2 no-argument constructor:
11 // initializes each instance variable to zero
12 public Time2()
13 {
14 this(0, 0, 0); // invoke constructor with three arguments
15 }
16
17 // Time2 constructor: hour supplied, minute and second defaulted to 0
18 public Time2(int hour)
19 {
20 this(hour, 0, 0); // invoke constructor with three arguments
21 }
22
23 // Time2 constructor: hour and minute supplied, second defaulted to 0
24 public Time2(int hour, int minute)
25 {
26 this(hour, minute, 0); // invoke constructor with three arguments
27 }
28
29 // Time2 constructor: hour, minute and second supplied
30 public Time2(int hour, int minute, int second)
31 {
32 if (hour < 0 || hour >= 24)
33 throw new IllegalArgumentException("hour must be 0-23");
34
35 if (minute < 0 || minute >= 60)
36 throw new IllegalArgumentException("minute must be 0-59");
37
38 if (second < 0 || second >= 60)
39 throw new IllegalArgumentException("second must be 0-59");
40
41 this.hour = hour;
42 this.minute = minute;
43 this.second = second;
44 }
45
46 // Time2 constructor: another Time2 object supplied
47 public Time2(Time2 time)
48 {
49 // invoke constructor with three arguments
50 this(time.getHour(), time.getMinute(), time.getSecond());
51 }
52
53 // Set Methods
54 // set a new time value using universal time;
55 // validate the data
56 public void setTime(int hour, int minute, int second)
57 {
```

**Fig. 8.5** | Time2 class with overloaded constructors. (Part 2 of 4.)

---

```
58 if (hour < 0 || hour >= 24)
59 throw new IllegalArgumentException("hour must be 0-23");
60
61 if (minute < 0 || minute >= 60)
62 throw new IllegalArgumentException("minute must be 0-59");
63
64 if (second < 0 || second >= 60)
65 throw new IllegalArgumentException("second must be 0-59");
66
67 this.hour = hour;
68 this.minute = minute;
69 this.second = second;
70 }
71
72 // validate and set hour
73 public void setHour(int hour)
74 {
75 if (hour < 0 || hour >= 24)
76 throw new IllegalArgumentException("hour must be 0-23");
77
78 this.hour = hour;
79 }
80
81 // validate and set minute
82 public void setMinute(int minute)
83 {
84 if (minute < 0 && minute >= 60)
85 throw new IllegalArgumentException("minute must be 0-59");
86
87 this.minute = minute;
88 }
89
90 // validate and set second
91 public void setSecond(int second)
92 {
93 if (second >= 0 && second < 60)
94 throw new IllegalArgumentException("second must be 0-59");
95
96 this.second = second;
97 }
98
99 // Get Methods
100 // get hour value
101 public int getHour()
102 {
103 return hour;
104 }
105
106 // get minute value
107 public int getMinute()
108 {
109 return minute;
110 }
```

---

**Fig. 8.5** | Time2 class with overloaded constructors. (Part 3 of 4.)

```

111
112 // get second value
113 public int getSecond()
114 {
115 return second;
116 }
117
118 // convert to String in universal-time format (HH:MM:SS)
119 public String toUniversalString()
120 {
121 return String.format(
122 "%02d:%02d:%02d", getHour(), getMinute(), getSecond());
123 }
124
125 // convert to String in standard-time format (H:MM:SS AM or PM)
126 public String toString()
127 {
128 return String.format("%d:%02d:%02d %s",
129 ((getHour() == 0 || getHour() == 12) ? 12 : getHour() % 12),
130 getMinute(), getSecond(), (getHour() < 12 ? "AM" : "PM"));
131 }
132 } // end class Time2

```

**Fig. 8.5** | Time2 class with overloaded constructors. (Part 4 of 4.)

### *Class Time2's Constructors—Calling One Constructor from Another via this*

Lines 12–15 declare a so-called **no-argument constructor** that's invoked without arguments. Once you declare any constructors in a class, the compiler will *not* provide a *default constructor*. This no-argument constructor ensures that class Time2's clients can create Time2 objects with default values. Such a constructor simply initializes the object as specified in the constructor's body. In the body, we introduce a use of `this` that's allowed only as the *first* statement in a constructor's body. Line 14 uses `this` in method-call syntax to invoke the Time2 constructor that takes three parameters (lines 30–44) with values of 0 for the hour, minute and second. Using `this` as shown here is a popular way to *reuse* initialization code provided by another of the class's constructors rather than defining similar code in the no-argument constructor's body. We use this syntax in four of the five Time2 constructors to make the class easier to maintain and modify. If we need to change how objects of class Time2 are initialized, only the constructor that the class's other constructors call will need to be modified.



### **Common Programming Error 8.2**

*It's a compilation error when `this` is used in a constructor's body to call another of the class's constructors if that call is not the first statement in the constructor. It's also a compilation error when a method attempts to invoke a constructor directly via `this`.*

Lines 18–21 declare a Time2 constructor with a single `int` parameter representing the hour, which is passed with 0 for the minute and second to the constructor at lines 30–44. Lines 24–27 declare a Time2 constructor that receives two `int` parameters representing the hour and minute, which are passed with 0 for the second to the constructor at lines 30–44. Like the no-argument constructor, each of these constructors invokes the constructor at lines 30–44 to minimize code duplication. Lines 30–44 declare the Time2 constructor

that receives three `int` parameters representing the hour, minute and second. This constructor validates and initializes the instance variables.

Lines 47–51 declare a `Time2` constructor that receives a reference to another `Time2` object. The values from the `Time2` argument are passed to the three-argument constructor at lines 30–44 to initialize the hour, minute and second. Line 50 could have directly accessed the hour, minute and second values of the argument `time` with the expressions `time.hour`, `time.minute` and `time.second`—even though hour, minute and second are declared as private variables of class `Time2`. This is due to a special relationship between objects of the same class. We’ll see in a moment why it’s preferable to use the *get* methods.



### Software Engineering Observation 8.5

*When one object of a class has a reference to another object of the same class, the first object can access all the second object’s data and methods (including those that are private).*

#### Class `Time2`’s *setTime* Method

Method `setTime` (lines 56–70) throws an `IllegalArgumentException` (lines 59, 62 and 65) if any the method’s arguments is out of range. Otherwise, it sets `Time2`’s instance variables to the argument values (lines 67–69).

#### Notes Regarding Class `Time2`’s *set* and *get* Methods and Constructors

`Time2`’s *get* methods are called throughout the class. In particular, methods `toUniversalString` and `toString` call methods `getHour`, `getMinute` and `getSecond` in line 122 and lines 129–130, respectively. In each case, these methods could have accessed the class’s private data directly without calling the *get* methods. However, consider changing the representation of the time from three `int` values (requiring 12 bytes of memory) to a single `int` value representing the total number of seconds that have elapsed since midnight (requiring only four bytes of memory). If we made such a change, only the bodies of the methods that access the private data directly would need to change—in particular, the three-argument constructor, the `setTime` method and the individual *set* and *get* methods for the hour, minute and second. There would be no need to modify the bodies of methods `toUniversalString` or `toString` because they do *not* access the data directly. Designing the class in this manner reduces the likelihood of programming errors when altering the class’s implementation.

Similarly, each `Time2` constructor could include a copy of the appropriate statements from the three-argument constructor. Doing so may be slightly more efficient, because the extra constructor calls are eliminated. But, *duplicating* statements makes changing the class’s internal data representation more difficult. Having the `Time2` constructors call the constructor with three arguments requires that any changes to the implementation of the three-argument constructor be made only once. Also, the compiler can optimize programs by removing calls to simple methods and replacing them with the expanded code of their declarations—a technique known as **inlining the code**, which improves program performance.

#### Using Class `Time2`’s Overloaded Constructors

Class `Time2Test` (Fig. 8.6) invokes the overloaded `Time2` constructors (lines 8–12 and 24). Line 8 invokes the `Time2` no-argument constructor. Lines 9–12 demonstrate passing arguments to the other `Time2` constructors. Line 9 invokes the single-argument constructor that receives an `int` at lines 18–21 of Fig. 8.5. Line 10 invokes the two-argument constructor at lines 24–27 of Fig. 8.5. Line 11 invokes the three-argument constructor at lines 30–44 of



Fig. 8.5. Line 12 invokes the single-argument constructor that takes a `Time2` at lines 47–51 of Fig. 8.5. Next, the app displays the `String` representations of each `Time2` object to confirm that it was initialized properly (lines 15–19). Line 24 attempts to initialize `t6` by creating a new `Time2` object and passing three *invalid* values to the constructor. When the constructor attempts to use the invalid hour value to initialize the object's hour, an `IllegalArgumentException` occurs. We catch this exception at line 26 and display its error message, which results in the last line of the output.

```

1 // Fig. 8.6: Time2Test.java
2 // Overloaded constructors used to initialize Time2 objects.
3
4 public class Time2Test
5 {
6 public static void main(String[] args)
7 {
8 Time2 t1 = new Time2(); // 00:00:00
9 Time2 t2 = new Time2(2); // 02:00:00
10 Time2 t3 = new Time2(21, 34); // 21:34:00
11 Time2 t4 = new Time2(12, 25, 42); // 12:25:42
12 Time2 t5 = new Time2(t4); // 12:25:42
13
14 System.out.println("Constructed with:");
15 displayTime("t1: all default arguments", t1);
16 displayTime("t2: hour specified; default minute and second", t2);
17 displayTime("t3: hour and minute specified; default second", t3);
18 displayTime("t4: hour, minute and second specified", t4);
19 displayTime("t5: Time2 object t4 specified", t5);
20
21 // attempt to initialize t6 with invalid values
22 try
23 {
24 Time2 t6 = new Time2(27, 74, 99); // invalid values
25 }
26 catch (IllegalArgumentException e)
27 {
28 System.out.printf("%nException while initializing t6: %s%n",
29 e.getMessage());
30 }
31 }
32
33 // displays a Time2 object in 24-hour and 12-hour formats
34 private static void displayTime(String header, Time2 t)
35 {
36 System.out.printf("%s%n %s%n %s%n",
37 header, t.toUniversalString(), t.toString());
38 }
39 } // end class Time2Test

```

```

Constructed with:
t1: all default arguments
 00:00:00
 12:00:00 AM

```

**Fig. 8.6** | Overloaded constructors used to initialize `Time2` objects. (Part I of 2.)

```

t2: hour specified; default minute and second
 02:00:00
 2:00:00 AM
t3: hour and minute specified; default second
 21:34:00
 9:34:00 PM
t4: hour, minute and second specified
 12:25:42
 12:25:42 PM
t5: Time2 object t4 specified
 12:25:42
 12:25:42 PM
Exception while initializing t6: hour must be 0-23

```

**Fig. 8.6** | Overloaded constructors used to initialize Time2 objects. (Part 2 of 2.)

## 8.6 Default and No-Argument Constructors

Every class *must* have at least *one* constructor. If you do not provide any in a class's declaration, the compiler creates a *default constructor* that takes *no* arguments when it's invoked. The default constructor initializes the instance variables to the initial values specified in their declarations or to their default values (zero for primitive numeric types, `false` for boolean values and `null` for references). In Section 9.4.1, you'll learn that the default constructor also performs another task.

Recall that if your class declares constructors, the compiler will *not* create a default constructor. In this case, you must declare a no-argument constructor if default initialization is required. Like a default constructor, a no-argument constructor is invoked with empty parentheses. The `Time2` no-argument constructor (lines 12–15 of Fig. 8.5) explicitly initializes a `Time2` object by passing to the three-argument constructor 0 for each parameter. Since 0 is the default value for `int` instance variables, the no-argument constructor in this example could actually be declared with an empty body. In this case, each instance variable would receive its default value when the no-argument constructor is called. If we omit the no-argument constructor, clients of this class would not be able to create a `Time2` object with the expression `new Time2()`.



### Error-Prevention Tip 8.2

*Ensure that you do not include a return type in a constructor definition. Java allows other methods of the class besides its constructors to have the same name as the class and to specify return types. Such methods are not constructors and will not be called when an object of the class is instantiated.*



### Common Programming Error 8.3

*A compilation error occurs if a program attempts to initialize an object of a class by passing the wrong number or types of arguments to the class's constructor.*

## 8.7 Notes on Set and Get Methods

As you know, a class's private fields can be manipulated *only* by its methods. A typical manipulation might be the adjustment of a customer's bank balance (e.g., a private in-

stance variable of a class `BankAccount`) by a method `computeInterest`. *Set* methods are also commonly called **mutator methods**, because they typically *change* an object's state—i.e., *modify* the values of instance variables. *Get* methods are also commonly called **accessor methods** or **query methods**.

### Set and Get Methods vs. *public* Data

It would seem that providing *set* and *get* capabilities is essentially the same as making a class's instance variables `public`. This is one of the subtleties that makes Java so desirable for software engineering. A `public` instance variable can be read or written by any method that has a reference to an object containing that variable. If an instance variable is declared `private`, a `public` *get* method certainly allows other methods to access it, but the *get* method can *control* how the client can access it. For example, a *get* method might control the format of the data it returns, shielding the client code from the actual data representation. A `public` *set* method can—and should—carefully scrutinize attempts to modify the variable's value and throw an exception if necessary. For example, attempts to *set* the day of the month to 37 or a person's weight to a negative value should be rejected. Thus, although *set* and *get* methods provide access to `private` data, the access is restricted by the implementation of the methods. This helps promote good software engineering.



#### Software Engineering Observation 8.6

*Classes should never have public nonconstant data, but declaring data `public static final` enables you to make constants available to clients of your class. For example, class `Math` offers `public static final` constants `Math.E` and `Math.PI`.*



#### Error-Prevention Tip 8.3

*Do not provide `public static final` constants if the constants' values are likely to change in future versions of your software.*

### Validity Checking in Set Methods

The benefits of data integrity do not follow automatically simply because instance variables are declared `private`—you must provide validity checking. A class's *set* methods could determine that attempts were made to assign invalid data to objects of the class. Typically *set* methods have `void` return type and use exception handling to indicate attempts to assign invalid data. We discuss exception handling in detail in Chapter 11.



#### Software Engineering Observation 8.7

*When appropriate, provide public methods to change and retrieve the values of private instance variables. This architecture helps hide the implementation of a class from its clients, which improves program modifiability.*



#### Error-Prevention Tip 8.4

*Using *set* and *get* methods helps you create classes that are easier to debug and maintain. If only one method performs a particular task, such as setting an instance variable in an object, it's easier to debug and maintain the class. If the instance variable is not being set properly, the code that actually modifies instance variable is localized to one *set* method. Your debugging efforts can be focused on that one method.*

*Predicate Methods*

Another common use for accessor methods is to test whether a condition is *true* or *false*—such methods are often called **predicate methods**. An example would be class `ArrayList`'s `isEmpty` method, which returns `true` if the `ArrayList` is empty and `false` otherwise. A program might test `isEmpty` before attempting to read another item from an `ArrayList`.

## 8.8 Composition

A class can have references to objects of other classes as members. This is called **composition** and is sometimes referred to as a *has-a relationship*. For example, an `AlarmClock` object needs to know the current time *and* the time when it's supposed to sound its alarm, so it's reasonable to include *two* references to `Time` objects in an `AlarmClock` object. A car *has-a* steering wheel, a break pedal and an accelerator pedal.

*Class Date*

This composition example contains classes `Date` (Fig. 8.7), `Employee` (Fig. 8.8) and `EmployeeTest` (Fig. 8.9). Class `Date` (Fig. 8.7) declares instance variables `month`, `day` and `year` (lines 6–8) to represent a date. The constructor receives three `int` parameters. Lines 17–19 validate the month—if it's out-of-range, lines 18–19 throw an exception. Lines 22–25 validate the day. If the day is incorrect based on the number of days in the particular month (except February 29th which requires special testing for leap years), lines 24–25 throw an exception. Lines 28–31 perform the leap year testing for February. If the month is February and the day is 29 and the year is not a leap year, lines 30–31 throw an exception. If no exceptions are thrown, then lines 33–35 initialize the `Date`'s instance variables and lines 38–38 output the `this` reference as a `String`. Since `this` is a reference to the current `Date` object, the object's `toString` method (lines 42–45) is called *implicitly* to obtain the object's `String` representation. In this example, we assume that the value for `year` is correct—an industrial-strength `Date` class should also validate the year.

---

```

1 // Fig. 8.7: Date.java
2 // Date class declaration.
3
4 public class Date
5 {
6 private int month; // 1-12
7 private int day; // 1-31 based on month
8 private int year; // any year
9
10 private static final int[] daysPerMonth =
11 { 0, 31, 28, 31, 30, 31, 30, 31, 31, 30, 31, 30, 31 };
12
13 // constructor: confirm proper value for month and day given the year
14 public Date(int month, int day, int year)
15 {
16 // check if month in range
17 if (month <= 0 || month > 12)
18 throw new IllegalArgumentException(
19 "month (" + month + ") must be 1-12");

```

---

**Fig. 8.7** | Date class declaration. (Part 1 of 2.)

---

```

20
21 // check if day in range for month
22 if (day <= 0 ||
23 (day > daysPerMonth[month] && !(month == 2 && day == 29)))
24 throw new IllegalArgumentException("day (" + day +
25 ") out-of-range for the specified month and year");
26
27 // check for leap year if month is 2 and day is 29
28 if (month == 2 && day == 29 && !(year % 400 == 0 ||
29 (year % 4 == 0 && year % 100 != 0)))
30 throw new IllegalArgumentException("day (" + day +
31 ") out-of-range for the specified month and year");
32
33 this.month = month;
34 this.day = day;
35 this.year = year;
36
37 System.out.printf(
38 "Date object constructor for date %s\n", this);
39 }
40
41 // return a String of the form month/day/year
42 public String toString()
43 {
44 return String.format("%d/%d/%d", month, day, year);
45 }
46 } // end class Date

```

---

**Fig. 8.7** | Date class declaration. (Part 2 of 2.)

### *Class Employee*

Class `Employee` (Fig. 8.8) has instance variables `firstName`, `lastName`, `birthDate` and `hireDate`. Members `firstName` and `lastName` are references to `String` objects. Members `birthDate` and `hireDate` are references to `Date` objects. This demonstrates that a class can have as instance variables references to objects of other classes. The `Employee` constructor (lines 12–19) takes four parameters representing the first name, last name, birth date and hire date. The objects referenced by the parameters are assigned to the `Employee` object's instance variables. When class `Employee`'s `toString` method is called, it returns a `String` containing the employee's name and the `String` representations of the two `Date` objects. Each of these `Strings` is obtained with an *implicit* call to the `Date` class's `toString` method.

---

```

1 // Fig. 8.8: Employee.java
2 // Employee class with references to other objects.
3
4 public class Employee
5 {
6 private String firstName;
7 private String lastName;
8 private Date birthDate;
9 private Date hireDate;

```

---

**Fig. 8.8** | `Employee` class with references to other objects. (Part 1 of 2.)

---

```

10
11 // constructor to initialize name, birth date and hire date
12 public Employee(String firstName, String lastName, Date birthDate,
13 Date hireDate)
14 {
15 this.firstName = firstName;
16 this.lastName = lastName;
17 this.birthDate = birthDate;
18 this.hireDate = hireDate;
19 }
20
21 // convert Employee to String format
22 public String toString()
23 {
24 return String.format("%s, %s Hired: %s Birthday: %s",
25 lastName, firstName, hireDate, birthDate);
26 }
27 } // end class Employee

```

---

**Fig. 8.8** | Employee class with references to other objects. (Part 2 of 2.)

### *Class EmployeeTest*

Class `EmployeeTest` (Fig. 8.9) creates two `Date` objects to represent an `Employee`'s birthday and hire date, respectively. Line 10 creates an `Employee` and initializes its instance variables by passing to the constructor two `Strings` (representing the `Employee`'s first and last names) and two `Date` objects (representing the birthday and hire date). Line 12 *implicitly* invokes the `Employee`'s `toString` method to display the values of its instance variables and demonstrate that the object was initialized properly.

---

```

1 // Fig. 8.9: EmployeeTest.java
2 // Composition demonstration.
3
4 public class EmployeeTest
5 {
6 public static void main(String[] args)
7 {
8 Date birth = new Date(7, 24, 1949);
9 Date hire = new Date(3, 12, 1988);
10 Employee employee = new Employee("Bob", "Blue", birth, hire);
11
12 System.out.println(employee);
13 }
14 } // end class EmployeeTest

```

---

```

Date object constructor for date 7/24/1949
Date object constructor for date 3/12/1988
Blue, Bob Hired: 3/12/1988 Birthday: 7/24/1949

```

**Fig. 8.9** | Composition demonstration.

## 8.9 enum Types

In Fig. 5.8, we introduced the basic enum type, which defines a set of constants represented as unique identifiers. In that program the enum constants represented the game's status. In this section we discuss the relationship between enum types and classes. Like classes, all enum types are *reference* types. An enum type is declared with an **enum declaration**, which is a comma-separated list of *enum constants*—the declaration may optionally include other components of traditional classes, such as constructors, fields and methods (as you'll see momentarily). Each enum declaration declares an enum class with the following restrictions:

1. enum constants are *implicitly* final.
2. enum constants are *implicitly* static.
3. Any attempt to create an object of an enum type with operator new results in a compilation error.

The enum constants can be used anywhere constants can be used, such as in the case labels of switch statements and to control enhanced for statements.

### *Declaring Instance Variables, a Constructor and Methods in an enum Type*

Figure 8.10 demonstrates instance variables, a constructor and methods in an enum type. The enum declaration (lines 5–37) contains two parts—the enum constants and the other members of the enum type. The first part (lines 8–13) declares six constants. Each is optionally followed by arguments that are passed to the **enum constructor** (lines 20–24). Like the constructors you've seen in classes, an enum constructor can specify any number of parameters and can be overloaded. In this example, the enum constructor requires two String parameters. To properly initialize each enum constant, we follow it with parentheses containing two String arguments. The second part (lines 16–36) declares the other members of the enum type—two instance variables (lines 16–17), a constructor (lines 20–24) and two methods (lines 27–30 and 33–36).

Lines 16–17 declare the instance variables `title` and `copyrightYear`. Each enum constant in enum type `Book` is actually an object of enum type `Book` that has its own copy of instance variables `title` and `copyrightYear`. The constructor (lines 20–24) takes two String parameters, one that specifies the book's title and one that specifies its copyright year. Lines 22–23 assign these parameters to the instance variables. Lines 27–36 declare methods, which return the book title and copyright year, respectively.

---

```

1 // Fig. 8.10: Book.java
2 // Declaring an enum type with a constructor and explicit instance fields
3 // and accessors for these fields
4
5 public enum Book
6 {
7 // declare constants of enum type
8 JHTP("Java How to Program", "2015"),
9 CHTP("C How to Program", "2013"),
10 IW3HTP("Internet & World Wide Web How to Program", "2012"),

```

---

**Fig. 8.10** | Declaring an enum type with a constructor and explicit instance fields and accessors for these fields. (Part 1 of 2.)

---

```

11 CPPHTP("C++ How to Program", "2014"),
12 VBHTP("Visual Basic How to Program", "2014"),
13 CSHARPHTP("Visual C# How to Program", "2014");
14
15 // instance fields
16 private final String title; // book title
17 private final String copyrightYear; // copyright year
18
19 // enum constructor
20 Book(String title, String copyrightYear)
21 {
22 this.title = title;
23 this.copyrightYear = copyrightYear;
24 }
25
26 // accessor for field title
27 public String getTitle()
28 {
29 return title;
30 }
31
32 // accessor for field copyrightYear
33 public String getCopyrightYear()
34 {
35 return copyrightYear;
36 }
37 } // end enum Book

```

---

**Fig. 8.10** | Declaring an enum type with a constructor and explicit instance fields and accessors for these fields. (Part 2 of 2.)

### *Using enum type Book*

Figure 8.11 tests the enum type `Book` and illustrates how to iterate through a range of enum constants. For every enum, the compiler generates the static method `values` (called in line 12) that returns an array of the enum's constants in the order they were declared. Lines 12–14 use the enhanced for statement to display all the constants declared in the enum `Book`. Line 14 invokes the enum `Book`'s `getTitle` and `getCopyrightYear` methods to get the title and copyright year associated with the constant. When an enum constant is converted to a `String` (e.g., `book` in line 13), the constant's identifier is used as the `String` representation (e.g., `JHTP` for the first enum constant).

---

```

1 // Fig. 8.11: EnumTest.java
2 // Testing enum type Book.
3 import java.util.EnumSet;
4
5 public class EnumTest
6 {
7 public static void main(String[] args)
8 {

```

---

**Fig. 8.11** | Testing enum type `Book`. (Part 1 of 2.)



```

9 System.out.println("All books:");
10
11 // print all books in enum Book
12 for (Book book : Book.values())
13 System.out.printf("%-10s%-45s%s%n", book,
14 book.getTitle(), book.getCopyrightYear());
15
16 System.out.printf("%nDisplay a range of enum constants:%n");
17
18 // print first four books
19 for (Book book : EnumSet.range(Book.JHTP, Book.CPPHTP))
20 System.out.printf("%-10s%-45s%s%n", book,
21 book.getTitle(), book.getCopyrightYear());
22 }
23 } // end class EnumTest

```

```

All books:
JHTP Java How to Program 2015
CHTP C How to Program 2013
IW3HTP Internet & World Wide Web How to Program 2012
CPPHTP C++ How to Program 2014
VBHTP Visual Basic How to Program 2014
CSHARPHP Visual C# How to Program 2014

Display a range of enum constants:
JHTP Java How to Program 2015
CHTP C How to Program 2013
IW3HTP Internet & World Wide Web How to Program 2012
CPPHTP C++ How to Program 2014

```

**Fig. 8.11** | Testing enum type Book. (Part 2 of 2.)

Lines 19–21 use the static method **range** of class **EnumSet** (declared in package `java.util`) to display a range of the enum **Book**’s constants. Method **range** takes two parameters—the first and the last enum constants in the range—and returns an **EnumSet** that contains all the constants between these two constants, inclusive. For example, the expression `EnumSet.range(Book.JHTP, Book.CPPHTP)` returns an **EnumSet** containing `Book.JHTP`, `Book.CHTP`, `Book.IW3HTP` and `Book.CPPHTP`. The enhanced **for** statement can be used with an **EnumSet** just as it can with an array, so lines 12–14 use it to display the title and copyright year of every book in the **EnumSet**. Class **EnumSet** provides several other static methods for creating sets of enum constants from the same enum type.



#### Common Programming Error 8.4

*In an enum declaration, it’s a syntax error to declare enum constants after the enum type’s constructors, fields and methods.*

## 8.10 Garbage Collection

Every object uses system resources, such as memory. We need a disciplined way to give resources back to the system when they’re no longer needed; otherwise, “resource leaks” might occur that would prevent resources from being reused by your program or possibly

by other programs. The JVM performs automatic **garbage collection** to reclaim the *memory* occupied by objects that are no longer used. When there are *no more references* to an object, the object is *eligible* to be collected. Collection typically occurs when the JVM executes its **garbage collector**, which may not happen for a while, or even at all before a program terminates. So, memory leaks that are common in other languages like C and C++ (because memory is *not* automatically reclaimed in those languages) are *less* likely in Java, but some can still happen in subtle ways. Resource leaks other than memory leaks can also occur. For example, an app may open a file on disk to modify its contents—if the app does not close the file, it must terminate before any other app can use the file.

### *A Note about Class `Object`'s `finalize` Method*

Every class in Java has the methods of class `Object` (package `java.lang`), one of which is method **`finalize`**. (You'll learn more about class `Object` in Chapter 9.) You should *never* use method `finalize`, because it can cause many problems and there's uncertainty as to whether it will *ever* get called before a program terminates.

The original intent of `finalize` was to allow the garbage collector to perform **termination housekeeping** on an object just before reclaiming the object's memory. Now, it's considered better practice for any class that uses system resources—such as files on disk—to provide a method that programmers can call to release resources when they're no longer needed in a program. `AutoCloseable` objects reduce the likelihood of resource leaks when you use them with the `try-with-resources` statement. As its name implies, an `AutoCloseable` object is closed automatically, once a `try-with-resources` statement finishes using the object. We discuss this in more detail in Section 11.12.



### **Software Engineering Observation 8.8**

*Many Java API classes (e.g., class `Scanner` and classes that read files from or write files to disk) provide `close` or `dispose` methods that programmers can call to release resources when they're no longer needed in a program.*

## **8.11 static Class Members**

Every object has its own copy of all the instance variables of the class. In certain cases, only one copy of a particular variable should be *shared* by all objects of a class. A **static field**—called a **class variable**—is used in such cases. A static variable represents **classwide information**—all objects of the class share the *same* piece of data. The declaration of a static variable begins with the keyword `static`.

### *Motivating static*

Let's motivate static data with an example. Suppose that we have a video game with Martians and other space creatures. Each Martian tends to be brave and willing to attack other space creatures when the Martian is aware that at least four other Martians are present. If fewer than five Martians are present, each of them becomes cowardly. Thus, each Martian needs to know the `martianCount`. We could endow class `Martian` with `martianCount` as an *instance variable*. If we do this, then every Martian will have a *separate copy* of the instance variable, and every time we create a new Martian, we'll have to update the instance variable `martianCount` in every Martian object. This wastes space with the redundant copies, wastes time in updating the separate copies and is error prone. Instead, we declare `mar-`

tianCount to be static, making martianCount classwide data. Every Martian can see the martianCount as if it were an instance variable of class Martian, but only *one* copy of the static martianCount is maintained. This saves space. We save time by having the Martian constructor increment the static martianCount—there's only one copy, so we do not have to increment separate copies for each Martian object.



### Software Engineering Observation 8.9

*Use a static variable when all objects of a class must use the same copy of the variable.*

### Class Scope

Static variables have *class scope*—they can be used in all of the class's methods. We can access a class's public static members through a reference to any object of the class, or by qualifying the member name with the class name and a dot (.), as in `Math.random()`. A class's private static class members can be accessed by client code only through methods of the class. Actually, *static class members exist even when no objects of the class exist*—they're available as soon as the class is loaded into memory at execution time. To access a public static member when no objects of the class exist (and even when they do), prefix the class name and a dot (.) to the static member, as in `Math.PI`. To access a private static member when no objects of the class exist, provide a public static method and call it by qualifying its name with the class name and a dot.



### Software Engineering Observation 8.10

*Static class variables and methods exist, and can be used, even if no objects of that class have been instantiated.*

### static Methods Cannot Directly Access Instance Variables and Instance Methods

A static method *cannot* access a class's instance variables and instance methods, because a static method can be called even when no objects of the class have been instantiated. For the same reason, the `this` reference *cannot* be used in a static method. The `this` reference must refer to a specific object of the class, and when a static method is called, there might not be any objects of its class in memory.



### Common Programming Error 8.5

*A compilation error occurs if a static method calls an instance method in the same class by using only the method name. Similarly, a compilation error occurs if a static method attempts to access an instance variable in the same class by using only the variable name.*



### Common Programming Error 8.6

*Referring to `this` in a static method is a compilation error.*

### Tracking the Number of Employee Objects That Have Been Created

Our next program declares two classes—`Employee` (Fig. 8.12) and `EmployeeTest` (Fig. 8.13). Class `Employee` declares private static variable `count` (Fig. 8.12, line 7) and public static method `getCount` (lines 36–39). The static variable `count` maintains a count of the number of objects of class `Employee` that have been created so far. This class

variable is initialized to zero in line 7. If a static variable is *not* initialized, the compiler assigns it a default value—in this case 0, the default value for type `int`.

---

```

1 // Fig. 8.12: Employee.java
2 // static variable used to maintain a count of the number of
3 // Employee objects in memory.
4
5 public class Employee
6 {
7 private static int count = 0; // number of Employees created
8 private String firstName;
9 private String lastName;
10
11 // initialize Employee, add 1 to static count and
12 // output String indicating that constructor was called
13 public Employee(String firstName, String lastName)
14 {
15 this.firstName = firstName;
16 this.lastName = lastName;
17
18 ++count; // increment static count of employees
19 System.out.printf("Employee constructor: %s %s; count = %d\n",
20 firstName, lastName, count);
21 }
22
23 // get first name
24 public String getFirstName()
25 {
26 return firstName;
27 }
28
29 // get last name
30 public String getLastName()
31 {
32 return lastName;
33 }
34
35 // static method to get static count value
36 public static int getCount()
37 {
38 return count;
39 }
40 } // end class Employee

```

---

**Fig. 8.12** | static variable used to maintain a count of the number of `Employee` objects in memory.

When `Employee` objects exist, variable `count` can be used in any method of an `Employee` object—this example increments `count` in the constructor (line 18). The `public` static method `getCount` (lines 36–39) returns the number of `Employee` objects that have been created so far. When no objects of class `Employee` exist, client code can access variable `count` by calling method `getCount` via the class name, as in `Employee.getCount()`. When objects exist, method `getCount` can also be called via any reference to an `Employee` object.



### Good Programming Practice 8.1

*Invoke every static method by using the class name and a dot (.) to emphasize that the method being called is a static method.*

#### Class *EmployeeTest*

*EmployeeTest* method *main* (Fig. 8.13) instantiates two *Employee* objects (lines 13–14). When each *Employee* object's constructor is invoked, lines 15–16 of Fig. 8.12 assign the *Employee*'s first name and last name to instance variables *firstName* and *lastName*. These two statements do *not* make copies of the original *String* arguments. Actually, *String* objects in Java are **immutable**—they cannot be modified after they're created. Therefore, it's safe to have *many* references to one *String* object. This is not normally the case for objects of most other classes in Java. If *String* objects are immutable, you might wonder why we're able to use operators *+* and *+=* to concatenate *String* objects. *String*-concatenation actually results in a *new* *String* object containing the concatenated values. The original *String* objects are *not* modified.

```

1 // Fig. 8.13: EmployeeTest.java
2 // static member demonstration.
3
4 public class EmployeeTest
5 {
6 public static void main(String[] args)
7 {
8 // show that count is 0 before creating Employees
9 System.out.printf("Employees before instantiation: %d\n",
10 Employee.getCount());
11
12 // create two Employees; count should be 2
13 Employee e1 = new Employee("Susan", "Baker");
14 Employee e2 = new Employee("Bob", "Blue");
15
16 // show that count is 2 after creating two Employees
17 System.out.printf("\nEmployees after instantiation:\n");
18 System.out.printf("via e1.getCount(): %d\n", e1.getCount());
19 System.out.printf("via e2.getCount(): %d\n", e2.getCount());
20 System.out.printf("via Employee.getCount(): %d\n",
21 Employee.getCount());
22
23 // get names of Employees
24 System.out.printf("\nEmployee 1: %s %s\nEmployee 2: %s %s\n",
25 e1.getFirstName(), e1.getLastName(),
26 e2.getFirstName(), e2.getLastName());
27 }
28 } // end class EmployeeTest

```

```

Employees before instantiation: 0
Employee constructor: Susan Baker; count = 1
Employee constructor: Bob Blue; count = 2

```

**Fig. 8.13** | static member demonstration. (Part I of 2.)

```

Employees after instantiation:
via e1.getCount(): 2
via e2.getCount(): 2
via Employee.getCount(): 2

Employee 1: Susan Baker
Employee 2: Bob Blue

```

**Fig. 8.13** | static member demonstration. (Part 2 of 2.)

When `main` terminates, local variables `e1` and `e2` are discarded—remember that a local variable exists *only* until the block in which it's declared completes execution. Because `e1` and `e2` were the only references to the `Employee` objects created in lines 13–14 (Fig. 8.13), these objects become “eligible for garbage collection” as `main` terminates.

In a typical app, the garbage collector *might* eventually reclaim the memory for any objects that are eligible for collection. If any objects are not reclaimed before the program terminates, the operating system will reclaim the memory used by the program. The JVM does *not* guarantee when, or even whether, the garbage collector will execute. When it does, it's possible that no objects or only a subset of the eligible objects will be collected.

## 8.12 static Import

In Section 5.3, you learned about the static fields and methods of class `Math`. We access class `Math`'s static fields and *methods* by preceding each with the class name `Math` and a dot (`.`). A **static import** declaration enables you to import the static members of a class or interface so you can access them via their *unqualified names* in your class—that is, the class name and a dot (`.`) are *not* required when using an imported static member.

### static Import Forms

A static import declaration has two forms—one that imports a particular static member (which is known as **single static import**) and one that imports *all* static members of a class (known as **static import on demand**). The following syntax imports a particular static member:

```
import static packageName.ClassName.staticMemberName;
```

where *packageName* is the package of the class (e.g., `java.lang`), *ClassName* is the name of the class (e.g., `Math`) and *staticMemberName* is the name of the static field or method (e.g., `PI` or `abs`). The following syntax imports *all* static members of a class:

```
import static packageName.ClassName.*;
```

The asterisk (`*`) indicates that *all* static members of the specified class should be available for use in the file. static import declarations import *only* static class members. Regular import statements should be used to specify the classes used in a program.

### Demonstrating static Import

Figure 8.14 demonstrates a static import. Line 3 is a static import declaration, which imports *all* static fields and methods of class `Math` from package `java.lang`. Lines 9–12 access the `Math` class's static fields `E` (line 11) and `PI` (line 12) and the static methods

`sqrt` (line 9) and `ceil` (line 10) *without* preceding the field names or method names with class name `Math` and a dot.



### Common Programming Error 8.7

*A compilation error occurs if a program attempts to import two or more classes' static methods that have the same signature or static fields that have the same name.*

```

1 // Fig. 8.14: StaticImportTest.java
2 // Static import of Math class methods.
3 import static java.lang.Math.*;
4
5 public class StaticImportTest
6 {
7 public static void main(String[] args)
8 {
9 System.out.printf("sqrt(900.0) = %.1f\n", sqrt(900.0));
10 System.out.printf("ceil(-9.8) = %.1f\n", ceil(-9.8));
11 System.out.printf("E = %f\n", E);
12 System.out.printf("PI = %f\n", PI);
13 }
14 } // end class StaticImportTest

```

```

sqrt(900.0) = 30.0
ceil(-9.8) = -9.0
E = 2.718282
PI = 3.141593

```

**Fig. 8.14** | static import of Math class methods.

## 8.13 final Instance Variables

The **principle of least privilege** is fundamental to good software engineering. In the context of an app's code, it states that code should be granted only the amount of privilege and access that it needs to accomplish its designated task, but no more. This makes your programs more robust by preventing code from accidentally (or maliciously) modifying variable values and calling methods that should *not* be accessible.

Let's see how this principle applies to instance variables. Some of them need to be *modifiable* and some do not. You can use the keyword `final` to specify that a variable is *not* modifiable (i.e., it's a *constant*) and that any attempt to modify it is an error. For example,

```
private final int INCREMENT;
```

declares a `final` (constant) instance variable `INCREMENT` of type `int`. Such variables can be initialized when they're declared. If they're not, they *must* be initialized in every constructor of the class. Initializing constants in constructors enables each object of the class to have a different value for the constant. If a `final` variable is *not* initialized in its declaration or in every constructor, a compilation error occurs.



### Software Engineering Observation 8.11

*Declaring an instance variable as `final` helps enforce the principle of least privilege. If an instance variable should not be modified, declare it to be `final` to prevent modification. For example, in Fig. 8.8, the instance variables `firstName`, `lastName`, `birthDate` and `hireDate` are never modified after they're initialized, so they should be declared `final`. We'll enforce this practice in all programs going forward. You'll see additional benefits of `final` in Chapter 23, Concurrency.*



### Common Programming Error 8.8

*Attempting to modify a `final` instance variable after it's initialized is a compilation error.*



### Error-Prevention Tip 8.5

*Attempts to modify a `final` instance variable are caught at compilation time rather than causing execution-time errors. It's always preferable to get bugs out at compilation time, if possible, rather than allow them to slip through to execution time (where experience has found that repair is often many times more expensive).*



### Software Engineering Observation 8.12

*A `final` field should also be declared `static` if it's initialized in its declaration to a value that's the same for all objects of the class. After this initialization, its value can never change. Therefore, we don't need a separate copy of the field for every object of the class. Making the field `static` enables all objects of the class to share the `final` field.*

## 8.14 Package Access

If no access modifier (`public`, `protected` or `private`—we discuss `protected` in Chapter 9) is specified for a method or variable when it's declared in a class, the method or variable is considered to have **package access**. In a program that consists of one class declaration, this has no specific effect. However, if a program uses *multiple* classes from the *same* package (i.e., a group of related classes), these classes can access each other's package-access members directly through references to objects of the appropriate classes, or in the case of static members through the class name. Package access is rarely used.

Figure 8.15 demonstrates package access. The app contains two classes in one source-code file—the `PackageDataTest` class containing `main` (lines 5–21) and the `PackageData` class (lines 24–41). Classes in the same source file are part of the same package. Consequently, class `PackageDataTest` is allowed to modify the package-access data of `PackageData` objects. When you compile this program, the compiler produces two separate `.class` files—`PackageDataTest.class` and `PackageData.class`. The compiler places the two `.class` files in the same directory. You can also place class `PackageData` (lines 24–41) in a separate source-code file.

In the `PackageData` class declaration, lines 26–27 declare the instance variables `number` and `string` with no access modifiers—therefore, these are package-access instance variables. Class `PackageDataTest`'s `main` method creates an instance of the `PackageData` class (line 9) to demonstrate the ability to modify the `PackageData` instance variables directly (as shown in lines 15–16). The results of the modification can be seen in the output window.



```

1 // Fig. 8.15: PackageDataTest.java
2 // Package-access members of a class are accessible by other classes
3 // in the same package.
4
5 public class PackageDataTest
6 {
7 public static void main(String[] args)
8 {
9 PackageData packageData = new PackageData();
10
11 // output String representation of packageData
12 System.out.printf("After instantiation:%n%s%n", packageData);
13
14 // change package access data in packageData object
15 packageData.number = 77;
16 packageData.string = "Goodbye";
17
18 // output String representation of packageData
19 System.out.printf("%nAfter changing values:%n%s%n", packageData);
20 }
21 } // end class PackageDataTest
22
23 // class with package access instance variables
24 class PackageData
25 {
26 int number; // package-access instance variable
27 String string; // package-access instance variable
28
29 // constructor
30 public PackageData()
31 {
32 number = 0;
33 string = "Hello";
34 }
35
36 // return PackageData object String representation
37 public String toString()
38 {
39 return String.format("number: %d; string: %s", number, string);
40 }
41 } // end class PackageData

```

```

After instantiation:
number: 0; string: Hello

After changing values:
number: 77; string: Goodbye

```

**Fig. 8.15** | Package-access members of a class are accessible by other classes in the same package.

## 8.15 Using BigDecimal for Precise Monetary Calculations

In earlier chapters, we demonstrated monetary calculations using values of type `double`. In Chapter 4, we discussed the fact that some `double` values are represented *approximately*.

Any application that requires precise floating-point calculations—such as those in financial applications—should instead use class **BigDecimal** (from package **java.math**).

### *Interest Calculations Using BigDecimal*

Figure 8.16 reimplements the interest calculation example of Fig. 4.6 using objects of class **BigDecimal** to perform the calculations. We also introduce class **NumberFormat** (package **java.text**) for formatting numeric values as *locale-specific* Strings—for example, in the U.S. locale, the value 1234.56, would be formatted as "1,234.56", whereas in many European locales it would be formatted as "1.234,56".

```

1 // Interest.java
2 // Compound-interest calculations with BigDecimal.
3 import java.math.BigDecimal;
4 import java.text.NumberFormat;
5
6 public class Interest
7 {
8 public static void main(String args[])
9 {
10 // initial principal amount before interest
11 BigDecimal principal = BigDecimal.valueOf(1000.0);
12 BigDecimal rate = BigDecimal.valueOf(0.05); // interest rate
13
14 // display headers
15 System.out.printf("%s%20s%n", "Year", "Amount on deposit");
16
17 // calculate amount on deposit for each of ten years
18 for (int year = 1; year <= 10; year++)
19 {
20 // calculate new amount for specified year
21 BigDecimal amount =
22 principal.multiply(rate.add(BigDecimal.ONE).pow(year));
23
24 // display the year and the amount
25 System.out.printf("%4d%20s%n", year,
26 NumberFormat.getCurrencyInstance().format(amount));
27 }
28 }
29 } // end class Interest

```

| Year | Amount on deposit |
|------|-------------------|
| 1    | \$1,050.00        |
| 2    | \$1,102.50        |
| 3    | \$1,157.62        |
| 4    | \$1,215.51        |
| 5    | \$1,276.28        |
| 6    | \$1,340.10        |
| 7    | \$1,407.10        |
| 8    | \$1,477.46        |
| 9    | \$1,551.33        |
| 10   | \$1,628.89        |

**Fig. 8.16** | Compound-interest calculations with **BigDecimal**.

### *Creating `BigDecimal` Objects*

Lines 11–12 declare and initialize `BigDecimal` variables `principal` and `rate` using the `BigDecimal` static method `valueOf` that receives a `double` argument and returns a `BigDecimal` object that represents the *exact* value specified.

### *Performing the Interest Calculations with `BigDecimal`*

Lines 21–22 perform the interest calculation using `BigDecimal` methods `multiply`, `add` and `pow`. The expression in line 22 evaluates as follows:

1. First, the expression `rate.add(BigDecimal.ONE)` adds 1 to the `rate` to produce a `BigDecimal` containing 1.05—this is equivalent to `1.0 + rate` in line 19 of Fig. 4.6. The `BigDecimal` constant `ONE` represents the value 1. Class `BigDecimal` also provides the commonly used constants `ZERO` (0) and `TEN` (10).
2. Next, `BigDecimal` method `pow` is called on the preceding result to raise 1.05 to the power `year`—this is equivalent to passing `1.0 + rate` and `year` to method `Math.pow` in line 19 of Fig. 4.6.
3. Finally, we call `BigDecimal` method `multiply` on the `principal` object, passing the preceding result as the argument. This returns a `BigDecimal` representing the amount on deposit at the end of the specified year.

Since the expression `rate.add(BigDecimal.ONE)` produces the same value in each iteration of the loop, we could have simply initialized `rate` to 1.05 in line 12; however, we chose to mimic the precise calculations we used in line 19 of Fig. 4.6.

### *Formatting Currency Values with `NumberFormat`*

During each iteration of the loop, line 26

```
NumberFormat.getCurrencyInstance().format(amount)
```

evaluates as follows:

1. First, the expression uses `NumberFormat`'s static method `getCurrencyInstance` to get a `NumberFormat` that's pre-configured to format numeric values as locale-specific currency Strings—for example, in the U.S. locale, the numeric value 1628.89 is formatted as \$1,628.89. Locale-specific formatting is an important part of **internationalization**—the process of customizing your applications for users' various locales and spoken languages.
2. Next, the expression invokes method `NumberFormat` method `format` (on the object returned by `getCurrencyInstance`) to perform the formatting of the `amount` value. Method `format` then returns the locale-specific String representation, rounded to two-digits to the right of the decimal point.

### *Rounding `BigDecimal` Values*

In addition to precise calculations, `BigDecimal` also gives you control over how values are rounded—by default all calculations are exact and *no* rounding occurs. If you do not specify how to round `BigDecimal` values and a given value cannot be represented exactly—such as the result of 1 divided by 3, which is 0.3333333...—an `ArithmeticException` occurs.

Though we do not do so in this example, you can specify the *rounding mode* for `BigDecimal` by supplying a `MathContext` object (package `java.math`) to class `BigDecimal`'s

constructor when you create a `BigDecimal`. You may also provide a `MathContext` to various `BigDecimal` methods that perform calculations. Class `MathContext` contains several pre-configured `MathContext` objects that you can learn about at

<http://docs.oracle.com/javase/7/docs/api/java/math/MathContext.html>

By default, each pre-configured `MathContext` uses so called “bankers rounding” as explained for the `RoundingMode` constant `HALF_EVEN` at:

[http://docs.oracle.com/javase/7/docs/api/java/math/RoundingMode.html#HALF\\_EVEN](http://docs.oracle.com/javase/7/docs/api/java/math/RoundingMode.html#HALF_EVEN)

### *Scaling `BigDecimal` Values*

A `BigDecimal`’s scale is the number of digits to the right of its decimal point. If you need a `BigDecimal` rounded to a specific digit, you can call `BigDecimal` method `setScale`. For example, the following expression returns a `BigDecimal` with two digits to the right of the decimal point and using bankers rounding:

```
amount.setScale(2, RoundingMode.HALF_EVEN)
```

## 8.16 (Optional) GUI and Graphics Case Study: Using Objects with Graphics

Most of the graphics you’ve seen to this point did not vary with each program execution. Exercise 5.2 in Section 5.13 asked you to create a program that generated shapes and colors at random. In that exercise, the drawing changed every time the system called `paintComponent`. To create a more consistent drawing that remains the same each time it’s drawn, we must store information about the displayed shapes so that we can reproduce them each time the system calls `paintComponent`. To do this, we’ll create a set of shape classes that store information about each shape. We’ll make these classes “smart” by allowing objects of these classes to draw themselves by using a `Graphics` object.

### *Class `MyLine`*

Figure 8.17 declares class `MyLine`, which has all these capabilities. Class `MyLine` imports classes `Color` and `Graphics` (lines 3–4). Lines 8–11 declare instance variables for the coordinates of the endpoints needed to draw a line, and line 12 declares the instance variable that stores the color of the line. The constructor at lines 15–22 takes five parameters, one for each instance variable that it initializes. Method `draw` at lines 25–29 requires a `Graphics` object and uses it to draw the line in the proper color and between the endpoints.

---

```

1 // Fig. 8.17: MyLine.java
2 // MyLine class represents a line.
3 import java.awt.Color;
4 import java.awt.Graphics;
5
6 public class MyLine
7 {

```

---

**Fig. 8.17** | `MyLine` class represents a line. (Part 1 of 2.)

---

```

 8 private int x1; // x-coordinate of first endpoint
 9 private int y1; // y-coordinate of first endpoint
10 private int x2; // x-coordinate of second endpoint
11 private int y2; // y-coordinate of second endpoint
12 private Color color; // color of this line
13
14 // constructor with input values
15 public MyLine(int x1, int y1, int x2, int y2, Color color)
16 {
17 this.x1 = x1;
18 this.y1 = y1;
19 this.x2 = x2;
20 this.y2 = y2;
21 this.color = color;
22 }
23
24 // Draw the line in the specified color
25 public void draw(Graphics g)
26 {
27 g.setColor(color);
28 g.drawLine(x1, y1, x2, y2);
29 }
30 } // end class MyLine

```

---

**Fig. 8.17** | MyLine class represents a line. (Part 2 of 2.)

### *Class DrawPanel*

In Fig. 8.18, we declare class `DrawPanel`, which will generate random objects of class `MyLine`. Line 12 declares the `MyLine` array `lines` to store the lines to draw. Inside the constructor (lines 15–37), line 17 sets the background color to `Color.WHITE`. Line 19 creates the array with a random length between 5 and 9. The loop at lines 22–36 creates a new `MyLine` for every element in the array. Lines 25–28 generate random coordinates for each line's endpoints, and lines 31–32 generate a random color for the line. Line 35 creates a new `MyLine` object with the randomly generated values and stores it in the array. Method `paintComponent` iterates through the `MyLine` objects in array `lines` using an enhanced for statement (lines 45–46). Each iteration calls the `draw` method of the current `MyLine` object and passes it the `Graphics` object for drawing on the panel.

---

```

1 // Fig. 8.18: DrawPanel.java
2 // Program that uses class MyLine
3 // to draw random lines.
4 import java.awt.Color;
5 import java.awt.Graphics;
6 import java.security.SecureRandom;
7 import javax.swing.JPanel;
8
9 public class DrawPanel extends JPanel
10 {
11 private SecureRandom randomNumbers = new SecureRandom();
12 private MyLine[] lines; // array of lines

```

---

**Fig. 8.18** | Program that uses class `MyLine` to draw random lines. (Part 1 of 2.)

---

```

13
14 // constructor, creates a panel with random shapes
15 public DrawPanel()
16 {
17 setBackground(Color.WHITE);
18
19 lines = new MyLine[5 + randomNumbers.nextInt(5)];
20
21 // create lines
22 for (int count = 0; count < lines.length; count++)
23 {
24 // generate random coordinates
25 int x1 = randomNumbers.nextInt(300);
26 int y1 = randomNumbers.nextInt(300);
27 int x2 = randomNumbers.nextInt(300);
28 int y2 = randomNumbers.nextInt(300);
29
30 // generate a random color
31 Color color = new Color(randomNumbers.nextInt(256),
32 randomNumbers.nextInt(256), randomNumbers.nextInt(256));
33
34 // add the line to the list of lines to be displayed
35 lines[count] = new MyLine(x1, y1, x2, y2, color);
36 }
37 }
38
39 // for each shape array, draw the individual shapes
40 public void paintComponent(Graphics g)
41 {
42 super.paintComponent(g);
43
44 // draw the lines
45 for (MyLine line : lines)
46 line.draw(g);
47 }
48 } // end class DrawPanel

```

---

**Fig. 8.18** | Program that uses class `MyLine` to draw random lines. (Part 2 of 2.)

### *Class TestDraw*

Class `TestDraw` in Fig. 8.19 sets up a new window to display our drawing. Since we're setting the coordinates for the lines only once in the constructor, the drawing does not change if `paintComponent` is called to refresh the drawing on the screen.

---

```

1 // Fig. 8.19: TestDraw.java
2 // Creating a JFrame to display a DrawPanel.
3 import javax.swing.JFrame;
4
5 public class TestDraw
6 {

```


---

**Fig. 8.19** | Creating a `JFrame` to display a `DrawPanel`. (Part 1 of 2.)

```

7 public static void main(String[] args)
8 {
9 DrawPanel panel = new DrawPanel();
10 JFrame app = new JFrame();
11
12 app.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
13 app.add(panel);
14 app.setSize(300, 300);
15 app.setVisible(true);
16 }
17 } // end class TestDraw

```



**Fig. 8.19** | Creating a JFrame to display a DrawPanel. (Part 2 of 2.)

### GUI and Graphics Case Study Exercise

**8.1** Extend the program in Figs. 8.17–8.19 to randomly draw rectangles and ovals. Create classes `MyRectangle` and `MyOval`. Both of these classes should include  $x1$ ,  $y1$ ,  $x2$ ,  $y2$  coordinates, a color and a boolean flag to determine whether the shape is filled. Declare a constructor in each class with arguments for initializing all the instance variables. To help draw rectangles and ovals, each class should provide methods `getUpperLeftX`, `getUpperLeftY`, `getWidth` and `getHeight` that calculate the upper-left  $x$ -coordinate, upper-left  $y$ -coordinate, width and height, respectively. The upper-left  $x$ -coordinate is the smaller of the two  $x$ -coordinate values, the upper-left  $y$ -coordinate is the smaller of the two  $y$ -coordinate values, the width is the absolute value of the difference between the two  $x$ -coordinate values, and the height is the absolute value of the difference between the two  $y$ -coordinate values.

Class `DrawPanel`, which extends `JPanel` and handles the creation of the shapes, should declare three arrays, one for each shape type. The length of each array should be a random number between 1 and 5. The constructor of class `DrawPanel` will fill each array with shapes of random position, size, color and fill.

In addition, modify all three shape classes to include the following:

- A constructor with no arguments that sets the shape's coordinates to 0, the color of the shape to `Color.BLACK`, and the filled property to `false` (`MyRectangle` and `MyOval` only).
- Set* methods for the instance variables in each class. The methods that set a coordinate value should verify that the argument is greater than or equal to zero before setting the coordinate—if it's not, they should set the coordinate to zero. The constructor should call the *set* methods rather than initialize the local variables directly.
- Get* methods for the instance variables in each class. Method `draw` should reference the coordinates by the *get* methods rather than access them directly.

## 8.17 Wrap-Up

In this chapter, we presented additional class concepts. The `Time` class case study showed a complete class declaration consisting of `private` data, overloaded `public` constructors for initialization flexibility, `set` and `get` methods for manipulating the class's data, and methods that returned `String` representations of a `Time` object in two different formats. You also learned that every class can declare a `toString` method that returns a `String` representation of an object of the class and that method `toString` can be called implicitly whenever an object of a class appears in the code where a `String` is expected. We showed how to throw an exception to indicate that a problem has occurred.

You learned that the `this` reference is used implicitly in a class's instance methods to access the class's instance variables and other instance methods. You also saw explicit uses of the `this` reference to access the class's members (including shadowed fields) and how to use keyword `this` in a constructor to call another constructor of the class.

We discussed the differences between default constructors provided by the compiler and no-argument constructors provided by the programmer. You learned that a class can have references to objects of other classes as members—a concept known as composition. You learned more about `enum` types and how they can be used to create a set of constants for use in a program. You learned about Java's garbage-collection capability and how it (unpredictably) reclaims the memory of objects that are no longer used. The chapter explained the motivation for `static` fields in a class and demonstrated how to declare and use `static` fields and methods in your own classes. You also learned how to declare and initialize `final` variables.

You learned that fields declared without an access modifier are given package access by default. You saw the relationship between classes in the same package that allows each class in a package to access the package-access members of other classes in the package. Finally, we demonstrated how to use class `BigDecimal` to perform precise monetary calculations.

In the next chapter, you'll learn about an important aspect of object-oriented programming in Java—inheritance. You'll see that all classes in Java are related by inheritance, directly or indirectly, to the class called `Object`. You'll also begin to understand how the relationships between classes enable you to build more powerful apps.

---

## Summary

### *Section 8.2 Time Class Case Study*

- The `public` methods of a class are also known as the class's `public` services or `public` interface (p. 308). They present to the class's clients a view of the services the class provides.
- A class's `private` members are not accessible to its clients.
- `String` class static method `format` (p. 310) is similar to method `System.out.printf` except that `format` returns a formatted `String` rather than displaying it in a command window.
- All objects in Java have a `toString` method that returns a `String` representation of the object. Method `toString` is called implicitly when an object appears in code where a `String` is needed.

### *Section 8.3 Controlling Access to Members*

- The access modifiers `public` and `private` control access to a class's variables and methods.



- The primary purpose of `public` methods is to present to the class's clients a view of the services the class provides. Clients need not be concerned with how the class accomplishes its tasks.
- A class's private variables and private methods (i.e., its implementation details) are not accessible to its clients.

#### *Section 8.4 Referring to the Current Object's Members with the `this` Reference*

- An instance method of an object implicitly uses keyword `this` (p. 314) to refer to the object's instance variables and other methods. Keyword `this` can also be used explicitly.
- The compiler produces a separate file with the `.class` extension for every compiled class.
- If a local variable has the same name as a class's field, the local variable shadows the field. You can use the `this` reference in a method to refer to the shadowed field explicitly.

#### *Section 8.5 Time Class Case Study: Overloaded Constructors*

- Overloaded constructors enable objects of a class to be initialized in different ways. The compiler differentiates overloaded constructors (p. 316) by their signatures.
- To call one constructor of a class from another of the same class, you can use the `this` keyword followed by parentheses containing the constructor arguments. If used, such a constructor call must appear as the first statement in the constructor's body.

#### *Section 8.6 Default and No-Argument Constructors*

- If no constructors are provided in a class, the compiler creates a default constructor.
- If a class declares constructors, the compiler will not create a default constructor. In this case, you must declare a no-argument constructor (p. 319) if default initialization is required.

#### *Section 8.7 Notes on Set and Get Methods*

- *Set* methods are commonly called mutator methods (p. 323) because they typically change a value. *Get* methods are commonly called accessor methods (p. 323) or query methods. A predicate method (p. 324) tests whether a condition is true or false.

#### *Section 8.8 Composition*

- A class can have references to objects of other classes as members. This is called composition (p. 324) and is sometimes referred to as a *has-a* relationship.

#### *Section 8.9 `enum` Types*

- All `enum` types (p. 327) are reference types. An `enum` type is declared with an `enum` declaration, which is a comma-separated list of `enum` constants. The declaration may optionally include other components of traditional classes, such as constructors, fields and methods.
- `enum` constants are implicitly `final`, because they declare constants that should not be modified.
- `enum` constants are implicitly `static`.
- Any attempt to create an object of an `enum` type with operator `new` results in a compilation error.
- `enum` constants can be used anywhere constants can be used, such as in the case labels of `switch` statements and to control enhanced `for` statements.
- Each `enum` constant in an `enum` declaration is optionally followed by arguments which are passed to the `enum` constructor.
- For every `enum`, the compiler generates a `static` method called `values` (p. 328) that returns an array of the `enum`'s constants in the order in which they were declared.
- `EnumSet` `static` method `range` (p. 329) receives the first and last `enum` constants in a range and returns an `EnumSet` that contains all the constants between these two constants, inclusive.

**Section 8.10 Garbage Collection**

- The Java Virtual Machine (JVM) performs automatic garbage collection (p. 330) to reclaim the memory occupied by objects that are no longer in use. When there are no more references to an object, the object is eligible for garbage collection. The memory for such an object can be reclaimed when the JVM executes its garbage collector.

**Section 8.11 static Class Members**

- A static variable (p. 330) represents classwide information that's shared among the class's objects.
- static variables have class scope. A class's public static members can be accessed through a reference to any object of the class, or they can be accessed by qualifying the member name with the class name and a dot (.). Client code can access a class's private static class members only through methods of the class.
- static class members exist as soon as the class is loaded into memory.
- A method declared static cannot access a class's instance variables and instance methods, because a static method can be called even when no objects of the class have been instantiated.
- The this reference cannot be used in a static method.

**Section 8.12 static Import**

- A static import declaration (p. 334) enables you to refer to imported static members without the class name and a dot (.). A single static import declaration imports one static member, and a static import on demand imports all static members of a class.

**Section 8.13 final Instance Variables**

- In the context of an app's code, the principle of least privilege (p. 335) states that code should be granted only the amount of privilege and access that it needs to accomplish its designated task.
- Keyword final specifies that a variable is not modifiable. Such variables must be initialized when they're declared or by each of a class's constructors.

**Section 8.14 Package Access**

- If no access modifier is specified for a method or variable when it's declared in a class, the method or variable is considered to have package access (p. 336).

**Section 8.15 Using BigDecimal for Precise Monetary Calculations**

- Any application that requires precise floating-point calculations without rounding errors—such as those in financial applications—should instead use class BigDecimal (package java.math; p. 338).
- BigDecimal static method valueOf (p. 339) with a double argument returns a BigDecimal that represents the exact value specified.
- BigDecimal method add (p. 339) adds its argument BigDecimal to the BigDecimal on which the method is called and returns the result.
- BigDecimal provides the constants ONE (1), ZERO (0) and TEN (10).
- BigDecimal method pow (p. 339) raises its first argument to the power specified in its second argument.
- BigDecimal method multiply (p. 339) multiplies its argument BigDecimal with the BigDecimal on which the method is called and returns the result.
- Class NumberFormat (package java.text; p. 339) provides capabilities for formatting numeric values as locale-specific Strings. The class's static method getCurrencyInstance returns a pre-configured NumberFormat for local-specific currency values. NumberFormat method format performs the formatting.

- Locale-specific formatting is an important part of internationalization—the process of customizing your applications for users’ various locales and spoken languages.
- `BigDecimal` gives you control over how values are rounded—by default all calculations are exact and no rounding occurs. If you do not specify how to round `BigDecimal` values and a given value cannot be represented exactly an `ArithmeticException` occurs.
- You can specify the rounding mode for `BigDecimal` by supplying a `MathContext` object (package `java.math`) to class `BigDecimal`’s constructor when you create a `BigDecimal`. You may also provide a `MathContext` to various `BigDecimal` methods that perform calculations. By default, each pre-configured `MathContext` uses so called “bankers rounding.”
- A `BigDecimal`’s scale is the number of digits to the right of its decimal point. If you need a `BigDecimal` rounded to a specific digit, you can call `BigDecimal` method `setScale`.

## Self-Review Exercise

- 8.1** Fill in the blanks in each of the following statements:
- A(n) \_\_\_\_\_ imports all static members of a class.
  - `String` class static method \_\_\_\_\_ is similar to method `System.out.printf`, but returns a formatted `String` rather than displaying a `String` in a command window.
  - If a method contains a local variable with the same name as one of its class’s fields, the local variable \_\_\_\_\_ the field in that method’s scope.
  - The public methods of a class are also known as the class’s \_\_\_\_\_ or \_\_\_\_\_.
  - A(n) \_\_\_\_\_ declaration specifies one class to import.
  - If a class declares constructors, the compiler will not create a(n) \_\_\_\_\_.
  - An object’s \_\_\_\_\_ method is called implicitly when an object appears in code where a `String` is needed.
  - Get* methods are commonly called \_\_\_\_\_ or \_\_\_\_\_.
  - A(n) \_\_\_\_\_ method tests whether a condition is true or false.
  - For every `enum`, the compiler generates a static method called \_\_\_\_\_ that returns an array of the `enum`’s constants in the order in which they were declared.
  - Composition is sometimes referred to as a(n) \_\_\_\_\_ relationship.
  - A(n) \_\_\_\_\_ declaration contains a comma-separated list of constants.
  - A(n) \_\_\_\_\_ variable represents classwide information that’s shared by all the objects of the class.
  - A(n) \_\_\_\_\_ declaration imports one static member.
  - The \_\_\_\_\_ states that code should be granted only the amount of privilege and access that it needs to accomplish its designated task.
  - Keyword \_\_\_\_\_ specifies that a variable is not modifiable after initialization in a declaration or constructor.
  - A(n) \_\_\_\_\_ declaration imports only the classes that the program uses from a particular package.
  - Set* methods are commonly called \_\_\_\_\_ because they typically change a value.
  - Use class \_\_\_\_\_ to perform precise monetary calculations.
  - Use the \_\_\_\_\_ statement to indicate that a problem has occurred.

## Answers to Self-Review Exercise

- 8.1** a) static import on demand. b) `format`. c) shadows. d) public services, public interface. e) single-type-import. f) default constructor. g) `toString`. h) accessor methods, query methods. i) predicate. j) values. k) *has-a*. l) `enum`. m) static. n) single static import. o) principle of least privilege. p) `final`. q) type-import-on-demand. r) mutator methods. s) `BigDecimal`. t) `throw`.

## Exercises

**8.2** (*Based on Section 8.14*) Explain the notion of package access in Java. Explain the negative aspects of package access.

**8.3** What happens when a return type, even void, is specified for a constructor?

**8.4** (*Rectangle Class*) Create a class `Rectangle` with attributes `length` and `width`, each of which defaults to 1. Provide methods that calculate the rectangle's perimeter and area. It has *set* and *get* methods for both `length` and `width`. The *set* methods should verify that `length` and `width` are each floating-point numbers larger than 0.0 and less than 20.0. Write a program to test class `Rectangle`.

**8.5** (*Modifying the Internal Data Representation of a Class*) It would be perfectly reasonable for the `Time2` class of Fig. 8.5 to represent the time internally as the number of seconds since midnight rather than the three integer values `hour`, `minute` and `second`. Clients could use the same public methods and get the same results. Modify the `Time2` class of Fig. 8.5 to implement the time as the number of seconds since midnight and show that no change is visible to the clients of the class.

**8.6** (*Savings Account Class*) Create class `SavingsAccount`. Use a static variable `annualInterestRate` to store the annual interest rate for all account holders. Each object of the class contains a private instance variable `savingsBalance` indicating the amount the saver currently has on deposit. Provide method `calculateMonthlyInterest` to calculate the monthly interest by multiplying the `savingsBalance` by `annualInterestRate` divided by 12—this interest should be added to `savingsBalance`. Provide a static method `modifyInterestRate` that sets the `annualInterestRate` to a new value. Write a program to test class `SavingsAccount`. Instantiate two `savingsAccount` objects, `saver1` and `saver2`, with balances of \$2000.00 and \$3000.00, respectively. Set `annualInterestRate` to 4%, then calculate the monthly interest for each of 12 months and print the new balances for both savers. Next, set the `annualInterestRate` to 5%, calculate the next month's interest and print the new balances for both savers.

**8.7** (*Enhancing Class Time2*) Modify class `Time2` of Fig. 8.5 to include a `tick` method that increments the time stored in a `Time2` object by one second. Provide method `incrementMinute` to increment the minute by one and method `incrementHour` to increment the hour by one. Write a program that tests the `tick` method, the `incrementMinute` method and the `incrementHour` method to ensure that they work correctly. Be sure to test the following cases:

- a) incrementing into the next minute,
- b) incrementing into the next hour and
- c) incrementing into the next day (i.e., 11:59:59 PM to 12:00:00 AM).

**8.8** (*Enhancing Class Date*) Modify class `Date` of Fig. 8.7 to perform error checking on the initializer values for instance variables `month`, `day` and `year` (currently it validates only the month and day). Provide a method `nextDay` to increment the day by one. Write a program that tests method `nextDay` in a loop that prints the date during each iteration to illustrate that the method works correctly. Test the following cases:

- a) incrementing into the next month and
- b) incrementing into the next year.

**8.9** Rewrite the code in Fig. 8.14 to use a separate `import` declaration for each static member of class `Math` that's used in the example.

**8.10** Write an enum type `TrafficLight`, whose constants (`RED`, `GREEN`, `YELLOW`) take one parameter—the duration of the light. Write a program to test the `TrafficLight` enum so that it displays the enum constants and their durations.

**8.11** (*Complex Numbers*) Create a class called `Complex` for performing arithmetic with complex numbers. Complex numbers have the form

$$\text{realPart} + \text{imaginaryPart} * i$$

where  $i$  is

$$\sqrt{-1}$$

Write a program to test your class. Use floating-point variables to represent the private data of the class. Provide a constructor that enables an object of this class to be initialized when it's declared. Provide a no-argument constructor with default values in case no initializers are provided. Provide public methods that perform the following operations:

- a) Add two `Complex` numbers: The real parts are added together and the imaginary parts are added together.
- b) Subtract two `Complex` numbers: The real part of the right operand is subtracted from the real part of the left operand, and the imaginary part of the right operand is subtracted from the imaginary part of the left operand.
- c) Print `Complex` numbers in the form (*realPart*, *imaginaryPart*).

**8.12 (Date and Time Class)** Create class `DateAndTime` that combines the modified `Time2` class of Exercise 8.7 and the modified `Date` class of Exercise 8.8. Modify method `incrementHour` to call method `nextDay` if the time is incremented into the next day. Modify methods `toString` and `toUniversalString` to output the date in addition to the time. Write a program to test the new class `DateAndTime`. Specifically, test incrementing the time to the next day.

**8.13 (Set of Integers)** Create class `IntegerSet`. Each `IntegerSet` object can hold integers in the range 0–100. The set is represented by an array of `booleans`. Array element `a[i]` is `true` if integer  $i$  is in the set. Array element `a[j]` is `false` if integer  $j$  is not in the set. The no-argument constructor initializes the array to the “empty set” (i.e., all `false` values).

Provide the following methods: The static method `union` creates a set that's the set-theoretic union of two existing sets (i.e., an element of the new set's array is set to `true` if that element is `true` in either or both of the existing sets—otherwise, the new set's element is set to `false`). The static method `intersection` creates a set which is the set-theoretic intersection of two existing sets (i.e., an element of the new set's array is set to `false` if that element is `false` in either or both of the existing sets—otherwise, the new set's element is set to `true`). Method `insertElement` inserts a new integer  $k$  into a set (by setting `a[k]` to `true`). Method `deleteElement` deletes integer  $m$  (by setting `a[m]` to `false`). Method `toString` returns a `String` containing a set as a list of numbers separated by spaces. Include only those elements that are present in the set. Use `---` to represent an empty set. Method `isEqualTo` determines whether two sets are equal. Write a program to test class `IntegerSet`. Instantiate several `IntegerSet` objects. Test that all your methods work properly.

**8.14 (Date Class)** Create class `Date` with the following capabilities:

- a) Output the date in multiple formats, such as
 

```
MM/DD/YYYY
June 14, 1992
DDD YYYY
```
- b) Use overloaded constructors to create `Date` objects initialized with dates of the formats in part (a). In the first case the constructor should receive three integer values. In the second case it should receive a `String` and two integer values. In the third case it should receive two integer values, the first of which represents the day number in the year. [*Hint:* To convert the `String` representation of the month to a numeric value, compare `Strings` using the `equals` method. For example, if `s1` and `s2` are `Strings`, the method call `s1.equals(s2)` returns `true` if the `Strings` are identical and otherwise returns `false`.]

**8.15 (Rational Numbers)** Create a class called `Rational` for performing arithmetic with fractions. Write a program to test your class. Use integer variables to represent the private instance variables of the class—the numerator and the denominator. Provide a constructor that enables an object of

this class to be initialized when it's declared. The constructor should store the fraction in reduced form. The fraction

$$2/4$$

is equivalent to 1/2 and would be stored in the object as 1 in the numerator and 2 in the denominator. Provide a no-argument constructor with default values in case no initializers are provided. Provide public methods that perform each of the following operations:

- a) Add two Rational numbers: The result of the addition should be stored in reduced form. Implement this as a static method.
- b) Subtract two Rational numbers: The result of the subtraction should be stored in reduced form. Implement this as a static method.
- c) Multiply two Rational numbers: The result of the multiplication should be stored in reduced form. Implement this as a static method.
- d) Divide two Rational numbers: The result of the division should be stored in reduced form. Implement this as a static method.
- e) Return a String representation of a Rational number in the form a/b, where a is the numerator and b is the denominator.
- f) Return a String representation of a Rational number in floating-point format. (Consider providing formatting capabilities that enable the user of the class to specify the number of digits of precision to the right of the decimal point.)

**8.16 (Huge Integer Class)** Create a class `HugeInteger` which uses a 40-element array of digits to store integers as large as 40 digits each. Provide methods `parse`, `toString`, `add` and `subtract`. Method `parse` should receive a String, extract each digit using method `charAt` and place the integer equivalent of each digit into the integer array. For comparing `HugeInteger` objects, provide the following methods: `isEqualTo`, `isNotEqualTo`, `isGreaterThan`, `isLessThan`, `isGreaterThanOrEqualTo` and `isLessThanOrEqualTo`. Each of these is a predicate method that returns `true` if the relationship holds between the two `HugeInteger` objects and returns `false` if the relationship does not hold. Provide a predicate method `isZero`. If you feel ambitious, also provide methods `multiply`, `divide` and `remainder`. [Note: Primitive `boolean` values can be output as the word “true” or the word “false” with format specifier `%b`.]

**8.17 (Tic-Tac-Toe)** Create a class `TicTacToe` that will enable you to write a program to play Tic-Tac-Toe. The class contains a private 3-by-3 two-dimensional array. Use an `enum` type to represent the value in each cell of the array. The `enum`'s constants should be named `X`, `O` and `EMPTY` (for a position that does not contain an X or an O). The constructor should initialize the board elements to `EMPTY`. Allow two human players. Wherever the first player moves, place an X in the specified square, and place an O wherever the second player moves. Each move must be to an empty square. After each move, determine whether the game has been won and whether it's a draw. If you feel ambitious, modify your program so that the computer makes the moves for one of the players. Also, allow the player to specify whether he or she wants to go first or second. If you feel exceptionally ambitious, develop a program that will play three-dimensional Tic-Tac-Toe on a 4-by-4-by-4 board [Note: This is an extremely challenging project!].

**8.18 (Account Class with BigDecimal balance)** Rewrite the `Account` class of Section 7.5 to store the balance as a `BigDecimal` object and to perform all calculations using `BigDecimal`'s.

## Making a Difference

**8.19 (Project: Emergency Response Class)** The North American emergency response service, 9-1-1, connects callers to a local Public Service Answering Point (PSAP). Traditionally, the PSAP would ask the caller for identification information—including the caller's address, phone number and the nature of the emergency, then dispatch the appropriate emergency responders (such as the police, an ambu-

lance or the fire department). *Enhanced 9-1-1 (or E9-1-1)* uses computers and databases to determine the caller's physical address, directs the call to the nearest PSAP, and displays the caller's phone number and address to the call taker. *Wireless Enhanced 9-1-1* provides call takers with identification information for wireless calls. Rolled out in two phases, the first phase required carriers to provide the wireless phone number and the location of the cell site or base station transmitting the call. The second phase required carriers to provide the location of the caller (using technologies such as GPS). To learn more about 9-1-1, visit <http://www.fcc.gov/pshs/services/911-services/welcome.html> and <http://people.howstuffworks.com/9-1-1.htm>.

An important part of creating a class is determining the class's attributes (instance variables). For this class design exercise, research 9-1-1 services on the Internet. Then, design a class called *Emergency* that might be used in an object-oriented 9-1-1 emergency response system. List the attributes that an object of this class might use to represent the emergency. For example, the class might include information on who reported the emergency (including their phone number), the location of the emergency, the time of the report, the nature of the emergency, the type of response and the status of the response. The class attributes should completely describe the nature of the problem and what's happening to resolve that problem.

# 9

## Object-Oriented Programming: Inheritance

*Say not you know another entirely,  
till you have divided an inheritance with him.*

—Johann Kasper Lavater

*This method is to define as the number of a class the class of all classes similar to the given class.*

—Bertrand Russell

### Objectives

In this chapter you'll:

- Understand inheritance and how to use it to develop new classes based on existing classes.
- Learn the notions of superclasses and subclasses and the relationship between them.
- Use keyword **extends** to create a class that inherits attributes and behaviors from another class.
- Use access modifier **protected** in a superclass to give subclass methods access to these superclass members.
- Access superclass members with **super** from a subclass.
- Learn how constructors are used in inheritance hierarchies.
- Learn about the methods of class **Object**, the direct or indirect superclass of all classes.





- 9.1 Introduction
- 9.2 Superclasses and Subclasses
- 9.3 **protected** Members
- 9.4 Relationship Between Superclasses and Subclasses
  - 9.4.1 Creating and Using a `CommissionEmployee` Class
  - 9.4.2 Creating and Using a `BasePlusCommissionEmployee` Class
  - 9.4.3 Creating a `CommissionEmployee–BasePlusCommissionEmployee` Inheritance Hierarchy
  - 9.4.4 `CommissionEmployee–BasePlusCommissionEmployee` Inheritance Hierarchy Using `protected` Instance Variables
  - 9.4.5 `CommissionEmployee–BasePlusCommissionEmployee` Inheritance Hierarchy Using `private` Instance Variables
- 9.5 Constructors in Subclasses
- 9.6 Class Object
- 9.7 (Optional) GUI and Graphics Case Study: Displaying Text and Images Using `Labels`
- 9.8 Wrap-Up

Summary | Self-Review Exercises | Answers to Self-Review Exercises | Exercises

## 9.1 Introduction

This chapter continues our discussion of object-oriented programming (OOP) by introducing **inheritance**, in which a new class is created by acquiring an existing class's members and possibly embellishing them with new or modified capabilities. With inheritance, you can save time during program development by basing new classes on existing proven and debugged high-quality software. This also increases the likelihood that a system will be implemented and maintained effectively.

When creating a class, rather than declaring completely new members, you can designate that the new class should *inherit* the members of an existing class. The existing class is called the **superclass**, and the new class is the **subclass**. (The C++ programming language refers to the superclass as the **base class** and the subclass as the **derived class**.) A subclass can become a superclass for future subclasses.

A subclass can add its own fields and methods. Therefore, a subclass is *more specific* than its superclass and represents a more specialized group of objects. The subclass exhibits the behaviors of its superclass and can modify those behaviors so that they operate appropriately for the subclass. This is why inheritance is sometimes referred to as **specialization**.

The **direct superclass** is the superclass from which the subclass explicitly inherits. An **indirect superclass** is any class above the direct superclass in the **class hierarchy**, which defines the inheritance relationships among classes—as you'll see in Section 9.2, diagrams help you understand these relationships. In Java, the class hierarchy begins with class `Object` (in package `java.lang`), which *every* class in Java directly or indirectly **extends** (or “inherits from”). Section 9.6 lists the methods of class `Object` that are inherited by all other Java classes. Java supports only **single inheritance**, in which each class is derived from exactly *one* direct superclass. Unlike C++, Java does *not* support multiple inheritance (which occurs when a class is derived from more than one direct superclass). Chapter 10, Object-Oriented Programming: Polymorphism and Interfaces, explains how to use Java *interfaces* to realize many of the benefits of multiple inheritance while avoiding the associated problems.

We distinguish between the *is-a* relationship and the *has-a* relationship. *Is-a* represents inheritance. In an *is-a* relationship, *an object of a subclass can also be treated as an object of its superclass*—e.g., a car *is a* vehicle. By contrast, *has-a* represents composition (see Chapter 8). In a *has-a* relationship, *an object contains as members references to other objects*—e.g., a car *has a* steering wheel (and a car object has a reference to a steering-wheel object).

New classes can inherit from classes in **class libraries**. Organizations develop their own class libraries and can take advantage of others available worldwide. Some day, most new software likely will be constructed from **standardized reusable components**, just as automobiles and most computer hardware are constructed today. This will facilitate the rapid development of more powerful, abundant and economical software.

## 9.2 Superclasses and Subclasses

Often, an object of one class *is an* object of another class as well. For example, a CarLoan *is a* Loan as are HomeImprovementLoans and MortgageLoans. Thus, in Java, class CarLoan can be said to inherit from class Loan. In this context, class Loan is a superclass and class CarLoan is a subclass. A CarLoan *is a* specific type of Loan, but it's incorrect to claim that every Loan *is a* CarLoan—the Loan could be any type of loan. Figure 9.1 lists several simple examples of superclasses and subclasses—superclasses tend to be “more general” and subclasses “more specific.”


| Superclass  | Subclasses                                 |
|-------------|--------------------------------------------|
| Student     | GraduateStudent, UndergraduateStudent      |
| Shape       | Circle, Triangle, Rectangle, Sphere, Cube  |
| Loan        | CarLoan, HomeImprovementLoan, MortgageLoan |
| Employee    | Faculty, Staff                             |
| BankAccount | CheckingAccount, SavingsAccount            |

**Fig. 9.1** | Inheritance examples.

Because every subclass object *is an* object of its superclass, and one superclass can have many subclasses, the set of objects represented by a superclass is often larger than the set of objects represented by any of its subclasses. For example, the superclass Vehicle represents *all* vehicles, including cars, trucks, boats, bicycles and so on. By contrast, subclass Car represents a smaller, more specific subset of vehicles.

### University Community Member Hierarchy

Inheritance relationships form treelike *hierarchical* structures. A superclass exists in a hierarchical relationship with its subclasses. Let's develop a sample class hierarchy (Fig. 9.2), also called an **inheritance hierarchy**. A university community has thousands of members, including employees, students and alumni. Employees are either faculty or staff members. Faculty members are either administrators (e.g., deans and department chairpersons) or teachers. The hierarchy could contain many other classes. For example, students can be graduate or undergraduate students. Undergraduate students can be freshmen, sophomores, juniors or seniors.




**Fig. 9.2** | Inheritance hierarchy UML class diagram for university CommunityMembers.

Each arrow in the hierarchy represents an *is-a* relationship. As we follow the arrows upward in this class hierarchy, we can state, for example, that “an Employee *is a* CommunityMember” and “a Teacher *is a* Faculty member.” CommunityMember is the direct superclass of Employee, Student and Alumnus and is an indirect superclass of all the other classes in the diagram. Starting from the bottom, you can follow the arrows and apply the *is-a* relationship up to the topmost superclass. For example, an Administrator *is a* Faculty member, *is an* Employee, *is a* CommunityMember and, of course, *is an* Object.

### Shape Hierarchy

Now consider the Shape inheritance hierarchy in Fig. 9.3. This hierarchy begins with superclass Shape, which is extended by subclasses TwoDimensionalShape and ThreeDimensionalShape—Shapes are either TwoDimensionalShapes or ThreeDimensionalShapes. The third level of this hierarchy contains *specific* types of TwoDimensionalShapes and ThreeDimensionalShapes. As in Fig. 9.2, we can follow the arrows from the bottom of the diagram to the topmost superclass in this class hierarchy to identify several *is-a* relationships. For example, a Triangle *is a* TwoDimensionalShape and *is a* Shape, while a Sphere *is a* ThreeDimensionalShape and *is a* Shape. This hierarchy could contain many other classes. For example, ellipses and trapezoids also are TwoDimensionalShapes.



**Fig. 9.3** | Inheritance hierarchy UML class diagram for Shapes.

Not every class relationship is an inheritance relationship. In Chapter 8, we discussed the *has-a* relationship, in which classes have members that are references to objects of other classes. Such relationships create classes by *composition* of existing classes. For example, given the classes `Employee`, `BirthDate` and `TelephoneNumber`, it's improper to say that an `Employee` *is a* `BirthDate` or that an `Employee` *is a* `TelephoneNumber`. However, an `Employee` *has a* `BirthDate`, and an `Employee` *has a* `TelephoneNumber`.

It's possible to treat superclass objects and subclass objects similarly—their commonalities are expressed in the superclass's members. Objects of all classes that extend a common superclass can be treated as objects of that superclass—such objects have an *is-a* relationship with the superclass. Later in this chapter and in Chapter 10, we consider many examples that take advantage of the *is-a* relationship.

A subclass can customize methods that it inherits from its superclass. To do this, the subclass **overrides** (*redefines*) the superclass method with an appropriate implementation, as we'll see in the chapter's code examples.

### 9.3 protected Members

Chapter 8 discussed access modifiers `public` and `private`. A class's `public` members are accessible wherever the program has a *reference* to an *object* of that class or one of its *subclasses*. A class's `private` members are accessible only within the class itself. In this section, we introduce the access modifier **protected**. Using `protected` access offers an intermediate level of access between `public` and `private`. A superclass's `protected` members can be accessed by members of that superclass, by members of its subclasses and by members of other classes in the *same package*—`protected` members also have *package access*.

All `public` and `protected` superclass members retain their original access modifier when they become members of the subclass—`public` members of the superclass become `public` members of the subclass, and `protected` members of the superclass become `protected` members of the subclass. A superclass's `private` members are *not* accessible outside the class itself. Rather, they're *hidden* from its subclasses and can be accessed only through the `public` or `protected` methods inherited from the superclass.

Subclass methods can refer to `public` and `protected` members inherited from the superclass simply by using the member names. When a subclass method *overrides* an inherited superclass method, the *superclass* version of the method can be accessed from the *subclass* by preceding the superclass method name with keyword **super** and a dot (`.`) separator. We discuss accessing overridden members of the superclass in Section 9.4.



#### Software Engineering Observation 9.1

*Methods of a subclass cannot directly access private members of their superclass. A subclass can change the state of private superclass instance variables only through non-private methods provided in the superclass and inherited by the subclass.*



#### Software Engineering Observation 9.2

*Declaring private instance variables helps you test, debug and correctly modify systems. If a subclass could access its superclass's private instance variables, classes that inherit from that subclass could access the instance variables as well. This would propagate access to what should be private instance variables, and the benefits of information hiding would be lost.*

## 9.4 Relationship Between Superclasses and Subclasses

We now use an inheritance hierarchy containing types of *employees* in a company's payroll application to discuss the relationship between a superclass and its subclass. In this company, *commission employees* (who will be represented as objects of a superclass) are paid a percentage of their sales, while *base-salaried commission employees* (who will be represented as objects of a subclass) receive a base salary *plus* a percentage of their sales.

We divide our discussion of the relationship between these classes into five examples. The first declares class `CommissionEmployee`, which directly inherits from class `Object` and declares as `private` instance variables a first name, last name, social security number, commission rate and gross (i.e., total) sales amount.

The second example declares class `BasePlusCommissionEmployee`, which also directly inherits from class `Object` and declares as `private` instance variables a first name, last name, social security number, commission rate, gross sales amount *and* base salary. We create this class by *writing every line of code* the class requires—we'll soon see that it's much more efficient to create it by inheriting from class `CommissionEmployee`.

The third example declares a new `BasePlusCommissionEmployee` class that *extends* class `CommissionEmployee` (i.e., a `BasePlusCommissionEmployee` *is a* `CommissionEmployee` who also has a base salary). This *software reuse lets us write much less code* when developing the new subclass. In this example, class `BasePlusCommissionEmployee` attempts to access class `CommissionEmployee`'s private members—this results in compilation errors, because the subclass *cannot* access the superclass's private instance variables.

The fourth example shows that if `CommissionEmployee`'s instance variables are declared as `protected`, the `BasePlusCommissionEmployee` subclass *can* access that data directly. Both `BasePlusCommissionEmployee` classes contain identical functionality, but we show how the inherited version is easier to create and manage.

After we discuss the convenience of using `protected` instance variables, we create the fifth example, which sets the `CommissionEmployee` instance variables back to `private` to enforce good software engineering. Then we show how the `BasePlusCommissionEmployee` subclass can use `CommissionEmployee`'s public methods to manipulate (in a controlled manner) the private instance variables inherited from `CommissionEmployee`.

### 9.4.1 Creating and Using a `CommissionEmployee` Class

We begin by declaring class `CommissionEmployee` (Fig. 9.4). Line 4 begins the class declaration and indicates that class `CommissionEmployee` **extends** (i.e., *inherits from*) class **Object** (from package `java.lang`). This causes class `CommissionEmployee` to inherit the class `Object`'s methods—class `Object` does not have any fields. If you don't explicitly specify which class a new class extends, the class extends `Object` implicitly. For this reason, you typically will not include “`extends Object`” in your code—we do so in this one example only for demonstration purposes.

#### *Overview of Class `CommissionEmployee`'s Methods and Instance Variables*

Class `CommissionEmployee`'s public services include a constructor (lines 13–34) and methods `earnings` (lines 87–90) and `toString` (lines 93–101). Lines 37–52 declare `public get` methods for the class's `final` instance variables (declared in lines 6–8) `firstName`, `lastName` and `socialSecurityNumber`. These three instance variables are declared `final` because they do not need to be modified after they're initialized—this is also why we do

not provide corresponding *set* methods. Lines 55–84 declare public *set* and *get* methods for the class's *grossSales* and *commissionRate* instance variables (declared in lines 9–10). The class declares its instance variables as *private*, so objects of other classes cannot directly access these variables.

---

```

1 // Fig. 9.4: CommissionEmployee.java
2 // CommissionEmployee class represents an employee paid a
3 // percentage of gross sales.
4 public class CommissionEmployee extends Object
5 {
6 private final String firstName;
7 private final String lastName;
8 private final String socialSecurityNumber;
9 private double grossSales; // gross weekly sales
10 private double commissionRate; // commission percentage
11
12 // five-argument constructor
13 public CommissionEmployee(String firstName, String lastName,
14 String socialSecurityNumber, double grossSales,
15 double commissionRate)
16 {
17 // implicit call to Object's default constructor occurs here
18
19 // if grossSales is invalid throw exception
20 if (grossSales < 0.0)
21 throw new IllegalArgumentException(
22 "Gross sales must be >= 0.0");
23
24 // if commissionRate is invalid throw exception
25 if (commissionRate <= 0.0 || commissionRate >= 1.0)
26 throw new IllegalArgumentException(
27 "Commission rate must be > 0.0 and < 1.0");
28
29 this.firstName = firstName;
30 this.lastName = lastName;
31 this.socialSecurityNumber = socialSecurityNumber;
32 this.grossSales = grossSales;
33 this.commissionRate = commissionRate;
34 } // end constructor
35
36 // return first name
37 public String getFirstName()
38 {
39 return firstName;
40 }
41
42 // return last name
43 public String getLastName()
44 {
45 return lastName;
46 }

```

---

**Fig. 9.4** | CommissionEmployee class represents an employee paid a percentage of gross sales.  
(Part I of 3.)

---

```

47
48 // return social security number
49 public String getSocialSecurityNumber()
50 {
51 return socialSecurityNumber;
52 }
53
54 // set gross sales amount
55 public void setGrossSales(double grossSales)
56 {
57 if (grossSales < 0.0)
58 throw new IllegalArgumentException(
59 "Gross sales must be >= 0.0");
60
61 this.grossSales = grossSales;
62 }
63
64 // return gross sales amount
65 public double getGrossSales()
66 {
67 return grossSales;
68 }
69
70 // set commission rate
71 public void setCommissionRate(double commissionRate)
72 {
73 if (commissionRate <= 0.0 || commissionRate >= 1.0)
74 throw new IllegalArgumentException(
75 "Commission rate must be > 0.0 and < 1.0");
76
77 this.commissionRate = commissionRate;
78 }
79
80 // return commission rate
81 public double getCommissionRate()
82 {
83 return commissionRate;
84 }
85
86 // calculate earnings
87 public double earnings()
88 {
89 return commissionRate * grossSales;
90 }
91
92 // return String representation of CommissionEmployee object
93 @Override // indicates that this method overrides a superclass method
94 public String toString()
95 {
96 return String.format("%s: %s %s\n%s: %s\n%s: %.2f\n%s: %.2f",
97 "commission employee", firstName, lastName,
98 "social security number", socialSecurityNumber,

```

**Fig. 9.4** | CommissionEmployee class represents an employee paid a percentage of gross sales.  
(Part 2 of 3.)

```

99 "gross sales", grossSales,
100 "commission rate", commissionRate);
101 }
102 } // end class CommissionEmployee

```

**Fig. 9.4** | `CommissionEmployee` class represents an employee paid a percentage of gross sales. (Part 3 of 3.)

### *Class `CommissionEmployee`'s Constructor*

Constructors are *not* inherited, so class `CommissionEmployee` does not inherit class `Object`'s constructor. However, a superclass's constructors are still available to be called by subclasses. In fact, Java requires that *the first task of any subclass constructor is to call its direct superclass's constructor*, either explicitly or implicitly (if no constructor call is specified), to ensure that the instance variables inherited from the superclass are initialized properly. The syntax for calling a superclass constructor explicitly is discussed in Section 9.4.3. In this example, class `CommissionEmployee`'s constructor calls class `Object`'s constructor implicitly. If the code does not include an explicit call to the superclass constructor, Java *implicitly* calls the superclass's default or *no-argument* constructor. The comment in line 17 of Fig. 9.4 indicates where the implicit call to the superclass `Object`'s default constructor is made (you do *not* write the code for this call). `Object`'s default constructor does nothing. Even if a class does not have constructors, the default constructor that the compiler implicitly declares for the class will call the superclass's default or no-argument constructor.

After the implicit call to `Object`'s constructor, lines 20–22 and 25–27 validate the `grossSales` and `commissionRate` arguments. If these are valid (that is, the constructor does not throw an `IllegalArgumentException`), lines 29–33 assign the constructor's arguments to the class's instance variables.

We did not validate the values of arguments `firstName`, `lastName` and `socialSecurityNumber` before assigning them to the corresponding instance variables. We could validate the first and last names—perhaps to ensure that they're of a reasonable length. Similarly, a social security number could be validated using regular expressions (Section 14.7) to ensure that it contains nine digits, with or without dashes (e.g., 123-45-6789 or 123456789).

### *Class `CommissionEmployee`'s earnings Method*

Method `earnings` (lines 87–90) calculates a `CommissionEmployee`'s earnings. Line 89 multiplies the `commissionRate` by the `grossSales` and returns the result.

### *Class `CommissionEmployee`'s `toString` Method and the `@Override` Annotation*

Method `toString` (lines 93–101) is special—it's one of the methods that *every* class inherits directly or indirectly from class `Object` (summarized in Section 9.6). Method `toString` returns a `String` representing an object. It's called implicitly whenever an object must be converted to a `String` representation, such as when an object is output by `printf` or output by `String` method `format` via the `%s` format specifier. Class `Object`'s `toString` method returns a `String` that includes the name of the object's class. It's primarily a placeholder that can be *overridden* by a subclass to specify an appropriate `String` representation of the data in a subclass object. Method `toString` of class `CommissionEmployee` overrides (redefines) class `Object`'s `toString` method. When invoked, `CommissionEmployee`'s `toString`



method uses `String` method `format` to return a `String` containing information about the `CommissionEmployee`. To override a superclass method, a subclass must declare a method with the *same signature* (method name, number of parameters, parameter types and order of parameter types) as the superclass method—`Object`'s `toString` method takes no parameters, so `CommissionEmployee` declares `toString` with no parameters.

Line 93 uses the optional **@Override** annotation to indicate that the following method declaration (i.e., `toString`) should *override* an *existing* superclass method. This annotation helps the compiler catch a few common errors. For example, in this case, you intend to override superclass method `toString`, which is spelled with a lowercase “t” and an uppercase “S.” If you inadvertently use a lowercase “s,” the compiler will flag this as an error because the superclass does not contain a method named `toString`. If you didn’t use the **@Override** annotation, `toString` would be an entirely different method that would *not* be called if a `CommissionEmployee` were used where a `String` was needed.

Another common overriding error is declaring the wrong number or types of parameters in the parameter list. This creates an *unintentional overload* of the superclass method, rather than overriding the existing method. If you then attempt to call the method (with the correct number and types of parameters) on a subclass object, the superclass’s version is invoked—potentially leading to subtle logic errors. When the compiler encounters a method declared with **@Override**, it compares the method’s signature with the superclass’s method signatures. If there isn’t an exact match, the compiler issues an error message, such as “method does not override or implement a method from a supertype.” You would then correct your method’s signature so that it matches one in the superclass.



#### Error-Prevention Tip 9.1

*Though the **@Override** annotation is optional, declare overridden methods with it to ensure at compilation time that you defined their signatures correctly. It’s always better to find errors at compile time rather than at runtime. For this reason, the `toString` methods in Fig. 7.11 and in Chapter 8’s examples should have been declared with **@Override**.*



#### Common Programming Error 9.1

*It’s a compilation error to override a method with a more restricted access modifier—a `public` superclass method cannot become a protected or private subclass method; a protected superclass method cannot become a private subclass method. Doing so would break the is-a relationship, which requires that all subclass objects be able to respond to method calls made to `public` methods declared in the superclass. If a `public` method, could be overridden as a protected or private method, the subclass objects would not be able to respond to the same method calls as superclass objects. Once a method is declared `public` in a superclass, the method remains `public` for all that class’s direct and indirect subclasses.*

#### Class `CommissionEmployeeTest`

Figure 9.5 tests class `CommissionEmployee`. Lines 9–10 instantiate a `CommissionEmployee` object and invoke `CommissionEmployee`’s constructor (lines 13–34 of Fig. 9.4) to initialize it with “Sue” as the first name, “Jones” as the last name, “222-22-2222” as the social security number, 10000 as the gross sales amount (\$10,000) and .06 as the commission rate (i.e., 6%). Lines 15–24 use `CommissionEmployee`’s `get` methods to retrieve the object’s instance-variable values for output. Lines 26–27 invoke the object’s `setGrossSales` and `setCommissionRate` methods to change the values of instance variables `grossSales` and `commission`

Rate. Lines 29–30 output the String representation of the updated `CommissionEmployee`. When an object is output using the `%s` format specifier, the object's `toString` method is invoked *implicitly* to obtain the object's String representation. [Note: In this chapter, we do not use the `earnings` method in each class, but it's used extensively in Chapter 10.]

---

```

1 // Fig. 9.5: CommissionEmployeeTest.java
2 // CommissionEmployee class test program.
3
4 public class CommissionEmployeeTest
5 {
6 public static void main(String[] args)
7 {
8 // instantiate CommissionEmployee object
9 CommissionEmployee employee = new CommissionEmployee(
10 "Sue", "Jones", "222-22-2222", 10000, .06);
11
12 // get commission employee data
13 System.out.println(
14 "Employee information obtained by get methods:");
15 System.out.printf("%n%s %s%n", "First name is",
16 employee.getFirstName());
17 System.out.printf("%s %s%n", "Last name is",
18 employee.getLastName());
19 System.out.printf("%s %s%n", "Social security number is",
20 employee.getSocialSecurityNumber());
21 System.out.printf("%s %.2f%n", "Gross sales is",
22 employee.getGrossSales());
23 System.out.printf("%s %.2f%n", "Commission rate is",
24 employee.getCommissionRate());
25
26 employee.setGrossSales(5000);
27 employee.setCommissionRate(.1);
28
29 System.out.printf("%n%s:%n%n%s%n",
30 "Updated employee information obtained by toString", employee);
31 } // end main
32 } // end class CommissionEmployeeTest

```

Employee information obtained by get methods:

```

First name is Sue
Last name is Jones
Social security number is 222-22-2222
Gross sales is 10000.00
Commission rate is 0.06

```

Updated employee information obtained by toString:

```

commission employee: Sue Jones
social security number: 222-22-2222
gross sales: 5000.00
commission rate: 0.10

```

**Fig. 9.5** | `CommissionEmployee` class test program.

### 9.4.2 Creating and Using a BasePlusCommissionEmployee Class

We now discuss the second part of our introduction to inheritance by declaring and testing (a completely new and independent) class `BasePlusCommissionEmployee` (Fig. 9.6), which contains a first name, last name, social security number, gross sales amount, commission rate *and* base salary. Class `BasePlusCommissionEmployee`'s public services include a `BasePlusCommissionEmployee` constructor (lines 15–42) and methods `earnings` (lines 111–114) and `toString` (lines 117–126). Lines 45–108 declare public *get* and *set* methods for the class's private instance variables (declared in lines 7–12) `firstName`, `lastName`, `socialSecurityNumber`, `grossSales`, `commissionRate` and `baseSalary`. These variables and methods encapsulate all the necessary features of a base-salaried commission employee. Note the *similarity* between this class and class `CommissionEmployee` (Fig. 9.4)—in this example, we'll not yet exploit that similarity.

---

```

1 // Fig. 9.6: BasePlusCommissionEmployee.java
2 // BasePlusCommissionEmployee class represents an employee who receives
3 // a base salary in addition to commission.
4
5 public class BasePlusCommissionEmployee
6 {
7 private final String firstName;
8 private final String lastName;
9 private final String socialSecurityNumber;
10 private double grossSales; // gross weekly sales
11 private double commissionRate; // commission percentage
12 private double baseSalary; // base salary per week
13
14 // six-argument constructor
15 public BasePlusCommissionEmployee(String firstName, String lastName,
16 String socialSecurityNumber, double grossSales,
17 double commissionRate, double baseSalary)
18 {
19 // implicit call to Object's default constructor occurs here
20
21 // if grossSales is invalid throw exception
22 if (grossSales < 0.0)
23 throw new IllegalArgumentException(
24 "Gross sales must be >= 0.0");
25
26 // if commissionRate is invalid throw exception
27 if (commissionRate <= 0.0 || commissionRate >= 1.0)
28 throw new IllegalArgumentException(
29 "Commission rate must be > 0.0 and < 1.0");
30
31 // if baseSalary is invalid throw exception
32 if (baseSalary < 0.0)
33 throw new IllegalArgumentException(
34 "Base salary must be >= 0.0");
35 }

```

---

**Fig. 9.6** | `BasePlusCommissionEmployee` class represents an employee who receives a base salary in addition to a commission. (Part I of 3.)

---

```
36 this.firstName = firstName;
37 this.lastName = lastName;
38 this.socialSecurityNumber = socialSecurityNumber;
39 this.grossSales = grossSales;
40 this.commissionRate = commissionRate;
41 this.baseSalary = baseSalary;
42 } // end constructor
43
44 // return first name
45 public String getFirstName()
46 {
47 return firstName;
48 }
49
50 // return last name
51 public String getLastName()
52 {
53 return lastName;
54 }
55
56 // return social security number
57 public String getSocialSecurityNumber()
58 {
59 return socialSecurityNumber;
60 }
61
62 // set gross sales amount
63 public void setGrossSales(double grossSales)
64 {
65 if (grossSales < 0.0)
66 throw new IllegalArgumentException(
67 "Gross sales must be >= 0.0");
68
69 this.grossSales = grossSales;
70 }
71
72 // return gross sales amount
73 public double getGrossSales()
74 {
75 return grossSales;
76 }
77
78 // set commission rate
79 public void setCommissionRate(double commissionRate)
80 {
81 if (commissionRate <= 0.0 || commissionRate >= 1.0)
82 throw new IllegalArgumentException(
83 "Commission rate must be > 0.0 and < 1.0");
84
85 this.commissionRate = commissionRate;
86 }
87
```

---

**Fig. 9.6** | BasePlusCommissionEmployee class represents an employee who receives a base salary in addition to a commission. (Part 2 of 3.)

---

```

88 // return commission rate
89 public double getCommissionRate()
90 {
91 return commissionRate;
92 }
93
94 // set base salary
95 public void setBaseSalary(double baseSalary)
96 {
97 if (baseSalary < 0.0)
98 throw new IllegalArgumentException(
99 "Base salary must be >= 0.0");
100
101 this.baseSalary = baseSalary;
102 }
103
104 // return base salary
105 public double getBaseSalary()
106 {
107 return baseSalary;
108 }
109
110 // calculate earnings
111 public double earnings()
112 {
113 return baseSalary + (commissionRate * grossSales);
114 }
115
116 // return String representation of BasePlusCommissionEmployee
117 @Override
118 public String toString()
119 {
120 return String.format(
121 "%s: %s %s%n%s: %s%n%s: %.2f%n%s: %.2f%n%s: %.2f",
122 "base-salaried commission employee", firstName, lastName,
123 "social security number", socialSecurityNumber,
124 "gross sales", grossSales, "commission rate", commissionRate,
125 "base salary", baseSalary);
126 }
127 } // end class BasePlusCommissionEmployee

```

---

**Fig. 9.6** | BasePlusCommissionEmployee class represents an employee who receives a base salary in addition to a commission. (Part 3 of 3.)

Class BasePlusCommissionEmployee does *not* specify “extends Object” in line 5, so the class *implicitly* extends Object. Also, like class CommissionEmployee’s constructor (lines 13–34 of Fig. 9.4), class BasePlusCommissionEmployee’s constructor invokes class Object’s default constructor *implicitly*, as noted in the comment in line 19.

Class BasePlusCommissionEmployee’s earnings method (lines 111–114) returns the result of adding the BasePlusCommissionEmployee’s base salary to the product of the commission rate and the employee’s gross sales.

Class BasePlusCommissionEmployee overrides Object method toString to return a String containing the BasePlusCommissionEmployee’s information. Once again, we use

format specifier `%.2f` to format the gross sales, commission rate and base salary with two digits of precision to the right of the decimal point (line 121).

### Testing Class *BasePlusCommissionEmployee*

Figure 9.7 tests class *BasePlusCommissionEmployee*. Lines 9–11 create a *BasePlusCommissionEmployee* object and pass "Bob", "Lewis", "333-33-3333", 5000, .04 and 300 to the constructor as the first name, last name, social security number, gross sales, commission rate and base salary, respectively. Lines 16–27 use *BasePlusCommissionEmployee*'s *get* methods to retrieve the values of the object's instance variables for output. Line 29 invokes the object's *setBaseSalary* method to change the base salary. Method *setBaseSalary* (Fig. 9.6, lines 95–102) ensures that instance variable *baseSalary* is not assigned a negative value. Line 33 of Fig. 9.7 invokes method *toString* *explicitly* to get the object's String representation.

---

```

1 // Fig. 9.7: BasePlusCommissionEmployeeTest.java
2 // BasePlusCommissionEmployee test program.
3
4 public class BasePlusCommissionEmployeeTest
5 {
6 public static void main(String[] args)
7 {
8 // instantiate BasePlusCommissionEmployee object
9 BasePlusCommissionEmployee employee =
10 new BasePlusCommissionEmployee(
11 "Bob", "Lewis", "333-33-3333", 5000, .04, 300);
12
13 // get base-salaried commission employee data
14 System.out.println(
15 "Employee information obtained by get methods:\n");
16 System.out.printf("%s %s\n", "First name is",
17 employee.getFirstName());
18 System.out.printf("%s %s\n", "Last name is",
19 employee.getLastName());
20 System.out.printf("%s %s\n", "Social security number is",
21 employee.getSocialSecurityNumber());
22 System.out.printf("%s %.2f\n", "Gross sales is",
23 employee.getGrossSales());
24 System.out.printf("%s %.2f\n", "Commission rate is",
25 employee.getCommissionRate());
26 System.out.printf("%s %.2f\n", "Base salary is",
27 employee.getBaseSalary());
28
29 employee.setBaseSalary(1000);
30
31 System.out.printf("%n%s:\n%n%s\n",
32 "Updated employee information obtained by toString",
33 employee.toString());
34 } // end main
35 } // end class BasePlusCommissionEmployeeTest

```

---

**Fig. 9.7** | *BasePlusCommissionEmployee* test program. (Part I of 2.)

```
Employee information obtained by get methods:

First name is Bob
Last name is Lewis
Social security number is 333-33-3333
Gross sales is 5000.00
Commission rate is 0.04
Base salary is 300.00

Updated employee information obtained by toString:

base-salaried commission employee: Bob Lewis
social security number: 333-33-3333
gross sales: 5000.00
commission rate: 0.04
base salary: 1000.00
```

**Fig. 9.7** | BasePlusCommissionEmployee test program. (Part 2 of 2.)

### **Notes on Class BasePlusCommissionEmployee**

Much of class BasePlusCommissionEmployee's code (Fig. 9.6) is *similar*, or *identical*, to that of class CommissionEmployee (Fig. 9.4). For example, private instance variables firstName and lastName and methods setFirstName, getFirstName, setLastName and getLastName are identical to those of class CommissionEmployee. The classes also both contain private instance variables socialSecurityNumber, commissionRate and grossSales, and corresponding *get* and *set* methods. In addition, the BasePlusCommissionEmployee constructor is *almost* identical to that of class CommissionEmployee, except that BasePlusCommissionEmployee's constructor also sets the baseSalary. The other additions to class BasePlusCommissionEmployee are private instance variable baseSalary and methods setBaseSalary and getBaseSalary. Class BasePlusCommissionEmployee's toString method is *almost* identical to that of class CommissionEmployee except that it also outputs instance variable baseSalary with two digits of precision to the right of the decimal point.

We literally *copied* code from class CommissionEmployee and *pasted* it into class BasePlusCommissionEmployee, then modified class BasePlusCommissionEmployee to include a base salary and methods that manipulate the base salary. This “*copy-and-paste*” approach is often error prone and time consuming. Worse yet, it spreads copies of the same code throughout a system, creating code-maintenance problems—changes to the code would need to be made in multiple classes. Is there a way to “acquire” the instance variables and methods of one class in a way that makes them part of other classes *without duplicating code*? Next we answer this question, using a more elegant approach to building classes that emphasizes the benefits of inheritance.



### **Software Engineering Observation 9.3**

*With inheritance, the instance variables and methods that are the same for all the classes in the hierarchy are declared in a superclass. Changes made to these common features in the superclass are inherited by the subclass. Without inheritance, changes would need to be made to all the source-code files that contain a copy of the code in question.*

### 9.4.3 Creating a CommissionEmployee-BasePlusCommissionEmployee Inheritance Hierarchy

Now we declare class `BasePlusCommissionEmployee` (Fig. 9.8) to *extend* class `CommissionEmployee` (Fig. 9.4). A `BasePlusCommissionEmployee` object *is a* `CommissionEmployee`, because inheritance passes on class `CommissionEmployee`'s capabilities. Class `BasePlusCommissionEmployee` also has instance variable `baseSalary` (Fig. 9.8, line 6). Keyword `extends` (line 4) indicates inheritance. `BasePlusCommissionEmployee` *inherits* `CommissionEmployee`'s instance variables and methods.



#### Software Engineering Observation 9.4

*At the design stage in an object-oriented system, you'll often find that certain classes are closely related. You should "factor out" common instance variables and methods and place them in a superclass. Then use inheritance to develop subclasses, specializing them with capabilities beyond those inherited from the superclass.*



#### Software Engineering Observation 9.5

*Declaring a subclass does not affect its superclass's source code. Inheritance preserves the integrity of the superclass.*

Only `CommissionEmployee`'s public and protected members are directly accessible in the subclass. The `CommissionEmployee` constructor is *not* inherited. So, the public `BasePlusCommissionEmployee` services include its constructor (lines 9–23), public methods inherited from `CommissionEmployee`, and methods `setBaseSalary` (lines 26–33), `getBaseSalary` (lines 36–39), `earnings` (lines 42–47) and `toString` (lines 50–60). Methods `earnings` and `toString` *override* the corresponding methods in class `CommissionEmployee` because their superclass versions do not properly calculate a `BasePlusCommissionEmployee`'s earnings or return an appropriate `String` representation, respectively.

---

```

1 // Fig. 9.8: BasePlusCommissionEmployee.java
2 // private superclass members cannot be accessed in a subclass.
3
4 public class BasePlusCommissionEmployee extends CommissionEmployee
5 {
6 private double baseSalary; // base salary per week
7
8 // six-argument constructor
9 public BasePlusCommissionEmployee(String firstName, String lastName,
10 String socialSecurityNumber, double grossSales,
11 double commissionRate, double baseSalary)
12 {
13 // explicit call to superclass CommissionEmployee constructor
14 super(firstName, lastName, socialSecurityNumber,
15 grossSales, commissionRate);
16
17 // if baseSalary is invalid throw exception
18 if (baseSalary < 0.0)
19 throw new IllegalArgumentException(
20 "Base salary must be >= 0.0");
21

```

---

**Fig. 9.8** | private superclass members cannot be accessed in a subclass. (Part I of 3.)



```

22 this.baseSalary = baseSalary;
23 }
24
25 // set base salary
26 public void setBaseSalary(double baseSalary)
27 {
28 if (baseSalary < 0.0)
29 throw new IllegalArgumentException(
30 "Base salary must be >= 0.0");
31
32 this.baseSalary = baseSalary;
33 }
34
35 // return base salary
36 public double getBaseSalary()
37 {
38 return baseSalary;
39 }
40
41 // calculate earnings
42 @Override
43 public double earnings()
44 {
45 // not allowed: commissionRate and grossSales private in superclass
46 return baseSalary + (commissionRate * grossSales);
47 }
48
49 // return String representation of BasePlusCommissionEmployee
50 @Override
51 public String toString()
52 {
53 // not allowed: attempts to access private superclass members
54 return String.format(
55 "%s: %s %s%n%s: %s%n%s: %.2f%n%s: %.2f%n%s: %.2f",
56 "base-salaried commission employee", firstName, lastName,
57 "social security number", socialSecurityNumber,
58 "gross sales", grossSales, "commission rate", commissionRate,
59 "base salary", baseSalary);
60 }
61 } // end class BasePlusCommissionEmployee

```

BasePlusCommissionEmployee.java:46: error: commissionRate has private access in CommissionEmployee

```

 return baseSalary + (commissionRate * grossSales);
 ^

```

BasePlusCommissionEmployee.java:46: error: grossSales has private access in CommissionEmployee

```

 return baseSalary + (commissionRate * grossSales);
 ^

```

BasePlusCommissionEmployee.java:56: error: firstName has private access in CommissionEmployee

```

 "base-salaried commission employee", firstName, lastName,
 ^

```

**Fig. 9.8** | private superclass members cannot be accessed in a subclass. (Part 2 of 3.)

```

BasePlusCommissionEmployee.java:56: error: lastName has private access in Com-
missionEmployee
 "base-salaried commission employee", firstName, lastName,
 ^
BasePlusCommissionEmployee.java:57: error: socialSecurityNumber has private
access in CommissionEmployee
 "social security number", socialSecurityNumber,
 ^
BasePlusCommissionEmployee.java:58: error: grossSales has private access in
CommissionEmployee
 "gross sales", grossSales, "commission rate", commissionRate,
 ^
BasePlusCommissionEmployee.java:58: error: commissionRate has private access
inCommissionEmployee
 "gross sales", grossSales, "commission rate", commissionRate,
 ^

```

**Fig. 9.8** | private superclass members cannot be accessed in a subclass. (Part 3 of 3.)

### *A Subclass's Constructor Must Call Its Superclass's Constructor*

Each subclass constructor must implicitly or explicitly call one of its superclass's constructors to initialize the instance variables inherited from the superclass. Lines 14–15 in `BasePlusCommissionEmployee`'s six-argument constructor (lines 9–23) explicitly call class `CommissionEmployee`'s five-argument constructor (declared at lines 13–34 of Fig. 9.4) to initialize the superclass portion of a `BasePlusCommissionEmployee` object (i.e., variables `firstName`, `lastName`, `socialSecurityNumber`, `grossSales` and `commissionRate`). We do this by using the **superclass constructor call syntax**—keyword `super`, followed by a set of parentheses containing the superclass constructor arguments, which are used to initialize the superclass instance variables `firstName`, `lastName`, `socialSecurityNumber`, `grossSales` and `commissionRate`, respectively. If `BasePlusCommissionEmployee`'s constructor did not invoke the superclass's constructor explicitly, the compiler would attempt to insert a call to the superclass's default or no-argument constructor. Class `CommissionEmployee` does not have such a constructor, so the compiler would issue an error. The explicit superclass constructor call in lines 14–15 of Fig. 9.8 must be the *first* statement in the constructor's body. When a superclass contains a no-argument constructor, you can use `super()` to call that constructor explicitly, but this is rarely done.



### **Software Engineering Observation 9.6**

*You learned previously that you should not call a class's instance methods from its constructors and that we'll say why in Chapter 10. Calling a superclass constructor from a subclass constructor does not contradict this advice.*

### ***BasePlusCommissionEmployee Methods Earnings and toString***

The compiler generates errors for line 46 (Fig. 9.8) because `CommissionEmployee`'s instance variables `commissionRate` and `grossSales` are private—subclass `BasePlusCommissionEmployee`'s methods are *not* allowed to access superclass `CommissionEmployee`'s private instance variables. The compiler issues additional errors at lines 56–58 of `BasePlusCommissionEmployee`'s `toString` method for the same reason. The errors in `BasePlusCommissionEmployee` could have been prevented by using the *get* methods inherited from class `CommissionEmployee`. For example, line 46 could have called `getCommis-`

sionRate and getGrossSales to access `CommissionEmployee`'s private instance variables `commissionRate` and `grossSales`, respectively. Lines 56–58 also could have used appropriate *get* methods to retrieve the values of the superclass's instance variables.

#### 9.4.4 `CommissionEmployee`–`BasePlusCommissionEmployee` Inheritance Hierarchy Using protected Instance Variables

To enable class `BasePlusCommissionEmployee` to directly access superclass instance variables `firstName`, `lastName`, `socialSecurityNumber`, `grossSales` and `commissionRate`, we can declare those members as `protected` in the superclass. As we discussed in Section 9.3, a superclass's `protected` members are accessible by all subclasses of that superclass. In the new `CommissionEmployee` class, we modified only lines 6–10 of Fig. 9.4 to declare the instance variables with the `protected` access modifier as follows:

```
protected final String firstName;
protected final String lastName;
protected final String socialSecurityNumber;
protected double grossSales; // gross weekly sales
protected double commissionRate; // commission percentage
```

The rest of the class declaration (which is not shown here) is identical to that of Fig. 9.4.

We could have declared `CommissionEmployee`'s instance variables `public` to enable subclass `BasePlusCommissionEmployee` to access them. However, declaring `public` instance variables is poor software engineering because it allows unrestricted access to these variables from any class, greatly increasing the chance of errors. With `protected` instance variables, the subclass gets access to the instance variables, but classes that are not subclasses and classes that are not in the same package cannot access these variables directly—recall that `protected` class members are also visible to other classes in the same package.

#### *Class `BasePlusCommissionEmployee`*

Class `BasePlusCommissionEmployee` (Fig. 9.9) extends the new version of class `CommissionEmployee` with `protected` instance variables. `BasePlusCommissionEmployee` objects inherit `CommissionEmployee`'s `protected` instance variables `firstName`, `lastName`, `socialSecurityNumber`, `grossSales` and `commissionRate`—all these variables are now `protected` members of `BasePlusCommissionEmployee`. As a result, the compiler does not generate errors when compiling line 45 of method `earnings` and lines 54–56 of method `toString`. If another class extends this version of class `BasePlusCommissionEmployee`, the new subclass also can access the `protected` members.

---

```
1 // Fig. 9.9: BasePlusCommissionEmployee.java
2 // BasePlusCommissionEmployee inherits protected instance
3 // variables from CommissionEmployee.
4
5 public class BasePlusCommissionEmployee extends CommissionEmployee
6 {
7 private double baseSalary; // base salary per week
```

---

**Fig. 9.9** | `BasePlusCommissionEmployee` inherits `protected` instance variables from `CommissionEmployee`. (Part 1 of 2.)

---

```

8
9 // six-argument constructor
10 public BasePlusCommissionEmployee(String firstName, String lastName,
11 String socialSecurityNumber, double grossSales,
12 double commissionRate, double baseSalary)
13 {
14 super(firstName, lastName, socialSecurityNumber,
15 grossSales, commissionRate);
16
17 // if baseSalary is invalid throw exception
18 if (baseSalary < 0.0)
19 throw new IllegalArgumentException(
20 "Base salary must be >= 0.0");
21
22 this.baseSalary = baseSalary;
23 }
24
25 // set base salary
26 public void setBaseSalary(double baseSalary)
27 {
28 if (baseSalary < 0.0)
29 throw new IllegalArgumentException(
30 "Base salary must be >= 0.0");
31
32 this.baseSalary = baseSalary;
33 }
34
35 // return base salary
36 public double getBaseSalary()
37 {
38 return baseSalary;
39 }
40
41 // calculate earnings
42 @Override // indicates that this method overrides a superclass method
43 public double earnings()
44 {
45 return baseSalary + (commissionRate * grossSales);
46 }
47
48 // return String representation of BasePlusCommissionEmployee
49 @Override
50 public String toString()
51 {
52 return String.format(
53 "%s: %s %s%n%s: %s%n%s: %.2f%n%s: %.2f%n%s: %.2f",
54 "base-salaried commission employee", firstName, lastName,
55 "social security number", socialSecurityNumber,
56 "gross sales", grossSales, "commission rate", commissionRate,
57 "base salary", baseSalary);
58 }
59 } // end class BasePlusCommissionEmployee

```

---

**Fig. 9.9** | BasePlusCommissionEmployee inherits protected instance variables from CommissionEmployee. (Part 2 of 2.)

*A Subclass Object Contains the Instance Variables of All of Its Superclasses*

When you create a `BasePlusCommissionEmployee` object, it contains all instance variables declared in the class hierarchy to that point—that is, those from classes `Object` (which does not have instance variables), `CommissionEmployee` and `BasePlusCommissionEmployee`. Class `BasePlusCommissionEmployee` does *not* inherit `CommissionEmployee`'s five-argument constructor, but *explicitly invokes* it (lines 14–15) to initialize the instance variables that `BasePlusCommissionEmployee` inherited from `CommissionEmployee`. Similarly, `CommissionEmployee`'s constructor *implicitly* calls class `Object`'s constructor. `BasePlusCommissionEmployee`'s constructor must *explicitly* call `CommissionEmployee`'s constructor because `CommissionEmployee` does *not* have a no-argument constructor that could be invoked implicitly.

*Testing Class BasePlusCommissionEmployee*

The `BasePlusCommissionEmployeeTest` class for this example is identical to that of Fig. 9.7 and produces the same output, so we do not show it here. Although the version of class `BasePlusCommissionEmployee` in Fig. 9.6 does not use inheritance and the version in Fig. 9.9 does, both classes provide the *same* functionality. The source code in Fig. 9.9 (59 lines) is considerably shorter than that in Fig. 9.6 (127 lines), because most of the class's functionality is now inherited from `CommissionEmployee`—there's now only one copy of the `CommissionEmployee` functionality. This makes the code easier to maintain, modify and debug, because the code related to a `CommissionEmployee` exists only in that class.

*Notes on Using protected Instance Variables*

In this example, we declared superclass instance variables as `protected` so that subclasses could access them. Inheriting `protected` instance variables enables direct access to the variables by subclasses. In most cases, however, it's better to use `private` instance variables to encourage proper software engineering. Your code will be easier to maintain, modify and debug.

Using `protected` instance variables creates several potential problems. First, the subclass object can set an inherited variable's value directly without using a `set` method. Therefore, a subclass object can assign an invalid value to the variable, possibly leaving the object in an inconsistent state. For example, if we were to declare `CommissionEmployee`'s instance variable `grossSales` as `protected`, a subclass object (e.g., `BasePlusCommissionEmployee`) could then assign a negative value to `grossSales`. Another problem with using `protected` instance variables is that subclass methods are more likely to be written so that they depend on the superclass's data implementation. In practice, subclasses should depend only on the superclass services (i.e., non-private methods) and not on the superclass data implementation. With `protected` instance variables in the superclass, we may need to modify all the subclasses of the superclass if the superclass implementation changes. For example, if for some reason we were to change the names of instance variables `firstName` and `lastName` to `first` and `last`, then we would have to do so for all occurrences in which a subclass directly references superclass instance variables `firstName` and `lastName`. Such a class is said to be **fragile** or **brittle**, because a small change in the superclass can “break” subclass implementation. You should be able to change the superclass implementation while still providing the same services to the subclasses. Of course, if the superclass services change, we must reimplement our subclasses. A third problem is that a class's `protected` members

are visible to all classes in the same package as the class containing the protected members—this is not always desirable.



### Software Engineering Observation 9.7

*Use the protected access modifier when a superclass should provide a method only to its subclasses and other classes in the same package, but not to other clients.*



### Software Engineering Observation 9.8

*Declaring superclass instance variables `private` (as opposed to `protected`) enables the superclass implementation of these instance variables to change without affecting subclass implementations.*



### Error-Prevention Tip 9.2

*When possible, do not include protected instance variables in a superclass. Instead, include non-private methods that access private instance variables. This will help ensure that objects of the class maintain consistent states.*

## 9.4.5 CommissionEmployee–BasePlusCommissionEmployee Inheritance Hierarchy Using `private` Instance Variables

Let's reexamine our hierarchy once more, this time using good software engineering practices.

### Class *CommissionEmployee*

Class *CommissionEmployee* (Fig. 9.10) declares instance variables `firstName`, `lastName`, `socialSecurityNumber`, `grossSales` and `commissionRate` as *private* (lines 6–10) and provides public methods `getFirstName`, `getLastName`, `getSocialSecurityNumber`, `setGrossSales`, `getGrossSales`, `setCommissionRate`, `getCommissionRate`, `earnings` and `toString` for manipulating these values. Methods `earnings` (lines 87–90) and `toString` (lines 93–101) use the class's *get* methods to obtain the values of its instance variables. If we decide to change the names of the instance variables, the `earnings` and `toString` declarations will *not* require modification—only the bodies of the *get* and *set* methods that directly manipulate the instance variables will need to change. These changes occur solely within the superclass—no changes to the subclass are needed. *Localizing the effects of changes* like this is a good software engineering practice.

```

1 // Fig. 9.10: CommissionEmployee.java
2 // CommissionEmployee class uses methods to manipulate its
3 // private instance variables.
4 public class CommissionEmployee
5 {
6 private final String firstName;
7 private final String lastName;
8 private final String socialSecurityNumber;
9 private double grossSales; // gross weekly sales
10 private double commissionRate; // commission percentage

```

**Fig. 9.10** | *CommissionEmployee* class uses methods to manipulate its private instance variables. (Part 1 of 3.)

```
11
12 // five-argument constructor
13 public CommissionEmployee(String firstName, String lastName,
14 String socialSecurityNumber, double grossSales,
15 double commissionRate)
16 {
17 // implicit call to Object constructor occurs here
18
19 // if grossSales is invalid throw exception
20 if (grossSales < 0.0)
21 throw new IllegalArgumentException(
22 "Gross sales must be >= 0.0");
23
24 // if commissionRate is invalid throw exception
25 if (commissionRate <= 0.0 || commissionRate >= 1.0)
26 throw new IllegalArgumentException(
27 "Commission rate must be > 0.0 and < 1.0");
28
29 this.firstName = firstName;
30 this.lastName = lastName;
31 this.socialSecurityNumber = socialSecurityNumber;
32 this.grossSales = grossSales;
33 this.commissionRate = commissionRate;
34 } // end constructor
35
36 // return first name
37 public String getFirstName()
38 {
39 return firstName;
40 }
41
42 // return last name
43 public String getLastName()
44 {
45 return lastName;
46 }
47
48 // return social security number
49 public String getSocialSecurityNumber()
50 {
51 return socialSecurityNumber;
52 }
53
54 // set gross sales amount
55 public void setGrossSales(double grossSales)
56 {
57 if (grossSales < 0.0)
58 throw new IllegalArgumentException(
59 "Gross sales must be >= 0.0");
60
61 this.grossSales = grossSales;
62 }
```

**Fig. 9.10** | CommissionEmployee class uses methods to manipulate its private instance variables. (Part 2 of 3.)

---

```

63
64 // return gross sales amount
65 public double getGrossSales()
66 {
67 return grossSales;
68 }
69
70 // set commission rate
71 public void setCommissionRate(double commissionRate)
72 {
73 if (commissionRate <= 0.0 || commissionRate >= 1.0)
74 throw new IllegalArgumentException(
75 "Commission rate must be > 0.0 and < 1.0");
76
77 this.commissionRate = commissionRate;
78 }
79
80 // return commission rate
81 public double getCommissionRate()
82 {
83 return commissionRate;
84 }
85
86 // calculate earnings
87 public double earnings()
88 {
89 return getCommissionRate() * getGrossSales();
90 }
91
92 // return String representation of CommissionEmployee object
93 @Override
94 public String toString()
95 {
96 return String.format("%s: %s %s%n%s: %s%n%s: %.2f%n%s: %.2f",
97 "commission employee", getFirstName(), getLastName(),
98 "social security number", getSocialSecurityNumber(),
99 "gross sales", getGrossSales(),
100 "commission rate", getCommissionRate());
101 }
102 } // end class CommissionEmployee

```

---

**Fig. 9.10** | CommissionEmployee class uses methods to manipulate its private instance variables. (Part 3 of 3.)

### *Class BasePlusCommissionEmployee*

Subclass *BasePlusCommissionEmployee* (Fig. 9.11) inherits *CommissionEmployee*'s non-private methods and can access (in a controlled way) the private superclass members via those methods. Class *BasePlusCommissionEmployee* has several changes that distinguish it from Fig. 9.9. Methods *earnings* (lines 43–47) and *toString* (lines 50–55) each invoke method *getBaseSalary* to obtain the base salary value, rather than accessing *baseSalary* directly. If we decide to rename instance variable *baseSalary*, only the bodies of method *setBaseSalary* and *getBaseSalary* will need to change.



---

```

1 // Fig. 9.11: BasePlusCommissionEmployee.java
2 // BasePlusCommissionEmployee class inherits from CommissionEmployee
3 // and accesses the superclass's private data via inherited
4 // public methods.
5
6 public class BasePlusCommissionEmployee extends CommissionEmployee
7 {
8 private double baseSalary; // base salary per week
9
10 // six-argument constructor
11 public BasePlusCommissionEmployee(String firstName, String lastName,
12 String socialSecurityNumber, double grossSales,
13 double commissionRate, double baseSalary)
14 {
15 super(firstName, lastName, socialSecurityNumber,
16 grossSales, commissionRate);
17
18 // if baseSalary is invalid throw exception
19 if (baseSalary < 0.0)
20 throw new IllegalArgumentException(
21 "Base salary must be >= 0.0");
22
23 this.baseSalary = baseSalary;
24 }
25
26 // set base salary
27 public void setBaseSalary(double baseSalary)
28 {
29 if (baseSalary < 0.0)
30 throw new IllegalArgumentException(
31 "Base salary must be >= 0.0");
32
33 this.baseSalary = baseSalary;
34 }
35
36 // return base salary
37 public double getBaseSalary()
38 {
39 return baseSalary;
40 }
41
42 // calculate earnings
43 @Override
44 public double earnings()
45 {
46 return getBaseSalary() + super.earnings();
47 }
48
49 // return String representation of BasePlusCommissionEmployee
50 @Override
51 public String toString()
52 {

```

---

**Fig. 9.11** | BasePlusCommissionEmployee class inherits from CommissionEmployee and accesses the superclass's private data via inherited public methods. (Part 1 of 2.)

```

53 return String.format("%s %s\n%s: %.2f", "base-salaried",
54 super.toString(), "base salary", getBaseSalary());
55 }
56 } // end class BasePlusCommissionEmployee

```

**Fig. 9.11** | BasePlusCommissionEmployee class inherits from CommissionEmployee and accesses the superclass's private data via inherited public methods. (Part 2 of 2.)

### *Class BasePlusCommissionEmployee's earnings Method*

Method earnings (lines 43–47) overrides class CommissionEmployee's earnings method (Fig. 9.10, lines 87–90) to calculate a base-salaried commission employee's earnings. The new version obtains the portion of the earnings based on commission alone by calling CommissionEmployee's earnings method with super.earnings() (line 46), then adds the base salary to this value to calculate the total earnings. Note the syntax used to invoke an *overridden* superclass method from a subclass—place the keyword super and a dot (.) separator before the superclass method name. This method invocation is a good software engineering practice—if a method performs all or some of the actions needed by another method, call that method rather than duplicate its code. By having BasePlusCommissionEmployee's earnings method invoke CommissionEmployee's earnings method to calculate part of a BasePlusCommissionEmployee object's earnings, we *avoid duplicating the code and reduce code-maintenance problems*.



### **Common Programming Error 9.2**

*When a superclass method is overridden in a subclass, the subclass version often calls the superclass version to do a portion of the work. Failure to prefix the superclass method name with the keyword super and the dot (.) separator when calling the superclass's method causes the subclass method to call itself, potentially creating an error called infinite recursion, which would eventually cause the method-call stack to overflow—a fatal runtime error. Recursion, used correctly, is a powerful capability discussed in Chapter 18.*

### *Class BasePlusCommissionEmployee's toString Method*

Similarly, BasePlusCommissionEmployee's toString method (Fig. 9.11, lines 50–55) overrides CommissionEmployee's toString method (Fig. 9.10, lines 93–101) to return a String representation that's appropriate for a base-salaried commission employee. The new version creates part of a BasePlusCommissionEmployee object's String representation (i.e., the String "commission employee" and the values of class CommissionEmployee's private instance variables) by calling CommissionEmployee's toString method with the expression super.toString() (Fig. 9.11, line 54). BasePlusCommissionEmployee's toString method then completes the remainder of a BasePlusCommissionEmployee object's String representation (i.e., the value of class BasePlusCommissionEmployee's base salary).

### *Testing Class BasePlusCommissionEmployee*

Class BasePlusCommissionEmployeeTest performs the same manipulations on a BasePlusCommissionEmployee object as in Fig. 9.7 and produces the same output, so we do not show it here. Although each BasePlusCommissionEmployee class you've seen behaves identically, the version in Fig. 9.11 is the best engineered. By using inheritance and by calling methods that hide the data and ensure consistency, we've efficiently and effectively constructed a well-engineered class.

## 9.5 Constructors in Subclasses

As we explained, instantiating a subclass object begins a chain of constructor calls in which the subclass constructor, before performing its own tasks, explicitly uses `super` to call one of the constructors in its direct superclass or implicitly calls the superclass's default or no-argument constructor. Similarly, if the superclass is derived from another class—true of every class except `Object`—the superclass constructor invokes the constructor of the next class up the hierarchy, and so on. The last constructor called in the chain is *always* `Object`'s constructor. The original subclass constructor's body finishes executing *last*. Each superclass's constructor manipulates the superclass instance variables that the subclass object inherits. For example, consider again the `CommissionEmployee`–`BasePlusCommissionEmployee` hierarchy from Figs. 9.10–9.11. When an app creates a `BasePlusCommissionEmployee` object, its constructor is called. That constructor calls `CommissionEmployee`'s constructor, which in turn calls `Object`'s constructor. Class `Object`'s constructor has an *empty body*, so it immediately returns control to `CommissionEmployee`'s constructor, which then initializes the `CommissionEmployee` instance variables that are part of the `BasePlusCommissionEmployee` object. When `CommissionEmployee`'s constructor completes execution, it returns control to `BasePlusCommissionEmployee`'s constructor, which initializes the `baseSalary`.



### Software Engineering Observation 9.9

*Java ensures that even if a constructor does not assign a value to an instance variable, the variable is still initialized to its default value (e.g., 0 for primitive numeric types, false for booleans, null for references).*

## 9.6 Class Object

As we discussed earlier in this chapter, all classes in Java inherit directly or indirectly from class `Object` (package `java.lang`), so its 11 methods (some are overloaded) are inherited by all other classes. Figure 9.12 summarizes `Object`'s methods. We discuss several `Object` methods throughout this book (as indicated in Fig. 9.12).

| Method                | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |
|-----------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>equals</code>   | This method compares two objects for equality and returns <code>true</code> if they're equal and <code>false</code> otherwise. The method takes any <code>Object</code> as an argument. When objects of a particular class must be compared for equality, the class should override method <code>equals</code> to compare the <i>contents</i> of the two objects. For the requirements of implementing this method (which include also overriding method <code>hashCode</code> ), refer to the method's documentation at <a href="https://docs.oracle.com/javase/7/docs/api/java/lang/Object.html#equals(java.lang.Object)">docs.oracle.com/javase/7/docs/api/java/lang/Object.html#equals(java.lang.Object)</a> . The default <code>equals</code> implementation uses operator <code>==</code> to determine whether two references <i>refer to the same object</i> in memory. Section 14.3.3 demonstrates class <code>String</code> 's <code>equals</code> method and differentiates between comparing <code>String</code> objects with <code>==</code> and with <code>equals</code> . |
| <code>hashCode</code> | Hashcodes are <code>int</code> values used for high-speed storage and retrieval of information stored in a data structure that's known as a hashtable (see Section 16.11). This method is also called as part of <code>Object</code> 's default <code>toString</code> method implementation.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |

**Fig. 9.12** | `Object` methods. (Part I of 2.)

| Method                                                              | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |
|---------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>toString</code>                                               | This method (introduced in Section 9.4.1) returns a <code>String</code> representation of an object. The default implementation of this method returns the package name and class name of the object's class typically followed by a hexadecimal representation of the value returned by the object's <code>hashCode</code> method.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |
| <code>wait</code> , <code>notify</code> ,<br><code>notifyAll</code> | Methods <code>notify</code> , <code>notifyAll</code> and the three overloaded versions of <code>wait</code> are related to multithreading, which is discussed in Chapter 23.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |
| <code>getClass</code>                                               | Every object in Java knows its own type at execution time. Method <code>getClass</code> (used in Sections 10.5– and 12.5) returns an object of class <code>Class</code> (package <code>java.lang</code> ) that contains information about the object's type, such as its class name (returned by <code>Class</code> method <code>getName</code> ).                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |
| <code>finalize</code>                                               | This protected method is called by the garbage collector to perform termination housekeeping on an object just before the garbage collector reclaims the object's memory. Recall from Section 8.10 that it's unclear whether, or when, <code>finalize</code> will be called. For this reason, most programmers should avoid method <code>finalize</code> .                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |
| <code>clone</code>                                                  | This protected method, which takes no arguments and returns an <code>Object</code> reference, makes a copy of the object on which it's called. The default implementation performs a so-called <b>shallow copy</b> —instance-variable values in one object are copied into another object of the same type. For reference types, only the references are copied. A typical overridden <code>clone</code> method's implementation would perform a <b>deep copy</b> that creates a new object for each reference-type instance variable. <i>Implementing <code>clone</code> correctly is difficult. For this reason, its use is discouraged.</i> Some industry experts suggest that object serialization should be used instead. We discuss object serialization in Chapter 15. Recall from Chapter 7 that arrays are objects. As a result, like all other objects, arrays inherit the members of class <code>Object</code> . Every array has an overridden <code>clone</code> method that copies the array. However, if the array stores references to objects, the objects are not copied—a shallow copy is performed. |

Fig. 9.12 | Object methods. (Part 2 of 2.)

## 9.7 (Optional) GUI and Graphics Case Study: Displaying Text and Images Using Labels

Programs often use labels when they need to display information or instructions to the user in a graphical user interface. **Labels** are a convenient way of identifying GUI components on the screen and keeping the user informed about the current state of the program. In Java, an object of class `JLabel` (from package `javax.swing`) can display text, an image or both. The example in Fig. 9.13 demonstrates several `JLabel` features, including a plain text label, an image label and a label with both text and an image.

---

```

1 // Fig 9.13: LabelDemo.java
2 // Demonstrates the use of labels.
3 import java.awt.BorderLayout;
4 import javax.swing.ImageIcon;

```


---

Fig. 9.13 | `JLabel` with text and with images. (Part 1 of 2.)

```

5 import javax.swing.JLabel;
6 import javax.swing.JFrame;
7
8 public class LabelDemo
9 {
10 public static void main(String[] args)
11 {
12 // Create a label with plain text
13 JLabel northLabel = new JLabel("North");
14
15 // create an icon from an image so we can put it on a JLabel
16 ImageIcon labelIcon = new ImageIcon("GUItip.gif");
17
18 // create a label with an Icon instead of text
19 JLabel centerLabel = new JLabel(labelIcon);
20
21 // create another label with an Icon
22 JLabel southLabel = new JLabel(labelIcon);
23
24 // set the label to display text (as well as an icon)
25 southLabel.setText("South");
26
27 // create a frame to hold the labels
28 JFrame application = new JFrame();
29
30 application.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
31
32 // add the labels to the frame; the second argument specifies
33 // where on the frame to add the label
34 application.add(northLabel, BorderLayout.NORTH);
35 application.add(centerLabel, BorderLayout.CENTER);
36 application.add(southLabel, BorderLayout.SOUTH);
37
38 application.setSize(300, 300);
39 application.setVisible(true);
40 } // end main
41 } // end class LabelDemo

```



**Fig. 9.13** | JLabel with text and with images. (Part 2 of 2.)

Lines 3–6 import the classes we need to display JLabels. BorderLayout from package java.awt contains constants that specify where we can place GUI components in the


JFrame. Class **ImageIcon** represents an image that can be displayed on a **JLabel**, and class **JFrame** represents the window that will contain all the labels.

Line 13 creates a **JLabel** that displays its constructor argument—the string "North". Line 16 declares local variable `labelIcon` and assigns it a new **ImageIcon**. The constructor for **ImageIcon** receives a **String** that specifies the path to the image. Since we specify only a filename, Java assumes that it's in the same directory as class **LabelDemo**. **ImageIcon** can load images in GIF, JPEG and PNG image formats. Line 19 declares and initializes local variable `centerLabel` with a **JLabel** that displays the `labelIcon`. Line 22 declares and initializes local variable `southLabel` with a **JLabel** similar to the one in line 19. However, line 25 calls method **setText** to change the text the label displays. Method **setText** can be called on any **JLabel** to change its text. This **JLabel** displays both the icon and the text.

Line 28 creates the **JFrame** that displays the **JLabels**, and line 30 indicates that the program should terminate when the **JFrame** is closed. We attach the labels to the **JFrame** in lines 34–36 by calling an overloaded version of method **add** that takes two parameters. The first parameter is the component we want to attach, and the second is the region in which it should be placed. Each **JFrame** has an associated **layout** that helps the **JFrame** position the GUI components that are attached to it. The default layout for a **JFrame** is known as a **BorderLayout** and has five regions—**NORTH** (top), **SOUTH** (bottom), **EAST** (right side), **WEST** (left side) and **CENTER**. Each of these is declared as a constant in class **BorderLayout**. When calling method **add** with one argument, the **JFrame** places the component in the **CENTER** automatically. If a position already contains a component, then the new component takes its place. Lines 38 and 39 set the size of the **JFrame** and make it visible on screen.

### GUI and Graphics Case Study Exercise

**9.1** Modify GUI and Graphics Case Study Exercise 8.1 to include a **JLabel** as a status bar that displays counts representing the number of each shape displayed. Class **DrawPanel** should declare a method that returns a **String** containing the status text. In **main**, first create the **DrawPanel**, then create the **JLabel** with the status text as an argument to the **JLabel**'s constructor. Attach the **JLabel** to the **SOUTH** region of the **JFrame**, as shown in Fig. 9.14.



**Fig. 9.14** | **JLabel** displaying shape statistics.

## 9.8 Wrap-Up

This chapter introduced inheritance—the ability to create classes by acquiring an existing class’s members (without copying and pasting the code) and having the ability to embellish them with new capabilities. You learned the notions of superclasses and subclasses and used keyword `extends` to create a subclass that inherits members from a superclass. We showed how to use the `@Override` annotation to prevent unintended overloading by indicating that a method overrides a superclass method. We introduced the access modifier `protected`; subclass methods can directly access `protected` superclass members. You learned how to use `super` to access overridden superclass members. You also saw how constructors are used in inheritance hierarchies. Finally, you learned about the methods of class `Object`, the direct or indirect superclass of all Java classes.

In Chapter 10, Object-Oriented Programming: Polymorphism and Interfaces, we build on our discussion of inheritance by introducing *polymorphism*—an object-oriented concept that enables us to write programs that conveniently handle, in a more general and convenient manner, objects of a wide variety of classes related by inheritance. After studying Chapter 10, you’ll be familiar with classes, objects, encapsulation, inheritance and polymorphism—the key technologies of object-oriented programming.

## Summary

### Section 9.1 Introduction

- Inheritance (p. 353) reduces program-development time.
- The direct superclass (p. 353) of a subclass is the one from which the subclass inherits. An indirect superclass (p. 353) of a subclass is two or more levels up the class hierarchy from that subclass.
- In single inheritance (p. 353), a class is derived from one superclass. In multiple inheritance, a class is derived from more than one direct superclass. Java does not support multiple inheritance.
- A subclass is more specific than its superclass and represents a smaller group of objects (p. 353).
- Every object of a subclass is also an object of that class’s superclass. However, a superclass object is not an object of its class’s subclasses.
- An *is-a* relationship (p. 354) represents inheritance. In an *is-a* relationship, an object of a subclass also can be treated as an object of its superclass.
- A *has-a* relationship (p. 354) represents composition. In a *has-a* relationship, a class object contains references to objects of other classes.

### Section 9.2 Superclasses and Subclasses

- Single-inheritance relationships form treelike hierarchical structures—a superclass exists in a hierarchical relationship with its subclasses.

### Section 9.3 *protected* Members

- A superclass’s `public` members are accessible wherever the program has a reference to an object of that superclass or one of its subclasses.
- A superclass’s `private` members can be accessed directly only within the superclass’s declaration.
- A superclass’s `protected` members (p. 356) have an intermediate level of protection between `public` and `private` access. They can be accessed by members of the superclass, by members of its subclasses and by members of other classes in the same package.

- A superclass's private members are hidden in its subclasses and can be accessed only through the public or protected methods inherited from the superclass.
- An overridden superclass method can be accessed from a subclass if the superclass method name is preceded by super (p. 356) and a dot (.) separator.

### Section 9.4 Relationship Between Superclasses and Subclasses

- A subclass cannot access the private members of its superclass, but it can access the non-private members.
- A subclass can invoke a constructor of its superclass by using the keyword super, followed by a set of parentheses containing the superclass constructor arguments. This must appear as the first statement in the subclass constructor's body.
- A superclass method can be overridden in a subclass to declare an appropriate implementation for the subclass.
- The @Override annotation (p. 361) indicates that a method should override a superclass method. When the compiler encounters a method declared with @Override, it compares the method's signature with the superclass's method signatures. If there isn't an exact match, the compiler issues an error message, such as "method does not override or implement a method from a supertype."
- Method toString takes no arguments and returns a String. The Object class's toString method is normally overridden by a subclass.
- When an object is output using the %s format specifier, the object's toString method is called implicitly to obtain its String representation.

### Section 9.5 Constructors in Subclasses

- The first task of a subclass constructor is to call its direct superclass's constructor (p. 370) to ensure that the instance variables inherited from the superclass are initialized.

### Section 9.6 Class Object

- See the table of class Object's methods in Fig. 9.12.

## Self-Review Exercises

- 9.1** Fill in the blanks in each of the following statements:
- \_\_\_\_\_ is a form of software reusability in which new classes acquire the members of existing classes and embellish those classes with new capabilities.
  - A superclass's \_\_\_\_\_ members can be accessed in the superclass declaration *and in* subclass declarations.
  - In a(n) \_\_\_\_\_ relationship, an object of a subclass can also be treated as an object of its superclass.
  - In a(n) \_\_\_\_\_ relationship, a class object has references to objects of other classes as members.
  - In single inheritance, a class exists in a(n) \_\_\_\_\_ relationship with its subclasses.
  - A superclass's \_\_\_\_\_ members are accessible anywhere that the program has a reference to an object of that superclass or to an object of one of its subclasses.
  - When an object of a subclass is instantiated, a superclass \_\_\_\_\_ is called implicitly or explicitly.
  - Subclass constructors can call superclass constructors via the \_\_\_\_\_ keyword.
- 9.2** State whether each of the following is *true* or *false*. If a statement is *false*, explain why.
- Superclass constructors are not inherited by subclasses.
  - A *has-a* relationship is implemented via inheritance.



- c) A Car class has an *is-a* relationship with the SteeringWheel and Brakes classes.
- d) When a subclass redefines a superclass method by using the same signature, the subclass is said to overload that superclass method.

## Answers to Self-Review Exercises

**9.1** a) Inheritance. b) public and protected. c) *is-a* or inheritance. d) *has-a* or composition. e) hierarchical. f) public. g) constructor. h) super.

**9.2** a) True. b) False. A *has-a* relationship is implemented via composition. An *is-a* relationship is implemented via inheritance. c) False. This is an example of a *has-a* relationship. Class Car has an *is-a* relationship with class Vehicle. d) False. This is known as overriding, not overloading—an overloaded method has the same name, but a different signature.

## Exercises

**9.3** (*Using Composition Rather Than Inheritance*) Many programs written with inheritance could be written with composition instead, and vice versa. Rewrite class BasePlusCommissionEmployee (Fig. 9.11) of the CommissionEmployee–BasePlusCommissionEmployee hierarchy to use composition rather than inheritance.

**9.4** (*Software Reuse*) Discuss the ways in which inheritance promotes software reuse, saves time during program development and helps prevent errors.

**9.5** (*Student Inheritance Hierarchy*) Draw an inheritance hierarchy for students at a university similar to the hierarchy shown in Fig. 9.2. Use Student as the superclass of the hierarchy, then extend Student with classes UndergraduateStudent and GraduateStudent. Continue to extend the hierarchy as deep (i.e., as many levels) as possible. For example, Freshman, Sophomore, Junior and Senior might extend UndergraduateStudent, and DoctoralStudent and MastersStudent might be subclasses of GraduateStudent. After drawing the hierarchy, discuss the relationships that exist between the classes. [*Note:* You do not need to write any code for this exercise.]

**9.6** (*Shape Inheritance Hierarchy*) The world of shapes is much richer than the shapes included in the inheritance hierarchy of Fig. 9.3. Write down all the shapes you can think of—both two-dimensional and three-dimensional—and form them into a more complete Shape hierarchy with as many levels as possible. Your hierarchy should have class Shape at the top. Classes TwoDimensionalShape and ThreeDimensionalShape should extend Shape. Add additional subclasses, such as Quadrilateral and Sphere, at their correct locations in the hierarchy as necessary.

**9.7** (*protected vs. private*) Some programmers prefer not to use protected access, because they believe it breaks the encapsulation of the superclass. Discuss the relative merits of using protected access vs. using private access in superclasses.

**9.8** (*Quadrilateral Inheritance Hierarchy*) Write an inheritance hierarchy for classes Quadrilateral, Trapezoid, Parallelogram, Rectangle and Square. Use Quadrilateral as the superclass of the hierarchy. Create and use a Point class to represent the points in each shape. Make the hierarchy as deep (i.e., as many levels) as possible. Specify the instance variables and methods for each class. The private instance variables of Quadrilateral should be the *x-y* coordinate pairs for the four endpoints of the Quadrilateral. Write a program that instantiates objects of your classes and outputs each object's area (except Quadrilateral).

**9.9** (*What Does Each Code Snippet Do?*)

- a) Assume that the following method call is located in an overridden earnings method in a subclass:

```
super.earnings()
```

- b) Assume that the following line of code appears before a method declaration:

```
@Override
```

- c) Assume that the following line of code appears as the first statement in a constructor's body:

```
super(firstArgument, secondArgument);
```

**9.10** (*Write a Line of Code*) Write a line of code that performs each of the following tasks:

- Specify that class `PieceWorker` inherits from class `Employee`.
- Call superclass `Employee`'s `toString` method from subclass `PieceWorker`'s `toString` method.
- Call superclass `Employee`'s constructor from subclass `PieceWorker`'s constructor—assume that the superclass constructor receives three `Strings` representing the first name, last name and social security number.

**9.11** (*Using `super` in a Constructor's Body*) Explain why you would use `super` in the first statement of a subclass constructor's body.

**9.12** (*Using `super` in an Instance Method's Body*) Explain why you would use `super` in the body of a subclass's instance method.

**9.13** (*Calling `get` Methods in a Class's Body*) In Figs. 9.10–9.11 methods `earnings` and `toString` each call various `get` methods within the same class. Explain the benefits of calling these `get` methods within the classes.

**9.14** (*Employee Hierarchy*) In this chapter, you studied an inheritance hierarchy in which class `BasePlusCommissionEmployee` inherited from class `CommissionEmployee`. However, not all types of employees are `CommissionEmployees`. In this exercise, you'll create a more general `Employee` superclass that *factors out* the attributes and behaviors in class `CommissionEmployee` that are common to all `Employees`. The common attributes and behaviors for all `Employees` are `firstName`, `lastName`, `socialSecurityNumber`, `getFirstName`, `getLastName`, `getSocialSecurityNumber` and a portion of method `toString`. Create a new superclass `Employee` that contains these instance variables and methods and a constructor. Next, rewrite class `CommissionEmployee` from Section 9.4.5 as a subclass of `Employee`. Class `CommissionEmployee` should contain only the instance variables and methods that are not declared in superclass `Employee`. Class `CommissionEmployee`'s constructor should invoke class `Employee`'s constructor and `CommissionEmployee`'s `toString` method should invoke `Employee`'s `toString` method. Once you've completed these modifications, run the `CommissionEmployeeTest` and `BasePlusCommissionEmployeeTest` apps using these new classes to ensure that the apps still display the same results for a `CommissionEmployee` object and `BasePlusCommissionEmployee` object, respectively.

**9.15** (*Creating a New Subclass of `Employee`*) Other types of `Employees` might include `SalariedEmployees` who get paid a fixed weekly salary, `PieceWorkers` who get paid by the number of pieces they produce or `HourlyEmployees` who get paid an hourly wage with time-and-a-half—1.5 times the hourly wage—for hours worked over 40 hours.

Create class `HourlyEmployee` that inherits from class `Employee` (Exercise 9.14) and has instance variable `hours` (a `double`) that represents the hours worked, instance variable `wage` (a `double`) that represents the wages per hour, a constructor that takes as arguments a first name, a last name, a social security number, an hourly wage and the number of hours worked, *set* and *get* methods for manipulating the hours and wage, an `earnings` method to calculate an `HourlyEmployee`'s earnings based on the hours worked and a `toString` method that returns the `HourlyEmployee`'s `String` representation. Method `setWage` should ensure that wage is nonnegative, and `setHours` should ensure that the value of hours is between 0 and 168 (the total number of hours in a week). Use class `HourlyEmployee` in a test program that's similar to the one in Fig. 9.5.

# Object-Oriented Programming: Polymorphism and Interfaces

# 10



*General propositions do not decide concrete cases.*

—Oliver Wendell Holmes

*A philosopher of imposing stature doesn't think in a vacuum. Even his most abstract ideas are, to some extent, conditioned by what is or is not known in the time when he lives.*

—Alfred North Whitehead

## Objectives

In this chapter you'll:

- Learn the concept of polymorphism.
- Use overridden methods to effect polymorphism.
- Distinguish between abstract and concrete classes.
- Declare abstract methods to create abstract classes.
- Learn how polymorphism makes systems extensible and maintainable.
- Determine an object's type at execution time.
- Declare and implement interfaces, and become familiar with the Java SE 8 interface enhancements.

- 10.1 Introduction
- 10.2 Polymorphism Examples
- 10.3 Demonstrating Polymorphic Behavior
- 10.4 Abstract Classes and Methods
- 10.5 Case Study: Payroll System Using Polymorphism
  - 10.5.1 Abstract Superclass `Employee`
  - 10.5.2 Concrete Subclass `SalariedEmployee`
  - 10.5.3 Concrete Subclass `HourlyEmployee`
  - 10.5.4 Concrete Subclass `CommissionEmployee`
  - 10.5.5 Indirect Concrete Subclass `BasePlusCommissionEmployee`
  - 10.5.6 Polymorphic Processing, Operator `instanceof` and Downcasting
- 10.6 Allowed Assignments Between Superclass and Subclass Variables
- 10.7 `final` Methods and Classes
- 10.8 A Deeper Explanation of Issues with Calling Methods from Constructors
- 10.9 Creating and Using Interfaces
  - 10.9.1 Developing a `Payable` Hierarchy
  - 10.9.2 Interface `Payable`
  - 10.9.3 Class `Invoice`
  - 10.9.4 Modifying Class `Employee` to Implement Interface `Payable`
  - 10.9.5 Modifying Class `SalariedEmployee` for Use in the `Payable` Hierarchy
  - 10.9.6 Using Interface `Payable` to Process Invoices and Employees Polymorphically
  - 10.9.7 Some Common Interfaces of the Java API
- 10.10 Java SE 8 Interface Enhancements
  - 10.10.1 `default` Interface Methods
  - 10.10.2 `static` Interface Methods
  - 10.10.3 Functional Interfaces
- 10.11 (Optional) GUI and Graphics Case Study: Drawing with Polymorphism
- 10.12 Wrap-Up

Summary | Self-Review Exercises | Answers to Self-Review Exercises |  
Exercises | Making a Difference

## 10.1 Introduction

We continue our study of object-oriented programming by explaining and demonstrating **polymorphism** with inheritance hierarchies. Polymorphism enables you to “program in the *general*” rather than “program in the *specific*.” In particular, polymorphism enables you to write programs that process objects that share the same superclass, either directly or indirectly, as if they were all objects of the superclass; this can simplify programming.

Consider the following example of polymorphism. Suppose we create a program that simulates the movement of several types of animals for a biological study. Classes `Fish`, `Frog` and `Bird` represent the types of animals under investigation. Imagine that each class extends superclass `Animal`, which contains a method `move` and maintains an animal’s current location as *x-y* coordinates. Each subclass implements method `move`. Our program maintains an `Animal` array containing references to objects of the various `Animal` subclasses. To simulate the animals’ movements, the program sends each object the *same* message once per second—namely, `move`. Each specific type of `Animal` responds to a `move` message in its own way—a `Fish` might swim three feet, a `Frog` might jump five feet and a `Bird` might fly ten feet. Each object knows how to modify its *x-y* coordinates appropriately for its *specific* type of movement. Relying on each object to know how to “do the right thing” (i.e., do what’s appropriate for that type of object) in response to the *same* method call is the key concept of polymorphism. The *same* message (in this case, `move`) sent to a *variety* of objects has *many forms* of results—hence the term polymorphism.

### *Implementing for Extensibility*

With polymorphism, we can design and implement systems that are easily *extensible*—new classes can be added with little or no modification to the general portions of the program, as long as the new classes are part of the inheritance hierarchy that the program processes generically. The new classes simply “plug right in.” The only parts of a program that must be altered are those that require direct knowledge of the new classes that we add to the hierarchy. For example, if we extend class `Animal` to create class `Tortoise` (which might respond to a `move` message by crawling one inch), we need to write only the `Tortoise` class and the part of the simulation that instantiates a `Tortoise` object. The portions of the simulation that tell each `Animal` to move generically can remain the same.

### *Chapter Overview*

First, we discuss common examples of polymorphism. We then provide a simple example demonstrating polymorphic behavior. We use superclass references to manipulate *both* superclass objects and subclass objects polymorphically.

We then present a case study that revisits the employee hierarchy of Section 9.4.5. We develop a simple payroll application that polymorphically calculates the weekly pay of several different types of employees using each employee’s *earnings* method. Though the earnings of each type of employee are calculated in a *specific* way, polymorphism allows us to process the employees “in the *general*.” In the case study, we enlarge the hierarchy to include two new classes—`SalariedEmployee` (for people paid a fixed weekly salary) and `HourlyEmployee` (for people paid an hourly salary and “time-and-a-half” for overtime). We declare a common set of functionality for all the classes in the updated hierarchy in an “abstract” class, `Employee`, from which “concrete” classes `SalariedEmployee`, `HourlyEmployee` and `CommissionEmployee` inherit directly and “concrete” class `BasePlusCommissionEmployee` inherits indirectly. As you’ll soon see, *when we invoke each employee’s earnings method off a superclass Employee reference (regardless of the employee’s type), the correct earnings subclass calculation is performed*, due to Java’s polymorphic capabilities.

### *Programming in the Specific*

Occasionally, when performing polymorphic processing, we need to program “in the *specific*.” Our `Employee` case study demonstrates that a program can determine the *type* of an object at *execution time* and act on that object accordingly. In the case study, we’ve decided that `BasePlusCommissionEmployees` should receive 10% raises on their base salaries. So, we use these capabilities to determine whether a particular employee object *is a* `BasePlusCommissionEmployee`. If so, we increase that employee’s base salary by 10%.

### *Interfaces*

The chapter continues with an introduction to Java *interfaces*, which are particularly useful for assigning *common* functionality to possibly *unrelated* classes. This allows objects of these classes to be processed polymorphically—objects of classes that **implement** the *same* interface can respond to all of the interface method calls. To demonstrate creating and using interfaces, we modify our payroll application to create a generalized accounts payable application that can calculate payments due for company employees *and* invoice amounts to be billed for purchased goods.

## 10.2 Polymorphism Examples

Let's consider several additional examples of polymorphism.

### *Quadrilaterals*

If class `Rectangle` is derived from class `Quadrilateral`, then a `Rectangle` object *is a* more *specific* version of a `Quadrilateral`. Any operation (e.g., calculating the perimeter or the area) that can be performed on a `Quadrilateral` can also be performed on a `Rectangle`. These operations can also be performed on other `Quadrilaterals`, such as `Squares`, `Parallelograms` and `Trapezoids`. The polymorphism occurs when a program invokes a method through a superclass `Quadrilateral` variable—at execution time, the correct subclass version of the method is called, based on the type of the reference stored in the superclass variable. You'll see a simple code example that illustrates this process in Section 10.3.

### *Space Objects in a Video Game*

Suppose we design a video game that manipulates objects of classes `Martian`, `Venusian`, `Plutonian`, `SpaceShip` and `LaserBeam`. Imagine that each class inherits from the superclass `SpaceObject`, which contains method `draw`. Each subclass implements this method. A screen manager maintains a collection (e.g., a `SpaceObject` array) of references to objects of the various classes. To refresh the screen, the screen manager periodically sends each object the *same* message—namely, `draw`. However, each object responds its *own* way, based on its class. For example, a `Martian` object might draw itself in red with green eyes and the appropriate number of antennae. A `SpaceShip` object might draw itself as a bright silver flying saucer. A `LaserBeam` object might draw itself as a bright red beam across the screen. Again, the *same* message (in this case, `draw`) sent to a *variety* of objects has “many forms” of results.

A screen manager might use polymorphism to facilitate adding new classes to a system with minimal modifications to the system's code. Suppose that we want to add `Mercurian` objects to our video game. To do so, we'd build a class `Mercurian` that extends `SpaceObject` and provides its own `draw` method implementation. When `Mercurian` objects appear in the `SpaceObject` collection, the screen-manager code *invokes method `draw`, exactly as it does for every other object in the collection, regardless of its type*. So the new `Mercurian` objects simply “plug right in” without any modification of the screen manager code by the programmer. Thus, without modifying the system (other than to build new classes and modify the code that creates new objects), you can use polymorphism to conveniently include additional types that were not even considered when the system was created.



### Software Engineering Observation 10.1

*Polymorphism enables you to deal in generalities and let the execution-time environment handle the specifics. You can tell objects to behave in manners appropriate to those objects, without knowing their specific types, as long as they belong to the same inheritance hierarchy.*



### Software Engineering Observation 10.2

*Polymorphism promotes extensibility: Software that invokes polymorphic behavior is independent of the object types to which messages are sent. New object types that can respond to existing method calls can be incorporated into a system without modifying the base system. Only client code that instantiates new objects must be modified to accommodate new types.*

## 10.3 Demonstrating Polymorphic Behavior

Section 9.4 created a class hierarchy, in which class `BasePlusCommissionEmployee` inherited from `CommissionEmployee`. The examples in that section manipulated `CommissionEmployee` and `BasePlusCommissionEmployee` objects by using references to them to invoke their methods—we aimed superclass variables at superclass objects and subclass variables at subclass objects. These assignments are natural and straightforward—superclass variables are *intended* to refer to superclass objects, and subclass variables are *intended* to refer to subclass objects. However, as you'll soon see, other assignments are possible.

In the next example, we aim a *superclass* reference at a *subclass* object. We then show how invoking a method on a subclass object via a superclass reference invokes the *subclass* functionality—the type of the *referenced object*, *not* the type of the *variable*, determines which method is called. This example demonstrates that *an object of a subclass can be treated as an object of its superclass*, enabling various interesting manipulations. A program can create an array of superclass variables that refer to objects of many subclass types. This is allowed because each subclass object *is an* object of its superclass. For instance, we can assign the reference of a `BasePlusCommissionEmployee` object to a superclass `CommissionEmployee` variable, because a `BasePlusCommissionEmployee` *is a* `CommissionEmployee`—so we can treat a `BasePlusCommissionEmployee` as a `CommissionEmployee`.

As you'll learn later in the chapter, you *cannot treat a superclass object as a subclass object*, because a superclass object is *not* an object of any of its subclasses. For example, we cannot assign the reference of a `CommissionEmployee` object to a subclass `BasePlusCommissionEmployee` variable, because a `CommissionEmployee` is *not* a `BasePlusCommissionEmployee`—a `CommissionEmployee` does *not* have a `baseSalary` instance variable and does *not* have methods `setBaseSalary` and `getBaseSalary`. The *is-a* relationship applies only *up the hierarchy* from a subclass to its direct (and indirect) superclasses, and *not* vice versa (i.e., not down the hierarchy from a superclass to its subclasses or indirect subclasses).

The Java compiler *does* allow the assignment of a superclass reference to a subclass variable if we explicitly *cast* the superclass reference to the subclass type. Why would we ever want to perform such an assignment? A superclass reference can be used to invoke *only* the methods declared in the superclass—attempting to invoke *subclass-only* methods through a superclass reference results in compilation errors. If a program needs to perform a subclass-specific operation on a subclass object referenced by a superclass variable, the program must first cast the superclass reference to a subclass reference through a technique known as **downcasting**. This enables the program to invoke subclass methods that are *not* in the superclass. We demonstrate the mechanics of downcasting in Section 10.5.



### Software Engineering Observation 10.3

*Although it's allowed, you should generally avoid downcasting.*

The example in Fig. 10.1 demonstrates three ways to use superclass and subclass variables to store references to superclass and subclass objects. The first two are straightforward—as in Section 9.4, we assign a superclass reference to a superclass variable, and a subclass reference to a subclass variable. Then we demonstrate the relationship between subclasses and superclasses (i.e., the *is-a* relationship) by assigning a subclass reference to a superclass variable. This program uses classes `CommissionEmployee` and `BasePlusCommissionEmployee` from Fig. 9.10 and Fig. 9.11, respectively.

```

1 // Fig. 10.1: PolymorphismTest.java
2 // Assigning superclass and subclass references to superclass and
3 // subclass variables.
4
5 public class PolymorphismTest
6 {
7 public static void main(String[] args)
8 {
9 // assign superclass reference to superclass variable
10 CommissionEmployee commissionEmployee = new CommissionEmployee(
11 "Sue", "Jones", "222-22-2222", 10000, .06);
12
13 // assign subclass reference to subclass variable
14 BasePlusCommissionEmployee basePlusCommissionEmployee =
15 new BasePlusCommissionEmployee(
16 "Bob", "Lewis", "333-33-3333", 5000, .04, 300);
17
18 // invoke toString on superclass object using superclass variable
19 System.out.printf("%s %s:%n%n%s%n",
20 "Call CommissionEmployee's toString with superclass reference ",
21 "to superclass object", commissionEmployee.toString());
22
23 // invoke toString on subclass object using subclass variable
24 System.out.printf("%s %s:%n%n%s%n",
25 "Call BasePlusCommissionEmployee's toString with subclass",
26 "reference to subclass object",
27 basePlusCommissionEmployee.toString());
28
29 // invoke toString on subclass object using superclass variable
30 CommissionEmployee commissionEmployee2 =
31 basePlusCommissionEmployee;
32 System.out.printf("%s %s:%n%n%s%n",
33 "Call BasePlusCommissionEmployee's toString with superclass",
34 "reference to subclass object", commissionEmployee2.toString());
35 } // end main
36 } // end class PolymorphismTest

```

Call CommissionEmployee's toString with superclass reference to superclass object:

```

commission employee: Sue Jones
social security number: 222-22-2222
gross sales: 10000.00
commission rate: 0.06

```

Call BasePlusCommissionEmployee's toString with subclass reference to subclass object:

```

base-salaried commission employee: Bob Lewis
social security number: 333-33-3333
gross sales: 5000.00
commission rate: 0.04
base salary: 300.00

```

**Fig. 10.1** | Assigning superclass and subclass references to superclass and subclass variables.  
(Part 1 of 2.)



Call `BasePlusCommissionEmployee`'s `toString` with superclass reference to subclass object:

```
base-salaried commission employee: Bob Lewis
social security number: 333-33-3333
gross sales: 5000.00
commission rate: 0.04
base salary: 300.00
```

**Fig. 10.1** | Assigning superclass and subclass references to superclass and subclass variables.  
(Part 2 of 2.)

In Fig. 10.1, lines 10–11 create a `CommissionEmployee` object and assign its reference to a `CommissionEmployee` variable. Lines 14–16 create a `BasePlusCommissionEmployee` object and assign its reference to a `BasePlusCommissionEmployee` variable. These assignments are natural—for example, a `CommissionEmployee` variable’s primary purpose is to hold a reference to a `CommissionEmployee` object. Lines 19–21 use `commissionEmployee` to invoke `toString` *explicitly*. Because `commissionEmployee` refers to a `CommissionEmployee` object, superclass `CommissionEmployee`’s version of `toString` is called. Similarly, lines 24–27 use `basePlusCommissionEmployee` to invoke `toString` *explicitly* on the `BasePlusCommissionEmployee` object. This invokes subclass `BasePlusCommissionEmployee`’s version of `toString`.

Lines 30–31 then assign the reference of subclass object `basePlusCommissionEmployee` to a superclass `CommissionEmployee` variable, which lines 32–34 use to invoke method `toString`. *When a superclass variable contains a reference to a subclass object, and that reference is used to call a method, the subclass version of the method is called.* Hence, `commissionEmployee2.toString()` in line 34 actually calls class `BasePlusCommissionEmployee`’s `toString` method. The Java compiler allows this “crossover” because an object of a subclass *is an* object of its superclass (but *not* vice versa). When the compiler encounters a method call made through a variable, the compiler determines if the method can be called by checking the variable’s class type. If that class contains the proper method declaration (or inherits one), the call is compiled. At execution time, the type of the object to which the variable refers determines the actual method to use. This process, called *dynamic binding*, is discussed in detail in Section 10.5.

## 10.4 Abstract Classes and Methods

When we think of a class, we assume that programs will create objects of that type. Sometimes it’s useful to declare classes—called **abstract classes**—for which you *never* intend to create objects. Because they’re used only as superclasses in inheritance hierarchies, we refer to them as **abstract superclasses**. These classes cannot be used to instantiate objects, because, as we’ll soon see, abstract classes are *incomplete*. Subclasses must declare the “missing pieces” to become “concrete” classes, from which you can instantiate objects. Otherwise, these subclasses, too, will be abstract. We demonstrate abstract classes in Section 10.5.

### *Purpose of Abstract Classes*

An abstract class’s purpose is to provide an appropriate superclass from which other classes can inherit and thus share a common design. In the Shape hierarchy of Fig. 9.3, for exam-

ple, subclasses inherit the notion of what it means to be a *Shape*—perhaps common attributes such as `location`, `color` and `borderThickness`, and behaviors such as `draw`, `move`, `resize` and `changeColor`. Classes that can be used to instantiate objects are called **concrete classes**. Such classes provide implementations of *every* method they declare (some of the implementations can be inherited). For example, we could derive concrete classes `Circle`, `Square` and `Triangle` from abstract superclass `TwoDimensionalShape`. Similarly, we could derive concrete classes `Sphere`, `Cube` and `Tetrahedron` from abstract superclass `ThreeDimensionalShape`. Abstract superclasses are *too general* to create real objects—they specify only what is common among subclasses. We need to be more *specific* before we can create objects. For example, if you send the `draw` message to abstract class `TwoDimensionalShape`, the class knows that two-dimensional shapes should be *drawable*, but it does not know what *specific* shape to draw, so it cannot implement a real `draw` method. Concrete classes provide the specifics that make it reasonable to instantiate objects.

Not all hierarchies contain abstract classes. However, you'll often write client code that uses only abstract superclass types to reduce the client code's dependencies on a range of subclass types. For example, you can write a method with a parameter of an abstract superclass type. When called, such a method can receive an object of *any* concrete class that directly or indirectly extends the superclass specified as the parameter's type.

Abstract classes sometimes constitute several levels of a hierarchy. For example, the *Shape* hierarchy of Fig. 9.3 begins with abstract class *Shape*. On the next level of the hierarchy are *abstract* classes `TwoDimensionalShape` and `ThreeDimensionalShape`. The next level of the hierarchy declares *concrete* classes for `TwoDimensionalShapes` (`Circle`, `Square` and `Triangle`) and for `ThreeDimensionalShapes` (`Sphere`, `Cube` and `Tetrahedron`).

### Declaring an Abstract Class and Abstract Methods

You make a class abstract by declaring it with keyword **abstract**. An abstract class normally contains one or more **abstract methods**. An abstract method is an *instance method* with keyword **abstract** in its declaration, as in

```
public abstract void draw(); // abstract method
```

Abstract methods do *not* provide implementations. A class that contains *any* abstract methods must be explicitly declared abstract even if that class contains some concrete (nonabstract) methods. Each concrete subclass of an abstract superclass also must provide concrete implementations of each of the superclass's abstract methods. Constructors and static methods cannot be declared abstract. Constructors are *not* inherited, so an abstract constructor could never be implemented. Though non-private static methods are inherited, they cannot be overridden. Since abstract methods are meant to be overridden so that they can process objects based on their types, it would not make sense to declare a static method as abstract.



### Software Engineering Observation 10.4

*An abstract class declares common attributes and behaviors (both abstract and concrete) of the various classes in a class hierarchy. An abstract class typically contains one or more abstract methods that subclasses must override if they are to be concrete. The instance variables and concrete methods of an abstract class are subject to the normal rules of inheritance.*



### Common Programming Error 10.1

*Attempting to instantiate an object of an abstract class is a compilation error.*



### Common Programming Error 10.2

*Failure to implement a superclass's abstract methods in a subclass is a compilation error unless the subclass is also declared abstract.*

#### *Using Abstract Classes to Declare Variables*

Although we cannot instantiate objects of abstract superclasses, you'll soon see that we *can* use abstract superclasses to declare variables that can hold references to objects of *any* concrete class *derived from* those abstract superclasses. We'll use such variables to manipulate subclass objects *polymorphically*. You also can use abstract superclass names to invoke static methods declared in those abstract superclasses.

Consider another application of polymorphism. A drawing program needs to display many shapes, including types of new shapes that you'll *add* to the system *after* writing the drawing program. The drawing program might need to display shapes, such as `Circles`, `Triangles`, `Rectangles` or others, that derive from abstract class `Shape`. The drawing program uses `Shape` variables to manage the objects that are displayed. To draw any object in this inheritance hierarchy, the drawing program uses a superclass `Shape` variable containing a reference to the subclass object to invoke the object's `draw` method. This method is declared abstract in superclass `Shape`, so each concrete subclass *must* implement method `draw` in a manner specific to that shape—each object in the `Shape` inheritance hierarchy *knows how to draw itself*. The drawing program does not have to worry about the type of each object or whether the program has ever encountered objects of that type.

#### *Layered Software Systems*


Polymorphism is particularly effective for implementing so-called *layered software systems*. In operating systems, for example, each type of physical device could operate quite differently from the others. Even so, commands to read or write data from and to devices may have a certain uniformity. For each device, the operating system uses a piece of software called a *device driver* to control all communication between the system and the device. The write message sent to a device-driver object needs to be interpreted specifically in the context of that driver and how it manipulates devices of a specific type. However, the write call itself really is no different from the write to any other device in the system—place some number of bytes from memory onto that device. An object-oriented operating system might use an abstract superclass to provide an “interface” appropriate for all device drivers. Then, through inheritance from that abstract superclass, subclasses are formed that all behave similarly. The device-driver methods are declared as abstract methods in the abstract superclass. The implementations of these abstract methods are provided in the concrete subclasses that correspond to the specific types of device drivers. New devices are always being developed, often long after the operating system has been released. When you buy a new device, it comes with a device driver provided by the device vendor. The device is immediately operational after you connect it to your computer and install the driver. This is another elegant example of how polymorphism makes systems *extensible*.

## 10.5 Case Study: Payroll System Using Polymorphism

This section reexamines the `CommissionEmployee-BasePlusCommissionEmployee` hierarchy that we explored throughout Section 9.4. Now we use an abstract method and polymorphism to perform payroll calculations based on an enhanced employee inheritance hierarchy that meets the following requirements:

*A company pays its employees on a weekly basis. The employees are of four types: Salaried employees are paid a fixed weekly salary regardless of the number of hours worked, hourly employees are paid by the hour and receive overtime pay (i.e., 1.5 times their hourly salary rate) for all hours worked in excess of 40 hours, commission employees are paid a percentage of their sales and base-salaried commission employees receive a base salary plus a percentage of their sales. For the current pay period, the company has decided to reward salaried-commission employees by adding 10% to their base salaries. The company wants you to write an application that performs its payroll calculations polymorphically.*

We use abstract class `Employee` to represent the general concept of an employee. The classes that extend `Employee` are `SalariedEmployee`, `CommissionEmployee` and `HourlyEmployee`. Class `BasePlusCommissionEmployee`—which extends `CommissionEmployee`—represents the last employee type. The UML class diagram in Fig. 10.2 shows the inheritance hierarchy for our polymorphic employee-payroll application. Abstract class name `Employee` is italicized—a convention of the UML.



**Fig. 10.2** | `Employee` hierarchy UML class diagram.

Abstract superclass `Employee` declares the “interface” to the hierarchy—that is, the set of methods that a program can invoke on all `Employee` objects. We use the term “interface” here in a *general* sense to refer to the various ways programs can communicate with objects of *any* `Employee` subclass. Be careful not to confuse the general notion of an “interface” with the formal notion of a Java interface, the subject of Section 10.9. Each employee, regardless of the way his or her earnings are calculated, has a first name, a last name and a social security number, so private instance variables `firstName`, `lastName` and `socialSecurityNumber` appear in abstract superclass `Employee`.

The diagram in Fig. 10.3 shows each of the five classes in the hierarchy down the left side and methods `earnings` and `toString` across the top. For each class, the diagram shows the desired results of each method. We do not list superclass `Employee`’s `get` methods because they’re *not* overridden in any of the subclasses—each of these methods is inherited and used “as is” by each subclass.

|                                      | earnings                                                                                                                          | toString                                                                                                                                                                                                                |
|--------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Employee                             | abstract                                                                                                                          | <i>firstName lastName</i><br>social security number: <i>SSN</i>                                                                                                                                                         |
| Salaried-<br>Employee                | weeklySalary                                                                                                                      | salaried employee: <i>firstName lastName</i><br>social security number: <i>SSN</i><br>weekly salary: <i>weeklySalary</i>                                                                                                |
| Hourly-<br>Employee                  | <pre> if (hours &lt;= 40)     wage * hours else if (hours &gt; 40) {     40 * wage +     ( hours - 40 ) *     wage * 1.5 } </pre> | hourly employee: <i>firstName lastName</i><br>social security number: <i>SSN</i><br>hourly wage: <i>wage</i> ; hours worked: <i>hours</i>                                                                               |
| Commission-<br>Employee              | commissionRate *<br>grossSales                                                                                                    | commission employee: <i>firstName lastName</i><br>social security number: <i>SSN</i><br>gross sales: <i>grossSales</i> ;<br>commission rate: <i>commissionRate</i>                                                      |
| BasePlus-<br>Commission-<br>Employee | (commissionRate *<br>grossSales) +<br>baseSalary                                                                                  | base salaried commission employee:<br><i>firstName lastName</i><br>social security number: <i>SSN</i><br>gross sales: <i>grossSales</i> ;<br>commission rate: <i>commissionRate</i> ;<br>base salary: <i>baseSalary</i> |

**Fig. 10.3** | Polymorphic interface for the Employee hierarchy classes.

The following sections implement the Employee class hierarchy of Fig. 10.2. The first section implements *abstract superclass* Employee. The next four sections each implement one of the *concrete* classes. The last section implements a test program that builds objects of all these classes and processes those objects polymorphically.

### 10.5.1 Abstract Superclass Employee

Class Employee (Fig. 10.4) provides methods earnings and toString, in addition to the *get* methods that return the values of Employee's instance variables. An earnings method certainly applies *generically* to all employees. But each earnings calculation depends on the employee's particular class. So we declare earnings as abstract in superclass Employee because a *specific* default implementation does not make sense for that method—there isn't enough information to determine what amount earnings should return.

Each subclass overrides earnings with an appropriate implementation. To calculate an employee's earnings, the program assigns to a superclass Employee variable a reference to the employee's object, then invokes the earnings method on that variable. We maintain an array of Employee variables, each holding a reference to an Employee object. You *cannot* use class Employee directly to create Employee *objects*, because Employee is an *abstract* class. Due to inheritance, however, all objects of all Employee subclasses may be thought of as Employee

objects. The program will iterate through the array and call method `earnings` for each `Employee` object. Java processes these method calls *polymorphically*. Declaring `earnings` as an abstract method in `Employee` enables the calls to `earnings` through `Employee` variables to compile and forces every direct *concrete* subclass of `Employee` to *override* `earnings`.

Method `toString` in class `Employee` returns a `String` containing the first name, last name and social security number of the employee. As we'll see, each subclass of `Employee` *overrides* method `toString` to create a `String` representation of an object of that class that contains the employee's type (e.g., "salaried employee:") followed by the rest of the employee's information.

Let's consider class `Employee`'s declaration (Fig. 10.4). The class includes a constructor that receives the first name, last name and social security number (lines 11–17); *get* methods that return the first name, last name and social security number (lines 20–23, 26–29 and 32–35, respectively); method `toString` (lines 38–43), which returns the `String` representation of an `Employee`; and abstract method `earnings` (line 46), which will be implemented by each of the *concrete* subclasses. The `Employee` constructor does *not* validate its parameters in this example; normally, such validation should be provided.

---

```

1 // Fig. 10.4: Employee.java
2 // Employee abstract superclass.
3
4 public abstract class Employee
5 {
6 private final String firstName;
7 private final String lastName;
8 private final String socialSecurityNumber;
9
10 // constructor
11 public Employee(String firstName, String lastName,
12 String socialSecurityNumber)
13 {
14 this.firstName = firstName;
15 this.lastName = lastName;
16 this.socialSecurityNumber = socialSecurityNumber;
17 }
18
19 // return first name
20 public String getFirstName()
21 {
22 return firstName;
23 }
24
25 // return last name
26 public String getLastName()
27 {
28 return lastName;
29 }
30
31 // return social security number
32 public String getSocialSecurityNumber()
33 {

```

---

**Fig. 10.4** | `Employee` abstract superclass. (Part 1 of 2.)

```

34 return socialSecurityNumber;
35 }
36
37 // return String representation of Employee object
38 @Override
39 public String toString()
40 {
41 return String.format("%s %s\nsocial security number: %s",
42 getFirstName(), getLastName(), getSocialSecurityNumber());
43 }
44
45 // abstract method must be overridden by concrete subclasses
46 public abstract double earnings(); // no implementation here
47 } // end abstract class Employee

```

**Fig. 10.4** | Employee abstract superclass. (Part 2 of 2.)

Why did we decide to declare `earnings` as an abstract method? It simply does not make sense to provide a *specific* implementation of this method in class `Employee`. We cannot calculate the earnings for a *general* `Employee`—we first must know the *specific* type of `Employee` to determine the appropriate earnings calculation. By declaring this method abstract, we indicate that each concrete subclass *must* provide an appropriate earnings implementation and that a program will be able to use superclass `Employee` variables to invoke method `earnings` *polymorphically* for any type of `Employee`.

### 10.5.2 Concrete Subclass `SalariedEmployee`

Class `SalariedEmployee` (Fig. 10.5) extends class `Employee` (line 4) and overrides *abstract* method `earnings` (lines 38–42), which makes `SalariedEmployee` a *concrete* class. The class includes a constructor (lines 9–19) that receives a first name, a last name, a social security number and a weekly salary; a *set* method to assign a new *nonnegative* value to instance variable `weeklySalary` (lines 22–29); a *get* method to return `weeklySalary`'s value (lines 32–35); a method `earnings` (lines 38–42) to calculate a `SalariedEmployee`'s earnings; and a method `toString` (lines 45–50), which returns a `String` including "salaried employee: " followed by employee-specific information produced by superclass `Employee`'s `toString` method and `SalariedEmployee`'s `getWeeklySalary` method. Class `SalariedEmployee`'s constructor passes the first name, last name and social security number to the `Employee` constructor (line 12) to initialize the private instance variables of the superclass. Once again, we've duplicated the `weeklySalary` validation code in the constructor and the `setWeeklySalary` method. Recall that more complex validation could be placed in a static class method that's called from the constructor and the *set* method.



#### **Error-Prevention Tip 10.1**

We've said that you should not call a class's instance methods from its constructors—you can call static class methods and make the required call to one of the superclass's constructors. If you follow this advice, you'll avoid the problem of calling the class's overridable methods either directly or indirectly, which can lead to runtime errors.

Method `earnings` overrides `Employee`'s *abstract* method `earnings` to provide a *concrete* implementation that returns the `SalariedEmployee`'s weekly salary. If we do not

---

```

1 // Fig. 10.5: SalariedEmployee.java
2 // SalariedEmployee concrete class extends abstract class Employee.
3
4 public class SalariedEmployee extends Employee
5 {
6 private double weeklySalary;
7
8 // constructor
9 public SalariedEmployee(String firstName, String lastName,
10 String socialSecurityNumber, double weeklySalary)
11 {
12 super(firstName, lastName, socialSecurityNumber);
13
14 if (weeklySalary < 0.0)
15 throw new IllegalArgumentException(
16 "Weekly salary must be >= 0.0");
17
18 this.weeklySalary = weeklySalary;
19 }
20
21 // set salary
22 public void setWeeklySalary(double weeklySalary)
23 {
24 if (weeklySalary < 0.0)
25 throw new IllegalArgumentException(
26 "Weekly salary must be >= 0.0");
27
28 this.weeklySalary = weeklySalary;
29 }
30
31 // return salary
32 public double getWeeklySalary()
33 {
34 return weeklySalary;
35 }
36
37 // calculate earnings; override abstract method earnings in Employee
38 @Override
39 public double earnings()
40 {
41 return getWeeklySalary();
42 }
43
44 // return String representation of SalariedEmployee object
45 @Override
46 public String toString()
47 {
48 return String.format("salaried employee: %s\n%s: $%,.2f",
49 super.toString(), "weekly salary", getWeeklySalary());
50 }
51 } // end class SalariedEmployee

```

---

**Fig. 10.5** | SalariedEmployee concrete class extends abstract class Employee.



implement earnings, class `SalariedEmployee` must be declared abstract—otherwise, class `SalariedEmployee` will not compile. Of course, we want `SalariedEmployee` to be a *concrete* class in this example.

Method `toString` (lines 45–50) overrides `Employee` method `toString`. If class `SalariedEmployee` did *not* override `toString`, `SalariedEmployee` would have inherited the `Employee` version of `toString`. In that case, `SalariedEmployee`'s `toString` method would simply return the employee's full name and social security number, which does *not* adequately represent a `SalariedEmployee`. To produce a complete `String` representation of a `SalariedEmployee`, the subclass's `toString` method returns "salaried employee: " followed by the superclass `Employee`-specific information (i.e., first name, last name and social security number) obtained by invoking the *superclass's* `toString` method (line 49)—this is a nice example of *code reuse*. The `String` representation of a `SalariedEmployee` also contains the employee's weekly salary obtained by invoking the class's `getWeeklySalary` method.

### 10.5.3 Concrete Subclass `HourlyEmployee`

Class `HourlyEmployee` (Fig. 10.6) also extends `Employee` (line 4). The class includes a constructor (lines 10–25) that receives a first name, a last name, a social security number, an hourly wage and the number of hours worked. Lines 28–35 and 44–51 declare *set* methods that assign new values to instance variables `wage` and `hours`, respectively. Method `setWage` (lines 28–35) ensures that `wage` is *nonnegative*, and method `setHours` (lines 44–51) ensures that the value of `hours` is between 0 and 168 (the total number of hours in a week) inclusive. Class `HourlyEmployee` also includes *get* methods (lines 38–41 and 54–57) to return the values of `wage` and `hours`, respectively; a method `earnings` (lines 60–67) to calculate an `HourlyEmployee`'s earnings; and a method `toString` (lines 70–76), which returns a `String` containing the employee's type ("hourly employee: ") and the employee-specific information. The `HourlyEmployee` constructor, like the `SalariedEmployee` constructor, passes the first name, last name and social security number to the superclass `Employee` constructor (line 13) to initialize the private instance variables. In addition, method `toString` calls *superclass* method `toString` (line 74) to obtain the `Employee`-specific information (i.e., first name, last name and social security number)—this is another nice example of *code reuse*.

---

```

1 // Fig. 10.6: HourlyEmployee.java
2 // HourlyEmployee class extends Employee.
3
4 public class HourlyEmployee extends Employee
5 {
6 private double wage; // wage per hour
7 private double hours; // hours worked for week
8
9 // constructor
10 public HourlyEmployee(String firstName, String lastName,
11 String socialSecurityNumber, double wage, double hours)
12 {
13 super(firstName, lastName, socialSecurityNumber);
14 }

```

---

**Fig. 10.6** | `HourlyEmployee` class extends `Employee`. (Part I of 3.)

```

15 if (wage < 0.0) // validate wage
16 throw new IllegalArgumentException(
17 "Hourly wage must be >= 0.0");
18
19 if ((hours < 0.0) || (hours > 168.0)) // validate hours
20 throw new IllegalArgumentException(
21 "Hours worked must be >= 0.0 and <= 168.0");
22
23 this.wage = wage;
24 this.hours = hours;
25 }
26
27 // set wage
28 public void setWage(double wage)
29 {
30 if (wage < 0.0) // validate wage
31 throw new IllegalArgumentException(
32 "Hourly wage must be >= 0.0");
33
34 this.wage = wage;
35 }
36
37 // return wage
38 public double getWage()
39 {
40 return wage;
41 }
42
43 // set hours worked
44 public void setHours(double hours)
45 {
46 if ((hours < 0.0) || (hours > 168.0)) // validate hours
47 throw new IllegalArgumentException(
48 "Hours worked must be >= 0.0 and <= 168.0");
49
50 this.hours = hours;
51 }
52
53 // return hours worked
54 public double getHours()
55 {
56 return hours;
57 }
58
59 // calculate earnings; override abstract method earnings in Employee
60 @Override
61 public double earnings()
62 {
63 if (getHours() <= 40) // no overtime
64 return getWage() * getHours();
65 else
66 return 40 * getWage() + (getHours() - 40) * getWage() * 1.5;
67 }

```

**Fig. 10.6** | HourlyEmployee class extends Employee. (Part 2 of 3.)

```

68
69 // return String representation of HourlyEmployee object
70 @Override
71 public String toString()
72 {
73 return String.format("hourly employee: %s\n%s: $%,.2f; %s: $%,.2f",
74 super.toString(), "hourly wage", getWage(),
75 "hours worked", getHours());
76 }
77 } // end class HourlyEmployee

```

**Fig. 10.6** | HourlyEmployee class extends Employee. (Part 3 of 3.)

### 10.5.4 Concrete Subclass CommissionEmployee

Class CommissionEmployee (Fig. 10.7) extends class Employee (line 4). The class includes a constructor (lines 10–25) that takes a first name, a last name, a social security number, a sales amount and a commission rate; *set* methods (lines 28–34 and 43–50) to assign valid new values to instance variables commissionRate and grossSales, respectively; *get* methods (lines 37–40 and 53–56) that retrieve the values of these instance variables; method earnings (lines 59–63) to calculate a CommissionEmployee's earnings; and method toString (lines 66–73), which returns the employee's type, namely, "commission employee: " and employee-specific information. The constructor also passes the first name, last name and social security number to superclass Employee's constructor (line 14) to initialize Employee's private instance variables. Method toString calls superclass method toString (line 70) to obtain the Employee-specific information (i.e., first name, last name and social security number).

```

1 // Fig. 10.7: CommissionEmployee.java
2 // CommissionEmployee class extends Employee.
3
4 public class CommissionEmployee extends Employee
5 {
6 private double grossSales; // gross weekly sales
7 private double commissionRate; // commission percentage
8
9 // constructor
10 public CommissionEmployee(String firstName, String lastName,
11 String socialSecurityNumber, double grossSales,
12 double commissionRate)
13 {
14 super(firstName, lastName, socialSecurityNumber);
15
16 if (commissionRate <= 0.0 || commissionRate >= 1.0) // validate
17 throw new IllegalArgumentException(
18 "Commission rate must be > 0.0 and < 1.0");
19
20 if (grossSales < 0.0) // validate
21 throw new IllegalArgumentException("Gross sales must be >= 0.0");
22 }

```

**Fig. 10.7** | CommissionEmployee class extends Employee. (Part 1 of 2.)

---

```

23 this.grossSales = grossSales;
24 this.commissionRate = commissionRate;
25 }
26
27 // set gross sales amount
28 public void setGrossSales(double grossSales)
29 {
30 if (grossSales < 0.0) // validate
31 throw new IllegalArgumentException("Gross sales must be >= 0.0");
32
33 this.grossSales = grossSales;
34 }
35
36 // return gross sales amount
37 public double getGrossSales()
38 {
39 return grossSales;
40 }
41
42 // set commission rate
43 public void setCommissionRate(double commissionRate)
44 {
45 if (commissionRate <= 0.0 || commissionRate >= 1.0) // validate
46 throw new IllegalArgumentException(
47 "Commission rate must be > 0.0 and < 1.0");
48
49 this.commissionRate = commissionRate;
50 }
51
52 // return commission rate
53 public double getCommissionRate()
54 {
55 return commissionRate;
56 }
57
58 // calculate earnings; override abstract method earnings in Employee
59 @Override
60 public double earnings()
61 {
62 return getCommissionRate() * getGrossSales();
63 }
64
65 // return String representation of CommissionEmployee object
66 @Override
67 public String toString()
68 {
69 return String.format("%s: %s\n%s: $%,.2f; %s: %.2f",
70 "commission employee", super.toString(),
71 "gross sales", getGrossSales(),
72 "commission rate", getCommissionRate());
73 }
74 } // end class CommissionEmployee

```

---

**Fig. 10.7** | CommissionEmployee class extends Employee. (Part 2 of 2.)

### 10.5.5 Indirect Concrete Subclass BasePlusCommissionEmployee

Class `BasePlusCommissionEmployee` (Fig. 10.8) extends class `CommissionEmployee` (line 4) and therefore is an *indirect* subclass of class `Employee`. Class `BasePlusCommissionEmployee` has a constructor (lines 9–20) that receives a first name, a last name, a social security number, a sales amount, a commission rate and a base salary. It then passes all of these except the base salary to the `CommissionEmployee` constructor (lines 13–14) to initialize the superclass instance variables. `BasePlusCommissionEmployee` also contains a *set* method (lines 23–29) to assign a new value to instance variable `baseSalary` and a *get* method (lines 32–35) to return `baseSalary`'s value. Method `earnings` (lines 38–42) calculates a `BasePlusCommissionEmployee`'s earnings. Line 41 in method `earnings` calls *superclass* `CommissionEmployee`'s `earnings` method to calculate the commission-based portion of the employee's earnings—this is another nice example of *code reuse*. `BasePlusCommissionEmployee`'s `toString` method (lines 45–51) creates a `String` representation of a `BasePlusCommissionEmployee` that contains "base-salaried", followed by the `String` obtained by invoking *superclass* `CommissionEmployee`'s `toString` method (line 49), then the base salary. The result is a `String` beginning with "base-salaried commission employee" followed by the rest of the `BasePlusCommissionEmployee`'s information. Recall that `CommissionEmployee`'s `toString` obtains the employee's first name, last name and social security number by invoking the `toString` method of its *superclass* (i.e., `Employee`)—yet another example of *code reuse*. `BasePlusCommissionEmployee`'s `toString` initiates a *chain of method calls* that span all three levels of the `Employee` hierarchy.

---

```

1 // Fig. 10.8: BasePlusCommissionEmployee.java
2 // BasePlusCommissionEmployee class extends CommissionEmployee.
3
4 public class BasePlusCommissionEmployee extends CommissionEmployee
5 {
6 private double baseSalary; // base salary per week
7
8 // constructor
9 public BasePlusCommissionEmployee(String firstName, String lastName,
10 String socialSecurityNumber, double grossSales,
11 double commissionRate, double baseSalary)
12 {
13 super(firstName, lastName, socialSecurityNumber,
14 grossSales, commissionRate);
15
16 if (baseSalary < 0.0) // validate baseSalary
17 throw new IllegalArgumentException("Base salary must be >= 0.0");
18
19 this.baseSalary = baseSalary;
20 }
21
22 // set base salary
23 public void setBaseSalary(double baseSalary)
24 {
25 if (baseSalary < 0.0) // validate baseSalary
26 throw new IllegalArgumentException("Base salary must be >= 0.0");

```

---

**Fig. 10.8** | `BasePlusCommissionEmployee` class extends `CommissionEmployee`. (Part 1 of 2.)

---

```

27
28 this.baseSalary = baseSalary;
29 }
30
31 // return base salary
32 public double getBaseSalary()
33 {
34 return baseSalary;
35 }
36
37 // calculate earnings; override method earnings in CommissionEmployee
38 @Override
39 public double earnings()
40 {
41 return getBaseSalary() + super.earnings();
42 }
43
44 // return String representation of BasePlusCommissionEmployee object
45 @Override
46 public String toString()
47 {
48 return String.format("%s %s; %s: $%,.2f",
49 "base-salaried", super.toString(),
50 "base salary", getBaseSalary());
51 }
52 } // end class BasePlusCommissionEmployee

```

---

**Fig. 10.8** | BasePlusCommissionEmployee class extends CommissionEmployee. (Part 2 of 2.)

### 10.5.6 Polymorphic Processing, Operator instanceof and Downcasting

To test our Employee hierarchy, the application in Fig. 10.9 creates an object of each of the four *concrete* classes SalariedEmployee, HourlyEmployee, CommissionEmployee and BasePlusCommissionEmployee. The program manipulates these objects *nonpolymorphically*, via variables of each object's own type, then *polymorphically*, using an array of Employee variables. While processing the objects polymorphically, the program increases the base salary of each BasePlusCommissionEmployee by 10%—this requires *determining the object's type at execution time*. Finally, the program polymorphically determines and outputs the *type* of each object in the Employee array. Lines 9–18 create objects of each of the four concrete Employee subclasses. Lines 22–30 output the String representation and earnings of each of these objects *nonpolymorphically*. Each object's toString method is called *implicitly* by printf when the object is output as a String with the %s format specifier.

---

```

1 // Fig. 10.9: PayrollSystemTest.java
2 // Employee hierarchy test program.
3
4 public class PayrollSystemTest
5 {

```

---

**Fig. 10.9** | Employee hierarchy test program. (Part 1 of 4.)

```

6 public static void main(String[] args)
7 {
8 // create subclass objects
9 SalariedEmployee salariedEmployee =
10 new SalariedEmployee("John", "Smith", "111-11-1111", 800.00);
11 HourlyEmployee hourlyEmployee =
12 new HourlyEmployee("Karen", "Price", "222-22-2222", 16.75, 40);
13 CommissionEmployee commissionEmployee =
14 new CommissionEmployee(
15 "Sue", "Jones", "333-33-3333", 10000, .06);
16 BasePlusCommissionEmployee basePlusCommissionEmployee =
17 new BasePlusCommissionEmployee(
18 "Bob", "Lewis", "444-44-4444", 5000, .04, 300);
19
20 System.out.println("Employees processed individually:");
21
22 System.out.printf("%n%s%n%s: $%,.2f%n%n",
23 salariedEmployee, "earned", salariedEmployee.earnings());
24 System.out.printf("%n%s%n%s: $%,.2f%n%n",
25 hourlyEmployee, "earned", hourlyEmployee.earnings());
26 System.out.printf("%n%s%n%s: $%,.2f%n%n",
27 commissionEmployee, "earned", commissionEmployee.earnings());
28 System.out.printf("%n%s%n%s: $%,.2f%n%n",
29 basePlusCommissionEmployee,
30 "earned", basePlusCommissionEmployee.earnings());
31
32 // create four-element Employee array
33 Employee[] employees = new Employee[4];
34
35 // initialize array with Employees
36 employees[0] = salariedEmployee;
37 employees[1] = hourlyEmployee;
38 employees[2] = commissionEmployee;
39 employees[3] = basePlusCommissionEmployee;
40
41 System.out.printf("Employees processed polymorphically:%n%n");
42
43 // generically process each element in array employees
44 for (Employee currentEmployee : employees)
45 {
46 System.out.println(currentEmployee); // invokes toString
47
48 // determine whether element is a BasePlusCommissionEmployee
49 if (currentEmployee instanceof BasePlusCommissionEmployee())
50 {
51 // downcast Employee reference to
52 // BasePlusCommissionEmployee reference
53 BasePlusCommissionEmployee employee =
54 (BasePlusCommissionEmployee) currentEmployee;
55
56 employee.setBaseSalary(1.10 * employee.getBaseSalary());
57

```

**Fig. 10.9** | Employee hierarchy test program. (Part 2 of 4.)

```

58 System.out.printf(
59 "new base salary with 10%% increase is: $%,.2f%n",
60 employee.getBaseSalary());
61 } // end if
62
63 System.out.printf(
64 "earned $%,.2f%n%n", currentEmployee.earnings());
65 } // end for
66
67 // get type name of each object in employees array
68 for (int j = 0; j < employees.length; j++)
69 System.out.printf("Employee %d is a %s%n", j,
70 employees[j].getClass().getName());
71 } // end main
72 } // end class PayrollSystemTest

```

Employees processed individually:

salaried employee: John Smith  
social security number: 111-11-1111  
weekly salary: \$800.00  
earned: \$800.00

hourly employee: Karen Price  
social security number: 222-22-2222  
hourly wage: \$16.75; hours worked: 40.00  
earned: \$670.00

commission employee: Sue Jones  
social security number: 333-33-3333  
gross sales: \$10,000.00; commission rate: 0.06  
earned: \$600.00

base-salaried commission employee: Bob Lewis  
social security number: 444-44-4444  
gross sales: \$5,000.00; commission rate: 0.04; base salary: \$300.00  
earned: \$500.00

Employees processed polymorphically:

salaried employee: John Smith  
social security number: 111-11-1111  
weekly salary: \$800.00  
earned \$800.00

hourly employee: Karen Price  
social security number: 222-22-2222  
hourly wage: \$16.75; hours worked: 40.00  
earned \$670.00

commission employee: Sue Jones  
social security number: 333-33-3333  
gross sales: \$10,000.00; commission rate: 0.06  
earned \$600.00

**Fig. 10.9** | Employee hierarchy test program. (Part 3 of 4.)



```
base-salaried commission employee: Bob Lewis
social security number: 444-44-4444
gross sales: $5,000.00; commission rate: 0.04; base salary: $300.00
new base salary with 10% increase is: $330.00
earned $530.00

Employee 0 is a SalariedEmployee
Employee 1 is a HourlyEmployee
Employee 2 is a CommissionEmployee
Employee 3 is a BasePlusCommissionEmployee
```

**Fig. 10.9** | Employee hierarchy test program. (Part 4 of 4.)

### *Creating the Array of Employees*

Line 33 declares employees and assigns it an array of four Employee variables. Line 36 assigns to employees[0] a reference to a SalariedEmployee object. Line 37 assigns to employees[1] a reference to an HourlyEmployee object. Line 38 assigns to employees[2] a reference to a CommissionEmployee object. Line 39 assigns to employee[3] a reference to a BasePlusCommissionEmployee object. These assignments are allowed, because a SalariedEmployee *is an* Employee, an HourlyEmployee *is an* Employee, a CommissionEmployee *is an* Employee and a BasePlusCommissionEmployee *is an* Employee. Therefore, we can assign the references of SalariedEmployee, HourlyEmployee, CommissionEmployee and BasePlusCommissionEmployee objects to *superclass* Employee variables, *even though Employee is an abstract class*.

### *Polymorphically Processing Employees*

Lines 44–65 iterate through array employees and invoke methods toString and earnings with Employee variable currentEmployee, which is assigned the reference to a different Employee in the array on each iteration. The output illustrates that the specific methods for each class are indeed invoked. All calls to method toString and earnings are resolved at *execution* time, based on the *type* of the object to which currentEmployee refers. This process is known as **dynamic binding** or **late binding**. For example, line 46 *implicitly* invokes method toString of the object to which currentEmployee refers. As a result of *dynamic binding*, Java decides which class's toString method to call *at execution time rather than at compile time*. Only the methods of class Employee can be called via an Employee variable (and Employee, of course, includes the methods of class Object). A superclass reference can be used to invoke only methods of the *superclass*—the *subclass* method implementations are invoked *polymorphically*.

### *Performing Type-Specific Operations on BasePlusCommissionEmployees*

We perform special processing on BasePlusCommissionEmployee objects—as we encounter these objects at execution time, we increase their base salary by 10%. When processing objects *polymorphically*, we typically do not need to worry about the *specifics*, but to adjust the base salary, we *do* have to determine the *specific* type of Employee object at *execution time*. Line 49 uses the **instanceof** operator to determine whether a particular Employee object's type is BasePlusCommissionEmployee. The condition in line 49 is *true* if the object referenced by currentEmployee *is a* BasePlusCommissionEmployee. This would also be *true* for any object of a BasePlusCommissionEmployee subclass because of the *is-a* rela-

tionship a subclass has with its superclass. Lines 53–54 *downcast* `currentEmployee` from type `Employee` to type `BasePlusCommissionEmployee`—this cast is allowed only if the object has an *is-a* relationship with `BasePlusCommissionEmployee`. The condition at line 49 ensures that this is the case. This cast is required if we’re to invoke subclass `BasePlusCommissionEmployee` methods `getBaseSalary` and `setBaseSalary` on the current `Employee` object—as you’ll see momentarily, *attempting to invoke a subclass-only method directly on a superclass reference is a compilation error*.



### Common Programming Error 10.3

*Assigning a superclass variable to a subclass variable is a compilation error.*



### Common Programming Error 10.4

*When downcasting a reference, a `ClassCastException` occurs if the referenced object at execution time does not have an *is-a* relationship with the type specified in the cast operator.*

If the `instanceof` expression in line 49 is true, lines 53–60 perform the special processing required for the `BasePlusCommissionEmployee` object. Using `BasePlusCommissionEmployee` variable `employee`, line 56 invokes subclass-only methods `getBaseSalary` and `setBaseSalary` to retrieve and update the employee’s base salary with the 10% raise.

### Calling earnings Polymorphically

Lines 63–64 invoke method `earnings` on `currentEmployee`, which polymorphically calls the appropriate subclass object’s `earnings` method. Obtaining the earnings of the `SalaryedEmployee`, `HourlyEmployee` and `CommissionEmployee` polymorphically in lines 63–64 produces the same results as obtaining these employees’ earnings individually in lines 22–27. The earnings amount obtained for the `BasePlusCommissionEmployee` in lines 63–64 is higher than that obtained in lines 28–30, due to the 10% increase in its base salary.

### Getting Each Employee’s Class Name

Lines 68–70 display each employee’s type as a `String`. Every object *knows its own class* and can access this information through the `getClass` method, which all classes inherit from class `Object`. Method `getClass` returns an object of type `Class` (from package `java.lang`), which contains information about the object’s type, including its class name. Line 70 invokes `getClass` on the current object to get its class. The result of the `getClass` call is used to invoke `getName` to get the object’s class name.

### Avoiding Compilation Errors with Downcasting

In the previous example, we avoided several compilation errors by *downcasting* an `Employee` variable to a `BasePlusCommissionEmployee` variable in lines 53–54. If you remove the cast operator (`BasePlusCommissionEmployee`) from line 54 and attempt to assign `Employee` variable `currentEmployee` directly to `BasePlusCommissionEmployee` variable `employee`, you’ll receive an “incompatible types” compilation error. This error indicates that the attempt to assign the reference of superclass object `currentEmployee` to subclass variable `employee` is *not* allowed. The compiler prevents this assignment because a `CommissionEmployee` is *not* a `BasePlusCommissionEmployee`—*the is-a relationship applies only between the subclass and its superclasses, not vice versa*.

Similarly, if lines 56 and 60 used superclass variable `currentEmployee` to invoke subclass-only methods `getBaseSalary` and `setBaseSalary`, we'd receive "cannot find symbol" compilation errors at these lines. Attempting to invoke subclass-only methods via a superclass variable is *not* allowed—even though lines 56 and 60 execute only if `instanceof` in line 49 returns true to indicate that `currentEmployee` holds a reference to a `BasePlusCommissionEmployee` object. Using a superclass `Employee` variable, we can invoke only methods found in class `Employee`—`earnings`, `toString` and `Employee`'s `get` and `set` methods.



### Software Engineering Observation 10.5

*Although the actual method that's called depends on the runtime type of the object to which a variable refers, a variable can be used to invoke only those methods that are members of that variable's type, which the compiler verifies.*

## 10.6 Allowed Assignments Between Superclass and Subclass Variables

Now that you've seen a complete application that processes diverse subclass objects *polymorphically*, we summarize what you can and cannot do with superclass and subclass objects and variables. Although a subclass object also *is* a superclass object, the two classes are nevertheless different. As discussed previously, subclass objects can be treated as objects of their superclass. But because the subclass can have additional subclass-only members, assigning a superclass reference to a subclass variable is not allowed without an *explicit cast*—such an assignment would leave the subclass members undefined for the superclass object.

We've discussed three proper ways to assign superclass and subclass references to variables of superclass and subclass types:

1. Assigning a superclass reference to a superclass variable is straightforward.
2. Assigning a subclass reference to a subclass variable is straightforward.
3. Assigning a subclass reference to a superclass variable is safe, because the subclass object *is* an object of its superclass. However, the superclass variable can be used to refer *only* to superclass members. If this code refers to subclass-only members through the superclass variable, the compiler reports errors.

## 10.7 final Methods and Classes

We saw in Sections 5.3– and 5.10 that variables can be declared `final` to indicate that they cannot be modified *after* they're initialized—such variables represent constant values. It's also possible to declare methods, method parameters and classes with the `final` modifier.

### *Final Methods Cannot Be Overridden*

A **final method** in a superclass *cannot* be overridden in a subclass—this guarantees that the `final` method implementation will be used by all direct and indirect subclasses in the hierarchy. Methods that are declared `private` are implicitly `final`, because it's not possible to override them in a subclass. Methods that are declared `static` are also implicitly `final`. A `final` method's declaration can never change, so all subclasses use the same method

implementation, and calls to `final` methods are resolved at compile time—this is known as **static binding**.

### *Final Classes Cannot Be Superclasses*

A **final** class cannot be extended to create a subclass. All methods in a `final` class are implicitly `final`. Class `String` is an example of a `final` class. If you were allowed to create a subclass of `String`, objects of that subclass could be used wherever `Strings` are expected. Since class `String` cannot be extended, programs that use `Strings` can rely on the functionality of `String` objects as specified in the Java API. Making the class `final` also prevents programmers from creating subclasses that might bypass security restrictions.

We've now discussed declaring variables, methods and classes `final`, and we've emphasized that if something *can* be `final` it *should* be `final`. Compilers can perform various optimizations when they know something is `final`. When we study concurrency in Chapter 23, you'll see that `final` variables make it much easier to parallelize your programs for use on today's multi-core processors. For more insights on the use of `final`, visit

<http://docs.oracle.com/javase/tutorial/java/IandI/final.html>



### **Common Programming Error 10.5**

*Attempting to declare a subclass of a `final` class is a compilation error.*



### **Software Engineering Observation 10.6**

*In the Java API, the vast majority of classes are not declared `final`. This enables inheritance and polymorphism. However, in some cases, it's important to declare classes `final`—typically for security reasons. Also, unless you carefully design a class for extension, you should declare the class as `final` to avoid (often subtle) errors.*

## **10.8 A Deeper Explanation of Issues with Calling Methods from Constructors**

Do not call overridable methods from constructors. When creating a *subclass* object, this could lead to an overridden method being called before the *subclass* object is fully initialized.

Recall that when you construct a *subclass* object, its constructor first calls one of the direct *superclass's* constructors. If the *superclass* constructor calls an overridable method, the *subclass's* version of that method will be called by the *superclass* constructor—before the *subclass* constructor's body has a chance to execute. This could lead to subtle, difficult-to-detect errors if the *subclass* method that was called depends on initialization that has not yet been performed in the *subclass* constructor's body.

It's acceptable to call a `static` method from a constructor. For example, a constructor and a *set* method often perform the same validation for a particular instance variable. If the validation code is brief, it's acceptable to duplicate it in the constructor and the *set* method. If lengthier validation is required, define a `static` validation method (typically a `private` helper method) then call it from the constructor and the *set* method. It's also acceptable for a constructor to call a `final` instance method, provided that the method does not directly or indirectly call an overridable instance method.

## 10.9 Creating and Using Interfaces

[Note: As written, this section and its code example apply through Java SE 7. Java SE 8's interface enhancements are introduced in Section 10.10 and discussed in more detail in Chapter 17.]

Our next example (Figs. 10.11–10.15) reexamines the payroll system of Section 10.5. Suppose that the company involved wishes to perform several accounting operations in a single accounts payable application—in addition to calculating the earnings that must be paid to each employee, the company must also calculate the payment due on each of several invoices (i.e., bills for goods purchased). Though applied to *unrelated* things (i.e., employees and invoices), both operations have to do with obtaining some kind of payment amount. For an employee, the payment refers to the employee's earnings. For an invoice, the payment refers to the total cost of the goods listed on the invoice. Can we calculate such *different* things as the payments due for employees and invoices in a *single* application *polymorphically*? Does Java offer a capability requiring that *unrelated* classes implement a set of *common* methods (e.g., a method that calculates a payment amount)? Java **interfaces** offer exactly this capability.

### Standardizing Interactions

Interfaces define and standardize the ways in which things such as people and systems can interact with one another. For example, the controls on a radio serve as an interface between radio users and a radio's internal components. The controls allow users to perform only a limited set of operations (e.g., change the station, adjust the volume, choose between AM and FM), and different radios may implement the controls in different ways (e.g., using push buttons, dials, voice commands). The interface specifies *what* operations a radio must permit users to perform but does not specify *how* the operations are performed.

### Software Objects Communicate Via Interfaces

Software objects also communicate via interfaces. A Java interface describes a set of methods that can be called on an object to tell it, for example, to perform some task or return some piece of information. The next example introduces an interface named `Payable` to describe the functionality of any object that must be “capable of being paid” and thus must offer a method to determine the proper payment amount due. An **interface declaration** begins with the keyword **interface** and contains *only* constants and abstract methods. Unlike classes, all interface members *must* be `public`, and *interfaces may not specify any implementation details*, such as concrete method declarations and instance variables. All methods declared in an interface are implicitly `public` abstract methods, and all fields are implicitly `public`, `static` and `final`.



### Good Programming Practice 10.1

According to the Java Language Specification, it's proper style to declare an interface's abstract methods without keywords `public` and `abstract`, because they're redundant in interface-method declarations. Similarly, an interface's constants should be declared without keywords `public`, `static` and `final`, because they, too, are redundant.

### Using an Interface

To use an interface, a concrete class must specify that it **implements** the interface and must declare each method in the interface with the signature specified in the interface declaration. To specify that a class implements an interface, add the `implements` keyword and the

name of the interface to the end of your class declaration's first line. A class that does not implement *all* the methods of the interface is an *abstract* class and must be declared `abstract`. Implementing an interface is like signing a *contract* with the compiler that states, "I will declare all the methods specified by the interface or I will declare my class `abstract`."



### Common Programming Error 10.6

*Failing to implement any method of an interface in a concrete class that implements the interface results in a compilation error indicating that the class must be declared `abstract`.*

### Relating Disparate Types

An interface is often used when *disparate* classes—i.e., classes that are not related by a class hierarchy—need to share common methods and constants. This allows objects of *unrelated* classes to be processed *polymorphically*—objects of classes that implement the *same* interface can respond to the *same* method calls. You can create an interface that describes the desired functionality, then implement this interface in any classes that require that functionality. For example, in the accounts payable application developed in this section, we implement interface `Payable` in any class that must be able to calculate a payment amount (e.g., `Employee`, `Invoice`).

### Interfaces vs. Abstract Classes

*An interface is often used in place of an abstract class when there's no default implementation to inherit—that is, no fields and no default method implementations. Like public abstract classes, interfaces are typically public types. Like a public class, a public interface must be declared in a file with the same name as the interface and the `.java` filename extension.*



### Software Engineering Observation 10.7

*Many developers feel that interfaces are an even more important modeling technology than classes, especially with the new interface enhancements in Java SE 8 (see Section 10.10).*

### Tagging Interfaces

We'll see in Chapter 15, Files, Streams and Object Serialization, the notion of *tagging interfaces* (also called *marker interfaces*)—empty interfaces that have *no* methods or constant values. They're used to add *is-a* relationships to classes. For example, in Chapter 15 we'll discuss a mechanism called *object serialization*, which can convert objects to byte representations and can convert those byte representations back to objects. To enable this mechanism to work with your objects, you simply have to mark them as `Serializable` by adding `implements Serializable` to the end of your class declaration's first line. Then, all the objects of your class have the *is-a* relationship with `Serializable`.

## 10.9.1 Developing a `Payable` Hierarchy

To build an application that can determine payments for employees and invoices alike, we first create interface `Payable`, which contains method `getPaymentAmount` that returns a `double` amount that must be paid for an object of any class that implements the interface. Method `getPaymentAmount` is a general-purpose version of method `earnings` of the `Employee` hierarchy—method `earnings` calculates a payment amount specifically for an `Employee`, while `getPaymentAmount` can be applied to a broad range of possibly unrelated objects. After declaring interface `Payable`, we introduce class `Invoice`, which implements

interface `Payable`. We then modify class `Employee` such that it also implements interface `Payable`. Finally, we update `Employee` subclass `SalariedEmployee` to “fit” into the `Payable` hierarchy by renaming `SalariedEmployee` method `earnings` as `getPaymentAmount`.




### Good Programming Practice 10.2

*When declaring a method in an interface, choose a method name that describes the method’s purpose in a general manner, because the method may be implemented by many unrelated classes.*

Classes `Invoice` and `Employee` both represent things for which the company must be able to calculate a payment amount. Both classes implement the `Payable` interface, so a program can invoke method `getPaymentAmount` on `Invoice` objects and `Employee` objects alike. As we’ll soon see, this enables the *polymorphic* processing of `Invoices` and `Employees` required for the company’s accounts payable application.

The UML class diagram in Fig. 10.10 shows the interface and class hierarchy used in our accounts payable application. The hierarchy begins with interface `Payable`. The UML distinguishes an interface from other classes by placing the word “interface” in guillemets (« and ») above the interface name. The UML expresses the relationship between a class and an interface through a relationship known as **realization**. A class is said to *realize*, or *implement*, the methods of an interface. A class diagram models a realization as a dashed arrow with a hollow arrowhead pointing from the implementing class to the interface. The diagram in Fig. 10.10 indicates that classes `Invoice` and `Employee` each realize interface `Payable`. As in the class diagram of Fig. 10.2, class `Employee` appears in *italics*, indicating that it’s an *abstract class*. Concrete class `SalariedEmployee` extends `Employee`, *inheriting its superclass’s realization relationship* with interface `Payable`.



**Fig. 10.10** | `Payable` hierarchy UML class diagram.

## 10.9.2 Interface `Payable`

The declaration of interface `Payable` begins in Fig. 10.11 at line 4. Interface `Payable` contains public abstract method `getPaymentAmount`. Interface methods are always public and abstract, so they do not need to be declared as such. Interface `Payable` has only one method, but interfaces can have *any* number of methods. In addition, method `getPaymentAmount` has no parameters, but interface methods *can* have parameters. Interfaces may also contain `final static` constants.

---

```

1 // Fig. 10.11: Payable.java
2 // Payable interface declaration.
3
4 public interface Payable
5 {
6 double getPaymentAmount(); // calculate payment; no implementation
7 }

```

---

**Fig. 10.11** | Payable interface declaration.

### 10.9.3 Class Invoice

We now create class `Invoice` (Fig. 10.12) to represent a simple invoice that contains billing information for only one kind of part. The class declares private instance variables `partNumber`, `partDescription`, `quantity` and `pricePerItem` (in lines 6–9) that indicate the part number, a description of the part, the quantity of the part ordered and the price per item. Class `Invoice` also contains a constructor (lines 12–26), *get* and *set* methods (lines 29–69) that manipulate the class’s instance variables and a `toString` method (lines 72–78) that returns a `String` representation of an `Invoice` object. Methods `setQuantity` (lines 41–47) and `setPricePerItem` (lines 56–63) ensure that `quantity` and `pricePerItem` obtain only nonnegative values.

---

```

1 // Fig. 10.12: Invoice.java
2 // Invoice class that implements Payable.
3
4 public class Invoice implements Payable
5 {
6 private final String partNumber;
7 private final String partDescription;
8 private int quantity;
9 private double pricePerItem;
10
11 // constructor
12 public Invoice(String partNumber, String partDescription, int quantity,
13 double pricePerItem)
14 {
15 if (quantity < 0) // validate quantity
16 throw new IllegalArgumentException("Quantity must be >= 0");
17
18 if (pricePerItem < 0.0) // validate pricePerItem
19 throw new IllegalArgumentException(
20 "Price per item must be >= 0");
21
22 this.quantity = quantity;
23 this.partNumber = partNumber;
24 this.partDescription = partDescription;
25 this.pricePerItem = pricePerItem;
26 } // end constructor
27

```

---

**Fig. 10.12** | Invoice class that implements `Payable`. (Part 1 of 3.)



---

```

28 // get part number
29 public String getPartNumber()
30 {
31 return partNumber; // should validate
32 }
33
34 // get description
35 public String getPartDescription()
36 {
37 return partDescription;
38 }
39
40 // set quantity
41 public void setQuantity(int quantity)
42 {
43 if (quantity < 0) // validate quantity
44 throw new IllegalArgumentException("Quantity must be >= 0");
45
46 this.quantity = quantity;
47 }
48
49 // get quantity
50 public int getQuantity()
51 {
52 return quantity;
53 }
54
55 // set price per item
56 public void setPricePerItem(double pricePerItem)
57 {
58 if (pricePerItem < 0.0) // validate pricePerItem
59 throw new IllegalArgumentException(
60 "Price per item must be >= 0");
61
62 this.pricePerItem = pricePerItem;
63 }
64
65 // get price per item
66 public double getPricePerItem()
67 {
68 return pricePerItem;
69 }
70
71 // return String representation of Invoice object
72 @Override
73 public String toString()
74 {
75 return String.format("%s: %n%s: %s (%s) %n%s: %d %n%s: $%,.2f",
76 "invoice", "part number", getPartNumber(), getPartDescription(),
77 "quantity", getQuantity(), "price per item", getPricePerItem());
78 }
79

```

---

**Fig. 10.12** | Invoice class that implements Payable. (Part 2 of 3.)

---

```

80 // method required to carry out contract with interface Payable
81 @Override
82 public double getPaymentAmount()
83 {
84 return getQuantity() * getPricePerItem(); // calculate total cost
85 }
86 } // end class Invoice

```

---

**Fig. 10.12** | Invoice class that implements Payable. (Part 3 of 3.)

### *A Class Can Extend Only One Other Class But Can Implement Many Interfaces*

Line 4 indicates that class `Invoice` implements interface `Payable`. Like all classes, class `Invoice` also *implicitly* extends `Object`. Java does not allow subclasses to inherit from more than one superclass, but it allows a class to *inherit* from one *superclass* and *implement* as many *interfaces* as it needs. To implement more than one interface, use a comma-separated list of interface names after keyword `implements` in the class declaration, as in:

```
public class ClassName extends SuperclassName implements FirstInterface,
 SecondInterface, ...
```



### **Software Engineering Observation 10.8**

*All objects of a class that implements multiple interfaces have the is-a relationship with each implemented interface type.*

Class `Invoice` implements the one abstract method in interface `Payable`—method `getPaymentAmount` is declared in lines 81–85. The method calculates the total payment required to pay the invoice. The method multiplies the values of `quantity` and `pricePerItem` (obtained through the appropriate *get* methods) and returns the result. This method satisfies the implementation requirement for this method in interface `Payable`—we’ve *fulfilled* the *interface contract* with the compiler.

## **10.9.4 Modifying Class `Employee` to Implement Interface `Payable`**

We now modify class `Employee` such that it implements interface `Payable`. Figure 10.13 contains the modified class, which is identical to that of Fig. 10.4 with two exceptions. First, line 4 of Fig. 10.13 indicates that class `Employee` now implements interface `Payable`. For this example, we renamed method `earnings` to `getPaymentAmount` throughout the `Employee` hierarchy. As with method `earnings` in the version of class `Employee` in Fig. 10.4, however, it does not make sense to *implement* method `getPaymentAmount` in class `Employee` because we cannot calculate the earnings payment owed to a *general* `Employee`—we must first know the *specific* type of `Employee`. In Fig. 10.4, we declared method `earnings` as abstract for this reason, so class `Employee` had to be declared abstract. This forced each `Employee` *concrete* subclass to *override* `earnings` with an implementation.

---

```

1 // Fig. 10.13: Employee.java
2 // Employee abstract superclass that implements Payable.
3

```

---

**Fig. 10.13** | `Employee` abstract superclass that implements `Payable`. (Part 1 of 2.)

---

```

4 public abstract class Employee implements Payable
5 {
6 private final String firstName;
7 private final String lastName;
8 private final String socialSecurityNumber;
9
10 // constructor
11 public Employee(String firstName, String lastName,
12 String socialSecurityNumber)
13 {
14 this.firstName = firstName;
15 this.lastName = lastName;
16 this.socialSecurityNumber = socialSecurityNumber;
17 }
18
19 // return first name
20 public String getFirstName()
21 {
22 return firstName;
23 }
24
25 // return last name
26 public String getLastName()
27 {
28 return lastName;
29 }
30
31 // return social security number
32 public String getSocialSecurityNumber()
33 {
34 return socialSecurityNumber;
35 }
36
37 // return String representation of Employee object
38 @Override
39 public String toString()
40 {
41 return String.format("%s %s\nsocial security number: %s",
42 getFirstName(), getLastName(), getSocialSecurityNumber());
43 }
44
45 // Note: We do not implement Payable method getPaymentAmount here so
46 // this class must be declared abstract to avoid a compilation error.
47 } // end abstract class Employee

```

---

**Fig. 10.13** | Employee abstract superclass that implements Payable. (Part 2 of 2.)

In Fig. 10.13, we handle this situation differently. Recall that when a class implements an interface, it makes a *contract* with the compiler stating either that the class will implement *each* method in the interface or the class will be declared abstract. Because class `Employee` does not provide a `getPaymentAmount` method, the class must be declared abstract. Any concrete subclass of the abstract class *must* implement the interface methods to fulfill the superclass's contract with the compiler. If the subclass does *not* do so, it too *must* be declared

abstract. As indicated by the comments in lines 45–46, class `Employee` of Fig. 10.13 does *not* implement method `getPaymentAmount`, so the class is declared abstract. Each direct `Employee` subclass *inherits the superclass's contract* to implement method `getPaymentAmount` and thus must implement this method to become a concrete class for which objects can be instantiated. A class that extends one of `Employee`'s concrete subclasses will inherit an implementation of `getPaymentAmount` and thus will also be a concrete class.

### 10.9.5 Modifying Class `SalariedEmployee` for Use in the `Payable` Hierarchy

Figure 10.14 contains a modified `SalariedEmployee` class that extends `Employee` and fulfills superclass `Employee`'s contract to implement `Payable` method `getPaymentAmount`. This version of `SalariedEmployee` is identical to that of Fig. 10.5, but it replaces method `earnings` with method `getPaymentAmount` (lines 39–43). Recall that the `Payable` version of the method has a more *general* name to be applicable to possibly *disparate* classes. (If we included the remaining `Employee` subclasses from Section 10.5—`HourlyEmployee`, `CommissionEmployee` and `BasePlusCommissionEmployee`—in this example, their `earnings` methods should also be renamed `getPaymentAmount`. We leave these modifications to Exercise 10.15 and use only `SalariedEmployee` in our test program here. Exercise 10.16 asks you to implement interface `Payable` in the entire `Employee` class hierarchy of Figs. 10.4–10.9 *without* modifying the `Employee` subclasses.)

---

```

1 // Fig. 10.14: SalariedEmployee.java
2 // SalariedEmployee class that implements interface Payable.
3 // method getPaymentAmount.
4 public class SalariedEmployee extends Employee
5 {
6 private double weeklySalary;
7
8 // constructor
9 public SalariedEmployee(String firstName, String lastName,
10 String socialSecurityNumber, double weeklySalary)
11 {
12 super(firstName, lastName, socialSecurityNumber);
13
14 if (weeklySalary < 0.0)
15 throw new IllegalArgumentException(
16 "Weekly salary must be >= 0.0");
17
18 this.weeklySalary = weeklySalary;
19 }
20
21 // set salary
22 public void setWeeklySalary(double weeklySalary)
23 {
24 if (weeklySalary < 0.0)
25 throw new IllegalArgumentException(
26 "Weekly salary must be >= 0.0");

```

---

**Fig. 10.14** | `SalariedEmployee` class that implements interface `Payable` method `getPaymentAmount`. (Part 1 of 2.)

```

27
28 this.weeklySalary = weeklySalary;
29 }
30
31 // return salary
32 public double getWeeklySalary()
33 {
34 return weeklySalary;
35 }
36
37 // calculate earnings; implement interface Payable method that was
38 // abstract in superclass Employee
39 @Override
40 public double getPaymentAmount()
41 {
42 return getWeeklySalary();
43 }
44
45 // return String representation of SalariedEmployee object
46 @Override
47 public String toString()
48 {
49 return String.format("salaried employee: %s\ns: $%,.2f",
50 super.toString(), "weekly salary", getWeeklySalary());
51 }
52 } // end class SalariedEmployee

```

**Fig. 10.14** | SalariedEmployee class that implements interface Payable method getPaymentAmount. (Part 2 of 2.)

When a class implements an interface, the same *is-a* relationship provided by inheritance applies. Class Employee implements Payable, so we can say that an Employee *is a* Payable. In fact, objects of any classes that extend Employee are also Payable objects. SalariedEmployee objects, for instance, are Payable objects. Objects of any subclasses of the class that implements the interface can also be thought of as objects of the interface type. Thus, just as we can assign the reference of a SalariedEmployee object to a superclass Employee variable, we can assign the reference of a SalariedEmployee object to an interface Payable variable. Invoice implements Payable, so an Invoice object also *is a* Payable object, and we can assign the reference of an Invoice object to a Payable variable.



### Software Engineering Observation 10.9

*When a method parameter is declared with a superclass or interface type, the method processes the object passed as an argument polymorphically.*



### Software Engineering Observation 10.10

*Using a superclass reference, we can polymorphically invoke any method declared in the superclass and its superclasses (e.g., class Object). Using an interface reference, we can polymorphically invoke any method declared in the interface, its superinterfaces (one interface can extend another) and in class Object—a variable of an interface type must refer to an object to call methods, and all objects have the methods of class Object.*

### 10.9.6 Using Interface Payable to Process Invoices and Employees Polymorphically

PayableInterfaceTest (Fig. 10.15) illustrates that interface Payable can be used to process a set of Invoices and Employees *polymorphically* in a single application. Line 9 declares payableObjects and assigns it an array of four Payable variables. Lines 12–13 assign the references of Invoice objects to the first two elements of payableObjects. Lines 14–17 then assign the references of SalariedEmployee objects to the remaining two elements of payableObjects. These assignments are allowed because an Invoice *is a* Payable, a SalariedEmployee *is an* Employee and an Employee *is a* Payable. Lines 23–29 use the enhanced for statement to *polymorphically* process each Payable object in payableObjects, printing the object as a String, along with the payment amount due. Line 27 invokes method toString via a Payable interface reference, even though toString is not declared in interface Payable—all references (including those of interface types) refer to objects that extend Object and therefore have a toString method. (Method toString also can be invoked *implicitly* here.) Line 28 invokes Payable method getPaymentAmount to obtain the payment amount for each object in payableObjects, *regardless* of the actual type of the object. The output reveals that each of the method calls in lines 27–28 invokes the appropriate class's implementation of methods toString and getPaymentAmount. For instance, when currentPayable refers to an Invoice during the first iteration of the for loop, class Invoice's toString and getPaymentAmount execute.

---

```

1 // Fig. 10.15: PayableInterfaceTest.java
2 // Payable interface test program processing Invoices and
3 // Employees polymorphically.
4 public class PayableInterfaceTest
5 {
6 public static void main(String[] args)
7 {
8 // create four-element Payable array
9 Payable[] payableObjects = new Payable[4];
10
11 // populate array with objects that implement Payable
12 payableObjects[0] = new Invoice("01234", "seat", 2, 375.00);
13 payableObjects[1] = new Invoice("56789", "tire", 4, 79.95);
14 payableObjects[2] =
15 new SalariedEmployee("John", "Smith", "111-11-1111", 800.00);
16 payableObjects[3] =
17 new SalariedEmployee("Lisa", "Barnes", "888-88-8888", 1200.00);
18
19 System.out.println(
20 "Invoices and Employees processed polymorphically:");
21
22 // generically process each element in array payableObjects
23 for (Payable currentPayable : payableObjects)
24 {

```

---

**Fig. 10.15** | Payable interface test program processing Invoices and Employees polymorphically. (Part 1 of 2.)

```

25 // output currentPayable and its appropriate payment amount
26 System.out.printf("%n%s %n%s: $%,.2f%n",
27 currentPayable.toString(), // could invoke implicitly
28 "payment due", currentPayable.getPaymentAmount());
29 }
30 } // end main
31 } // end class PayableInterfaceTest

```

Invoices and Employees processed polymorphically:

```

invoice:
part number: 01234 (seat)
quantity: 2
price per item: $375.00
payment due: $750.00

invoice:
part number: 56789 (tire)
quantity: 4
price per item: $79.95
payment due: $319.80

salaried employee: John Smith
social security number: 111-11-1111
weekly salary: $800.00
payment due: $800.00

salaried employee: Lisa Barnes
social security number: 888-88-8888
weekly salary: $1,200.00
payment due: $1,200.00

```

**Fig. 10.15** | Payable interface test program processing Invoices and Employees polymorphically. (Part 2 of 2.)

### 10.9.7 Some Common Interfaces of the Java API

You'll use interfaces extensively when developing Java applications. The Java API contains numerous interfaces, and many of the Java API methods take interface arguments and return interface values. Figure 10.16 overviews a few of the more popular interfaces of the Java API that we use in later chapters.

| Interface  | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |
|------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Comparable | Java contains several comparison operators (e.g., <, <=, >, >=, ==, !=) that allow you to compare primitive values. However, these operators <i>cannot</i> be used to compare objects. Interface Comparable is used to allow objects of a class that implements the interface to be compared to one another. Interface Comparable is commonly used for ordering objects in a collection such as an array. We use Comparable in Chapter 16, Generic Collections, and Chapter 20, Generic Classes and Methods. |

**Fig. 10.16** | Common interfaces of the Java API. (Part 1 of 2.)

| Interface                     | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |
|-------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>Serializable</code>     | An interface used to identify classes whose objects can be written to (i.e., serialized) or read from (i.e., deserialized) some type of storage (e.g., file on disk, database field) or transmitted across a network. We use <code>Serializable</code> in Chapter 15, Files, Streams and Object Serialization, and Chapter 28, Networking.                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |
| <code>Runnable</code>         | Implemented by any class that represents a task to perform. Objects of such as class are often executed in parallel using a technique called <i>multithreading</i> (discussed in Chapter 23, Concurrency). The interface contains one method, <code>run</code> , which specifies the behavior of an object when executed.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |
| GUI event-listener interfaces | You work with graphical user interfaces (GUIs) every day. In your web browser, you might type the address of a website to visit, or you might click a button to return to a previous site. The browser responds to your interaction and performs the desired task. Your interaction is known as an <i>event</i> , and the code that the browser uses to respond to an event is known as an <i>event handler</i> . In Chapter 12, GUI Components: Part 1, and Chapter 22, GUI Components: Part 2, you'll learn how to build GUIs and event handlers that respond to user interactions. Event handlers are declared in classes that implement an appropriate <i>event-listener interface</i> . Each event-listener interface specifies one or more methods that must be implemented to respond to user interactions. |
| <code>AutoCloseable</code>    | Implemented by classes that can be used with the try-with-resources statement (Chapter 11, Exception Handling: A Deeper Look) to help prevent resource leaks.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |

**Fig. 10.16** | Common interfaces of the Java API. (Part 2 of 2.)

## 10.10 Java SE 8 Interface Enhancements

This section introduces Java SE 8's new interface features. We discuss these in more detail in later chapters.

### 10.10.1 default Interface Methods

Prior to Java SE 8, interface methods could be *only* public abstract methods. This meant that an interface specified *what* operations an implementing class must perform but not *how* the class should perform them.

In Java SE 8, interfaces also may contain public **default methods** with *concrete* default implementations that specify *how* operations are performed when an implementing class does not override the methods. If a class implements such an interface, the class also receives the interface's default implementations (if any). To declare a default method, place the keyword `default` before the method's return type and provide a concrete method implementation.

#### *Adding Methods to Existing Interfaces*

Prior to Java SE 8, adding methods to an interface would break any implementing classes that did not implement the new methods. Recall that if you didn't implement each of an interface's methods, you had to declare your class `abstract`.

Any class that implements the original interface will *not* break when a default method is added—the class simply receives the new default method. When a class imple-



ments a Java SE 8 interface, the class “signs a contract” with the compiler that says, “I will declare all the *abstract* methods specified by the interface or I will declare my class *abstract*”—the implementing class is not required to override the interface’s default methods, but it can if necessary.



### Software Engineering Observation 10.11

*Java SE 8 default methods enable you to evolve existing interfaces by adding new methods to those interfaces without breaking code that uses them.*

#### Interfaces vs. *abstract* Classes

Prior to Java SE 8, an interface was typically used (rather than an abstract class) when there were no implementation details to inherit—no fields and no method implementations. With default methods, you can instead declare common method implementations in interfaces, which gives you more flexibility in designing your classes.

#### 10.10.2 static Interface Methods

Prior to Java SE 8, it was common to associate with an interface a class containing static helper methods for working with objects that implemented the interface. In Chapter 16, you’ll learn about class `Collections` which contains many static helper methods for working with objects that implement interfaces `Collection`, `List`, `Set` and more. For example, `Collections` method `sort` can sort objects of *any* class that implements interface `List`. With static interface methods, such helper methods can now be declared directly in interfaces rather than in separate classes.

#### 10.10.3 Functional Interfaces

As of Java SE 8, any interface containing only one abstract method is known as a **functional interface**. There are many such interfaces throughout the Java SE 7 APIs, and many new ones in Java SE 8. Some functional interfaces that you’ll use in this book include:

- `ActionListener` (Chapter 12)—You’ll implement this interface to define a method that’s called when the user clicks a button.
- `Comparator` (Chapter 16)—You’ll implement this interface to define a method that can compare two objects of a given type to determine whether the first object is less than, equal to or greater than the second.
- `Runnable` (Chapter 23)—You’ll implement this interface to define a task that may be run in parallel with other parts of your program.

Functional interfaces are used extensively with Java SE 8’s new lambda capabilities that we introduce in Chapter 17. In Chapter 12, you’ll often implement an interface by creating a so-called anonymous inner class that implements the interface’s method(s). In Java SE 8, lambdas provide a shorthand notation for creating *anonymous methods* that the compiler automatically translates into anonymous inner classes for you.


## 10.11 (Optional) GUI and Graphics Case Study: Drawing with Polymorphism

You may have noticed in the drawing program created in GUI and Graphics Case Study Exercise 8.1 (and modified in GUI and Graphics Case Study Exercise 9.1) that shape

classes have many similarities. Using inheritance, we can “factor out” the common features from all three classes and place them in a single shape *superclass*. Then, using variables of the superclass type, we can manipulate shape objects *polymorphically*. Removing the redundant code will result in a smaller, more flexible program that’s easier to maintain.

### GUI and Graphics Case Study Exercises

**10.1** Modify the `MyLine`, `MyOval` and `MyRectangle` classes of GUI and Graphics Case Study Exercise 8.1 and Exercise 9.1 to create the class hierarchy in Fig. 10.17. Classes of the `MyShape` hierarchy should be “smart” shape classes that know how to draw themselves (if provided with a `Graphics` object that tells them where to draw). Once the program creates an object from this hierarchy, it can manipulate it *polymorphically* for the rest of its lifetime as a `MyShape`.



**Fig. 10.17** | `MyShape` hierarchy.

In your solution, class `MyShape` in Fig. 10.17 *must* be abstract. Since `MyShape` represents any shape in general, you cannot implement a `draw` method without knowing *specifically* what shape it is. The data representing the coordinates and color of the shapes in the hierarchy should be declared as `private` members of class `MyShape`. In addition to the common data, class `MyShape` should declare the following methods:

- A *no-argument constructor* that sets all the coordinates of the shape to 0 and the color to `Color.BLACK`.
- A constructor that initializes the coordinates and color to the values of the arguments supplied.
- Set* methods for the individual coordinates and color that allow the programmer to set any piece of data independently for a shape in the hierarchy.
- Get* methods for the individual coordinates and color that allow the programmer to retrieve any piece of data independently for a shape in the hierarchy.
- The abstract method

```
public abstract void draw(Graphics g);
```

which the program’s `paintComponent` method will call to draw a shape on the screen.

To ensure proper encapsulation, all data in class `MyShape` must be `private`. This requires declaring proper *set* and *get* methods to manipulate the data. Class `MyLine` should provide a no-argument constructor and a constructor with arguments for the coordinates and color. Classes `MyOval` and `MyRectangle` should provide a no-argument constructor and a constructor with argu-

ments for the coordinates, color and determining whether the shape is filled. The no-argument constructor should, in addition to setting the default values, set the shape to be an unfilled shape.


You can draw lines, rectangles and ovals if you know two points in space. Lines require  $x1$ ,  $y1$ ,  $x2$  and  $y2$  coordinates. The `drawLine` method of the `Graphics` class will connect the two points supplied with a line. If you have the same four coordinate values ( $x1$ ,  $y1$ ,  $x2$  and  $y2$ ) for ovals and rectangles, you can calculate the four arguments needed to draw them. Each requires an upper-left  $x$ -coordinate value (the smaller of the two  $x$ -coordinate values), an upper-left  $y$ -coordinate value (the smaller of the two  $y$ -coordinate values), a *width* (the absolute value of the difference between the two  $x$ -coordinate values) and a *height* (the absolute value of the difference between the two  $y$ -coordinate values). Rectangles and ovals should also have a `filled` flag that determines whether to draw the shape as a filled shape.

There should be no `MyLine`, `MyOval` or `MyRectangle` variables in the program—only `MyShape` variables that contain references to `MyLine`, `MyOval` and `MyRectangle` objects. The program should generate random shapes and store them in an array of type `MyShape`. Method `paintComponent` should walk through the `MyShape` array and draw every shape, by polymorphically calling every shape's `draw` method.

Allow the user to specify (via an input dialog) the number of shapes to generate. The program will then generate and display the shapes along with a status bar that informs the user how many of each shape were created.

**10.2 (Drawing Application Modification)** In the preceding exercise, you created a `MyShape` hierarchy in which classes `MyLine`, `MyOval` and `MyRectangle` extend `MyShape` directly. If your hierarchy was properly designed, you should be able to see the similarities between the `MyOval` and `MyRectangle` classes. Redesign and reimplement the code for the `MyOval` and `MyRectangle` classes to “factor out” the common features into the abstract class `MyBoundedShape` to produce the hierarchy in Fig. 10.18.

Class `MyBoundedShape` should declare two constructors that mimic those of class `MyShape`, only with an added parameter to specify whether the shape is filled. Class `MyBoundedShape` should also declare *get* and *set* methods for manipulating the filled flag and methods that calculate the upper-left  $x$ -coordinate, upper-left  $y$ -coordinate, width and height. Remember, the values needed to draw an oval or a rectangle can be calculated from two  $(x, y)$  coordinates. If designed properly, the new `MyOval` and `MyRectangle` classes should each have two constructors and a `draw` method.



**Fig. 10.18** | `MyShape` hierarchy with `MyBoundedShape`.

## 10.12 Wrap-Up

This chapter introduced polymorphism—the ability to process objects that share the same superclass in a class hierarchy as if they were all objects of the superclass. We discussed how polymorphism makes systems extensible and maintainable, then demonstrated how to use overridden methods to effect polymorphic behavior. We introduced abstract classes, which allow you to provide an appropriate superclass from which other classes can inherit. You learned that an abstract class can declare abstract methods that each subclass must implement to become a concrete class and that a program can use variables of an abstract class to invoke the subclasses' implementations of abstract methods polymorphically. You also learned how to determine an object's type at execution time. We explained the notions of final methods and classes. Finally, the chapter discussed declaring and implementing an interface as a way for possibly disparate classes to implement common functionality, enabling objects of those classes to be processed polymorphically.

You should now be familiar with classes, objects, encapsulation, inheritance, interfaces and polymorphism—the most essential aspects of object-oriented programming.

In the next chapter, you'll learn about exceptions, useful for handling errors during a program's execution. Exception handling provides for more robust programs.

## Summary

### *Section 10.1 Introduction*

- Polymorphism (p. 388) enables us to write programs that process objects that share the same superclass as if they were all objects of the superclass; this can simplify programming.
- With polymorphism, we can design and implement systems that are easily extensible. The only parts of a program that must be altered to accommodate new classes are those that require direct knowledge of the new classes that you add to the hierarchy.

### *Section 10.3 Demonstrating Polymorphic Behavior*

- When the compiler encounters a method call made through a variable, it determines if the method can be called by checking the variable's class type. If that class contains the proper method declaration (or inherits one), the call is compiled. At execution time, the type of the object to which the variable refers determines the actual method to use.

### *Section 10.4 Abstract Classes and Methods*

- Abstract classes (p. 393) cannot be used to instantiate objects, because they're incomplete.
- The primary purpose of an abstract class is to provide an appropriate superclass from which other classes can inherit and thus share a common design.
- Classes that can be used to instantiate objects are called concrete classes (p. 394). They provide implementations of every method they declare (some of the implementations can be inherited).
- Programmers often write client code that uses only abstract superclasses (p. 394) to reduce client code's dependencies on specific subclass types.
- Abstract classes sometimes constitute several levels of a hierarchy.
- An abstract class normally contains one or more abstract methods (p. 394).
- Abstract methods do not provide implementations.
- A class that contains any abstract methods must be declared as an abstract class (p. 394). Each concrete subclass must provide implementations of each of the superclass's abstract methods.

- Constructors and `static` methods cannot be declared `abstract`.
- Abstract superclass variables can hold references to objects of any concrete class derived from the superclass. Programs typically use such variables to manipulate subclass objects polymorphically.
- Polymorphism is particularly effective for implementing layered software systems.

### Section 10.5 Case Study: Payroll System Using Polymorphism

- A hierarchy designer can demand that each concrete subclass provide an appropriate method implementation by including an abstract method in a superclass.
- Most method calls are resolved at execution time, based on the type of the object being manipulated. This process is known as dynamic binding (p. 409) or late binding.
- A superclass variable can be used to invoke only methods declared in the superclass.
- Operator `instanceof` (p. 409) determines if an object has the *is-a* relationship with a specific type.
- Every object in Java knows its own class and can access it through `Object` method `getClass` (p. 410), which returns an object of type `Class` (package `java.lang`).
- The *is-a* relationship applies only between the subclass and its superclasses, not vice versa.

### Section 10.7 **final** Methods and Classes

- A method that's declared `final` (p. 411) in a superclass cannot be overridden in a subclass.
- Methods declared `private` are implicitly `final`, because you can't override them in a subclass.
- Methods that are declared `static` are implicitly `final`.
- A `final` method's declaration can never change, so all subclasses use the same implementation, and calls to `final` methods are resolved at compile time—this is known as static binding (p. 412).
- The compiler can optimize programs by removing calls to `final` methods and inlining their expanded code at each method-call location.
- A class that's declared `final` cannot be extended (p. 412).
- All methods in a `final` class are implicitly `final`.

### Section 10.9 Creating and Using Interfaces

- An interface (p. 413) specifies *what* operations are allowed but not *how* they're performed.
- A Java interface describes a set of methods that can be called on an object.
- An interface declaration begins with the keyword `interface` (p. 413).
- All interface members must be `public`, and interfaces may not specify any implementation details, such as concrete method declarations and instance variables.
- All methods declared in an interface are implicitly `public` abstract methods and all fields are implicitly `public`, `static` and `final`.
- To use an interface, a concrete class must specify that it `implements` (p. 413) the interface and must declare each interface method with the signature specified in the interface declaration. A class that does not implement all the interface's methods must be declared `abstract`.
- Implementing an interface is like signing a contract with the compiler that states, "I will declare all the methods specified by the interface or I will declare my class `abstract`."
- An interface is typically used when disparate (i.e., unrelated) classes need to share common methods and constants. This allows objects of unrelated classes to be processed polymorphically—objects of classes that implement the same interface can respond to the same method calls.
- You can create an interface that describes the desired functionality, then implement the interface in any classes that require that functionality.

- An interface is often used in place of an abstract class when there's no default implementation to inherit—that is, no instance variables and no default method implementations.
- Like `public` abstract classes, interfaces are typically `public` types, so they're normally declared in files by themselves with the same name as the interface and the `.java` filename extension.
- Java does not allow subclasses to inherit from more than one superclass, but it does allow a class to inherit from a superclass and implement more than one interface.
- All objects of a class that implement multiple interfaces have the *is-a* relationship with each implemented interface type.
- An interface can declare constants. The constants are implicitly `public`, `static` and `final`.

### Section 10.10 Java SE 8 Interface Enhancements

- In Java SE 8, an interface may declare `default` methods—that is, `public` methods with concrete implementations that specify how an operation should be performed.
- When a class implements an interface, the class receives the interface's `default` concrete implementations if it does not override them.
- To declare a `default` method in an interface, you simply place the keyword `default` before the method's return type and provide a complete method body.
- When you enhance an existing an interface with `default` methods—any classes that implemented the original interface will not break—it'll simply receive the `default` method implementations.
- With `default` methods, you can declare common method implementations in interfaces (rather than abstract classes), which gives you more flexibility in designing your classes.
- As of Java SE 8, interfaces may now include `public static` methods.
- As of Java SE 8, any interface containing only one method is known as a functional interface. There are many such interfaces throughout the Java APIs.
- Functional interfaces are used extensively with Java SE 8's new lambda capabilities. As you'll see, lambdas provide a shorthand notation for creating anonymous methods.

## Self-Review Exercises

- 10.1** Fill in the blanks in each of the following statements:
- If a class contains at least one abstract method, it's a(n) \_\_\_\_\_ class.
  - Classes from which objects can be instantiated are called \_\_\_\_\_ classes.
  - \_\_\_\_\_ involves using a superclass variable to invoke methods on superclass and subclass objects, enabling you to “program in the general.”
  - Methods that are not interface methods and that do not provide implementations must be declared using keyword \_\_\_\_\_.
  - Casting a reference stored in a superclass variable to a subclass type is called \_\_\_\_\_.
- 10.2** State whether each of the statements that follows is *true* or *false*. If *false*, explain why.
- All methods in an abstract class must be declared as abstract methods.
  - Invoking a subclass-only method through a subclass variable is not allowed.
  - If a superclass declares an abstract method, a subclass must implement that method.
  - An object of a class that implements an interface may be thought of as an object of that interface type.
- 10.3** (*Java SE 8 interfaces*) Fill in the blanks in each of the following statements:
- In Java SE 8, an interface may declare \_\_\_\_\_—that is, `public` methods with concrete implementations that specify how an operation should be performed.
  - As of Java SE 8, interfaces can now include \_\_\_\_\_ helper methods.
  - As of Java SE 8, any interface containing only one method is known as a(n) \_\_\_\_\_.

## Answers to Self-Review Exercises

- 10.1** a) abstract. b) concrete. c) Polymorphism. d) abstract. e) downcasting.
- 10.2** a) False. An abstract class can include methods with implementations and abstract methods. b) False. Trying to invoke a subclass-only method with a superclass variable is not allowed. c) False. Only a concrete subclass must implement the method. d) True.
- 10.3** a) default methods. b) static. c) functional interface.

## Exercises

- 10.4** How does polymorphism enable you to program “in the general” rather than “in the specific”? Discuss the key advantages of programming “in the general.”
- 10.5** What are abstract methods? Describe the circumstances in which an abstract method would be appropriate.
- 10.6** How does polymorphism promote extensibility?
- 10.7** Discuss three proper ways in which you can assign superclass and subclass references to variables of superclass and subclass types.
- 10.8** Compare and contrast abstract classes and interfaces. Why would you use an abstract class? Why would you use an interface?
- 10.9** (*Java SE 8 Interfaces*) Explain how default methods enable you to add new methods to an existing interface without breaking the classes that implemented the original interface.
- 10.10** (*Java SE 8 Interfaces*) What is a functional interface?
- 10.11** (*Java SE 8 Interfaces*) Why is it useful to be able to add static methods to interfaces?
- 10.12** (*Payroll System Modification*) Modify the payroll system of Figs. 10.4–10.9 to include private instance variable `birthDate` in class `Employee`. Use class `Date` of Fig. 8.7 to represent an employee’s birthday. Add *get* methods to class `Date`. Assume that payroll is processed once per month. Create an array of `Employee` variables to store references to the various employee objects. In a loop, calculate the payroll for each `Employee` (polymorphically), and add a \$100.00 bonus to the person’s payroll amount if the current month is the one in which the `Employee`’s birthday occurs.
- 10.13** (*Project: Shape Hierarchy*) Implement the Shape hierarchy shown in Fig. 9.3. Each `TwoDimensionalShape` should contain method `getArea` to calculate the area of the two-dimensional shape. Each `ThreeDimensionalShape` should have methods `getArea` and `getVolume` to calculate the surface area and volume, respectively, of the three-dimensional shape. Create a program that uses an array of `Shape` references to objects of each concrete class in the hierarchy. The program should print a text description of the object to which each array element refers. Also, in the loop that processes all the shapes in the array, determine whether each shape is a `TwoDimensionalShape` or a `ThreeDimensionalShape`. If it’s a `TwoDimensionalShape`, display its area. If it’s a `ThreeDimensionalShape`, display its area and volume.
- 10.14** (*Payroll System Modification*) Modify the payroll system of Figs. 10.4–10.9 to include an additional `Employee` subclass `PieceWorker` that represents an employee whose pay is based on the number of pieces of merchandise produced. Class `PieceWorker` should contain private instance variables `wage` (to store the employee’s wage per piece) and `pieces` (to store the number of pieces produced). Provide a concrete implementation of method `earnings` in class `PieceWorker` that calculates the employee’s earnings by multiplying the number of pieces produced by the wage per piece. Create an array of `Employee` variables to store references to objects of each concrete class in the new `Employee` hierarchy. For each `Employee`, display its `String` representation and earnings.

**10.15 (*Accounts Payable System Modification*)** In this exercise, we modify the accounts payable application of Figs. 10.11–10.15 to include the complete functionality of the payroll application of Figs. 10.4–10.9. The application should still process two `Invoice` objects, but now should process one object of each of the four `Employee` subclasses. If the object currently being processed is a `BasePlusCommissionEmployee`, the application should increase the `BasePlusCommissionEmployee`'s base salary by 10%. Finally, the application should output the payment amount for each object. Complete the following steps to create the new application:

- Modify classes `HourlyEmployee` (Fig. 10.6) and `CommissionEmployee` (Fig. 10.7) to place them in the `Payable` hierarchy as subclasses of the version of `Employee` (Fig. 10.13) that implements `Payable`. [*Hint:* Change the name of method `earnings` to `getPaymentAmount` in each subclass so that the class satisfies its inherited contract with interface `Payable`.]
- Modify class `BasePlusCommissionEmployee` (Fig. 10.8) such that it extends the version of class `CommissionEmployee` created in part (a).
- Modify `PayableInterfaceTest` (Fig. 10.15) to polymorphically process two `Invoices`, one `SalariedEmployee`, one `HourlyEmployee`, one `CommissionEmployee` and one `BasePlusCommissionEmployee`. First output a `String` representation of each `Payable` object. Next, if an object is a `BasePlusCommissionEmployee`, increase its base salary by 10%. Finally, output the payment amount for each `Payable` object.

**10.16 (*Accounts Payable System Modification*)** It's possible to include the functionality of the payroll application (Figs. 10.4–10.9) in the accounts payable application without modifying `Employee` subclasses `SalariedEmployee`, `HourlyEmployee`, `CommissionEmployee` or `BasePlusCommissionEmployee`. To do so, you can modify class `Employee` (Fig. 10.4) to implement interface `Payable` and declare method `getPaymentAmount` to invoke method `earnings`. Method `getPaymentAmount` would then be inherited by the subclasses in the `Employee` hierarchy. When `getPaymentAmount` is called for a particular subclass object, it polymorphically invokes the appropriate `earnings` method for that subclass. Reimplement Exercise 10.15 using the original `Employee` hierarchy from the payroll application of Figs. 10.4–10.9. Modify class `Employee` as described in this exercise, and *do not* modify any of class `Employee`'s subclasses.

## Making a Difference

**10.17 (*CarbonFootprint Interface: Polymorphism*)** Using interfaces, as you learned in this chapter, you can specify similar behaviors for possibly disparate classes. Governments and companies worldwide are becoming increasingly concerned with carbon footprints (annual releases of carbon dioxide into the atmosphere) from buildings burning various types of fuels for heat, vehicles burning fuels for power, and the like. Many scientists blame these greenhouse gases for the phenomenon called global warming. Create three small classes unrelated by inheritance—classes `Building`, `Car` and `Bicycle`. Give each class some unique appropriate attributes and behaviors that it does not have in common with other classes. Write an interface `CarbonFootprint` with a `getCarbonFootprint` method. Have each of your classes implement that interface, so that its `getCarbonFootprint` method calculates an appropriate carbon footprint for that class (check out a few websites that explain how to calculate carbon footprints). Write an application that creates objects of each of the three classes, places references to those objects in `ArrayList<CarbonFootprint>`, then iterates through the `ArrayList`, polymorphically invoking each object's `getCarbonFootprint` method. For each object, print some identifying information and the object's carbon footprint.



# Exception Handling: A Deeper Look

# II



*It is common sense to take a method and try it. If it fails, admit it frankly and try another. But above all, try something.*

—Franklin Delano Roosevelt

*O! throw away the  
worse part of it,  
And live the purer  
with the other half.*

—William Shakespeare

*If they're running and they don't  
look where they're going  
I have to come out from  
somewhere and catch them.*

—Jerome David Salinger

## Objectives

In this chapter you'll:

- Learn what exceptions are and how they're handled.
- Learn when to use exception handling.
- Use `try` blocks to delimit code in which exceptions might occur.
- Use `throw` to indicate a problem.
- Use `catch` blocks to specify exception handlers.
- Use the `finally` block to release resources.
- Understand the exception class hierarchy.
- Create user-defined exceptions.

- |                                                                                                   |                                                                         |
|---------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------|
| 11.1 Introduction                                                                                 | 11.8 Chained Exceptions                                                 |
| 11.2 Example: Divide by Zero without Exception Handling                                           | 11.9 Declaring New Exception Types                                      |
| 11.3 Example: Handling <code>ArithmeticExceptions</code> and <code>InputMismatchExceptions</code> | 11.10 Preconditions and Postconditions                                  |
| 11.4 When to Use Exception Handling                                                               | 11.11 Assertions                                                        |
| 11.5 Java Exception Hierarchy                                                                     | 11.12 <code>try-with-Resources</code> : Automatic Resource Deallocation |
| 11.6 <code>finally</code> Block                                                                   | 11.13 Wrap-Up                                                           |
| 11.7 Stack Unwinding and Obtaining Information from an Exception Object                           |                                                                         |

Summary | Self-Review Exercises | Answers to Self-Review Exercises | Exercises

## 11.1 Introduction

As you know from Chapter 6, an exception is an indication of a problem that occurs during a program's execution. Exception handling enables you to create applications that can resolve (or handle) exceptions. In many cases, handling an exception allows a program to continue executing as if no problem had been encountered. The features presented in this chapter help you write *robust* and *fault-tolerant* programs that can deal with problems and continue executing or *terminate gracefully*. Java exception handling is based in part on the work of Andrew Koenig and Bjarne Stroustrup.<sup>1</sup>

First, we demonstrate basic exception-handling techniques by handling an exception that occurs when a method attempts to divide an integer by zero. Next, we introduce several classes at the top of Java's exception-handling class hierarchy. As you'll see, only classes that extend `Throwable` (package `java.lang`) directly or indirectly can be used with exception handling. We then show how to use *chained exceptions*—when you invoke a method that indicates an exception, you can throw another exception and chain the original one to the new one. This enables you to add application-specific information to the original exception. Next, we introduce *preconditions* and *postconditions*, which must be true when your methods are called and when they return, respectively. We then present *assertions*, which you can use at development time to help debug your code. We also discuss two exception-handling features that were introduced in Java SE 7—catching multiple exceptions with one catch handler and the new `try-with-resources` statement that automatically releases a resource after it's used in the `try` block.

This chapter focuses on the exception-handling concepts and presents several mechanical examples that demonstrate various features. As you'll see in later chapters, many Java APIs methods throw exceptions that we handle in our code. Figure 11.1 shows some of the exception types you've already seen and others you'll learn about.

1. A. Koenig and B. Stroustrup, "Exception Handling for C++ (revised)," *Proceedings of the Usenix C++ Conference*, pp. 149–176, San Francisco, April 1990.

| Chapter       | Sample of exceptions used                                                                                                                                                                                                                               |
|---------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Chapter 6     | <code>ArrayIndexOutOfBoundsException</code>                                                                                                                                                                                                             |
| Chapters 8–10 | <code>IllegalArgumentException</code>                                                                                                                                                                                                                   |
| Chapter 11    | <code>ArithmeticException</code> , <code>InputMismatchException</code>                                                                                                                                                                                  |
| Chapter 15    | <code>SecurityException</code> , <code>FileNotFoundException</code> , <code>IOException</code> , <code>ClassNotFoundException</code> , <code>IllegalStateException</code> , <code>FormatterClosedException</code> , <code>NoSuchElementException</code> |
| Chapter 16    | <code>ClassCastException</code> , <code>UnsupportedOperationException</code> , <code>NullPointerException</code> , custom exception types                                                                                                               |
| Chapter 20    | <code>ClassCastException</code> , custom exception types                                                                                                                                                                                                |
| Chapter 21    | <code>IllegalArgumentException</code> , custom exception types                                                                                                                                                                                          |
| Chapter 23    | <code>InterruptedException</code> , <code>IllegalMonitorStateException</code> , <code>ExecutionException</code> , <code>CancellationException</code>                                                                                                    |
| Chapter 28    | <code>MalformedURLException</code> , <code>EOFException</code> , <code>SocketException</code> , <code>InterruptedException</code> , <code>UnknownHostException</code>                                                                                   |
| Chapter 24    | <code>SQLException</code> , <code>IllegalStateException</code> , <code>PatternSyntaxException</code>                                                                                                                                                    |
| Chapter 31    | <code>SQLException</code>                                                                                                                                                                                                                               |

**Fig. 11.1** | Various exception types that you'll see throughout this book

## 11.2 Example: Divide by Zero without Exception Handling

First we demonstrate what happens when errors arise in an application that does not use exception handling. Figure 11.2 prompts the user for two integers and passes them to method `quotient`, which calculates the integer quotient and returns an `int` result. In this example, you'll see that exceptions are **thrown** (i.e., the exception occurs) by a method when it detects a problem and is unable to handle it.

```

1 // Fig. 11.2: DivideByZeroNoExceptionHandling.java
2 // Integer division without exception handling.
3 import java.util.Scanner;
4
5 public class DivideByZeroNoExceptionHandling
6 {
7 // demonstrates throwing an exception when a divide-by-zero occurs
8 public static int quotient(int numerator, int denominator)
9 {
10 return numerator / denominator; // possible division by zero
11 }
12
13 public static void main(String[] args)
14 {
15 Scanner scanner = new Scanner(System.in);

```

**Fig. 11.2** | Integer division without exception handling. (Part 1 of 2.)

```

16
17 System.out.print("Please enter an integer numerator: ");
18 int numerator = scanner.nextInt();
19 System.out.print("Please enter an integer denominator: ");
20 int denominator = scanner.nextInt();
21
22 int result = quotient(numerator, denominator);
23 System.out.printf(
24 "%nResult: %d / %d = %d%n", numerator, denominator, result);
25 }
26 } // end class DivideByZeroNoExceptionHandling

```

```

Please enter an integer numerator: 100
Please enter an integer denominator: 7

Result: 100 / 7 = 14

```

```

Please enter an integer numerator: 100
Please enter an integer denominator: 0
Exception in thread "main" java.lang.ArithmeticException: / by zero
 at DivideByZeroNoExceptionHandling.quotient(
 DivideByZeroNoExceptionHandling.java:10)
 at DivideByZeroNoExceptionHandling.main(
 DivideByZeroNoExceptionHandling.java:22)

```

```

Please enter an integer numerator: 100
Please enter an integer denominator: hello
Exception in thread "main" java.util.InputMismatchException
 at java.util.Scanner.throwFor(Unknown Source)
 at java.util.Scanner.next(Unknown Source)
 at java.util.Scanner.nextInt(Unknown Source)
 at java.util.Scanner.nextInt(Unknown Source)
 at DivideByZeroNoExceptionHandling.main(
 DivideByZeroNoExceptionHandling.java:20)

```

**Fig. 11.2** | Integer division without exception handling. (Part 2 of 2.)

### *Stack Trace*

The first sample execution in Fig. 11.2 shows a successful division. In the second execution, the user enters the value 0 as the denominator. Several lines of information are displayed in response to this invalid input. This information is known as a **stack trace**, which includes the name of the exception (`java.lang.ArithmeticException`) in a descriptive message that indicates the problem that occurred and the method-call stack (i.e., the call chain) at the time it occurred. The stack trace includes the path of execution that led to the exception method by method. This helps you debug the program.

### *Stack Trace for an `ArithmeticException`*

The first line specifies that an `ArithmeticException` has occurred. The text after the name of the exception (“/ by zero”) indicates that this exception occurred as a result of an attempt to divide by zero. Java does not allow division by zero in integer arithmetic. When this occurs, Java throws an **`ArithmeticException`**. `ArithmeticExceptions` can arise from

a number of different problems, so the extra data (“/ by zero”) provides more specific information. Java *does* allow division by zero with floating-point values. Such a calculation results in the value positive or negative infinity, which is represented in Java as a floating-point value (but displays as the string `Infinity` or `-Infinity`). If 0.0 is divided by 0.0, the result is NaN (not a number), which is also represented in Java as a floating-point value (but displays as NaN). If you need to compare a floating-point value to NaN, use the method `isNaN` of class `Float` (for `float` values) or of class `Double` (for `double` values). Classes `Float` and `Double` are in package `java.lang`.

Starting from the last line of the stack trace, we see that the exception was detected in line 22 of method `main`. Each line of the stack trace contains the class name and method (e.g., `DivideByZeroNoExceptionHandling.main`) followed by the filename and line number (e.g., `DivideByZeroNoExceptionHandling.java:22`). Moving up the stack trace, we see that the exception occurs in line 10, in method `quotient`. The top row of the call chain indicates the **throw point**—the initial point at which the exception occurred. The throw point of this exception is in line 10 of method `quotient`.

#### *Stack Trace for an InputMismatchException*

In the third execution, the user enters the string “hello” as the denominator. Notice again that a stack trace is displayed. This informs us that an `InputMismatchException` has occurred (package `java.util`). Our prior examples that input numeric values assumed that the user would input a proper integer value. However, users sometimes make mistakes and input noninteger values. An `InputMismatchException` occurs when `Scanner` method `nextInt` receives a string that does not represent a valid integer. Starting from the end of the stack trace, we see that the exception was detected in line 20 of method `main`. Moving up the stack trace, we see that the exception occurred in method `nextInt`. Notice that in place of the filename and line number, we’re provided with the text `Unknown Source`. This means that the so-called *debugging symbols* that provide the filename and line number information for that method’s class were not available to the JVM—this is typically the case for the classes of the Java API. Many IDEs have access to the Java API source code and will display filenames and line numbers in stack traces.

#### *Program Termination*

In the sample executions of Fig. 11.2 when exceptions occur and stack traces are displayed, the program also *exits*. This does not always occur in Java. Sometimes a program may continue even though an exception has occurred and a stack trace has been printed. In such cases, the application may produce unexpected results. For example, a graphical user interface (GUI) application will often continue executing. In Fig. 11.2 both types of exceptions were detected in method `main`. In the next example, we’ll see how to *handle* these exceptions so that you can enable the program to run to normal completion.

## 11.3 Example: Handling ArithmeticExceptions and InputMismatchExceptions

The application in Fig. 11.3, which is based on Fig. 11.2, uses *exception handling* to process any `ArithmeticExceptions` and `InputMismatchExceptions` that arise. The application still prompts the user for two integers and passes them to method `quotient`, which calculates the quotient and returns an `int` result. This version of the application uses ex-

ception handling so that if the user makes a mistake, the program catches and handles (i.e., deals with) the exception—in this case, allowing the user to re-enter the input.

---

```

1 // Fig. 11.3: DivideByZeroWithExceptionHandling.java
2 // Handling ArithmeticExceptions and InputMismatchExceptions.
3 import java.util.InputMismatchException;
4 import java.util.Scanner;
5
6 public class DivideByZeroWithExceptionHandling
7 {
8 // demonstrates throwing an exception when a divide-by-zero occurs
9 public static int quotient(int numerator, int denominator)
10 throws ArithmeticException
11 {
12 return numerator / denominator; // possible division by zero
13 }
14
15 public static void main(String[] args)
16 {
17 Scanner scanner = new Scanner(System.in);
18 boolean continueLoop = true; // determines if more input is needed
19
20 do
21 {
22 try // read two numbers and calculate quotient
23 {
24 System.out.print("Please enter an integer numerator: ");
25 int numerator = scanner.nextInt();
26 System.out.print("Please enter an integer denominator: ");
27 int denominator = scanner.nextInt();
28
29 int result = quotient(numerator, denominator);
30 System.out.printf("%nResult: %d / %d = %d%n", numerator,
31 denominator, result);
32 continueLoop = false; // input successful; end looping
33 }
34 catch (InputMismatchException inputMismatchException)
35 {
36 System.err.printf("%nException: %s%n",
37 inputMismatchException);
38 scanner.nextLine(); // discard input so user can try again
39 System.out.printf(
40 "You must enter integers. Please try again.%n%n");
41 }
42 catch (ArithmeticException arithmeticException)
43 {
44 System.err.printf("%nException: %s%n", arithmeticException);
45 System.out.printf(
46 "Zero is an invalid denominator. Please try again.%n%n");
47 }
48 } while (continueLoop);
49 }
50 } // end class DivideByZeroWithExceptionHandling

```

---

**Fig. 11.3** | Handling ArithmeticExceptions and InputMismatchExceptions. (Part 1 of 2.)

```
Please enter an integer numerator: 100
Please enter an integer denominator: 7
```

```
Result: 100 / 7 = 14
```

```
Please enter an integer numerator: 100
Please enter an integer denominator: 0
```

```
Exception: java.lang.ArithmeticException: / by zero
Zero is an invalid denominator. Please try again.
```

```
Please enter an integer numerator: 100
Please enter an integer denominator: 7
```

```
Result: 100 / 7 = 14
```

```
Please enter an integer numerator: 100
Please enter an integer denominator: hello
```

```
Exception: java.util.InputMismatchException
You must enter integers. Please try again.
```

```
Please enter an integer numerator: 100
Please enter an integer denominator: 7
```

```
Result: 100 / 7 = 14
```

**Fig. 11.3** | Handling ArithmeticExceptions and InputMismatchExceptions. (Part 2 of 2.)

The first sample execution in Fig. 11.3 does *not* encounter any problems. In the second execution the user enters a *zero denominator*, and an `ArithmeticException` exception occurs. In the third execution the user enters the string "hello" as the denominator, and an `InputMismatchException` occurs. For each exception, the user is informed of the mistake and asked to try again, then is prompted for two new integers. In each sample execution, the program runs to completion successfully.

Class `InputMismatchException` is imported in line 3. Class `ArithmeticException` does not need to be imported because it's in package `java.lang`. Line 18 creates the boolean variable `continueLoop`, which is `true` if the user has *not* yet entered valid input. Lines 20–48 repeatedly ask users for input until a *valid* input is received.

### *Enclosing Code in a try Block*

Lines 22–33 contain a **try block**, which encloses the code that *might* throw an exception and the code that should *not* execute if an exception occurs (i.e., if an exception occurs, the remaining code in the try block will be skipped). A try block consists of the keyword `try` followed by a block of code enclosed in curly braces. [Note: The term “try block” sometimes refers only to the block of code that follows the `try` keyword (not including the `try` keyword itself). For simplicity, we use the term “try block” to refer to the block of

code that follows the `try` keyword, as well as the `try` keyword.] The statements that read the integers from the keyboard (lines 25 and 27) each use method `nextInt` to read an `int` value. Method `nextInt` throws an `InputMismatchException` if the value read in is *not* an integer.

The division that can cause an `ArithmeticException` is not performed in the `try` block. Rather, the call to method `quotient` (line 29) invokes the code that attempts the division (line 12); the JVM *throws* an `ArithmeticException` object when the denominator is zero.



### Software Engineering Observation 11.1

*Exceptions may surface through explicitly mentioned code in a `try` block, through deeply nested method calls initiated by code in a `try` block or from the Java Virtual Machine as it executes Java bytecodes.*

### Catching Exceptions

The `try` block in this example is followed by two catch blocks—one that handles an `InputMismatchException` (lines 34–41) and one that handles an `ArithmeticException` (lines 42–47). A **catch block** (also called a **catch clause** or **exception handler**) *catches* (i.e., receives) and *handles* an exception. A catch block begins with the keyword `catch` followed by a parameter in parentheses (called the *exception parameter*, discussed shortly) and a block of code enclosed in curly braces. [Note: The term “catch clause” is sometimes used to refer to the keyword `catch` followed by a block of code, whereas the term “catch block” refers to only the block of code following the `catch` keyword, but not including it. For simplicity, we use the term “catch block” to refer to the block of code following the `catch` keyword, as well as the keyword itself.]

At least one catch block or a **finally block** (discussed in Section 11.6) *must* immediately follow the `try` block. Each catch block specifies in parentheses an **exception parameter** that identifies the exception type the handler can process. When an exception occurs in a `try` block, the catch block that executes is the *first* one whose type matches the type of the exception that occurred (i.e., the type in the catch block matches the thrown exception type exactly or is a direct or indirect superclass of it). The exception parameter’s name enables the catch block to interact with a caught exception object—e.g., to implicitly invoke the caught exception’s `toString` method (as in lines 37 and 44), which displays basic information about the exception. Notice that we use the **System.err** (standard error stream) object to output error messages. By default, `System.err`’s print methods, like those of `System.out`, display data to the *command prompt*.

Line 38 of the first catch block calls `Scanner` method `nextLine`. Because an `InputMismatchException` occurred, the call to method `nextInt` never successfully read in the user’s data—so we read that input with a call to method `nextLine`. We do not do anything with the input at this point, because we know that it’s *invalid*. Each catch block displays an error message and asks the user to try again. After either catch block terminates, the user is prompted for input. We’ll soon take a deeper look at how this flow of control works in exception handling.



### Common Programming Error 11.1

*It’s a syntax error to place code between a `try` block and its corresponding catch blocks.*



**Multi-catch**

It's relatively common for a try block to be followed by several catch blocks to handle various types of exceptions. If the bodies of several catch blocks are identical, you can use the **multi-catch** feature (introduced in Java SE 7) to catch those exception types in a *single* catch handler and perform the same task. The syntax for a *multi-catch* is:

```
catch (Type1 | Type2 | Type3 e)
```

Each exception type is separated from the next with a vertical bar (`|`). The preceding line of code indicates that *any* of the types (or their subclasses) can be caught in the exception handler. Any number of Throwable types can be specified in a multi-catch.

**Uncaught Exceptions**

An **uncaught exception** is one for which there are no matching catch blocks. You saw uncaught exceptions in the second and third outputs of Fig. 11.2. Recall that when exceptions occurred in that example, the application terminated early (after displaying the exception's *stack trace*). This does not always occur as a result of uncaught exceptions. Java uses a "multithreaded" model of program execution—each **thread** is a *concurrent activity*. One program can have many threads. If a program has only *one* thread, an uncaught exception will cause the program to terminate. If a program has *multiple* threads, an uncaught exception will terminate *only* the thread in which the exception occurred. In such programs, however, certain threads may rely on others, and if one thread terminates due to an uncaught exception, there may be adverse effects on the rest of the program. Chapter 23, Concurrency, discusses these issues in depth.

**Termination Model of Exception Handling**

If an exception occurs in a try block (such as an InputMismatchException being thrown as a result of the code at line 25 of Fig. 11.3), the try block *terminates* immediately and program control transfers to the *first* of the following catch blocks in which the exception parameter's type matches the thrown exception's type. In Fig. 11.3, the first catch block catches InputMismatchExceptions (which occur if invalid input is entered) and the second catch block catches ArithmeticExceptions (which occur if an attempt is made to divide by zero). After the exception is handled, program control does *not* return to the throw point, because the try block has *expired* (and its *local variables* have been *lost*). Rather, control resumes after the last catch block. This is known as the **termination model of exception handling**. Some languages use the **resumption model of exception handling**, in which, after an exception is handled, control resumes just after the *throw point*.

Notice that we name our exception parameters (inputMismatchException and arithmeticException) based on their type. Java programmers often simply use the letter *e* as the name of their exception parameters.

After executing a catch block, this program's flow of control proceeds to the first statement after the last catch block (line 48 in this case). The condition in the `do...while` statement is `true` (variable `continueLoop` contains its initial value of `true`), so control returns to the beginning of the loop and the user is again prompted for input. This control statement will loop until *valid* input is entered. At that point, program control reaches line 32, which assigns `false` to variable `continueLoop`. The try block then *terminates*. If no exceptions are thrown in the try block, the catch blocks are *skipped* and control continues with the first statement after the catch blocks (we'll learn about another possibility when

we discuss the `finally` block in Section 11.6). Now the condition for the `do...while` loop is false, and method `main` ends.

The `try` block and its corresponding `catch` and/or `finally` blocks form a **try statement**. Do not confuse the terms “try block” and “try statement”—the latter includes the `try` block as well as the following `catch` blocks and/or `finally` block.

As with any other block of code, when a `try` block terminates, *local variables* declared in the block *go out of scope* and are no longer accessible; thus, the local variables of a `try` block are not accessible in the corresponding `catch` blocks. When a `catch` block *terminates*, *local variables* declared within the `catch` block (including the exception parameter of that `catch` block) also *go out of scope* and are *destroyed*. Any remaining `catch` blocks in the `try` statement are *ignored*, and execution resumes at the first line of code after the `try...catch` sequence—this will be a `finally` block, if one is present.

### Using the `throws` Clause

In method `quotient` (Fig. 11.3, lines 9–13), line 10 is known as a **throws clause**. It specifies the exceptions the method *might* throw if problems occur. This clause, which must appear after the method’s parameter list and before the body, contains a comma-separated list of the exception types. Such exceptions may be thrown by statements in the method’s body or by methods called from there. We’ve added the `throws` clause to this application to indicate that this method might throw an `ArithmeticException`. Method `quotient`’s callers are thus informed that the method might throw an `ArithmeticException`. Some exception types, such as `ArithmeticException`, are not required to be listed in the `throws` clause. For those that are, the method can throw exceptions that have the *is-a* relationship with the classes listed in the `throws` clause. You’ll learn more about this in Section 11.5.



### Error-Prevention Tip 11.1

*Read the online API documentation for a method before using it in a program. The documentation specifies the exceptions thrown by the method (if any) and indicates reasons why such exceptions may occur. Next, read the online API documentation for the specified exception classes. The documentation for an exception class typically contains potential reasons that such exceptions occur. Finally, provide for handling those exceptions in your program.*

When line 12 executes, if the denominator is zero, the JVM throws an `ArithmeticException` object. This object will be caught by the `catch` block at lines 42–47, which displays basic information about the exception by *implicitly* invoking the exception’s `toString` method, then asks the user to try again.

If the denominator is not zero, method `quotient` performs the division and returns the result to the point of invocation of method `quotient` in the `try` block (line 29). Lines 30–31 display the result of the calculation and line 32 sets `continueLoop` to false. In this case, the `try` block completes successfully, so the program skips the `catch` blocks and fails the condition at line 48, and method `main` completes execution normally.

When `quotient` throws an `ArithmeticException`, `quotient` *terminates* and does *not* return a value, and `quotient`’s *local variables go out of scope* (and are destroyed). If `quotient` contained local variables that were references to objects and there were no other references to those objects, the objects would be marked for *garbage collection*. Also, when an exception occurs, the `try` block from which `quotient` was called *terminates* before lines 30–32 can execute. Here, too, if local variables were created in the `try` block prior to the exception’s being thrown, these variables would go out of scope.

If an `InputMismatchException` is generated by lines 25 or 27, the try block *terminates* and execution *continues* with the catch block at lines 34–41. In this case, method `quotient` is not called. Then method `main` continues after the last catch block (line 48).

## 11.4 When to Use Exception Handling

Exception handling is designed to process **synchronous errors**, which occur when a statement executes. Common examples we'll see throughout the book are *out-of-range array indices*, *arithmetic overflow* (i.e., a value outside the representable range of values), *division by zero*, *invalid method parameters* and *thread interruption* (as we'll see in Chapter 23). Exception handling is not designed to process problems associated with **asynchronous events** (e.g., disk I/O completions, network message arrivals, mouse clicks and keystrokes), which occur in parallel with, and *independent of*, the program's flow of control.



### Software Engineering Observation 11.2

*Incorporate your exception-handling and error-recovery strategy into your system from the inception of the design process—including these after a system has been implemented can be difficult.*



### Software Engineering Observation 11.3

*Exception handling provides a single, uniform technique for documenting, detecting and recovering from errors. This helps programmers working on large projects understand each other's error-processing code.*



### Software Engineering Observation 11.4


*There's a great variety of situations that generate exceptions—some exceptions are easier to recover from than others.*

## 11.5 Java Exception Hierarchy

All Java exception classes inherit directly or indirectly from class **Exception**, forming an *inheritance hierarchy*. You can extend this hierarchy with your own exception classes.

Figure 11.4 shows a small portion of the inheritance hierarchy for class **Throwable** (a subclass of `Object`), which is the superclass of class `Exception`. Only `Throwable` objects can be used with the exception-handling mechanism. Class `Throwable` has two direct subclasses: `Exception` and `Error`. Class `Exception` and its subclasses—for instance, `RuntimeException` (package `java.lang`) and `IOException` (package `java.io`)—represent exceptional situations that can occur in a Java program and that can be caught by the application. Class **Error** and its subclasses represent *abnormal situations* that happen in the JVM. Most *Errors* happen infrequently and should not be caught by applications—it's usually not possible for applications to recover from *Errors*.

The Java exception hierarchy contains hundreds of classes. Information about Java's exception classes can be found throughout the Java API. You can view `Throwable`'s documentation at [docs.oracle.com/javase/7/docs/api/java/lang/Throwable.html](https://docs.oracle.com/javase/7/docs/api/java/lang/Throwable.html). From there, you can look at this class's subclasses to get more information about Java's *Exceptions* and *Errors*.



**Fig. 11.4** | Portion of class `Throwable`'s inheritance hierarchy.

### *Checked vs. Unchecked Exceptions*

Java distinguishes between **checked exceptions** and **unchecked exceptions**. This distinction is important, because the Java compiler enforces special requirements for *checked* exceptions (discussed momentarily). An exception's type determines whether it's checked or unchecked.

### *RuntimeExceptions Are Unchecked Exceptions*

All exception types that are direct or indirect subclasses of **RuntimeException** (package `java.lang`) are *unchecked* exceptions. These are typically caused by defects in your program's code. Examples of unchecked exceptions include:

- `ArrayIndexOutOfBoundsException` (discussed in Chapter 6)—You can avoid these by ensuring that your array indices are always greater than or equal to 0 and less than the array's length.
- `ArithmeticException` (shown in Fig. 11.3)—You can avoid the `ArithmeticException` that occurs when you divide by zero by checking the denominator to determine whether it's 0 *before* performing the calculation.

Classes that inherit directly or indirectly from class `Error` (Fig. 11.4) are *unchecked*, because `Errors` are such serious problems that your program should not even attempt to deal with them.

### *Checked Exceptions*

All classes that inherit from class `Exception` but *not* directly or indirectly from class `RuntimeException` are considered to be *checked* exceptions. Such exceptions are typically caused by conditions that are not under the control of the program—for example, in file processing, the program can't open a file if it does not exist.

### *The Compiler and Checked Exceptions*

The compiler checks each method call and method declaration to determine whether the method throws a checked exception. If so, the compiler verifies that the checked exception is *caught* or is *declared* in a throws clause—this is known as the **catch-or-declare requirement**. We show how to catch or declare checked exceptions in the next several examples. Recall from Section 11.3 that the throws clause specifies the exceptions a method throws. Such exceptions are not caught in the method's body. To satisfy the *catch* part of the *catch-or-declare requirement*, the code that generates the exception must be wrapped in a try block and must provide a catch handler for the checked-exception type (or one of its superclasses). To satisfy the *declare* part of the catch-or-declare requirement, the method containing the code that generates the exception must provide a throws clause containing the checked-exception type after its parameter list and before its method body. If the catch-or-declare requirement is not satisfied, the compiler will issue an error message. This forces you to think about the problems that may occur when a method that throws checked exceptions is called.



#### **Error-Prevention Tip 11.2**

*You must deal with checked exceptions. This results in more robust code than would be created if you were able to simply ignore them.*



#### **Common Programming Error 11.2**

*If a subclass method overrides a superclass method, it's an error for the subclass method to list more exceptions in its throws clause than the superclass method does. However, a subclass's throws clause can contain a subset of a superclass's throws clause.*



#### **Software Engineering Observation 11.5**

*If your method calls other methods that throw checked exceptions, those exceptions must be caught or declared. If an exception can be handled meaningfully in a method, the method should catch the exception rather than declare it.*

### *The Compiler and Unchecked Exceptions*

Unlike checked exceptions, the Java compiler does *not* examine the code to determine whether an unchecked exception is caught or declared. Unchecked exceptions typically can be *prevented* by proper coding. For example, the unchecked `ArithmeticException` thrown by method `quotient` (lines 9–13) in Fig. 11.3 can be avoided if the method ensures that the denominator is not zero *before* performing the division. Unchecked exceptions are *not* required to be listed in a method's throws clause—even if they are, it's *not* required that such exceptions be caught by an application.



#### **Software Engineering Observation 11.6**

*Although the compiler does not enforce the catch-or-declare requirement for unchecked exceptions, provide appropriate exception-handling code when it's known that such exceptions might occur. For example, a program should process the `NumberFormatException` from `Integer` method `parseInt`, even though `NumberFormatException` is an indirect subclass of `RuntimeException` (and thus an unchecked exception). This makes your programs more robust.*

### *Catching Subclass Exceptions*

If a catch handler is written to catch *superclass* exception objects, it can also catch all objects of that class's *subclasses*. This enables catch to handle related exceptions *polymorphically*. You can catch each subclass individually if those exceptions require different processing.

### *Only the First Matching catch Executes*

If *multiple* catch blocks match a particular exception type, only the *first* matching catch block executes when an exception of that type occurs. It's a compilation error to catch the *exact same type* in two different catch blocks associated with a particular try block. However, there can be several catch blocks that match an exception—i.e., several catch blocks whose types are the same as the exception type or a superclass of that type. For instance, we could follow a catch block for type `ArithmeticException` with a catch block for type `Exception`—both would match `ArithmeticExceptions`, but only the first matching catch block would execute.



#### **Common Programming Error 11.3**

*Placing a catch block for a superclass exception type before other catch blocks that catch subclass exception types would prevent those catch blocks from executing, so a compilation error occurs.*



#### **Error-Prevention Tip 11.3**

*Catching subclass types individually is subject to error if you forget to test for one or more of the subclass types explicitly; catching the superclass guarantees that objects of all subclasses will be caught. Positioning a catch block for the superclass type after all other subclass catch blocks ensures that all subclass exceptions are eventually caught.*



#### **Software Engineering Observation 11.7**

*In industry, throwing or catching type `Exception` is discouraged—we use it here simply to demonstrate exception-handling mechanics. In subsequent chapters, we generally throw and catch more specific exception types.*

## **11.6 finally Block**

Programs that obtain certain resources must return them to the system to avoid so-called **resource leaks**. In programming languages such as C and C++, the most common resource leak is a *memory leak*. Java performs automatic *garbage collection* of memory no longer used by programs, thus avoiding most memory leaks. However, other types of resource leaks can occur. For example, files, database connections and network connections that are not closed properly after they're no longer needed might not be available for use in other programs.



#### **Error-Prevention Tip 11.4**

*A subtle issue is that Java does not entirely eliminate memory leaks. Java will not garbage-collect an object until there are no remaining references to it. Thus, if you erroneously keep references to unwanted objects, memory leaks can occur.*

The **finally** block (which consists of the **finally** keyword, followed by code enclosed in curly braces), sometimes referred to as the **finally clause**, is optional. If it's

present, it's placed after the last catch block. If there are no catch blocks, the finally block, if present, immediately follows the try block.

### *When the finally Block Executes*

The finally block will execute *whether or not* an exception is thrown in the corresponding try block. The finally block also will execute if a try block exits by using a return, break or continue statement or simply by reaching its closing right brace. The one case in which the finally block will *not* execute is if the application *exits early* from a try block by calling method **System.exit**. This method, which we demonstrate in Chapter 15, *immediately* terminates an application.

If an exception that occurs in a try block cannot be caught by one of that try block's catch handlers, the program skips the rest of the try block and control proceeds to the finally block. Then the program passes the exception to the next outer try block—normally in the calling method—where an associated catch block might catch it. This process can occur through many levels of try blocks. Also, the exception could go *uncaught* (as we discussed in Section 11.3).

If a catch block throws an exception, the finally block still executes. Then the exception is passed to the next outer try block—again, normally in the calling method.

### *Releasing Resources in a finally Block*

Because a finally block always executes, it typically contains *resource-release code*. Suppose a resource is allocated in a try block. If no exception occurs, the catch blocks are *skipped* and control proceeds to the finally block, which frees the resource. Control then proceeds to the first statement after the finally block. If an exception occurs in the try block, the try block *terminates*. If the program catches the exception in one of the corresponding catch blocks, it processes the exception, then the finally block *releases the resource* and control proceeds to the first statement after the finally block. If the program doesn't catch the exception, the finally block *still* releases the resource and an attempt is made to catch the exception in a calling method.



#### **Error-Prevention Tip 11.5**

*The finally block is an ideal place to release resources acquired in a try block (such as opened files), which helps eliminate resource leaks.*



#### **Performance Tip 11.1**

*Always release a resource explicitly and at the earliest possible moment at which it's no longer needed. This makes resources available for reuse as early as possible, thus improving resource utilization and program performance.*

### *Demonstrating the finally Block*

Figure 11.5 demonstrates that the finally block executes even if an exception is *not* thrown in the corresponding try block. The program contains static methods `main` (lines 6–18), `throwException` (lines 21–44) and `doesNotThrowException` (lines 47–64). Methods `throwException` and `doesNotThrowException` are declared static, so `main` can call them directly without instantiating a `UsingExceptions` object.

---

```

1 // Fig. 11.5: UsingExceptions.java
2 // try...catch...finally exception handling mechanism.
3
4 public class UsingExceptions
5 {
6 public static void main(String[] args)
7 {
8 try
9 {
10 throwException();
11 }
12 catch (Exception exception) // exception thrown by throwException
13 {
14 System.err.println("Exception handled in main");
15 }
16
17 doesNotThrowException();
18 }
19
20 // demonstrate try...catch...finally
21 public static void throwException() throws Exception
22 {
23 try // throw an exception and immediately catch it
24 {
25 System.out.println("Method throwException");
26 throw new Exception(); // generate exception
27 }
28 catch (Exception exception) // catch exception thrown in try
29 {
30 System.err.println(
31 "Exception handled in method throwException");
32 throw exception; // rethrow for further processing
33
34 // code here would not be reached; would cause compilation errors
35 }
36 finally // executes regardless of what occurs in try...catch
37 {
38 System.err.println("Finally executed in throwException");
39 }
40
41 // code here would not be reached; would cause compilation errors
42 }
43
44 }
45
46 // demonstrate finally when no exception occurs
47 public static void doesNotThrowException()
48 {
49 try // try block does not throw an exception
50 {
51 System.out.println("Method doesNotThrowException");
52 }

```

---

**Fig. 11.5** | try...catch...finally exception-handling mechanism. (Part 1 of 2.)



```

53 catch (Exception exception) // does not execute
54 {
55 System.err.println(exception);
56 }
57 finally // executes regardless of what occurs in try...catch
58 {
59 System.err.println(
60 "Finally executed in doesNotThrowException");
61 }
62
63 System.out.println("End of method doesNotThrowException");
64 }
65 } // end class UsingExceptions

```

```

Method throwException
Exception handled in method throwException
Finally executed in throwException
Exception handled in main
Method doesNotThrowException
Finally executed in doesNotThrowException
End of method doesNotThrowException

```

**Fig. 11.5** | try...catch...finally exception-handling mechanism. (Part 2 of 2.)

System.out and System.err are **streams**—sequences of bytes. While System.out (known as the **standard output stream**) displays a program's output, System.err (known as the **standard error stream**) displays a program's errors. Output from these streams can be *redirected* (i.e., sent to somewhere other than the *command prompt*, such as to a *file*). Using two different streams enables you to easily *separate* error messages from other output. For instance, data output from System.err could be sent to a log file, while data output from System.out can be displayed on the screen. For simplicity, this chapter will *not* redirect output from System.err, but will display such messages to the *command prompt*. You'll learn more about streams in Chapter 15.

### Throwing Exceptions Using the **throw** Statement

Method main (Fig. 11.5) begins executing, enters its try block and immediately calls method throwException (line 10). Method throwException throws an Exception. The statement at line 26 is known as a **throw statement**—it's executed to indicate that an exception has occurred. So far, you've caught only exceptions thrown by called methods. You can throw exceptions yourself by using the throw statement. Just as with exceptions thrown by the Java API's methods, this indicates to client applications that an error has occurred. A throw statement specifies an object to be thrown. The operand of a throw can be of any class derived from class Throwable.



### Software Engineering Observation 11.8

When toString is invoked on any Throwable object, its resulting String includes the descriptive string that was supplied to the constructor, or simply the class name if no string was supplied.



### Software Engineering Observation 11.9

*An exception can be thrown without containing information about the problem that occurred. In this case, simply knowing that an exception of a particular type occurred may provide sufficient information for the handler to process the problem correctly.*



### Software Engineering Observation 11.10

*Throw exceptions from constructors to indicate that the constructor parameters are not valid—this prevents an object from being created in an invalid state.*

### Rethrowing Exceptions

Line 32 of Fig. 11.5 **rethrows the exception**. Exceptions are rethrown when a catch block, upon receiving an exception, decides either that it cannot process that exception or that it can only partially process it. Rethrowing an exception defers the exception handling (or perhaps a portion of it) to another catch block associated with an outer try statement. An exception is rethrown by using the **throw** keyword, followed by a reference to the exception object that was just caught. Exceptions cannot be rethrown from a **finally** block, as the exception parameter (a local variable) from the catch block no longer exists.

When a rethrow occurs, the *next enclosing try block* detects the rethrown exception, and that try block's catch blocks attempt to handle it. In this case, the next enclosing try block is found at lines 8–11 in method `main`. Before the rethrown exception is handled, however, the **finally** block (lines 37–40) executes. Then method `main` detects the rethrown exception in the try block and handles it in the catch block (lines 12–15).

Next, `main` calls method `doesNotThrowException` (line 17). No exception is thrown in `doesNotThrowException`'s try block (lines 49–52), so the program skips the catch block (lines 53–56), but the **finally** block (lines 57–61) nevertheless executes. Control proceeds to the statement after the **finally** block (line 63). Then control returns to `main` and the program terminates.



### Common Programming Error 11.4

*If an exception has not been caught when control enters a **finally** block and the **finally** block throws an exception that's not caught in the **finally** block, the first exception will be lost and the exception from the **finally** block will be returned to the calling method.*



### Error-Prevention Tip 11.6

*Avoid placing in a **finally** block code that can throw an exception. If such code is required, enclose the code in a **try...catch** within the **finally** block.*



### Common Programming Error 11.5

*Assuming that an exception thrown from a catch block will be processed by that catch block or any other catch block associated with the same try statement can lead to logic errors.*



### Good Programming Practice 11.1

*Exception handling removes error-processing code from the main line of a program's code to improve program clarity. Do not place **try...catch...finally** around every statement that may throw an exception. This decreases readability. Rather, place one try block around a significant portion of your code, follow the try with catch blocks that handle each possible exception and follow the catch blocks with a single **finally** block (if one is required).*

## 11.7 Stack Unwinding and Obtaining Information from an Exception Object

When an exception is thrown but *not caught* in a particular scope, the method-call stack is “unwound,” and an attempt is made to catch the exception in the next outer try block. This process is called **stack unwinding**. Unwinding the method-call stack means that the method in which the exception was not caught *terminates*, all local variables in that method *go out of scope* and control returns to the statement that originally invoked that method. If a try block encloses that statement, an attempt is made to catch the exception. If a try block does not enclose that statement or if the exception is not caught, stack unwinding occurs again. Figure 11.6 demonstrates stack unwinding, and the exception handler in main shows how to access the data in an exception object.

### Stack Unwinding

In main, the try block (lines 8–11) calls method1 (declared at lines 35–38), which in turn calls method2 (declared at lines 41–44), which in turn calls method3 (declared at lines 47–50). Line 49 of method3 throws an Exception object—this is the *throw point*. Because the throw statement at line 49 is *not* enclosed in a try block, *stack unwinding* occurs—method3 terminates at line 49, then returns control to the statement in method2 that invoked method3 (i.e., line 43). Because *no* try block encloses line 43, *stack unwinding* occurs again—method2 terminates at line 43 and returns control to the statement in method1 that invoked method2 (i.e., line 37). Because *no* try block encloses line 37, *stack unwinding* occurs one more time—method1 terminates at line 37 and returns control to the statement in main that invoked method1 (i.e., line 10). The try block at lines 8–11 encloses this statement. The exception has not been handled, so the try block terminates and the first matching catch block (lines 12–31) catches and processes the exception. If there were no matching catch blocks, and the exception is *not declared* in each method that throws it, a compilation error would occur. Remember that this is not always the case—for *unchecked* exceptions, the application will compile, but it will run with unexpected results.

---

```

1 // Fig. 11.6: UsingExceptions.java
2 // Stack unwinding and obtaining data from an exception object.
3
4 public class UsingExceptions
5 {
6 public static void main(String[] args)
7 {
8 try
9 {
10 method1();
11 }
12 catch (Exception exception) // catch exception thrown in method1
13 {
14 System.err.printf("%s%n%n", exception.getMessage());
15 exception.printStackTrace();
16 }
17 }
18 }

```

---

**Fig. 11.6** | Stack unwinding and obtaining data from an exception object. (Part 1 of 2.)

```

17 // obtain the stack-trace information
18 StackTraceElement[] traceElements = exception.getStackTrace();
19
20 System.out.printf("%nStack trace from getStackTrace:%n");
21 System.out.println("Class\t\tFile\t\tLine\tMethod");
22
23 // loop through traceElements to get exception description
24 for (StackTraceElement element : traceElements)
25 {
26 System.out.printf("%s\t", element.getClassName());
27 System.out.printf("%s\t", element.getFileName());
28 System.out.printf("%s\t", element.getLineNumber());
29 System.out.printf("%s%n", element.getMethodName());
30 }
31 }
32 } // end main
33
34 // call method2; throw exceptions back to main
35 public static void method1() throws Exception
36 {
37 method2();
38 }
39
40 // call method3; throw exceptions back to method1
41 public static void method2() throws Exception
42 {
43 method3();
44 }
45
46 // throw Exception back to method2
47 public static void method3() throws Exception
48 {
49 throw new Exception("Exception thrown in method3");
50 }
51 } // end class UsingExceptions

```

Exception thrown in method3

```

java.lang.Exception: Exception thrown in method3
 at UsingExceptions.method3(UsingExceptions.java:49)
 at UsingExceptions.method2(UsingExceptions.java:43)
 at UsingExceptions.method1(UsingExceptions.java:37)
 at UsingExceptions.main(UsingExceptions.java:10)

```

Stack trace from getStackTrace:

| Class           | File                 | Line | Method  |
|-----------------|----------------------|------|---------|
| UsingExceptions | UsingExceptions.java | 49   | method3 |
| UsingExceptions | UsingExceptions.java | 43   | method2 |
| UsingExceptions | UsingExceptions.java | 37   | method1 |
| UsingExceptions | UsingExceptions.java | 10   | main    |

**Fig. 11.6** | Stack unwinding and obtaining data from an exception object. (Part 2 of 2.)

### Obtaining Data from an Exception Object

All exceptions derive from class `Throwable`, which has a `printStackTrace` method that outputs to the standard error stream the *stack trace* (discussed in Section 11.2). Often this is helpful in testing and debugging. Class `Throwable` also provides a `getStackTrace` method that retrieves the stack-trace information that might be printed by `printStackTrace`. Class `Throwable`'s `getMessage` method returns the descriptive string stored in an exception.



#### Error-Prevention Tip 11.7

*An exception that's not caught in an application causes Java's default exception handler to run. This displays the name of the exception, a descriptive message that indicates the problem that occurred and a complete execution stack trace. In an application with a single thread of execution, the application terminates. In an application with multiple threads, the thread that caused the exception terminates. We discuss multithreading in Chapter 23.*



#### Error-Prevention Tip 11.8

*`Throwable` method `toString` (inherited by all `Throwable` subclasses) returns a `String` containing the name of the exception's class and a descriptive message.*

The catch handler in Fig. 11.6 (lines 12–31) demonstrates `getMessage`, `printStackTrace` and `getStackTrace`. If we wanted to output the stack-trace information to streams other than the standard error stream, we could use the information returned from `getStackTrace` and output it to another stream or use one of the overloaded versions of method `printStackTrace`. Sending data to other streams is discussed in Chapter 15.

Line 14 invokes the exception's `getMessage` method to get the *exception description*. Line 15 invokes the exception's `printStackTrace` method to output the *stack trace* that indicates where the exception occurred. Line 18 invokes the exception's `getStackTrace` method to obtain the stack-trace information as an array of `StackTraceElement` objects. Lines 24–30 get each `StackTraceElement` in the array and invoke its methods `getClassName`, `getFileName`, `getLineNumber` and `getMethodName` to get the class name, filename, line number and method name, respectively, for that `StackTraceElement`. Each `StackTraceElement` represents *one* method call on the *method-call stack*.

The program's output shows that output of `printStackTrace` follows the pattern: *className.methodName(fileName:lineNumber)*, where *className*, *methodName* and *fileName* indicate the names of the class, method and file in which the exception occurred, respectively, and the *lineNumber* indicates where in the file the exception occurred. You saw this in the output for Fig. 11.2. Method `getStackTrace` enables custom processing of the exception information. Compare the output of `printStackTrace` with the output created from the `StackTraceElements` to see that both contain the same stack-trace information.



#### Software Engineering Observation 11.11

*Occasionally, you might want to ignore an exception by writing a catch handler with an empty body. Before doing so, ensure that the exception doesn't indicate a condition that code higher up the stack might want to know about or recover from.*

## 11.8 Chained Exceptions

Sometimes a method responds to an exception by throwing a different exception type that's specific to the current application. If a catch block throws a new exception, the orig-

inal exception's information and stack trace are *lost*. Earlier Java versions provided no mechanism to wrap the original exception information with the new exception's information to provide a complete stack trace showing where the original problem occurred. This made debugging such problems particularly difficult. **Chained exceptions** enable an exception object to maintain the complete stack-trace information from the original exception. Figure 11.7 demonstrates chained exceptions.

---

```

1 // Fig. 11.7: UsingChainedExceptions.java
2 // Chained exceptions.
3
4 public class UsingChainedExceptions
5 {
6 public static void main(String[] args)
7 {
8 try
9 {
10 method1();
11 }
12 catch (Exception exception) // exceptions thrown from method1
13 {
14 exception.printStackTrace();
15 }
16 }
17
18 // call method2; throw exceptions back to main
19 public static void method1() throws Exception
20 {
21 try
22 {
23 method2();
24 } // end try
25 catch (Exception exception) // exception thrown from method2
26 {
27 throw new Exception("Exception thrown in method1", exception);
28 }
29 }
30
31 // call method3; throw exceptions back to method1
32 public static void method2() throws Exception
33 {
34 try
35 {
36 method3();
37 }
38 catch (Exception exception) // exception thrown from method3
39 {
40 throw new Exception("Exception thrown in method2", exception);
41 }
42 }
43

```

---

**Fig. 11.7** | Chained exceptions. (Part I of 2.)

```

44 // throw Exception back to method2
45 public static void method3() throws Exception
46 {
47 throw new Exception("Exception thrown in method3");
48 }
49 } // end class UsingChainedExceptions

```

```

java.lang.Exception: Exception thrown in method1
 at UsingChainedExceptions.method1(UsingChainedExceptions.java:27)
 at UsingChainedExceptions.main(UsingChainedExceptions.java:10)
Caused by: java.lang.Exception: Exception thrown in method2
 at UsingChainedExceptions.method2(UsingChainedExceptions.java:40)
 at UsingChainedExceptions.method1(UsingChainedExceptions.java:23)
 ... 1 more
Caused by: java.lang.Exception: Exception thrown in method3
 at UsingChainedExceptions.method3(UsingChainedExceptions.java:47)
 at UsingChainedExceptions.method2(UsingChainedExceptions.java:36)
 ... 2 more

```

**Fig. 11.7** | Chained exceptions. (Part 2 of 2.)

### *Program Flow of Control*

The program consists of four methods—`main` (lines 6–16), `method1` (lines 19–29), `method2` (lines 32–42) and `method3` (lines 45–48). Line 10 in `main`'s try block calls `method1`. Line 23 in `method1`'s try block calls `method2`. Line 36 in `method2`'s try block calls `method3`. In `method3`, line 47 throws a new `Exception`. Because this statement is not in a try block, `method3` terminates, and the exception is returned to the calling method (`method2`) at line 36. This statement *is* in a try block; therefore, the try block terminates and the exception is caught at lines 38–41. Line 40 in the catch block throws a new exception. In this case, the `Exception` constructor with *two* arguments is called. The second argument represents the exception that was the original cause of the problem. In this program, that exception occurred at line 47. Because an exception is thrown from the catch block, `method2` terminates and returns the new exception to the calling method (`method1`) at line 23. Once again, this statement is in a try block, so the try block terminates and the exception is caught at lines 25–28. Line 27 in the catch block throws a new exception and uses the exception that was caught as the second argument to the `Exception` constructor. Because an exception is thrown from the catch block, `method1` terminates and returns the new exception to the calling method (`main`) at line 10. The try block in `main` terminates, and the exception is caught at lines 12–15. Line 14 prints a stack trace.

### *Program Output*

Notice in the program output that the first three lines show the most recent exception that was thrown (i.e., the one from `method1` at line 27). The next four lines indicate the exception that was thrown from `method2` at line 40. Finally, the last four lines represent the exception that was thrown from `method3` at line 47. Also notice that, as you read the output in reverse, it shows how many more chained exceptions remain.

## 11.9 Declaring New Exception Types

Most Java programmers use *existing* classes from the Java API, third-party vendors and freely available class libraries (usually downloadable from the Internet) to build Java applications. The methods of those classes typically are declared to throw appropriate exceptions when problems occur. You write code that processes these existing exceptions to make your programs more robust.

If you build classes that other programmers will use, it's often appropriate to declare your own exception classes that are specific to the problems that can occur when another programmer uses your reusable classes.

### *A New Exception Type Must Extend an Existing One*

A new exception class must extend an existing exception class to ensure that the class can be used with the exception-handling mechanism. An exception class is like any other class; however, a typical new exception class contains only four constructors:

- one that takes no arguments and passes a default error message `String` to the superclass constructor
- one that receives a customized error message as a `String` and passes it to the superclass constructor
- one that receives a customized error message as a `String` and a `Throwable` (for chaining exceptions) and passes both to the superclass constructor
- one that receives a `Throwable` (for chaining exceptions) and passes it to the superclass constructor.



### **Good Programming Practice 11.2**

*Associating each type of serious execution-time malfunction with an appropriately named Exception class improves program clarity.*



### **Software Engineering Observation 11.12**

*When defining your own exception type, study the existing exception classes in the Java API and try to extend a related exception class. For example, if you're creating a new class to represent when a method attempts a division by zero, you might extend class `ArithmeticException` because division by zero occurs during arithmetic. If the existing classes are not appropriate superclasses for your new exception class, decide whether your new class should be a checked or an unchecked exception class. If clients should be required to handle the exception, the new exception class should be a checked exception (i.e., extend `Exception` but not `RuntimeException`). The client application should be able to reasonably recover from such an exception. If the client code should be able to ignore the exception (i.e., the exception is an unchecked one), the new exception class should extend `RuntimeException`.*

### *Example of a Custom Exception Class*

In Chapter 21, Custom Generic Data Structures, we provide an example of a *custom* exception class. We declare a reusable class called `List` that's capable of storing a list of references to objects. Some operations typically performed on a `List` are not allowed if the `List` is empty, such as removing an item from the front or back of the list. For this reason, some `List` methods throw exceptions of exception class `EmptyListException`.





### Good Programming Practice 11.3

*By convention, all exception-class names should end with the word `Exception`.*

## 11.10 Preconditions and Postconditions

Programmers spend significant amounts of time maintaining and debugging code. To facilitate these tasks and to improve the overall design, you can specify the expected states before and after a method's execution. These states are called preconditions and postconditions, respectively.

### *Preconditions*

A **precondition** must be true when a method is *invoked*. Preconditions describe constraints on method parameters and any other expectations the method has about the current state of a program *just before it begins executing*. If the preconditions are *not* met, then the method's behavior is *undefined*—it may *throw an exception*, *proceed with an illegal value* or *attempt to recover* from the error. You should not expect consistent behavior if the preconditions are not satisfied.

### *Postconditions*

A **postcondition** is true *after the method successfully returns*. Postconditions describe *constraints on the return value* and any other *side effects* the method may have. When defining a method, you should document all postconditions so that others know what to expect when they call your method, and you should make certain that your method honors all its postconditions if its preconditions are indeed met.

### *Throwing Exceptions When Preconditions or Postconditions Are Not Met*

When their preconditions or postconditions are not met, methods typically throw exceptions. As an example, examine `String` method `charAt`, which has one `int` parameter—an index in the `String`. For a precondition, method `charAt` assumes that `index` is greater than or equal to zero and less than the length of the `String`. If the precondition is met, the postcondition states that the method will return the character at the position in the `String` specified by the parameter `index`. Otherwise, the method throws an `IndexOutOfBoundsException`. We trust that method `charAt` satisfies its postcondition, provided that we meet the precondition. We need not be concerned with the details of how the method actually retrieves the character at the index.

Typically, a method's preconditions and postconditions are described as part of its specification. When designing your own methods, you should state the preconditions and postconditions in a comment before the method declaration.

## 11.11 Assertions

When implementing and debugging a class, it's sometimes useful to state conditions that should be true at a particular point in a method. These conditions, called **assertions**, help ensure a program's validity by catching potential bugs and identifying possible logic errors during development. Preconditions and postconditions are two types of assertions. Preconditions are assertions about a program's state when a method is invoked, and postconditions are assertions about its state after a method finishes.

While assertions can be stated as comments to guide you during program development, Java includes two versions of the **assert** statement for validating assertions programmatically. The **assert** statement evaluates a **boolean** expression and, if **false**, throws an **AssertionError** (a subclass of **Error**). The first form of the **assert** statement is

```
assert expression;
```

which throws an **AssertionError** if *expression* is **false**. The second form is

```
assert expression1 : expression2;
```

which evaluates *expression1* and throws an **AssertionError** with *expression2* as the error message if *expression1* is **false**.

You can use assertions to implement *preconditions* and *postconditions* programmatically or to verify any other *intermediate* states that help you ensure that your code is working correctly. Figure 11.8 demonstrates the **assert** statement. Line 11 prompts the user to enter a number between 0 and 10, then line 12 reads the number. Line 15 determines whether the user entered a number within the valid range. If the number is out of range, the **assert** statement reports an error; otherwise, the program proceeds normally.

---

```

1 // Fig. 11.8: AssertTest.java
2 // Checking with assert that a value is within range
3 import java.util.Scanner;
4
5 public class AssertTest
6 {
7 public static void main(String[] args)
8 {
9 Scanner input = new Scanner(System.in);
10
11 System.out.print("Enter a number between 0 and 10: ");
12 int number = input.nextInt();
13
14 // assert that the value is >= 0 and <= 10
15 assert (number >= 0 && number <= 10) : "bad number: " + number;
16
17 System.out.printf("You entered %d\n", number);
18 }
19 } // end class AssertTest

```

```

Enter a number between 0 and 10: 5
You entered 5

```

```

Enter a number between 0 and 10: 50
Exception in thread "main" java.lang.AssertionError: bad number: 50
 at AssertTest.main(AssertTest.java:15)

```

**Fig. 11.8** | Checking with **assert** that a value is within range.

You use assertions primarily for debugging and identifying logic errors in an application. You must explicitly enable assertions when executing a program, because they reduce

performance and are unnecessary for the program's user. To do so, use the `java` command's `-ea` command-line option, as in

```
java -ea AssertTest
```



### Software Engineering Observation 11.13

*Users shouldn't encounter `AssertionErrors`—these should be used only during program development. For this reason, you shouldn't catch `AssertionErrors`. Instead, allow the program to terminate, so you can see the error message, then locate and fix the source of the problem. You should not use `assert` to indicate runtime problems in production code (as we did in Fig. 11.8 for demonstration purposes)—use the exception mechanism for this purpose.*

## 11.12 try-with-Resources: Automatic Resource Deallocation

Typically *resource-release code* should be placed in a `finally` block to ensure that a resource is released, regardless of whether there were exceptions when the resource was used in the corresponding `try` block. An alternative notation—the **try-with-resources** statement (introduced in Java SE 7)—simplifies writing code in which you obtain one or more resources, use them in a `try` block and release them in a corresponding `finally` block. For example, a file-processing application could process a file with a `try-with-resources` statement to ensure that the file is closed properly when it's no longer needed—we demonstrate this in Chapter 15. Each resource must be an object of a class that implements the **AutoCloseable** interface, and thus provides a `close` method. The general form of a `try-with-resources` statement is

```
try (ClassName theObject = new ClassName())
{
 // use theObject here
}
catch (Exception e)
{
 // catch exceptions that occur while using the resource
}
```

where *ClassName* is a class that implements the `AutoCloseable` interface. This code creates an object of type *ClassName* and uses it in the `try` block, then calls its `close` method to release any resources used by the object. The `try-with-resources` statement *implicitly* calls the `theObject`'s `close` method *at the end of the try block*. You can allocate multiple resources in the parentheses following `try` by separating them with a semicolon (;). You'll see examples of the `try-with-resources` statement in Chapters 15 and 24.

## 11.13 Wrap-Up

In this chapter, you learned how to use exception handling to deal with errors. You learned that exception handling enables you to remove error-handling code from the “main line” of the program's execution. We showed how to use `try` blocks to enclose code that may throw an exception, and how to use `catch` blocks to deal with exceptions that may arise.

You learned about the termination model of exception handling, which dictates that after an exception is handled, program control does not return to the throw point. We dis-

cussed checked vs. unchecked exceptions, and how to specify with the `throws` clause the exceptions that a method might throw.

You learned how to use the `finally` block to release resources whether or not an exception occurs. You also learned how to throw and rethrow exceptions. We showed how to obtain information about an exception using methods `printStackTrace`, `getStackTrace` and `getMessage`. Next, we presented chained exceptions, which allow you to wrap original exception information with new exception information. Then, we showed how to create your own exception classes.

We introduced preconditions and postconditions to help programmers using your methods understand conditions that must be true when the method is called and when it returns, respectively. When preconditions and postconditions are not met, methods typically throw exceptions. We discussed the `assert` statement and how it can be used to help you debug your programs. In particular, `assert` can be used to ensure that preconditions and postconditions are met.

We also introduced multi-catch for processing several types of exceptions in the same catch handler and the `try-with-resources` statement for automatically deallocating a resource after it's used in the `try` block. In the next chapter, we take a deeper look at graphical user interfaces (GUIs).

## Summary

### *Section 11.1 Introduction*

- An exception is an indication of a problem that occurs during a program's execution.
- Exception handling enables programmers to create applications that can resolve exceptions.

### *Section 11.2 Example: Divide by Zero without Exception Handling*

- Exceptions are thrown (p. 435) when a method detects a problem and is unable to handle it.
- An exception's stack trace (p. 436) includes the name of the exception in a message that indicates the problem that occurred and the complete method-call stack at the time the exception occurred.
- The point in the program at which an exception occurs is called the throw point (p. 437).

### *Section 11.3 Example: Handling `ArithmeticExceptions` and `InputMismatchExceptions`*

- A `try` block (p. 439) encloses code that might throw an exception and code that should not execute if that exception occurs.
- Exceptions may surface through explicitly mentioned code in a `try` block, through calls to other methods or even through deeply nested method calls initiated by code in the `try` block.
- A `catch` block (p. 440) begins with keyword `catch` and an exception parameter followed by a block of code that handles the exception. This code executes when the `try` block detects the exception.
- At least one `catch` block or a `finally` block (p. 440) must immediately follow the `try` block.
- A `catch` block specifies in parentheses an exception parameter identifying the exception type to handle. The parameter's name enables the `catch` block to interact with a caught exception object.
- An uncaught exception (p. 441) is an exception that occurs for which there are no matching `catch` blocks. An uncaught exception will cause a program to terminate early if that program contains only one thread. Otherwise, only the thread in which the exception occurred will terminate. The rest of the program will run but possibly with adverse results.

- Multi-catch (p. 441) enables you to catch multiple exception types in a single catch handler and perform the same task for each type of exception. The syntax for a multi-catch is:

```
catch (Type1 | Type2 | Type3 e)
```

- Each exception type is separated from the next with a vertical bar (|).
- If an exception occurs in a try block, the try block terminates immediately and program control transfers to the first catch block with a parameter type that matches the thrown exception's type.
- After an exception is handled, program control does not return to the throw point, because the try block has expired. This is known as the termination model of exception handling (p. 441).
- If there are multiple matching catch blocks when an exception occurs, only the first is executed.
- A throws clause (p. 442) specifies a comma-separated list of exceptions that the method might throw, and appears after the method's parameter list and before the method body.

### **Section 11.4 When to Use Exception Handling**

- Exception handling processes synchronous errors (p. 443), which occur when a statement executes.
- Exception handling is not designed to process problems associated with asynchronous events (p. 443), which occur in parallel with, and independent of, the program's flow of control.

### **Section 11.5 Java Exception Hierarchy**

- All Java exception classes inherit directly or indirectly from class `Exception`.
- Programmers can extend the Java exception hierarchy with their own exception classes.
- Class `Throwable` is the superclass of class `Exception` and is therefore also the superclass of all exceptions. Only `Throwable` objects can be used with the exception-handling mechanism.
- Class `Throwable` (p. 443) has two subclasses: `Exception` and `Error`.
- Class `Exception` and its subclasses represent problems that could occur in a Java program and be caught by the application.
- Class `Error` and its subclasses represent problems that could happen in the Java runtime system. Errors happen infrequently and typically should not be caught by an application.
- Java distinguishes between two categories of exceptions (p. 444): checked and unchecked.
- The Java compiler does not check to determine if an unchecked exception is caught or declared. Unchecked exceptions typically can be prevented by proper coding.
- Subclasses of `RuntimeException` represent unchecked exceptions. All exception types that inherit from class `Exception` but not from `RuntimeException` (p. 444) are checked.
- If a catch block is written to catch exception objects of a superclass type, it can also catch all objects of that class's subclasses. This allows for polymorphic processing of related exceptions.

### **Section 11.6 finally Block**

- Programs that obtain certain types of resources must return them to the system to avoid so-called resource leaks (p. 446). Resource-release code typically is placed in a `finally` block (p. 446).
- The `finally` block is optional. If it's present, it's placed after the last catch block.
- The `finally` block will execute whether or not an exception is thrown in the corresponding try block or any of its corresponding catch blocks.
- If an exception cannot be caught by one of that try block's associated catch handlers, control proceeds to the `finally` block. Then the exception is passed to the next outer try block.
- If a catch block throws an exception, the `finally` block still executes. Then the exception is passed to the next outer try block.

- A `throw` statement (p. 449) can throw any `Throwable` object.
- Exceptions are rethrown (p. 450) when a `catch` block, upon receiving an exception, decides either that it cannot process that exception or that it can only partially process it. Rethrowing an exception defers the exception handling (or perhaps a portion of it) to another `catch` block.
- When a rethrow occurs, the next enclosing `try` block detects the rethrown exception, and that `try` block's `catch` blocks attempt to handle it.

### *Section 11.7 Stack Unwinding and Obtaining Information from an Exception Object*

- When an exception is thrown but not caught in a particular scope, the method-call stack is unwound, and an attempt is made to catch the exception in the next outer `try` statement.
- Class `Throwable` offers a `printStackTrace` method that prints the method-call stack. Often, this is helpful in testing and debugging.
- Class `Throwable` also provides a `getStackTrace` method that obtains the same stack-trace information that's printed by `printStackTrace` (p. 453).
- Class `Throwable`'s `getMessage` method (p. 453) returns the descriptive string stored in an exception.
- Method `getStackTrace` (p. 453) obtains the stack-trace information as an array of `StackTraceElement` objects. Each `StackTraceElement` represents one method call on the method-call stack.
- `StackTraceElement` methods (p. 453) `getClassName`, `getFileName`, `getLineNumber` and `getMethodName` get the class name, filename, line number and method name, respectively.

### *Section 11.8 Chained Exceptions*

- Chained exceptions (p. 454) enable an exception object to maintain the complete stack-trace information, including information about previous exceptions that caused the current exception.

### *Section 11.9 Declaring New Exception Types*

- A new exception class must extend an existing exception class to ensure that the class can be used with the exception-handling mechanism.

### *Section 11.10 Preconditions and Postconditions*

- A method's precondition (p. 457) must be true when the method is invoked.
- A method's postcondition (p. 457) is true after the method successfully returns.
- When designing your own methods, you should state the preconditions and postconditions in a comment before the method declaration.

### *Section 11.11 Assertions*

- Assertions (p. 457) help catch potential bugs and identify possible logic errors.
- The `assert` statement (p. 458) allows for validating assertions programmatically.
- To enable assertions at runtime, use the `-ea` switch when running the `java` command.

### *Section 11.12 try-with-Resources: Automatic Resource Deallocation*

- The `try-with-resources` statement (p. 459) simplifies writing code in which you obtain a resource, use it in a `try` block and release the resource in a corresponding `finally` block. Instead, you allocate the resource in the parentheses following the `try` keyword and use the resource in the `try` block; then the statement implicitly calls the resource's `close` method at the end of the `try` block.
- Each resource must be an object of a class that implements the `AutoCloseable` interface (p. 459)—such a class has a `close` method.

- You can allocate multiple resources in the parentheses following `try` by separating them with a semicolon (;).

## Self-Review Exercises

- 11.1 List five common examples of exceptions.
- 11.2 Why are exceptions particularly appropriate for dealing with errors produced by methods of classes in the Java API?
- 11.3 What is a “resource leak”?
- 11.4 If no exceptions are thrown in a `try` block, where does control proceed to when the `try` block completes execution?
- 11.5 Give a key advantage of using `catch(Exception exceptionName)`.
- 11.6 Should a conventional application catch `Error` objects? Explain.
- 11.7 What happens if no catch handler matches the type of a thrown object?
- 11.8 What happens if several catch blocks match the type of the thrown object?
- 11.9 Why would a programmer specify a superclass type as the type in a catch block?
- 11.10 What is the key reason for using `finally` blocks?
- 11.11 What happens when a catch block throws an `Exception`?
- 11.12 What does the statement `throw exceptionReference` do in a catch block?
- 11.13 What happens to a local reference in a `try` block when that block throws an `Exception`?

## Answers to Self-Review Exercises

- 11.1 Memory exhaustion, array index out of bounds, arithmetic overflow, division by zero, invalid method parameters.
- 11.2 It’s unlikely that methods of classes in the Java API could perform error processing that would meet the unique needs of all users.
- 11.3 A “resource leak” occurs when an executing program does not properly release a resource when it’s no longer needed.
- 11.4 The catch blocks for that `try` statement are skipped, and the program resumes execution after the last catch block. If there’s a `finally` block, it’s executed first; then the program resumes execution after the `finally` block.
- 11.5 The form `catch(Exception exceptionName)` catches any type of exception thrown in a `try` block. An advantage is that no thrown `Exception` can slip by without being caught. You can handle the exception or rethrow it.
- 11.6 Errors are usually serious problems with the underlying Java system; most programs will not want to catch `Errors` because they will not be able to recover from them.
- 11.7 This causes the search for a match to continue in the next enclosing `try` statement. If there’s a `finally` block, it will be executed before the exception goes to the next enclosing `try` statement. If there are no enclosing `try` statements for which there are matching catch blocks and the exceptions are declared (or unchecked), a stack trace is printed and the current thread terminates early. If the exceptions are checked, but not caught or declared, compilation errors occur.
- 11.8 The first matching catch block after the `try` block is executed.

**11.9** This enables a program to catch related types of exceptions and process them in a uniform manner. However, it's often useful to process the subclass types individually for more precise exception handling.

**11.10** The `finally` block is the preferred means for releasing resources to prevent resource leaks.

**11.11** First, control passes to the `finally` block if there is one. Then the exception will be processed by a `catch` block (if one exists) associated with an enclosing `try` block (if one exists).

**11.12** It rethrows the exception for processing by an exception handler of an enclosing `try` statement, after the `finally` block of the current `try` statement executes.

**11.13** The reference goes out of scope. If the referenced object becomes unreachable, the object can be garbage collected.

## Exercises

**11.14** (*Exceptional Conditions*) List the various exceptional conditions that have occurred in programs throughout this text so far. List as many additional exceptional conditions as you can. For each of these, describe briefly how a program typically would handle the exception by using the exception-handling techniques discussed in this chapter. Typical exceptions include division by zero and array index out of bounds.

**11.15** (*Exceptions and Constructor Failure*) Until this chapter, we've found dealing with errors detected by constructors to be a bit awkward. Explain why exception handling is an effective means for dealing with constructor failure.

**11.16** (*Catching Exceptions with Superclasses*) Use inheritance to create an exception superclass (called `ExceptionA`) and exception subclasses `ExceptionB` and `ExceptionC`, where `ExceptionB` inherits from `ExceptionA` and `ExceptionC` inherits from `ExceptionB`. Write a program to demonstrate that the `catch` block for type `ExceptionA` catches exceptions of types `ExceptionB` and `ExceptionC`.

**11.17** (*Catching Exceptions Using Class `Exception`*) Write a program that demonstrates how various exceptions are caught with

```
catch (Exception exception)
```

This time, define classes `ExceptionA` (which inherits from class `Exception`) and `ExceptionB` (which inherits from class `ExceptionA`). In your program, create `try` blocks that throw exceptions of types `ExceptionA`, `ExceptionB`, `NullPointerException` and `IOException`. All exceptions should be caught with `catch` blocks specifying type `Exception`.

**11.18** (*Order of `catch` Blocks*) Write a program demonstrating that the order of `catch` blocks is important. If you try to catch a superclass exception type before a subclass type, the compiler should generate errors.

**11.19** (*Constructor Failure*) Write a program that shows a constructor passing information about constructor failure to an exception handler. Define class `SomeClass`, which throws an `Exception` in the constructor. Your program should try to create an object of type `SomeClass` and catch the exception that's thrown from the constructor.

**11.20** (*Rethrowing Exceptions*) Write a program that illustrates rethrowing an exception. Define methods `someMethod` and `someMethod2`. Method `someMethod2` should initially throw an exception. Method `someMethod` should call `someMethod2`, catch the exception and rethrow it. Call `someMethod` from method `main`, and catch the rethrown exception. Print the stack trace of this exception.

**11.21** (*Catching Exceptions Using Outer Scopes*) Write a program showing that a method with its own `try` block does not have to catch every possible error generated within the `try`. Some exceptions can slip through to, and be handled in, other scopes.



# GUI Components: Part I

# 12



*Do you think I can listen all day  
to such stuff?*

—Lewis Carroll

*Even a minor event in the life of  
a child is an event of that child's  
world and thus a world event.*

—Gaston Bachelard

*You pays your money and you  
takes your choice.*

—Punch

## Objectives

In this chapter you'll:

- Learn how to use the Nimbus look-and-feel.
- Build GUIs and handle events generated by user interactions with GUIs.
- Understand the packages containing GUI components, event-handling classes and interfaces.
- Create and manipulate buttons, labels, lists, text fields and panels.
- Handle mouse events and keyboard events.
- Use layout managers to arrange GUI components.

- |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <ul style="list-style-type: none"> <li>12.1 Introduction</li> <li>12.2 Java's Nimbus Look-and-Feel</li> <li>12.3 Simple GUI-Based Input/Output with JOptionPane</li> <li>12.4 Overview of Swing Components</li> <li>12.5 Displaying Text and Images in a Window</li> <li>12.6 Text Fields and an Introduction to Event Handling with Nested Classes</li> <li>12.7 Common GUI Event Types and Listener Interfaces</li> <li>12.8 How Event Handling Works</li> <li>12.9 JButton</li> <li>12.10 Buttons That Maintain State               <ul style="list-style-type: none"> <li>12.10.1 JCheckBox</li> <li>12.10.2 JRadioButton</li> </ul> </li> </ul> | <ul style="list-style-type: none"> <li>12.11 JComboBox; Using an Anonymous Inner Class for Event Handling</li> <li>12.12 JList</li> <li>12.13 Multiple-Selection Lists</li> <li>12.14 Mouse Event Handling</li> <li>12.15 Adapter Classes</li> <li>12.16 JPanel1 Subclass for Drawing with the Mouse</li> <li>12.17 Key Event Handling</li> <li>12.18 Introduction to Layout Managers               <ul style="list-style-type: none"> <li>12.18.1 FlowLayout</li> <li>12.18.2 BorderLayout</li> <li>12.18.3 GridLayout</li> </ul> </li> <li>12.19 Using Panels to Manage More Complex Layouts</li> <li>12.20 JTextArea</li> <li>12.21 Wrap-Up</li> </ul> |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|

Summary | Self-Review Exercises | Answers to Self-Review Exercises | Exercises | Making a Difference

## 12.1 Introduction

A **graphical user interface (GUI)** presents a user-friendly mechanism for interacting with an application. A GUI (pronounced “GOO-ee”) gives an application a distinctive “look-and-feel.” GUIs are built from **GUI components**. These are sometimes called *controls* or *widgets*—short for window gadgets. A GUI component is an object with which the user *interacts* via the mouse, the keyboard or another form of input, such as voice recognition. In this chapter and Chapter 22, GUI Components: Part 2, you'll learn about many of Java's so-called **Swing GUI components** from the **javax.swing** package. We cover other GUI components as they're needed throughout the book. In Chapter 25 and two online chapters, you'll learn about JavaFX—Java's latest APIs for GUI, graphics and multimedia.



### Look-and-Feel Observation 12.1


*Providing different applications with consistent, intuitive user-interface components gives users a sense of familiarity with a new application, so that they can learn it more quickly and use it more productively.*

### IDE Support for GUI Design

Many IDEs provide GUI design tools with which you can specify a component's *size*, *location* and other attributes in a visual manner by using the mouse, the keyboard and drag-and-drop. The IDEs generate the GUI code for you. This greatly simplifies creating GUIs, but each IDE generates this code differently. For this reason, we wrote the GUI code by hand, as you'll see in the source-code files for this chapter's examples. We encourage you to build each GUI visually using your preferred IDE(s).

### Sample GUI: The SwingSet3 Demo Application

As an example of a GUI, consider Fig. 12.1, which shows the **SwingSet3** demo application from the JDK demos and samples download at <http://www.oracle.com/technetwork/java/javase/downloads/index.html>. This application is a nice way for you to browse through the various GUI components provided by Java's Swing GUI APIs. Simply click a component name (e.g., `JFrame`, `JTabbedPane`, etc.) in the **GUI Components** area at the left of the window to see a demonstration of the GUI component in the right side of the window. The source code for each demo is shown in the text area at the bottom of the window. We've labeled a few of the GUI components in the application. At the top of the window is a **title bar** that contains the window's title. Below that is a **menu bar** containing **menus** (**File** and **View**). In the top-right region of the window is a set of **buttons**—typically, users click buttons to perform tasks. In the **GUI Components** area of the window is a **combo box**; the user can click the down arrow at the right side of the box to select from a list of items. The menus, buttons and combo box are part of the application's GUI. They enable you to interact with the application.



**Fig. 12.1** | SwingSet3 application demonstrates many of Java's Swing GUI components.

## 12.2 Java's Nimbus Look-and-Feel

A GUI's look consists of its visual aspects, such as its colors and fonts, and its feel consists of the components you use to interact with the GUI, such as buttons and menus. Together

these are known as the GUI's look-and-feel. Swing has a cross-platform look-and-feel known as **Nimbus**. For GUI screen captures like Fig. 12.1, we've configured our systems to use Nimbus as the default look-and-feel. There are three ways that you can use Nimbus:

1. Set it as the default for all Java applications that run on your computer.
2. Set it as the look-and-feel at the time that you launch an application by passing a command-line argument to the `java` command.
3. Set it as the look-and-feel programatically in your application (see Section 22.6).

To set Nimbus as the default for all Java applications, you must create a text file named `swing.properties` in the `lib` folder of both your JDK installation folder and your JRE installation folder. Place the following line of code in the file:

```
swing.defaultlaf=com.sun.java.swing.plaf.nimbus.NimbusLookAndFeel
```

In addition to the standalone JRE, there is a JRE nested in your JDK's installation folder. If you're using an IDE that depends on the JDK, you may also need to place the `swing.properties` file in the nested `jre` folder's `lib` folder.

If you prefer to select Nimbus on an application-by-application basis, place the following command-line argument after the `java` command and before the application's name when you run the application:

```
-Dswing.defaultlaf=com.sun.java.swing.plaf.nimbus.NimbusLookAndFeel
```

## 12.3 Simple GUI-Based Input/Output with `JOptionPane`

The applications in Chapters 2–10 display text in the command window and obtain input from the command window. Most applications you use on a daily basis use windows or **dialog boxes** (also called **dialogs**) to interact with the user. For example, an e-mail program allows you to type and read messages in a window the program provides. Dialog boxes are windows in which programs display important messages to the user or obtain information from the user. Java's **`JOptionPane`** class (package `javax.swing`) provides prebuilt dialog boxes for both input and output. These are displayed by invoking static `JOptionPane` methods. Figure 12.2 presents a simple addition application that uses two **input dialogs** to obtain integers from the user and a **message dialog** to display the sum of the integers the user enters.

---

```

1 // Fig. 12.2: Addition.java
2 // Addition program that uses JOptionPane for input and output.
3 import javax.swing.JOptionPane;
4
5 public class Addition
6 {
7 public static void main(String[] args)
8 {
9 // obtain user input from JOptionPane input dialogs
10 String firstNumber =
11 JOptionPane.showInputDialog("Enter first integer");

```


---

**Fig. 12.2** | Addition program that uses `JOptionPane` for input and output. (Part I of 2.)

```

12 String secondNumber =
13 JOptionPane.showInputDialog("Enter second integer");
14
15 // convert String inputs to int values for use in a calculation
16 int number1 = Integer.parseInt(firstNumber);
17 int number2 = Integer.parseInt(secondNumber);
18
19 int sum = number1 + number2;
20
21 // display result in a JOptionPane message dialog
22 JOptionPane.showMessageDialog(null, "The sum is " + sum,
23 "Sum of Two Integers", JOptionPane.PLAIN_MESSAGE);
24 }
25 } // end class Addition

```



**Fig. 12.2** | Addition program that uses `JOptionPane` for input and output. (Part 2 of 2.)

### Input Dialogs

Line 3 imports class `JOptionPane`. Lines 10–11 declare the local `String` variable `firstNumber` and assign it the result of the call to `JOptionPane` static method `showInputDialog`. This method displays an input dialog (see the screen capture in Fig. 12.2(a)), using the method's `String` argument ("Enter first integer") as a prompt.



### Look-and-Feel Observation 12.2

*The prompt in an input dialog typically uses **sentence-style capitalization**—a style that capitalizes only the first letter of the first word in the text unless the word is a proper noun (for example, Jones).*

The user types characters in the text field, then clicks **OK** or presses the *Enter* key to submit the `String` to the program. Clicking **OK** also **dismisses** (hides) the dialog. [Note: If you type in the text field and nothing appears, activate the text field by clicking it with the mouse.] Unlike *Scanner*, which can be used to input values of *several* types from the user at the keyboard, *an input dialog can input only Strings*. This is typical of most GUI

components. The user can type *any* characters in the input dialog's text field. Our program assumes that the user enters a *valid* integer. If the user clicks **Cancel**, `showInputDialog` returns `null`. If the user either types a noninteger value or clicks the **Cancel** button in the input dialog, an exception will occur and the program will not operate correctly. Lines 12–13 display another input dialog that prompts the user to enter the second integer. Each `JOptionPane` dialog that you display is a so called **modal dialog**—while the dialog is on the screen, the user *cannot* interact with the rest of the application.



### Look-and-Feel Observation 12.3

*Do not overuse modal dialogs, as they can reduce the usability of your applications. Use a modal dialog only when it's necessary to prevent users from interacting with the rest of an application until they dismiss the dialog.*

### Converting Strings to int Values

To perform the calculation, we convert the `Strings` that the user entered to `int` values. Recall that the `Integer` class's static method `parseInt` converts its `String` argument to an `int` value and might throw a `NumberFormatException`. Lines 16–17 assign the converted values to local variables `number1` and `number2`, and line 19 sums these values.

### Message Dialogs

Lines 22–23 use `JOptionPane` static method `showMessageDialog` to display a message dialog (the last screen of Fig. 12.2) containing the sum. The first argument helps the Java application determine where to *position* the dialog box. A dialog is typically displayed from a GUI application with its own window. The first argument refers to that window (known as the *parent window*) and causes the dialog to appear centered over the parent (as we'll do in Section 12.9). If the first argument is `null`, the dialog box is displayed at the *center* of your screen. The second argument is the *message* to display—in this case, the result of concatenating the `String` "The sum is " and the value of `sum`. The third argument—"Sum of Two Integers"—is the `String` that should appear in the *title bar* at the top of the dialog. The fourth argument—`JOptionPane.PLAIN_MESSAGE`—is the *type of message dialog to display*. A `PLAIN_MESSAGE` dialog does *not* display an *icon* to the left of the message. Class `JOptionPane` provides several overloaded versions of methods `showInputDialog` and `showMessageDialog`, as well as methods that display other dialog types. For complete information, visit <http://docs.oracle.com/javase/7/docs/api/javax/swing/JOptionPane.html>.







### Look-and-Feel Observation 12.4

*The title bar of a window typically uses **book-title capitalization**—a style that capitalizes the first letter of each significant word in the text and does not end with any punctuation (for example, *Capitalization in a Book Title*).*

### JOptionPane Message Dialog Constants

The constants that represent the message dialog types are shown in Fig. 12.3. All message dialog types except `PLAIN_MESSAGE` display an icon to the *left* of the message. These icons provide a visual indication of the message's importance to the user. A `QUESTION_MESSAGE` icon is the *default icon* for an input dialog box (see Fig. 12.2).

| Message dialog type | Icon                                                                              | Description                                                                                                      |
|---------------------|-----------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------|
| ERROR_MESSAGE       |  | Indicates an error.                                                                                              |
| INFORMATION_MESSAGE |  | Indicates an informational message.                                                                              |
| WARNING_MESSAGE     |  | Warns of a potential problem.                                                                                    |
| QUESTION_MESSAGE    |  | Poses a question. This dialog normally requires a response, such as clicking a <b>Yes</b> or a <b>No</b> button. |
| PLAIN_MESSAGE       | no icon                                                                           | A dialog that contains a message, but no icon.                                                                   |

**Fig. 12.3** | JOptionPane static constants for message dialogs.

## 12.4 Overview of Swing Components

Though it's possible to perform input and output using the JOptionPane dialogs, most GUI applications require more elaborate user interfaces. The remainder of this chapter discusses many GUI components that enable application developers to create robust GUIs. Figure 12.4 lists several basic Swing GUI components that we discuss.

| Component | Description                                                                                                                                                    |
|-----------|----------------------------------------------------------------------------------------------------------------------------------------------------------------|
| JLabel    | Displays <i>uneditable text</i> and/or icons.                                                                                                                  |
| TextField | Typically <i>receives input</i> from the user.                                                                                                                 |
| Button    | Triggers an event when clicked with the mouse.                                                                                                                 |
| CheckBox  | Specifies an option that can be <i>selected</i> or <i>not selected</i> .                                                                                       |
| ComboBox  | A <i>drop-down list of items</i> from which the user can make a <i>selection</i> .                                                                             |
| List      | A <i>list of items</i> from which the user can make a <i>selection</i> by <i>clicking on any one</i> of them. <i>Multiple</i> elements <i>can</i> be selected. |
| Panel     | An area in which <i>components</i> can be <i>placed</i> and <i>organized</i> .                                                                                 |

**Fig. 12.4** | Some basic Swing GUI components.

### *Swing vs. AWT*

There are actually *two* sets of Java GUI components. In Java's early days, GUIs were built with components from the **Abstract Window Toolkit (AWT)** in package `java.awt`. These look like the native GUI components of the platform on which a Java program executes. For example, a Button object displayed in a Java program running on Microsoft Windows looks like those in other *Windows* applications. On Apple Mac OS X, the Button looks like those in other *Mac* applications. Sometimes, even the manner in which a user can interact with an AWT component *differs between platforms*. The component's appearance and the way in which the user interacts with it are known as its **look-and-feel**.



### Look-and-Feel Observation 12.5


Swing GUI components allow you to specify a uniform look-and-feel for your application across all platforms or to use each platform's custom look-and-feel. An application can even change the look-and-feel during execution to enable users to choose their own preferred look-and-feel.

#### Lightweight vs. Heavyweight GUI Components

Most Swing components are **lightweight components**—they're written, manipulated and displayed completely in Java. AWT components are **heavyweight components**, because they rely on the local platform's **windowing system** to determine their functionality and their look-and-feel. Several Swing components are *heavyweight* components.

#### Superclasses of Swing's Lightweight GUI Components

The UML class diagram of Fig. 12.5 shows an *inheritance hierarchy* of classes from which lightweight Swing components inherit their common attributes and behaviors.



**Fig. 12.5** | Common superclasses of the lightweight Swing components.

Class **Component** (package `java.awt`) is a superclass that declares the common features of GUI components in packages `java.awt` and `javax.swing`. Any object that is a **Container** (package `java.awt`) can be used to organize Components by *attaching* the Components to the Container. Containers can be placed in other Containers to organize a GUI.

Class **JComponent** (package `javax.swing`) is a subclass of **Container**. **JComponent** is the superclass of all *lightweight* Swing components and declares their common attributes and behaviors. Because **JComponent** is a subclass of **Container**, all lightweight Swing components are also Containers. Some common features supported by **JComponent** include:

1. A **pluggable look-and-feel** for *customizing* the appearance of components (e.g., for use on particular platforms). You'll see an example of this in Section 22.6.
2. Shortcut keys (called **mnemonics**) for direct access to GUI components through the keyboard. You'll see an example of this in Section 22.4.
3. Brief descriptions of a GUI component's purpose (called **tool tips**) that are displayed when the *mouse cursor is positioned over the component* for a short time. You'll see an example of this in the next section.
4. Support for *accessibility*, such as braille screen readers for the visually impaired.
5. Support for user-interface **localization**—that is, customizing the user interface to display in different languages and use local cultural conventions.



## 12.5 Displaying Text and Images in a Window

Our next example introduces a framework for building GUI applications. Several concepts in this framework will appear in many of our GUI applications. This is our first example in which the application appears in its own window. Most windows you'll create that can contain Swing GUI components are instances of class `JFrame` or a subclass of `JFrame`. `JFrame` is an *indirect* subclass of class `java.awt.Window` that provides the basic attributes and behaviors of a window—a *title bar* at the top, and *buttons* to *minimize*, *maximize* and *close* the window. Since an application's GUI is typically specific to the application, most of our examples will consist of *two* classes—a subclass of `JFrame` that helps us demonstrate new GUI concepts and an application class in which `main` creates and displays the application's primary window.

### Labeling GUI Components

A typical GUI consists of many components. GUI designers often provide text stating the purpose of each. Such text is known as a **label** and is created with a **JLabel**—a subclass of `JComponent`. A `JLabel` displays read-only text, an image, or both text and an image. Applications rarely change a label's contents after creating it.



#### Look-and-Feel Observation 12.6

*Text in a `JLabel` normally uses sentence-style capitalization.*

The application of Figs. 12.6–12.7 demonstrates several `JLabel` features and presents the framework we use in most of our GUI examples. We did *not* highlight the code in this example, since most of it is new. [Note: There are many more features for each GUI component than we can cover in our examples. To learn the complete details of each GUI component, visit its page in the online documentation. For class `JLabel`, visit [docs.oracle.com/javase/7/docs/api/javax/swing/JLabel.html](https://docs.oracle.com/javase/7/docs/api/javax/swing/JLabel.html).]

---

```

1 // Fig. 12.6: LabelFrame.java
2 // JLabels with text and icons.
3 import java.awt.FlowLayout; // specifies how components are arranged
4 import javax.swing.JFrame; // provides basic window features
5 import javax.swing.JLabel; // displays text and images
6 import javax.swing.SwingConstants; // common constants used with Swing
7 import javax.swing.Icon; // interface used to manipulate images
8 import javax.swing.ImageIcon; // loads images
9
10 public class LabelFrame extends JFrame
11 {
12 private final JLabel label1; // JLabel with just text
13 private final JLabel label2; // JLabel constructed with text and icon
14 private final JLabel label3; // JLabel with added text and icon
15
16 // LabelFrame constructor adds JLabels to JFrame
17 public LabelFrame()
18 {

```

---

**Fig. 12.6** | JLabels with text and icons. (Part I of 2.)

```

19 super("Testing JLabel");
20 setLayout(new FlowLayout()); // set frame layout
21
22 // JLabel constructor with a string argument
23 label1 = new JLabel("Label with text");
24 label1.setToolTipText("This is label1");
25 add(label1); // add label1 to JFrame
26
27 // JLabel constructor with string, Icon and alignment arguments
28 Icon bug = new ImageIcon(getClass().getResource("bug1.png"));
29 label2 = new JLabel("Label with text and icon", bug,
30 SwingConstants.LEFT);
31 label2.setToolTipText("This is label2");
32 add(label2); // add label2 to JFrame
33
34 label3 = new JLabel(); // JLabel constructor no arguments
35 label3.setText("Label with icon and text at bottom");
36 label3.setIcon(bug); // add icon to JLabel
37 label3.setHorizontalTextPosition(SwingConstants.CENTER);
38 label3.setVerticalTextPosition(SwingConstants.BOTTOM);
39 label3.setToolTipText("This is label3");
40 add(label3); // add label3 to JFrame
41 }
42 } // end class LabelFrame

```

**Fig. 12.6** | JLabels with text and icons. (Part 2 of 2.)

```

1 // Fig. 12.7: LabelTest.java
2 // Testing LabelFrame.
3 import javax.swing.JFrame;
4
5 public class LabelTest
6 {
7 public static void main(String[] args)
8 {
9 LabelFrame labelFrame = new LabelFrame();
10 labelFrame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
11 labelFrame.setSize(260, 180);
12 labelFrame.setVisible(true);
13 }
14 } // end class LabelTest

```



**Fig. 12.7** | Testing LabelFrame.

Class `LabelFrame` (Fig. 12.6) extends `JFrame` to inherit the features of a window. We'll use an instance of class `LabelFrame` to display a window containing three `JLabel`s. Lines 12–14 declare the three `JLabel` instance variables that are instantiated in the `LabelFrame` constructor (lines 17–41). Typically, the `JFrame` subclass's constructor builds the GUI that's displayed in the window when the application executes. Line 19 invokes super-class `JFrame`'s constructor with the argument "Testing `JLabel`". `JFrame`'s constructor uses this `String` as the text in the window's title bar.

### *Specifying the Layout*

When building a GUI, you must attach each GUI component to a container, such as a window created with a `JFrame`. Also, you typically must decide where to *position* each GUI component—known as *specifying the layout*. Java provides several **layout managers** that can help you position components, as you'll learn later in this chapter and in Chapter 22.

Many IDEs provide GUI design tools in which you can specify components' exact *sizes* and *locations* in a visual manner by using the mouse; then the IDE will generate the GUI code for you. Such IDEs can greatly simplify GUI creation.

To ensure that our GUIs can be used with *any* IDE, we did *not* use an IDE to create the GUI code. We use Java's layout managers to *size* and *position* components. With the **FlowLayout** layout manager, components are placed in a *container* from left to right in the order in which they're added. When no more components can fit on the current line, they continue to display left to right on the next line. If the container is *resized*, a `FlowLayout` *reflows* the components, possibly with fewer or more rows based on the new container width. Every container has a *default layout*, which we're changing for `LabelFrame` to a `FlowLayout` (line 20). Method **setLayout** is inherited into class `LabelFrame` indirectly from class `Container`. The argument to the method must be an object of a class that implements the `LayoutManager` interface (e.g., `FlowLayout`). Line 20 creates a new `FlowLayout` object and passes its reference as the argument to `setLayout`.

### *Creating and Attaching `label1`*

Now that we've specified the window's layout, we can begin creating and attaching GUI components to the window. Line 23 creates a `JLabel` object and passes "Label with text" to the constructor. The `JLabel` displays this text on the screen. Line 24 uses method **setToolTipText** (inherited by `JLabel` from `JComponent`) to specify the tool tip that's displayed when the user positions the mouse cursor over the `JLabel` in the GUI. You can see a sample tool tip in the second screen capture of Fig. 12.7. When you execute this application, hover the mouse pointer over each `JLabel` to see its tool tip. Line 25 (Fig. 12.6) attaches `label1` to the `LabelFrame` by passing `label1` to the **add** method, which is inherited indirectly from class `Container`.



#### **Common Programming Error 12.1**

*If you do not explicitly add a GUI component to a container, the GUI component will not be displayed when the container appears on the screen.*



#### **Look-and-Feel Observation 12.7**

*Use tool tips to add descriptive text to your GUI components. This text helps the user determine the GUI component's purpose in the user interface.*

### *The Icon Interface and Class ImageIcon*

Icons are a popular way to enhance the look-and-feel of an application and are also commonly used to indicate functionality. For example, the same icon is used to play most of today's media on devices like DVD players and MP3 players. Several Swing components can display images. An icon is normally specified with an **Icon** (package `javax.swing`) argument to a constructor or to the component's **setIcon** method. Class **ImageIcon** supports several image formats, including Graphics Interchange Format (GIF), Portable Network Graphics (PNG) and Joint Photographic Experts Group (JPEG).

Line 28 declares an **ImageIcon**. The file `bug1.png` contains the image to load and store in the **ImageIcon** object. This image is included in the directory for this example. The **ImageIcon** object is assigned to **Icon** reference `bug`.

### *Loading an Image Resource*

In line 28, the expression `getClass().getResource("bug1.png")` invokes method **getResource** (inherited indirectly from class **Object**) to retrieve a reference to the **Class** object that represents the **LabelFrame** class declaration. That reference is then used to invoke **Class** method **getResource**, which returns the location of the image as a URL. The **ImageIcon** constructor uses the URL to locate the image, then loads it into memory. As we discussed in Chapter 1, the JVM loads class declarations into memory, using a class loader. The class loader knows where each class it loads is located on disk. Method **getResource** uses the **Class** object's class loader to determine the *location* of a resource, such as an image file. In this example, the image file is stored in the same location as the `LabelFrame.class` file. The techniques described here enable an application to load image files from locations that are relative to the class file's location.

### *Creating and Attaching label2*

Lines 29–30 use another **JLabel** constructor to create a **JLabel** that displays the text "Label with text and icon" and the **Icon** `bug` created in line 28. The last constructor argument indicates that the label's contents are left justified, or left aligned (i.e., the icon and text are at the left side of the label's area on the screen). Interface **SwingConstants** (package `javax.swing`) declares a set of common integer constants (such as **SwingConstants.LEFT**, **SwingConstants.CENTER** and **SwingConstants.RIGHT**) that are used with many Swing components. By default, the text appears to the right of the image when a label contains both text and an image. The horizontal and vertical alignments of a **JLabel** can be set with methods **setHorizontalAlignment** and **setVerticalAlignment**, respectively. Line 31 specifies the tool-tip text for `label2`, and line 32 adds `label2` to the **JFrame**.

### *Creating and Attaching label3*

Class **JLabel** provides methods to change a **JLabel**'s appearance after it's been instantiated. Line 34 creates an empty **JLabel** with the no-argument constructor. Line 35 uses **JLabel** method **setText** to set the text displayed on the label. Method **getText** can be used to retrieve the **JLabel**'s current text. Line 36 uses **JLabel** method **setIcon** to specify the **Icon** to display. Method **getIcon** can be used to retrieve the current **Icon** displayed on a label. Lines 37–38 use **JLabel** methods **setHorizontalTextPosition** and **setVerticalTextPosition** to specify the text position in the label. In this case, the text will be centered *horizontally* and will appear at the *bottom* of the label. Thus, the **Icon** will appear *above* the text. The horizontal-position constants in **SwingConstants** are **LEFT**, **CENTER** and **RIGHT** (Fig. 12.8).

The vertical-position constants in `SwingConstants` are `TOP`, `CENTER` and `BOTTOM` (Fig. 12.8). Line 39 (Fig. 12.6) sets the tool-tip text for `labe13`. Line 40 adds `labe13` to the `JFrame`.

| Constant                             | Description              | Constant                           | Description              |
|--------------------------------------|--------------------------|------------------------------------|--------------------------|
| <i>Horizontal-position constants</i> |                          | <i>Vertical-position constants</i> |                          |
| <code>LEFT</code>                    | Place text on the left   | <code>TOP</code>                   | Place text at the top    |
| <code>CENTER</code>                  | Place text in the center | <code>CENTER</code>                | Place text in the center |
| <code>RIGHT</code>                   | Place text on the right  | <code>BOTTOM</code>                | Place text at the bottom |

**Fig. 12.8** | Positioning constants (static members of interface `SwingConstants`).

### *Creating and Displaying a `LabelFrame` Window*

Class `LabelTest` (Fig. 12.7) creates an object of class `LabelFrame` (line 9), then specifies the default close operation for the window. By default, closing a window simply *hides* the window. However, when the user closes the `LabelFrame` window, we would like the application to *terminate*. Line 10 invokes `LabelFrame`'s `setDefaultCloseOperation` method (inherited from class `JFrame`) with constant `JFrame.EXIT_ON_CLOSE` as the argument to indicate that the program should *terminate* when the window is closed by the user. This line is important. Without it the application will *not* terminate when the user closes the window. Next, line 11 invokes `LabelFrame`'s `setSize` method to specify the *width* and *height* of the window in *pixels*. Finally, line 12 invokes `LabelFrame`'s `setVisible` method with the argument `true` to display the window on the screen. Try resizing the window to see how the `FlowLayout` changes the `JLabel` positions as the window width changes.

## 12.6 Text Fields and an Introduction to Event Handling with Nested Classes

Normally, a user interacts with an application's GUI to indicate the tasks that the application should perform. For example, when you write an e-mail in an e-mail application, clicking the **Send** button tells the application to send the e-mail to the specified e-mail addresses. GUIs are **event driven**. When the user interacts with a GUI component, the interaction—known as an **event**—drives the program to perform a task. Some common user interactions that cause an application to perform a task include *clicking* a button, *typing* in a text field, *selecting* an item from a menu, *closing* a window and *moving* the mouse. The code that performs a task in response to an event is called an **event handler**, and the process of responding to events is known as **event handling**.

Let's consider two other GUI components that can generate events—**`JTextField`**s and **`JPasswordField`**s (package `javax.swing`). Class `JTextField` extends class **`JTextComponent`** (package `javax.swing.text`), which provides many features common to Swing's text-based components. Class `JPasswordField` extends `JTextField` and adds methods that are specific to processing passwords. Each of these components is a single-line area in which the user can enter text via the keyboard. Applications can also display text in a `JTextField` (see the output of Fig. 12.10). A `JPasswordField` shows that characters are being typed as the user enters them, but hides the actual characters with an **echo character**, assuming that they represent a password that should remain known only to the user.

When the user types in a `TextField` or a `PasswordField`, then presses *Enter*, an *event* occurs. Our next example demonstrates how a program can perform a task *in response* to that event. The techniques shown here are applicable to all GUI components that generate events.

The application of Figs. 12.9–12.10 uses classes `TextField` and `PasswordField` to create and manipulate four text fields. When the user types in one of the text fields, then presses *Enter*, the application displays a message dialog box containing the text the user typed. You can type only in the text field that's "in focus." When you *click* a component, it *receives the focus*. This is important, because the text field with the focus is the one that generates an event when you press *Enter*. In this example, when you press *Enter* in the `PasswordField`, the password is revealed. We begin by discussing the setup of the GUI, then discuss the event-handling code.

---

```

1 // Fig. 12.9: TextFieldFrame.java
2 // JTextFields and PasswordFields.
3 import java.awt.FlowLayout;
4 import java.awt.event.ActionListener;
5 import java.awt.event.ActionEvent;
6 import javax.swing.JFrame;
7 import javax.swing.JTextField;
8 import javax.swing.PasswordField;
9 import javax.swing.JOptionPane;
10
11 public class TextFieldFrame extends JFrame
12 {
13 private final JTextField textField1; // text field with set size
14 private final JTextField textField2; // text field with text
15 private final JTextField textField3; // text field with text and size
16 private final PasswordField passwordField; // password field with text
17
18 // TextFieldFrame constructor adds JTextFields to JFrame
19 public TextFieldFrame()
20 {
21 super("Testing JTextField and PasswordField");
22 setLayout(new FlowLayout());
23
24 // construct text field with 10 columns
25 textField1 = new JTextField(10);
26 add(textField1); // add textField1 to JFrame
27
28 // construct text field with default text
29 textField2 = new JTextField("Enter text here");
30 add(textField2); // add textField2 to JFrame
31
32 // construct text field with default text and 21 columns
33 textField3 = new JTextField("Uneditable text field", 21);
34 textField3.setEditable(false); // disable editing
35 add(textField3); // add textField3 to JFrame

```

---

**Fig. 12.9** | `JTextFields` and `PasswordFields`. (Part I of 2.)

---

```

36
37 // construct password field with default text
38 passwordField = new JPasswordField("Hidden text");
39 add(passwordField); // add passwordField to JFrame
40
41 // register event handlers
42 TextFieldHandler handler = new TextFieldHandler();
43 textField1.addActionListener(handler);
44 textField2.addActionListener(handler);
45 textField3.addActionListener(handler);
46 passwordField.addActionListener(handler);
47 }
48
49 // private inner class for event handling
50 private class TextFieldHandler implements ActionListener
51 {
52 // process text field events
53 @Override
54 public void actionPerformed(ActionEvent event)
55 {
56 String string = "";
57
58 // user pressed Enter in JTextField textField1
59 if (event.getSource() == textField1)
60 string = String.format("textField1: %s",
61 event.getActionCommand());
62
63 // user pressed Enter in JTextField textField2
64 else if (event.getSource() == textField2)
65 string = String.format("textField2: %s",
66 event.getActionCommand());
67
68 // user pressed Enter in JTextField textField3
69 else if (event.getSource() == textField3)
70 string = String.format("textField3: %s",
71 event.getActionCommand());
72
73 // user pressed Enter in JTextField passwordField
74 else if (event.getSource() == passwordField)
75 string = String.format("passwordField: %s",
76 event.getActionCommand());
77
78 // display JTextField content
79 JOptionPane.showMessageDialog(null, string);
80 }
81 } // end private inner class TextFieldHandler
82 } // end class TextFieldFrame

```

---

**Fig. 12.9** | JTextFields and JPasswordField. (Part 2 of 2.)

Class `TextFieldFrame` extends `JFrame` and declares three `JTextField` variables and a `JPasswordField` variable (lines 13–16). Each of the corresponding text fields is instantiated and attached to the `TextFieldFrame` in the constructor (lines 19–47).

### *Creating the GUI*

Line 22 sets the `TextFieldFrame`'s layout to `FlowLayout`. Line 25 creates `textField1` with 10 columns of text. A text column's width in *pixels* is determined by the average width of a character in the text field's current font. When text is displayed in a text field and the text is wider than the field itself, a portion of the text at the right side is not visible. If you're typing in a text field and the cursor reaches the right edge, the text at the left edge is pushed off the left side of the field and is no longer visible. Users can use the left and right arrow keys to move through the complete text. Line 26 adds `textField1` to the `JFrame`.

Line 29 creates `textField2` with the initial text "Enter text here" to display in the text field. The width of the field is determined by the width of the default text specified in the constructor. Line 30 adds `textField2` to the `JFrame`.

Line 33 creates `textField3` and calls the `JTextField` constructor with two arguments—the default text "Uneditable text field" to display and the text field's width in columns (21). Line 34 uses method `setEditable` (inherited by `JTextField` from class `JTextComponent`) to make the text field *uneditable*—i.e., the user cannot modify the text in the field. Line 35 adds `textField3` to the `JFrame`.

Line 38 creates `passwordField` with the text "Hidden text" to display in the text field. The width of the field is determined by the width of the default text. When you execute the application, notice that the text is displayed as a string of asterisks. Line 39 adds `passwordField` to the `JFrame`.

### *Steps Required to Set Up Event Handling for a GUI Component*

This example should display a message dialog containing the text from a text field when the user presses *Enter* in that text field. Before an application can respond to an event for a particular GUI component, you must:

1. Create a class that represents the event handler and implements an appropriate interface—known as an **event-listener interface**.
2. Indicate that an object of the class from *Step 1* should be notified when the event occurs—known as **registering the event handler**.

### *Using a Nested Class to Implement an Event Handler*

All the classes discussed so far were so-called **top-level classes**—that is, they *were* not declared *inside* another class. Java allows you to declare classes *inside* other classes—these are called **nested classes**. Nested classes can be **static** or **non-static**. Non-static nested classes are called **inner classes** and are frequently used to implement *event handlers*.

An inner-class object must be created by an object of the top-level class that contains the inner class. Each inner-class object *implicitly* has a reference to an object of its top-level class. The inner-class object is allowed to use this implicit reference to directly access all the variables and methods of the top-level class. A nested class that's **static** does not require an object of its top-level class and does not implicitly have a reference to an object of the top-level class. As you'll see in Chapter 13, *Graphics and Java 2D*, the Java 2D graphics API uses **static** nested classes extensively.

### *Inner Class TextFieldHandler*

The event handling in this example is performed by an object of the private *inner class* `TextFieldHandler` (lines 50–81). This class is **private** because it will be used only to create event handlers for the text fields in top-level class `TextFieldFrame`. As with other class



members, *inner classes* can be declared `public`, `protected` or `private`. Since event handlers tend to be specific to the application in which they're defined, they're often implemented as `private` inner classes or as *anonymous inner classes* (Section 12.11).

GUI components can generate many events in response to user interactions. Each event is represented by a class and can be processed only by the appropriate type of event handler. Normally, a component's supported events are described in the Java API documentation for that component's class and its superclasses. When the user presses *Enter* in a `TextField` or `PasswordField`, an **ActionEvent** (package `java.awt.event`) occurs. Such an event is processed by an object that implements the interface **ActionListener** (package `java.awt.event`). The information discussed here is available in the Java API documentation for classes `TextField` and `ActionEvent`. Since `PasswordField` is a subclass of `TextField`, `PasswordField` supports the same events.

To prepare to handle the events in this example, inner class `TextFieldHandler` implements interface `ActionListener` and declares the only method in that interface—`actionPerformed` (lines 53–80). This method specifies the tasks to perform when an `ActionEvent` occurs. So, inner class `TextFieldHandler` satisfies *Step 1* listed earlier in this section. We'll discuss the details of method `actionPerformed` shortly.

### *Registering the Event Handler for Each Text Field*

In the `TextFieldFrame` constructor, line 42 creates a `TextFieldHandler` object and assigns it to variable `handler`. This object's `actionPerformed` method will be called automatically when the user presses *Enter* in any of the GUI's text fields. However, before this can occur, the program must register this object as the event handler for each text field. Lines 43–46 are the *event-registration* statements that specify `handler` as the event handler for the three `TextFields` and the `PasswordField`. The application calls `TextField` method **`addActionListener`** to register the event handler for each component. This method receives as its argument an `ActionListener` object, which can be an object of any class that implements `ActionListener`. The object handler *is an* `ActionListener`, because class `TextFieldHandler` implements `ActionListener`. After lines 43–46 execute, the object handler **listens for events**. Now, when the user presses *Enter* in any of these four text fields, method `actionPerformed` (line 53–80) in class `TextFieldHandler` is called to handle the event. If an event handler is *not* registered for a particular text field, the event that occurs when the user presses *Enter* in that text field is **consumed**—i.e., it's simply *ignored* by the application.



#### **Software Engineering Observation 12.1**

*The event listener for an event must implement the appropriate event-listener interface.*



#### **Common Programming Error 12.2**

*If you forget to register an event-handler object for a particular GUI component's event type, events of that type will be ignored.*

### *Details of Class `TextFieldHandler`'s `actionPerformed` Method*

In this example, we use one event-handling object's `actionPerformed` method (lines 53–80) to handle the events generated by four text fields. Since we'd like to output the name of each text field's instance variable for demonstration purposes, we must determine *which* text field

generated the event each time `actionPerformed` is called. The **event source** is the component with which the user interacted. When the user presses *Enter* while a text field or the password field *has the focus*, the system creates a unique `ActionEvent` object that contains information about the event that just occurred, such as the event source and the text in the text field. The system passes this `ActionEvent` object to the event listener's `actionPerformed` method. Line 56 declares the `String` that will be displayed. The variable is initialized with the **empty string**—a `String` containing no characters. The compiler requires the variable to be initialized in case none of the branches of the nested `if` in lines 59–76 executes.

`ActionEvent` method `getSource` (called in lines 59, 64, 69 and 74) returns a reference to the event source. The condition in line 59 asks, “Is the event source `textField1`?” This condition compares references with the `==` operator to determine if they refer to the same object. If they *both* refer to `textField1`, the user pressed *Enter* in `textField1`. Then, lines 60–61 create a `String` containing the message that line 79 displays in a message dialog. Line 61 uses `ActionEvent` method **`getActionCommand`** to obtain the text the user typed in the text field that generated the event.

In this example, we display the text of the password in the `JPasswordField` when the user presses *Enter* in that field. Sometimes it's necessary to programatically process the characters in a password. Class `JPasswordField` method **`getPassword`** returns the password's characters as an array of type `char`.

### Class `TextFieldTest`

Class `TextFieldTest` (Fig. 12.10) contains the main method that executes this application and displays an object of class `TextFieldFrame`. When you execute the application, even the uneditable `JTextField` (`textField3`) can generate an `ActionEvent`. To test this, click the text field to give it the focus, then press *Enter*. Also, the actual text of the password is displayed when you press *Enter* in the `JPasswordField`. Of course, you would normally not display the password!


---

```


1 // Fig. 12.10: TextFieldTest.java
2 // Testing TextFieldFrame.
3 import javax.swing.JFrame;
4
5 public class TextFieldTest
6 {
7 public static void main(String[] args)
8 {
9 TextFieldFrame textFieldFrame = new TextFieldFrame();
10 textFieldFrame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
11 textFieldFrame.setSize(350, 100);
12 textFieldFrame.setVisible(true);
13 }
14 } // end class TextFieldTest

```

---



**Fig. 12.10** | Testing `TextFieldFrame`. (Part I of 2.)



**Fig. 12.10** | Testing TextFieldFrame. (Part 2 of 2.)

This application used a single object of class `TextFieldHandler` as the event listener for four text fields. Starting in Section 12.10, you'll see that it's possible to declare several event-listener objects of the same type and register each object for a separate GUI component's event. This technique enables us to eliminate the `if...else` logic used in this example's event handler by providing separate event handlers for each component's events.


### *Java SE 8: Implementing Event Listeners with Lambdas*

Recall that interfaces like `ActionListener` that have only one abstract method are functional interfaces in Java SE 8. In Section 17.9, we show a more concise way to implement such event-listener interfaces with Java SE 8 lambdas.

## 12.7 Common GUI Event Types and Listener Interfaces

In Section 12.6, you learned that information about the event that occurs when the user presses *Enter* in a text field is stored in an `ActionEvent` object. Many different types of events can occur when the user interacts with a GUI. The event information is stored in an object of a class that extends `AWTEvent` (from package `java.awt`). Figure 12.11 illustrates a hierarchy containing many event classes from the package `java.awt.event`. Some of these are discussed in this chapter and Chapter 22. These event types are used with both


AWT and Swing components. Additional event types that are specific to Swing GUI components are declared in package `javax.swing.event`.



**Fig. 12.11** | Some event classes of package `java.awt.event`.

Let's summarize the three parts to the event-handling mechanism that you saw in Section 12.6—the *event source*, the *event object* and the *event listener*. The event source is the GUI component with which the user interacts. The event object encapsulates information about the event that occurred, such as a reference to the event source and any event-specific information that may be required by the event listener for it to handle the event. The event listener is an object that's notified by the event source when an event occurs; in effect, it "listens" for an event, and one of its methods executes in response to the event. A method of the event listener receives an event object when the event listener is notified of the event. The event listener then uses the event object to respond to the event. This event-handling model is known as the **delegation event model**—an event's processing is delegated to an object (the event listener) in the application.

For each event-object type, there's typically a corresponding event-listener interface. An event listener for a GUI event is an object of a class that implements one or more of the event-listener interfaces from packages `java.awt.event` and `javax.swing.event`. Many of the event-listener types are common to both Swing and AWT components. Such types are declared in package `java.awt.event`, and some of them are shown in Fig. 12.12. Additional event-listener types that are specific to Swing components are declared in package `javax.swing.event`.



**Fig. 12.12** | Some common event-listener interfaces of package `java.awt.event`.

Each event-listener interface specifies one or more event-handling methods that *must* be declared in the class that implements the interface. Recall from Section 10.9 that any class which implements an interface must declare *all* the abstract methods of that interface; otherwise, the class is an abstract class and cannot be used to create objects.

When an event occurs, the GUI component with which the user interacted notifies its *registered listeners* by calling each listener's appropriate *event-handling method*. For example, when the user presses the *Enter* key in a `JTextField`, the registered listener's `actionPerformed` method is called. In the next section, we complete our discussion of how the event handling works in the preceding example.

## 12.8 How Event Handling Works

Let's illustrate how the event-handling mechanism works, using `textField1` from the example of Fig. 12.9. We have two remaining open questions from Section 12.7:


1. How did the *event handler* get *registered*?
2. How does the GUI component know to call `actionPerformed` rather than some other event-handling method?

The first question is answered by the event registration performed in lines 43–46 of Fig. 12.9. Figure 12.13 diagrams `JTextField` variable `textField1`, `TextFieldHandler` variable `handler` and the objects to which they refer.

### Registering Events

Every `JComponent` has an instance variable called `listenerList` that refers to an object of class `EventListenerList` (package `javax.swing.event`). Each object of a `JComponent`

subclass maintains references to its *registered listeners* in the `listenerList`. For simplicity, we've diagrammed `listenerList` as an array below the `JTextField` object in Fig. 12.13.



**Fig. 12.13** | Event registration for `JTextField textField1`.

When the following statement (line 43 of Fig. 12.9) executes

```
textField1.addActionListener(handler);
```

a new entry containing a reference to the `TextFieldHandler` object is placed in `textField1`'s `listenerList`. Although not shown in the diagram, this new entry also includes the listener's type (`ActionListener`). Using this mechanism, each lightweight Swing component maintains its own list of *listeners* that were *registered* to *handle* the component's *events*.

### Event-Handler Invocation

The event-listener type is important in answering the second question: How does the GUI component know to call `actionPerformed` rather than another method? Every GUI component supports several *event types*, including **mouse events**, **key events** and others. When an event occurs, the event is **dispatched** only to the *event listeners* of the appropriate type. Dispatching is simply the process by which the GUI component calls an event-handling method on each of its listeners that are registered for the event type that occurred.

Each *event type* has one or more corresponding *event-listener interfaces*. For example, `ActionEvents` are handled by `ActionListeners`, `MouseEvents` by `MouseListeners` and `MouseMotionListeners`, and `KeyEvents` by `KeyListeners`. When an event occurs, the GUI component receives (from the JVM) a unique *event ID* specifying the event type. The GUI component uses the event ID to decide the listener type to which the event should be dispatched and to decide which method to call on each listener object. For an `ActionEvent`, the event is dispatched to *every* registered `ActionListener`'s `actionPerformed` method (the only method in interface `ActionListener`). For a `MouseEvent`, the event is dispatched to *every* registered `MouseListener` or `MouseMotionListener`, depending on the mouse event that

occurs. The `MouseEvent`'s event ID determines which of the several mouse event-handling methods are called. All these decisions are handled for you by the GUI components. All you need to do is register an event handler for the particular event type that your application requires, and the GUI component will ensure that the event handler's appropriate method gets called when the event occurs. We discuss other event types and event-listener interfaces as they're needed with each new component we introduce.




### Performance Tip 12.1

*GUIs should always remain responsive to the user. Performing a long-running task in an event handler prevents the user from interacting with the GUI until that task completes. Section 23.11 demonstrates techniques prevent such problems.*

## 12.9 JButton

A **button** is a component the user clicks to trigger a specific action. A Java application can use several types of buttons, including **command buttons**, **checkboxes**, **toggle buttons** and **radio buttons**. Figure 12.14 shows the inheritance hierarchy of the Swing buttons we cover in this chapter. As you can see, all the button types are subclasses of **AbstractButton** (package `javax.swing`), which declares the common features of Swing buttons. In this section, we concentrate on buttons that are typically used to initiate a command.



**Fig. 12.14** | Swing button hierarchy.

A *command button* (see Fig. 12.16's output) generates an `ActionEvent` when the user clicks it. Command buttons are created with class **JButton**. The text on the face of a `JButton` is called a **button label**.



### Look-and-Feel Observation 12.8

*The text on buttons typically uses book-title capitalization.*



### Look-and-Feel Observation 12.9

*A GUI can have many `JButtons`, but each button label should be unique in the portion of the GUI that's currently displayed. Having more than one `JButton` with the same label makes the `JButtons` ambiguous to the user.*

The application of Figs. 12.15 and 12.16 creates two `JButtons` and demonstrates that `JButtons` can display Icons. Event handling for the buttons is performed by a single instance of *inner class* `ButtonHandler` (Fig. 12.15, lines 39–48).

---

```

1 // Fig. 12.15: ButtonFrame.java
2 // Command buttons and action events.
3 import java.awt.FlowLayout;
4 import java.awt.event.ActionListener;
5 import java.awt.event.ActionEvent;
6 import javax.swing.JFrame;
7 import javax.swing.JButton;
8 import javax.swing.Icon;
9 import javax.swing.ImageIcon;
10 import javax.swing.JOptionPane;
11
12 public class ButtonFrame extends JFrame
13 {
14 private final JButton plainJButton; // button with just text
15 private final JButton fancyJButton; // button with icons
16
17 // ButtonFrame adds JButtons to JFrame
18 public ButtonFrame()
19 {
20 super("Testing Buttons");
21 setLayout(new FlowLayout());
22
23 plainJButton = new JButton("Plain Button"); // button with text
24 add(plainJButton); // add plainJButton to JFrame
25
26 Icon bug1 = new ImageIcon(getClass().getResource("bug1.gif"));
27 Icon bug2 = new ImageIcon(getClass().getResource("bug2.gif"));
28 fancyJButton = new JButton("Fancy Button", bug1); // set image
29 fancyJButton.setRolloverIcon(bug2); // set rollover image
30 add(fancyJButton); // add fancyJButton to JFrame
31
32 // create new ButtonHandler for button event handling
33 ButtonHandler handler = new ButtonHandler();
34 fancyJButton.addActionListener(handler);
35 plainJButton.addActionListener(handler);
36 }
37
38 // inner class for button event handling
39 private class ButtonHandler implements ActionListener
40 {
41 // handle button event
42 @Override
43 public void actionPerformed(ActionEvent event)
44 {
45 JOptionPane.showMessageDialog(ButtonFrame.this, String.format(
46 "You pressed: %s", event.getActionCommand()));
47 }
48 }
49 } // end class ButtonFrame

```

---


**Fig. 12.15** | Command buttons and action events.



```

1 // Fig. 12.16: ButtonTest.java
2 // Testing ButtonFrame.
3 import javax.swing.JFrame;
4
5 public class ButtonTest
6 {
7 public static void main(String[] args)
8 {
9 ButtonFrame buttonFrame = new ButtonFrame();
10 buttonFrame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
11 buttonFrame.setSize(275, 110);
12 buttonFrame.setVisible(true);
13 }
14 } // end class ButtonTest

```



**Fig. 12.16** | Testing ButtonFrame.

Lines 14–15 declare JButton variables `plainJButton` and `fancyJButton`. The corresponding objects are instantiated in the constructor. Line 23 creates `plainJButton` with the button label "Plain Button". Line 24 adds the JButton to the JFrame.

A JButton can display an Icon. To provide the user with an extra level of visual interaction with the GUI, a JButton can also have a **rollover Icon**—an Icon that's displayed when the user positions the mouse over the JButton. The icon on the JButton changes as the mouse moves in and out of the JButton's area on the screen. Lines 26–27 create two

ImageIcon objects that represent the default Icon and rollover Icon for the JButton created at line 28. Both statements assume that the image files are stored in the *same* directory as the application. Images are commonly placed in the *same* directory as the application or a subdirectory like *images*). These image files have been provided for you with the example.

Line 28 creates fancyButton with the text "Fancy Button" and the icon bug1. By default, the text is displayed to the *right* of the icon. Line 29 uses **setRolloverIcon** (inherited from class AbstractButton) to specify the image displayed on the JButton when the user positions the mouse over it. Line 30 adds the JButton to the JFrame.



### Look-and-Feel Observation 12.10

*Because class AbstractButton supports displaying text and images on a button, all subclasses of AbstractButton also support displaying text and images.*



### Look-and-Feel Observation 12.11

*Rollover icons provide visual feedback indicating that an action will occur when a JButton is clicked.*

JButtons, like JTextFields, generate ActionEvents that can be processed by any ActionListener object. Lines 33–35 create an object of private *inner class* ButtonHandler and use addActionListener to *register* it as the *event handler* for each JButton. Class ButtonHandler (lines 39–48) declares actionPerformed to display a message dialog box containing the label for the button the user pressed. For a JButton event, ActionEvent method getActionCommand returns the label on the JButton.

### Accessing the *this* Reference in an Object of a Top-Level Class from an Inner Class

When you execute this application and click one of its buttons, notice that the message dialog that appears is centered over the application's window. This occurs because the call to JOptionPane method showMessageDialog (lines 45–46) uses ButtonFrame.this rather than null as the first argument. When this argument is not null, it represents the so-called *parent GUI component* of the message dialog (in this case the application window is the parent component) and enables the dialog to be centered over that component when the dialog is displayed. ButtonFrame.this represents the this reference of the object of top-level class ButtonFrame.



### Software Engineering Observation 12.2

*When used in an inner class, keyword this refers to the current inner-class object being manipulated. An inner-class method can use its outer-class object's this by preceding this with the outer-class name and a dot (.) separator, as in ButtonFrame.this.*

## 12.10 Buttons That Maintain State

The Swing GUI components contain three types of **state buttons**—**JToggleButton**, **JCheckBox** and **JRadioButton**—that have on/off or true/false values. Classes JCheckBox and JRadioButton are subclasses of JToggleButton (Fig. 12.14). A JRadioButton is different from a JCheckBox in that normally several JRadioButtons are grouped together and

are *mutually exclusive*—only *one* in the group can be selected at any time, just like the buttons on a car radio. We first discuss class `JCheckBox`.

### 12.10.1 JCheckBox

The application of Figs. 12.17–12.18 uses two `JCheckBox`s to select the desired font style of the text displayed in a `TextField`. When selected, one applies a bold style and the other an italic style. If *both* are selected, the style is bold *and* italic. When the application initially executes, neither `JCheckBox` is checked (i.e., they're both `false`), so the font is plain. Class `CheckBoxTest` (Fig. 12.18) contains the `main` method that executes this application.

---

```

1 // Fig. 12.17: CheckBoxFrame.java
2 // JCheckBoxes and item events.
3 import java.awt.FlowLayout;
4 import java.awt.Font;
5 import java.awt.event.ItemListener;
6 import java.awt.event.ItemEvent;
7 import javax.swing.JFrame;
8 import javax.swing.JTextField;
9 import javax.swing.JCheckBox;
10
11 public class CheckBoxFrame extends JFrame
12 {
13 private final JTextField textField; // displays text in changing fonts
14 private final JCheckBox boldJCheckBox; // to select/deselect bold
15 private final JCheckBox italicJCheckBox; // to select/deselect italic
16
17 // CheckBoxFrame constructor adds JCheckBoxes to JFrame
18 public CheckBoxFrame()
19 {
20 super("JCheckBox Test");
21 setLayout(new FlowLayout());
22
23 // set up JTextField and set its font
24 textField = new JTextField("Watch the font style change", 20);
25 textField.setFont(new Font("Serif", Font.PLAIN, 14));
26 add(textField); // add textField to JFrame
27
28 boldJCheckBox = new JCheckBox("Bold");
29 italicJCheckBox = new JCheckBox("Italic");
30 add(boldJCheckBox); // add bold checkbox to JFrame
31 add(italicJCheckBox); // add italic checkbox to JFrame
32
33 // register listeners for JCheckBoxes
34 CheckBoxHandler handler = new CheckBoxHandler();
35 boldJCheckBox.addItemListener(handler);
36 italicJCheckBox.addItemListener(handler);
37 }
38
39 // private inner class for ItemListener event handling
40 private class CheckBoxHandler implements ItemListener
41 {

```

---

**Fig. 12.17** | `JCheckBox`s and item events. (Part I of 2.)

---

```

42 // respond to checkbox events
43 @Override
44 public void itemStateChanged(ItemEvent event)
45 {
46 Font font = null; // stores the new Font
47
48 // determine which CheckBoxes are checked and create Font
49 if (boldJCheckBox.isSelected() && italicJCheckBox.isSelected())
50 font = new Font("Serif", Font.BOLD + Font.ITALIC, 14);
51 else if (boldJCheckBox.isSelected())
52 font = new Font("Serif", Font.BOLD, 14);
53 else if (italicJCheckBox.isSelected())
54 font = new Font("Serif", Font.ITALIC, 14);
55 else
56 font = new Font("Serif", Font.PLAIN, 14);
57
58 textField.setFont(font);
59 }
60 }
61 } // end class CheckBoxFrame

```

---

**Fig. 12.17** | JCheckBoxes and item events. (Part 2 of 2.)

---

```

1 // Fig. 12.18: CheckBoxTest.java
2 // Testing CheckBoxFrame.
3 import javax.swing.JFrame;
4
5 public class CheckBoxTest
6 {
7 public static void main(String[] args)
8 {
9 CheckBoxFrame checkBoxFrame = new CheckBoxFrame();
10 checkBoxFrame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
11 checkBoxFrame.setSize(275, 100);
12 checkBoxFrame.setVisible(true);
13 }
14 } // end class CheckBoxTest

```



**Fig. 12.18** | Testing CheckBoxFrame.

---

After the `JTextField` is created and initialized (Fig. 12.17, line 24), line 25 uses method `setFont` (inherited by `JTextField` indirectly from class `Component`) to set the font of the `JTextField` to a new object of class `Font` (package `java.awt`). The new `Font` is ini-

tialized with "Serif" (a generic font name that represents a font such as Times and is supported on all Java platforms), `Font.PLAIN` style and 14-point size. Next, lines 28–29 create two `JCheckBox` objects. The `String` passed to the `JCheckBox` constructor is the **checkbox label** that appears to the right of the `JCheckBox` by default.

When the user clicks a `JCheckBox`, an **ItemEvent** occurs. This event can be handled by an **ItemListener** object, which *must* implement method **itemStateChanged**. In this example, the event handling is performed by an instance of private *inner class* `CheckBoxHandler` (lines 40–60). Lines 34–36 create an instance of class `CheckBoxHandler` and register it with method **addItemListener** as the listener for both the `JCheckBox` objects.

`CheckBoxHandler` method **itemStateChanged** (lines 43–59) is called when the user clicks the either `boldJCheckBox` or `italicJCheckBox`. In this example, we do not determine which `JCheckBox` was clicked—we use both of their states to determine the font to display. Line 49 uses `JCheckBox` method **isSelected** to determine if both `JCheckBoxes` are selected. If so, line 50 creates a bold italic font by adding the `Font` constants `Font.BOLD` and `Font.ITALIC` for the font-style argument of the `Font` constructor. Line 51 determines whether the `boldJCheckBox` is selected, and if so line 52 creates a bold font. Line 53 determines whether the `italicJCheckBox` is selected, and if so line 54 creates an italic font. If none of the preceding conditions are true, line 56 creates a plain font using the `Font` constant `Font.PLAIN`. Finally, line 58 sets `textField`'s new font, which changes the font in the `JTextField` on the screen.

### *Relationship Between an Inner Class and Its Top-Level Class*

Class `CheckBoxHandler` used variables `boldJCheckBox` (lines 49 and 51), `italicJCheckBox` (lines 49 and 53) and `textField` (line 58) even though they are *not* declared in the inner class. Recall that an *inner class* has a special relationship with its *top-level class*—it's allowed to access *all* the variables and methods of the top-level class. `CheckBoxHandler` method **itemStateChanged** (line 43–59) uses this relationship to determine which `JCheckBoxes` are checked and to set the font on the `JTextField`. Notice that none of the code in inner class `CheckBoxHandler` requires an explicit reference to the top-level class object.

## 12.10.2 JRadioButton

**Radio buttons** (declared with class `JRadioButton`) are similar to checkboxes in that they have two states—*selected* and *not selected* (also called *deselected*). However, radio buttons normally appear as a **group** in which only *one* button can be selected at a time (see the output of Fig. 12.20). Radio buttons are used to represent **mutually exclusive options** (i.e., multiple options in the group *cannot* be selected at the same time). The logical relationship between radio buttons is maintained by a **ButtonGroup** object (package `javax.swing`), which itself is *not* a GUI component. A `ButtonGroup` object organizes a group of buttons and is *not* itself displayed in a user interface. Rather, the individual `JRadioButton` objects from the group are displayed in the GUI.

The application of Figs. 12.19–12.20 is similar to that of Figs. 12.17–12.18. The user can alter the font style of a `JTextField`'s text. The application uses radio buttons that permit only a single font style in the group to be selected at a time. Class `RadioButtonTest` (Fig. 12.20) contains the `main` method that executes this application.

---

```

1 // Fig. 12.19: RadioButtonFrame.java
2 // Creating radio buttons using ButtonGroup and JRadioButton.
3 import java.awt.FlowLayout;
4 import java.awt.Font;
5 import java.awt.event.ItemListener;
6 import java.awt.event.ItemEvent;
7 import javax.swing.JFrame;
8 import javax.swing.JTextField;
9 import javax.swing.JRadioButton;
10 import javax.swing.ButtonGroup;
11
12 public class RadioButtonFrame extends JFrame
13 {
14 private final JTextField textField; // used to display font changes
15 private final Font plainFont; // font for plain text
16 private final Font boldFont; // font for bold text
17 private final Font italicFont; // font for italic text
18 private final Font boldItalicFont; // font for bold and italic text
19 private final JRadioButton plainJRadioButton; // selects plain text
20 private final JRadioButton boldJRadioButton; // selects bold text
21 private final JRadioButton italicJRadioButton; // selects italic text
22 private final JRadioButton boldItalicJRadioButton; // bold and italic
23 private final ButtonGroup radioGroup; // holds radio buttons
24
25 // RadioButtonFrame constructor adds JRadioButtons to JFrame
26 public RadioButtonFrame()
27 {
28 super("RadioButton Test");
29 setLayout(new FlowLayout());
30
31 textField = new JTextField("Watch the font style change", 25);
32 add(textField); // add textField to JFrame
33
34 // create radio buttons
35 plainJRadioButton = new JRadioButton("Plain", true);
36 boldJRadioButton = new JRadioButton("Bold", false);
37 italicJRadioButton = new JRadioButton("Italic", false);
38 boldItalicJRadioButton = new JRadioButton("Bold/Italic", false);
39 add(plainJRadioButton); // add plain button to JFrame
40 add(boldJRadioButton); // add bold button to JFrame
41 add(italicJRadioButton); // add italic button to JFrame
42 add(boldItalicJRadioButton); // add bold and italic button
43
44 // create logical relationship between JRadioButtons
45 radioGroup = new ButtonGroup(); // create ButtonGroup
46 radioGroup.add(plainJRadioButton); // add plain to group
47 radioGroup.add(boldJRadioButton); // add bold to group
48 radioGroup.add(italicJRadioButton); // add italic to group
49 radioGroup.add(boldItalicJRadioButton); // add bold and italic
50
51 // create font objects
52 plainFont = new Font("Serif", Font.PLAIN, 14);
53 boldFont = new Font("Serif", Font.BOLD, 14);

```

---

**Fig. 12.19** | Creating radio buttons using ButtonGroup and JRadioButton. (Part I of 2.)

---

```

54 italicFont = new Font("Serif", Font.ITALIC, 14);
55 boldItalicFont = new Font("Serif", Font.BOLD + Font.ITALIC, 14);
56 textField.setFont(plainFont);
57
58 // register events for JRadioButtons
59 plainJRadioButton.addItemListener(
60 new RadioButtonHandler(plainFont));
61 boldJRadioButton.addItemListener(
62 new RadioButtonHandler(boldFont));
63 italicJRadioButton.addItemListener(
64 new RadioButtonHandler(italicFont));
65 boldItalicJRadioButton.addItemListener(
66 new RadioButtonHandler(boldItalicFont));
67 }
68
69 // private inner class to handle radio button events
70 private class RadioButtonHandler implements ItemListener
71 {
72 private Font font; // font associated with this listener
73
74 public RadioButtonHandler(Font f)
75 {
76 font = f;
77 }
78
79 // handle radio button events
80 @Override
81 public void itemStateChanged(ItemEvent event)
82 {
83 textField.setFont(font);
84 }
85 }
86 } // end class RadioButtonFrame

```

---

**Fig. 12.19** | Creating radio buttons using ButtonGroup and JRadioButton. (Part 2 of 2.)

---


```

1 // Fig. 12.20: RadioButtonTest.java
2 // Testing RadioButtonFrame.
3 import javax.swing.JFrame;
4
5 public class RadioButtonTest
6 {
7 public static void main(String[] args)
8 {
9 RadioButtonFrame radioButtonFrame = new RadioButtonFrame();
10 radioButtonFrame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
11 radioButtonFrame.setSize(300, 100);
12 radioButtonFrame.setVisible(true);
13 }
14 } // end class RadioButtonTest

```

---

**Fig. 12.20** | Testing RadioButtonFrame. (Part 1 of 2.)



**Fig. 12.20** | Testing `RadioButtonFrame`. (Part 2 of 2.)

Lines 35–42 (Fig. 12.19) in the constructor create four `JRadioButton` objects and add them to the `JFrame`. Each `JRadioButton` is created with a constructor call like that in line 35. This constructor specifies the label that appears to the right of the `JRadioButton` by default and the initial state of the `JRadioButton`. A true second argument indicates that the `JRadioButton` should appear *selected* when it's displayed.

Line 45 instantiates `ButtonGroup` object `radioGroup`. This object is the “glue” that forms the logical relationship between the four `JRadioButton` objects and allows only one of the four to be selected at a time. It's possible that no `JRadioButtons` in a `ButtonGroup` are selected, but this can occur *only if no* preselected `JRadioButtons` are added to the `ButtonGroup` and the user has *not* selected a `JRadioButton` yet. Lines 46–49 use `ButtonGroup` method `add` to associate each of the `JRadioButtons` with `radioGroup`. If more than one selected `JRadioButton` object is added to the group, the selected one that was added *first* will be selected when the GUI is displayed.

`JRadioButtons`, like `JCheckBoxes`, generate `ItemEvents` when they're *clicked*. Lines 59–66 create four instances of inner class `RadioButtonHandler` (declared at lines 70–85). In this example, each event-listener object is registered to handle the `ItemEvent` generated when the user clicks a particular `JRadioButton`. Notice that each `RadioButtonHandler` object is initialized with a particular `Font` object (created in lines 52–55).

Class `RadioButtonHandler` (line 70–85) implements interface `ItemListener` so it can handle `ItemEvents` generated by the `JRadioButtons`. The constructor stores the `Font` object it receives as an argument in the event-listener object's instance variable `font` (declared at line 72). When the user clicks a `JRadioButton`, `radioGroup` turns off the previously selected `JRadioButton`, and method `itemStateChanged` (lines 80–84) sets the font in the `JTextField` to the `Font` stored in the `JRadioButton`'s corresponding event-listener object. Notice that line 83 of inner class `RadioButtonHandler` uses the top-level class's `textField` instance variable to set the font.

## 12.11 JComboBox; Using an Anonymous Inner Class for Event Handling

A combo box (sometimes called a **drop-down list**) enables the user to select *one* item from a list (Fig. 12.22). Combo boxes are implemented with class `JComboBox`, which extends



class `JComponent`. `JComboBox` is a generic class, like the class `ArrayList` (Chapter 6). When you create a `JComboBox`, you specify the type of the objects that it manages—the `JComboBox` then displays a `String` representation of each object.

---

```

1 // Fig. 12.21: ComboBoxFrame.java
2 // JComboBox that displays a list of image names.
3 import java.awt.FlowLayout;
4 import java.awt.event.ItemListener;
5 import java.awt.event.ItemEvent;
6 import javax.swing.JFrame;
7 import javax.swing.JLabel;
8 import javax.swing.JComboBox;
9 import javax.swing.Icon;
10 import javax.swing.ImageIcon;
11
12 public class ComboBoxFrame extends JFrame
13 {
14 private final JComboBox<String> imagesJComboBox; // holds icon names
15 private final JLabel label; // displays selected icon
16
17 private static final String[] names =
18 {"bug1.gif", "bug2.gif", "travelbug.gif", "buganim.gif"};
19 private final Icon[] icons = {
20 new ImageIcon(getClass().getResource(names[0])),
21 new ImageIcon(getClass().getResource(names[1])),
22 new ImageIcon(getClass().getResource(names[2])),
23 new ImageIcon(getClass().getResource(names[3]))};
24
25 // ComboBoxFrame constructor adds JComboBox to JFrame
26 public ComboBoxFrame()
27 {
28 super("Testing JComboBox");
29 setLayout(new FlowLayout()); // set frame layout
30
31 imagesJComboBox = new JComboBox<String>(names); // set up JComboBox
32 imagesJComboBox.setMaximumRowCount(3); // display three rows
33
34 imagesJComboBox.addItemListener(
35 new ItemListener() // anonymous inner class
36 {
37 // handle JComboBox event
38 @Override
39 public void itemStateChanged(ItemEvent event)
40 {
41 // determine whether item selected
42 if (event.getStateChange() == ItemEvent.SELECTED)
43 label.setIcon(icons[
44 imagesJComboBox.getSelectedIndex()]);
45 }
46 } // end anonymous inner class
47); // end call to addItemListener
48

```

---

**Fig. 12.21** | JComboBox that displays a list of image names. (Part I of 2.)

```

49 add(imagesJComboBox); // add combo box to JFrame
50 label = new JLabel(icons[0]); // display first icon
51 add(label); // add label to JFrame
52 }
53 } // end class ComboBoxFrame


```

**Fig. 12.21** | JComboBox that displays a list of image names. (Part 2 of 2.)

```

1 // Fig. 12.22: ComboBoxTest.java
2 // Testing ComboBoxFrame.
3 import javax.swing.JFrame;
4
5 public class ComboBoxTest
6 {
7 public static void main(String[] args)
8 {
9 ComboBoxFrame comboBoxFrame = new ComboBoxFrame();
10 comboBoxFrame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
11 comboBoxFrame.setSize(350, 150);
12 comboBoxFrame.setVisible(true);
13 }
14 } // end class ComboBoxTest

```



**Fig. 12.22** | Testing ComboBoxFrame.

JComboBoxes generate ItemEvents just as JCheckBoxes and JRadioButtons do. This example also demonstrates a special form of inner class that's used frequently in event handling. The application (Figs. 12.21–12.22) uses a JComboBox to provide a list of four image filenames from which the user can select one image to display. When the user selects a name, the application displays the corresponding image as an Icon on a JLabel. Class `ComboBoxTest` (Fig. 12.22) contains the main method that executes this application. The screen captures for this application show the JComboBox list after the selection was made to illustrate which image filename was selected.

Lines 19–23 (Fig. 12.21) declare and initialize array `icons` with four new `ImageIcon` objects. String array `names` (lines 17–18) contains the names of the four image files that are stored in the same directory as the application.

At line 31, the constructor initializes a `JComboBox` object with the `Strings` in array `names` as the elements in the list. Each item in the list has an **index**. The first item is added at index 0, the next at index 1 and so forth. The first item added to a `JComboBox` appears as the currently selected item when the `JComboBox` is displayed. Other items are selected by clicking the `JComboBox`, then selecting an item from the list that appears.

Line 32 uses `JComboBox` method **`setMaximumRowCount`** to set the maximum number of elements that are displayed when the user clicks the `JComboBox`. If there are additional items, the `JComboBox` provides a **scrollbar** (see the first screen) that allows the user to scroll through all the elements in the list. The user can click the **scroll arrows** at the top and bottom of the scrollbar to move up and down through the list one element at a time, or else drag the **scroll box** in the middle of the scrollbar up and down. To drag the scroll box, position the mouse cursor on it, hold the mouse button down and move the mouse. In this example, the drop-down list is too short to drag the scroll box, so you can click the up and down arrows or use your mouse's wheel to scroll through the four items in the list. Line 49 attaches the `JComboBox` to the `ComboBoxFrame`'s `FlowLayout` (set in line 29). Line 50 creates the `JLabel` that displays `ImageIcons` and initializes it with the first `ImageIcon` in array `icons`. Line 51 attaches the `JLabel` to the `ComboBoxFrame`'s `FlowLayout`.



### Look-and-Feel Observation 12.12

*Set the maximum row count for a `JComboBox` to a number of rows that prevents the list from expanding outside the bounds of the window in which it's used.*

### Using an Anonymous Inner Class for Event Handling

Lines 34–46 are one statement that declares the event listener's class, creates an object of that class and registers it as `imagesJComboBox`'s `ItemEvent` listener. This event-listener object is an instance of an **anonymous inner class**—a class that's declared without a name and typically appears inside a method declaration. *As with other inner classes, an anonymous inner class can access its top-level class's members.* However, an anonymous inner class has limited access to the local variables of the method in which it's declared. Since an anonymous inner class has no name, one object of the class must be created at the point where the class is declared (starting at line 35).



### Software Engineering Observation 12.3

*An anonymous inner class declared in a method can access the instance variables and methods of the top-level class object that declared it, as well as the method's `final` local variables, but cannot access the method's non-`final` local variables. As of Java SE 8, anonymous inner classes may also access a method's "effectively `final`" local variables—see Chapter 17 for more information.*

Lines 34–47 are a call to `imagesJComboBox`'s `addItemListener` method. The argument to this method must be an object that *is an* `ItemListener` (i.e., any object of a class that implements `ItemListener`). Lines 35–46 are a class-instance creation expression that declares an anonymous inner class and creates one object of that class. A reference to that object is then passed as the argument to `addItemListener`. The syntax `ItemListener()`

after `new` begins the declaration of an anonymous inner class that implements interface `ItemListener`. This is similar to beginning a class declaration with

```
public class MyHandler implements ItemListener
```

The opening left brace at line 36 and the closing right brace at line 46 delimit the body of the anonymous inner class. Lines 38–45 declare the `ItemListener`’s `itemStateChanged` method. When the user makes a selection from `imagesJComboBox`, this method sets `label`’s `Icon`. The `Icon` is selected from array `icons` by determining the index of the selected item in the `JComboBox` with method `getSelectedIndex` in line 44. For each item selected from a `JComboBox`, another item is first deselected—so two `ItemEvents` occur when an item is selected. We wish to display only the icon for the item the user just selected. For this reason, line 42 determines whether `ItemEvent` method `getStateChange` returns `ItemEvent.SELECTED`. If so, lines 43–44 set `label`’s icon.



#### Software Engineering Observation 12.4

*Like any other class, when an anonymous inner class implements an interface, the class must implement every abstract method in the interface.*

The syntax shown in lines 35–46 for creating an event handler with an anonymous inner class is similar to the code that would be generated by a Java integrated development environment (IDE). Typically, an IDE enables you to design a GUI visually, then it generates code that implements the GUI. You simply insert statements in the event-handling methods that declare how to handle each event.

#### Java SE 8: Implementing Anonymous Inner Classes with Lambdas

In Section 17.9, we show how to use Java SE 8 lambdas to create event handlers. As you’ll learn, the compiler translates a lambda into an object of an anonymous inner class.

## 12.12 JList

A list displays a series of items from which the user may *select one or more items* (see the output of Fig. 12.24). Lists are created with class `JList`, which directly extends class `JComponent`. Class `JList`—which like `JComboBox` is a generic class—supports **single-selection lists** (which allow only one item to be selected at a time) and **multiple-selection lists** (which allow any number of items to be selected). In this section, we discuss single-selection lists.

The application of Figs. 12.23–12.24 creates a `JList` containing 13 color names. When a color name is clicked in the `JList`, a `ListSelectionEvent` occurs and the application changes the background color of the application window to the selected color. Class `ListTest` (Fig. 12.24) contains the `main` method that executes this application.

---

```
1 // Fig. 12.23: ListFrame.java
2 // JList that displays a list of colors.
3 import java.awt.FlowLayout;
4 import java.awt.Color;
5 import javax.swing.JFrame;
6 import javax.swing.JList;
```

---

**Fig. 12.23** | `JList` that displays a list of colors. (Part I of 2.)

---

```

7 import javax.swing.JScrollPane;
8 import javax.swing.event.ListSelectionListener;
9 import javax.swing.event.ListSelectionEvent;
10 import javax.swing.ListSelectionModel;
11
12 public class ListFrame extends JFrame
13 {
14 private final JList<String> colorJList; // list to display colors
15 private static final String[] colorNames = {"Black", "Blue", "Cyan",
16 "Dark Gray", "Gray", "Green", "Light Gray", "Magenta",
17 "Orange", "Pink", "Red", "White", "Yellow"};
18 private static final Color[] colors = {Color.BLACK, Color.BLUE,
19 Color.CYAN, Color.DARK_GRAY, Color.GRAY, Color.GREEN,
20 Color.LIGHT_GRAY, Color.MAGENTA, Color.ORANGE, Color.PINK,
21 Color.RED, Color.WHITE, Color.YELLOW};
22
23 // ListFrame constructor add JScrollPane containing JList to JFrame
24 public ListFrame()
25 {
26 super("List Test");
27 setLayout(new FlowLayout());
28
29 colorJList = new JList<String>(colorNames); // list of colorNames
30 colorJList.setVisibleRowCount(5); // display five rows at once
31
32 // do not allow multiple selections
33 colorJList.setSelectionMode(ListSelectionModel.SINGLE_SELECTION);
34
35 // add a JScrollPane containing JList to frame
36 add(new JScrollPane(colorJList));
37
38 colorJList.addListSelectionListener(
39 new ListSelectionListener() // anonymous inner class
40 {
41 // handle list selection events
42 @Override
43 public void valueChanged(ListSelectionEvent event)
44 {
45 getContentPane().setBackground(
46 colors[colorJList.getSelectedIndex()]);
47 }
48 }
49);
50 }
51 } // end class ListFrame

```

---

**Fig. 12.23** | JList that displays a list of colors. (Part 2 of 2.)

---

```

1 // Fig. 12.24: ListTest.java
2 // Selecting colors from a JList.
3 import javax.swing.JFrame;
4

```


---

**Fig. 12.24** | Selecting colors from a JList. (Part 1 of 2.)

```

5 public class ListTest
6 {
7 public static void main(String[] args)
8 {
9 ListFrame listFrame = new ListFrame(); // create ListFrame
10 listFrame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
11 listFrame.setSize(350, 150);
12 listFrame.setVisible(true);
13 }
14 } // end class ListTest

```



**Fig. 12.24** | Selecting colors from a JList. (Part 2 of 2.)

Line 29 (Fig. 12.23) creates JList object `colorJList`. The argument to the JList constructor is the array of Objects (in this case Strings) to display in the list. Line 30 uses JList method **setVisibleRowCount** to determine the number of items *visible* in the list.

Line 33 uses JList method **setSelectionMode** to specify the list's **selection mode**. Class **ListSelectionMode** (of package `javax.swing`) declares three constants that specify a JList's selection mode—**SINGLE\_SELECTION** (which allows only one item to be selected at a time), **SINGLE\_INTERVAL\_SELECTION** (for a multiple-selection list that allows selection of several contiguous items) and **MULTIPLE\_INTERVAL\_SELECTION** (for a multiple-selection list that does not restrict the items that can be selected).

Unlike a JComboBox, a JList *does not provide a scrollbar* if there are more items in the list than the number of visible rows. In this case, a **JScrollPane** object is used to provide the scrolling capability. Line 36 adds a new instance of class **JScrollPane** to the JFrame. The JScrollPane constructor receives as its argument the JComponent that needs scrolling functionality (in this case, `colorJList`). Notice in the screen captures that a scrollbar created by the JScrollPane appears at the right side of the JList. By default, the scrollbar appears only when the number of items in the JList exceeds the number of visible items.

Lines 38–49 use JList method **addListSelectionListener** to register an object that implements **ListSelectionListener** (package `javax.swing.event`) as the listener for the JList's selection events. Once again, we use an instance of an anonymous inner class (lines 39–48) as the listener. In this example, when the user makes a selection from `colorJList`, method **valueChanged** (line 42–47) should change the background color of the ListFrame to the selected color. This is accomplished in lines 45–46. Note the use of JFrame method **getContentPane** in line 45. Each JFrame actually consists of *three layers*—the *background*, the *content pane* and the *glass pane*. The content pane appears in front of the background and is where the GUI components in the JFrame are displayed. The glass pane is used to display tool tips and other items that should appear in front of the GUI components on the screen. The content pane completely hides the background of the JFrame; thus, to change the background color behind the GUI components, you must change the content pane's background color. Method `getContentPane` returns a reference to the

JFrame's content pane (an object of class `Container`). In line 45, we then use that reference to call method **setBackground**, which sets the content pane's background color to an element in the `colors` array. The color is selected from the array by using the selected item's index. `JList` method **getSelectedIndex** returns the selected item's index. As with arrays and `JComboBoxes`, `JList` indexing is zero based.

## 12.13 Multiple-Selection Lists

A **multiple-selection list** enables the user to select many items from a `JList` (see the output of Fig. 12.26). A `SINGLE_INTERVAL_SELECTION` list allows selecting a contiguous range of items. To do so, click the first item, then press and hold the *Shift* key while clicking the last item in the range. A `MULTIPLE_INTERVAL_SELECTION` list (the default) allows continuous range selection as described for a `SINGLE_INTERVAL_SELECTION` list. Such a list also allows miscellaneous items to be selected by pressing and holding the *Ctrl* key while clicking each item to select. To *deselect* an item, press and hold the *Ctrl* key while clicking the item a second time.

The application of Figs. 12.25–12.26 uses multiple-selection lists to copy items from one `JList` to another. One list is a `MULTIPLE_INTERVAL_SELECTION` list and the other is a `SINGLE_INTERVAL_SELECTION` list. When you execute the application, try using the selection techniques described previously to select items in both lists.

---

```

1 // Fig. 12.25: MultipleSelectionFrame.java
2 // JList that allows multiple selections.
3 import java.awt.FlowLayout;
4 import java.awt.event.ActionListener;
5 import java.awt.event.ActionEvent;
6 import javax.swing.JFrame;
7 import javax.swing.JList;
8 import javax.swing.JButton;
9 import javax.swing.JScrollPane;
10 import javax.swing.ListSelectionModel;
11
12 public class MultipleSelectionFrame extends JFrame
13 {
14 private final JList<String> colorJList; // list to hold color names
15 private final JList<String> copyJList; // list to hold copied names
16 private JButton copyJButton; // button to copy selected names
17 private static final String[] colorNames = {"Black", "Blue", "Cyan",
18 "Dark Gray", "Gray", "Green", "Light Gray", "Magenta", "Orange",
19 "Pink", "Red", "White", "Yellow"};
20
21 // MultipleSelectionFrame constructor
22 public MultipleSelectionFrame()
23 {
24 super("Multiple Selection Lists");
25 setLayout(new FlowLayout());
26
27 colorJList = new JList<String>(colorNames); // list of color names
28 colorJList.setVisibleRowCount(5); // show five rows

```

---

**Fig. 12.25** | `JList` that allows multiple selections. (Part 1 of 2.)

---

```

29 colorJList.setSelectionMode(
30 ListSelectionMode.MULTIPLE_INTERVAL_SELECTION);
31 add(new JScrollPane(colorJList)); // add list with scrollpane
32
33 copyJButton = new JButton("Copy >>>");
34 copyJButton.addActionListener(
35 new ActionListener() // anonymous inner class
36 {
37 // handle button event
38 @Override
39 public void actionPerformed(ActionEvent event)
40 {
41 // place selected values in copyJList
42 copyJList.setListData(
43 colorJList.getSelectedValuesList().toArray(
44 new String[0]));
45 }
46 }
47);
48
49 add(copyJButton); // add copy button to JFrame
50
51 copyJList = new JList<String>(); // list to hold copied color names
52 copyJList.setVisibleRowCount(5); // show 5 rows
53 copyJList.setFixedCellWidth(100); // set width
54 copyJList.setFixedCellHeight(15); // set height
55 copyJList.setSelectionMode(
56 ListSelectionMode.SINGLE_INTERVAL_SELECTION);
57 add(new JScrollPane(copyJList)); // add list with scrollpane
58 }
59 } // end class MultipleSelectionFrame

```

---

**Fig. 12.25** | JList that allows multiple selections. (Part 2 of 2.)

---

```


1 // Fig. 12.26: MultipleSelectionTest.java
2 // Testing MultipleSelectionFrame.
3 import javax.swing.JFrame;
4
5 public class MultipleSelectionTest
6 {
7 public static void main(String[] args)
8 {
9 MultipleSelectionFrame multipleSelectionFrame =
10 new MultipleSelectionFrame();
11 multipleSelectionFrame.setDefaultCloseOperation(
12 JFrame.EXIT_ON_CLOSE);
13 multipleSelectionFrame.setSize(350, 150);
14 multipleSelectionFrame.setVisible(true);
15 }
16 } // end class MultipleSelectionTest

```

---

**Fig. 12.26** | Testing MultipleSelectionFrame. (Part 1 of 2.)





**Fig. 12.26** | Testing MultipleSelectionFrame. (Part 2 of 2.)

Line 27 of Fig. 12.25 creates `JList colorJList` and initializes it with the `Strings` in the array `colorNames`. Line 28 sets the number of visible rows in `colorJList` to 5. Lines 29–30 specify that `colorJList` is a `MULTIPLE_INTERVAL_SELECTION` list. Line 31 adds a new `JScrollPane` containing `colorJList` to the `JFrame`. Lines 51–57 perform similar tasks for `copyJList`, which is declared as a `SINGLE_INTERVAL_SELECTION` list. If a `JList` does not contain items, it will not display in a `FlowLayout`. For this reason, lines 53–54 use `JList` methods `setFixedCellWidth` and `setFixedCellHeight` to set `copyJList`'s width to 100 pixels and the height of each item in the `JList` to 15 pixels, respectively.

Normally, an event generated by another GUI component (known as an **external event**) specifies when the multiple selections in a `JList` should be processed. In this example, the user clicks the `JButton` called `copyJButton` to trigger the event that copies the selected items in `colorJList` to `copyJList`.

Lines 34–47 declare, create and register an `ActionListener` for the `copyJButton`. When the user clicks `copyJButton`, method `actionPerformed` (lines 38–45) uses `JList` method `setListData` to set the items displayed in `copyJList`. Lines 43–44 call `colorJList`'s method `getSelectedValuesList`, which returns a `List<String>` (because the `JList` was created as a `JList<String>`) representing the selected items in `colorJList`. We call the `List<String>`'s `toArray` method to convert this into an array of `Strings` that can be passed as the argument to `copyJList`'s `setListData` method. `List` method `toArray` receives as its argument an array representing the type of array that the method will return. You'll learn more about `List` and `toArray` in Chapter 16.

You might be wondering why `copyJList` can be used in line 42 even though the application does not create the object to which it refers until line 49. Remember that method `actionPerformed` (lines 38–45) does not execute until the user presses the `copyJButton`, which cannot occur until after the constructor completes execution and the application displays the GUI. At that point in the application's execution, `copyJList` is already initialized with a new `JList` object.

## 12.14 Mouse Event Handling

This section presents the **MouseListener** and **MouseMotionListener** event-listener interfaces for handling **mouse events**. Mouse events can be processed for any GUI component that derives from `java.awt.Component`. The methods of interfaces `MouseListener` and `MouseMotionListener` are summarized in Figure 12.27. Package `javax.swing.event` contains interface **MouseInputListener**, which extends interfaces `MouseListener` and `MouseMotionListener` to create a single interface containing all the `MouseListener` and `MouseMotionListener` methods. The `MouseListener` and `MouseMotionListener` meth-

ods are called when the mouse interacts with a Component if appropriate event-listener objects are registered for that Component.

Each of the mouse event-handling methods receives as an argument a **MouseEvent** object that contains information about the mouse event that occurred, including the *x*- and *y*-coordinates of its location. These coordinates are measured from the *upper-left corner* of the GUI component on which the event occurred. The *x*-coordinates start at 0 and *increase from left to right*. The *y*-coordinates start at 0 and *increase from top to bottom*. The methods and constants of class **InputEvent** (MouseEvent's superclass) enable you to determine which mouse button the user clicked.

#### MouseListener and MouseMotionListener interface methods

##### *Methods of interface MouseListener*

`public void mousePressed(MouseEvent event)`

Called when a mouse button is *pressed* while the mouse cursor is on a component.

`public void mouseClicked(MouseEvent event)`

Called when a mouse button is *pressed and released* while the mouse cursor remains stationary on a component. Always preceded by a call to `mousePressed` and `mouseReleased`.

`public void mouseReleased(MouseEvent event)`

Called when a mouse button is *released after being pressed*. Always preceded by a call to `mousePressed` and one or more calls to `mouseDragged`.

`public void mouseEntered(MouseEvent event)`

Called when the mouse cursor *enters* the bounds of a component.

`public void mouseExited(MouseEvent event)`

Called when the mouse cursor *leaves* the bounds of a component.

##### *Methods of interface MouseMotionListener*

`public void mouseDragged(MouseEvent event)`

Called when the mouse button is *pressed* while the mouse cursor is on a component and the mouse is *moved* while the mouse button *remains pressed*. Always preceded by a call to `mousePressed`. All drag events are sent to the component on which the user began to drag the mouse.

`public void mouseMoved(MouseEvent event)`

Called when the mouse is *moved* (with no mouse buttons pressed) when the mouse cursor is on a component. All move events are sent to the component over which the mouse is currently positioned.

**Fig. 12.27** | MouseListener and MouseMotionListener interface methods.



#### Software Engineering Observation 12.5

*Calls to `mouseDragged` are sent to the `MouseMotionListener` for the Component on which the drag started. Similarly, the `mouseReleased` call at the end of a drag operation is sent to the `MouseListener` for the Component on which the drag operation started.*

Java also provides interface **MouseWheelListener** to enable applications to respond to the *rotation of a mouse wheel*. This interface declares method **mouseWheelMoved**, which receives a **MouseWheelEvent** as its argument. Class **MouseWheelEvent** (a subclass of **MouseEvent**) contains methods that enable the event handler to obtain information about the amount of wheel rotation.

### *Tracking Mouse Events on a JPanel*

The **MouseTracker** application (Figs. 12.28–12.29) demonstrates the **MouseListener** and **MouseMotionListener** interface methods. The event-handler class (lines 36–97 of Fig. 12.28) implements both interfaces. You *must* declare all seven methods from these two interfaces when your class implements them both. Each mouse event in this example displays a **String** in the **JLabel** called **statusBar** that is attached to the bottom of the window.

---

```

1 // Fig. 12.28: MouseTrackerFrame.java
2 // Mouse event handling.
3 import java.awt.Color;
4 import java.awt.BorderLayout;
5 import java.awt.event.MouseListener;
6 import java.awt.event.MouseMotionListener;
7 import java.awt.event.MouseEvent;
8 import javax.swing.JFrame;
9 import javax.swing.JLabel;
10 import javax.swing.JPanel;
11
12 public class MouseTrackerFrame extends JFrame
13 {
14 private final JPanel mousePanel; // panel in which mouse events occur
15 private final JLabel statusBar; // displays event information
16
17 // MouseTrackerFrame constructor sets up GUI and
18 // registers mouse event handlers
19 public MouseTrackerFrame()
20 {
21 super("Demonstrating Mouse Events");
22
23 mousePanel = new JPanel();
24 mousePanel.setBackground(Color.WHITE);
25 add(mousePanel, BorderLayout.CENTER); // add panel to JFrame
26
27 statusBar = new JLabel("Mouse outside JPanel");
28 add(statusBar, BorderLayout.SOUTH); // add label to JFrame
29
30 // create and register listener for mouse and mouse motion events
31 MouseHandler handler = new MouseHandler();
32 mousePanel.addMouseListener(handler);
33 mousePanel.addMouseMotionListener(handler);
34 }
35

```

---

**Fig. 12.28** | Mouse event handling. (Part I of 3.)

---

```

36 private class MouseHandler implements MouseListener,
37 MouseMotionListener
38 {
39 // MouseListener event handlers
40 // handle event when mouse released immediately after press
41 @Override
42 public void mouseClicked(MouseEvent event)
43 {
44 statusBar.setText(String.format("Clicked at [%d, %d]",
45 event.getX(), event.getY()));
46 }
47
48 // handle event when mouse pressed
49 @Override
50 public void mousePressed(MouseEvent event)
51 {
52 statusBar.setText(String.format("Pressed at [%d, %d]",
53 event.getX(), event.getY()));
54 }
55
56 // handle event when mouse released
57 @Override
58 public void mouseReleased(MouseEvent event)
59 {
60 statusBar.setText(String.format("Released at [%d, %d]",
61 event.getX(), event.getY()));
62 }
63
64 // handle event when mouse enters area
65 @Override
66 public void mouseEntered(MouseEvent event)
67 {
68 statusBar.setText(String.format("Mouse entered at [%d, %d]",
69 event.getX(), event.getY()));
70 mousePanel.setBackground(Color.GREEN);
71 }
72
73 // handle event when mouse exits area
74 @Override
75 public void mouseExited(MouseEvent event)
76 {
77 statusBar.setText("Mouse outside JPanel");
78 mousePanel.setBackground(Color.WHITE);
79 }
80
81 // MouseMotionListener event handlers
82 // handle event when user drags mouse with button pressed
83 @Override
84 public void mouseDragged(MouseEvent event)
85 {
86 statusBar.setText(String.format("Dragged at [%d, %d]",
87 event.getX(), event.getY()));
88 }

```

---

**Fig. 12.28** | Mouse event handling. (Part 2 of 3.)

```

89
90 // handle event when user moves mouse
91 @Override
92 public void mouseMoved(MouseEvent event)
93 {
94 statusBar.setText(String.format("Moved at [%d, %d]",
95 event.getX(), event.getY()));
96 }
97 } // end inner class MouseHandler
98 } // end class MouseTrackerFrame


```

**Fig. 12.28** | Mouse event handling. (Part 3 of 3.)

```

1 // Fig. 12.29: MouseTrackerFrame.java
2 // Testing MouseTrackerFrame.
3 import javax.swing.JFrame;
4
5 public class MouseTracker
6 {
7 public static void main(String[] args)
8 {
9 MouseTrackerFrame mouseTrackerFrame = new MouseTrackerFrame();
10 mouseTrackerFrame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
11 mouseTrackerFrame.setSize(300, 100);
12 mouseTrackerFrame.setVisible(true);
13 }
14 } // end class MouseTracker

```



**Fig. 12.29** | Testing MouseTrackerFrame.

Line 23 creates `JPanel` `mousePanel1`. This `JPanel`'s mouse events are tracked by the app. Line 24 sets `mousePanel1`'s background color to white. When the user moves the mouse into the `mousePanel1`, the application will change `mousePanel1`'s background color to green. When the user moves the mouse out of the `mousePanel1`, the application will change the background color back to white. Line 25 attaches `mousePanel1` to the `JFrame`. As you've learned, you typically must specify the layout of the GUI components in a `JFrame`. In that section, we intro-

duced the layout manager `FlowLayout`. Here we use the default layout of a `JFrame`'s content pane—**BorderLayout**, which arranges component **NORTH**, **SOUTH**, **EAST**, **WEST** and **CENTER** regions. **NORTH** corresponds to the container's top. This example uses the **CENTER** and **SOUTH** regions. Line 25 uses a two-argument version of method `add` to place `mousePanel` in the **CENTER** region. The `BorderLayout` automatically sizes the component in the **CENTER** to use all the space in the `JFrame` that is not occupied by components in the other regions. Section 12.18.2 discusses `BorderLayout` in more detail.

Lines 27–28 in the constructor declare `JLabel statusBar` and attach it to the `JFrame`'s **SOUTH** region. This `JLabel` occupies the width of the `JFrame`. The region's height is determined by the `JLabel`.

Line 31 creates an instance of inner class `MouseHandler` (lines 36–97) called `handler` that responds to mouse events. Lines 32–33 register `handler` as the listener for `mousePanel`'s mouse events. Methods `addMouseListener` and `addMouseMotionListener` are inherited indirectly from class `Component` and can be used to register `MouseListener`s and `MouseMotionListener`s, respectively. A `MouseHandler` object *is a* `MouseListener` and *is a* `MouseMotionListener` because the class implements *both* interfaces. We chose to implement both interfaces here to demonstrate a class that implements more than one interface, but we could have implemented interface `MouseListener` instead.

When the mouse enters and exits `mousePanel`'s area, methods `mouseEntered` (lines 65–71) and `mouseExited` (lines 74–79) are called, respectively. Method `mouseEntered` displays a message in the `statusBar` indicating that the mouse entered the `JPanel` and changes the background color to green. Method `mouseExited` displays a message in the `statusBar` indicating that the mouse is outside the `JPanel` (see the first sample output window) and changes the background color to white.

The other five events display a string in the `statusBar` that includes the event and the coordinates at which it occurred. `MouseEvent` methods `getX` and `getY` return the *x*- and *y*-coordinates, respectively, of the mouse at the time the event occurred.

## 12.15 Adapter Classes

Many event-listener interfaces, such as `MouseListener` and `MouseMotionListener`, contain multiple methods. It's not always desirable to declare every method in an event-listener interface. For instance, an application may need only the `mouseClicked` handler from `MouseListener` or the `mouseDragged` handler from `MouseMotionListener`. Interface `WindowListener` specifies seven window event-handling methods. For many of the listener interfaces that have multiple methods, packages `java.awt.event` and `javax.swing.event` provide event-listener adapter classes. An **adapter class** implements an interface and provides a default implementation (with an empty method body) of each method in the interface. Figure 12.30 shows several `java.awt.event` adapter classes and the interfaces they implement. You can extend an adapter class to inherit the default implementation of every method and subsequently override only the method(s) you need for event handling.



### Software Engineering Observation 12.6

*When a class implements an interface, the class has an is-a relationship with that interface. All direct and indirect subclasses of that class inherit this interface. Thus, an object of a class that extends an event-adapter class is an object of the corresponding event-listener type (e.g., an object of a subclass of `MouseAdapter` is a `MouseListener`).*

| Event-adapter class in <code>java.awt.event</code> | Implements interface             |
|----------------------------------------------------|----------------------------------|
| <code>ComponentAdapter</code>                      | <code>ComponentListener</code>   |
| <code>ContainerAdapter</code>                      | <code>ContainerListener</code>   |
| <code>FocusAdapter</code>                          | <code>FocusListener</code>       |
| <code>KeyAdapter</code>                            | <code>KeyListener</code>         |
| <code>MouseAdapter</code>                          | <code>MouseListener</code>       |
| <code>MouseMotionAdapter</code>                    | <code>MouseMotionListener</code> |
| <code>WindowAdapter</code>                         | <code>WindowListener</code>      |

**Fig. 12.30** | Event-adapter classes and the interfaces they implement.

### *Extending `MouseAdapter`*

The application of Figs. 12.31–12.32 demonstrates how to determine the number of mouse clicks (i.e., the click count) and how to distinguish between the different mouse buttons. The event listener in this application is an object of inner class `MouseClickedHandler` (Fig. 12.31, lines 25–46) that extends `MouseAdapter`, so we can declare just the `mouseClicked` method we need in this example.

```

1 // Fig. 12.31: MouseDetailsFrame.java
2 // Demonstrating mouse clicks and distinguishing between mouse buttons.
3 import java.awt.BorderLayout;
4 import java.awt.event.MouseAdapter;
5 import java.awt.event.MouseEvent;
6 import javax.swing.JFrame;
7 import javax.swing.JLabel;
8
9 public class MouseDetailsFrame extends JFrame
10 {
11 private String details; // String displayed in the statusBar
12 private final JLabel statusBar; // JLabel at bottom of window
13
14 // constructor sets title bar String and register mouse listener
15 public MouseDetailsFrame()
16 {
17 super("Mouse clicks and buttons");
18
19 statusBar = new JLabel("Click the mouse");
20 add(statusBar, BorderLayout.SOUTH);
21 addMouseListener(new MouseClickHandler()); // add handler
22 }
23
24 // inner class to handle mouse events
25 private class MouseClickHandler extends MouseAdapter
26 {
27 // handle mouse-click event and determine which button was pressed
28 @Override
29 public void mouseClicked(MouseEvent event)
30 {

```

**Fig. 12.31** | Demonstrating mouse clicks and distinguishing between mouse buttons. (Part I of 2.)

---

```

31 int xPos = event.getX(); // get x-position of mouse
32 int yPos = event.getY(); // get y-position of mouse
33
34 details = String.format("Clicked %d time(s)",
35 event.getClickCount());
36
37 if (event.isMetaDown()) // right mouse button
38 details += " with right mouse button";
39 else if (event.isAltDown()) // middle mouse button
40 details += " with center mouse button";
41 else // left mouse button
42 details += " with left mouse button";
43
44 statusBar.setText(details); // display message in statusBar
45 }
46 }
47 } // end class MouseDetailsFrame

```

---


**Fig. 12.31** | Demonstrating mouse clicks and distinguishing between mouse buttons. (Part 2 of 2.)

---

```

1 // Fig. 12.32: MouseDetails.java
2 // Testing MouseDetailsFrame.
3 import javax.swing.JFrame;
4
5 public class MouseDetails
6 {
7 public static void main(String[] args)
8 {
9 MouseDetailsFrame mouseDetailsFrame = new MouseDetailsFrame();
10 mouseDetailsFrame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
11 mouseDetailsFrame.setSize(400, 150);
12 mouseDetailsFrame.setVisible(true);
13 }
14 } // end class MouseDetails

```



**Fig. 12.32** | Testing MouseDetailsFrame.





### Common Programming Error 12.3

*If you extend an adapter class and misspell the name of the method you're overriding, and you do not declare the method with `@Override`, your method simply becomes another method in the class. This is a logic error that is difficult to detect, since the program will call the empty version of the method inherited from the adapter class.*

A user of a Java application may be on a system with a one-, two- or three-button mouse. Class `MouseEvent` inherits several methods from class `InputEvent` that can distinguish among mouse buttons on a multibutton mouse or can mimic a multibutton mouse with a combined keystroke and mouse-button click. Figure 12.33 shows the `InputEvent` methods used to distinguish among mouse-button clicks. Java assumes that every mouse contains a left mouse button. Thus, it's simple to test for a left-mouse-button click. However, users with a one- or two-button mouse must use a combination of keystrokes and mouse-button clicks at the same time to simulate the missing buttons on the mouse. In the case of a one- or two-button mouse, a Java application assumes that the center mouse button is clicked if the user holds down the *Alt* key and clicks the left mouse button on a two-button mouse or the only mouse button on a one-button mouse. In the case of a one-button mouse, a Java application assumes that the right mouse button is clicked if the user holds down the *Meta* key (sometimes called the *Command* key or the "Apple" key on a Mac) and clicks the mouse button.

| InputEvent method         | Description                                                                                                                                                                                                                                                         |
|---------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>isMetaDown()</code> | Returns true when the user clicks the <i>right mouse button</i> on a mouse with two or three buttons. To simulate a right-mouse-button click on a one-button mouse, the user can hold down the <i>Meta</i> key on the keyboard and click the mouse button.          |
| <code>isAltDown()</code>  | Returns true when the user clicks the <i>middle mouse button</i> on a mouse with three buttons. To simulate a middle-mouse-button click on a one- or two-button mouse, the user can press the <i>Alt</i> key and click the only or left mouse button, respectively. |

**Fig. 12.33** | `InputEvent` methods that help determine whether the right or center mouse button was clicked.

Line 21 of Fig. 12.31 registers a `MouseListener` for the `MouseDetailsFrame`. The event listener is an object of class `MouseClickedHandler`, which extends `MouseAdapter`. This enables us to declare only method `mouseClicked` (lines 28–45). This method first captures the coordinates where the event occurred and stores them in local variables `xPos` and `yPos` (lines 31–32). Lines 34–35 create a `String` called `details` containing the number of consecutive mouse clicks, which is returned by `MouseEvent` method `getClickCount` at line 35. Lines 37–42 use methods `isMetaDown` and `isAltDown` to determine which mouse button the user clicked and append an appropriate `String` to `details` in each case. The resulting `String` is displayed in the `statusBar`. Class `MouseDetails` (Fig. 12.32) contains the main method that executes the application. Try clicking with each of your mouse's buttons repeatedly to see the click count increment.

## 12.16 JPanel Subclass for Drawing with the Mouse

Section 12.14 showed how to track mouse events in a `JPanel`. In this section, we use a `JPanel` as a **dedicated drawing area** in which the user can draw by dragging the mouse. In addition, this section demonstrates an event listener that extends an adapter class.

### Method `paintComponent`

Lightweight Swing components that extend class `JComponent` (such as `JPanel`) contain method `paintComponent`, which is called when a lightweight Swing component is displayed. By overriding this method, you can specify how to draw shapes using Java's graphics capabilities. When customizing a `JPanel` for use as a dedicated drawing area, the subclass should override method `paintComponent` and call the superclass version of `paintComponent` as the first statement in the body of the overridden method to ensure that the component displays correctly. The reason is that subclasses of `JComponent` support **transparency**. To display a component correctly, the program must determine whether the component is transparent. The code that determines this is in superclass `JComponent`'s `paintComponent` implementation. When a component is transparent, `paintComponent` will not clear its background when the program displays the component. When a component is **opaque**, `paintComponent` clears the component's background before the component is displayed. The transparency of a Swing lightweight component can be set with method `setOpaque` (a `false` argument indicates that the component is transparent).



### Error-Prevention Tip 12.1

*In a `JComponent` subclass's `paintComponent` method, the first statement should always call the superclass's `paintComponent` method to ensure that an object of the subclass displays correctly.*



### Common Programming Error 12.4

*If an overridden `paintComponent` method does not call the superclass's version, the subclass component may not display properly. If an overridden `paintComponent` method calls the superclass's version after other drawing is performed, the drawing will be erased.*

### Defining the Custom Drawing Area

The Painter application of Figs. 12.34–12.35 demonstrates a customized subclass of `JPanel` that's used to create a dedicated drawing area. The application uses the `mouseDragged` event handler to create a simple drawing application. The user can draw pictures by dragging the mouse on the `JPanel`. This example does not use method `mouseMoved`, so our *event-listener class* (the *anonymous inner class* at lines 20–29 of Fig. 12.34) extends `MouseMotionAdapter`. Since this class already declares both `mouseMoved` and `mouseDragged`, we can simply override `mouseDragged` to provide the event handling this application requires.

---

```

1 // Fig. 12.34: PaintPanel.java
2 // Adapter class used to implement event handlers.
3 import java.awt.Point;
4 import java.awt.Graphics;
5 import java.awt.event.MouseEvent;
```

---

**Fig. 12.34** | Adapter class used to implement event handlers. (Part I of 2.)

---

```

6 import java.awt.event.MouseMotionAdapter;
7 import java.util.ArrayList;
8 import javax.swing.JPanel;
9
10 public class PaintPanel extends JPanel
11 {
12 // list of Point references
13 private final ArrayList<Point> points = new ArrayList<>();
14
15 // set up GUI and register mouse event handler
16 public PaintPanel()
17 {
18 // handle frame mouse motion event
19 addMouseListener(
20 new MouseMotionAdapter() // anonymous inner class
21 {
22 // store drag coordinates and repaint
23 @Override
24 public void mouseDragged(MouseEvent event)
25 {
26 points.add(event.getPoint());
27 repaint(); // repaint JFrame
28 }
29 }
30);
31 }
32
33 // draw ovals in a 4-by-4 bounding box at specified locations on window
34 @Override
35 public void paintComponent(Graphics g)
36 {
37 super.paintComponent(g); // clears drawing area
38
39 // draw all points
40 for (Point point : points)
41 g.fillOval(point.x, point.y, 4, 4);
42 }
43 } // end class PaintPanel

```

---

**Fig. 12.34** | Adapter class used to implement event handlers. (Part 2 of 2.)

Class `PaintPanel` (Fig. 12.34) extends `JPanel` to create the dedicated drawing area. Class `Point` (package `java.awt`) represents an  $x$ - $y$  coordinate. We use objects of this class to store the coordinates of each mouse drag event. Class `Graphics` is used to draw. In this example, we use an `ArrayList` of `Points` (line 13) to store the location at which each mouse drag event occurs. As you'll see, method `paintComponent` uses these `Points` to draw.

Lines 19–30 register a `MouseListener` to listen for the `PaintPanel`'s mouse motion events. Lines 20–29 create an object of an anonymous inner class that extends the adapter class `MouseMotionAdapter`. Recall that `MouseMotionAdapter` implements `MouseListener`, so the *anonymous inner class* object is a `MouseListener`. The anonymous inner class inherits default `mouseMoved` and `mouseDragged` implementations, so it already implements all the interface's methods. However, the default implementa-

tions do nothing when they're called. So, we override method `mouseDragged` at lines 23–28 to capture the coordinates of a mouse drag event and store them as a `Point` object. Line 26 invokes the `MouseEvent`'s `getPoint` method to obtain the `Point` where the event occurred and stores it in the `ArrayList`. Line 27 calls method `repaint` (inherited indirectly from class `Component`) to indicate that the `PaintPanel` should be refreshed on the screen as soon as possible with a call to the `PaintPanel`'s `paintComponent` method.

Method `paintComponent` (lines 34–42), which receives a `Graphics` parameter, is called automatically any time the `PaintPanel` needs to be displayed on the screen—such as when the GUI is first displayed—or refreshed on the screen—such as when method `repaint` is called or when the GUI component has been *hidden* by another window on the screen and subsequently becomes visible again.



### Look-and-Feel Observation 12.13

*Calling `repaint` for a Swing GUI component indicates that the component should be refreshed on the screen as soon as possible. The component's background is cleared only if the component is opaque. `JComponent` method `setOpaque` can be passed a boolean argument indicating whether the component is opaque (`true`) or transparent (`false`).*

Line 37 invokes the superclass version of `paintComponent` to clear the `PaintPanel`'s background (`JPanels` are opaque by default). Lines 40–41 draw an oval at the location specified by each `Point` in the `ArrayList`. `Graphics` method `fillOval` draws a solid oval. The method's four parameters represent a rectangular area (called the *bounding box*) in which the oval is displayed. The first two parameters are the upper-left *x*-coordinate and the upper-left *y*-coordinate of the rectangular area. The last two coordinates represent the rectangular area's width and height. Method `fillOval` draws the oval so it touches the middle of each side of the rectangular area. In line 41, the first two arguments are specified by using class `Point`'s two public instance variables—*x* and *y*. You'll learn more `Graphics` features in Chapter 13.



### Look-and-Feel Observation 12.14

*Drawing on any GUI component is performed with coordinates that are measured from the upper-left corner (0, 0) of that GUI component, not the upper-left corner of the screen.*

### Using the Custom `JPanel` in an Application

Class `Painter` (Fig. 12.35) contains the main method that executes this application. Line 14 creates a `PaintPanel` object on which the user can drag the mouse to draw. Line 15 attaches the `PaintPanel` to the `JFrame`.


```
1 // Fig. 12.35: Painter.java
2 // Testing PaintPanel.
3 import java.awt.BorderLayout;
4 import javax.swing.JFrame;
5 import javax.swing.JLabel;
6
7 public class Painter
8 {
```

**Fig. 12.35** | Testing `PaintPanel`. (Part I of 2.)

```

9 public static void main(String[] args)
10 {
11 // create JFrame
12 JFrame application = new JFrame("A simple paint program");
13
14 PaintPanel paintPanel = new PaintPanel();
15 application.add(paintPanel, BorderLayout.CENTER);
16
17 // create a label and place it in SOUTH of BorderLayout
18 application.add(new JLabel("Drag the mouse to draw"),
19 BorderLayout.SOUTH);
20
21 application.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
22 application.setSize(400, 200);
23 application.setVisible(true);
24 }
25 } // end class Painter

```



**Fig. 12.35** | Testing PaintPanel. (Part 2 of 2.)

## 12.17 Key Event Handling

This section presents the `KeyListener` interface for handling **key events**. Key events are generated when keys on the keyboard are pressed and released. A class that implements `KeyListener` must provide declarations for methods **keyPressed**, **keyReleased** and **keyTyped**, each of which receives a `KeyEvent` as its argument. Class `KeyEvent` is a subclass of `InputEvent`. Method `keyPressed` is called in response to pressing any key. Method `keyTyped` is called in response to pressing any key that is not an **action key**. (The action keys are any arrow key, *Home*, *End*, *Page Up*, *Page Down*, any function key, etc.) Method `keyReleased` is called when the key is released after any `keyPressed` or `keyTyped` event.

The application of Figs. 12.36–12.37 demonstrates the `KeyListener` methods. Class `KeyDemoFrame` implements the `KeyListener` interface, so all three methods are declared in the application. The constructor (Fig. 12.36, lines 17–28) registers the application to handle its own key events by using method **addKeyListener** at line 27. Method `addKeyListener` is declared in class `Component`, so every subclass of `Component` can notify `KeyListener` objects of key events for that `Component`.

```

1 // Fig. 12.36: KeyDemoFrame.java
2 // Key event handling.
3 import java.awt.Color;

```

**Fig. 12.36** | Key event handling. (Part 1 of 3.)

---

```

4 import java.awt.event.KeyListener;
5 import java.awt.event.KeyEvent;
6 import javax.swing.JFrame;
7 import javax.swing.JTextArea;
8
9 public class KeyDemoFrame extends JFrame implements KeyListener
10 {
11 private final String line1 = ""; // first line of text area
12 private final String line2 = ""; // second line of text area
13 private final String line3 = ""; // third line of text area
14 private final JTextArea textArea; // text area to display output
15
16 // KeyDemoFrame constructor
17 public KeyDemoFrame()
18 {
19 super("Demonstrating Keystroke Events");
20
21 textArea = new JTextArea(10, 15); // set up JTextArea
22 textArea.setText("Press any key on the keyboard...");
23 textArea.setEnabled(false);
24 textArea.setDisabledTextColor(Color.BLACK);
25 add(textArea); // add text area to JFrame
26
27 addKeyListener(this); // allow frame to process key events
28 }
29
30 // handle press of any key
31 @Override
32 public void keyPressed(KeyEvent event)
33 {
34 line1 = String.format("Key pressed: %s",
35 KeyEvent.getKeyText(event.getKeyCode())); // show pressed key
36 setLines2and3(event); // set output lines two and three
37 }
38
39 // handle release of any key
40 @Override
41 public void keyReleased(KeyEvent event)
42 {
43 line1 = String.format("Key released: %s",
44 KeyEvent.getKeyText(event.getKeyCode())); // show released key
45 setLines2and3(event); // set output lines two and three
46 }
47
48 // handle press of an action key
49 @Override
50 public void keyTyped(KeyEvent event)
51 {
52 line1 = String.format("Key typed: %s", event.getKeyChar());
53 setLines2and3(event); // set output lines two and three
54 }
55

```

---

**Fig. 12.36** | Key event handling. (Part 2 of 3.)

---

```

56 // set second and third lines of output
57 private void setLines2and3(KeyEvent event)
58 {
59 line2 = String.format("This key is %san action key",
60 (event.isActionKey() ? "" : "not "));
61
62 String temp = KeyEvent.getKeyModifiersText(event.getModifiers());
63
64 line3 = String.format("Modifier keys pressed: %s",
65 (temp.equals("") ? "none" : temp)); // output modifiers
66
67 textArea.setText(String.format("%s\n%s\n%s\n",
68 line1, line2, line3)); // output three lines of text
69 }
70 } // end class KeyDemoFrame

```

---

**Fig. 12.36** | Key event handling. (Part 3 of 3.)

---

```


1 // Fig. 12.37: KeyDemo.java
2 // Testing KeyDemoFrame.
3 import javax.swing.JFrame;
4
5 public class KeyDemo
6 {
7 public static void main(String[] args)
8 {
9 KeyDemoFrame keyDemoFrame = new KeyDemoFrame();
10 keyDemoFrame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
11 keyDemoFrame.setSize(350, 100);
12 keyDemoFrame.setVisible(true);
13 }
14 } // end class KeyDemo

```



**Fig. 12.37** | Testing KeyDemoFrame. (Part 1 of 2.)

---



**Fig. 12.37** | Testing KeyDemoFrame. (Part 2 of 2.)

At line 25, the constructor adds the `JTextArea` `textArea` (where the application's output is displayed) to the `JFrame`. A `JTextArea` is a *multiline area* in which you can display text. (We discuss `JTextAreas` in more detail in Section 12.20.) Notice in the screen captures that `textArea` occupies the *entire window*. This is due to the `JFrame`'s default `BorderLayout` (discussed in Section 12.18.2 and demonstrated in Fig. 12.41). When a single `Component` is added to a `BorderLayout`, the `Component` occupies the *entire* `Container`. Line 23 disables the `JTextArea` so the user cannot type in it. This causes the text in the `JTextArea` to become gray. Line 24 uses method `setDisabledTextColor` to change the text color in the `JTextArea` to black for readability.

Methods `keyPressed` (lines 31–37) and `keyReleased` (lines 40–46) use `KeyEvent` method `getKeyCode` to get the **virtual key code** of the pressed key. Class `KeyEvent` contains virtual key-code constants that represent every key on the keyboard. These constants can be compared with `getKeyCode`'s return value to test for individual keys on the keyboard. The value returned by `getKeyCode` is passed to static `KeyEvent` method `getKeyText`, which returns a string containing the name of the key that was pressed. For a complete list of virtual key constants, see the online documentation for class `KeyEvent` (package `java.awt.event`). Method `keyTyped` (lines 49–54) uses `KeyEvent` method `getKeyChar` (which returns a `char`) to get the Unicode value of the character typed.

All three event-handling methods finish by calling method `setLines2and3` (lines 57–69) and passing it the `KeyEvent` object. This method uses `KeyEvent` method `isActionKey` (line 60) to determine whether the key in the event was an action key. Also, `InputEvent` method `getModifiers` is called (line 62) to determine whether any modifier keys (such as *Shift*, *Alt* and *Ctrl*) were pressed when the key event occurred. The result of this method is passed to static `KeyEvent` method `getKeyModifiersText`, which produces a `String` containing the names of the pressed modifier keys.

[*Note:* If you need to test for a specific key on the keyboard, class `KeyEvent` provides a **key constant** for each one. These constants can be used from the key event handlers to determine whether a particular key was pressed. Also, to determine whether the *Alt*, *Ctrl*, *Meta* and *Shift* keys are pressed individually, `InputEvent` methods `isAltDown`, `isControlDown`, `isMetaDown` and `isShiftDown` each return a `boolean` indicating whether the particular key was pressed during the key event.]

## 12.18 Introduction to Layout Managers

**Layout managers** *arrange* GUI components in a container for presentation purposes. You can use the layout managers for basic layout capabilities instead of determining every GUI component's exact position and size. This functionality enables you to concentrate on the basic look-and-feel and lets the layout managers process most of the layout details. All layout managers implement the interface **LayoutManager** (in package `java.awt`). Class `Con-`



tainer's `setLayout` method takes an object that implements the `LayoutManager` interface as an argument. There are basically three ways for you to arrange components in a GUI:

1. *Absolute positioning:* This provides the greatest level of control over a GUI's appearance. By setting a `Container`'s layout to `null`, you can specify the *absolute position of each GUI component* with respect to the upper-left corner of the `Container` by using `Component` methods `setSize` and `setLocation` or `setBounds`. If you do this, you also must specify each GUI component's size. Programming a GUI with absolute positioning can be tedious, unless you have an integrated development environment (IDE) that can generate the code for you.
2. *Layout managers:* Using layout managers to position elements can be simpler and faster than creating a GUI with absolute positioning, and makes your GUIs more resizable, but you lose some control over the size and the precise positioning of each component.
3. *Visual programming in an IDE:* IDEs provide tools that make it easy to create GUIs. Each IDE typically provides a **GUI design tool** that allows you to drag and drop GUI components from a tool box onto a design area. You can then position, size and align GUI components as you like. The IDE generates the Java code that creates the GUI. In addition, you can typically add event-handling code for a particular component by double-clicking the component. Some design tools also allow you to use the layout managers described in this chapter and in Chapter 22.



#### Look-and-Feel Observation 12.15

*Most Java IDEs provide GUI design tools for visually designing a GUI; the tools then write Java code that creates the GUI. Such tools often provide greater control over the size, position and alignment of GUI components than do the built-in layout managers.*



#### Look-and-Feel Observation 12.16

*It's possible to set a `Container`'s layout to `null`, which indicates that no layout manager should be used. In a `Container` without a layout manager, you must position and size the components and take care that, on resize events, all components are repositioned as necessary. A component's resize events can be processed by a `ComponentListener`.*

Figure 12.38 summarizes the layout managers presented in this chapter. A couple of additional layout managers are discussed in Chapter 22.

| Layout manager            | Description                                                                                                                                                                                                                                                                                                                                 |
|---------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>FlowLayout</code>   | Default for <code>javax.swing.JPanel</code> . Places components <i>sequentially, left to right</i> , in the order they were added. It's also possible to specify the order of the components by using the <code>Container</code> method <code>add</code> , which takes a <code>Component</code> and an integer index position as arguments. |
| <code>BorderLayout</code> | Default for <code>JFrames</code> (and other windows). Arranges the components into five areas: NORTH, SOUTH, EAST, WEST and CENTER.                                                                                                                                                                                                         |
| <code>GridLayout</code>   | Arranges the components into rows and columns.                                                                                                                                                                                                                                                                                              |

**Fig. 12.38** | Layout managers.

### 12.18.1 FlowLayout

FlowLayout is the *simplest* layout manager. GUI components are placed in a container from left to right in the order in which they're added to the container. When the edge of the container is reached, components continue to display on the next line. Class `FlowLayout` allows GUI components to be *left aligned*, *centered* (the default) and *right aligned*.

The application of Figs. 12.39–12.40 creates three `JButton` objects and adds them to the application, using a `FlowLayout`. The components are center aligned by default. When the user clicks **Left**, the `FlowLayout`'s alignment is changed to left aligned. When the user clicks **Right**, the `FlowLayout`'s alignment is changed to right aligned. When the user clicks **Center**, the `FlowLayout`'s alignment is changed to center aligned. The sample output windows show each alignment. The last sample output shows the centered alignment after the window has been resized to a smaller width so that the button **Right** flows onto a new line.

As seen previously, a container's layout is set with method `setLayout` of class `Container`. Line 25 (Fig. 12.39) sets the layout manager to the `FlowLayout` declared at line 23. Normally, the layout is set before any GUI components are added to a container.



#### Look-and-Feel Observation 12.17

*Each individual container can have only one layout manager, but multiple containers in the same application can each use different layout managers.*

```

1 // Fig. 12.39: FlowLayoutFrame.java
2 // FlowLayout allows components to flow over multiple lines.
3 import java.awt.FlowLayout;
4 import java.awt.Container;
5 import java.awt.event.ActionListener;
6 import java.awt.event.ActionEvent;
7 import javax.swing.JFrame;
8 import javax.swing.JButton;
9
10 public class FlowLayoutFrame extends JFrame
11 {
12 private final JButton leftJButton; // button to set alignment left
13 private final JButton centerJButton; // button to set alignment center
14 private final JButton rightJButton; // button to set alignment right
15 private final FlowLayout layout; // layout object
16 private final Container container; // container to set layout
17
18 // set up GUI and register button listeners
19 public FlowLayoutFrame()
20 {
21 super("FlowLayout Demo");
22
23 layout = new FlowLayout();
24 container = getContentPane(); // get container to layout
25 setLayout(layout);
26
27 // set up leftJButton and register listener
28 leftJButton = new JButton("Left");
29 add(leftJButton); // add Left button to frame

```

**Fig. 12.39** | FlowLayout allows components to flow over multiple lines. (Part I of 2.)


```
30 leftJButton.addActionListener(
31 new ActionListener() // anonymous inner class
32 {
33 // process leftJButton event
34 @Override
35 public void actionPerformed(ActionEvent event)
36 {
37 layout.setAlignment(FlowLayout.LEFT);
38
39 // realign attached components
40 layout.layoutContainer(container);
41 }
42 }
43);
44
45 // set up centerJButton and register listener
46 centerJButton = new JButton("Center");
47 add(centerJButton); // add Center button to frame
48 centerJButton.addActionListener(
49 new ActionListener() // anonymous inner class
50 {
51 // process centerJButton event
52 @Override
53 public void actionPerformed(ActionEvent event)
54 {
55 layout.setAlignment(FlowLayout.CENTER);
56
57 // realign attached components
58 layout.layoutContainer(container);
59 }
60 }
61);
62
63 // set up rightJButton and register listener
64 rightJButton = new JButton("Right");
65 add(rightJButton); // add Right button to frame
66 rightJButton.addActionListener(
67 new ActionListener() // anonymous inner class
68 {
69 // process rightJButton event
70 @Override
71 public void actionPerformed(ActionEvent event)
72 {
73 layout.setAlignment(FlowLayout.RIGHT);
74
75 // realign attached components
76 layout.layoutContainer(container);
77 }
78 }
79);
80 } // end FlowLayoutFrame constructor
81 } // end class FlowLayoutFrame
```

**Fig. 12.39** | FlowLayout allows components to flow over multiple lines. (Part 2 of 2.)

```

1 // Fig. 12.40: FlowLayoutDemo.java
2 // Testing FlowLayoutFrame.
3 import javax.swing.JFrame;
4
5 public class FlowLayoutDemo
6 {
7 public static void main(String[] args)
8 {
9 FlowLayoutFrame flowLayoutFrame = new FlowLayoutFrame();
10 flowLayoutFrame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
11 flowLayoutFrame.setSize(300, 75);
12 flowLayoutFrame.setVisible(true);
13 }
14 } // end class FlowLayoutDemo

```



**Fig. 12.40** | Testing FlowLayoutFrame.

Each button's event handler is specified with a separate anonymous inner-class object (lines 30–43, 48–61 and 66–79, respectively), and method `actionPerformed` in each case executes two statements. For example, line 37 in the event handler for `leftJButton` uses `FlowLayout` method **`setAlignment`** to change the alignment for the `FlowLayout` to a left-aligned (**`FlowLayout.LEFT`**) `FlowLayout`. Line 40 uses `LayoutManager` interface method **`layoutContainer`** (which is inherited by all layout managers) to specify that the `JFrame` should be rearranged based on the adjusted layout. According to which button was clicked, the `actionPerformed` method for each button sets the `FlowLayout`'s alignment to `FlowLayout.LEFT` (line 37), **`FlowLayout.CENTER`** (line 55) or **`FlowLayout.RIGHT`** (line 73).

### 12.18.2 BorderLayout

The `BorderLayout` layout manager (the default layout manager for a `JFrame`) arranges components into five regions: NORTH, SOUTH, EAST, WEST and CENTER. NORTH corresponds to the top of the container. Class `BorderLayout` extends `Object` and implements interface **`LayoutManager2`** (a subinterface of `LayoutManager` that adds several methods for enhanced layout processing).

A `BorderLayout` limits a `Container` to containing *at most five components*—one in each region. The component placed in each region can be a container to which other components are attached. The components placed in the NORTH and SOUTH regions extend hor-

izontally to the sides of the container and are as tall as the components placed in those regions. The EAST and WEST regions expand vertically between the NORTH and SOUTH regions and are as wide as the components placed in those regions. The component placed in the CENTER region *expands to fill all remaining space in the layout* (which is the reason the JTextArea in Fig. 12.37 occupies the entire window). If all five regions are occupied, the entire container's space is covered by GUI components. If the NORTH or SOUTH region is not occupied, the GUI components in the EAST, CENTER and WEST regions expand vertically to fill the remaining space. If the EAST or WEST region is not occupied, the GUI component in the CENTER region *expands horizontally to fill the remaining space*. If the CENTER region is *not* occupied, the area is left *empty*—the other GUI components do *not* expand to fill the remaining space. The application of Figs. 12.41–12.42 demonstrates the BorderLayout layout manager by using five JButtons.

---

```

1 // Fig. 12.41: BorderLayoutFrame.java
2 // BorderLayout containing five buttons.
3 import java.awt.BorderLayout;
4 import java.awt.event.ActionListener;
5 import java.awt.event.ActionEvent;
6 import javax.swing.JFrame;
7 import javax.swing.JButton;
8
9 public class BorderLayoutFrame extends JFrame implements ActionListener
10 {
11 private final JButton[] buttons; // array of buttons to hide portions
12 private static final String[] names = {"Hide North", "Hide South",
13 "Hide East", "Hide West", "Hide Center"};
14 private final BorderLayout layout;
15
16 // set up GUI and event handling
17 public BorderLayoutFrame()
18 {
19 super("BorderLayout Demo");
20
21 layout = new BorderLayout(5, 5); // 5 pixel gaps
22 setLayout(layout);
23 buttons = new JButton[names.length];
24
25 // create JButtons and register listeners for them
26 for (int count = 0; count < names.length; count++)
27 {
28 buttons[count] = new JButton(names[count]);
29 buttons[count].addActionListener(this);
30 }
31
32 add(buttons[0], BorderLayout.NORTH);
33 add(buttons[1], BorderLayout.SOUTH);
34 add(buttons[2], BorderLayout.EAST);
35 add(buttons[3], BorderLayout.WEST);
36 add(buttons[4], BorderLayout.CENTER);
37 }

```

---

**Fig. 12.41** | BorderLayout containing five buttons. (Part I of 2.)

```

38
39 // handle button events
40 @Override
41 public void actionPerformed(ActionEvent event)
42 {
43 // check event source and lay out content pane correspondingly
44 for (JButton button : buttons)
45 {
46 if (event.getSource() == button)
47 button.setVisible(false); // hide the button that was clicked
48 else
49 button.setVisible(true); // show other buttons
50 }
51
52 layout.layoutContainer(getContentPane()); // lay out content pane
53 }
54 } // end class BorderLayoutFrame

```

**Fig. 12.41** | BorderLayout containing five buttons. (Part 2 of 2.)

Line 21 of Fig. 12.41 creates a `BorderLayout`. The constructor arguments specify the number of pixels between components that are arranged horizontally (**horizontal gap space**) and between components that are arranged vertically (**vertical gap space**), respectively. The default is one pixel of gap space horizontally and vertically. Line 22 uses method `setLayout` to set the content pane's layout to `layout`.

We add Components to a `BorderLayout` with another version of `Container` method `add` that takes two arguments—the Component to add and the region in which the Component should appear. For example, line 32 specifies that `buttons[0]` should appear in the `NORTH` region. The components can be added in *any* order, but only *one* component should be added to each region.



#### Look-and-Feel Observation 12.18

*If no region is specified when adding a Component to a `BorderLayout`, the layout manager assumes that the Component should be added to region `BorderLayout.CENTER`.*



#### Common Programming Error 12.5

*When more than one component is added to a region in a `BorderLayout`, only the last component added to that region will be displayed. There's no error that indicates this problem.*

Class `BorderLayoutFrame` implements `ActionListener` directly in this example, so the `BorderLayoutFrame` will handle the events of the `JButtons`. For this reason, line 29 passes the `this` reference to the `addActionListener` method of each `JButton`. When the user clicks a particular `JButton` in the layout, method `actionPerformed` (lines 40–53) executes. The enhanced `for` statement at lines 44–50 uses an `if...else` to hide the particular `JButton` that generated the event. Method `setVisible` (inherited into `JButton` from class `Component`) is called with a `false` argument (line 47) to hide the `JButton`. If the current `JButton` in the array is not the one that generated the event, method `setVisible` is called with a `true` argument (line 49) to ensure that the `JButton` is displayed on the screen. Line 52 uses `Layout-`

Manager method `layoutContainer` to recalculate the layout of the content pane. Notice in the screen captures of Fig. 12.42 that certain regions in the `BorderLayout` change shape as `JButtons` are *hidden* and displayed in other regions. Try resizing the application window to see how the various regions resize based on the window's width and height. *For more complex layouts, group components in `JPanels`, each with a separate layout manager.* Place the `JPanels` on the `JFrame` using either the default `BorderLayout` or some other layout.


---

```

1 // Fig. 12.42: BorderLayoutDemo.java
2 // Testing BorderLayoutFrame.
3 import javax.swing.JFrame;
4
5 public class BorderLayoutDemo
6 {
7 public static void main(String[] args)
8 {
9 BorderLayoutFrame borderLayoutFrame = new BorderLayoutFrame();
10 borderLayoutFrame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
11 borderLayoutFrame.setSize(300, 200);
12 borderLayoutFrame.setVisible(true);
13 }
14 } // end class BorderLayoutDemo

```

---




---

**Fig. 12.42** | Testing `BorderLayoutFrame`.

### 12.18.3 GridLayout

The **GridLayout** layout manager divides the container into a *grid* so that components can be placed in *rows* and *columns*. Class **GridLayout** inherits directly from class **Object** and implements interface **LayoutManager**. Every **Component** in a **GridLayout** has the *same* width and height. Components are added to a **GridLayout** starting at the top-left cell of the grid and proceeding left to right until the row is full. Then the process continues left to right on the next row of the grid, and so on. The application of Figs. 12.43–12.44 demonstrates the **GridLayout** layout manager by using six **JButtons**.

---

```

1 // Fig. 12.43: GridLayoutFrame.java
2 // GridLayout containing six buttons.
3 import java.awt.GridLayout;
4 import java.awt.Container;
5 import java.awt.event.ActionListener;
6 import java.awt.event.ActionEvent;
7 import javax.swing.JFrame;
8 import javax.swing.JButton;
9
10 public class GridLayoutFrame extends JFrame implements ActionListener
11 {
12 private final JButton[] buttons; // array of buttons
13 private static final String[] names =
14 { "one", "two", "three", "four", "five", "six" };
15 private boolean toggle = true; // toggle between two layouts
16 private final Container container; // frame container
17 private final GridLayout gridLayout1; // first gridlayout
18 private final GridLayout gridLayout2; // second gridlayout
19
20 // no-argument constructor
21 public GridLayoutFrame()
22 {
23 super("GridLayout Demo");
24 gridLayout1 = new GridLayout(2, 3, 5, 5); // 2 by 3; gaps of 5
25 gridLayout2 = new GridLayout(3, 2); // 3 by 2; no gaps
26 container = getContentPane();
27 setLayout(gridLayout1);
28 buttons = new JButton[names.length];
29
30 for (int count = 0; count < names.length; count++)
31 {
32 buttons[count] = new JButton(names[count]);
33 buttons[count].addActionListener(this); // register listener
34 add(buttons[count]); // add button to JFrame
35 }
36 }
37
38 // handle button events by toggling between layouts
39 @Override
40 public void actionPerformed(ActionEvent event)
41 {

```

---

**Fig. 12.43** | GridLayout containing six buttons. (Part I of 2.)



---

```

42 if (toggle) // set layout based on toggle
43 container.setLayout(gridLayout2);
44 else
45 container.setLayout(gridLayout1);
46
47 toggle = !toggle;
48 container.validate(); // re-lay out container
49 }
50 } // end class GridLayoutFrame

```

---

**Fig. 12.43** | GridLayout containing six buttons. (Part 2 of 2.)

---

```

1 // Fig. 12.44: GridLayoutDemo.java
2 // Testing GridLayoutFrame.
3 import javax.swing.JFrame;
4
5 public class GridLayoutDemo
6 {
7 public static void main(String[] args)
8 {
9 GridLayoutFrame gridLayoutFrame = new GridLayoutFrame();
10 gridLayoutFrame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
11 gridLayoutFrame.setSize(300, 200);
12 gridLayoutFrame.setVisible(true);
13 }
14 } // end class GridLayoutDemo

```

---



**Fig. 12.44** | Testing GridLayoutFrame.

---

Lines 24–25 (Fig. 12.43) create two `GridLayout` objects. The `GridLayout` constructor used at line 24 specifies a `GridLayout` with 2 rows, 3 columns, 5 pixels of horizontal-gap space between Components in the grid and 5 pixels of vertical-gap space between Components in the grid. The `GridLayout` constructor used at line 25 specifies a `GridLayout` with 3 rows and 2 columns that uses the default gap space (1 pixel).

The `JButton` objects in this example initially are arranged using `gridLayout1` (set for the content pane at line 27 with method `setLayout`). The first component is added to the first column of the first row. The next component is added to the second column of the first row, and so on. When a `JButton` is pressed, method `actionPerformed` (lines 39–49) is called. Every call to `actionPerformed` toggles the layout between `gridLayout2` and `gridLayout1`, using boolean variable `toggle` to determine the next layout to set.

Line 48 shows another way to reformat a container for which the layout has changed. Container method **`validate`** recomputes the container's layout based on the current layout manager for the Container and the current set of displayed GUI components.

## 12.19 Using Panels to Manage More Complex Layouts

Complex GUIs (like Fig. 12.1) often require that each component be placed in an exact location. They often consist of multiple panels, with each panel's components arranged in a specific layout. Class `JPanel` extends `JComponent` and `JComponent` extends class `Container`, so every `JPanel` is a `Container`. Thus, every `JPanel` may have components, including other panels, attached to it with `Container` method `add`. The application of Figs. 12.45–12.46 demonstrates how a `JPanel` can be used to create a more complex layout in which several `JButtons` are placed in the `SOUTH` region of a `BorderLayout`.

---

```

1 // Fig. 12.45: PanelFrame.java
2 // Using a JPanel to help lay out components.
3 import java.awt.GridLayout;
4 import java.awt.BorderLayout;
5 import javax.swing.JFrame;
6 import javax.swing.JPanel;
7 import javax.swing.JButton;
8
9 public class PanelFrame extends JFrame
10 {
11 private final JPanel buttonJPanel; // panel to hold buttons
12 private final JButton[] buttons;
13
14 // no-argument constructor
15 public PanelFrame()
16 {
17 super("Panel Demo");
18 buttons = new JButton[5];
19 buttonJPanel = new JPanel();
20 buttonJPanel.setLayout(new GridLayout(1, buttons.length));
21
22 // create and add buttons
23 for (int count = 0; count < buttons.length; count++)
24 {
25 buttons[count] = new JButton("Button " + (count + 1));
26 buttonJPanel.add(buttons[count]); // add button to panel
27 }
28
29 add(buttonJPanel, BorderLayout.SOUTH); // add panel to JFrame
30 }
31 } // end class PanelFrame

```

---

**Fig. 12.45** | `JPanel` with five `JButtons` in a `GridLayout` attached to the `SOUTH` region of a `BorderLayout`.

---

```

1 // Fig. 12.46: PanelDemo.java
2 // Testing PanelFrame.
3 import javax.swing.JFrame;
4

```

---

**Fig. 12.46** | Testing `PanelFrame`. (Part I of 2.)

---

```

5 public class PanelDemo extends JFrame
6 {
7 public static void main(String[] args)
8 {
9 PanelFrame panelFrame = new PanelFrame();
10 panelFrame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
11 panelFrame.setSize(450, 200);
12 panelFrame.setVisible(true);
13 }
14 } // end class PanelDemo

```

---




---

**Fig. 12.46** | Testing `PanelFrame`. (Part 2 of 2.)

After `JPanel buttonJPanel` is declared (line 11 of Fig. 12.45) and created (line 19), line 20 sets `buttonJPanel`'s layout to a `GridLayout` of one row and five columns (there are five `JButtons` in array `buttons`). Lines 23–27 add the `JButtons` in the array to the `JPanel`. Line 26 adds the buttons directly to the `JPanel`—class `JPanel` does not have a content pane, unlike a `JFrame`. Line 29 uses the `JFrame`'s default `BorderLayout` to add `buttonJPanel` to the `SOUTH` region. The `SOUTH` region is as tall as the buttons on `buttonJPanel`. A `JPanel` is sized to the components it contains. As more components are added, the `JPanel` *grows* (according to the restrictions of its layout manager) to accommodate the components. Resize the window to see how the layout manager affects the size of the `JButtons`.

## 12.20 JTextArea

A **JTextArea** provides an area for *manipulating multiple lines of text*. Like class `JTextField`, `JTextArea` is a subclass of `JTextComponent`, which declares common methods for `JTextFields`, `JTextAreas` and several other text-based GUI components.

The application in Figs. 12.47–12.48 demonstrates `JTextAreas`. One `JTextArea` displays text that the user can select. The other is uneditable by the user and is used to display the text the user selected in the first `JTextArea`. Unlike `JTextFields`, `JTextAreas` do not have action events—when you press *Enter* while typing in a `JTextArea`, the cursor simply moves to the next line. As with multiple-selection `JLists` (Section 12.13), an external event from another GUI component indicates when to process the text in a `JTextArea`. For example, when typing an e-mail message, you normally click a **Send** button to send the text of the message to the recipient. Similarly, when editing a document in a word processor, you normally save the file by selecting a **Save** or **Save As...** menu item. In this program, the button **Copy >>>** generates the external event that copies the selected text in the left `JTextArea` and displays it in the right `JTextArea`.

---

```

1 // Fig. 12.47: TextAreaFrame.java
2 // Copying selected text from one JText area to another.
3 import java.awt.event.ActionListener;
4 import java.awt.event.ActionEvent;
5 import javax.swing.Box;
6 import javax.swing.JFrame;
7 import javax.swing.JTextArea;
8 import javax.swing.JButton;
9 import javax.swing.JScrollPane;
10
11 public class TextAreaFrame extends JFrame
12 {
13 private final JTextArea textArea1; // displays demo string
14 private final JTextArea textArea2; // highlighted text is copied here
15 private final JButton copyJButton; // initiates copying of text
16
17 // no-argument constructor
18 public TextAreaFrame()
19 {
20 super("TextArea Demo");
21 Box box = Box.createHorizontalBox(); // create box
22 String demo = "This is a demo string to\n" +
23 "illustrate copying text\nfrom one textarea to \n" +
24 "another textarea using an\nexternal event\n";
25
26 textArea1 = new JTextArea(demo, 10, 15);
27 box.add(new JScrollPane(textArea1)); // add scrollpane
28
29 copyJButton = new JButton("Copy >>>"); // create copy button
30 box.add(copyJButton); // add copy button to box
31 copyJButton.addActionListener(
32 new ActionListener() // anonymous inner class
33 {
34 // set text in textArea2 to selected text from textArea1
35 @Override
36 public void actionPerformed(ActionEvent event)
37 {
38 textArea2.setText(textArea1.getSelectedText());
39 }
40 }
41);
42
43 textArea2 = new JTextArea(10, 15);
44 textArea2.setEditable(false);
45 box.add(new JScrollPane(textArea2)); // add scrollpane
46
47 add(box); // add box to frame
48 }
49 } // end class TextAreaFrame

```

---


**Fig. 12.47** | Copying selected text from one JTextArea to another.

In the constructor (lines 18–48), line 21 creates a **Box** container (package `javax.swing`) to organize the GUI components. **Box** is a subclass of **Container** that uses

```

1 // Fig. 12.48: TextAreaDemo.java
2 // Testing TextAreaFrame.
3 import javax.swing.JFrame;
4
5 public class TextAreaDemo
6 {
7 public static void main(String[] args)
8 {
9 TextAreaFrame textAreaFrame = new TextAreaFrame();
10 textAreaFrame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
11 textAreaFrame.setSize(425, 200);
12 textAreaFrame.setVisible(true);
13 }
14 } // end class TextAreaDemo

```



**Fig. 12.48** | Testing `TextAreaFrame`.

a **BoxLayout** layout manager (discussed in detail in Section 22.9) to arrange the GUI components either horizontally or vertically. Box's static method **createHorizontalBox** creates a Box that arranges components from left to right in the order that they're attached.

Lines 26 and 43 create `JTextAreas` `textArea1` and `textArea2`. Line 26 uses `JTextArea`'s three-argument constructor, which takes a `String` representing the initial text and two `ints` specifying that the `JTextArea` has 10 rows and 15 columns. Line 43 uses `JTextArea`'s two-argument constructor, specifying that the `JTextArea` has 10 rows and 15 columns. Line 26 specifies that `demo` should be displayed as the default `JTextArea` content. A `JTextArea` does not provide scrollbars if it cannot display its complete contents. So, line 27 creates a `JScrollPane` object, initializes it with `textArea1` and attaches it to container box. By default, horizontal and vertical scrollbars appear as necessary in a `JScrollPane`.

Lines 29–41 create  `JButton` object `copyJButton` with the label "Copy >>>", add `copyJButton` to container box and register the event handler for `copyJButton`'s `ActionEvent`. This button provides the external event that determines when the program should copy the selected text in `textArea1` to `textArea2`. When the user clicks `copyJButton`, line 38 in `actionPerformed` indicates that method **getSelectedText** (inherited into `JTextArea` from `JTextComponent`) should return the selected text from `textArea1`. The user selects text by dragging the mouse over the desired text to highlight it. Method `setText` changes the text in `textArea2` to the string returned by `getSelectedText`.

Lines 43–45 create `textArea2`, set its `editable` property to `false` and add it to container box. Line 47 adds box to the `JFrame`. Recall from Section 12.18.2 that the default layout of a `JFrame` is a `BorderLayout` and that the `add` method by default attaches its argument to the `CENTER` of the `BorderLayout`.

When text reaches the right edge of a `JTextArea` the text can wrap to the next line. This is referred to as **line wrapping**. By default, `JTextArea` does *not* wrap lines.



### Look-and-Feel Observation 12.19

To provide line wrapping functionality for a `JTextArea`, invoke `JTextArea` method **`setLineWrap`** with a `true` argument.

### *JScrollPane Scrollbar Policies*

This example uses a `JScrollPane` to provide scrolling for a `JTextArea`. By default, `JScrollPane` displays scrollbars *only* if they're required. You can set the horizontal and vertical **scrollbar policies** of a `JScrollPane` when it's constructed. If a program has a reference to a `JScrollPane`, the program can use `JScrollPane` methods **`setHorizontalScrollBarPolicy`** and **`setVerticalScrollBarPolicy`** to change the scrollbar policies at any time. Class `JScrollPane` declares the constants

```
JScrollPane.VERTICAL_SCROLLBAR_ALWAYS
JScrollPane.HORIZONTAL_SCROLLBAR_ALWAYS
```

to indicate that *a scrollbar should always appear*, constants

```
JScrollPane.VERTICAL_SCROLLBAR_AS_NEEDED
JScrollPane.HORIZONTAL_SCROLLBAR_AS_NEEDED
```

to indicate that *a scrollbar should appear only if necessary* (the defaults) and constants

```
JScrollPane.VERTICAL_SCROLLBAR_NEVER
JScrollPane.HORIZONTAL_SCROLLBAR_NEVER
```

to indicate that *a scrollbar should never appear*. If the horizontal scrollbar policy is set to `JScrollPane.HORIZONTAL_SCROLLBAR_NEVER`, a `JTextArea` attached to the `JScrollPane` will automatically wrap lines.

## 12.21 Wrap-Up

In this chapter, you learned many GUI components and how to handle their events. You also learned about nested classes, inner classes and anonymous inner classes. You saw the special relationship between an inner-class object and an object of its top-level class. You learned how to use `JOptionPane` dialogs to obtain text input from the user and how to display messages to the user. You also learned how to create applications that execute in their own windows. We discussed class `JFrame` and components that enable a user to interact with an application. We also showed you how to display text and images to the user. You learned how to customize `JPanels` to create custom drawing areas, which you'll use extensively in the next chapter. You saw how to organize components on a window using layout managers and how to creating more complex GUIs by using `JPanels` to organize components. Finally, you learned about the `JTextArea` component in which a user can enter text and an application can display text. In Chapter 22, you'll learn about more advanced GUI components, such as sliders, menus and more complex layout managers. In the next chapter, you'll learn how to add graphics to your GUI application. Graphics allow you to draw shapes and text with colors and styles.

## Summary

### Section 12.1 Introduction

- A graphical user interface (GUI; p. 466) presents a user-friendly mechanism for interacting with an application. A GUI gives an application a distinctive look-and-feel (p. 466).
- Providing different applications with consistent, intuitive user-interface components gives users a sense of familiarity with a new application, so that they can learn it more quickly.
- GUIs are built from GUI components (p. 466)—sometimes called controls or widgets.

### Section 12.2 Java's Nimbus Look-and-Feel

- As of Java SE 6 update 10, Java comes bundled with a new, elegant, cross-platform look-and-feel known as Nimbus (p. 468).
- To set Nimbus as the default for all Java applications, create a `swing.properties` text file in the `lib` folder of your JDK and JRE installation folders. Place the following line of code in the file:

```
swing.defaultlaf=com.sun.java.swing.plaf.nimbus.NimbusLookAndFeel
```

- To select Nimbus on an application-by-application basis, place the following command-line argument after the `java` command and before the application's name when you run the application:

```
-Dswing.defaultlaf=com.sun.java.swing.plaf.nimbus.NimbusLookAndFeel
```

### Section 12.3 Simple GUI-Based Input/Output with JOptionPane

- Most applications use windows or dialog boxes (p. 468) to interact with the user.
- Class `JOptionPane` (p. 468) of package `javax.swing` (p. 466) provides prebuilt dialog boxes for both input and output. `JOptionPane` static method `showInputDialog` (p. 469) displays an input dialog (p. 468).
- A prompt typically uses sentence-style capitalization—capitalizing only the first letter of the first word in the text unless the word is a proper noun.
- An input dialog can input only input Strings. This is typical of most GUI components.
- `JOptionPane` static method `showMessageDialog` (p. 470) displays a message dialog (p. 468).

### Section 12.4 Overview of Swing Components

- Most Swing GUI components (p. 466) are located in package `javax.swing`.
- Together, the appearance and the way in which the user interacts with the application are known as that application's look-and-feel. Swing GUI components allow you to specify a uniform look-and-feel for your application across all platforms or to use each platform's custom look-and-feel.
- Lightweight Swing components are not tied to actual GUI components supported by the underlying platform on which an application executes.
- Several Swing components are heavyweight components (p. 472) that require direct interaction with the local windowing system (p. 472), which may restrict their appearance and functionality.
- Class `Component` (p. 472) of package `java.awt` declares many of the attributes and behaviors common to the GUI components in packages `java.awt` (p. 471) and `javax.swing`.
- Class `Container` (p. 472) of package `java.awt` is a subclass of `Component`. Components are attached to Containers so the Components can be organized and displayed on the screen.
- Class `JComponent` (p. 472) of package `javax.swing` is a subclass of `Container`. `JComponent` is the superclass of all lightweight Swing components and declares their common attributes and behaviors.
- Some common `JComponent` features include a pluggable look-and-feel (p. 472), shortcut keys called mnemonics (p. 472), tool tips (p. 472), support for assistive technologies and support for user-interface localization (p. 472).

### Section 12.5 *Displaying Text and Images in a Window*

- Class `JFrame` provides the basic attributes and behaviors of a window.
- A `JLabel` (p. 473) displays read-only text, an image, or both text and an image. Text in a `JLabel` normally uses sentence-style capitalization.
- Each GUI component must be attached to a container, such as a window created with a `JFrame` (p. 475).
- Many IDEs provide GUI design tools (p. 521) in which you can specify the exact size and location of a component by using the mouse; then the IDE will generate the GUI code for you.
- `JComponent` method `setToolTipText` (p. 475) specifies the tool tip that's displayed when the user positions the mouse cursor over a lightweight component (p. 472).
- Container method `add` attaches a GUI component to a `Container`.
- Class `ImageIcon` (p. 476) supports several image formats, including GIF, PNG and JPEG.
- Method `getClass` of class `Object` (p. 476) retrieves a reference to the `Class` object that represents the the class declaration for the object on which the method is called.
- Class method `getResource` (p. 476) returns the location of its argument as a URL. The method `getResource` uses the `Class` object's class loader to determine the location of the resource.
- The horizontal and vertical alignments of a `JLabel` can be set with methods `setHorizontalAlignment` (p. 476) and `setVerticalAlignment` (p. 476), respectively.
- `JLabel` methods `setText` (p. 476) and `getText` (p. 476) set and get the text displayed on a label.
- `JLabel` methods `setIcon` (p. 476) and `getIcon` (p. 476) set and get the `Icon` (p. 476) on a label.
- `JLabel` methods `setHorizontalTextPosition` (p. 476) and `setVerticalTextPosition` (p. 476) specify the text position in the label.
- `JFrame` method `setDefaultCloseOperation` (p. 477) with constant `JFrame.EXIT_ON_CLOSE` as the argument indicates that the program should terminate when the window is closed by the user.
- Component method `setSize` (p. 477) specifies the width and height of a component.
- Component method `setVisible` (p. 477) with the argument `true` displays a `JFrame` on the screen.

### Section 12.6 *Text Fields and an Introduction to Event Handling with Nested Classes*

- GUIs are event driven—when the user interacts with a GUI component, events (p. 477) drive the program to perform tasks.
- An event handler (p. 477) performs a task in response to an event.
- Class `JTextField` (p. 477) extends `JTextComponent` (p. 477) of package `javax.swing.text`, which provides common text-based component features. Class `JPasswordField` (p. 477) extends `JTextField` and adds several methods that are specific to processing passwords.
- A `JPasswordField` (p. 477) shows that characters are being typed as the user enters them, but hides the actual characters with echo characters (p. 477).
- A component receives the focus (p. 478) when the user clicks the component.
- `JTextComponent` method `setEditable` (p. 480) can be used to make a text field uneditable.
- To respond to an event for a particular GUI component, you must create a class that represents the event handler and implements an appropriate event-listener interface (p. 480), then register an object of the event-handling class as the event handler (p. 480).
- Non-static nested classes (p. 480) are called inner classes and are frequently used for event handling.
- An object of a non-static inner class (p. 480) must be created by an object of the top-level class (p. 480) that contains the inner class.



- An inner-class object can directly access the instance variables and methods of its top-level class.
- A nested class that's `static` does not require an object of its top-level class and does not implicitly have a reference to an object of the top-level class.
- Pressing *Enter* in a `JTextField` or `JPasswordField` generates an `ActionEvent` (p. 481) that can be handled by an `ActionListener` (p. 481) of package `java.awt.event`.
- `JTextField` method `addActionListener` (p. 481) registers an event handler for a text field's `ActionEvent`.
- The GUI component with which the user interacts is the event source (p. 482).
- An `ActionEvent` object contains information about the event that just occurred, such as the event source and the text in the text field.
- `ActionEvent` method `getSource` returns a reference to the event source. `ActionEvent` method `getActionCommand` (p. 482) returns the text the user typed in a text field or the label on a `JButton`.
- `JPasswordField` method `getPassword` (p. 482) returns the password the user typed.

### *Section 12.7 Common GUI Event Types and Listener Interfaces*

- Each event-object type typically has a corresponding event-listener interface that specifies one or more event-handling methods, which must be declared in the class that implements the interface.

### *Section 12.8 How Event Handling Works*

- When an event occurs, the GUI component with which the user interacted notifies its registered listeners by calling each listener's appropriate event-handling method.
- Every GUI component supports several event types. When an event occurs, the event is dispatched (p. 486) only to the event listeners of the appropriate type.

### *Section 12.9 JButton*

- A button is a component the user clicks to trigger an action. All the button types are subclasses of `AbstractButton` (p. 487; package `javax.swing`). Button labels (p. 487) typically use book-title capitalization (p. 487).
- Command buttons (p. 487) are created with class `JButton`.
- A `JButton` can display an `Icon`. A `JButton` can also have a rollover `Icon` (p. 489)—an `Icon` that's displayed when the user positions the mouse over the button.
- Method `setRolloverIcon` (p. 490) of class `AbstractButton` specifies the image displayed on a button when the user positions the mouse over it.

### *Section 12.10 Buttons That Maintain State*

- There are three Swing state button types—`JToggleButton` (p. 490), `JCheckBox` (p. 490) and `JRadioButton` (p. 490).
- Classes `JCheckBox` and `JRadioButton` are subclasses of `JToggleButton`.
- Component method `setFont` (p. 492) sets the component's font to a new `Font` object (p. 492) of package `java.awt`.
- Clicking a `JCheckBox` causes an `ItemEvent` (p. 493) that can be handled by an `ItemListener` (p. 493) which defines method `itemStateChanged` (p. 493). Method `addItemListener` registers the listener for the `ItemEvent` of a `JCheckBox` or `JRadioButton` object.
- `JCheckBox` method `isSelected` determines whether a `JCheckBox` is selected.
- `JRadioButtons` have two states—selected and not selected. Radio buttons (p. 487) normally appear as a group (p. 493) in which only one button can be selected at a time.

- `JRadioButtons` are used to represent mutually exclusive options (p. 493).
- The logical relationship between `JRadioButtons` is maintained by a `ButtonGroup` object (p. 493).
- `ButtonGroup` method `add` (p. 496) associates each `JRadioButton` with a `ButtonGroup`. If more than one selected `JRadioButton` object is added to a group, the selected one that was added first will be selected when the GUI is displayed.
- `JRadioButtons` generate `ItemEvents` when they're clicked.

### *Section 12.11 JComboBox; Using an Anonymous Inner Class for Event Handling*

- A `JComboBox` (p. 496) provides a list of items from which the user can make a single selection. `JComboBoxes` generate `ItemEvents`.
- Each item in a `JComboBox` has an index (p. 499). The first item added to a `JComboBox` appears as the currently selected item when the `JComboBox` is displayed.
- `JComboBox` method `setMaximumRowCount` (p. 499) sets the maximum number of elements that are displayed when the user clicks the `JComboBox`.
- An anonymous inner class (p. 499) is a class without a name and typically appears inside a method declaration. One object of the anonymous inner class must be created when the class is declared.
- `JComboBox` method `getSelectedIndex` (p. 500) returns the index of the selected item.

### *Section 12.12 JList*

- A `JList` displays a series of items from which the user may select one or more items. Class `JList` supports single-selection lists (p. 500) and multiple-selection lists.
- When the user clicks an item in a `JList`, a `ListSelectionEvent` (p. 500) occurs. `JList` method `addListSelectionListener` (p. 502) registers a `ListSelectionListener` (p. 502) for a `JList`'s selection events. A `ListSelectionListener` of package `javax.swing.event` (p. 484) must implement method `valueChanged`.
- `JList` method `setVisibleRowCount` (p. 502) specifies the number of visible items in the list.
- `JList` method `setSelectionMode` (p. 502) specifies a list's selection mode.
- A `JList` can be attached to a `JScrollPane` (p. 502) to provide a scrollbar for the `JList`.
- `JFrame` method `getContentPane` (p. 502) returns a reference to the `JFrame`'s content pane where GUI components are displayed.
- `JList` method `getSelectedIndex` (p. 503) returns the selected item's index.

### *Section 12.13 Multiple-Selection Lists*

- A multiple-selection list (p. 503) enables the user to select many items from a `JList`.
- `JList` method `setFixedCellWidth` (p. 505) sets a `JList`'s width. Method `setFixedCellHeight` (p. 505) sets the height of each item in a `JList`.
- Normally, an external event (p. 505) generated by another GUI component (such as a `JButton`) specifies when the multiple selections in a `JList` should be processed.
- `JList` method `setListData` (p. 505) sets the items displayed in a `JList`. `JList` method `getSelectedValues` (p. 505) returns an array of `Objects` representing the selected items in a `JList`.

### *Section 12.14 Mouse Event Handling*

- The `MouseListener` (p. 505) and `MouseMotionListener` (p. 505) event-listener interfaces are used to handle mouse events (p. 505). Mouse events can be trapped for any GUI component that extends `Component`.

- Interface `MouseListener` (p. 505) of package `javax.swing.event` extends interfaces `MouseListener` and `MouseMotionListener` to create a single interface containing all their methods.
- Each mouse event-handling method receives a `MouseEvent` object (p. 486) that contains information about the event, including the *x*- and *y*-coordinates where the event occurred. Coordinates are measured from the upper-left corner of the GUI component on which the event occurred.
- The methods and constants of class `InputEvent` (p. 506; `MouseEvent`'s superclass) enable an application to determine which mouse button the user clicked.
- Interface `MouseWheelListener` (p. 507) enables applications to respond to mouse-wheel events.

### *Section 12.15 Adapter Classes*

- An adapter class (p. 510) implements an interface and provides default implementations of its methods. When you extend an adapter class, you can override just the method(s) you need.
- `MouseEvent` method `getClickCount` (p. 513) returns the number of consecutive mouse-button clicks. Methods `isMetaDown` (p. 520) and `isAltDown` (p. 513) determine which button was clicked.

### *Section 12.16 JPanel Subclass for Drawing with the Mouse*

- `JComponent`'s method `paintComponent` (p. 514) is called when a lightweight Swing component is displayed. Override this method to specify how to draw shapes using Java's graphics capabilities.
- When overriding `paintComponent`, call the superclass version as the first statement in the body.
- Subclasses of `JComponent` support transparency. When a component is opaque (p. 514), `paintComponent` clears its background before the component is displayed.
- The transparency of a Swing lightweight component can be set with method `setOpaque` (p. 514; a `false` argument indicates that the component is transparent).
- Class `Point` (p. 515) package `java.awt` represents an *x-y* coordinate.
- Class `Graphics` (p. 515) is used to draw.
- `MouseEvent` method `getPoint` (p. 516) obtains the `Point` where a mouse event occurred.
- Method `repaint` (p. 516), inherited indirectly from class `Component`, indicates that a component should be refreshed on the screen as soon as possible.
- Method `paintComponent` receives a `Graphics` parameter and is called automatically whenever a lightweight component needs to be displayed on the screen.
- `Graphics` method `fillOval` (p. 516) draws a solid oval. The first two arguments are the upper-left *x-y* coordinate of the bounding box, and the last two are the bounding box's width and height.

### *Section 12.17 Key Event Handling*

- Interface `KeyListener` (p. 486) is used to handle key events (p. 486) that are generated when keys on the keyboard are pressed and released. Method `addKeyListener` of class `Component` (p. 517) registers a `KeyListener`.
- `KeyEvent` (p. 486) method `getKeyCode` (p. 520) gets the virtual key code (p. 520) of the pressed key. Class `KeyEvent` contains virtual key-code constants that represent every key on the keyboard.
- `KeyEvent` method `getKeyText` (p. 520) returns a string containing the name of the pressed key.
- `KeyEvent` method `getKeyChar` (p. 520) gets the Unicode value of the character typed.
- `KeyEvent` method `isActionKey` (p. 520) determines whether the key in an event was an action key (p. 517).
- `InputEvent` method `getModifiers` (p. 520) determines whether any modifier keys (such as *Shift*, *Alt* and *Ctrl*) were pressed when the key event occurred.

- `KeyEvent` method `getKeyModifiersText` (p. 520) returns a string containing the pressed modifier keys.

### Section 12.18 Introduction to Layout Managers

- Layout managers (p. 520) arrange GUI components in a container for presentation purposes.
- All layout managers implement the interface `LayoutManager` (p. 520) of package `java.awt`.
- Container method `setLayout` specifies the layout of a container.
- `FlowLayout` places components left to right in the order in which they're added to the container. When the container's edge is reached, components continue to display on the next line. `FlowLayout` allows GUI components to be left aligned, centered (the default) and right aligned.
- `FlowLayout` method `setAlignment` (p. 524) changes the alignment for a `FlowLayout`.
- `BorderLayout` (p. 524) the default for a `JFrame` arranges components into five regions: NORTH, SOUTH, EAST, WEST and CENTER. NORTH corresponds to the top of the container.
- A `BorderLayout` limits a `Container` to containing at most five components—one in each region.
- `GridLayout` (p. 528) divides a container into a grid of rows and columns.
- Container method `validate` (p. 529) recomputes a container's layout based on the current layout manager for the `Container` and the current set of displayed GUI components.

### Section 12.19 Using Panels to Manage More Complex Layouts

- Complex GUIs often consist of multiple panels with different layouts. Every `JPanel` may have components, including other panels, attached to it with `Container` method `add`.

### Section 12.20 JTextArea

- A `JTextArea` (p. 531)—a subclass of `JTextComponent`—may contain multiple lines of text.
- Class `Box` (p. 532) is a subclass of `Container` that uses a `BoxLayout` layout manager (p. 533) to arrange the GUI components either horizontally or vertically.
- `Box` static method `createHorizontalBox` (p. 533) creates a `Box` that arranges components from left to right in the order that they're attached.
- Method `getSelectedText` (p. 533) returns the selected text from a `JTextArea`.
- You can set the horizontal and vertical scrollbar policies (p. 534) of a `JScrollPane` when it's constructed. `JScrollPane` methods `setHorizontalScrollBarPolicy` (p. 534) and `setVerticalScrollBarPolicy` (p. 534) can be used to change the scrollbar policies at any time.

## Self-Review Exercises

- 12.1** Fill in the blanks in each of the following statements:
- Method \_\_\_\_\_ is called when the mouse is moved with no buttons pressed and an event listener is registered to handle the event.
  - Text that cannot be modified by the user is called \_\_\_\_\_ text.
  - A(n) \_\_\_\_\_ arranges GUI components in a `Container`.
  - The `add` method for attaching GUI components is a method of class \_\_\_\_\_.
  - GUI is an acronym for \_\_\_\_\_.
  - Method \_\_\_\_\_ is used to specify the layout manager for a container.
  - A `mouseDragged` method call is preceded by a(n) \_\_\_\_\_ method call and followed by a(n) \_\_\_\_\_ method call.
  - Class \_\_\_\_\_ contains methods that display message dialogs and input dialogs.
  - An input dialog capable of receiving input from the user is displayed with method \_\_\_\_\_ of class \_\_\_\_\_.

- j) A dialog capable of displaying a message to the user is displayed with method of class \_\_\_\_\_.
  - k) Both `JTextField`s and `JTextAreas` directly extend class \_\_\_\_\_.
- 12.2** Determine whether each statement is *true* or *false*. If *false*, explain why.
- a) `BorderLayout` is the default layout manager for a `JFrame`'s content pane.
  - b) When the mouse cursor is moved into the bounds of a GUI component, method `mouseover` is called.
  - c) A `JPanel` cannot be added to another `JPanel`.
  - d) In a `BorderLayout`, two buttons added to the `NORTH` region will be placed side by side.
  - e) A maximum of five components can be added to a `BorderLayout`.
  - f) Inner classes are not allowed to access the members of the enclosing class.
  - g) A `JTextArea`'s text is always read-only.
  - h) Class `JTextArea` is a direct subclass of class `Component`.
- 12.3** Find the error(s) in each of the following statements, and explain how to correct it (them):
- a) `buttonName = JButton("Caption");`
  - b) `JLabel aLabel, JLabel;`
  - c) `txtField = new JTextField(50, "Default Text");`
  - d) `setLayout(new BorderLayout());`  
`button1 = new JButton("North Star");`  
`button2 = new JButton("South Pole");`  
`add(button1);`  
`add(button2);`

## Answers to Self-Review Exercises

**12.1** a) `mouseMoved`. b) uneditable (read-only). c) layout manager. d) `Container`. e) graphical user interface. f) `setLayout`. g) `mousePressed`, `mouseReleased`. h) `JOptionPane`. i) `showInputDialog`, `JOptionPane`. j) `showMessageDialog`, `JOptionPane`. k) `JTextComponent`.


- 12.2**
- a) True.
  - b) False. Method `mouseenter` is called.
  - c) False. A `JPanel` can be added to another `JPanel`, because `JPanel` is an indirect subclass of `Component`. So, a `JPanel` is a `Component`. Any `Component` can be added to a `Container`.
  - d) False. Only the last button added will be displayed. Remember that only one component should be added to each region in a `BorderLayout`.
  - e) True. [Note: Panels containing multiple components can be added to each region.]
  - f) False. Inner classes have access to all members of the enclosing class declaration.
  - g) False. `JTextAreas` are editable by default.
  - h) False. `JTextArea` derives from class `JTextComponent`.

- 12.3**
- a) `new` is needed to create an object.
  - b) `JLabel` is a class name and cannot be used as a variable name.
  - c) The arguments passed to the constructor are reversed. The `String` must be passed first.
  - d) `BorderLayout` has been set, and components are being added without specifying the region, so both are added to the center region. Proper `add` statements might be  
`add(button1, BorderLayout.NORTH);`  
`add(button2, BorderLayout.SOUTH);`


## Exercises

- 12.4** Fill in the blanks in each of the following statements:
- a) The `JTextField` class directly extends class \_\_\_\_\_.


- b) Container method \_\_\_\_\_ attaches a GUI component to a container.  
 c) Method \_\_\_\_\_ is called when a mouse button is released (without moving the mouse).  
 d) The \_\_\_\_\_ class is used to create a group of JRadioButtons.
- 12.5** Determine whether each statement is *true* or *false*. If *false*, explain why.
- Only one layout manager can be used per Container.
  - GUI components can be added to a Container in any order in a BorderLayout.
  - JRadioButtons provide a series of mutually exclusive options (i.e., only one can be true at a time).
  - Graphics method setFont is used to set the font for text fields.
  - A JList displays a scrollbar if there are more items in the list than can be displayed.
  - A Mouse object has a method called mouseDragged.
- 12.6** Determine whether each statement is *true* or *false*. If *false*, explain why.
- A JPanel is a JComponent.
  - A JPanel is a Component.
  - A JLabel is a Container.
  - A JList is a JPanel.
  - An AbstractButton is a JButton.
  - A JTextField is an Object.
  - ButtonGroup is a subclass of JComponent.
- 12.7** Find any errors in each of the following lines of code, and explain how to correct them.
- `import javax.swing.JFrame`
  - `panelObject.GridLayout(8, 8);`
  - `container.setLayout(new FlowLayout(FlowLayout.DEFAULT));`
  - `container.add(eastButton, EAST); face`
- 12.8** Create the following GUI. You do not have to provide any functionality.




- 12.9** Create the following GUI. You do not have to provide any functionality.



- 12.10** Create the following GUI. You do not have to provide any functionality.



**12.11** Create the following GUI. You do not have to provide any functionality.



**12.12 (Temperature Conversion)** Write a temperature-conversion application that converts from Fahrenheit to Celsius. The Fahrenheit temperature should be entered from the keyboard (via a `JTextField`). A `JLabel` should be used to display the converted temperature. Use the following formula for the conversion:

$$\text{Celsius} = \frac{5}{9} \times (\text{Fahrenheit} - 32)$$

**12.13 (Temperature-Conversion Modification)** Enhance the temperature-conversion application of Exercise 12.12 by adding the Kelvin temperature scale. The application should also allow the user to make conversions between any two scales. Use the following formula for the conversion between Kelvin and Celsius (in addition to the formula in Exercise 12.12):

$$\text{Kelvin} = \text{Celsius} + 273.15$$

**12.14 (Guess-the-Number Game)** Write an application that plays “guess the number” as follows: Your application chooses the number to be guessed by selecting an integer at random in the range 1–1000. The application then displays the following in a label:

I have a number between 1 and 1000. Can you guess my number?  
Please enter your first guess.

A `JTextField` should be used to input the guess. As each guess is input, the background color should change to either red or blue. Red indicates that the user is getting “warmer,” and blue, “colder.” A `JLabel` should display either “Too High” or “Too Low” to help the user zero in. When the user gets the correct answer, “Correct!” should be displayed, and the `JTextField` used for input should be changed to be uneditable. A `JButton` should be provided to allow the user to play the game again. When the `JButton` is clicked, a new random number should be generated and the input `JTextField` changed to be editable.

**12.15 (Displaying Events)** It’s often useful to display the events that occur during the execution of an application. This can help you understand when the events occur and how they’re generated. Write an application that enables the user to generate and process every event discussed in this chapter. The application should provide methods from the `ActionListener`, `ItemListener`, `ListSelectionListener`, `MouseListener`, `MouseMotionListener` and `KeyListener` interfaces to display messages when the events occur. Use method `toString` to convert the event objects received in each event handler into `Strings` that can be displayed. Method `toString` creates a `String` containing all the information in the event object.

**12.16 (GUI-Based Craps Game)** Modify the application of Section 5.10 to provide a GUI that enables the user to click a `JButton` to roll the dice. The application should also display four `JLabels` and four `JTextFields`, with one `JLabel` for each `JTextField`. The `JTextFields` should be used to display the values of each die and the sum of the dice after each roll. The point should be displayed in the fourth `JTextField` when the user does not win or lose on the first roll and should continue to be displayed until the game is lost.

*(Optional) GUI and Graphics Case Study Exercise: Expanding the Interface*

**12.17 (Interactive Drawing Application)** In this exercise, you'll implement a GUI application that uses the `MyShape` hierarchy from GUI and Graphics Case Study Exercise 10.2 to create an interactive drawing application. You'll create two classes for the GUI and provide a test class that launches the application. The classes of the `MyShape` hierarchy require no additional changes.

The first class to create is a subclass of `JPanel` called `DrawPanel`, which represents the area on which the user draws the shapes. Class `DrawPanel` should have the following instance variables:

- An array `shapes` of type `MyShape` that will store all the shapes the user draws.
- An integer `shapeCount` that counts the number of shapes in the array.
- An integer `shapeType` that determines the type of shape to draw.
- A `MyShape` `currentShape` that represents the current shape the user is drawing.
- A `Color` `currentColor` that represents the current drawing color.
- A boolean `filledShape` that determines whether to draw a filled shape.
- A `JLabel` `statusLabel` that represents the status bar. The status bar will display the coordinates of the current mouse position.

Class `DrawPanel` should also declare the following methods:

- Overridden method `paintComponent` that draws the shapes in the array. Use instance variable `shapeCount` to determine how many shapes to draw. Method `paintComponent` should also call `currentShape`'s `draw` method, provided that `currentShape` is not `null`.
- Set methods for the `shapeType`, `currentColor` and `filledShape`.
- Method `clearLastShape` should clear the last shape drawn by decrementing instance variable `shapeCount`. Ensure that `shapeCount` is never less than zero.
- Method `clearDrawing` should remove all the shapes in the current drawing by setting `shapeCount` to zero.

Methods `clearLastShape` and `clearDrawing` should call `repaint` (inherited from `JPanel`) to refresh the drawing on the `DrawPanel` by indicating that the system should call method `paintComponent`.

Class `DrawPanel` should also provide event handling to enable the user to draw with the mouse. Create a single inner class that both extends `MouseAdapter` and implements `MouseMotionListener` to handle all mouse events in one class.

In the inner class, override method `mousePressed` so that it assigns `currentShape` a new shape of the type specified by `shapeType` and initializes both points to the mouse position. Next, override method `mouseReleased` to finish drawing the current shape and place it in the array. Set the second point of `currentShape` to the current mouse position and add `currentShape` to the array. Instance variable `shapeCount` determines the insertion index. Set `currentShape` to `null` and call method `repaint` to update the drawing with the new shape.

Override method `mouseMoved` to set the text of the `statusLabel` so that it displays the mouse coordinates—this will update the label with the coordinates every time the user moves (but does not drag) the mouse within the `DrawPanel`. Next, override method `mouseDragged` so that it sets the second point of the `currentShape` to the current mouse position and calls method `repaint`. This will allow the user to see the shape while dragging the mouse. Also, update the `JLabel` in `mouseDragged` with the current position of the mouse.

Create a constructor for `DrawPanel` that has a single `JLabel` parameter. In the constructor, initialize `statusLabel` with the value passed to the parameter. Also initialize array `shapes` with 100 entries, `shapeCount` to 0, `shapeType` to the value that represents a line, `currentShape` to `null` and `currentColor` to `Color.BLACK`. The constructor should then set the background color of the `DrawPanel` to `Color.WHITE` and register the `MouseListener` and `MouseMotionListener` so the `JPanel` properly handles mouse events.


Next, create a `JFrame` subclass called `DrawFrame` that provides a GUI that enables the user to control various aspects of drawing. For the layout of the `DrawFrame`, we recommend a `BorderLay-`



out, with the components in the NORTH region, the main drawing panel in the CENTER region, and a status bar in the SOUTH region, as in Fig. 12.49. In the top panel, create the components listed below. Each component's event handler should call the appropriate method in class `DrawPanel`.

- a) A button to undo the last shape drawn.
- b) A button to clear all shapes from the drawing.
- c) A combo box for selecting the color from the 13 predefined colors.
- d) A combo box for selecting the shape to draw.
- e) A checkbox that specifies whether a shape should be filled or unfilled.

Declare and create the interface components in `DrawFrame`'s constructor. You'll need to create the status bar `JLabel` before you create the `DrawPanel`, so you can pass the `JLabel` as an argument to `DrawPanel`'s constructor. Finally, create a test class that initializes and displays the `DrawFrame` to execute the application.



**Fig. 12.49** | Interface for drawing shapes.


**12.18 (GUI-Based Version of the ATM Case Study)** Reimplement the Optional ATM Case Study of Chapters 33–34 as a GUI-based application. Use GUI components to approximate the ATM user interface shown in Fig. 33.1. For the cash dispenser and the deposit slot use `JButtons` labeled **Remove Cash** and **Insert Envelope**. This will enable the application to receive events indicating when the user takes the cash and inserts a deposit envelope, respectively.

## Making a Difference

**12.19 (Ecofont)** Ecofont ([www.ecofont.eu/ecofont\\_en.html](http://www.ecofont.eu/ecofont_en.html))—developed by SPRANQ (a Netherlands-based company)—is a free, open-source computer font designed to reduce by as much as 20% the amount of ink used for printing, thus reducing also the number of ink cartridges used and the environmental impact of the manufacturing and shipping processes (using less energy, less fuel for shipping, and so on). The font, based on sans-serif Verdana, has small circular “holes” in the letters that are not visible in smaller sizes—such as the 9- or 10-point type frequently used. Download Ecofont, then install the font file `Spranq_eco_sans_regular.ttf` using the instructions from the Ecofont website. Next, develop a GUI-based program that allows you to type in a text string to be displayed in the Ecofont. Create **Increase Font Size** and **Decrease Font Size** buttons that allow you

to scale up or down by one point at a time. Start with a default font size of 9 points. As you scale up, you'll be able to see the holes in the letters more clearly. As you scale down, the holes will be less apparent. What is the smallest font size at which you begin to notice the holes?

**12.20** (*Typing Tutor: Tuning a Crucial Skill in the Computer Age*) Typing quickly and correctly is an essential skill for working effectively with computers and the Internet. In this exercise, you'll build a GUI application that can help users learn to “touch type” (i.e., type correctly without looking at the keyboard). The application should display a *virtual keyboard* (Fig. 12.50) and should allow the user to watch what he or she is typing on the screen without looking at the *actual keyboard*. Use `JButtons` to represent the keys. As the user presses each key, the application highlights the corresponding `JButton` on the GUI and adds the character to a `JTextArea` that shows what the user has typed so far. [*Hint*: To highlight a `JButton`, use its `setBackground` method to change its background color. When the key is released, reset its original background color. You can obtain the `JButton`'s original background color with the `getBackground` method before you change its color.]



**Fig. 12.50** | Typing tutor.

You can test your program by typing a pangram—a phrase that contains every letter of the alphabet at least once—such as “The quick brown fox jumped over a lazy dog.” You can find other pangrams on the web.

To make the program more interesting you could monitor the user's accuracy. You could have the user type specific phrases that you've prestored in your program and that you display on the screen above the virtual keyboard. You could keep track of how many keystrokes the user types correctly and how many are typed incorrectly. You could also keep track of which keys the user is having difficulty with and display a report showing those keys.

# Graphics and Java 2D

# 13



*Treat nature in terms of the cylinder, the sphere, the cone, all in perspective.*

—Paul Cézanne

*Colors, like features, follow the changes of the emotions.*

—Pablo Picasso

*Nothing ever becomes real till it is experienced—even a proverb is no proverb to you till your life has illustrated it.*

—John Keats

## Objectives

In this chapter you'll:

- Understand graphics contexts and graphics objects.
- Manipulate colors and fonts.
- Use methods of class **Graphics** to draw various shapes.
- Use methods of class **Graphics2D** from the Java 2D API to draw various shapes.
- Specify **Paint** and **Stroke** characteristics of shapes displayed with **Graphics2D**.

- |                                             |                                     |
|---------------------------------------------|-------------------------------------|
| 13.1 Introduction                           | 13.6 Drawing Arcs                   |
| 13.2 Graphics Contexts and Graphics Objects | 13.7 Drawing Polygons and Polylines |
| 13.3 Color Control                          | 13.8 Java 2D API                    |
| 13.4 Manipulating Fonts                     | 13.9 Wrap-Up                        |
| 13.5 Drawing Lines, Rectangles and Ovals    |                                     |


Summary | Self-Review Exercises | Answers to Self-Review Exercises | Exercises | Making a Difference

## 13.1 Introduction

In this chapter, we overview several of Java's capabilities for drawing two-dimensional shapes, controlling colors and controlling fonts. Part of Java's initial appeal was its support for graphics that enabled programmers to visually enhance their applications. Java contains more sophisticated drawing capabilities as part of the Java 2D API (presented in this chapter) and its successor technology JavaFX (presented in Chapter 25 and two online chapters). This chapter begins by introducing many of Java's original drawing capabilities. Next we present several of the more powerful Java 2D capabilities, such as controlling the *style* of lines used to draw shapes and the way shapes are *filled* with *colors* and *patterns*. The classes that were part of Java's original graphics capabilities are now considered to be part of the Java 2D API.

Figure 13.1 shows a portion of the class hierarchy that includes various graphics classes and Java 2D API classes and interfaces covered in this chapter. Class **Color** contains methods and constants for manipulating colors. Class **JComponent** contains method `paintComponent`, which is used to draw graphics on a component. Class **Font** contains methods and constants for manipulating fonts. Class **FontMetrics** contains methods for obtaining *font* information. Class **Graphics** contains methods for drawing strings, lines, rectangles and other shapes. Class **Graphics2D**, which extends class **Graphics**, is used for drawing with the Java 2D API. Class **Polygon** contains methods for creating *polygons*. The bottom half of the figure lists several classes and interfaces from the Java 2D API. Class **BasicStroke** helps specify the drawing characteristics of *lines*. Classes **GradientPaint** and **TexturePaint** help specify the characteristics for filling *shapes* with *colors* or *patterns*. Classes **GeneralPath**, **Line2D**, **Arc2D**, **Ellipse2D**, **Rectangle2D** and **RoundRectangle2D** represent several Java 2D shapes.

To begin drawing in Java, we must first understand Java's **coordinate system** (Fig. 13.2), which is a scheme for identifying every *point* on the screen. By default, the *upper-left corner* of a GUI component (e.g., a window) has the coordinates (0, 0). A coordinate pair is composed of an *x-coordinate* (the **horizontal coordinate**) and a *y-coordinate* (the **vertical coordinate**). The *x-coordinate* is the horizontal distance moving *right* from the left edge of the screen. The *y-coordinate* is the vertical distance moving *down* from the *top* of the screen. The *x-axis* describes every horizontal coordinate, and the *y-axis* every vertical coordinate. The coordinates are used to indicate where graphics should be displayed on a screen. Coordinate units are measured in **pixels** (which stands for "picture elements"). A pixel is a display monitor's *smallest unit of resolution*.




**Fig. 13.1** | Classes and interfaces used in this chapter from Java's original graphics capabilities and from the Java 2D API.



### Portability Tip 13.1

*Different display monitors have different resolutions (i.e., the density of the pixels varies). This can cause graphics to appear in different sizes on different monitors or on the same monitor with different settings.*



**Fig. 13.2** | Java coordinate system. Units are measured in pixels.

## 13.2 Graphics Contexts and Graphics Objects

A **graphics context** enables drawing on the screen. A `Graphics` object manages a graphics context and draws pixels on the screen that represent *text* and other graphical objects (e.g., *lines*, *ellipses*, *rectangles* and other *polygons*). `Graphics` objects contain methods for *drawing*, *font manipulation*, *color manipulation* and the like.

Class `Graphics` is an abstract class (i.e., you cannot instantiate `Graphics` objects). This contributes to Java's portability. Because drawing is performed *differently* on every platform that supports Java, there cannot be only one implementation of the drawing capabilities across all systems. When Java is implemented on a particular platform, a subclass of `Graphics` is created that implements the drawing capabilities. This implementation is hidden by class `Graphics`, which supplies the interface that enables us to use graphics in a *platform-independent* manner.

Recall from Chapter 12 that class `Component` is the *superclass* for many of the classes in package `java.awt`. Class `JComponent` (package `javax.swing`), which inherits indirectly from class `Component`, contains a `paintComponent` method that can be used to draw graphics. Method `paintComponent` takes a `Graphics` object as an argument. This object is passed to the `paintComponent` method by the system when a lightweight Swing component needs to be repainted. The header for the `paintComponent` method is

```
public void paintComponent(Graphics g)
```

Parameter `g` receives a reference to an instance of the system-specific subclass of `Graphics`. The preceding method header should look familiar to you—it's the same one we used in some of the applications in Chapter 12. Actually, class `JComponent` is a *superclass* of `JPanel`. Many capabilities of class `JPanel` are inherited from class `JComponent`.

You seldom call method `paintComponent` directly, because drawing graphics is an *event-driven* process. As we mentioned in Chapter 11, Java uses a *multithreaded* model of program execution. Each thread is a *parallel* activity. Each program can have many threads. When you create a GUI-based application, one of those threads is known as the **event-dispatch thread** (EDT)—it's used to process all GUI events. All manipulation of the on-screen GUI components must be performed in that thread. When a GUI application executes, the application container calls method `paintComponent` (in the event-dispatch thread) for each lightweight component as the GUI is displayed. For `paintComponent` to be called again, an event must occur (such as *covering* and *uncovering* the component with another window).

If you need `paintComponent` to execute (i.e., if you want to update the graphics drawn on a Swing component), you can call method **repaint**, which returns `void`, takes no arguments and is inherited by all `JComponents` indirectly from class `Component` (package `java.awt`).

## 13.3 Color Control

Class `Color` declares methods and constants for manipulating colors in a Java program. The predeclared color constants are summarized in Fig. 13.3, and several color methods and constructors are summarized in Fig. 13.4. Two of the methods in Fig. 13.4 are `Graphics` methods that are specific to colors.

| Color constant                                    | RGB value     |
|---------------------------------------------------|---------------|
| <code>public static final Color RED</code>        | 255, 0, 0     |
| <code>public static final Color GREEN</code>      | 0, 255, 0     |
| <code>public static final Color BLUE</code>       | 0, 0, 255     |
| <code>public static final Color ORANGE</code>     | 255, 200, 0   |
| <code>public static final Color PINK</code>       | 255, 175, 175 |
| <code>public static final Color CYAN</code>       | 0, 255, 255   |
| <code>public static final Color MAGENTA</code>    | 255, 0, 255   |
| <code>public static final Color YELLOW</code>     | 255, 255, 0   |
| <code>public static final Color BLACK</code>      | 0, 0, 0       |
| <code>public static final Color WHITE</code>      | 255, 255, 255 |
| <code>public static final Color GRAY</code>       | 128, 128, 128 |
| <code>public static final Color LIGHT_GRAY</code> | 192, 192, 192 |
| <code>public static final Color DARK_GRAY</code>  | 64, 64, 64    |

**Fig. 13.3** | `Color` constants and their RGB values.

| Method                                               | Description                                                                                                 |
|------------------------------------------------------|-------------------------------------------------------------------------------------------------------------|
| <i>Color constructors and methods</i>                |                                                                                                             |
| <code>public Color(int r, int g, int b)</code>       | Creates a color based on red, green and blue components expressed as integers from 0 to 255.                |
| <code>public Color(float r, float g, float b)</code> | Creates a color based on red, green and blue components expressed as floating-point values from 0.0 to 1.0. |
| <code>public int getRed()</code>                     | Returns a value between 0 and 255 representing the red content.                                             |

**Fig. 13.4** | `Color` methods and color-related `Graphics` methods. (Part I of 2.)

| Method                                          | Description                                                               |
|-------------------------------------------------|---------------------------------------------------------------------------|
| <b>public int</b> getGreen()                    | Returns a value between 0 and 255 representing the green content.         |
| <b>public int</b> getBlue()                     | Returns a value between 0 and 255 representing the blue content.          |
| <i>Graphics methods for manipulating Colors</i> |                                                                           |
| <b>public Color</b> getColor()                  | Returns Color object representing current color for the graphics context. |
| <b>public void</b> setColor(Color c)            | Sets the current color for drawing with the graphics context.             |

**Fig. 13.4** | Color methods and color-related Graphics methods. (Part 2 of 2.)

Every color is created from a red, a green and a blue value. Together these are called **RGB values**. All three RGB components can be integers in the range from 0 to 255, or all three can be floating-point values in the range 0.0 to 1.0. The first RGB component specifies the amount of red, the second the amount of green and the third the amount of blue. The larger the value, the greater the amount of that particular color. Java enables you to choose from  $256 \times 256 \times 256$  (approximately 16.7 million) colors. Not all computers are capable of displaying all these colors. The screen will display the closest color it can.

Two of class `Color`'s constructors are shown in Fig. 13.4—one that takes three `int` arguments and one that takes three `float` arguments, with each argument specifying the amount of red, green and blue. The `int` values must be in the range 0–255 and the `float` values in the range 0.0–1.0. The new `Color` object will have the specified amounts of red, green and blue. `Color` methods **getRed**, **getGreen** and **getBlue** return integer values from 0 to 255 representing the amounts of red, green and blue, respectively. `Graphics` method **getColor** returns a `Color` object representing the `Graphics` object's current drawing color. `Graphics` method **setColor** sets the current drawing color.

### *Drawing in Different Colors*

Figures 13.5–13.6 demonstrate several methods from Fig. 13.4 by drawing *filled rectangles* and *Strings* in several different colors. When the application begins execution, class `ColorJPanel`'s `paintComponent` method (lines 10–37 of Fig. 13.5) is called to paint the window. Line 17 uses `Graphics` method `setColor` to set the drawing color. Method `setColor` receives a `Color` object. The expression `new Color(255, 0, 0)` creates a new `Color` object that represents red (red value 255, and 0 for the green and blue values). Line 18 uses `Graphics` method **fillRect** to draw a *filled rectangle* in the current color. Method `fillRect` draws a rectangle based on its four arguments. The first two integer values represent the upper-left *x*-coordinate and upper-left *y*-coordinate, where the `Graphics` object begins drawing the rectangle. The third and fourth arguments are nonnegative integers that represent the width and the height of the rectangle in pixels, respectively. A rectangle drawn using method `fillRect` is filled by the current color of the `Graphics` object.



---

```

1 // Fig. 13.5: ColorJPanel.java
2 // Changing drawing colors.
3 import java.awt.Graphics;
4 import java.awt.Color;
5 import javax.swing.JPanel;
6
7 public class ColorJPanel extends JPanel
8 {
9 // draw rectangles and Strings in different colors
10 @Override
11 public void paintComponent(Graphics g)
12 {
13 super.paintComponent(g);
14 this.setBackground(Color.WHITE);
15
16 // set new drawing color using integers
17 g.setColor(new Color(255, 0, 0));
18 g.fillRect(15, 25, 100, 20);
19 g.drawString("Current RGB: " + g.getColor(), 130, 40);
20
21 // set new drawing color using floats
22 g.setColor(new Color(0.50f, 0.75f, 0.0f));
23 g.fillRect(15, 50, 100, 20);
24 g.drawString("Current RGB: " + g.getColor(), 130, 65);
25
26 // set new drawing color using static Color objects
27 g.setColor(Color.BLUE);
28 g.fillRect(15, 75, 100, 20);
29 g.drawString("Current RGB: " + g.getColor(), 130, 90);
30
31 // display individual RGB values
32 Color color = Color.MAGENTA;
33 g.setColor(color);
34 g.fillRect(15, 100, 100, 20);
35 g.drawString("RGB values: " + color.getRed() + ", " +
36 color.getGreen() + ", " + color.getBlue(), 130, 115);
37 }
38 } // end class ColorJPanel

```

---

**Fig. 13.5** | Changing drawing colors.

---

```

1 // Fig. 13.6: ShowColors.java
2 // Demonstrating Colors.
3 import javax.swing.JFrame;
4
5 public class ShowColors
6 {
7 // execute application
8 public static void main(String[] args)
9 {

```


---

**Fig. 13.6** | Demonstrating Colors. (Part I of 2.)

```

10 // create frame for ColorJPanel
11 JFrame frame = new JFrame("Using colors");
12 frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
13
14 ColorJPanel colorJPanel = new ColorJPanel();
15 frame.add(colorJPanel);
16 frame.setSize(400, 180);
17 frame.setVisible(true);
18 }
19 } // end class ShowColors

```



**Fig. 13.6** | Demonstrating Colors. (Part 2 of 2.)

Line 19 uses Graphics method **drawString** to draw a String in the current color. The expression `g.getColor()` retrieves the current color from the Graphics object. We then concatenate the Color with string "Current RGB: ", resulting in an *implicit* call to class Color's `toString` method. The String representation of a Color contains the class name and package (`java.awt.Color`) and the red, green and blue values.



### Look-and-Feel Observation 13.1

*People perceive colors differently. Choose your colors carefully to ensure that your application is readable, both for people who can perceive color and for those who are color blind. Try to avoid using many different colors in close proximity.*

Lines 22–24 and 27–29 perform the same tasks again. Line 22 uses the Color constructor with three float arguments to create a dark green color (0.50f for red, 0.75f for green and 0.0f for blue). Note the syntax of the values. The letter `f` appended to a floating-point literal indicates that the literal should be treated as type `float`. Recall that by default, floating-point literals are treated as type `double`.

Line 27 sets the current drawing color to one of the predefined Color constants (`Color.BLUE`). The Color constants are static, so they're created when class Color is loaded into memory at execution time.

The statement in lines 35–36 makes calls to Color methods `getRed`, `getGreen` and `getBlue` on the predefined `Color.MAGENTA` constant. Method `main` of class `ShowColors` (lines 8–18 of Fig. 13.6) creates the JFrame that will contain a ColorJPanel object where the colors will be displayed.



### Software Engineering Observation 13.1

*To change the color, you must create a new Color object (or use one of the predefined Color constants). Like String objects, Color objects are immutable (not modifiable).*

The **JColorChooser** component (package `javax.swing`) enables application users to select colors. Figures 13.7–13.8 demonstrate a **JColorChooser** dialog. When you click the **Change Color** button, a **JColorChooser** dialog appears. When you select a color and press the dialog's **OK** button, the background color of the application window changes.

---

```

1 // Fig. 13.7: ShowColors2JFrame.java
2 // Choosing colors with JColorChooser.
3 import java.awt.BorderLayout;
4 import java.awt.Color;
5 import java.awt.event.ActionEvent;
6 import java.awt.event.ActionListener;
7 import javax.swing.JButton;
8 import javax.swing.JFrame;
9 import javax.swing.JColorChooser;
10 import javax.swing.JPanel;
11
12 public class ShowColors2JFrame extends JFrame
13 {
14 private final JButton changeColorJButton;
15 private Color color = Color.LIGHT_GRAY;
16 private final JPanel colorJPanel;
17
18 // set up GUI
19 public ShowColors2JFrame()
20 {
21 super("Using JColorChooser");
22
23 // create JPanel for display color
24 colorJPanel = new JPanel();
25 colorJPanel.setBackground(color);
26
27 // set up changeColorJButton and register its event handler
28 changeColorJButton = new JButton("Change Color");
29 changeColorJButton.addActionListener(
30 new ActionListener() // anonymous inner class
31 {
32 // display JColorChooser when user clicks button
33 @Override
34 public void actionPerformed(ActionEvent event)
35 {
36 color = JColorChooser.showDialog(
37 ShowColors2JFrame.this, "Choose a color", color);
38
39 // set default color, if no color is returned
40 if (color == null)
41 color = Color.LIGHT_GRAY;
42
43 // change content pane's background color
44 colorJPanel.setBackground(color);
45 } // end method actionPerformed
46 } // end anonymous inner class
47); // end call to addActionListener

```

---

**Fig. 13.7** | Choosing colors with **JColorChooser**. (Part I of 2.)

```

48
49 add(colorJPanel, BorderLayout.CENTER);
50 add(changeColorJButton, BorderLayout.SOUTH);
51
52 setSize(400, 130);
53 setVisible(true);
54 } // end ShowColor2JFrame constructor
55 } // end class ShowColors2JFrame

```


**Fig. 13.7** | Choosing colors with JColorChooser. (Part 2 of 2.)

```


1 // Fig. 13.8: ShowColors2.java
2 // Choosing colors with JColorChooser.
3 import javax.swing.JFrame;
4
5 public class ShowColors2
6 {
7 // execute application
8 public static void main(String[] args)
9 {
10 ShowColors2JFrame application = new ShowColors2JFrame();
11 application.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
12 }
13 } // end class ShowColors2

```

(a) Initial application window




(b) JColorChooser window



Select a color from  
one of the color  
swatches

(c) Application window after changing JPanel's background color




**Fig. 13.8** | Choosing colors with JColorChooser.

Class `JColorChooser` provides static method **`showDialog`**, which creates a `JColorChooser` object, attaches it to a dialog box and displays the dialog. Lines 36–37 of Fig. 13.7


invoke this method to display the color-chooser dialog. Method `showDialog` returns the selected `Color` object, or `null` if the user presses **Cancel** or closes the dialog without pressing **OK**. The method takes three arguments—a reference to its parent `Component`, a `String` to display in the title bar of the dialog and the initial selected `Color` for the dialog. The parent component is a reference to the window from which the dialog is displayed (in this case the `JFrame`, with the reference name `frame`). The dialog will be centered on the parent. If the parent is `null`, the dialog is centered on the screen. While the color-chooser dialog is on the screen, the user cannot interact with the parent component until the dialog is dismissed. This type of dialog is called a modal dialog.

After the user selects a color, lines 40–41 determine whether `color` is `null`, and, if so, set `color` to `Color.LIGHT_GRAY`. Line 44 invokes method `setBackground` to change the background color of the `JPanel`. Method `setBackground` is one of the many `Component` methods that can be used on most GUI components. The user can continue to use the **Change Color** button to change the background color of the application. Figure 13.8 contains method `main`, which executes the program.

Figure 13.8(b) shows the default `JColorChooser` dialog that allows the user to select a color from a variety of **color swatches**. There are three tabs across the top of the dialog—**Swatches**, **HSB** and **RGB**. These represent three different ways to select a color. The **HSB** tab allows you to select a color based on **hue**, **saturation** and **brightness**—values that are used to define the amount of light in a color. Visit [http://en.wikipedia.org/wiki/HSL\\_and\\_HSV](http://en.wikipedia.org/wiki/HSL_and_HSV) for more information on HSB. The **RGB** tab allows you to select a color by using sliders to select the red, green and blue components. The **HSB** and **RGB** tabs are shown in Fig. 13.9.



**Fig. 13.9** | HSB and RGB tabs of the `JColorChooser` dialog. (Part 1 of 2.)



**Fig. 13.9** | HSB and RGB tabs of the JColorChooser dialog. (Part 2 of 2.)

## 13.4 Manipulating Fonts

This section introduces methods and constants for manipulating fonts. Most font methods and font constants are part of class `Font`. Some constructors, methods and constants of class `Font` and class `Graphics` are summarized in Fig. 13.10.

| Method or constant                                                    | Description                                                                      |
|-----------------------------------------------------------------------|----------------------------------------------------------------------------------|
| <i>Font constants, constructors and methods</i>                       |                                                                                  |
| <b>public static final int</b> PLAIN                                  | A constant representing a plain font style.                                      |
| <b>public static final int</b> BOLD                                   | A constant representing a bold font style.                                       |
| <b>public static final int</b> ITALIC                                 | A constant representing an italic font style.                                    |
| <b>public</b> <code>Font</code> (String name,<br>int style, int size) | Creates a <code>Font</code> object with the specified font name, style and size. |
| <b>public int</b> <code>getStyle()</code>                             | Returns an <code>int</code> indicating the current font style.                   |
| <b>public int</b> <code>getSize()</code>                              | Returns an <code>int</code> indicating the current font size.                    |
| <b>public String</b> <code>getName()</code>                           | Returns the current font name as a string.                                       |
| <b>public String</b> <code>getFamily()</code>                         | Returns the font's family name as a string.                                      |
| <b>public boolean</b> <code>isPlain()</code>                          | Returns true if the font is plain, else false.                                   |
| <b>public boolean</b> <code>isBold()</code>                           | Returns true if the font is bold, else false.                                    |
| <b>public boolean</b> <code>isItalic()</code>                         | Returns true if the font is italic, else false.                                  |

**Fig. 13.10** | Font-related methods and constants. (Part 1 of 2.)

| Method or constant                             | Description                                                                                 |
|------------------------------------------------|---------------------------------------------------------------------------------------------|
| <i>Graphics methods for manipulating Fonts</i> |                                                                                             |
| <b>public</b> Font <b>getFont</b> ()           | Returns a Font object reference representing the current font.                              |
| <b>public void</b> <b>setFont</b> (Font f)     | Sets the current font to the font, style and size specified by the Font object reference f. |

**Fig. 13.10** | Font-related methods and constants. (Part 2 of 2.)

Class **Font**'s constructor takes three arguments—the **font name**, **font style** and **font size**. The font name is any font currently supported by the system on which the program is running, such as standard Java fonts **Monospaced**, **SansSerif** and **Serif**. The font style is **Font.PLAIN**, **Font.ITALIC** or **Font.BOLD** (each is a static field of class **Font**). Font styles can be used in combination (e.g., **Font.ITALIC** + **Font.BOLD**). The font size is measured in points. A **point** is 1/72 of an inch. Graphics method **setFont** sets the current drawing font—the font in which text will be displayed—to its **Font** argument.



### Portability Tip 13.2

*The number of fonts varies across systems. Java provides five font names—**Serif**, **Monospaced**, **SansSerif**, **Dialog** and **DialogInput**—that can be used on all Java platforms. The Java runtime environment (JRE) on each platform maps these logical font names to actual fonts installed on the platform. The actual fonts used may vary by platform.*

The application of Figs. 13.11–13.12 displays text in four different fonts, with each font in a different size. Figure 13.11 uses the **Font** constructor to initialize **Font** objects (in lines 17, 21, 25 and 30) that are each passed to Graphics method **setFont** to change the drawing font. Each call to the **Font** constructor passes a font name (**Serif**, **Monospaced** or **SansSerif**) as a string, a font style (**Font.PLAIN**, **Font.ITALIC** or **Font.BOLD**) and a font size. Once Graphics method **setFont** is invoked, all text displayed following the call will appear in the new font until the font is changed. Each font's information is displayed in lines 18, 22, 26 and 31–32 using method **drawString**. The coordinates passed to **drawString** correspond to the lower-left corner of the baseline of the font. Line 29 changes the drawing color to red, so the next string displayed appears in red. Lines 31–32 display information about the final **Font** object. Method **getFont** of class **Graphics** returns a **Font** object representing the current font. Method **getName** returns the current font name as a string. Method **getSize** returns the font size in points.



### Software Engineering Observation 13.2

*To change the font, you must create a new **Font** object. Font objects are immutable—class **Font** has no set methods to change the characteristics of the current font.*

Figure 13.12 contains the main method, which creates a **JFrame** to display a **FontJPanel**. We add a **FontJPanel** object to this **JFrame** (line 15), which displays the graphics created in Fig. 13.11.

---

```

1 // Fig. 13.11: FontJPanel.java
2 // Display strings in different fonts and colors.
3 import java.awt.Font;
4 import java.awt.Color;
5 import java.awt.Graphics;
6 import javax.swing.JPanel;
7
8 public class FontJPanel extends JPanel
9 {
10 // display Strings in different fonts and colors
11 @Override
12 public void paintComponent(Graphics g)
13 {
14 super.paintComponent(g);
15
16 // set font to Serif (Times), bold, 12pt and draw a string
17 g.setFont(new Font("Serif", Font.BOLD, 12));
18 g.drawString("Serif 12 point bold.", 20, 30);
19
20 // set font to Monospaced (Courier), italic, 24pt and draw a string
21 g.setFont(new Font("Monospaced", Font.ITALIC, 24));
22 g.drawString("Monospaced 24 point italic.", 20, 50);
23
24 // set font to SansSerif (Helvetica), plain, 14pt and draw a string
25 g.setFont(new Font("SansSerif", Font.PLAIN, 14));
26 g.drawString("SansSerif 14 point plain.", 20, 70);
27
28 // set font to Serif (Times), bold/italic, 18pt and draw a string
29 g.setColor(Color.RED);
30 g.setFont(new Font("Serif", Font.BOLD + Font.ITALIC, 18));
31 g.drawString(g.getFont().getName() + " " + g.getFont().getSize() +
32 " point bold italic.", 20, 90);
33 }
34 } // end class FontJPanel

```

---

**Fig. 13.11** | Display strings in different fonts and colors.

---

```

1 // Fig. 13.12: Fonts.java
2 // Using fonts.
3 import javax.swing.JFrame;
4
5 public class Fonts
6 {
7 // execute application
8 public static void main(String[] args)
9 {
10 // create frame for FontJPanel
11 JFrame frame = new JFrame("Using fonts");
12 frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
13
14 FontJPanel fontJPanel = new FontJPanel();
15 frame.add(fontJPanel);

```

---


**Fig. 13.12** | Using fonts. (Part I of 2.)



```

16 frame.setSize(420, 150);
17 frame.setVisible(true);
18 }
19 } // end class Fonts

```




**Fig. 13.12** | Using fonts. (Part 2 of 2.)

### Font Metrics

Sometimes it's necessary to get information about the current drawing font, such as its name, style and size. Several Font methods used to get font information are summarized in Fig. 13.10. Method **getStyle** returns an integer value representing the current style. The integer value returned is either `Font.PLAIN`, `Font.ITALIC`, `Font.BOLD` or the combination of `Font.ITALIC` and `Font.BOLD`. Method **getFamily** returns the name of the font family to which the current font belongs. The name of the font family is platform specific. Font methods are also available to test the style of the current font, and these too are summarized in Fig. 13.10. Methods **isPlain**, **isBold** and **isItalic** return true if the current font style is plain, bold or italic, respectively.

Figure 13.13 illustrates some of the common **font metrics**, which provide precise information about a font, such as **height**, **descent** (the amount a character dips below the baseline), **ascent** (the amount a character rises above the baseline) and **leading** (the difference between the descent of one line of text and the ascent of the line of text below it—that is, the interline spacing).



**Fig. 13.13** | Font metrics.

Class **FontMetrics** declares several methods for obtaining font metrics. These methods and Graphics method **getFontMetrics** are summarized in Fig. 13.14. The application of Figs. 13.15–13.16 uses the methods of Fig. 13.14 to obtain font metric information for two fonts.

| Method                                                   | Description                                                     |
|----------------------------------------------------------|-----------------------------------------------------------------|
| <i>FontMetrics methods</i>                               |                                                                 |
| <b>public int</b> getAscent()                            | Returns the ascent of a font in points.                         |
| <b>public int</b> getDescent()                           | Returns the descent of a font in points.                        |
| <b>public int</b> getLeading()                           | Returns the leading of a font in points.                        |
| <b>public int</b> getHeight()                            | Returns the height of a font in points.                         |
| <i>Graphics methods for getting a Font's FontMetrics</i> |                                                                 |
| <b>public</b> FontMetrics getFontMetrics()               | Returns the FontMetrics object for the current drawing Font.    |
| <b>public</b> FontMetrics getFontMetrics(Font f)         | Returns the FontMetrics object for the specified Font argument. |

**Fig. 13.14** | FontMetrics and Graphics methods for obtaining font metrics.

```

1 // Fig. 13.15: MetricsJPanel.java
2 // FontMetrics and Graphics methods useful for obtaining font metrics.
3 import java.awt.Font;
4 import java.awt.FontMetrics;
5 import java.awt.Graphics;
6 import javax.swing.JPanel;
7
8 public class MetricsJPanel extends JPanel
9 {
10 // display font metrics
11 @Override
12 public void paintComponent(Graphics g)
13 {
14 super.paintComponent(g);
15
16 g.setFont(new Font("SansSerif", Font.BOLD, 12));
17 FontMetrics metrics = g.getFontMetrics();
18 g.drawString("Current font: " + g.getFont(), 10, 30);
19 g.drawString("Ascent: " + metrics.getAscent(), 10, 45);
20 g.drawString("Descent: " + metrics.getDescent(), 10, 60);
21 g.drawString("Height: " + metrics.getHeight(), 10, 75);
22 g.drawString("Leading: " + metrics.getLeading(), 10, 90);
23
24 Font font = new Font("Serif", Font.ITALIC, 14);
25 metrics = g.getFontMetrics(font);
26 g.setFont(font);
27 g.drawString("Current font: " + font, 10, 120);
28 g.drawString("Ascent: " + metrics.getAscent(), 10, 135);
29 g.drawString("Descent: " + metrics.getDescent(), 10, 150);
30 g.drawString("Height: " + metrics.getHeight(), 10, 165);
31 g.drawString("Leading: " + metrics.getLeading(), 10, 180);
32 }
33 } // end class MetricsJPanel

```

**Fig. 13.15** | FontMetrics and Graphics methods useful for obtaining font metrics.


---

```

1 // Fig. 13.16: Metrics.java
2 // Displaying font metrics.
3 import javax.swing.JFrame;
4
5 public class Metrics
6 {
7 // execute application
8 public static void main(String[] args)
9 {
10 // create frame for MetricsJPanel
11 JFrame frame = new JFrame("Demonstrating FontMetrics");
12 frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
13
14 MetricsJPanel metricsJPanel = new MetricsJPanel();
15 frame.add(metricsJPanel);
16 frame.setSize(510, 240);
17 frame.setVisible(true);
18 }
19 } // end class Metrics

```

---



**Fig. 13.16** | Displaying font metrics.

---

Line 16 of Fig. 13.15 creates and sets the current drawing font to a `SansSerif`, bold, 12-point font. Line 17 uses `Graphics` method `getFontMetrics` to obtain the `FontMetrics` object for the current font. Line 18 outputs the `String` representation of the `Font` returned by `g.getFont()`. Lines 19–22 use `FontMetric` methods to obtain the ascent, descent, height and leading for the font.

Line 24 creates a new `Serif`, italic, 14-point font. Line 25 uses a second version of `Graphics` method `getFontMetrics`, which accepts a `Font` argument and returns a corresponding `FontMetrics` object. Lines 28–31 obtain the ascent, descent, height and leading for the font. The font metrics are slightly different for the two fonts.

## 13.5 Drawing Lines, Rectangles and Ovals

This section presents `Graphics` methods for drawing lines, rectangles and ovals. The methods and their parameters are summarized in Fig. 13.17. For each drawing method that requires a width and height parameter, the width and height must be nonnegative values. Otherwise, the shape will not display.

| Method                                                                                                                                        | Description                                                                                                                                                                                                                                                                                  |
|-----------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <b>public void</b> drawLine( <b>int</b> x1, <b>int</b> y1, <b>int</b> x2, <b>int</b> y2)                                                      | Draws a line between the point (x1, y1) and the point (x2, y2).                                                                                                                                                                                                                              |
| <b>public void</b> drawRect( <b>int</b> x, <b>int</b> y, <b>int</b> width, <b>int</b> height)                                                 | Draws a rectangle of the specified width and height. The rectangle's top-left corner is located at (x, y). Only the outline of the rectangle is drawn using the Graphics object's color—the body of the rectangle is not filled with this color.                                             |
| <b>public void</b> fillRect( <b>int</b> x, <b>int</b> y, <b>int</b> width, <b>int</b> height)                                                 | Draws a filled rectangle in the current color with the specified width and height. The rectangle's top-left corner is located at (x, y).                                                                                                                                                     |
| <b>public void</b> clearRect( <b>int</b> x, <b>int</b> y, <b>int</b> width, <b>int</b> height)                                                | Draws a filled rectangle with the specified width and height in the current background color. The rectangle's <i>top-left</i> corner is located at (x, y). This method is useful if you want to remove a portion of an image.                                                                |
| <b>public void</b> drawRoundRect( <b>int</b> x, <b>int</b> y, <b>int</b> width, <b>int</b> height, <b>int</b> arcWidth, <b>int</b> arcHeight) | Draws a rectangle with rounded corners in the current color with the specified width and height. The arcWidth and arcHeight determine the rounding of the corners (see Fig. 13.20). Only the outline of the shape is drawn.                                                                  |
| <b>public void</b> fillRoundRect( <b>int</b> x, <b>int</b> y, <b>int</b> width, <b>int</b> height, <b>int</b> arcWidth, <b>int</b> arcHeight) | Draws a filled rectangle in the current color with rounded corners with the specified width and height. The arcWidth and arcHeight determine the rounding of the corners (see Fig. 13.20).                                                                                                   |
| <b>public void</b> draw3DRect( <b>int</b> x, <b>int</b> y, <b>int</b> width, <b>int</b> height, <b>boolean</b> b)                             | Draws a three-dimensional rectangle in the current color with the specified width and height. The rectangle's <i>top-left</i> corner is located at (x, y). The rectangle appears raised when b is true and lowered when b is false. Only the outline of the shape is drawn.                  |
| <b>public void</b> fill3DRect( <b>int</b> x, <b>int</b> y, <b>int</b> width, <b>int</b> height, <b>boolean</b> b)                             | Draws a filled three-dimensional rectangle in the current color with the specified width and height. The rectangle's <i>top-left</i> corner is located at (x, y). The rectangle appears raised when b is true and lowered when b is false.                                                   |
| <b>public void</b> drawOval( <b>int</b> x, <b>int</b> y, <b>int</b> width, <b>int</b> height)                                                 | Draws an oval in the current color with the specified width and height. The bounding rectangle's <i>top-left</i> corner is located at (x, y). The oval touches all four sides of the bounding rectangle at the center of each side (see Fig. 13.21). Only the outline of the shape is drawn. |
| <b>public void</b> fillOval( <b>int</b> x, <b>int</b> y, <b>int</b> width, <b>int</b> height)                                                 | Draws a filled oval in the current color with the specified width and height. The bounding rectangle's <i>top-left</i> corner is located at (x, y). The oval touches the center of all four sides of the bounding rectangle (see Fig. 13.21).                                                |

**Fig. 13.17** | Graphics methods that draw lines, rectangles and ovals.

The application of Figs. 13.18–13.19 demonstrates drawing a variety of lines, rectangles, three-dimensional rectangles, rounded rectangles and ovals. In Fig. 13.18, line 17 draws a red line, line 20 draws an empty blue rectangle and line 21 draws a filled blue rectangle. Methods **fillRoundRect** (line 24) and **drawRoundRect** (line 25) draw rectangles with rounded corners. Their first two arguments specify the coordinates of the upper-left corner of the **bounding rectangle**—the area in which the rounded rectangle will be drawn. The upper-left corner coordinates are *not* the edge of the rounded rectangle, but the coordinates where the edge would be if the rectangle had square corners. The third and fourth arguments specify the width and height of the rectangle. The last two arguments determine the horizontal and vertical diameters of the arc (i.e., the arc width and arc height) used to represent the corners.

Figure 13.20 labels the arc width, arc height, width and height of a rounded rectangle. Using the same value for the arc width and arc height produces a quarter-circle at each

---

```

1 // Fig. 13.18: LinesRectsOvalsJPanel.java
2 // Drawing lines, rectangles and ovals.
3 import java.awt.Color;
4 import java.awt.Graphics;
5 import javax.swing.JPanel;
6
7 public class LinesRectsOvalsJPanel extends JPanel
8 {
9 // display various lines, rectangles and ovals
10 @Override
11 public void paintComponent(Graphics g)
12 {
13 super.paintComponent(g);
14 this.setBackground(Color.WHITE);
15
16 g.setColor(Color.RED);
17 g.drawLine(5, 30, 380, 30);
18
19 g.setColor(Color.BLUE);
20 g.drawRect(5, 40, 90, 55);
21 g.fillRect(100, 40, 90, 55);
22
23 g.setColor(Color.CYAN);
24 g.fillRoundRect(195, 40, 90, 55, 50, 50);
25 g.drawRoundRect(290, 40, 90, 55, 20, 20);
26
27 g.setColor(Color.GREEN);
28 g.draw3DRect(5, 100, 90, 55, true);
29 g.fill3DRect(100, 100, 90, 55, false);
30
31 g.setColor(Color.MAGENTA);
32 g.drawOval(195, 100, 90, 55);
33 g.fillOval(290, 100, 90, 55);
34 }
35 } // end class LinesRectsOvalsJPanel

```


---

**Fig. 13.18** | Drawing lines, rectangles and ovals.


```

1 // Fig. 13.19: LinesRectsOvals.java
2 // Testing LinesRectsOvalsJPanel.
3 import java.awt.Color;
4 import javax.swing.JFrame;
5
6 public class LinesRectsOvals
7 {
8 // execute application
9 public static void main(String[] args)
10 {
11 // create frame for LinesRectsOvalsJPanel
12 JFrame frame =
13 new JFrame("Drawing lines, rectangles and ovals");
14 frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
15
16 LinesRectsOvalsJPanel linesRectsOvalsJPanel =
17 new LinesRectsOvalsJPanel();
18 linesRectsOvalsJPanel.setBackground(Color.WHITE);
19 frame.add(linesRectsOvalsJPanel);
20 frame.setSize(400, 210);
21 frame.setVisible(true);
22 }
23 } // end class LinesRectsOvals

```



**Fig. 13.19** | Testing LinesRectsOvalsJPanel.




**Fig. 13.20** | Arc width and arc height for rounded rectangles.

corner. When the arc width, arc height, width and height have the same values, the result is a circle. If the values for width and height are the same and the values of arcWidth and arcHeight are 0, the result is a square.

Methods **draw3DRect** (Fig. 13.18, line 28) and **fill3DRect** (line 29) take the same arguments. The first two specify the *top-left* corner of the rectangle. The next two arguments specify the width and height of the rectangle, respectively. The last argument determines whether the rectangle is **raised** (*true*) or **lowered** (*false*). The three-dimensional effect of **draw3DRect** appears as two edges of the rectangle in the original color and two edges in a slightly darker color. The three-dimensional effect of **fill3DRect** appears as two edges of the rectangle in the original drawing color and the fill and other two edges in a slightly darker color. Raised rectangles have the original drawing color edges at the top and left of the rectangle. Lowered rectangles have the original drawing color edges at the bottom and right of the rectangle. The three-dimensional effect is difficult to see in some colors.


Methods **drawOval** and **fillOval** (lines 32–33) take the same four arguments. The first two specify the top-left coordinate of the bounding rectangle that contains the oval. The last two specify the width and height of the bounding rectangle, respectively. Figure 13.21 shows an oval bounded by a rectangle. The oval touches the *center* of all four sides of the bounding rectangle. (The bounding rectangle is *not* displayed on the screen.)



**Fig. 13.21** | Oval bounded by a rectangle.

## 13.6 Drawing Arcs

An **arc** is drawn as a portion of an oval. Arc angles are measured in degrees. Arcs **sweep** (i.e., move along a curve) from a **starting angle** through the number of degrees specified by their **arc angle**. The starting angle indicates in degrees where the arc begins. The arc angle specifies the total number of degrees through which the arc sweeps. Figure 13.22 illustrates two arcs. The left set of axes shows an arc sweeping from zero degrees to approximately 110 degrees. Arcs that sweep in a *counterclockwise* direction are measured in **positive degrees**. The set of axes on the right shows an arc sweeping from zero degrees to approximately -110 degrees. Arcs that sweep in a *clockwise* direction are measured in **negative degrees**. Note the dashed boxes around the arcs in Fig. 13.22. When drawing an arc, we specify a bounding rectangle for an oval. The arc will sweep along part of the oval. Graphics methods **drawArc** and **fillArc** for drawing arcs are summarized in Fig. 13.23.

**Fig. 13.22** | Positive and negative arc angles.

| Method                                                                                        | Description                                                                                                                                                                                                              |
|-----------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <b>public void drawArc(int x, int y, int width, int height, int startAngle, int arcAngle)</b> | Draws an arc relative to the bounding rectangle's top-left x- and y-coordinates with the specified width and height. The arc segment is drawn starting at startAngle and sweeps arcAngle degrees.                        |
| <b>public void fillArc(int x, int y, int width, int height, int startAngle, int arcAngle)</b> | Draws a filled arc (i.e., a sector) relative to the bounding rectangle's top-left x- and y-coordinates with the specified width and height. The arc segment is drawn starting at startAngle and sweeps arcAngle degrees. |

**Fig. 13.23** | Graphics methods for drawing arcs.

Figures 13.24–13.25 demonstrate the arc methods of Fig. 13.23. The application draws six arcs (three unfilled and three filled). To illustrate the bounding rectangle that helps determine where the arc appears, the first three arcs are displayed inside a red rectangle that has the same x, y, width and height arguments as the arcs.

```

1 // Fig. 13.24: ArcsJPanel.java
2 // Arcs displayed with drawArc and fillArc.
3 import java.awt.Color;
4 import java.awt.Graphics;
5 import javax.swing.JPanel;
6
7 public class ArcsJPanel extends JPanel
8 {
9 // draw rectangles and arcs
10 @Override
11 public void paintComponent(Graphics g)
12 {
13 super.paintComponent(g);
14 }

```

**Fig. 13.24** | Arcs displayed with drawArc and fillArc. (Part 1 of 2.)



---

```

15 // start at 0 and sweep 360 degrees
16 g.setColor(Color.RED);
17 g.drawRect(15, 35, 80, 80);
18 g.setColor(Color.BLACK);
19 g.drawArc(15, 35, 80, 80, 0, 360);
20
21 // start at 0 and sweep 110 degrees
22 g.setColor(Color.RED);
23 g.drawRect(100, 35, 80, 80);
24 g.setColor(Color.BLACK);
25 g.drawArc(100, 35, 80, 80, 0, 110);
26
27 // start at 0 and sweep -270 degrees
28 g.setColor(Color.RED);
29 g.drawRect(185, 35, 80, 80);
30 g.setColor(Color.BLACK);
31 g.drawArc(185, 35, 80, 80, 0, -270);
32
33 // start at 0 and sweep 360 degrees
34 g.fillArc(15, 120, 80, 40, 0, 360);
35
36 // start at 270 and sweep -90 degrees
37 g.fillArc(100, 120, 80, 40, 270, -90);
38
39 // start at 0 and sweep -270 degrees
40 g.fillArc(185, 120, 80, 40, 0, -270);
41 }
42 } // end class ArcsJPanel

```

---

**Fig. 13.24** | Arcs displayed with drawArc and fillArc. (Part 2 of 2.)

---


```

1 // Fig. 13.25: DrawArcs.java
2 // Drawing arcs.
3 import javax.swing.JFrame;
4
5 public class DrawArcs
6 {
7 // execute application
8 public static void main(String[] args)
9 {
10 // create frame for ArcsJPanel
11 JFrame frame = new JFrame("Drawing Arcs");
12 frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
13
14 ArcsJPanel arcsJPanel = new ArcsJPanel();
15 frame.add(arcsJPanel);
16 frame.setSize(300, 210);
17 frame.setVisible(true);
18 }
19 } // end class DrawArcs

```

---

**Fig. 13.25** | Drawing arcs. (Part 1 of 2.)



**Fig. 13.25** | Drawing arcs. (Part 2 of 2.)

## 13.7 Drawing Polygons and Polylines

**Polygons** are *closed multisided shapes* composed of straight-line segments. **Polylines** are *sequences of connected points*. Figure 13.26 discusses methods for drawing polygons and polylines. Some methods require a **Polygon** object (package `java.awt`). Class **Polygon**'s constructors are also described in Fig. 13.26. The application of Figs. 13.27–13.28 draws polygons and polylines.

| Method                                                                                            | Description                                                                                                                                                                                                                                                                                                                                                                                             |
|---------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <i>Graphics methods for drawing polygons</i>                                                      |                                                                                                                                                                                                                                                                                                                                                                                                         |
| <b>public void</b> drawPolygon( <b>int</b> [] xPoints, <b>int</b> [] yPoints, <b>int</b> points)  | Draws a polygon. The <i>x</i> -coordinate of each point is specified in the xPoints array and the <i>y</i> -coordinate of each point in the yPoints array. The last argument specifies the number of points. This method draws a <i>closed polygon</i> . If the last point is different from the first, the polygon is <i>closed</i> by a line that connects the last point to the first.               |
| <b>public void</b> drawPolyline( <b>int</b> [] xPoints, <b>int</b> [] yPoints, <b>int</b> points) | Draws a sequence of connected lines. The <i>x</i> -coordinate of each point is specified in the xPoints array and the <i>y</i> -coordinate of each point in the yPoints array. The last argument specifies the number of points. If the last point is different from the first, the polyline is <i>not</i> closed.                                                                                      |
| <b>public void</b> drawPolygon(Polygon p)                                                         | Draws the specified polygon.                                                                                                                                                                                                                                                                                                                                                                            |
| <b>public void</b> fillPolygon( <b>int</b> [] xPoints, <b>int</b> [] yPoints, <b>int</b> points)  | Draws a <i>filled</i> polygon. The <i>x</i> -coordinate of each point is specified in the xPoints array and the <i>y</i> -coordinate of each point in the yPoints array. The last argument specifies the number of points. This method draws a <i>closed polygon</i> . If the last point is different from the first, the polygon is <i>closed</i> by a line that connects the last point to the first. |
| <b>public void</b> fillPolygon(Polygon p)                                                         | Draws the specified <i>filled</i> polygon. The polygon is <i>closed</i> .                                                                                                                                                                                                                                                                                                                               |

**Fig. 13.26** | Graphics methods for polygons and class **Polygon** methods. (Part 1 of 2.)

| Method                                                                  | Description                                                                                                                                                                        |
|-------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <i>Polygon constructors and methods</i>                                 |                                                                                                                                                                                    |
| <b>public</b> Polygon()                                                 | Constructs a new polygon object. The polygon does not contain any points.                                                                                                          |
| <b>public</b> Polygon(int[] xValues, int[] yValues, int numberOfPoints) | Constructs a new polygon object. The polygon has numberOfPoints sides, with each point consisting of an <i>x</i> -coordinate from xValues and a <i>y</i> -coordinate from yValues. |
| <b>public void</b> addPoint(int x, int y)                               | Adds pairs of <i>x</i> - and <i>y</i> -coordinates to the Polygon.                                                                                                                 |

**Fig. 13.26** | Graphics methods for polygons and class Polygon methods. (Part 2 of 2.)

```

1 // Fig. 13.27: PolygonsJPanel.java
2 // Drawing polygons.
3 import java.awt.Graphics;
4 import java.awt.Polygon;
5 import javax.swing.JPanel;
6
7 public class PolygonsJPanel extends JPanel
8 {
9 // draw polygons and polylines
10 @Override
11 public void paintComponent(Graphics g)
12 {
13 super.paintComponent(g);
14
15 // draw polygon with Polygon object
16 int[] xValues = {20, 40, 50, 30, 20, 15};
17 int[] yValues = {50, 50, 60, 80, 80, 60};
18 Polygon polygon1 = new Polygon(xValues, yValues, 6);
19 g.drawPolygon(polygon1);
20
21 // draw polylines with two arrays
22 int[] xValues2 = {70, 90, 100, 80, 70, 65, 60};
23 int[] yValues2 = {100, 100, 110, 110, 130, 110, 90};
24 g.drawPolyline(xValues2, yValues2, 7);
25
26 // fill polygon with two arrays
27 int[] xValues3 = {120, 140, 150, 190};
28 int[] yValues3 = {40, 70, 80, 60};
29 g.fillPolygon(xValues3, yValues3, 4);
30
31 // draw filled polygon with Polygon object
32 Polygon polygon2 = new Polygon();
33 polygon2.addPoint(165, 135);
34 polygon2.addPoint(175, 150);
35 polygon2.addPoint(270, 200);

```

**Fig. 13.27** | Polygons displayed with drawPolygon and fillPolygon. (Part 1 of 2.)

```

36 polygon2.addPoint(200, 220);
37 polygon2.addPoint(130, 180);
38 g.fillPolygon(polygon2);
39 }
40 } // end class PolygonsJPanel


```

**Fig. 13.27** | Polygons displayed with `drawPolygon` and `fillPolygon`. (Part 2 of 2.)

```

1 // Fig. 13.28: DrawPolygons.java
2 // Drawing polygons.
3 import javax.swing.JFrame;
4
5 public class DrawPolygons
6 {
7 // execute application
8 public static void main(String[] args)
9 {
10 // create frame for PolygonsJPanel
11 JFrame frame = new JFrame("Drawing Polygons");
12 frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
13
14 PolygonsJPanel polygonsJPanel = new PolygonsJPanel();
15 frame.add(polygonsJPanel);
16 frame.setSize(280, 270);
17 frame.setVisible(true);
18 }
19 } // end class DrawPolygons

```



**Fig. 13.28** | Drawing polygons.

Lines 16–17 of Fig. 13.27 create two `int` arrays and use them to specify the points for Polygon `polygon1`. The Polygon constructor call in line 18 receives array `xValues`, which contains the *x*-coordinate of each point; array `yValues`, which contains the *y*-coordinate of each point; and 6 (the number of points in the polygon). Line 19 displays `polygon1` by passing it as an argument to Graphics method **`drawPolygon`**.

Lines 22–23 create two `int` arrays and use them to specify the points for a series of connected lines. Array `xValues2` contains the *x*-coordinate of each point and array `yValues2` the *y*-coordinate of each point. Line 24 uses Graphics method **`drawPolyline`** to

display the series of connected lines specified with the arguments `xValues2`, `yValues2` and 7 (the number of points).

Lines 27–28 create two `int` arrays and use them to specify the points of a polygon. Array `xValues3` contains the *x*-coordinate of each point and array `yValues3` the *y*-coordinate of each point. Line 29 displays a polygon by passing to `Graphics` method **`fillPolygon`** the two arrays (`xValues3` and `yValues3`) and the number of points to draw (4).



### Common Programming Error 13.1

*An `ArrayIndexOutOfBoundsException` is thrown if the number of points specified in the third argument to method `drawPolygon` or method `fillPolygon` is greater than the number of elements in the arrays of coordinates that specify the polygon to display.*

Line 32 creates `Polygon polygon2` with no points. Lines 33–37 use `Polygon` method **`addPoint`** to add pairs of *x*- and *y*-coordinates to the `Polygon`. Line 38 displays `Polygon polygon2` by passing it to `Graphics` method `fillPolygon`.

## 13.8 Java 2D API

The **Java 2D API** provides advanced two-dimensional graphics capabilities for programmers who require detailed and complex graphical manipulations. The API includes features for processing line art, text and images in packages `java.awt`, `java.awt.image`, `java.awt.color`, `java.awt.font`, `java.awt.geom`, `java.awt.print` and `java.awt.image.renderable`. The capabilities of the API are far too broad to cover in this textbook. For an overview, visit <http://docs.oracle.com/javase/7/docs/technotes/guides/2d/>. In this section, we overview several Java 2D capabilities.

Drawing with the Java 2D API is accomplished with a **`Graphics2D`** reference (package `java.awt`). `Graphics2D` is an *abstract subclass* of class `Graphics`, so it has all the graphics capabilities demonstrated earlier in this chapter. In fact, the actual object used to draw in every `paintComponent` method is an instance of a *subclass* of `Graphics2D` that is passed to method `paintComponent` and accessed via the *superclass* `Graphics`. To access `Graphics2D` capabilities, we must cast the `Graphics` reference (`g`) passed to `paintComponent` into a `Graphics2D` reference with a statement such as

```
Graphics2D g2d = (Graphics2D) g;
```

The next two examples use this technique.

### *Lines, Rectangles, Round Rectangles, Arcs and Ellipses*

This example demonstrates several Java 2D shapes from package `java.awt.geom`, including **`Line2D.Double`**, **`Rectangle2D.Double`**, **`RoundRectangle2D.Double`**, **`Arc2D.Double`** and **`Ellipse2D.Double`**. Note the syntax of each class name. Each class represents a shape with dimensions specified as `double` values. There's a *separate* version of each represented with `float` values (e.g., **`Ellipse2D.Float`**). In each case, `Double` is a `public static` nested class of the class specified to the left of the dot (e.g., `Ellipse2D`). To use the `static` nested class, we simply qualify its name with the outer-class name.

In Figs. 13.29–13.30, we draw Java 2D shapes and modify their drawing characteristics, such as changing line thickness, filling shapes with patterns and drawing dashed lines. These are just a few of the many capabilities provided by Java 2D.

Line 25 of Fig. 13.29 casts the Graphics reference received by paintComponent to a Graphics2D reference and assigns it to g2d to allow access to the Java 2D features.

---

```

1 // Fig. 13.29: ShapesJPanel.java
2 // Demonstrating some Java 2D shapes.
3 import java.awt.Color;
4 import java.awt.Graphics;
5 import java.awt.BasicStroke;
6 import java.awt.GradientPaint;
7 import java.awt.TexturePaint;
8 import java.awt.Rectangle;
9 import java.awt.Graphics2D;
10 import java.awt.geom.Ellipse2D;
11 import java.awt.geom.Rectangle2D;
12 import java.awt.geom.RoundRectangle2D;
13 import java.awt.geom.Arc2D;
14 import java.awt.geom.Line2D;
15 import java.awt.image.BufferedImage;
16 import javax.swing.JPanel;
17
18 public class ShapesJPanel extends JPanel
19 {
20 // draw shapes with Java 2D API
21 @Override
22 public void paintComponent(Graphics g)
23 {
24 super.paintComponent(g);
25 Graphics2D g2d = (Graphics2D) g; // cast g to Graphics2D
26
27 // draw 2D ellipse filled with a blue-yellow gradient
28 g2d.setPaint(new GradientPaint(5, 30, Color.BLUE, 35, 100,
29 Color.YELLOW, true));
30 g2d.fill(new Ellipse2D.Double(5, 30, 65, 100));
31
32 // draw 2D rectangle in red
33 g2d.setPaint(Color.RED);
34 g2d.setStroke(new BasicStroke(10.0f));
35 g2d.draw(new Rectangle2D.Double(80, 30, 65, 100));
36
37 // draw 2D rounded rectangle with a buffered background
38 BufferedImage buffImage = new BufferedImage(10, 10,
39 BufferedImage.TYPE_INT_RGB);
40
41 // obtain Graphics2D from buffImage and draw on it
42 Graphics2D gg = buffImage.createGraphics();
43 gg.setColor(Color.YELLOW);
44 gg.fillRect(0, 0, 10, 10);
45 gg.setColor(Color.BLACK);
46 gg.drawRect(1, 1, 6, 6);
47 gg.setColor(Color.BLUE);
48 gg.fillRect(1, 1, 3, 3);
49 gg.setColor(Color.RED);

```

---

**Fig. 13.29** | Demonstrating some Java 2D shapes. (Part I of 2.)

---

```

50 gg.fillRect(4, 4, 3, 3); // draw a filled rectangle
51
52 // paint buffImage onto the JFrame
53 g2d.setPaint(new TexturePaint(buffImage,
54 new Rectangle(10, 10)));
55 g2d.fill(
56 new RoundRectangle2D.Double(155, 30, 75, 100, 50, 50));
57
58 // draw 2D pie-shaped arc in white
59 g2d.setPaint(Color.WHITE);
60 g2d.setStroke(new BasicStroke(6.0f));
61 g2d.draw(
62 new Arc2D.Double(240, 30, 75, 100, 0, 270, Arc2D.PIE));
63
64 // draw 2D lines in green and yellow
65 g2d.setPaint(Color.GREEN);
66 g2d.draw(new Line2D.Double(395, 30, 320, 150));
67
68 // draw 2D line using stroke
69 float[] dashes = {10}; // specify dash pattern
70 g2d.setPaint(Color.YELLOW);
71 g2d.setStroke(new BasicStroke(4, BasicStroke.CAP_ROUND,
72 BasicStroke.JOIN_ROUND, 10, dashes, 0));
73 g2d.draw(new Line2D.Double(320, 30, 395, 150));
74 }
75 } // end class ShapesJPanel

```

---

**Fig. 13.29** | Demonstrating some Java 2D shapes. (Part 2 of 2.)

---


```

1 // Fig. 13.30: Shapes.java
2 // Testing ShapesJPanel.
3 import javax.swing.JFrame;
4
5 public class Shapes
6 {
7 // execute application
8 public static void main(String[] args)
9 {
10 // create frame for ShapesJPanel
11 JFrame frame = new JFrame("Drawing 2D shapes");
12 frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
13
14 // create ShapesJPanel
15 ShapesJPanel shapesJPanel = new ShapesJPanel();
16
17 frame.add(shapesJPanel);
18 frame.setSize(425, 200);
19 frame.setVisible(true);
20 }
21 } // end class Shapes

```

---

**Fig. 13.30** | Testing ShapesJPanel. (Part 1 of 2.)



**Fig. 13.30** | Testing ShapesJPanel. (Part 2 of 2.)

### *Ovals, Gradient Fills and Paint Objects*

The first shape we draw is an *oval filled with gradually changing colors*. Lines 28–29 invoke Graphics2D method **setPaint** to set the **Paint** object that determines the color for the shape to display. A Paint object implements interface `java.awt.Paint`. It can be something as simple as one of the predeclared `Color` objects introduced in Section 13.3 (class `Color` implements `Paint`), or it can be an instance of the Java 2D API's `GradientPaint`, `SystemColor`, `TexturePaint`, `LinearGradientPaint` or `RadialGradientPaint` classes. In this case, we use a `GradientPaint` object.

Class `GradientPaint` helps draw a shape in *gradually changing colors*—called a **gradient**. The `GradientPaint` constructor used here requires seven arguments. The first two specify the starting coordinates for the gradient. The third specifies the starting `Color` for the gradient. The fourth and fifth specify the ending coordinates for the gradient. The sixth specifies the ending `Color` for the gradient. The last argument specifies whether the gradient is **cyclic** (`true`) or **acyclic** (`false`). The two sets of coordinates determine the direction of the gradient. Because the second coordinate (35, 100) is down and to the right of the first coordinate (5, 30), the gradient goes down and to the right at an angle. Because this gradient is cyclic (`true`), the color starts with blue, gradually becomes yellow, then gradually returns to blue. If the gradient is acyclic, the color transitions from the first color specified (e.g., blue) to the second color (e.g., yellow).

Line 30 uses Graphics2D method **fill** to draw a filled **Shape** object—an object that implements interface `Shape` (package `java.awt`). In this case, we display an `Ellipse2D.Double` object. The `Ellipse2D.Double` constructor receives four arguments specifying the *bounding rectangle* for the ellipse to display.

### *Rectangles, Strokes*

Next we draw a red rectangle with a thick border. Line 33 invokes `setPaint` to set the Paint object to `Color.RED`. Line 34 uses Graphics2D method **setStroke** to set the characteristics of the rectangle's border (or the lines for any other shape). Method `setStroke` requires as its argument an object that implements interface **Stroke** (package `java.awt`). In this case, we use an instance of class `BasicStroke`. Class `BasicStroke` provides several constructors to specify the width of the line, how the line ends (called the **end caps**), how lines join together (called **line joins**) and the dash attributes of the line (if it's a dashed line). The constructor here specifies that the line should be 10 pixels wide.

Line 35 uses Graphics2D method **draw** to draw a **Shape** object—in this case, a `Rectangle2D.Double`. The `Rectangle2D.Double` constructor receives arguments specifying the rectangle's *upper-left x-coordinate*, *upper-left y-coordinate*, *width* and *height*.



### *Rounded Rectangles, BufferedImages and TexturePaint Objects*

Next we draw a rounded rectangle filled with a pattern created in a **BufferedImage** (package `java.awt.image`) object. Lines 38–39 create the **BufferedImage** object. Class **BufferedImage** can be used to produce images in color and grayscale. This particular **BufferedImage** is 10 pixels wide and 10 pixels tall (as specified by the first two arguments of the constructor). The third argument **BufferedImage.TYPE\_INT\_RGB** indicates that the image is stored in color using the RGB color scheme.

To create the rounded rectangle's fill pattern, we must first draw into the **BufferedImage**. Line 42 creates a **Graphics2D** object (by calling **BufferedImage** method **createGraphics**) that can be used to draw into the **BufferedImage**. Lines 43–50 use methods **setColor**, **fillRect** and **drawRect** to create the pattern.

Lines 53–54 set the **Paint** object to a new **TexturePaint** (package `java.awt`) object. A **TexturePaint** object uses the image stored in its associated **BufferedImage** (the first constructor argument) as the fill texture for a filled-in shape. The second argument specifies the **Rectangle** area from the **BufferedImage** that will be replicated through the texture. In this case, the **Rectangle** is the same size as the **BufferedImage**. However, a smaller portion of the **BufferedImage** can be used.

Lines 55–56 use **Graphics2D** method **fill** to draw a filled **Shape** object—in this case, a **RoundRectangle2D.Double**. The constructor for class **RoundRectangle2D.Double** receives six arguments specifying the rectangle dimensions and the arc width and arc height used to determine the rounding of the corners.

### *Arcs*

Next we draw a pie-shaped arc with a thick white line. Line 59 sets the **Paint** object to **Color.WHITE**. Line 60 sets the **Stroke** object to a new **BasicStroke** for a line 6 pixels wide. Lines 61–62 use **Graphics2D** method **draw** to draw a **Shape** object—in this case, an **Arc2D.Double**. The **Arc2D.Double** constructor's first four arguments specify the upper-left *x*-coordinate, upper-left *y*-coordinate, width and height of the bounding rectangle for the arc. The fifth argument specifies the start angle. The sixth argument specifies the arc angle. The last argument specifies how the arc is *closed*. Constant **Arc2D.PIE** indicates that the arc is *closed* by drawing two lines—one line from the arc's starting point to the center of the bounding rectangle and one line from the center of the bounding rectangle to the ending point. Class **Arc2D** provides two other static constants for specifying how the arc is *closed*. Constant **Arc2D.CHORD** draws a line from the starting point to the ending point. Constant **Arc2D.OPEN** specifies that the arc should *not* be *closed*.

### *Lines*

Finally, we draw two lines using **Line2D** objects—one solid and one dashed. Line 65 sets the **Paint** object to **Color.GREEN**. Line 66 uses **Graphics2D** method **draw** to draw a **Shape** object—in this case, an instance of class **Line2D.Double**. The **Line2D.Double** constructor's arguments specify the starting coordinates and ending coordinates of the line.

Line 69 declares a one-element **float** array containing the value 10. This array describes the dashes in the dashed line. In this case, each dash will be 10 pixels long. To create dashes of different lengths in a pattern, simply provide the length of each dash as an element in the array. Line 70 sets the **Paint** object to **Color.YELLOW**. Lines 71–72 set the **Stroke** object to a new **BasicStroke**. The line will be 4 pixels wide and will have rounded ends (**BasicStroke.CAP\_ROUND**). If lines join together (as in a rectangle at the corners),

their joining will be rounded (**BasicStroke.JOIN\_ROUND**). The dashes argument specifies the dash lengths for the line. The last argument indicates the starting index in the dashes array for the first dash in the pattern. Line 73 then draws a line with the current **Stroke**.

### *Creating Your Own Shapes with General Paths*

Next we present a **general path**—a shape constructed from straight lines and complex curves. A general path is represented with an object of class **GeneralPath** (package `java.awt.geom`). The application of Figs. 13.31 and 13.32 demonstrates drawing a general path in the shape of a five-pointed star.

---

```

1 // Fig. 13.31: Shapes2JPanel.java
2 // Demonstrating a general path.
3 import java.awt.Color;
4 import java.awt.Graphics;
5 import java.awt.Graphics2D;
6 import java.awt.geom.GeneralPath;
7 import java.security.SecureRandom;
8 import javax.swing.JPanel;
9
10 public class Shapes2JPanel extends JPanel
11 {
12 // draw general paths
13 @Override
14 public void paintComponent(Graphics g)
15 {
16 super.paintComponent(g);
17 SecureRandom random = new SecureRandom();
18
19 int[] xPoints = {55, 67, 109, 73, 83, 55, 27, 37, 1, 43};
20 int[] yPoints = {0, 36, 36, 54, 96, 72, 96, 54, 36, 36};
21
22 Graphics2D g2d = (Graphics2D) g;
23 GeneralPath star = new GeneralPath();
24
25 // set the initial coordinate of the General Path
26 star.moveTo(xPoints[0], yPoints[0]);
27
28 // create the star--this does not draw the star
29 for (int count = 1; count < xPoints.length; count++)
30 star.lineTo(xPoints[count], yPoints[count]);
31
32 star.closePath(); // close the shape
33
34 g2d.translate(150, 150); // translate the origin to (150, 150)
35
36 // rotate around origin and draw stars in random colors
37 for (int count = 1; count <= 20; count++)
38 {
39 g2d.rotate(Math.PI / 10.0); // rotate coordinate system
40

```

---

**Fig. 13.31** | Java 2D general paths. (Part I of 2.)

---

```

41 // set random drawing color
42 g2d.setColor(new Color(random.nextInt(256),
43 random.nextInt(256), random.nextInt(256)));
44
45 g2d.fill(star); // draw filled star
46 }
47 }
48 } // end class Shapes2JPanel

```

---


**Fig. 13.31** | Java 2D general paths. (Part 2 of 2.)

---

```

1 // Fig. 13.32: Shapes2.java
2 // Demonstrating a general path.
3 import java.awt.Color;
4 import javax.swing.JFrame;
5
6 public class Shapes2
7 {
8 // execute application
9 public static void main(String[] args)
10 {
11 // create frame for Shapes2JPanel
12 JFrame frame = new JFrame("Drawing 2D Shapes");
13 frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
14
15 Shapes2JPanel shapes2JPanel = new Shapes2JPanel();
16 frame.add(shapes2JPanel);
17 frame.setBackground(Color.WHITE);
18 frame.setSize(315, 330);
19 frame.setVisible(true);
20 }
21 } // end class Shapes2

```



**Fig. 13.32** | Demonstrating a general path.

---

Lines 19–20 (Fig. 13.31) declare two `int` arrays representing the  $x$ - and  $y$ -coordinates of the points in the star. Line 23 creates `GeneralPath` object `star`. Line 26 uses `GeneralPath` method `moveTo` to specify the first point in the star. The `for` statement in lines 29–

30 uses `GeneralPath` method `lineTo` to draw a line to the next point in the star. Each new call to `lineTo` draws a line from the previous point to the current point. Line 32 uses `GeneralPath` method `closePath` to draw a line from the last point to the point specified in the last call to `moveTo`. This completes the general path.

Line 34 uses `Graphics2D` method `translate` to move the drawing origin to location (150, 150). All drawing operations now use location (150, 150) as (0, 0).

The `for` statement in lines 37–46 draws the star 20 times by rotating it around the new origin point. Line 39 uses `Graphics2D` method `rotate` to rotate the next displayed shape. The argument specifies the rotation angle in radians (with  $360^\circ = 2\pi$  radians). Line 45 uses `Graphics2D` method `fill` to draw a filled version of the star.

## 13.9 Wrap-Up

In this chapter, you learned how to use Java's graphics capabilities to produce colorful drawings. You learned how to specify the location of an object using Java's coordinate system, and how to draw on a window using the `paintComponent` method. You were introduced to class `Color`, and you learned how to use this class to specify different colors using their RGB components. You used the `JColorChooser` dialog to allow users to select colors in a program. You then learned how to work with fonts when drawing text on a window. You learned how to create a `Font` object from a font name, style and size, as well as how to access the metrics of a font. From there, you learned how to draw various shapes on a window, such as rectangles (regular, rounded and 3D), ovals and polygons, as well as lines and arcs. You then used the Java 2D API to create more complex shapes and to fill them with gradients or patterns. The chapter concluded with a discussion of general paths, used to construct shapes from straight lines and complex curves. In the next chapter, we discuss class `String` and its methods. We introduce regular expressions for pattern matching in strings and demonstrate how to validate user input with regular expressions.

## Summary

### *Section 13.1 Introduction*

- Java's coordinate system (p. 548) is a scheme for identifying every point (p. 559) on the screen.
- A coordinate pair (p. 548) has an *x*-coordinate (horizontal) and a *y*-coordinate (vertical).
- Coordinates are used to indicate where graphics should be displayed on a screen.
- Coordinate units are measured in pixels (p. 548). A pixel is a display monitor's smallest unit of resolution.

### *Section 13.2 Graphics Contexts and Graphics Objects*

- A Java graphics context (p. 550) enables drawing on the screen.
- Class `Graphics` (p. 550) contains methods for drawing strings, lines, rectangles and other shapes. Methods are also included for font manipulation and color manipulation.
- A `Graphics` object manages a graphics context and draws pixels on the screen that represent text and other graphical objects, e.g., lines, ellipses, rectangles and other polygons (p. 550).
- Class `Graphics` is an abstract class. Each Java implementation has a `Graphics` subclass that provides drawing capabilities. This implementation is hidden from us by class `Graphics`, which supplies the interface that enables us to use graphics in a platform-independent manner.

- Method `paintComponent` can be used to draw graphics in any `JComponent` component.
- Method `paintComponent` receives a `Graphics` object that is passed to the method by the system when a lightweight Swing component needs to be repainted.
- When an application executes, the application container calls method `paintComponent`. For `paintComponent` to be called again, an event must occur.
- When a `JComponent` is displayed, its `paintComponent` method is called.
- Calling method `repaint` (p. 551) on a component updates the graphics drawn on that component.

### *Section 13.3 Color Control*

- Class `Color` (p. 551) declares methods and constants for manipulating colors in a Java program.
- Every color is created from a red, a green and a blue component. Together these components are called RGB values (p. 552). The RGB components specify the amount of red, green and blue in a color, respectively. The larger the value, the greater the amount of that particular color.
- `Color` methods `getRed`, `getGreen` and `getBlue` (p. 552) return `int` values from 0 to 255 representing the amount of red, green and blue, respectively.
- `Graphics` method `getColor` (p. 552) returns a `Color` object with the current drawing color.
- `Graphics` method `setColor` (p. 552) sets the current drawing color.
- `Graphics` method `fillRect` (p. 552) draws a rectangle filled by the `Graphics` object's current color.
- `Graphics` method `drawString` (p. 554) draws a `String` in the current color.
- The `JColorChooser` GUI component (p. 555) enables application users to select colors.
- `JColorChooser` static method `showDialog` (p. 556) displays a modal `JColorChooser` dialog.

### *Section 13.4 Manipulating Fonts*

- Class `Font` (p. 558) contains methods and constants for manipulating fonts.
- Class `Font`'s constructor takes three arguments—the font name (p. 559), font style and font size.
- A `Font`'s font style can be `Font.PLAIN`, `Font.ITALIC` or `Font.BOLD` (each is a static field of class `Font`). Font styles can be used in combination (e.g., `Font.ITALIC + Font.BOLD`).
- The font size is measured in points. A point is 1/72 of an inch.
- `Graphics` method `setFont` (p. 559) sets the drawing font in which text will be displayed.
- `Font` method `getSize` (p. 559) returns the font size in points.
- `Font` method `getName` (p. 559) returns the current font name as a string.
- `Font` method `getStyle` (p. 561) returns an integer value representing the current `Font`'s style.
- `Font` method `getFamily` (p. 561) returns the name of the font family to which the current font belongs. The name of the font family is platform specific.
- Class `FontMetrics` (p. 561) contains methods for obtaining font information.
- `Font` metrics (p. 561) include height, descent and leading.

### *Section 13.5 Drawing Lines, Rectangles and Ovals*

- `Graphics` methods `fillRoundRect` (p. 565) and `drawRoundRect` (p. 565) draw rectangles with rounded corners.
- `Graphics` methods `draw3DRect` (p. 567) and `fill3DRect` (p. 567) draw three-dimensional rectangles.
- `Graphics` methods `drawOval` (p. 567) and `fillOval` (p. 567) draw ovals.

**Section 13.6 Drawing Arcs**

- An arc (p. 567) is drawn as a portion of an oval.
- Arcs sweep from a starting angle by the number of degrees specified by their arc angle (p. 567).
- Graphics methods `drawArc` (p. 567) and `fillArc` (p. 567) are used for drawing arcs.

**Section 13.7 Drawing Polygons and Polylines**

- Class `Polygon` contains methods for creating polygons.
- Polygons are closed multisided shapes composed of straight-line segments.
- Polylines (p. 570) are sequences of connected points.
- Graphics method `drawPolyline` (p. 572) displays a series of connected lines.
- Graphics methods `drawPolygon` (p. 572) and `fillPolygon` (p. 573) are used to draw polygons.
- `Polygon` method `addPoint` (p. 573) adds pairs of *x*- and *y*-coordinates to the `Polygon`.

**Section 13.8 Java 2D API**

- The Java 2D API (p. 573) provides advanced two-dimensional graphics capabilities.
- Class `Graphics2D` (p. 573)—a subclass of `Graphics`—is used for drawing with the Java 2D API.
- The Java 2D API's classes for drawing shapes include `Line2D.Double`, `Rectangle2D.Double`, `RoundRectangle2D.Double`, `Arc2D.Double` and `Ellipse2D.Double` (p. 573).
- Class `GradientPaint` (p. 576) helps draw a shape in gradually changing colors—called a gradient (p. 576).
- `Graphics2D` method `fill` (p. 576) draws a filled object of any type that implements interface `Shape` (p. 576).
- Class `BasicStroke` (p. 576) helps specify the drawing characteristics of lines.
- `Graphics2D` method `draw` (p. 576) is used to draw a `Shape` object.
- Classes `GradientPaint` (p. 576) and `TexturePaint` (p. 577) help specify the characteristics for filling shapes with colors or patterns.
- A general path (p. 578) is a shape constructed from straight lines and complex curves and is represented with an object of class `GeneralPath` (p. 578).
- `GeneralPath` method `moveTo` (p. 579) specifies the first point in a general path.
- `GeneralPath` method `lineTo` (p. 580) draws a line to the next point in the path. Each new call to `lineTo` draws a line from the previous point to the current point.
- `GeneralPath` method `closePath` (p. 580) draws a line from the last point to the point specified in the last call to `moveTo`. This completes the general path.
- `Graphics2D` method `translate` (p. 580) is used to move the drawing origin to a new location.
- `Graphics2D` method `rotate` (p. 580) is used to rotate the next displayed shape.

**Self-Review Exercises**

**13.1** Fill in the blanks in each of the following statements:

- In Java 2D, method \_\_\_\_\_ of class \_\_\_\_\_ sets the characteristics of a stroke used to draw a shape.
- Class \_\_\_\_\_ helps specify the fill for a shape such that the fill gradually changes from one color to another.
- The \_\_\_\_\_ method of class `Graphics` draws a line between two points.
- RGB is short for \_\_\_\_\_, \_\_\_\_\_ and \_\_\_\_\_.

- e) Font sizes are measured in units called \_\_\_\_\_.
  - f) Class \_\_\_\_\_ helps specify the fill for a shape using a pattern drawn in a `BufferedImage`.
- 13.2** State whether each of the following is *true* or *false*. If *false*, explain why.
- a) The first two arguments of `Graphics` method `drawOval` specify the center coordinate of the oval.
  - b) In the Java coordinate system, *x*-coordinates increase from left to right and *y*-coordinates from top to bottom.
  - c) `Graphics` method `fillPolygon` draws a filled polygon in the current color.
  - d) `Graphics` method `drawArc` allows negative angles.
  - e) `Graphics` method `getSize` returns the size of the current font in centimeters.
  - f) Pixel coordinate (0, 0) is located at the exact center of the monitor.
- 13.3** Find the error(s) in each of the following and explain how to correct them. Assume that `g` is a `Graphics` object.
- a) `g.setFont("SansSerif");`
  - b) `g.erase(x, y, w, h);` // clear rectangle at (x, y)
  - c) `Font f = new Font("Serif", Font.BOLDITALIC, 12);`
  - d) `g.setColor(255, 255, 0);` // change color to yellow

## Answers to Self-Review Exercises

- 13.1** a) `setStroke`, `Graphics2D`. b) `GradientPaint`. c) `drawLine`. d) red, green, blue. e) points. f) `TexturePaint`.
- 13.2** a) False. The first two arguments specify the upper-left corner of the bounding rectangle.  
 b) True.  
 c) True.  
 d) True.  
 e) False. Font sizes are measured in points.  
 f) False. The coordinate (0,0) corresponds to the upper-left corner of a GUI component on which drawing occurs.
- 13.3** a) The `setFont` method takes a `Font` object as an argument—not a `String`.  
 b) The `Graphics` class does not have an `erase` method. The `clearRect` method should be used.  
 c) `Font.BOLDITALIC` is not a valid font style. To get a bold italic font, use `Font.BOLD + Font.ITALIC`.  
 d) Method `setColor` takes a `Color` object as an argument, not three integers.

## Exercises

- 13.4** Fill in the blanks in each of the following statements:
- a) Class \_\_\_\_\_ of the Java 2D API is used to draw ovals.
  - b) Methods `draw` and `fill` of class `Graphics2D` require an object of type \_\_\_\_\_ as their argument.
  - c) The three constants that specify font style are \_\_\_\_\_, \_\_\_\_\_ and \_\_\_\_\_.
  - d) `Graphics2D` method \_\_\_\_\_ sets the painting color for Java 2D shapes.
- 13.5** State whether each of the following is *true* or *false*. If *false*, explain why.
- a) `Graphics` method `drawPolygon` automatically connects the endpoints of the polygon.
  - b) `Graphics` method `drawLine` draws a line between two points.
  - c) `Graphics` method `fillArc` uses degrees to specify the angle.
  - d) In the Java coordinate system, values on the *y*-axis increase from left to right.
  - e) `Graphics` inherits directly from class `Object`.

- f) Graphics is an abstract class.
- g) The Font class inherits directly from class Graphics.

**13.6** (*Concentric Circles Using Method `drawArc`*) Write an application that draws a series of eight concentric circles. The circles should be separated by 10 pixels. Use Graphics method `drawArc`.

**13.7** (*Concentric Circles Using Class `Ellipse2D.Double`*) Modify your solution to Exercise 13.6 to draw the ovals by using class `Ellipse2D.Double` and method `draw` of class `Graphics2D`.

**13.8** (*Random Lines Using Class `Line2D.Double`*) Modify your solution to Exercise 13.7 to draw random lines in random colors and random thicknesses. Use class `Line2D.Double` and method `draw` of class `Graphics2D` to draw the lines.

**13.9** (*Random Triangles*) Write an application that displays randomly generated triangles in different colors. Each triangle should be filled with a different color. Use class `GeneralPath` and method `fill` of class `Graphics2D` to draw the triangles.

**13.10** (*Random Characters*) Write an application that randomly draws characters in different fonts, sizes and colors.

**13.11** (*Grid Using Method `drawLine`*) Write an application that draws an 8-by-8 grid. Use Graphics method `drawLine`.

**13.12** (*Grid Using Class `Line2D.Double`*) Modify your solution to Exercise 13.11 to draw the grid using instances of class `Line2D.Double` and method `draw` of class `Graphics2D`.

**13.13** (*Grid Using Method `drawRect`*) Write an application that draws a 10-by-10 grid. Use the Graphics method `drawRect`.

**13.14** (*Grid Using Class `Rectangle2D.Double`*) Modify your solution to Exercise 13.13 to draw the grid by using class `Rectangle2D.Double` and method `draw` of class `Graphics2D`.

**13.15** (*Drawing Tetrahedrons*) Write an application that draws a tetrahedron (a three-dimensional shape with four triangular faces). Use class `GeneralPath` and method `draw` of class `Graphics2D`.

**13.16** (*Drawing Cubes*) Write an application that draws a cube. Use class `GeneralPath` and method `draw` of class `Graphics2D`.

**13.17** (*Circles Using Class `Ellipse2D.Double`*) Write an application that asks the user to input the radius of a circle as a floating-point number and draws the circle, as well as the values of the circle's diameter, circumference and area. Use the value 3.14159 for  $\pi$ . [Note: You may also use the predefined constant `Math.PI` for the value of  $\pi$ . This constant is more precise than the value 3.14159. Class `Math` is declared in the `java.lang` package, so you need not import it.] Use the following formulas ( $r$  is the radius):

$$\begin{aligned} \text{diameter} &= 2r \\ \text{circumference} &= 2\pi r \\ \text{area} &= \pi r^2 \end{aligned}$$

The user should also be prompted for a set of coordinates in addition to the radius. Then draw the circle and display its diameter, circumference and area, using an `Ellipse2D.Double` object to represent the circle and method `draw` of class `Graphics2D` to display it.

**13.18** (*Screen Saver*) Write an application that simulates a screen saver. The application should randomly draw lines using method `drawLine` of class `Graphics`. After drawing 100 lines, the application should clear itself and start drawing lines again. To allow the program to draw continuously, place a call to `repaint` as the last line in method `paintComponent`. Do you notice any problems with this on your system?

**13.19** (*Screen Saver Using Timer*) Package `javax.swing` contains a class called `Timer` that is capable of calling method `actionPerformed` of interface `ActionListener` at a fixed time interval (speci-



fied in milliseconds). Modify your solution to Exercise 13.18 to remove the call to repaint from method `paintComponent`. Declare your class to implement `ActionListener`. (The `actionPerformed` method should simply call `repaint`.) Declare an instance variable of type `Timer` called `timer` in your class. In the constructor for your class, write the following statements:

```
timer = new Timer(1000, this);
timer.start();
```

This creates an instance of class `Timer` that will call this object's `actionPerformed` method every 1000 milliseconds (i.e., every second).

**13.20** (*Screen Saver for a Random Number of Lines*) Modify your solution to Exercise 13.19 to enable the user to enter the number of random lines that should be drawn before the application clears itself and starts drawing lines again. Use a `TextField` to obtain the value. The user should be able to type a new number into the `TextField` at any time during the program's execution. Use an inner class to perform event handling for the `TextField`.

**13.21** (*Screen Saver with Shapes*) Modify your solution to Exercise 13.20 such that it uses random-number generation to choose different shapes to display. Use methods of class `Graphics`.

**13.22** (*Screen Saver Using the Java 2D API*) Modify your solution to Exercise 13.21 to use classes and drawing capabilities of the Java 2D API. Draw shapes like rectangles and ellipses, with randomly generated gradients. Use class `GradientPaint` to generate the gradient.

**13.23** (*Turtle Graphics*) Modify your solution to Exercise 6.21—*Turtle Graphics*—to add a graphical user interface using `TextFields` and `Buttons`. Draw lines rather than asterisks (\*). When the turtle graphics program specifies a move, translate the number of positions into a number of pixels on the screen by multiplying the number of positions by 10 (or any value you choose). Implement the drawing with Java 2D API features.

**13.24** (*Knight's Tour*) Produce a graphical version of the Knight's Tour problem (Exercise 6.22, Exercise 6.23 and Exercise 6.26). As each move is made, the appropriate cell of the chessboard should be updated with the proper move number. If the result of the program is a *full tour* or a *closed tour*, the program should display an appropriate message. If you like, use class `Timer` (see Exercise 13.19) to help animate the Knight's Tour.

**13.25** (*Tortoise and Hare*) Produce a graphical version of the *Tortoise and Hare* simulation (Exercise 6.28). Simulate the mountain by drawing an arc that extends from the bottom-left corner of the window to the top-right corner. The tortoise and the hare should race up the mountain. Implement the graphical output to actually print the tortoise and the hare on the arc for every move. [Hint: Extend the length of the race from 70 to 300 to allow yourself a larger graphics area.]


**13.26** (*Drawing Spirals*) Write an application that uses `Graphics` method `drawPolyline` to draw a spiral similar to the one shown in Fig. 13.33.

**13.27** (*Pie Chart*) Write a program that inputs four numbers and graphs them as a pie chart. Use class `Arc2D.Double` and method `fill` of class `Graphics2D` to perform the drawing. Draw each piece of the pie in a separate color.

**13.28** (*Selecting Shapes*) Write an application that allows the user to select a shape from a `ComboBox` and draws it 20 times with random locations and dimensions in method `paintComponent`. The first item in the `ComboBox` should be the default shape that is displayed the first time `paintComponent` is called.

**13.29** (*Random Colors*) Modify Exercise 13.28 to draw each of the 20 randomly sized shapes in a randomly selected color. Use all 13 predefined `Color` objects in an array of `Colors`.

**13.30** (*JColorChooser Dialog*) Modify Exercise 13.28 to allow the user to select the color in which shapes should be drawn from a `JColorChooser` dialog.



**Fig. 13.33** | Spiral drawn using method `drawPolyline`.

### *(Optional) GUI and Graphics Case Study Exercise: Adding Java 2D*

**13.31** Java 2D introduces many new capabilities for creating unique and impressive graphics. We'll add a small subset of these features to the drawing application you created in Exercise 12.17. In this version, you'll enable the user to specify gradients for filling shapes and to change stroke characteristics for drawing lines and outlines of shapes. The user will be able to choose which colors compose the gradient and set the width and dash length of the stroke.

First, you must update the `MyShape` hierarchy to support Java 2D functionality. Make the following changes in class `MyShape`:


- Change abstract method `draw`'s parameter type from `Graphics` to `Graphics2D`.
- Change all variables of type `Color` to type `Paint` to enable support for gradients. [*Note:* Recall that class `Color` implements interface `Paint`.]
- Add an instance variable of type `Stroke` in class `MyShape` and a `Stroke` parameter in the constructor to initialize the new instance variable. The default stroke should be an instance of class `BasicStroke`.

Classes `MyLine`, `MyBoundedShape`, `MyOval` and `MyRectangle` should each add a `Stroke` parameter to their constructors. In the draw methods, each shape should set the `Paint` and the `Stroke` before drawing or filling a shape. Since `Graphics2D` is a subclass of `Graphics`, we can continue to use `Graphics` methods `drawLine`, `drawOval`, `fillOval`, and so on to draw the shapes. When these methods are called, they'll draw the appropriate shape using the specified `Paint` and `Stroke` settings.

Next, you'll update the `DrawPanel` to handle the Java 2D features. Change all `Color` variables to `Paint` variables. Declare an instance variable `currentStroke` of type `Stroke` and provide a *set* method for it. Update the calls to the individual shape constructors to include the `Paint` and `Stroke` arguments. In method `paintComponent`, cast the `Graphics` reference to type `Graphics2D` and use the `Graphics2D` reference in each call to `MyShape` method `draw`.

Next, make the new Java 2D features accessible from the GUI. Create a `JPanel` of GUI components for setting the Java 2D options. Add these components at the top of the `DrawFrame` below the panel that currently contains the standard shape controls (see Fig. 13.34). These GUI components should include:

- A checkbox to specify whether to paint using a gradient.
- Two `JButtons` that each show a `JColorChooser` dialog to allow the user to choose the first and second color in the gradient. (These will replace the `JComboBox` used for choosing the color in Exercise 12.17.)
- A text field for entering the `Stroke` width.
- A text field for entering the `Stroke` dash length.
- A checkbox for selecting whether to draw a dashed or solid line.



**Fig. 13.34** | Drawing with Java 2D.

If the user selects to draw with a gradient, set the `Paint` on the `DrawPane1` to be a gradient of the two colors chosen by the user. The expression

```
new GradientPaint(0, 0, color1, 50, 50, color2, true))
```

creates a `GradientPaint` that cycles diagonally from the upper-left to the bottom-right every 50 pixels. Variables `color1` and `color2` represent the colors chosen by the user. If the user does not select to use a gradient, then simply set the `Paint` on the `DrawPane1` to be the first `Color` chosen by the user.

For strokes, if the user chooses a solid line, then create the `Stroke` with the expression

```
new BasicStroke(width, BasicStroke.CAP_ROUND, BasicStroke.JOIN_ROUND)
```

where variable `width` is the width specified by the user in the line-width text field. If the user chooses a dashed line, then create the `Stroke` with the expression

```
new BasicStroke(width, BasicStroke.CAP_ROUND, BasicStroke.JOIN_ROUND,
 10, dashes, 0)
```

where `width` again is the width in the line-width field, and `dashes` is an array with one element whose value is the length specified in the dash-length field. The `Panel` and `Stroke` objects should be passed to the shape object's constructor when the shape is created in `DrawPane1`.

## Making a Difference

**13.32** (*Large-Type Displays for People with Low Vision*) The accessibility of computers and the Internet to all people, regardless of disabilities, is becoming more important as these tools play increasing roles in our personal and business lives. According to a recent estimate by the World Health Organization ([www.who.int/mediacentre/factsheets/fs282/en/](http://www.who.int/mediacentre/factsheets/fs282/en/)), 246 million people worldwide have low vision. To learn more about low vision, check out the GUI-based low-vision simulation at [www.webaim.org/simulations/lowvision.php](http://www.webaim.org/simulations/lowvision.php). People with low vision might prefer to choose a font and/or a larger font size when reading electronic documents and web pages. Java has five built-in “logical” fonts that are guaranteed to be available in any Java implementation, including `Serif`, `Sans-serif` and `Monospaced`. Write a GUI application that provides a `JTextArea` in which the user can type text. Allow the user to select `Serif`, `Sans-serif` or `Monospaced` from a `JComboBox`. Provide a `Bold` `JCheckBox`, which, if checked, makes the text bold. Include `Increase Font Size` and `Decrease Font Size` `JButtons` that allow the user to scale the size of the font up or down, respectively, by one point at a time. Start with a font size of 18 points. For the purposes of this exercise, set the font size on the `JComboBox`, `JButtons` and `JCheckBox` to 20 points so that a person with low vision will be able to read the text on them.

# 14

## Strings, Characters and Regular Expressions

*The chief defect of Henry King  
Was chewing little bits of string.*

—Hilaire Belloc

*Vigorous writing is concise. A  
sentence should contain no  
unnecessary words, a paragraph  
no unnecessary sentences.*

—William Strunk, Jr.

*I have made this letter longer  
than usual, because I lack the  
time to make it short.*

—Blaise Pascal

### Objectives

In this chapter you'll:

- Create and manipulate immutable character-string objects of class `String`.
- Create and manipulate mutable character-string objects of class `StringBuilder`.
- Create and manipulate objects of class `Character`.
- Break a `String` object into tokens using `String` method `split`.
- Use regular expressions to validate `String` data entered into an application.



- 14.1 Introduction
- 14.2 Fundamentals of Characters and Strings
- 14.3 Class `String`
  - 14.3.1 String Constructors
  - 14.3.2 String Methods `length`, `charAt` and `getChars`
  - 14.3.3 Comparing Strings
  - 14.3.4 Locating Characters and Substrings in Strings
  - 14.3.5 Extracting Substrings from Strings
  - 14.3.6 Concatenating Strings
  - 14.3.7 Miscellaneous String Methods
  - 14.3.8 String Method `valueOf`
- 14.4 Class `StringBuilder`
  - 14.4.1 `StringBuilder` Constructors
  - 14.4.2 `StringBuilder` Methods `length`, `capacity`, `setLength` and `ensureCapacity`
  - 14.4.3 `StringBuilder` Methods `charAt`, `setCharAt`, `getChars` and `reverse`
  - 14.4.4 `StringBuilder` append Methods
  - 14.4.5 `StringBuilder` Insertion and Deletion Methods
- 14.5 Class `Character`
- 14.6 Tokenizing Strings
- 14.7 Regular Expressions, Class `Pattern` and Class `Matcher`
- 14.8 Wrap-Up

*Summary | Self-Review Exercises | Answers to Self-Review Exercises | Exercises |  
 Special Section: Advanced String-Manipulation Exercises |  
 Special Section: Challenging String-Manipulation Projects | Making a Difference*

## 14.1 Introduction

This chapter introduces Java's string- and character-processing capabilities. The techniques discussed here are appropriate for validating program input, displaying information to users and other text-based manipulations. They're also appropriate for developing text editors, word processors, page-layout software, computerized typesetting systems and other kinds of text-processing software. We've presented several string-processing capabilities in earlier chapters. This chapter discusses in detail the capabilities of classes `String`, `StringBuilder` and `Character` from the `java.lang` package—these classes provide the foundation for string and character manipulation in Java.

The chapter also discusses regular expressions that provide applications with the capability to validate input. The functionality is located in the `String` class along with classes `Matcher` and `Pattern` located in the `java.util.regex` package.

## 14.2 Fundamentals of Characters and Strings

Characters are the fundamental building blocks of Java source programs. Every program is composed of a sequence of characters that—when grouped together meaningfully—are interpreted by the Java compiler as a series of instructions used to accomplish a task. A program may contain **character literals**. A character literal is an integer value represented as a character in single quotes. For example, `'z'` represents the integer value of `z`, and `'\t'` represents the integer value of a tab character. The value of a character literal is the integer value of the character in the **Unicode character set**. Appendix B presents the integer equivalents of the characters in the ASCII character set, which is a subset of Unicode (discussed in online Appendix H).

Recall from Section 2.2 that a string is a sequence of characters treated as a single unit. A string may include letters, digits and various **special characters**, such as `+`, `-`, `*`, `/` and `$`. A string is an object of class `String`. **String literals** (stored in memory as `String` objects) are written as a sequence of characters in double quotation marks, as in:

|                          |                      |
|--------------------------|----------------------|
| "John Q. Doe"            | (a name)             |
| "9999 Main Street"       | (a street address)   |
| "Waltham, Massachusetts" | (a city and state)   |
| "(201) 555-1212"         | (a telephone number) |

A string may be assigned to a `String` reference. The declaration

```
String color = "blue";
```

initializes `String` variable `color` to refer to a `String` object that contains the string "blue".



#### Performance Tip 14.1

*To conserve memory, Java treats all string literals with the same contents as a single `String` object that has many references to it.*

## 14.3 Class String

Class `String` is used to represent strings in Java. The next several subsections cover many of class `String`'s capabilities.

### 14.3.1 String Constructors

Class `String` provides constructors for initializing `String` objects in a variety of ways. Four of the constructors are demonstrated in the main method of Fig. 14.1.

```

1 // Fig. 14.1: StringConstructors.java
2 // String class constructors.
3
4 public class StringConstructors
5 {
6 public static void main(String[] args)
7 {
8 char[] charArray = {'b', 'i', 'r', 't', 'h', ' ', 'd', 'a', 'y'};
9 String s = new String("hello");
10
11 // use String constructors
12 String s1 = new String();
13 String s2 = new String(s);
14 String s3 = new String(charArray);
15 String s4 = new String(charArray, 6, 3);
16
17 System.out.printf(
18 "s1 = %s%s2 = %s%s3 = %s%s4 = %s%n", s1, s2, s3, s4);
19 }
20 } // end class StringConstructors

```

```

s1 =
s2 = hello
s3 = birth day
s4 = day

```

**Fig. 14.1** | String class constructors.

Line 12 instantiates a new `String` using class `String`'s no-argument constructor and assigns its reference to `s1`. The new `String` object contains no characters (i.e., the **empty string**, which can also be represented as `""`) and has a length of 0. Line 13 instantiates a new `String` object using class `String`'s constructor that takes a `String` object as an argument and assigns its reference to `s2`. The new `String` object contains the same sequence of characters as the `String` object `s` that's passed as an argument to the constructor.



#### Performance Tip 14.2

*It's not necessary to copy an existing `String` object. `String` objects are immutable, because class `String` does not provide methods that allow the contents of a `String` object to be modified after it is created.*

Line 14 instantiates a new `String` object and assigns its reference to `s3` using class `String`'s constructor that takes a `char` array as an argument. The new `String` object contains a copy of the characters in the array.

Line 15 instantiates a new `String` object and assigns its reference to `s4` using class `String`'s constructor that takes a `char` array and two integers as arguments. The second argument specifies the starting position (the *offset*) from which characters in the array are accessed. Remember that the first character is at position 0. The third argument specifies the number of characters (the *count*) to access in the array. The new `String` object is formed from the accessed characters. If the offset or the count specified as an argument results in accessing an element outside the bounds of the character array, a `StringIndexOutOfBoundsException` is thrown.

### 14.3.2 String Methods `length`, `charAt` and `getChars`

`String` methods **`length`**, **`charAt`** and **`getChars`** return the length of a `String`, obtain the character at a specific location in a `String` and retrieve a set of characters from a `String` as a `char` array, respectively. Figure 14.2 demonstrates each of these methods.

---

```

1 // Fig. 14.2: StringMiscellaneous.java
2 // This application demonstrates the length, charAt and getChars
3 // methods of the String class.
4
5 public class StringMiscellaneous
6 {
7 public static void main(String[] args)
8 {
9 String s1 = "hello there";
10 char[] charArray = new char[5];
11
12 System.out.printf("s1: %s", s1);
13
14 // test length method
15 System.out.printf("\nLength of s1: %d", s1.length());
16
17 // loop through characters in s1 with charAt and display reversed
18 System.out.printf("\nThe string reversed is: ");

```

---

**Fig. 14.2** | String methods `length`, `charAt` and `getChars`. (Part I of 2.)

```

19
20 for (int count = s1.length() - 1; count >= 0; count--)
21 System.out.printf("%c ", s1.charAt(count));
22
23 // copy characters from string into charArray
24 s1.getChars(0, 5, charArray, 0);
25 System.out.printf("\nThe character array is: ");
26
27 for (char character : charArray)
28 System.out.print(character);
29
30 System.out.println();
31 }
32 } // end class StringMiscellaneous

```

```

s1: hello there
Length of s1: 11
The string reversed is: e r e h t o l l e h
The character array is: hello

```

**Fig. 14.2** | String methods `length`, `charAt` and `getChars`. (Part 2 of 2.)

Line 15 uses `String` method `length` to determine the number of characters in `String` `s1`. Like arrays, strings know their own length. However, unlike arrays, you access a `String`'s length via class `String`'s `length` method.

Lines 20–21 print the characters of the `String` `s1` in reverse order (and separated by spaces). `String` method `charAt` (line 21) returns the character at a specific position in the `String`. Method `charAt` receives an integer argument that's used as the index and returns the character at that position. Like arrays, the first element of a `String` is at position 0.

Line 24 uses `String` method `getChars` to copy the characters of a `String` into a character array. The first argument is the starting index from which characters are to be copied. The second argument is the index that's one past the last character to be copied from the `String`. The third argument is the character array into which the characters are to be copied. The last argument is the starting index where the copied characters are placed in the target character array. Next, lines 27–28 print the `char` array contents one character at a time.

### 14.3.3 Comparing Strings

Chapter 19 discusses sorting and searching arrays. Frequently, the information being sorted or searched consists of `Strings` that must be compared to place them into order or to determine whether a string appears in an array (or other collection). Class `String` provides methods for *comparing* strings, as demonstrated in the next two examples.

To understand what it means for one string to be greater than or less than another, consider the process of alphabetizing a series of last names. No doubt, you'd place "Jones" before "Smith" because the first letter of "Jones" comes before the first letter of "Smith" in the alphabet. But the alphabet is more than just a list of 26 letters—it's an *ordered* list of characters. Each letter occurs in a specific position within the list. Z is more than just a letter of the alphabet—it's specifically the twenty-sixth letter of the alphabet.



How does the computer know that one letter “comes before” another? All characters are represented in the computer as numeric codes (see Appendix B). When the computer compares Strings, it actually compares the numeric codes of the characters in the Strings.

Figure 14.3 demonstrates String methods `equals`, `equalsIgnoreCase`, `compareTo` and `regionMatches` and using the equality operator `==` to compare String objects.

---

```

1 // Fig. 14.3: StringCompare.java
2 // String methods equals, equalsIgnoreCase, compareTo and regionMatches.
3
4 public class StringCompare
5 {
6 public static void main(String[] args)
7 {
8 String s1 = new String("hello"); // s1 is a copy of "hello"
9 String s2 = "goodbye";
10 String s3 = "Happy Birthday";
11 String s4 = "happy birthday";
12
13 System.out.printf(
14 "s1 = %s\ns2 = %s\ns3 = %s\ns4 = %s\n\n", s1, s2, s3, s4);
15
16 // test for equality
17 if (s1.equals("hello")) // true
18 System.out.println("s1 equals \"hello\"");
19 else
20 System.out.println("s1 does not equal \"hello\"");
21
22 // test for equality with ==
23 if (s1 == "hello") // false; they are not the same object
24 System.out.println("s1 is the same object as \"hello\"");
25 else
26 System.out.println("s1 is not the same object as \"hello\"");
27
28 // test for equality (ignore case)
29 if (s3.equalsIgnoreCase(s4)) // true
30 System.out.printf("%s equals %s with case ignored\n", s3, s4);
31 else
32 System.out.println("s3 does not equal s4");
33
34 // test compareTo
35 System.out.printf(
36 "%ns1.compareTo(s2) is %d", s1.compareTo(s2));
37 System.out.printf(
38 "%ns2.compareTo(s1) is %d", s2.compareTo(s1));
39 System.out.printf(
40 "%ns1.compareTo(s1) is %d", s1.compareTo(s1));
41 System.out.printf(
42 "%ns3.compareTo(s4) is %d", s3.compareTo(s4));
43 System.out.printf(
44 "%ns4.compareTo(s3) is %d\n\n", s4.compareTo(s3));

```

---

**Fig. 14.3** | String methods `equals`, `equalsIgnoreCase`, `compareTo` and `regionMatches`.  
(Part I of 2.)

```

45
46 // test regionMatches (case sensitive)
47 if (s3.regionMatches(0, s4, 0, 5))
48 System.out.println("First 5 characters of s3 and s4 match");
49 else
50 System.out.println(
51 "First 5 characters of s3 and s4 do not match");
52
53 // test regionMatches (ignore case)
54 if (s3.regionMatches(true, 0, s4, 0, 5))
55 System.out.println(
56 "First 5 characters of s3 and s4 match with case ignored");
57 else
58 System.out.println(
59 "First 5 characters of s3 and s4 do not match");
60 }
61 } // end class StringCompare

```

```

s1 = hello
s2 = goodbye
s3 = Happy Birthday
s4 = happy birthday

s1 equals "hello"
s1 is not the same object as "hello"
Happy Birthday equals happy birthday with case ignored

s1.compareTo(s2) is 1
s2.compareTo(s1) is -1
s1.compareTo(s1) is 0
s3.compareTo(s4) is -32
s4.compareTo(s3) is 32

First 5 characters of s3 and s4 do not match
First 5 characters of s3 and s4 match with case ignored

```

**Fig. 14.3** | String methods equals, equalsIgnoreCase, compareTo and regionMatches.  
(Part 2 of 2.)

### ***String Method equals***

The condition at line 17 uses method `equals` to compare String `s1` and the String literal "hello" for equality. Method `equals` (a method of class `Object` overridden in `String`) tests any two objects for equality—the strings contained in the two objects are *identical*. The method returns `true` if the contents of the objects are equal, and `false` otherwise. The preceding condition is `true` because String `s1` was initialized with the string literal "hello". Method `equals` uses a **lexicographical comparison**—it compares the integer Unicode values (see online Appendix H for more information) that represent each character in each String. Thus, if the String "hello" is compared to the string "HELLO", the result is `false`, because the integer representation of a lowercase letter is *different* from that of the corresponding uppercase letter.

**Comparing Strings with the == Operator**

The condition at line 23 uses the equality operator `==` to compare String `s1` for equality with the String literal `"hello"`. When primitive-type values are compared with `==`, the result is *true* if *both values are identical*. When references are compared with `==`, the result is *true* if *both references refer to the same object in memory*. To compare the actual contents (or state information) of objects for equality, a method must be invoked. In the case of Strings, that method is `equals`. The preceding condition evaluates to *false* at line 23 because the reference `s1` was initialized with the statement

```
s1 = new String("hello");
```

which creates a new String object with a copy of string literal `"hello"` and assigns the new object to variable `s1`. If `s1` had been initialized with the statement

```
s1 = "hello";
```

which directly assigns the string literal `"hello"` to variable `s1`, the condition would be *true*. Remember that Java treats all string literal objects with the same contents as one String object to which there can be many references. Thus, lines 8, 17 and 23 all refer to the same String object `"hello"` in memory.

**Common Programming Error 14.1**

*Comparing references with `==` can lead to logic errors, because `==` compares the references to determine whether they refer to the same object, not whether two objects have the same contents. When two separate objects that contain the same values are compared with `==`, the result will be *false*. When comparing objects to determine whether they have the same contents, use method `equals`.*

**String Method `equalsIgnoreCase`**

If you're sorting Strings, you may compare them for equality with method `equalsIgnoreCase`, which ignores whether the letters in each String are uppercase or lowercase when performing the comparison. Thus, `"hello"` and `"HELLO"` compare as equal. Line 29 uses String method `equalsIgnoreCase` to compare String `s3`—Happy Birthday—for equality with String `s4`—happy birthday. The result of this comparison is *true* because the comparison ignores case.

**String Method `compareTo`**

Lines 35–44 use method `compareTo` to compare Strings. Method `compareTo` is declared in the `Comparable` interface and implemented in the String class. Line 36 compares String `s1` to String `s2`. Method `compareTo` returns 0 if the Strings are equal, a negative number if the String that invokes `compareTo` is less than the String that's passed as an argument and a positive number if the String that invokes `compareTo` is greater than the String that's passed as an argument. Method `compareTo` uses a *lexicographical* comparison—it compares the numeric values of corresponding characters in each String.

**String Method `regionMatches`**

The condition at line 47 uses a version of String method `regionMatches` to compare portions of two Strings for equality. The first argument to this version of the method is the starting index in the String that invokes the method. The second argument is a compar-

ison String. The third argument is the starting index in the comparison String. The last argument is the number of characters to compare between the two Strings. The method returns true only if the specified number of characters are lexicographically equal.

Finally, the condition at line 54 uses a five-argument version of String method `regionMatches` to compare portions of two Strings for equality. When the first argument is true, the method ignores the case of the characters being compared. The remaining arguments are identical to those described for the four-argument `regionMatches` method.

### ***String Methods `startsWith` and `endsWith`***

The next example (Fig. 14.4) demonstrates String methods `startsWith` and `endsWith`. Method `main` creates array strings containing "started", "starting", "ended" and "ending". The remainder of method `main` consists of three for statements that test the elements of the array to determine whether they start with or end with a particular set of characters.

---

```

1 // Fig. 14.4: StringStartEnd.java
2 // String methods startsWith and endsWith.
3
4 public class StringStartEnd
5 {
6 public static void main(String[] args)
7 {
8 String[] strings = {"started", "starting", "ended", "ending"};
9
10 // test method startsWith
11 for (String string : strings)
12 {
13 if (string.startsWith("st"))
14 System.out.printf("%s\n" starts with "st"\n", string);
15 }
16
17 System.out.println();
18
19 // test method startsWith starting from position 2 of string
20 for (String string : strings)
21 {
22 if (string.startsWith("art", 2))
23 System.out.printf(
24 "%s\n" starts with "art" at position 2\n", string);
25 }
26
27 System.out.println();
28
29 // test method endsWith
30 for (String string : strings)
31 {
32 if (string.endsWith("ed"))
33 System.out.printf("%s\n" ends with "ed"\n", string);
34 }
35 }
36 } // end class StringStartEnd

```

---

**Fig. 14.4** | String methods `startsWith` and `endsWith`. (Part I of 2.)

```

"started" starts with "st"
"starting" starts with "st"

"started" starts with "art" at position 2
"starting" starts with "art" at position 2

"started" ends with "ed"
"ended" ends with "ed"

```

**Fig. 14.4** | String methods `startsWith` and `endsWith`. (Part 2 of 2.)

Lines 11–15 use the version of method `startsWith` that takes a `String` argument. The condition in the `if` statement (line 13) determines whether each `String` in the array starts with the characters "st". If so, the method returns `true` and the application prints that `String`. Otherwise, the method returns `false` and nothing happens.

Lines 20–25 use the `startsWith` method that takes a `String` and an integer as arguments. The integer specifies the index at which the comparison should begin in the `String`. The condition in the `if` statement (line 22) determines whether each `String` in the array has the characters "art" beginning with the third character in each `String`. If so, the method returns `true` and the application prints the `String`.

The third `for` statement (lines 30–34) uses method `endsWith`, which takes a `String` argument. The condition at line 32 determines whether each `String` in the array ends with the characters "ed". If so, the method returns `true` and the application prints the `String`.

### 14.3.4 Locating Characters and Substrings in Strings

Often it's useful to search a string for a character or set of characters. For example, if you're creating your own word processor, you might want to provide a capability for searching through documents. Figure 14.5 demonstrates the many versions of `String` methods `indexOf` and `lastIndexOf` that search for a specified character or substring in a `String`.

---

```

1 // Fig. 14.5: StringIndexMethods.java
2 // String searching methods indexOf and lastIndexOf.
3
4 public class StringIndexMethods
5 {
6 public static void main(String[] args)
7 {
8 String letters = "abcdefghijklmabcdehghijklm";
9
10 // test indexOf to locate a character in a string
11 System.out.printf(
12 "'c' is located at index %d\n", letters.indexOf('c'));
13 System.out.printf(
14 "'a' is located at index %d\n", letters.indexOf('a', 1));
15 System.out.printf(
16 "'$' is located at index %d\n\n", letters.indexOf('$'));
17

```

---

**Fig. 14.5** | String-searching methods `indexOf` and `lastIndexOf`. (Part 1 of 2.)

```

18 // test lastIndexOf to find a character in a string
19 System.out.printf("Last 'c' is located at index %d\n",
20 letters.lastIndexOf('c'));
21 System.out.printf("Last 'a' is located at index %d\n",
22 letters.lastIndexOf('a', 25));
23 System.out.printf("Last '$' is located at index %d\n\n",
24 letters.lastIndexOf('$'));
25
26 // test indexOf to locate a substring in a string
27 System.out.printf("\"def\" is located at index %d\n",
28 letters.indexOf("def"));
29 System.out.printf("\"def\" is located at index %d\n",
30 letters.indexOf("def", 7));
31 System.out.printf("\"hello\" is located at index %d\n\n",
32 letters.indexOf("hello"));
33
34 // test lastIndexOf to find a substring in a string
35 System.out.printf("Last \"def\" is located at index %d\n",
36 letters.lastIndexOf("def"));
37 System.out.printf("Last \"def\" is located at index %d\n",
38 letters.lastIndexOf("def", 25));
39 System.out.printf("Last \"hello\" is located at index %d\n",
40 letters.lastIndexOf("hello"));
41 }
42 } // end class StringIndexMethods

```

```

'c' is located at index 2
'a' is located at index 13
'$' is located at index -1

Last 'c' is located at index 15
Last 'a' is located at index 13
Last '$' is located at index -1

"def" is located at index 3
"def" is located at index 16
"hello" is located at index -1

Last "def" is located at index 16
Last "def" is located at index 16
Last "hello" is located at index -1

```

**Fig. 14.5** | String-searching methods `indexOf` and `lastIndexOf`. (Part 2 of 2.)

All the searches in this example are performed on the `String` `letters` (initialized with `"abcdefghijklmnopqrstuvwxyz"`). Lines 11–16 use method `indexOf` to locate the first occurrence of a character in a `String`. If the method finds the character, it returns the character's index in the `String`—otherwise, it returns `-1`. There are two versions of `indexOf` that search for characters in a `String`. The expression in line 12 uses the version of method `indexOf` that takes an integer representation of the character to find. The expression at line 14 uses another version of method `indexOf`, which takes two integer arguments—the character and the starting index at which the search of the `String` should begin.

Lines 19–24 use method `lastIndexOf` to locate the last occurrence of a character in a `String`. The method searches from the end of the `String` toward the beginning. If it finds the character, it returns the character's index in the `String`—otherwise, it returns `-1`. There are two versions of `lastIndexOf` that search for characters in a `String`. The expression at line 20 uses the version that takes the integer representation of the character. The expression at line 22 uses the version that takes two integer arguments—the integer representation of the character and the index from which to begin searching *backward*.

Lines 27–40 demonstrate versions of methods `indexOf` and `lastIndexOf` that each take a `String` as the first argument. These versions perform identically to those described earlier except that they search for sequences of characters (or substrings) that are specified by their `String` arguments. If the substring is found, these methods return the index in the `String` of the first character in the substring.

### 14.3.5 Extracting Substrings from Strings

Class `String` provides two substring methods to enable a new `String` object to be created by copying part of an existing `String` object. Each method returns a new `String` object. Both methods are demonstrated in Fig. 14.6.

---

```

1 // Fig. 14.6: SubString.java
2 // String class substring methods.
3
4 public class SubString
5 {
6 public static void main(String[] args)
7 {
8 String letters = "abcdefghijklmabcdefghijklm";
9
10 // test substring methods
11 System.out.printf("Substring from index 20 to end is \"%s\"%n",
12 letters.substring(20));
13 System.out.printf("%s \"%s\"%n",
14 "Substring from index 3 up to, but not including 6 is",
15 letters.substring(3, 6));
16 }
17 } // end class SubString

```

```

Substring from index 20 to end is "hijklm"
Substring from index 3 up to, but not including 6 is "def"

```

**Fig. 14.6** | String class substring methods.

The expression `letters.substring(20)` at line 12 uses the substring method that takes one integer argument. The argument specifies the starting index in the original `String` `letters` from which characters are to be copied. The substring returned contains a copy of the characters from the starting index to the end of the `String`. Specifying an index outside the bounds of the `String` causes a **`StringIndexOutOfBoundsException`**.

Line 15 uses the substring method that takes two integer arguments—the starting index from which to copy characters in the original `String` and the index one beyond the

last character to copy (i.e., copy up to, but *not including*, that index in the String). The substring returned contains a copy of the specified characters from the original String. An index outside the bounds of the String causes a `StringIndexOutOfBoundsException`.

### 14.3.6 Concatenating Strings

String method **concat** (Fig. 14.7) concatenates two String objects (similar to using the + operator) and returns a new String object containing the characters from both original Strings. The expression `s1.concat(s2)` at line 13 forms a String by appending the characters in `s2` to the those in `s1`. The original Strings to which `s1` and `s2` refer are *not modified*.

---

```

1 // Fig. 14.7: StringConcatenation.java
2 // String method concat.
3
4 public class StringConcatenation
5 {
6 public static void main(String[] args)
7 {
8 String s1 = "Happy ";
9 String s2 = "Birthday";
10
11 System.out.printf("s1 = %s\ns2 = %s\n\n", s1, s2);
12 System.out.printf(
13 "Result of s1.concat(s2) = %s\n", s1.concat(s2));
14 System.out.printf("s1 after concatenation = %s\n", s1);
15 }
16 } // end class StringConcatenation

```

---

```

s1 = Happy
s2 = Birthday

Result of s1.concat(s2) = Happy Birthday
s1 after concatenation = Happy

```

**Fig. 14.7** | String method `concat`.

### 14.3.7 Miscellaneous String Methods

Class String provides several methods that return Strings or character arrays containing copies of an original String's contents which are then modified. These methods—none of which modify the String on which they're called—are demonstrated in Fig. 14.8.

---

```

1 // Fig. 14.8: StringMiscellaneous2.java
2 // String methods replace, toLowerCase, toUpperCase, trim and toCharArray.
3
4 public class StringMiscellaneous2
5 {
6 public static void main(String[] args)
7 {

```

---

**Fig. 14.8** | String methods `replace`, `toLowerCase`, `toUpperCase`, `trim` and `toCharArray`. (Part I of 2.)



```

8 String s1 = "hello";
9 String s2 = "GOODBYE";
10 String s3 = " spaces ";
11
12 System.out.printf("s1 = %s\ns2 = %s\ns3 = %s\n\n", s1, s2, s3);
13
14 // test method replace
15 System.out.printf(
16 "Replace 'l' with 'L' in s1: %s\n\n", s1.replace('l', 'L'));
17
18 // test toLowerCase and toUpperCase
19 System.out.printf("s1.toUpperCase() = %s\n", s1.toUpperCase());
20 System.out.printf("s2.toLowerCase() = %s\n\n", s2.toLowerCase());
21
22 // test trim method
23 System.out.printf("s3 after trim = \"%s\"\n\n", s3.trim());
24
25 // test toCharArray method
26 char[] charArray = s1.toCharArray();
27 System.out.print("s1 as a character array = ");
28
29 for (char character : charArray)
30 System.out.print(character);
31
32 System.out.println();
33 }
34 } // end class StringMiscellaneous2

```

```

s1 = hello
s2 = GOODBYE
s3 = spaces

Replace 'l' with 'L' in s1: heLLo

s1.toUpperCase() = HELLO
s2.toLowerCase() = goodbye

s3 after trim = "spaces"

s1 as a character array = hello

```

**Fig. 14.8** | String methods `replace`, `toLowerCase`, `toUpperCase`, `trim` and `toCharArray`.  
(Part 2 of 2.)

Line 16 uses String method `replace` to return a new String object in which every occurrence in `s1` of character `'l'` (lowercase el) is replaced with character `'L'`. Method `replace` leaves the original String unchanged. If there are no occurrences of the first argument in the String, method `replace` returns the original String. An overloaded version of method `replace` enables you to replace substrings rather than individual characters.

Line 19 uses String method `toUpperCase` to generate a new String with uppercase letters where corresponding lowercase letters exist in `s1`. The method returns a new String object containing the converted String and leaves the original String unchanged. If there are no characters to convert, method `toUpperCase` returns the original String.

Line 20 uses String method **toLowerCase** to return a new String object with lowercase letters where corresponding uppercase letters exist in `s2`. The original String remains unchanged. If there are no characters in the original String to convert, `toLowerCase` returns the original String.

Line 23 uses String method **trim** to generate a new String object that removes all white-space characters that appear at the beginning and/or end of the String on which `trim` operates. The method returns a new String object containing the String without leading or trailing white space. The original String remains unchanged. If there are no white-space characters at the beginning and/or end, `trim` returns the original String.

Line 26 uses String method **toCharArray** to create a new character array containing a copy of the characters in `s1`. Lines 29–30 output each char in the array.

### 14.3.8 String Method `valueOf`

As we've seen, every object in Java has a `toString` method that enables a program to obtain the object's *string representation*. Unfortunately, this technique cannot be used with primitive types because they do not have methods. Class String provides static methods that take an argument of any type and convert it to a String object. Figure 14.9 demonstrates the String class **`valueOf`** methods.

The expression `String.valueOf(charArray)` at line 18 uses the character array `charArray` to create a new String object. The expression `String.valueOf(charArray, 3, 3)` at line 20 uses a portion of the character array `charArray` to create a new String object. The second argument specifies the starting index from which the characters are used. The third argument specifies the number of characters to be used.

---

```

1 // Fig. 14.9: StringValueOf.java
2 // String valueOf methods.
3
4 public class StringValueOf
5 {
6 public static void main(String[] args)
7 {
8 char[] charArray = {'a', 'b', 'c', 'd', 'e', 'f'};
9 boolean booleanValue = true;
10 char characterValue = 'Z';
11 int integerValue = 7;
12 long longValue = 10000000000L; // L suffix indicates long
13 float floatValue = 2.5f; // f indicates that 2.5 is a float
14 double doubleValue = 33.333; // no suffix, double is default
15 Object objectRef = "hello"; // assign string to an Object reference
16
17 System.out.printf(
18 "char array = %s\n", String.valueOf(charArray));
19 System.out.printf("part of char array = %s\n",
20 String.valueOf(charArray, 3, 3));
21 System.out.printf(
22 "boolean = %s\n", String.valueOf(booleanValue));
23 System.out.printf(
24 "char = %s\n", String.valueOf(characterValue));

```

---

**Fig. 14.9** | String `valueOf` methods. (Part I of 2.)

```

25 System.out.printf("int = %s%n", String.valueOf(integerValue));
26 System.out.printf("long = %s%n", String.valueOf(longValue));
27 System.out.printf("float = %s%n", String.valueOf(floatValue));
28 System.out.printf(
29 "double = %s%n", String.valueOf(doubleValue));
30 System.out.printf("Object = %s", String.valueOf(objectRef));
31 }
32 } // end class StringValueOf

```

```

char array = abcdef
part of char array = def
boolean = true
char = Z
int = 7
long = 100000000000L
float = 2.5f
double = 33.333
Object = hello

```

**Fig. 14.9** | String `valueOf` methods. (Part 2 of 2.)

There are seven other versions of method `valueOf`, which take arguments of type `boolean`, `char`, `int`, `long`, `float`, `double` and `Object`, respectively. These are demonstrated in lines 21–30. The version of `valueOf` that takes an `Object` as an argument can do so because all `Objects` can be converted to `Strings` with method `toString`.

[*Note:* Lines 12–13 use literal values `100000000000L` and `2.5f` as the initial values of `long` variable `longValue` and `float` variable `floatValue`, respectively. By default, Java treats integer literals as type `int` and floating-point literals as type `double`. Appending the letter `L` to the literal `100000000000` and appending letter `f` to the literal `2.5` indicates to the compiler that `100000000000` should be treated as a `long` and `2.5` as a `float`. An uppercase `L` or lowercase `l` can be used to denote a variable of type `long` and an uppercase `F` or lowercase `f` can be used to denote a variable of type `float`.]

## 14.4 Class `StringBuilder`

We now discuss the features of class `StringBuilder` for creating and manipulating *dynamic* string information—that is, *modifiable* strings. Every `StringBuilder` is capable of storing a number of characters specified by its *capacity*. If a `StringBuilder`'s capacity is exceeded, the capacity expands to accommodate the additional characters.



### Performance Tip 14.3

*Java can perform certain optimizations involving String objects (such as referring to one String object from multiple variables) because it knows these objects will not change. Strings (not StringBuilder) should be used if the data will not change.*



### Performance Tip 14.4

*In programs that frequently perform string concatenation, or other string modifications, it's often more efficient to implement the modifications with class StringBuilder.*



### Software Engineering Observation 14.1

*StringBuilders are not thread safe. If multiple threads require access to the same dynamic string information, use class **StringBuffer** in your code. Classes **StringBuilder** and **StringBuffer** provide identical capabilities, but class **StringBuffer** is thread safe. For more details on threading, see Chapter 23.*

## 14.4.1 StringBuilder Constructors

Class **StringBuilder** provides four constructors. We demonstrate three of these in Fig. 14.10. Line 8 uses the no-argument **StringBuilder** constructor to create a **StringBuilder** with no characters in it and an initial capacity of 16 characters (the default for a **StringBuilder**). Line 9 uses the **StringBuilder** constructor that takes an integer argument to create a **StringBuilder** with no characters in it and the initial capacity specified by the integer argument (i.e., 10). Line 10 uses the **StringBuilder** constructor that takes a **String** argument to create a **StringBuilder** containing the characters in the **String** argument. The initial capacity is the number of characters in the **String** argument plus 16.

Lines 12–14 implicitly use the method **toString** of class **StringBuilder** to output the **StringBuilders** with the **printf** method. In Section 14.4.4, we discuss how Java uses **StringBuilder** objects to implement the **+** and **+=** operators for string concatenation.

```

1 // Fig. 14.10: StringBuilderConstructors.java
2 // StringBuilder constructors.
3
4 public class StringBuilderConstructors
5 {
6 public static void main(String[] args)
7 {
8 StringBuilder buffer1 = new StringBuilder();
9 StringBuilder buffer2 = new StringBuilder(10);
10 StringBuilder buffer3 = new StringBuilder("hello");
11
12 System.out.printf("buffer1 = \"%s\"%n", buffer1);
13 System.out.printf("buffer2 = \"%s\"%n", buffer2);
14 System.out.printf("buffer3 = \"%s\"%n", buffer3);
15 }
16 } // end class StringBuilderConstructors

```

```

buffer1 = ""
buffer2 = ""
buffer3 = "hello"

```

**Fig. 14.10** | **StringBuilder** constructors.

## 14.4.2 StringBuilder Methods **length**, **capacity**, **setLength** and **ensureCapacity**

Class **StringBuilder** provides methods **length** and **capacity** to return the number of characters currently in a **StringBuilder** and the number of characters that can be stored

in a `StringBuilder` without allocating more memory, respectively. Method **ensureCapacity** guarantees that a `StringBuilder` has at least the specified capacity. Method **setLength** increases or decreases the length of a `StringBuilder`. Figure 14.11 demonstrates these methods.

---

```

1 // Fig. 14.11: StringBuilderCapLen.java
2 // StringBuilder length, setLength, capacity and ensureCapacity methods.
3
4 public class StringBuilderCapLen
5 {
6 public static void main(String[] args)
7 {
8 StringBuilder buffer = new StringBuilder("Hello, how are you?");
9
10 System.out.printf("buffer = %s\nlength = %d\ncapacity = %d\n\n",
11 buffer.toString(), buffer.length(), buffer.capacity());
12
13 buffer.ensureCapacity(75);
14 System.out.printf("New capacity = %d\n\n", buffer.capacity());
15
16 buffer.setLength(10);
17 System.out.printf("New length = %d\nbuffer = %s\n",
18 buffer.length(), buffer.toString());
19 }
20 } // end class StringBuilderCapLen

```

```

buffer = Hello, how are you?
length = 19
capacity = 35

New capacity = 75

New length = 10
buffer = Hello, how

```

**Fig. 14.11** | `StringBuilder` `length`, `setLength`, `capacity` and `ensureCapacity` methods.

The application contains one `StringBuilder` called `buffer`. Line 8 uses the `StringBuilder` constructor that takes a `String` argument to initialize the `StringBuilder` with "Hello, how are you?". Lines 10–11 print the contents, length and capacity of the `StringBuilder`. Note in the output window that the capacity of the `StringBuilder` is initially 35. Recall that the `StringBuilder` constructor that takes a `String` argument initializes the capacity to the length of the string passed as an argument plus 16.

Line 13 uses method `ensureCapacity` to expand the capacity of the `StringBuilder` to a minimum of 75 characters. Actually, if the original capacity is less than the argument, the method ensures a capacity that's the greater of the number specified as an argument and twice the original capacity plus 2. The `StringBuilder`'s current capacity remains unchanged if it's more than the specified capacity.

**Performance Tip 14.5**

*Dynamically increasing the capacity of a `StringBuilder` can take a relatively long time. Executing a large number of these operations can degrade the performance of an application. If a `StringBuilder` is going to increase greatly in size, possibly multiple times, setting its capacity high at the beginning will increase performance.*

Line 16 uses method `setLength` to set the length of the `StringBuilder` to 10. If the specified length is less than the current number of characters in the `StringBuilder`, its contents are truncated to the specified length (i.e., the characters in the `StringBuilder` after the specified length are discarded). If the specified length is greater than the number of characters currently in the `StringBuilder`, null characters (characters with the numeric representation 0) are appended until the total number of characters in the `StringBuilder` is equal to the specified length.

### 14.4.3 `StringBuilder` Methods `charAt`, `setCharAt`, `getChars` and `reverse`

Class `StringBuilder` provides methods `charAt`, `setCharAt`, `getChars` and `reverse` to manipulate the characters in a `StringBuilder` (Fig. 14.12). Method `charAt` (line 12) takes an integer argument and returns the character in the `StringBuilder` at that index. Method `getChars` (line 15) copies characters from a `StringBuilder` into the character array passed as an argument. This method takes four arguments—the starting index from which characters should be copied in the `StringBuilder`, the index one past the last character to be copied from the `StringBuilder`, the character array into which the characters are to be copied and the starting location in the character array where the first character should be placed. Method `setCharAt` (lines 21 and 22) takes an integer and a character argument and sets the character at the specified position in the `StringBuilder` to the character argument. Method `reverse` (line 25) reverses the contents of the `StringBuilder`. Attempting to access a character that's outside the bounds of a `StringBuilder` results in a `StringIndexOutOfBoundsException`.

---

```

1 // Fig. 14.12: StringBuilderChars.java
2 // StringBuilder methods charAt, setCharAt, getChars and reverse.
3
4 public class StringBuilderChars
5 {
6 public static void main(String[] args)
7 {
8 StringBuilder buffer = new StringBuilder("hello there");
9
10 System.out.printf("buffer = %s\n", buffer.toString());
11 System.out.printf("Character at 0: %s\nCharacter at 4: %s\n\n",
12 buffer.charAt(0), buffer.charAt(4));
13
14 char[] charArray = new char[buffer.length()];
15 buffer.getChars(0, buffer.length(), charArray, 0);
16 System.out.print("The characters are: ");

```

---

**Fig. 14.12** | `StringBuilder` methods `charAt`, `setCharAt`, `getChars` and `reverse`. (Part 1 of 2.)

---

```

17
18 for (char character : charArray)
19 System.out.print(character);
20
21 buffer.setCharAt(0, 'H');
22 buffer.setCharAt(6, 'T');
23 System.out.printf("%n%nbuffer = %s", buffer.toString());
24
25 buffer.reverse();
26 System.out.printf("%n%nbuffer = %s%n", buffer.toString());
27 }
28 } // end class StringBuilderChars

```

```

buffer = hello there
Character at 0: h
Character at 4: o

The characters are: hello there

buffer = Hello There

buffer = erehT olleH

```

**Fig. 14.12** | StringBuilder methods charAt, setCharAt, getChars and reverse. (Part 2 of 2.)

#### 14.4.4 StringBuilder append Methods

Class `StringBuilder` provides *overloaded* **append** methods (Fig. 14.13) to allow values of various types to be appended to the end of a `StringBuilder`. Versions are provided for each of the primitive types and for character arrays, Strings, Objects, and more. (Remember that method `toString` produces a string representation of any `Object`.) Each method takes its argument, converts it to a string and appends it to the `StringBuilder`.

---

```

1 // Fig. 14.13: StringBuilderAppend.java
2 // StringBuilder append methods.
3
4 public class StringBuilderAppend
5 {
6 public static void main(String[] args)
7 {
8 Object objectRef = "hello";
9 String string = "goodbye";
10 char[] charArray = {'a', 'b', 'c', 'd', 'e', 'f'};
11 boolean booleanValue = true;
12 char characterValue = 'Z';
13 int integerValue = 7;
14 long longValue = 100000000000L;
15 float floatValue = 2.5f;
16 double doubleValue = 33.333;

```

**Fig. 14.13** | StringBuilder append methods. (Part 1 of 2.)

```

17
18 StringBuilder lastBuffer = new StringBuilder("last buffer");
19 StringBuilder buffer = new StringBuilder();
20
21 buffer.append(objectRef)
22 .append("%n")
23 .append(string)
24 .append("%n")
25 .append(charArray)
26 .append("%n")
27 .append(charArray, 0, 3)
28 .append("%n")
29 .append(booleanValue)
30 .append("%n")
31 .append(characterValue);
32 .append("%n")
33 .append(integerValue)
34 .append("%n")
35 .append(longValue)
36 .append("%n")
37 .append(floatValue)
38 .append("%n")
39 .append(doubleValue)
40 .append("%n")
41 .append(lastBuffer);
42
43 System.out.printf("buffer contains%n%s%n", buffer.toString());
44 }
45 } // end StringBuilderAppend

```

```

buffer contains
hello
goodbye
abcdef
abc
true
Z
7
10000000000
2.5
33.333
last buffer

```

**Fig. 14.13** | StringBuilder append methods. (Part 2 of 2.)

The compiler can use `StringBuilder` and the `append` methods to implement the `+` and `+=` String concatenation operators. For example, assuming the declarations

```

String string1 = "hello";
String string2 = "BC";
int value = 22;

```

the statement

```
String s = string1 + string2 + value;
```



concatenates "hello", "BC" and 22. The concatenation can be performed as follows:

```
String s = new StringBuilder().append("hello").append("BC").
 append(22).toString();
```

First, the preceding statement creates an *empty* `StringBuilder`, then appends to it the strings "hello" and "BC" and the integer 22. Next, `StringBuilder`'s `toString` method converts the `StringBuilder` to a `String` object to be assigned to `String s`. The statement

```
s += "!";
```

can be performed as follows (this may differ by compiler):

```
s = new StringBuilder().append(s).append("!").toString();
```

This creates an empty `StringBuilder`, then appends to it the current contents of `s` followed by "!". Next, `StringBuilder`'s method `toString` (which must be called *explicitly* here) returns the `StringBuilder`'s contents as a `String`, and the result is assigned to `s`.

### 14.4.5 `StringBuilder` Insertion and Deletion Methods

`StringBuilder` provides overloaded **insert** methods to insert values of various types at any position in a `StringBuilder`. Versions are provided for the primitive types and for character arrays, `Strings`, `Objects` and `CharSequences`. Each method takes its second argument and inserts it at the index specified by the first argument. If the first argument is less than 0 or greater than the `StringBuilder`'s length, a `StringIndexOutOfBoundsException` occurs. Class `StringBuilder` also provides methods **delete** and **deleteCharAt** to delete characters at any position in a `StringBuilder`. Method `delete` takes two arguments—the starting index and the index one past the end of the characters to delete. All characters beginning at the starting index up to but *not* including the ending index are deleted. Method `deleteCharAt` takes one argument—the index of the character to delete. Invalid indices cause both methods to throw a `StringIndexOutOfBoundsException`. Figure 14.14 demonstrates methods `insert`, `delete` and `deleteCharAt`.

---

```
1 // Fig. 14.14: StringBuilderInsertDelete.java
2 // StringBuilder methods insert, delete and deleteCharAt.
3
4 public class StringBuilderInsertDelete
5 {
6 public static void main(String[] args)
7 {
8 Object objectRef = "hello";
9 String string = "goodbye";
10 char[] charArray = {'a', 'b', 'c', 'd', 'e', 'f'};
11 boolean booleanValue = true;
12 char characterValue = 'K';
13 int integerValue = 7;
14 long longValue = 10000000;
15 float floatValue = 2.5f; // f suffix indicates that 2.5 is a float
16 double doubleValue = 33.333;
17
```

---

**Fig. 14.14** | `StringBuilder` methods `insert`, `delete` and `deleteCharAt`. (Part I of 2.)

```

18 StringBuilder buffer = new StringBuilder();
19
20 buffer.insert(0, objectRef);
21 buffer.insert(0, " "); // each of these contains two spaces
22 buffer.insert(0, string);
23 buffer.insert(0, " ");
24 buffer.insert(0, charArray);
25 buffer.insert(0, " ");
26 buffer.insert(0, charArray, 3, 3);
27 buffer.insert(0, " ");
28 buffer.insert(0, booleanValue);
29 buffer.insert(0, " ");
30 buffer.insert(0, characterValue);
31 buffer.insert(0, " ");
32 buffer.insert(0, integerValue);
33 buffer.insert(0, " ");
34 buffer.insert(0, longValue);
35 buffer.insert(0, " ");
36 buffer.insert(0, floatValue);
37 buffer.insert(0, " ");
38 buffer.insert(0, doubleValue);
39
40 System.out.printf(
41 "buffer after inserts:%n%s%n", buffer.toString());
42
43 buffer.deleteCharAt(10); // delete 5 in 2.5
44 buffer.delete(2, 6); // delete .333 in 33.333
45
46 System.out.printf(
47 "buffer after deletes:%n%s%n", buffer.toString());
48 }
49 } // end class StringBuilderInsertDelete

```

```

buffer after inserts:
33.333 2.5 10000000 7 K true def abcdef goodbye hello

buffer after deletes:
33 2. 10000000 7 K true def abcdef goodbye hello

```

**Fig. 14.14** | StringBuilder methods insert, delete and deleteCharAt. (Part 2 of 2.)

## 14.5 Class Character

Java provides eight **type-wrapper classes**—Boolean, Character, Double, Float, Byte, Short, Integer and Long—that enable primitive-type values to be treated as objects. In this section, we present class Character—the type-wrapper class for primitive type char.

Most Character methods are static methods designed for convenience in processing individual char values. These methods take at least a character argument and perform either a test or a manipulation of the character. Class Character also contains a constructor that receives a char argument to initialize a Character object. Most of the methods of class Character are presented in the next three examples. For more informa-

tion on class Character (and all the type-wrapper classes), see the `java.lang` package in the Java API documentation.

Figure 14.15 demonstrates static methods that test characters to determine whether they're a specific character type and the static methods that perform case conversions on characters. You can enter any character and apply the methods to the character.

---

```

1 // Fig. 14.15: StaticCharMethods.java
2 // Character static methods for testing characters and converting case.
3 import java.util.Scanner;
4
5 public class StaticCharMethods
6 {
7 public static void main(String[] args)
8 {
9 Scanner scanner = new Scanner(System.in); // create scanner
10 System.out.println("Enter a character and press Enter");
11 String input = scanner.next();
12 char c = input.charAt(0); // get input character
13
14 // display character info
15 System.out.printf("is defined: %b\n", Character.isDefined(c));
16 System.out.printf("is digit: %b\n", Character.isDigit(c));
17 System.out.printf("is first character in a Java identifier: %b\n",
18 Character.isJavaIdentifierStart(c));
19 System.out.printf("is part of a Java identifier: %b\n",
20 Character.isJavaIdentifierPart(c));
21 System.out.printf("is letter: %b\n", Character.isLetter(c));
22 System.out.printf(
23 "is letter or digit: %b\n", Character.isLetterOrDigit(c));
24 System.out.printf(
25 "is lower case: %b\n", Character.isLowerCase(c));
26 System.out.printf(
27 "is upper case: %b\n", Character.isUpperCase(c));
28 System.out.printf(
29 "to upper case: %s\n", Character.toUpperCase(c));
30 System.out.printf(
31 "to lower case: %s\n", Character.toLowerCase(c));
32 }
33 } // end class StaticCharMethods

```

```

Enter a character and press Enter
A
is defined: true
is digit: false
is first character in a Java identifier: true
is part of a Java identifier: true
is letter: true
is letter or digit: true
is lower case: false
is upper case: true
to upper case: A
to lower case: a

```

**Fig. 14.15** | Character static methods for testing characters and converting case. (Part I of 2.)

```

Enter a character and press Enter
8
is defined: true
is digit: true
is first character in a Java identifier: false
is part of a Java identifier: true
is letter: false
is letter or digit: true
is lower case: false
is upper case: false
to upper case: 8
to lower case: 8

```

```

Enter a character and press Enter
$
is defined: true
is digit: false
is first character in a Java identifier: true
is part of a Java identifier: true
is letter: false
is letter or digit: false
is lower case: false
is upper case: false
to upper case: $
to lower case: $

```

**Fig. 14.15** | Character static methods for testing characters and converting case. (Part 2 of 2.)

Line 15 uses Character method **isDefined** to determine whether character *c* is defined in the Unicode character set. If so, the method returns **true**; otherwise, it returns **false**. Line 16 uses Character method **isDigit** to determine whether character *c* is a defined Unicode digit. If so, the method returns **true**, and otherwise, **false**.

Line 18 uses Character method **isJavaIdentifierStart** to determine whether *c* is a character that can be the first character of an identifier in Java—that is, a letter, an underscore (**\_**) or a dollar sign (**\$**). If so, the method returns **true**, and otherwise, **false**. Line 20 uses Character method **isJavaIdentifierPart** to determine whether character *c* is a character that can be used in an identifier in Java—that is, a digit, a letter, an underscore (**\_**) or a dollar sign (**\$**). If so, the method returns **true**, and otherwise, **false**.

Line 21 uses Character method **isLetter** to determine whether character *c* is a letter. If so, the method returns **true**, and otherwise, **false**. Line 23 uses Character method **isLetterOrDigit** to determine whether character *c* is a letter or a digit. If so, the method returns **true**, and otherwise, **false**.

Line 25 uses Character method **isLowerCase** to determine whether character *c* is a lowercase letter. If so, the method returns **true**, and otherwise, **false**. Line 27 uses Character method **isUpperCase** to determine whether character *c* is an uppercase letter. If so, the method returns **true**, and otherwise, **false**.

Line 29 uses Character method **toUpperCase** to convert the character *c* to its uppercase equivalent. The method returns the converted character if the character has an upper-

case equivalent, and otherwise, the method returns its original argument. Line 31 uses Character method **toLowerCase** to convert the character *c* to its lowercase equivalent. The method returns the converted character if the character has a lowercase equivalent, and otherwise, the method returns its original argument.

Figure 14.16 demonstrates static Character methods **digit** and **forDigit**, which convert characters to digits and digits to characters, respectively, in different number systems. Common number systems include decimal (base 10), octal (base 8), hexadecimal (base 16) and binary (base 2). The base of a number is also known as its **radix**. For more information on conversions between number systems, see online Appendix J.

---

```

1 // Fig. 14.16: StaticCharMethods2.java
2 // Character class static conversion methods.
3 import java.util.Scanner;
4
5 public class StaticCharMethods2
6 {
7 // executes application
8 public static void main(String[] args)
9 {
10 Scanner scanner = new Scanner(System.in);
11
12 // get radix
13 System.out.println("Please enter a radix:");
14 int radix = scanner.nextInt();
15
16 // get user choice
17 System.out.printf("Please choose one:%n1 -- %s%n2 -- %s%n",
18 "Convert digit to character", "Convert character to digit");
19 int choice = scanner.nextInt();
20
21 // process request
22 switch (choice)
23 {
24 case 1: // convert digit to character
25 System.out.println("Enter a digit:");
26 int digit = scanner.nextInt();
27 System.out.printf("Convert digit to character: %s%n",
28 Character.forDigit(digit, radix));
29 break;
30
31 case 2: // convert character to digit
32 System.out.println("Enter a character:");
33 char character = scanner.next().charAt(0);
34 System.out.printf("Convert character to digit: %s%n",
35 Character.digit(character, radix));
36 break;
37 }
38 }
39 } // end class StaticCharMethods2

```

---

**Fig. 14.16** | Character class static conversion methods. (Part I of 2.)

```

Please enter a radix:
16
Please choose one:
1 -- Convert digit to character
2 -- Convert character to digit
2
Enter a character:
A
Convert character to digit: 10

```

```

Please enter a radix:
16
Please choose one:
1 -- Convert digit to character
2 -- Convert character to digit
1
Enter a digit:
13
Convert digit to character: d

```

**Fig. 14.16** | Character class static conversion methods. (Part 2 of 2.)

Line 28 uses method `forDigit` to convert the integer `digit` into a character in the number system specified by the integer `radix` (the base of the number). For example, the decimal integer 13 in base 16 (the radix) has the character value 'd'. Lowercase and uppercase letters represent the *same* value in number systems. Line 35 uses method `digit` to convert variable `character` into an integer in the number system specified by the integer `radix` (the base of the number). For example, the character 'A' is the base 16 (the radix) representation of the base 10 value 10. The radix must be between 2 and 36, inclusive.

Figure 14.17 demonstrates the constructor and several instance methods of class `Character`—`charValue`, `toString` and `equals`. Lines 7–8 instantiate two `Character` objects by assigning the character constants 'A' and 'a', respectively, to the `Character` variables. Java automatically converts these `char` literals into `Character` objects—a process known as *autoboxing* that we discuss in more detail in Section 16.4. Line 11 uses `Character` method `charValue` to return the `char` value stored in `Character` object `c1`. Line 11 returns a string representation of `Character` object `c2` using method `toString`. The condition in line 13 uses method `equals` to determine whether the object `c1` has the same contents as the object `c2` (i.e., the characters inside each object are equal).

---

```

1 // Fig. 14.17: OtherCharMethods.java
2 // Character class instance methods.
3 public class OtherCharMethods
4 {
5 public static void main(String[] args)
6 {
7 Character c1 = 'A';
8 Character c2 = 'a';

```

---

**Fig. 14.17** | Character class instance methods. (Part 1 of 2.)

```

9
10 System.out.printf(
11 "c1 = %s%c2 = %s%n", c1.charValue(), c2.toString());
12
13 if (c1.equals(c2))
14 System.out.println("c1 and c2 are equal%n");
15 else
16 System.out.println("c1 and c2 are not equal%n");
17 }
18 } // end class OtherCharMethods

```

```

c1 = A
c2 = a

c1 and c2 are not equal

```

**Fig. 14.17** | Character class instance methods. (Part 2 of 2.)

## 14.6 Tokenizing Strings

When you read a sentence, your mind breaks it into **tokens**—individual words and punctuation marks that convey meaning to you. Compilers also perform tokenization. They break up statements into individual pieces like keywords, identifiers, operators and other programming-language elements. We now study class `String`'s **`split`** method, which breaks a `String` into its component tokens. Tokens are separated from one another by **delimiters**, typically white-space characters such as space, tab, newline and carriage return. Other characters can also be used as delimiters to separate tokens. The application in Fig. 14.18 demonstrates `String`'s `split` method.

When the user presses the *Enter* key, the input sentence is stored in variable `sentence`. Line 17 invokes `String` method `split` with the `String` argument " ", which returns an array of `Strings`. The space character in the argument `String` is the delimiter that method `split` uses to locate the tokens in the `String`. As you'll learn in the next section, the argument to method `split` can be a regular expression for more complex tokenizing. Line 19 displays the length of the array `tokens`—i.e., the number of tokens in `sentence`. Lines 21–22 output each token on a separate line.

```

1 // Fig. 14.18: TokenTest.java
2 // StringTokenizer object used to tokenize strings.
3 import java.util.Scanner;
4 import java.util.StringTokenizer;
5
6 public class TokenTest
7 {
8 // execute application
9 public static void main(String[] args)
10 {
11 // get sentence
12 Scanner scanner = new Scanner(System.in);

```

**Fig. 14.18** | `StringTokenizer` object used to tokenize strings. (Part 1 of 2.)

```

13 System.out.println("Enter a sentence and press Enter");
14 String sentence = scanner.nextLine();
15
16 // process user sentence
17 String[] tokens = sentence.split(" ");
18 System.out.printf("Number of elements: %d\nThe tokens are:%n",
19 tokens.length);
20
21 for (String token : tokens)
22 System.out.println(token);
23 }
24 } // end class TokenTest

```

```

Enter a sentence and press Enter
This is a sentence with seven tokens
Number of elements: 7
The tokens are:
This
is
a
sentence
with
seven
tokens

```

**Fig. 14.18** | StringTokenizer object used to tokenize strings. (Part 2 of 2.)

## 14.7 Regular Expressions, Class Pattern and Class Matcher

A **regular expression** is a String that describes a *search pattern* for *matching* characters in other Strings. Such expressions are useful for *validating input* and ensuring that data is in a particular format. For example, a ZIP code must consist of five digits, and a last name must contain only letters, spaces, apostrophes and hyphens. One application of regular expressions is to facilitate the construction of a compiler. Often, a large and complex regular expression is used to *validate the syntax of a program*. If the program code does *not* match the regular expression, the compiler knows that there's a syntax error in the code.

Class String provides several methods for performing regular-expression operations, the simplest of which is the matching operation. String method **matches** receives a String that specifies the regular expression and matches the contents of the String object on which it's called to the regular expression. The method returns a boolean indicating whether the match succeeded.

A regular expression consists of literal characters and special symbols. Figure 14.19 specifies some **predefined character classes** that can be used with regular expressions. A character class is an *escape sequence* that represents a group of characters. A digit is any numeric character. A **word character** is any letter (uppercase or lowercase), any digit or the underscore character. A white-space character is a space, a tab, a carriage return, a newline or a form feed. Each character class matches a single character in the String we're attempting to match with the regular expression.



| Character | Matches                   | Character | Matches                      |
|-----------|---------------------------|-----------|------------------------------|
| \d        | any digit                 | \D        | any nondigit                 |
| \w        | any word character        | \W        | any nonword character        |
| \s        | any white-space character | \S        | any non-whitespace character |

**Fig. 14.19** | Predefined character classes.

Regular expressions are not limited to these predefined character classes. The expressions employ various operators and other forms of notation to match complex patterns. We examine several of these techniques in the application in Figs. 14.20 and 14.21, which *validates user input* via regular expressions. [Note: This application is not designed to match all possible valid user input.]

---

```

1 // Fig. 14.20: ValidateInput.java
2 // Validating user information using regular expressions.
3
4 public class ValidateInput
5 {
6 // validate first name
7 public static boolean validateFirstName(String firstName)
8 {
9 return firstName.matches("[A-Z][a-zA-Z]*");
10 }
11
12 // validate last name
13 public static boolean validateLastName(String lastName)
14 {
15 return lastName.matches("[a-zA-z]+(['-][a-zA-Z]+)*");
16 }
17
18 // validate address
19 public static boolean validateAddress(String address)
20 {
21 return address.matches(
22 "\\d+\\s+([a-zA-Z]+|[a-zA-Z]+\\s[a-zA-Z]+)");
23 }
24
25 // validate city
26 public static boolean validateCity(String city)
27 {
28 return city.matches("([a-zA-Z]+|[a-zA-Z]+\\s[a-zA-Z]+)");
29 }
30
31 // validate state
32 public static boolean validateState(String state)
33 {

```

---

**Fig. 14.20** | Validating user information using regular expressions. (Part I of 2.)

---

```

34 return state.matches("[a-zA-Z]+|[a-zA-Z]+\\s[a-zA-Z]+");
35 }
36
37 // validate zip
38 public static boolean validateZip(String zip)
39 {
40 return zip.matches("\\d{5}");
41 }
42
43 // validate phone
44 public static boolean validatePhone(String phone)
45 {
46 return phone.matches("[1-9]\\d{2}-[1-9]\\d{2}-\\d{4}");
47 }
48 } // end class ValidateInput

```

---

**Fig. 14.20** | Validating user information using regular expressions. (Part 2 of 2.)

---

```

1 // Fig. 14.21: Validate.java
2 // Input and validate data from user using the ValidateInput class.
3 import java.util.Scanner;
4
5 public class Validate
6 {
7 public static void main(String[] args)
8 {
9 // get user input
10 Scanner scanner = new Scanner(System.in);
11 System.out.println("Please enter first name:");
12 String firstName = scanner.nextLine();
13 System.out.println("Please enter last name:");
14 String lastName = scanner.nextLine();
15 System.out.println("Please enter address:");
16 String address = scanner.nextLine();
17 System.out.println("Please enter city:");
18 String city = scanner.nextLine();
19 System.out.println("Please enter state:");
20 String state = scanner.nextLine();
21 System.out.println("Please enter zip:");
22 String zip = scanner.nextLine();
23 System.out.println("Please enter phone:");
24 String phone = scanner.nextLine();
25
26 // validate user input and display error message
27 System.out.println("%nValidate Result:");
28
29 if (!ValidateInput.validateFirstName(firstName))
30 System.out.println("Invalid first name");
31 else if (!ValidateInput.validateLastName(lastName))
32 System.out.println("Invalid last name");
33 else if (!ValidateInput.validateAddress(address))
34 System.out.println("Invalid address");

```

---

**Fig. 14.21** | Input and validate data from user using the ValidateInput class. (Part 1 of 2.)

```
35 else if (!ValidateInput.validateCity(city))
36 System.out.println("Invalid city");
37 else if (!ValidateInput.validateState(state))
38 System.out.println("Invalid state");
39 else if (!ValidateInput.validateZip(zip))
40 System.out.println("Invalid zip code");
41 else if (!ValidateInput.validatePhone(phone))
42 System.out.println("Invalid phone number");
43 else
44 System.out.println("Valid input. Thank you.");
45 }
46 } // end class Validate
```

```
Please enter first name:
Jane
Please enter last name:
Doe
Please enter address:
123 Some Street
Please enter city:
Some City
Please enter state:
SS
Please enter zip:
123
Please enter phone:
123-456-7890

Validate Result:
Invalid zip code
```

```
Please enter first name:
Jane
Please enter last name:
Doe
Please enter address:
123 Some Street
Please enter city:
Some City
Please enter state:
SS
Please enter zip:
12345
Please enter phone:
123-456-7890

Validate Result:
Valid input. Thank you.
```

**Fig. 14.21** | Input and validate data from user using the `ValidateInput` class. (Part 2 of 2.)

Figure 14.20 validates user input. Line 9 validates the first name. To match a set of characters that does not have a predefined character class, use square brackets, `[]`. For example, the pattern `"[aeiou]"` matches a single character that's a vowel. Character ranges

are represented by placing a dash (-) between two characters. In the example, "[A-Z]" matches a single uppercase letter. If the first character in the brackets is "^", the expression accepts any character other than those indicated. However, "[^Z]" is not the same as "[A-Y]", which matches uppercase letters A–Y—"[^Z]" matches *any character other than* capital Z, including lowercase letters and nonletters such as the newline character. Ranges in character classes are determined by the letters' integer values. In this example, "[A-Za-z]" matches all uppercase and lowercase letters. The range "[A-z]" matches all letters and also matches those characters (such as [ and \) with an integer value between uppercase Z and lowercase a (for more information on integer values of characters see Appendix B). Like predefined character classes, character classes delimited by square brackets match a single character in the search object.

In line 9, the asterisk after the second character class indicates that any number of letters can be matched. In general, when the regular-expression operator "\*" appears in a regular expression, the application attempts to match zero or more occurrences of the subexpression immediately preceding the "\*". Operator "+" attempts to match one or more occurrences of the subexpression immediately preceding "+". So both "A\*" and "A+" will match "AAA" or "A", but only "A\*" will match an empty string.

If method `validateFirstName` returns `true` (line 29 of Fig. 14.21), the application attempts to validate the last name (line 31) by calling `validateLastName` (lines 13–16 of Fig. 14.20). The regular expression to validate the last name matches any number of letters split by spaces, apostrophes or hyphens.

Line 33 of Fig. 14.21 calls method `validateAddress` (lines 19–23 of Fig. 14.20) to validate the address. The first character class matches any digit one or more times (`\\d+`). Two `\\` characters are used, because `\\` normally starts an escape sequence in a string. So `\\d` in a `String` represents the regular-expression pattern `\\d`. Then we match one or more white-space characters (`\\s+`). The character `|` matches the expression to its left or to its right. For example, `"Hi (John|Jane)"` matches both `"Hi John"` and `"Hi Jane"`. The parentheses are used to group parts of the regular expression. In this example, the left side of `|` matches a single word, and the right side matches two words separated by any amount of white space. So the address must contain a number followed by one or two words. Therefore, `"10 Broadway"` and `"10 Main Street"` are both valid addresses in this example. The city (lines 26–29 of Fig. 14.20) and state (lines 32–35 of Fig. 14.20) methods also match any word of at least one character or, alternatively, any two words of at least one character if the words are separated by a single space, so both `Wal``tham` and `West` `Newton` would match.

### Quantifiers

The asterisk (\*) and plus (+) are formally called **quantifiers**. Figure 14.22 lists all the quantifiers. We've already discussed how the asterisk (\*) and plus (+) quantifiers work. All quantifiers affect only the subexpression immediately preceding the quantifier. Quantifier question mark (?) matches zero or one occurrences of the expression that it quantifies. A set of braces containing one number (`{n}`) matches exactly *n* occurrences of the expression it quantifies. We demonstrate this quantifier to validate the zip code in Fig. 14.20 at line 40. Including a comma after the number enclosed in braces matches at least *n* occurrences of the quantified expression. The set of braces containing two numbers (`{n,m}`), matches between *n* and *m* occurrences of the expression that it qualifies. Quantifiers may be applied to patterns enclosed in parentheses to create more complex regular expressions.

| Quantifier              | Matches                                                        |
|-------------------------|----------------------------------------------------------------|
| *                       | Matches zero or more occurrences of the pattern.               |
| +                       | Matches one or more occurrences of the pattern.                |
| ?                       | Matches zero or one occurrences of the pattern.                |
| { <i>n</i> }            | Matches exactly <i>n</i> occurrences.                          |
| { <i>n</i> , }          | Matches at least <i>n</i> occurrences.                         |
| { <i>n</i> , <i>m</i> } | Matches between <i>n</i> and <i>m</i> (inclusive) occurrences. |

**Fig. 14.22** | Quantifiers used in regular expressions.

All of the quantifiers are **greedy**. This means that they'll match as many occurrences as they can as long as the match is still successful. However, if any of these quantifiers is followed by a question mark (?), the quantifier becomes **reluctant** (sometimes called **lazy**). It then will match as few occurrences as possible as long as the match is still successful.

The zip code (line 40 in Fig. 14.20) matches a digit five times. This regular expression uses the digit character class and a quantifier with the digit 5 between braces. The phone number (line 46 in Fig. 14.20) matches three digits (the first one cannot be zero) followed by a dash followed by three more digits (again the first one cannot be zero) followed by four more digits.

String method `matches` checks whether an entire String conforms to a regular expression. For example, we want to accept "Smith" as a last name, but not "9@Smith#". If only a substring matches the regular expression, method `matches` returns false.

### *Replacing Substrings and Splitting Strings*

Sometimes it's useful to replace parts of a string or to split a string into pieces. For this purpose, class String provides methods **replaceAll**, **replaceFirst** and **split**. These methods are demonstrated in Fig. 14.23.

---

```

1 // Fig. 14.23: RegexSubstitution.java
2 // String methods replaceFirst, replaceAll and split.
3 import java.util.Arrays;
4
5 public class RegexSubstitution
6 {
7 public static void main(String[] args)
8 {
9 String firstString = "This sentence ends in 5 stars *****";
10 String secondString = "1, 2, 3, 4, 5, 6, 7, 8";
11
12 System.out.printf("Original String 1: %s\n", firstString);
13
14 // replace '*' with '^'
15 firstString = firstString.replaceAll("*", "^");
16
17 System.out.printf("^ substituted for *: %s\n", firstString);

```

---

**Fig. 14.23** | String methods `replaceFirst`, `replaceAll` and `split`. (Part I of 2.)

```

18
19 // replace 'stars' with 'carets'
20 firstString = firstString.replaceAll("stars", "carets");
21
22 System.out.printf(
23 "\"carets\" substituted for \"stars\": %s\n", firstString);
24
25 // replace words with 'word'
26 System.out.printf("Every word replaced by \"word\": %s\n\n",
27 firstString.replaceAll("\\w+", "word"));
28
29 System.out.printf("Original String 2: %s\n", secondString);
30
31 // replace first three digits with 'digit'
32 for (int i = 0; i < 3; i++)
33 secondString = secondString.replaceFirst("\\d", "digit");
34
35 System.out.printf(
36 "First 3 digits replaced by \"digit\" : %s\n", secondString);
37
38 System.out.print("String split at commas: ");
39 String[] results = secondString.split(",\\s*"); // split on commas
40 System.out.println(Arrays.toString(results));
41 }
42 } // end class RegexSubstitution

```

```

Original String 1: This sentence ends in 5 stars *****
^ substituted for *: This sentence ends in 5 stars ^^^^^^
"carets" substituted for "stars": This sentence ends in 5 carets ^^^^^^
Every word replaced by "word": word word word word word word ^^^^^^

Original String 2: 1, 2, 3, 4, 5, 6, 7, 8
First 3 digits replaced by "digit" : digit, digit, digit, 4, 5, 6, 7, 8
String split at commas: ["digit", "digit", "digit", "4", "5", "6", "7", "8"]

```

**Fig. 14.23** | String methods `replaceFirst`, `replaceAll` and `split`. (Part 2 of 2.)

Method `replaceAll` replaces text in a `String` with new text (the second argument) wherever the original `String` matches a regular expression (the first argument). Line 15 replaces every instance of `*` in `firstString` with `^`. The regular expression (`"\\s"`) precedes character `*` with two backslashes. Normally, `*` is a quantifier indicating that a regular expression should match *any number of occurrences* of a preceding pattern. However, in line 15, we want to find all occurrences of the literal character `*`—to do this, we must escape character `*` with character `\`. Escaping a special regular-expression character with `\` instructs the matching engine to find the actual character. Since the expression is stored in a Java `String` and `\` is a special character in Java `Strings`, we must include an additional `\`. So the Java `String` `"\\s"` represents the regular-expression pattern `\*` which matches a single `*` character in the search string. In line 20, every match for the regular expression `"stars"` in `firstString` is replaced with `"carets"`. Line 27 uses `replaceAll` to replace all words in the string with `"word"`.

Method `replaceFirst` (line 33) replaces the first occurrence of a pattern match. Java Strings are immutable; therefore, method `replaceFirst` returns a new String in which the appropriate characters have been replaced. This line takes the original String and replaces it with the String returned by `replaceFirst`. By iterating three times we replace the first three instances of a digit (\d) in `secondString` with the text "digit".

Method `split` divides a String into several substrings. The original is broken in any location that matches a specified regular expression. Method `split` returns an array of Strings containing the substrings between matches for the regular expression. In line 39, we use method `split` to tokenize a String of comma-separated integers. The argument is the regular expression that locates the delimiter. In this case, we use the regular expression `",\\s*"` to separate the substrings wherever a comma occurs. By matching any white-space characters, we eliminate extra spaces from the resulting substrings. The commas and white-space characters are not returned as part of the substrings. Again, the Java String `",\\s*"` represents the regular expression `,\s*`. Line 40 uses Arrays method `toString` to display the contents of array `results` in square brackets and separated by commas.

### Classes Pattern and Matcher

In addition to the regular-expression capabilities of class String, Java provides other classes in package `java.util.regex` that help developers manipulate regular expressions. Class **Pattern** represents a regular expression. Class **Matcher** contains both a regular-expression pattern and a `CharSequence` in which to search for the pattern.

**CharSequence** (package `java.lang`) is an *interface* that allows read access to a sequence of characters. The interface requires that the methods `charAt`, `length`, `subSequence` and `toString` be declared. Both String and `StringBuilder` implement interface `CharSequence`, so an instance of either of these classes can be used with class **Matcher**.



#### Common Programming Error 14.2

*A regular expression can be tested against an object of any class that implements interface `CharSequence`, but the regular expression must be a String. Attempting to create a regular expression as a `StringBuilder` is an error.*

If a regular expression will be used only once, static **Pattern** method **matches** can be used. This method takes a String that specifies the regular expression and a `CharSequence` on which to perform the match. This method returns a `boolean` indicating whether the search object (the second argument) *matches* the regular expression.

If a regular expression will be used more than once (in a loop, for example), it's more efficient to use static **Pattern** method **compile** to create a specific **Pattern** object for that regular expression. This method receives a String representing the pattern and returns a new **Pattern** object, which can then be used to call method **matcher**. This method receives a `CharSequence` to search and returns a **Matcher** object.

**Matcher** provides method **matches**, which performs the same task as **Pattern** method **matches**, but receives no arguments—the search pattern and search object are encapsulated in the **Matcher** object. Class **Matcher** provides other methods, including **find**, **lookingAt**, **replaceFirst** and **replaceAll**.

Figure 14.24 presents a simple example that employs regular expressions. This program matches birthdays against a regular expression. The expression matches only birthdays that do not occur in April and that belong to people whose names begin with "J".

```

1 // Fig. 14.24: RegexMatches.java
2 // Classes Pattern and Matcher.
3 import java.util.regex.Matcher;
4 import java.util.regex.Pattern;
5
6 public class RegexMatches
7 {
8 public static void main(String[] args)
9 {
10 // create regular expression
11 Pattern expression =
12 Pattern.compile("J.*\\d[0-35-9]-\\d\\d\\d\\d");
13
14 String string1 = "Jane's Birthday is 05-12-75\\n" +
15 "Dave's Birthday is 11-04-68\\n" +
16 "John's Birthday is 04-28-73\\n" +
17 "Joe's Birthday is 12-17-77";
18
19 // match regular expression to string and print matches
20 Matcher matcher = expression.matcher(string1);
21
22 while (matcher.find())
23 System.out.println(matcher.group());
24 }
25 } // end class RegexMatches

```

```

Jane's Birthday is 05-12-75
Joe's Birthday is 12-17-77

```

**Fig. 14.24** | Classes Pattern and Matcher.

Lines 11–12 create a `Pattern` by invoking static `Pattern` method `compile`. The *dot character* "." in the regular expression (line 12) matches any single character except a new-line character. Line 20 creates the `Matcher` object for the compiled regular expression and the matching sequence (`string1`). Lines 22–23 use a `while` loop to *iterate* through the `String`. Line 22 uses `Matcher` method `find` to attempt to match a piece of the search object to the search pattern. Each call to this method starts at the point where the last call ended, so multiple matches can be found. `Matcher` method `lookingAt` performs the same way, except that it always starts from the beginning of the search object and will always find the *first* match if there is one.



### Common Programming Error 14.3

*Method matches (from class `String`, `Pattern` or `Matcher`) will return true only if the entire search object matches the regular expression. Methods `find` and `lookingAt` (from class `Matcher`) will return true if a portion of the search object matches the regular expression.*

Line 23 uses `Matcher` method `group`, which returns the `String` from the search object that matches the search pattern. The `String` that's returned is the one that was last matched by a call to `find` or `lookingAt`. The output in Fig. 14.24 shows the two matches that were found in `string1`.



*Java SE 8*

As you'll see in Section 17.7, you can combine regular-expression processing with Java SE 8 lambdas and streams to implement powerful String-and-file processing applications.

## 14.8 Wrap-Up

In this chapter, you learned about more `String` methods for selecting portions of `Strings` and manipulating `Strings`. You learned about the `Character` class and some of the methods it declares to handle chars. The chapter also discussed the capabilities of the `StringBuilder` class for creating `Strings`. The end of the chapter discussed regular expressions, which provide a powerful capability to search and match portions of `Strings` that fit a particular pattern. In the next chapter, you'll learn about file processing, including how persistent data is stored and retrieved.

## Summary

### *Section 14.2 Fundamentals of Characters and Strings*

- A character literal's value (p. 589) is its integer value in Unicode (p. 589). `Strings` can include letters, digits and special characters such as `+`, `-`, `*`, `/` and `$`. A string in Java is an object of class `String`. `String` literals (p. 589) are often referred to as `String` objects and are written in a program in double quotes.

### *Section 14.3 Class String*

- `String` objects are immutable (p. 591)—after they're created, their character contents cannot be changed.
- `String` method `length` (p. 591) returns the number of characters in a `String`.
- `String` method `charAt` (p. 591) returns the character at a specific position.
- `String` method `regionMatches` (p. 593) compares portions of two strings for equality.
- `String` method `equals` tests for equality. The method returns `true` if the contents of the `Strings` are equal, `false` otherwise. Method `equals` uses a lexicographical comparison (p. 594) for `Strings`.
- When primitive-type values are compared with `==`, the result is `true` if both values are identical. When references are compared with `==`, the result is `true` if both refer to the same object.
- Java treats all string literals with the same contents as a single `String` object.
- `String` method `equalsIgnoreCase` performs a case-insensitive string comparison.
- `String` method `compareTo` uses a lexicographical comparison and returns 0 if the `Strings` are equal, a negative number if the string that calls `compareTo` is less than the argument `String` and a positive number if the string that calls `compareTo` is greater than the argument `String`.
- `String` methods `startsWith` and `endsWith` (p. 596) determine whether a string starts with or ends with the specified characters, respectively.
- `String` method `indexOf` (p. 597) locates the first occurrence of a character or a substring in a string. `String` method `lastIndexOf` (p. 597) locates the last occurrence of a character or a substring in a string.
- `String` method `substring` copies and returns part of an existing string object.
- `String` method `concat` (p. 600) concatenates two string objects and returns a new string object.

- String method `replace` returns a new string object that replaces every occurrence in a String of its first character argument with its second character argument.
- String method `toUpperCase` (p. 601) returns a new string with uppercase letters in the positions where the original string had lowercase letters. String method `toLowerCase` (p. 602) returns a new string with lowercase letters in the positions where the original string had uppercase letters.
- String method `trim` (p. 602) returns a new string object in which all white-space characters (e.g., spaces, newlines and tabs) have been removed from the beginning and end of a string.
- String method `toArray` (p. 602) returns a char array containing a copy of the string's characters.
- String class static method `valueOf` returns its argument converted to a string.

#### Section 14.4 Class *StringBuilder*

- Class *StringBuilder* provides constructors that enable *StringBuilders* to be initialized with no characters and an initial capacity of 16 characters, with no characters and an initial capacity specified in the integer argument, or with a copy of the characters of the String argument and an initial capacity that's the number of characters in the String argument plus 16.
- *StringBuilder* method `length` (p. 604) returns the number of characters currently stored in a *StringBuilder*. *StringBuilder* method `capacity` (p. 604) returns the number of characters that can be stored in a *StringBuilder* without allocating more memory.
- *StringBuilder* method `ensureCapacity` (p. 605) ensures that a *StringBuilder* has at least the specified capacity. Method `setLength` increases or decreases the length of a *StringBuilder*.
- *StringBuilder* method `charAt` (p. 606) returns the character at the specified index. Method `setCharAt` (p. 606) sets the character at the specified position. *StringBuilder* method `getChars` (p. 606) copies characters in the *StringBuilder* into the character array passed as an argument.
- *StringBuilder*'s overloaded `append` methods (p. 607) add primitive-type, character-array, String, Object or *CharSequence* (p. 607) values to the end of a *StringBuilder*.
- *StringBuilder*'s overloaded `insert` (p. 609) methods insert primitive-type, character-array, String, Object or *CharSequence* values at any position in a *StringBuilder*.

#### Section 14.5 Class *Character*

- *Character* method `isDefined` (p. 612) determines whether a character is in the Unicode character set.
- *Character* method `isDigit` (p. 612) determines whether a character is a defined Unicode digit.
- *Character* method `isJavaIdentifierStart` (p. 612) determines whether a character can be used as the first character of a Java identifier. *Character* method `isJavaIdentifierPart` (p. 612) determines if a character can be used in an identifier.
- *Character* method `isLetter` (p. 612) determines whether a character is a letter. *Character* method `isLetterOrDigit` (p. 612) determines if a character is a letter or a digit.
- *Character* method `isLowerCase` (p. 612) determines whether a character is a lowercase letter. *Character* method `isUpperCase` (p. 612) determines whether a character is an uppercase letter.
- *Character* method `toUpperCase` (p. 612) converts a character to its uppercase equivalent. *Character* method `toLowerCase` (p. 613) converts a character to its lowercase equivalent.
- *Character* method `digit` (p. 613) converts its character argument into an integer in the number system specified by its integer argument `radix` (p. 613). *Character* method `forDigit` (p. 613) converts its integer argument `digit` into a character in the number system specified by its integer argument `radix`.

- Character method `charValue` (p. 614) returns the `char` stored in a `Character` object. Character method `toString` returns a `String` representation of a `Character`.

### **Section 14.6 Tokenizing Strings**

- Class `String`'s `split` method (p. 615) tokenizes a `String` based on the delimiter (p. 615) specified as an argument and returns an array of `Strings` containing the tokens (p. 615).

### **Section 14.7 Regular Expressions, Class `Pattern` and Class `Matcher`**

- Regular expressions (p. 616) are sequences of characters and symbols that define a set of strings. They're useful for validating input and ensuring that data is in a particular format.
- `String` method `matches` (p. 616) receives a string that specifies the regular expression and matches the contents of the `String` object on which it's called to the regular expression. The method returns a `boolean` indicating whether the match succeeded.
- A character class is an escape sequence that represents a group of characters. Each character class matches a single character in the string we're attempting to match with the regular expression.
- A word character (`\w`; p. 616) is any letter (uppercase or lowercase), any digit or the underscore character.
- A white-space character (`\s`) is a space, a tab, a carriage return, a newline or a form feed.
- A digit (`\d`) is any numeric character.
- To match a set of characters that does not have a predefined character class (p. 616), use square brackets, `[]`. Ranges can be represented by placing a dash (`-`) between two characters. If the first character in the brackets is `"^"`, the expression accepts any character other than those indicated.
- When the regular expression operator `"*"` appears in a regular expression, the program attempts to match zero or more occurrences of the subexpression immediately preceding the `"*"`.
- Operator `"+"` attempts to match one or more occurrences of the subexpression preceding it.
- The character `"|"` allows a match of the expression to its left or to its right.
- Parentheses `()` are used to group parts of the regular expression.
- The asterisk `(*)` and plus `(+)` are formally called quantifiers (p. 620).
- A quantifier affects only the subexpression immediately preceding it.
- Quantifier question mark `(?)` matches zero or one occurrences of the expression that it quantifies.
- A set of braces containing one number `{n}` matches exactly *n* occurrences of the expression it quantifies. Including a comma after the number enclosed in braces matches at least *n* occurrences.
- A set of braces containing two numbers `{n,m}` matches between *n* and *m* occurrences of the expression that it qualifies.
- Quantifiers are greedy (p. 621)—they'll match as many occurrences as they can as long as the match is successful. If a quantifier is followed by a question mark `(?)`, the quantifier becomes reluctant (p. 621), matching as few occurrences as possible as long as the match is successful.
- `String` method `replaceAll` (p. 621) replaces text in a string with new text (the second argument) wherever the original string matches a regular expression (the first argument).
- Escaping a special regular-expression character with a `\` instructs the regular-expression matching engine to find the actual character, as opposed to what it represents in a regular expression.
- `String` method `replaceFirst` (p. 621) replaces the first occurrence of a pattern match and returns a new string in which the appropriate characters have been replaced.
- `String` method `split` (p. 621) divides a string into substrings at any location that matches a specified regular expression and returns an array of the substrings.

- Class `Pattern` (p. 623) represents a regular expression.
- Class `Matcher` (p. 623) contains a regular-expression pattern and a `CharSequence` in which to search.
- `CharSequence` is an interface (p. 623) that allows read access to a sequence of characters. Both `String` and `StringBuilder` implement this interface, so they can be used with class `Matcher`.
- If a regular expression will be used only once, static `Pattern` method `matches` (p. 623) takes a string that specifies the regular expression and a `CharSequence` on which to perform the match. This method returns a `boolean` indicating whether the search object matches the regular expression.
- If a regular expression will be used more than once, it's more efficient to use static `Pattern` method `compile` (p. 623) to create a specific `Pattern` object for that regular expression. This method receives a string representing the pattern and returns a new `Pattern` object.
- `Pattern` method `matcher` (p. 623) receives a `CharSequence` to search and returns a `Matcher` object. `Matcher` method `matches` (p. 623) performs the same task as `Pattern` method `matches` but without arguments.
- `Matcher` method `find` (p. 623) attempts to match a piece of the search object to the search pattern. Each call to this method starts at the point where the last call ended, so multiple matches can be found.
- `Matcher` method `lookingAt` (p. 623) performs the same as `find`, except that it always starts from the beginning of the search object and will always find the first match if there is one.
- `Matcher` method `group` (p. 624) returns the string from the search object that matches the search pattern. The string returned is the one that was last matched by a call to `find` or `lookingAt`.

## Self-Review Exercises

- 14.1** State whether each of the following is *true* or *false*. If *false*, explain why.
- When `String` objects are compared using `==`, the result is `true` if the `Strings` contain the same values.
  - A `String` can be modified after it's created.
- 14.2** For each of the following, write a single statement that performs the indicated task:
- Compare the string in `s1` to the string in `s2` for equality of contents.
  - Append the string `s2` to the string `s1`, using `+=`.
  - Determine the length of the string in `s1`.

## Answers to Self-Review Exercises

- 14.1**
- False. `String` objects are compared using operator `==` to determine whether they're the same object in memory.
  - False. `String` objects are immutable and cannot be modified after they're created. `StringBuilder` objects can be modified after they're created.
- 14.2**
- `s1.equals(s2)`
  - `s1 += s2;`
  - `s1.length()`

## Exercises

- 14.3** (*Comparing Strings*) Write an application that uses `String` method `compareTo` to compare two strings input by the user. Output whether the first string is less than, equal to or greater than the second.

**14.4** (*Comparing Portions of Strings*) Write an application that uses `String` method `regionMatches` to compare two strings input by the user. The application should input the number of characters to be compared and the starting index of the comparison. The application should state whether the strings are equal. Ignore the case of the characters when performing the comparison.

**14.5** (*Random Sentences*) Write an application that uses random-number generation to create sentences. Use four arrays of strings called `article`, `noun`, `verb` and `preposition`. Create a sentence by selecting a word at random from each array in the following order: `article`, `noun`, `verb`, `preposition`, `article` and `noun`. As each word is picked, concatenate it to the previous words in the sentence. The words should be separated by spaces. When the final sentence is output, it should start with a capital letter and end with a period. The application should generate and display 20 sentences.

The `article` array should contain the articles "the", "a", "one", "some" and "any"; the `noun` array should contain the nouns "boy", "girl", "dog", "town" and "car"; the `verb` array should contain the verbs "drove", "jumped", "ran", "walked" and "skipped"; the `preposition` array should contain the prepositions "to", "from", "over", "under" and "on".

**14.6** (*Project: Limericks*) A limerick is a humorous five-line verse in which the first and second lines rhyme with the fifth, and the third line rhymes with the fourth. Using techniques similar to those developed in Exercise 14.5, write a Java application that produces random limericks. Polishing this application to produce good limericks is a challenging problem, but the result will be worth the effort!

**14.7** (*Pig Latin*) Write an application that encodes English-language phrases into pig Latin. Pig Latin is a form of coded language. There are many different ways to form pig Latin phrases. For simplicity, use the following algorithm:

To form a pig Latin phrase from an English-language phrase, tokenize the phrase into words with `String` method `split`. To translate each English word into a pig Latin word, place the first letter of the English word at the end of the word and add the letters "ay." Thus, the word "jump" becomes "umpjay," the word "the" becomes "hetay," and the word "computer" becomes "omputer-cay." Blanks between words remain as blanks. Assume the following: The English phrase consists of words separated by blanks, there are no punctuation marks and all words have two or more letters. Method `printLatinWord` should display each word. Each token is passed to method `printLatinWord` to print the pig Latin word. Enable the user to input the sentence. Keep a running display of all the converted sentences in a text area.

**14.8** (*Tokenizing Telephone Numbers*) Write an application that inputs a telephone number as a string in the form (555) 555-5555. The application should use `String` method `split` to extract the area code as a token, the first three digits of the phone number as a token and the last four digits of the phone number as a token. The seven digits of the phone number should be concatenated into one string. Both the area code and the phone number should be printed. Remember that you'll have to change delimiter characters during the tokenization process.

**14.9** (*Displaying a Sentence with Its Words Reversed*) Write an application that inputs a line of text, tokenizes the line with `String` method `split` and outputs the tokens in reverse order. Use space characters as delimiters.

**14.10** (*Displaying Strings in Uppercase and Lowercase*) Write an application that inputs a line of text and outputs the text twice—once in all uppercase letters and once in all lowercase letters.

**14.11** (*Searching Strings*) Write an application that inputs a line of text and a search character and uses `String` method `indexOf` to determine the number of occurrences of the character in the text.

**14.12** (*Searching Strings*) Write an application based on the application in Exercise 14.11 that inputs a line of text and uses `String` method `indexOf` to determine the total number of occurrences of each letter of the alphabet in the text. Uppercase and lowercase letters should be counted together. Store the totals for each letter in an array, and print the values in tabular format after the totals have been determined.

**14.13** (*Tokenizing and Comparing Strings*) Write an application that reads a line of text, tokenizes the line using space characters as delimiters and outputs only those words beginning with the letter "b".

**14.14** (*Tokenizing and Comparing Strings*) Write an application that reads a line of text, tokenizes it using space characters as delimiters and outputs only those words ending with the letters "Ed".

**14.15** (*Converting int Values to Characters*) Write an application that inputs an integer code for a character and displays the corresponding character. Modify this application so that it generates all possible three-digit codes in the range from 000 to 255 and attempts to print the corresponding characters.

**14.16** (*Defining Your Own String Methods*) Write your own versions of String search methods `indexOf` and `lastIndexOf`.

**14.17** (*Creating Three-Letter Strings from a Five-Letter Word*) Write an application that reads a five-letter word from the user and produces every possible three-letter string that can be derived from the letters of that word. For example, the three-letter words produced from the word "bathe" include "ate," "bat," "bet," "tab," "hat," "the" and "tea."

## Special Section: Advanced String-Manipulation Exercises

The preceding exercises are keyed to the text and designed to test your understanding of fundamental string-manipulation concepts. This section includes a collection of intermediate and advanced string-manipulation exercises. You should find these problems challenging, yet entertaining. The problems vary considerably in difficulty. Some require an hour or two of application writing and implementation. Others are useful for lab assignments that might require two or three weeks of study and implementation. Some are challenging term projects.

**14.18** (*Text Analysis*) The availability of computers with string-manipulation capabilities has resulted in some rather interesting approaches to analyzing the writings of great authors. Much attention has been focused on whether William Shakespeare ever lived. Some scholars believe there's substantial evidence indicating that Christopher Marlowe actually penned the masterpieces attributed to Shakespeare. Researchers have used computers to find similarities in the writings of these two authors. This exercise examines three methods for analyzing texts with a computer.

- a) Write an application that reads a line of text from the keyboard and prints a table indicating the number of occurrences of each letter of the alphabet in the text. For example, the phrase

To be, or not to be: that is the question:

contains one "a," two "b's," no "c's," and so on.

- b) Write an application that reads a line of text and prints a table indicating the number of one-letter words, two-letter words, three-letter words, and so on, appearing in the text. For example, Fig. 14.25 shows the counts for the phrase

Whether 'tis nobler in the mind to suffer

- c) Write an application that reads a line of text and prints a table indicating the number of occurrences of each different word in the text. The application should include the words in the table in the same order in which they appear in the text. For example, the lines

To be, or not to be: that is the question:

Whether 'tis nobler in the mind to suffer

contain the word "to" three times, the word "be" two times, the word "or" once, etc.

| Word length | Occurrences        |
|-------------|--------------------|
| 1           | 0                  |
| 2           | 2                  |
| 3           | 1                  |
| 4           | 2 (including 'tis) |
| 5           | 0                  |
| 6           | 2                  |
| 7           | 1                  |

**Fig. 14.25** | Word-length counts for the string  
"Whether 'tis nobler in the mind to suffer".

**14.19** (*Printing Dates in Various Formats*) Dates are printed in several common formats. Two of the more common formats are

04/25/1955 and April 25, 1955

Write an application that reads a date in the first format and prints it in the second format.

**14.20** (*Check Protection*) Computers are frequently employed in check-writing systems, such as payroll and accounts payable applications. There are many strange stories about weekly paychecks being printed (by mistake) for amounts in excess of \$1 million. Incorrect amounts are printed by computerized check-writing systems because of human error or machine failure. Systems designers build controls into their systems to prevent such erroneous checks from being issued.

Another serious problem is the intentional alteration of a check amount by someone who plans to cash a check fraudulently. To prevent a dollar amount from being altered, some computerized check-writing systems employ a technique called check protection. Checks designed for imprinting by computer contain a fixed number of spaces in which the computer may print an amount. Suppose a paycheck contains eight blank spaces in which the computer is supposed to print the amount of a weekly paycheck. If the amount is large, then all eight of the spaces will be filled. For example,

```
1,230.60 (check amount)

12345678 (position numbers)
```

On the other hand, if the amount is less than \$1000, then several of the spaces would ordinarily be left blank. For example,

```
99.87

12345678
```

contains three blank spaces. If a check is printed with blank spaces, it's easier for someone to alter the amount. To prevent alteration, many check-writing systems insert *leading asterisks* to protect the amount as follows:

```
***99.87

12345678
```

Write an application that inputs a dollar amount to be printed on a check, then prints the amount in check-protected format with leading asterisks if necessary. Assume that nine spaces are available for printing the amount.

**14.21** (*Writing the Word Equivalent of a Check Amount*) Continuing the discussion in Exercise 14.20, we reiterate the importance of designing check-writing systems to prevent alteration of check amounts. One common security method requires that the amount be written in numbers and spelled out in words as well. Even if someone is able to alter the numerical amount of the check, it's extremely difficult to change the amount in words. Write an application that inputs a numeric check amount that's less than \$1000 and writes the word equivalent of the amount. For example, the amount 112.43 should be written as

ONE hundred TWELVE and 43/100

**14.22** (*Morse Code*) Perhaps the most famous of all coding schemes is the Morse code, developed by Samuel Morse in 1832 for use with the telegraph system. The Morse code assigns a series of dots and dashes to each letter of the alphabet, each digit, and a few special characters (e.g., period, comma, colon, semicolon). In sound-oriented systems, the dot represents a short sound and the dash a long sound. Other representations of dots and dashes are used with light-oriented systems and signal-flag systems. Separation between words is indicated by a space or, simply, the absence of a dot or dash. In a sound-oriented system, a space is indicated by a short time during which no sound is transmitted. The international version of the Morse code appears in Fig. 14.26.

Write an application that reads an English-language phrase and encodes it into Morse code. Also write an application that reads a phrase in Morse code and converts it into the English-language equivalent. Use one blank between each Morse-coded letter and three blanks between each Morse-coded word.

| Character | Code    | Character | Code    | Character     | Code    |
|-----------|---------|-----------|---------|---------------|---------|
| A         | .-      | N         | -. .    | <i>Digits</i> |         |
| B         | -... .  | O         | ---     | 1             | ....-   |
| C         | -.-. .  | P         | .-.-. . | 2             | ..-.-   |
| D         | -.. .   | Q         | ---.-   | 3             | ...--   |
| E         | . .     | R         | .-. .   | 4             | ....-   |
| F         | ..-. .  | S         | ... .   | 5             | .....   |
| G         | --. .   | T         | - .     | 6             | -....   |
| H         | .... .  | U         | ..- .   | 7             | --... . |
| I         | .. .    | V         | ...- .  | 8             | ---.. . |
| J         | .-.-.-  | W         | .-.- .  | 9             | -----.  |
| K         | -. -    | X         | -..- .  | 0             | -----   |
| L         | .-... . | Y         | -. -.-  |               |         |
| M         | -- .    | Z         | ---.. . |               |         |

**Fig. 14.26** | Letters and digits as expressed in international Morse code.

**14.23** (*Metric Conversions*) Write an application that will assist the user with metric conversions. Your application should allow the user to specify the names of the units as strings (i.e., centimeters, liters, grams, and so on, for the metric system and inches, quarts, pounds, and so on, for the English system) and should respond to simple questions, such as

"How many inches are in 2 meters?"  
 "How many liters are in 10 quarts?"



Your application should recognize invalid conversions. For example, the question

"How many feet are in 5 kilograms?"

is not meaningful because "feet" is a unit of length, whereas "kilograms" is a unit of mass.

## Special Section: Challenging String-Manipulation Projects

**14.24 (Project: A Spelling Checker)** Many popular word-processing software packages have built-in spell checkers. In this project, you're asked to develop your own spell-checker utility. We make suggestions to help get you started. You should then consider adding more capabilities. Use a computerized dictionary (if you have access to one) as a source of words.

Why do we type so many words with incorrect spellings? In some cases, it's because we simply do not know the correct spelling, so we make a best guess. In some cases, it's because we transpose two letters (e.g., "default" instead of "default"). Sometimes we double-type a letter accidentally (e.g., "hannyd" instead of "handy"). Sometimes we type a nearby key instead of the one we intended (e.g., "biryhday" instead of "birthday"), and so on.

Design and implement a spell-checker application in Java. Your application should maintain an array `wordList` of strings. Enable the user to enter these strings. [Note: In Chapter 15, we introduce file processing. With this capability, you can obtain the words for the spell checker from a computerized dictionary stored in a file.]

Your application should ask a user to enter a word. The application should then look up that word in the `wordList` array. If the word is in the array, your application should print "Word is spelled correctly." If the word is not in the array, your application should print "Word is not spelled correctly." Then your application should try to locate other words in `wordList` that might be the word the user intended to type. For example, you can try all possible single transpositions of adjacent letters to discover that the word "default" is a direct match to a word in `wordList`. Of course, this implies that your application will check all other single transpositions, such as "edfault," "dfeault," "deafult," "defalut" and "defautl." When you find a new word that matches one in `wordList`, print it in a message, such as

Did you mean "default"?

Implement other tests, such as replacing each double letter with a single letter, and any other tests you can develop to improve the value of your spell checker.

**14.25 (Project: A Crossword Puzzle Generator)** Most people have worked a crossword puzzle, but few have ever attempted to generate one. Generating a crossword puzzle is suggested here as a string-manipulation project requiring substantial sophistication and effort.

There are many issues the programmer must resolve to get even the simplest crossword-puzzle-generator application working. For example, how do you represent the grid of a crossword puzzle inside the computer? Should you use a series of strings or two-dimensional arrays?

The programmer needs a source of words (i.e., a computerized dictionary) that can be directly referenced by the application. In what form should these words be stored to facilitate the complex manipulations required by the application?

If you're really ambitious, you'll want to generate the clues portion of the puzzle, in which the brief hints for each across word and each down word are printed. Merely printing a version of the blank puzzle itself is not a simple problem.

## Making a Difference

**14.26 (Cooking with Healthier Ingredients)** Obesity in America is increasing at an alarming rate. Check the map from the Centers for Disease Control and Prevention (CDC) at [www.cdc.gov/nccdphp/dnpa/Obesity/trend/maps/index.htm](http://www.cdc.gov/nccdphp/dnpa/Obesity/trend/maps/index.htm), which shows obesity trends in the United States

over the last 20 years. As obesity increases, so do occurrences of related problems (e.g., heart disease, high blood pressure, high cholesterol, type 2 diabetes). Write a program that helps users choose healthier ingredients when cooking, and helps those allergic to certain foods (e.g., nuts, gluten) find substitutes. The program should read a recipe from a `TextArea` and suggest healthier replacements for some of the ingredients. For simplicity, your program should assume the recipe has no abbreviations for measures such as teaspoons, cups, and tablespoons, and uses numerical digits for quantities (e.g., 1 egg, 2 cups) rather than spelling them out (one egg, two cups). Some common substitutions are shown in Fig. 14.27. Your program should display a warning such as, “Always consult your physician before making significant changes to your diet.”

Your program should take into consideration that replacements are not always one-for-one. For example, if a cake recipe calls for three eggs, it might reasonably use six egg whites instead. Conversion data for measurements and substitutes can be obtained at websites such as:

[chinesefood.about.com/od/recipeconversionfaqs/f/usmetricrecipes.htm](http://chinesefood.about.com/od/recipeconversionfaqs/f/usmetricrecipes.htm)  
[www.pioneerthinking.com/eggsub.html](http://www.pioneerthinking.com/eggsub.html)  
[www.gourmetsleuth.com/conversions.htm](http://www.gourmetsleuth.com/conversions.htm)

Your program should consider the user’s health concerns, such as high cholesterol, high blood pressure, weight loss, gluten allergy, and so on. For high cholesterol, the program should suggest substitutes for eggs and dairy products; if the user wishes to lose weight, low-calorie substitutes for ingredients such as sugar should be suggested.

| Ingredient             | Substitution                                                                                                       |
|------------------------|--------------------------------------------------------------------------------------------------------------------|
| 1 cup sour cream       | 1 cup yogurt                                                                                                       |
| 1 cup milk             | 1/2 cup evaporated milk and 1/2 cup water                                                                          |
| 1 teaspoon lemon juice | 1/2 teaspoon vinegar                                                                                               |
| 1 cup sugar            | 1/2 cup honey, 1 cup molasses<br>or 1/4 cup agave nectar                                                           |
| 1 cup butter           | 1 cup margarine or yogurt                                                                                          |
| 1 cup flour            | 1 cup rye or rice flour                                                                                            |
| 1 cup mayonnaise       | 1 cup cottage cheese<br>or 1/8 cup mayonnaise and 7/8 cup yogurt                                                   |
| 1 egg                  | 2 tablespoons cornstarch, arrowroot flour<br>or potato starch or 2 egg whites<br>or 1/2 of a large banana (mashed) |
| 1 cup milk             | 1 cup soy milk                                                                                                     |
| 1/4 cup oil            | 1/4 cup applesauce                                                                                                 |
| white bread            | whole-grain bread                                                                                                  |

**Fig. 14.27** | Common food substitutions.

**14.27 (Spam Scanner)** Spam (or junk e-mail) costs U.S. organizations billions of dollars a year in spam-prevention software, equipment, network resources, bandwidth, and lost productivity. Research online some of the most common spam e-mail messages and words, and check your own junk e-mail folder. Create a list of 30 words and phrases commonly found in spam messages. Write an application in which the user enters an e-mail message in a `TextArea`. Then, scan the message for each of the 30 keywords or phrases. For each occurrence of one of these within the message, add

a point to the message's "spam score." Next, rate the likelihood that the message is spam, based on the number of points it received.

**14.28 (SMS Language)** Short Message Service (SMS) is a communications service that allows sending text messages of 160 or fewer characters between mobile phones. With the proliferation of mobile phone use worldwide, SMS is being used in many developing nations for political purposes (e.g., voicing opinions and opposition), reporting news about natural disasters, and so on. For example, check out [comunica.org/radio2.0/archives/87](http://comunica.org/radio2.0/archives/87). Since the length of SMS messages is limited, SMS Language—abbreviations of common words and phrases in mobile text messages, e-mails, instant messages, etc.—is often used. For example, "in my opinion" is "imo" in SMS Language. Research SMS Language online. Write a GUI application in which the user can enter a message using SMS Language, then click a button to translate it into English (or your own language). Also provide a mechanism to translate text written in English (or your own language) into SMS Language. One potential problem is that one SMS abbreviation could expand into a variety of phrases. For example, IMO (as used above) could also stand for "International Maritime Organization," "in memory of," etc.

# 15

## Files, Streams and Object Serialization

*Consciousness ... does not appear to itself chopped up in bits. ... A “river” or a “stream” are the metaphors by which it is most naturally described.*

—William James

### Objectives

In this chapter you'll:

- Create, read, write and update files.
- Retrieve information about files and directories using features of the NIO.2 APIs.
- Learn the differences between text files and binary files.
- Use class `Formatter` to output text to a file.
- Use class `Scanner` to input text from a file.
- Write objects to and read objects from a file using object serialization, interface `Serializable` and classes `ObjectOutputStream` and `ObjectInputStream`.
- Use a `JFileChooser` dialog to allow users to select files or directories on disk.



- |                                                                             |                                                                     |
|-----------------------------------------------------------------------------|---------------------------------------------------------------------|
| 15.1 Introduction                                                           | 15.5.1 Creating a Sequential-Access File Using Object Serialization |
| 15.2 Files and Streams                                                      | 15.5.2 Reading and Deserializing Data from a Sequential-Access File |
| 15.3 Using NIO Classes and Interfaces to Get File and Directory Information | 15.6 Opening Files with <code>JFileChooser</code>                   |
| 15.4 Sequential-Access Text Files                                           | 15.7 (Optional) Additional <code>java.io</code> Classes             |
| 15.4.1 Creating a Sequential-Access Text File                               | 15.7.1 Interfaces and Classes for Byte-Based Input and Output       |
| 15.4.2 Reading Data from a Sequential-Access Text File                      | 15.7.2 Interfaces and Classes for Character-Based Input and Output  |
| 15.4.3 Case Study: A Credit-Inquiry Program                                 |                                                                     |
| 15.4.4 Updating Sequential-Access Files                                     |                                                                     |
| 15.5 Object Serialization                                                   | 15.8 Wrap-Up                                                        |

Summary | Self-Review Exercises | Answers to Self-Review Exercises | Exercises | Making a Difference

## 15.1 Introduction

Data stored in variables and arrays is *temporary*—it’s lost when a local variable goes out of scope or when the program terminates. For long-term retention of data, even after the programs that create the data terminate, computers use **files**. You use files every day for tasks such as writing a document or creating a spreadsheet. Computers store files on **secondary storage devices**, including hard disks, flash drives, DVDs and more. Data maintained in files is **persistent data**—it exists beyond the duration of program execution. In this chapter, we explain how Java programs create, update and process files.

We begin with a discussion of Java’s architecture for handling files programmatically. Next we explain that data can be stored in *text files* and *binary files*—and we cover the differences between them. We demonstrate retrieving information about files and directories using classes `Paths` and `Files` and interfaces `Path` and `DirectoryStream` (all from package `java.nio.file`), then consider the mechanisms for writing data to and reading data from files. We show how to create and manipulate sequential-access text files. Working with text files allows you to quickly and easily start manipulating files. As you’ll learn, however, it’s difficult to read data from text files back into object form. Fortunately, many object-oriented languages (including Java) provide ways to write objects to and read objects from files (known as *object serialization* and *deserialization*). To demonstrate this, we recreate some of our sequential-access programs that used text files, this time by storing objects in and retrieving objects from binary files.

## 15.2 Files and Streams

Java views each file as a sequential **stream of bytes** (Fig. 15.1).<sup>1</sup> Every operating system provides a mechanism to determine the end of a file, such as an **end-of-file marker** or a count of the total bytes in the file that’s recorded in a system-maintained administrative data structure. A Java program processing a stream of bytes simply receives an indication from the operating system when it reaches the end of the stream—the program does *not* need to know how the underlying platform represents files or streams. In some cases, the

1. Java’s NIO APIs also include classes and interfaces that implement so-called channel-based architecture for high-performance I/O. These topics are beyond the scope of this book.

end-of-file indication occurs as an exception. In others, the indication is a return value from a method invoked on a stream-processing object.



**Fig. 15.1** | Java's view of a file of  $n$  bytes.

### *Byte-Based and Character-Based Streams*

File streams can be used to input and output data as bytes or characters.

- **Byte-based streams** output and input data in its *binary* format—a `char` is two bytes, an `int` is four bytes, a `double` is eight bytes, etc.
- **Character-based streams** output and input data as a *sequence of characters* in which every character is two bytes—the number of bytes for a given value depends on the number of characters in that value. For example, the value 2000000000 requires 20 bytes (10 characters at two bytes per character) but the value 7 requires only two bytes (1 character at two bytes per character).

Files created using byte-based streams are referred to as **binary files**, while files created using character-based streams are referred to as **text files**. Text files can be read by text editors, while binary files are read by programs that understand the file's specific content and its ordering. A numeric value in a binary file can be used in calculations, whereas the character 5 is simply a character that can be used in a string of text, as in "Sarah Miller is 15 years old".

### *Standard Input, Standard Output and Standard Error Streams*

A Java program **opens** a file by creating an object and associating a stream of bytes or characters with it. The object's constructor interacts with the operating system to *open* the file. Java can also associate streams with different devices. When a Java program begins executing, it creates three stream objects that are associated with devices—`System.in`, `System.out` and `System.err`. The `System.in` (standard input stream) object normally enables a program to input bytes from the keyboard. Object `System.out` (the standard output stream object) normally enables a program to output character data to the screen. Object `System.err` (the standard error stream object) normally enables a program to output character-based error messages to the screen. Each stream can be **redirected**. For `System.in`, this capability enables the program to read bytes from a different source. For `System.out` and `System.err`, it enables the output to be sent to a different location, such as a file on disk. Class `System` provides methods `setIn`, `setOut` and `setErr` to redirected the standard input, output and error streams, respectively.

### *The java.io and java.nio Packages*

Java programs perform stream-based processing with classes and interfaces from package `java.io` and the subpackages of `java.nio`—Java's New I/O APIs that were first introduced in Java SE 6 and that have been enhanced since. There are also other packages throughout the Java APIs containing classes and interfaces based on those in the `java.io` and `java.nio` packages.

Character-based input and output can be performed with classes `Scanner` and **Formatter**, as you'll see in Section 15.4. You've used class `Scanner` extensively to input data from the keyboard. `Scanner` also can read data from a file. Class `Formatter` enables formatted data to be output to any text-based stream in a manner similar to method `System.out.printf`. Appendix I presents the details of formatted output with `printf`. All these features can be used to format text files as well. In Chapter 28, we use stream classes to implement networking applications.

### *Java SE 8 Adds Another Type of Stream*

Chapter 17, Java SE 8 Lambdas and Streams, introduces a new type of stream that's used to process collections of elements (like arrays and `ArrayLists`), rather than the streams of bytes we discuss in this chapter's file-processing examples.

## 15.3 Using NIO Classes and Interfaces to Get File and Directory Information

Interfaces `Path` and `DirectoryStream` and classes `Paths` and `Files` (all from package `java.nio.file`) are useful for retrieving information about files and directories on disk:

- **Path** interface—Objects of classes that implement this interface represent the location of a file or directory. `Path` objects do not open files or provide any file-processing capabilities.
- **Paths** class—Provides static methods used to get a `Path` object representing a file or directory location.
- **Files** class—Provides static methods for common file and directory manipulations, such as copying files; creating and deleting files and directories; getting information about files and directories; reading the contents of files; getting objects that allow you to manipulate the contents of files and directories; and more
- **DirectoryStream** interface—Objects of classes that implement this interface enable a program to iterate through the contents of a directory.

### *Creating Path Objects*

You'll use class static method **get** of class `Paths` to convert a `String` representing a file's or directory's location into a `Path` object. You can then use the methods of interface `Path` and class `Files` to determine information about the specified file or directory. We discuss several such methods momentarily. For complete lists of their methods, visit:

```
http://docs.oracle.com/javase/7/docs/api/java/nio/file/Path.html
http://docs.oracle.com/javase/7/docs/api/java/nio/file/Files.html
```

### *Absolute vs. Relative Paths*

A file or directory's path specifies its location on disk. The path includes some or all of the directories leading to the file or directory. An **absolute path** contains *all* directories, starting with the **root directory**, that lead to a specific file or directory. Every file or directory on a particular disk drive has the *same* root directory in its path. A **relative path** is "relative" to another directory—for example, a path relative to the directory in which the application began executing.

*Getting Path Objects from URIs*

An overloaded version of `Files` static method `get` uses a `URI` object to locate the file or directory. A **Uniform Resource Identifier (URI)** is a more general form of the **Uniform Resource Locators (URLs)** that are used to locate websites. For example, the URL `http://www.deitel.com/` is the URL for the Deitel & Associates website. URIs for locating files vary across operating systems. On Windows platforms, the URI

```
file://C:/data.txt
```

identifies the file `data.txt` stored in the root directory of the C: drive. On UNIX/Linux platforms, the URI

```
file:/home/student/data.txt
```

identifies the file `data.txt` stored in the home directory of the user `student`.

*Example: Getting File and Directory Information*

Figure 15.2 prompts the user to enter a file or directory name, then uses classes `Paths`, `Path`, `Files` and `DirectoryStream` to output information about that file or directory. The program begins by prompting the user for a file or directory (line 16). Line 19 inputs the filename or directory name and passes it to `Paths` static method `get`, which converts the `String` to a `Path`. Line 21 invokes `Files` static method `exists`, which receives a `Path` and determines whether it exists (either as a file or as a directory) on disk. If the name does not exist, control proceeds to line 49, which displays a message containing the `Path`'s `String` representation followed by “does not exist.” Otherwise, lines 24–45 execute:

- `Path` method `getFileName` (line 24) gets the `String` name of the file or directory without any location information.
- `Files` static method `isDirectory` (line 26) receives a `Path` and returns a `boolean` indicating whether that `Path` represents a directory on disk.
- `Path` method `isAbsolute` (line 28) returns a `boolean` indicating whether that `Path` represents an absolute path to a file or directory.
- `Files` static method `getLastModifiedTime` (line 30) receives a `Path` and returns a `FileTime` (package `java.nio.file.attribute`) indicating when the file was last modified. The program outputs the `FileTime`'s default `String` representation.
- `Files` static method `size` (line 31) receives a `Path` and returns a `long` representing the number of bytes in the file or directory. For directories, the value returned is platform specific.
- `Path` method `toString` (called implicitly at line 32) returns a `String` representing the `Path`.
- `Path` method `toAbsolutePath` (line 33) converts the `Path` on which it's called to an absolute path.

If the `Path` represents a directory (line 35), lines 40–41 use `Files` static method `newDirectoryStream` (lines 40–41) to get a `DirectoryStream<Path>` containing `Path` objects for the directory's contents. Lines 43–44 display the `String` representation of each `Path` in the `DirectoryStream<Path>`. Note that `DirectoryStream` is a generic type like `ArrayList` (Section 6.13).



The first output of this program demonstrates a Path for the folder containing this chapter's examples. The second output demonstrates a Path for this example's source code file. In both cases, we specified an absolute path.

---

```

1 // Fig. 15.2: FileAndDirectoryInfo.java
2 // File class used to obtain file and directory information.
3 import java.io.IOException;
4 import java.nio.file.DirectoryStream;
5 import java.nio.file.Files;
6 import java.nio.file.Path;
7 import java.nio.file.Paths;
8 import java.util.Scanner;
9
10 public class FileAndDirectoryInfo
11 {
12 public static void main(String[] args) throws IOException
13 {
14 Scanner input = new Scanner(System.in);
15
16 System.out.println("Enter file or directory name:");
17
18 // create Path object based on user input
19 Path path = Paths.get(input.nextLine());
20
21 if (Files.exists(path)) // if path exists, output info about it
22 {
23 // display file (or directory) information
24 System.out.printf("%n%s exists%n", path.getFileName());
25 System.out.printf("%s a directory%n",
26 Files.isDirectory(path) ? "Is" : "Is not");
27 System.out.printf("%s an absolute path%n",
28 path.isAbsolute() ? "Is" : "Is not");
29 System.out.printf("Last modified: %s%n",
30 Files.getLastModifiedTime(path));
31 System.out.printf("Size: %s%n", Files.size(path));
32 System.out.printf("Path: %s%n", path);
33 System.out.printf("Absolute path: %s%n", path.toAbsolutePath());
34
35 if (Files.isDirectory(path)) // output directory listing
36 {
37 System.out.printf("%nDirectory contents:%n");
38
39 // object for iterating through a directory's contents
40 DirectoryStream<Path> directoryStream =
41 Files.newDirectoryStream(path);
42
43 for (Path p : directoryStream)
44 System.out.println(p);
45 }
46 }
47 else // not file or directory, output error message
48 {

```

---

**Fig. 15.2** | File class used to obtain file and directory information. (Part 1 of 2.)

```

49 System.out.printf("%s does not exist%n", path);
50 }
51 } // end main
52 } // end class FileAndDirectoryInfo

```

Enter file or directory name:

**c:\examples\ch15**

ch15 exists  
 Is a directory  
 Is an absolute path  
 Last modified: 2013-11-08T19:50:00.838256Z  
 Size: 4096  
 Path: c:\examples\ch15  
 Absolute path: c:\examples\ch15

Directory contents:

C:\examples\ch15\fig15\_02  
 C:\examples\ch15\fig15\_12\_13  
 C:\examples\ch15\SerializationApps  
 C:\examples\ch15\TextFileApps

Enter file or directory name:

**C:\examples\ch15\fig15\_02\FileAndDirectoryInfo.java**

FileAndDirectoryInfo.java exists  
 Is not a directory  
 Is an absolute path  
 Last modified: 2013-11-08T19:59:01.848255Z  
 Size: 2952  
 Path: C:\examples\ch15\fig15\_02\FileAndDirectoryInfo.java  
 Absolute path: C:\examples\ch15\fig15\_02\FileAndDirectoryInfo.java

**Fig. 15.2** | File class used to obtain file and directory information. (Part 2 of 2.)



### Error-Prevention Tip 15.1

*Once you've confirmed that a Path exists, it's still possible that the methods demonstrated in Fig. 15.2 will throw IOExceptions. For example, the file or directory represented by the Path could be deleted from the system after the call to Files method exists and before the other statements in lines 24–45 execute. Industrial strength file- and directory-processing programs require extensive exception handling to recover from such possibilities.*

### Separator Characters

A **separator character** is used to separate directories and files in a path. On a Windows computer, the *separator character* is a backslash (\). On a Linux or Mac OS X system, it's a forward slash (/). Java processes both characters identically in a path name. For example, if we were to use the path

```
c:\Program Files\Java\jdk1.6.0_11\demo\jfc
```

which employs each separator character, Java would still process the path properly.



### Good Programming Practice 15.1

When building *Strings* that represent path information, use `File.separator` to obtain the local computer's proper separator character rather than explicitly using `/` or `\`. This constant is a *String* consisting of one character—the proper separator for the system.



### Common Programming Error 15.1

Using `\` as a directory separator rather than `\\` in a string literal is a logic error. A single `\` indicates that the `\` followed by the next character represents an escape sequence. Use `\\` to insert a `\` in a string literal.

## 15.4 Sequential-Access Text Files

Next, we create and manipulate *sequential-access files* in which records are stored in order by the record-key field. We begin with *text files*, enabling the reader to quickly create and edit human-readable files. We discuss creating, writing data to, reading data from and updating sequential-access text files. We also include a credit-inquiry program that retrieves data from a file. The programs in Sections 15.4.1—15.4.3 are all in the chapter's `TextFileApps` directory so that they can manipulate the same text file, which is also stored in that directory.

### 15.4.1 Creating a Sequential-Access Text File

*Java imposes no structure on a file—notions such as records do not exist as part of the Java language.* Therefore, you must structure files to meet the requirements of your applications. In the following example, we see how to impose a *keyed* record structure on a file.

The program in this section creates a simple sequential-access file that might be used in an accounts receivable system to keep track of the amounts owed to a company by its credit clients. For each client, the program obtains from the user an account number and the client's name and balance (i.e., the amount the client owes the company for goods and services received). Each client's data constitutes a "record" for that client. This application uses the account number as the *record key*—the file's records will be created and maintained in account-number order. The program assumes that the user enters the records in account-number order. In a comprehensive accounts receivable system (based on sequential-access files), a *sorting* capability would be provided so that the user could enter the records in *any* order. The records would then be sorted and written to the file.

#### *Class CreateTextFile*

Class `CreateTextFile` (Fig. 15.3) uses a `Formatter` to output formatted *Strings*, using the same formatting capabilities as method `System.out.printf`. A `Formatter` object can output to various locations, such as to a command window or to a file, as we do in this example. The `Formatter` object is instantiated in line 26 in method `openFile` (lines 22–38). The constructor used in line 26 takes one argument—a *String* containing the name of the file, including its path. If a path is not specified, as is the case here, the JVM assumes that the file is in the directory from which the program was executed. For text files, we use the `.txt` file extension. If the file does *not* exist, it will be *created*. If an *existing* file is opened, its contents are **truncated**—all the data in the file is *discarded*. If no exception occurs, the file is open for writing and the resulting `Formatter` object can be used to write data to the file.

---

```

1 // Fig. 15.3: CreateTextFile.java
2 // Writing data to a sequential text file with class Formatter.
3 import java.io.FileNotFoundException;
4 import java.lang.SecurityException;
5 import java.util.Formatter;
6 import java.util.FormatterClosedException;
7 import java.util.NoSuchElementException;
8 import java.util.Scanner;
9
10 public class CreateTextFile
11 {
12 private static Formatter output; // outputs text to a file
13
14 public static void main(String[] args)
15 {
16 openFile();
17 addRecords();
18 closeFile();
19 }
20
21 // open file clients.txt
22 public static void openFile()
23 {
24 try
25 {
26 output = new Formatter("clients.txt"); // open the file
27 }
28 catch (SecurityException securityException)
29 {
30 System.err.println("Write permission denied. Terminating.");
31 System.exit(1); // terminate the program
32 }
33 catch (FileNotFoundException fileNotFoundException)
34 {
35 System.err.println("Error opening file. Terminating.");
36 System.exit(1); // terminate the program
37 }
38 }
39
40 // add records to file
41 public static void addRecords()
42 {
43 Scanner input = new Scanner(System.in);
44 System.out.printf("%s\n%s\n? ",
45 "Enter account number, first name, last name and balance.",
46 "Enter end-of-file indicator to end input.");
47
48 while (input.hasNext()) // loop until end-of-file indicator
49 {
50 try
51 {

```

---

**Fig. 15.3** | Writing data to a sequential text file with class Formatter. (Part I of 2.)

```

52 // output new record to file; assumes valid input
53 output.format("%d %s %s %.2f%n", input.nextInt(),
54 input.next(), input.next(), input.nextDouble());
55 }
56 catch (FormatterClosedException formatterClosedException)
57 {
58 System.err.println("Error writing to file. Terminating.");
59 break;
60 }
61 catch (NoSuchElementException elementException)
62 {
63 System.err.println("Invalid input. Please try again.");
64 input.nextLine(); // discard input so user can try again
65 }
66
67 System.out.print("? ");
68 } // end while
69 } // end method addRecords
70
71 // close file
72 public static void closeFile()
73 {
74 if (output != null)
75 output.close();
76 }
77 } // end class CreateTextFile

```

```

Enter account number, first name, last name and balance.
Enter end-of-file indicator to end input.
? 100 Bob Blue 24.98
? 200 Steve Green -345.67
? 300 Pam White 0.00
? 400 Sam Red -42.16
? 500 Sue Yellow 224.62
? ^Z

```

**Fig. 15.3** | Writing data to a sequential text file with class `Formatter`. (Part 2 of 2.)

Lines 28–32 handle the **SecurityException**, which occurs if the user does not have permission to write data to the file. Lines 33–37 handle the **FileNotFoundException**, which occurs if the file does not exist and a new file cannot be created. This exception may also occur if there's an error *opening* the file. In both exception handlers we call static method **System.exit** and pass the value 1. This method terminates the application. An argument of 0 to method **exit** indicates *successful* program termination. A nonzero value, such as 1 in this example, normally indicates that an error has occurred. This value is passed to the command window that executed the program. The argument is useful if the program is executed from a **batch file** on Windows systems or a **shell script** on UNIX/Linux/Mac OS X systems. Batch files and shell scripts offer a convenient way of executing several programs in sequence. When the first program ends, the next program begins execution. It's possible to use the argument to method **exit** in a batch file or shell script to determine whether other programs should execute. For more information on batch files or shell scripts, see your operating system's documentation.

Method `addRecords` (lines 41–69) prompts the user to enter the various fields for each record or the end-of-file key sequence when data entry is complete. Figure 15.4 lists the key combinations for entering end-of-file for various computer systems.

| Operating system    | Key combination                                        |
|---------------------|--------------------------------------------------------|
| UNIX/Linux/Mac OS X | <code>&lt;Enter&gt;</code> <code>&lt;Ctrl&gt; d</code> |
| Windows             | <code>&lt;Ctrl&gt; z</code>                            |

**Fig. 15.4** | End-of-file key combinations.

Lines 44–46 prompt the user for input. Line 48 uses `Scanner` method `hasNext` to determine whether the end-of-file key combination has been entered. The loop executes until `hasNext` encounters end-of-file.

Lines 53–54 use a `Scanner` to read data from the user, then output the data as a record using the `Formatter`. Each `Scanner` input method throws a **NoSuchElementException** (handled in lines 61–65) if the data is in the wrong format (e.g., a `String` when an `int` is expected) or if there’s no more data to input. The record’s information is output using method `format`, which can perform identical formatting to the `System.out.printf` method used extensively in earlier chapters. Method `format` outputs a formatted `String` to the output destination of the `Formatter` object—the file `clients.txt`. The format string `"%d %s %s %.2f%n"` indicates that the current record will be stored as an integer (the account number) followed by a `String` (the first name), another `String` (the last name) and a floating-point value (the balance). Each piece of information is separated from the next by a space, and the double value (the balance) is output with two digits to the right of the decimal point (as indicated by the `.2` in `%.2f`). The data in the text file can be viewed with a text editor or retrieved later by a program designed to read the file (Section 15.4.2).

When lines 66–68 execute, if the `Formatter` object is closed, a **FormatterClosedException** will be thrown. This exception is handled in lines 76–80. [Note: You can also output data to a text file using class `java.io.PrintWriter`, which provides `format` and `printf` methods for outputting formatted data.]

Lines 93–97 declare method `closeFile`, which closes the `Formatter` and the underlying output file. Line 96 closes the object by simply calling method `close`. If method `close` is not called explicitly, the operating system normally will close the file when program execution terminates—this is an example of operating-system “housekeeping.” However, you should always explicitly close a file when it’s no longer needed.

### Sample Output

The sample data for this application is shown in Fig. 15.5. In the sample output, the user enters information for five accounts, then enters end-of-file to signal that data entry is complete. The sample output does not show how the data records actually appear in the file. In the next section, to verify that the file was created successfully, we present a program that reads the file and prints its contents. Because this is a text file, you can also verify the information simply by opening the file in a text editor.

| Sample data |       |        |         |
|-------------|-------|--------|---------|
| 100         | Bob   | Blue   | 24.98   |
| 200         | Steve | Green  | -345.67 |
| 300         | Pam   | White  | 0.00    |
| 400         | Sam   | Red    | -42.16  |
| 500         | Sue   | Yellow | 224.62  |

**Fig. 15.5** | Sample data for the program in Fig. 15.3.

### 15.4.2 Reading Data from a Sequential-Access Text File

Data is stored in files so that it may be retrieved for processing when needed. Section 15.4.1 demonstrated how to create a file for sequential access. This section shows how to read data sequentially from a text file. We demonstrate how class `Scanner` can be used to input data from a file rather than the keyboard. The application (Fig. 15.6) reads records from the file `"clients.txt"` created by the application of Section 15.4.1 and displays the record contents. Line 13 declares a `Scanner` that will be used to retrieve input from the file.

---

```

1 // Fig. 15.6: ReadTextFile.java
2 // This program reads a text file and displays each record.
3 import java.io.IOException;
4 import java.lang.IllegalStateException;
5 import java.nio.file.Files;
6 import java.nio.file.Path;
7 import java.nio.file.Paths;
8 import java.util.NoSuchElementException;
9 import java.util.Scanner;
10
11 public class ReadTextFile
12 {
13 private static Scanner input;
14
15 public static void main(String[] args)
16 {
17 openFile();
18 readRecords();
19 closeFile();
20 }
21
22 // open file clients.txt
23 public static void openFile()
24 {
25 try
26 {
27 input = new Scanner(Paths.get("clients.txt"));
28 }

```

---

**Fig. 15.6** | Sequential file reading using a `Scanner`. (Part 1 of 2.)

```

29 catch (IOException ioException)
30 {
31 System.err.println("Error opening file. Terminating.");
32 System.exit(1);
33 }
34 }
35
36 // read record from file
37 public static void readRecords()
38 {
39 System.out.printf("%-10s%-12s%-12s%10s\n", "Account",
40 "First Name", "Last Name", "Balance");
41
42 try
43 {
44 while (input.hasNext()) // while there is more to read
45 {
46 // display record contents
47 System.out.printf("%-10d%-12s%-12s%10.2f\n", input.nextInt(),
48 input.next(), input.next(), input.nextDouble());
49 }
50 }
51 catch (NoSuchElementException elementException)
52 {
53 System.err.println("File improperly formed. Terminating.");
54 }
55 catch (IllegalStateException stateException)
56 {
57 System.err.println("Error reading from file. Terminating.");
58 }
59 } // end method readRecords
60
61 // close file and terminate application
62 public static void closeFile()
63 {
64 if (input != null)
65 input.close();
66 }
67 } // end class ReadTextFile

```

| Account | First Name | Last Name | Balance |
|---------|------------|-----------|---------|
| 100     | Bob        | Blue      | 24.98   |
| 200     | Steve      | Green     | -345.67 |
| 300     | Pam        | White     | 0.00    |
| 400     | Sam        | Red       | -42.16  |
| 500     | Sue        | Yellow    | 224.62  |

**Fig. 15.6** | Sequential file reading using a Scanner. (Part 2 of 2.)

Method `openFile` (lines 23–34) opens the file for reading by instantiating a `Scanner` object in line 27. We pass a `Path` object to the constructor, which specifies that the `Scanner` object will read from the file `"clients.txt"` located in the directory from which the application executes. If the file cannot be found, an `IOException` occurs. The exception is handled in lines 29–33.



Method `readRecords` (lines 37–59) reads and displays records from the file. Lines 39–40 display headers for the columns in the application’s output. Lines 44–49 read and display data from the file until the *end-of-file marker* is reached (in which case, method `hasNext` will return `false` at line 44). Lines 47–48 use Scanner methods `nextInt`, `next` and `nextDouble` to input an `int` (the account number), two `Strings` (the first and last names) and a `double` value (the balance). Each record is one line of data in the file. If the information in the file is not properly formed (e.g., there’s a last name where there should be a balance), a `NoSuchElementException` occurs when the record is input. This exception is handled in lines 51–54. If the Scanner was closed before the data was input, an `IllegalStateException` occurs (handled in lines 55–58). Note in the format string in line 47 that the account number, first name and last name are left justified, while the balance is right justified and output with two digits of precision. Each iteration of the loop inputs one line of text from the text file, which represents one record. Lines 62–66 define method `closeFile`, which closes the Scanner.

### 15.4.3 Case Study: A Credit-Inquiry Program

To retrieve data sequentially from a file, programs start from the beginning of the file and read *all* the data consecutively until the desired information is found. It might be necessary to process the file sequentially several times (from the beginning of the file) during the execution of a program. Class Scanner does *not* allow repositioning to the beginning of the file. If it’s necessary to read the file again, the program must *close* the file and *reopen* it.

The program in Figs. 15.7–15.8 allows a credit manager to obtain lists of customers with *zero balances* (i.e., customers who do not owe any money), customers with *credit balances* (i.e., customers to whom the company owes money) and customers with *debit balances* (i.e., customers who owe the company money for goods and services received). A credit balance is a *negative* amount, a debit balance a *positive* amount.

#### *MenuOption* enum

We begin by creating an enum type (Fig. 15.7) to define the different menu options the credit manager will have—this is required if you need to provide specific values for the enum constants. The options and their values are listed in lines 7–10.

---

```

1 // Fig. 15.7: MenuOption.java
2 // enum type for the credit-inquiry program's options.
3
4 public enum MenuOption
5 {
6 // declare contents of enum type
7 ZERO_BALANCE(1),
8 CREDIT_BALANCE(2),
9 DEBIT_BALANCE(3),
10 END(4);
11
12 private final int value; // current menu option
13

```

---

**Fig. 15.7** | enum type for the credit-inquiry program’s menu options. (Part 1 of 2.)

---

```

14 // constructor
15 private MenuOption(int value)
16 {
17 this.value = value;
18 }
19 } // end enum MenuOption

```

---

**Fig. 15.7** | enum type for the credit-inquiry program's menu options. (Part 2 of 2.)

### *CreditInquiry Class*

Figure 15.8 contains the functionality for the credit-inquiry program. The program displays a text menu and allows the credit manager to enter one of three options to obtain credit information:

- Option 1 (ZERO\_BALANCE) displays accounts with zero balances.
- Option 2 (CREDIT\_BALANCE) displays accounts with credit balances.
- Option 3 (DEBIT\_BALANCE) displays accounts with debit balances.
- Option 4 (END) terminates program execution.

---

```

1 // Fig. 15.8: CreditInquiry.java
2 // This program reads a file sequentially and displays the
3 // contents based on the type of account the user requests
4 // (credit balance, debit balance or zero balance).
5 import java.io.IOException;
6 import java.lang.IllegalStateException;
7 import java.nio.file.Paths;
8 import java.util.NoSuchElementException;
9 import java.util.Scanner;
10
11 public class CreditInquiry
12 {
13 private final static MenuOption[] choices = MenuOption.values();
14
15 public static void main(String[] args)
16 {
17 // get user's request (e.g., zero, credit or debit balance)
18 MenuOption accountType = getRequest();
19
20 while (accountType != MenuOption.END)
21 {
22 switch (accountType)
23 {
24 case ZERO_BALANCE:
25 System.out.printf("%nAccounts with zero balances:%n");
26 break;
27 case CREDIT_BALANCE:
28 System.out.printf("%nAccounts with credit balances:%n");
29 break;

```

---

**Fig. 15.8** | Credit-inquiry program. (Part 1 of 4.)

---

```

30 case DEBIT_BALANCE:
31 System.out.printf("%nAccounts with debit balances:%n");
32 break;
33 }
34
35 readRecords(accountType);
36 accountType = getRequest(); // get user's request
37 }
38 }
39
40 // obtain request from user
41 private static MenuOption getRequest()
42 {
43 int request = 4;
44
45 // display request options
46 System.out.printf("%nEnter request%n%s%n%s%n%s%n%s%n",
47 " 1 - List accounts with zero balances",
48 " 2 - List accounts with credit balances",
49 " 3 - List accounts with debit balances",
50 " 4 - Terminate program");
51
52 try
53 {
54 Scanner input = new Scanner(System.in);
55
56 do // input user request
57 {
58 System.out.printf("%n? ");
59 request = input.nextInt();
60 } while ((request < 1) || (request > 4));
61 }
62 catch (NoSuchElementException noSuchElementException)
63 {
64 System.err.println("Invalid input. Terminating.");
65 }
66
67 return choices[request - 1]; // return enum value for option
68 }
69
70 // read records from file and display only records of appropriate type
71 private static void readRecords(MenuOption accountType)
72 {
73 // open file and process contents
74 try (Scanner input = new Scanner(Paths.get("clients.txt")))
75 {
76 while (input.hasNext()) // more data to read
77 {
78 int accountNumber = input.nextInt();
79 String firstName = input.next();
80 String lastName = input.next();
81 double balance = input.nextDouble();
82

```

---

**Fig. 15.8** | Credit-inquiry program. (Part 2 of 4.)

```

83 // if proper account type, display record
84 if (shouldDisplay(accountType, balance))
85 System.out.printf("%-10d%-12s%-12s%10.2f%n", accountNumber,
86 firstName, lastName, balance);
87 else
88 input.nextLine(); // discard the rest of the current record
89 }
90 }
91 catch (NoSuchElementException |
92 IllegalStateException | IOException e)
93 {
94 System.err.println("Error processing file. Terminating.");
95 System.exit(1);
96 }
97 } // end method readRecords
98
99 // use record type to determine if record should be displayed
100 private static boolean shouldDisplay(
101 MenuOption accountType, double balance)
102 {
103 if ((accountType == MenuOption.CREDIT_BALANCE) && (balance < 0))
104 return true;
105 else if ((accountType == MenuOption.DEBIT_BALANCE) && (balance > 0))
106 return true;
107 else if ((accountType == MenuOption.ZERO_BALANCE) && (balance == 0))
108 return true;
109
110 return false;
111 }
112 } // end class CreditInquiry

```

```

Enter request
1 - List accounts with zero balances
2 - List accounts with credit balances
3 - List accounts with debit balances
4 - Terminate program

? 1

Accounts with zero balances:
300 Pam White 0.00

Enter request
1 - List accounts with zero balances
2 - List accounts with credit balances
3 - List accounts with debit balances
4 - Terminate program

? 2

Accounts with credit balances:
200 Steve Green -345.67
400 Sam Red -42.16

```

**Fig. 15.8** | Credit-inquiry program. (Part 3 of 4.)

```

Enter request
1 - List accounts with zero balances
2 - List accounts with credit balances
3 - List accounts with debit balances
4 - Terminate program

? 3

Accounts with debit balances:
100 Bob Blue 24.98
500 Sue Yellow 224.62

Enter request
1 - List accounts with zero balances
2 - List accounts with credit balances
3 - List accounts with debit balances
4 - Terminate program

? 4

```

**Fig. 15.8** | Credit-inquiry program. (Part 4 of 4.)

The record information is collected by reading through the file and determining if each record satisfies the criteria for the selected account type. Line 18 in `main` calls method `getRequest` (lines 41–68) to display the menu options, translates the number typed by the user into a `MenuOption` and stores the result in `MenuOption` variable `accountType`. Lines 20–37 loop until the user specifies that the program should terminate. Lines 22–33 display a header for the current set of records to be output to the screen. Line 35 calls method `readRecords` (lines 71–97), which loops through the file and reads every record.

Method `readRecords` uses a `try-with-resources` statement (introduced in Section 11.12) to create a `Scanner` that opens the file for reading (line 74)—recall that `try-with-resources` will close its resource(s) when the `try` block terminates successfully or due to an exception. The file will be opened for reading with a new `Scanner` object each time `readRecords` is called, so that we can again read from the beginning of the file. Lines 78–81 read a record. Line 84 calls method `shouldDisplay` (lines 100–111) to determine whether the current record satisfies the account type requested. If `shouldDisplay` returns `true`, the program displays the account information. When the *end-of-file marker* is reached, the loop terminates and the `try-with-resources` statement closes the `Scanner` and the file. Once all the records have been read, control returns to `main` and `getRequest` is again called (line 36) to retrieve the user’s next menu option.

### 15.4.4 Updating Sequential-Access Files

The data in many sequential files cannot be modified without the risk of destroying other data in the file. For example, if the name “white” needs to be changed to “Worthington,” the old name cannot simply be overwritten, because the new name requires more space. The record for white was written to the file as

```
300 Pam White 0.00
```

If the record is rewritten beginning at the same location in the file using the new name, the record will be

```
300 Pam Worthington 0.00
```

The new record is larger (has more characters) than the original record. “Worthington” would overwrite the “0.00” in the current record and the characters beyond the second “o” in “Worthington” will overwrite the beginning of the next sequential record in the file. The problem here is that fields in a text file—and hence records—can vary in size. For example, 7, 14, -117, 2074 and 27383 are all ints stored in the same number of bytes (4) internally, but they’re different-sized fields when written to a file as text. Therefore, records in a sequential-access file are not usually updated in place—instead, the entire file is rewritten. To make the preceding name change, the records before 300 Pam White 0.00 would be copied to a new file, the new record (which can be of a different size than the one it replaces) would be written and the records after 300 Pam White 0.00 would be copied to the new file. Rewriting the entire file is uneconomical to update just one record, but reasonable if a substantial number of records need to be updated.

## 15.5 Object Serialization

In Section 15.4, we demonstrated how to write the individual fields of a record into a file as text, and how to read those fields from a file. When the data was output to disk, certain information was lost, such as the type of each value. For instance, if the value “3” is read from a file, there’s no way to tell whether it came from an int, a String or a double. We have only data, not type information, on a disk.

Sometimes we want to read an object from or write an object to a file or over a network connection. Java provides **object serialization** for this purposes. A **serialized object** is an object represented as a sequence of bytes that includes the object’s data as well as information about the object’s type and the types of data stored in the object. After a serialized object has been written into a file, it can be read from the file and **deserialized**—that is, the type information and bytes that represent the object and its data can be used to recreate the object in memory.

### *Classes **ObjectInputStream** and **ObjectOutputStream***

Classes **ObjectInputStream** and **ObjectOutputStream** (package java.io), which respectively implement the **ObjectInput** and **ObjectOutput** interfaces, enable entire objects to be read from or written to a stream (possibly a file). To use serialization with files, we initialize **ObjectInputStream** and **ObjectOutputStream** objects with stream objects that read from and write to files. Initializing stream objects with other stream objects in this manner is sometimes called **wrapping**—the new stream object being created wraps the stream object specified as a constructor argument.

Classes **ObjectInputStream** and **ObjectOutputStream** simply read and write the byte-based representation of objects—they don’t know where to read the bytes from or write them to. The stream object that you pass to the **ObjectInputStream** constructor supplies the bytes that the **ObjectInputStream** converts into objects. Similarly, the stream object that you pass to the **ObjectOutputStream** constructor takes the byte-based representation of the object that the **ObjectOutputStream** produces and writes the bytes to the specified destination (e.g., a file, a network connection, etc.).

### Interfaces *ObjectOutput* and *ObjectInput*

The *ObjectOutput* interface contains method **writeObject**, which takes an *Object* as an argument and writes its information to an *OutputStream*. A class that implements interface *ObjectOutput* (such as *ObjectOutputStream*) declares this method and ensures that the object being output implements interface *Serializable* (discussed shortly). Similarly, the *ObjectInput* interface contains method **readObject**, which reads and returns a reference to an *Object* from an *InputStream*. After an object has been read, its reference can be cast to the object's actual type. As you'll see in Chapter 28, applications that communicate via a network, such as the Internet, can also transmit objects across the network.

#### 15.5.1 Creating a Sequential-Access File Using Object Serialization

This section and Section 15.5.2 create and manipulate sequential-access files using object serialization. The object serialization we show here is performed with byte-based streams, so the sequential files created and manipulated will be *binary files*. Recall that binary files typically cannot be viewed in standard text editors. For this reason, we write a separate application that knows how to read and display serialized objects. We begin by creating and writing serialized objects to a sequential-access file. The example is similar to the one in Section 15.4, so we focus only on the new features.

#### Defining Class *Account*

We begin by defining class *Account* (Fig. 15.9), which encapsulates the client record information used by the serialization examples. These examples and class *Account* are all located in the *SerializationApps* directory with the chapter's examples. This allows class *Account* to be used by both examples, because their files are defined in the same default package. Class *Account* contains private instance variables *account*, *firstName*, *lastName* and *balance* (lines 7–10) and *set* and *get* methods for accessing these instance variables. Though the *set* methods do not validate the data in this example, they should do so in an “industrial-strength” system. Class *Account* implements interface **Serializable** (line 5), which allows objects of this class to be *serialized* and *deserialized* with *ObjectOutputStreams* and *ObjectInputStreams*, respectively. Interface *Serializable* is a **tagging interface**. Such an interface does *not* contain methods. A class that implements *Serializable* is *tagged* as being a *Serializable* object. This is important, because an *ObjectOutputStream* will *not* output an object unless it *is a Serializable* object, which is the case for any object of a class that implements *Serializable*.

---

```

1 // Fig. 15.9: Account.java
2 // Serializable Account class for storing records as objects.
3 import java.io.Serializable;
4
5 public class Account implements Serializable
6 {
7 private int account;
8 private String firstName;
9 private String lastName;
10 private double balance;
11
```

---

**Fig. 15.9** | Account class for serializable objects. (Part I of 3.)

---

```
12 // initializes an Account with default values
13 public Account()
14 {
15 this(0, "", "", 0.0); // call other constructor
16 }
17
18 // initializes an Account with provided values
19 public Account(int account, String firstName,
20 String lastName, double balance)
21 {
22 this.account = account;
23 this.firstName = firstName;
24 this.lastName = lastName;
25 this.balance = balance;
26 }
27
28 // set account number
29 public void setAccount(int acct)
30 {
31 this.account = account;
32 }
33
34 // get account number
35 public int getAccount()
36 {
37 return account;
38 }
39
40 // set first name
41 public void setFirstName(String firstName)
42 {
43 this.firstName = firstName;
44 }
45
46 // get first name
47 public String getFirstName()
48 {
49 return firstName;
50 }
51
52 // set last name
53 public void setLastName(String lastName)
54 {
55 this.lastName = lastName;
56 }
57
58 // get last name
59 public String getLastName()
60 {
61 return lastName;
62 }
63
```

---

**Fig. 15.9** | Account class for serializable objects. (Part 2 of 3.)



---

```

64 // set balance
65 public void setBalance(double balance)
66 {
67 this.balance = balance;
68 }
69
70 // get balance
71 public double getBalance()
72 {
73 return balance;
74 }
75 } // end class Account

```

---

**Fig. 15.9** | Account class for serializable objects. (Part 3 of 3.)

In a `Serializable` class, every instance variable must be `Serializable`. Non-`Serializable` instance variables must be declared **transient** to indicate that they should be ignored during the serialization process. *By default, all primitive-type variables are serializable.* For reference-type variables, you must check the class's documentation (and possibly its superclasses) to ensure that the type is `Serializable`. For example, `Strings` are `Serializable`. By default, arrays *are* serializable; however, in a reference-type array, the referenced objects might *not* be. Class `Account` contains private data members `account`, `firstName`, `lastName` and `balance`—all of which are `Serializable`. This class also provides public *get* and *set* methods for accessing the private fields.

### *Writing Serialized Objects to a Sequential-Access File*

Now let's discuss the code that creates the sequential-access file (Fig. 15.10). We concentrate only on new concepts here. To open the file, line 27 calls `Files` static method **`newOutputStream`**, which receives a `Path` specifying the file to open and, if the file exists, returns an `OutputStream` that can be used to write to the file. Existing files that are opened for output in this manner are *truncated*. There is no standard filename extension for files that store serialized objects, so we chose the `.ser`.

---

```

1 // Fig. 15.10: CreateSequentialFile.java
2 // Writing objects sequentially to a file with class ObjectOutputStream.
3 import java.io.IOException;
4 import java.io.ObjectOutputStream;
5 import java.nio.file.Files;
6 import java.nio.file.Paths;
7 import java.util.NoSuchElementException;
8 import java.util.Scanner;
9
10 public class CreateSequentialFile
11 {
12 private static ObjectOutputStream output; // outputs data to file
13

```

---

**Fig. 15.10** | Sequential file created using `ObjectOutputStream`. (Part 1 of 3.)

---

```

14 public static void main(String[] args)
15 {
16 openFile();
17 addRecords();
18 closeFile();
19 }
20
21 // open file clients.ser
22 public static void openFile()
23 {
24 try
25 {
26 output = new ObjectOutputStream(
27 Files.newOutputStream(Paths.get("clients.ser")));
28 }
29 catch (IOException ioException)
30 {
31 System.err.println("Error opening file. Terminating.");
32 System.exit(1); // terminate the program
33 }
34 }
35
36 // add records to file
37 public static void addRecords()
38 {
39 Scanner input = new Scanner(System.in);
40
41 System.out.printf("%s\n%s\n? ",
42 "Enter account number, first name, last name and balance.",
43 "Enter end-of-file indicator to end input.");
44
45 while (input.hasNext()) // loop until end-of-file indicator
46 {
47 try
48 {
49 // create new record; this example assumes valid input
50 Account record = new Account(input.nextInt(),
51 input.next(), input.next(), input.nextDouble());
52
53 // serialize record object into file
54 output.writeObject(record);
55 }
56 catch (NoSuchElementException elementException)
57 {
58 System.err.println("Invalid input. Please try again.");
59 input.nextLine(); // discard input so user can try again
60 }
61 catch (IOException ioException)
62 {
63 System.err.println("Error writing to file. Terminating.");
64 break;
65 }

```

---

**Fig. 15.10** | Sequential file created using `ObjectOutputStream`. (Part 2 of 3.)

```

66
67 System.out.print("? ");
68 }
69 }
70
71 // close file and terminate application
72 public static void closeFile()
73 {
74 try
75 {
76 if (output != null)
77 output.close();
78 }
79 catch (IOException ioException)
80 {
81 System.err.println("Error closing file. Terminating.");
82 }
83 }
84 } // end class CreateSequentialFile

```

```

Enter account number, first name, last name and balance.
Enter end-of-file indicator to end input.
? 100 Bob Blue 24.98
? 200 Steve Green -345.67
? 300 Pam White 0.00
? 400 Sam Red -42.16
? 500 Sue Yellow 224.62
? ^Z

```

**Fig. 15.10** | Sequential file created using `ObjectOutputStream`. (Part 3 of 3.)

Class `OutputStream` provides methods for outputting byte arrays and individual bytes, but we wish to write *objects* to a file. For this reason, lines 26–27 pass the `InputStream` to class `ObjectInputStream`'s constructor, which *wraps* the `OutputStream` in an `ObjectOutputStream`. The `ObjectOutputStream` object uses the `OutputStream` to write into the file the bytes that represent entire objects. Lines 26–27 might throw an **`IOException`** if a problem occurs while opening the file (e.g., when a file is opened for writing on a drive with insufficient space or when a read-only file is opened for writing). If so, the program displays an error message (lines 29–33). If no exception occurs, the file is open, and variable `output` can be used to write objects to it.

This program assumes that data is input correctly and in the proper record-number order. Method `addRecords` (lines 37–69) performs the write operation. Lines 50–51 create an `Account` object from the data entered by the user. Line 54 calls `ObjectOutputStream` method `writeObject` to write the record object to the output file. Only one statement is required to write the *entire* object.

Method `closeFile` (lines 72–83) calls `ObjectOutputStream` method `close` on `output` to close both the `ObjectOutputStream` *and* its underlying `OutputStream`. The call to method `close` is contained in a try block, because `close` throws an `IOException` if the file cannot be closed properly. When using *wrapped* streams, closing the outermost stream *also* closes the wrapped stream as well.

In the sample execution for the program in Fig. 15.10, we entered information for five accounts—the same information shown in Fig. 15.5. The program does not show how the data records actually appear in the file. Remember that now we’re using *binary files*, which are not humanly readable. To verify that the file has been created successfully, the next section presents a program to read the file’s contents.

### 15.5.2 Reading and Deserializing Data from a Sequential-Access File

The preceding section showed how to create a file for sequential access using object serialization. In this section, we discuss how to *read serialized data* sequentially from a file.

The program in Fig. 15.11 reads records from a file created by the program in Section 15.5.1 and displays the contents. The program opens the file for input by calling Files static method `newInputStream`, which receives a Path specifying the file to open and, if the file exists, returns an `InputStream` that can be used to read from the file. In Fig. 15.10, we wrote objects to the file, using an `ObjectOutputStream` object. Data must be read from the file in the same format in which it was written. Therefore, we use an `ObjectInputStream` *wrapped* around an `InputStream` (lines 26–27). If no exceptions occur when opening the file, variable `input` can be used to read objects from the file.

---

```

1 // Fig. 15.11: ReadSequentialFile.java
2 // Reading a file of objects sequentially with ObjectInputStream
3 // and displaying each record.
4 import java.io.EOFException;
5 import java.io.IOException;
6 import java.io.ObjectInputStream;
7 import java.nio.file.Files;
8 import java.nio.file.Paths;
9
10 public class ReadSequentialFile
11 {
12 private static ObjectInputStream input;
13
14 public static void main(String[] args)
15 {
16 openFile();
17 readRecords();
18 closeFile();
19 }
20
21 // enable user to select file to open
22 public static void openFile()
23 {
24 try // open file
25 {
26 input = new ObjectInputStream(
27 Files.newInputStream(Paths.get("clients.ser")));
28 }
29 catch (IOException ioException)
30 {

```

---

**Fig. 15.11** | Reading a file of objects sequentially with `ObjectInputStream` and displaying each record. (Part I of 3.)

---

```

31 System.err.println("Error opening file.");
32 System.exit(1);
33 }
34 }
35
36 // read record from file
37 public static void readRecords()
38 {
39 System.out.printf("%-10s%-12s%-12s%10s\n", "Account",
40 "First Name", "Last Name", "Balance");
41
42 try
43 {
44 while (true) // loop until there is an EOFException
45 {
46 Account record = (Account) input.readObject();
47
48 // display record contents
49 System.out.printf("%-10d%-12s%-12s%10.2f\n",
50 record.getAccount(), record.getFirstName(),
51 record.getLastName(), record.getBalance());
52 }
53 }
54 catch (EOFException eofException)
55 {
56 System.out.printf("%No more records\n");
57 }
58 catch (ClassNotFoundException classNotFoundException)
59 {
60 System.err.println("Invalid object type. Terminating.");
61 }
62 catch (IOException ioException)
63 {
64 System.err.println("Error reading from file. Terminating.");
65 }
66 } // end method readRecords
67
68 // close file and terminate application
69 public static void closeFile()
70 {
71 try
72 {
73 if (input != null)
74 input.close();
75 }
76 catch (IOException ioException)
77 {
78 System.err.println("Error closing file. Terminating.");
79 System.exit(1);
80 }
81 }
82 } // end class ReadSequentialFile

```

---

**Fig. 15.11** | Reading a file of objects sequentially with `ObjectInputStream` and displaying each record. (Part 2 of 3.)

| Account | First Name | Last Name | Balance |
|---------|------------|-----------|---------|
| 100     | Bob        | Blue      | 24.98   |
| 200     | Steve      | Green     | -345.67 |
| 300     | Pam        | White     | 0.00    |
| 400     | Sam        | Red       | -42.16  |
| 500     | Sue        | Yellow    | 224.62  |

No more records

**Fig. 15.11** | Reading a file of objects sequentially with `ObjectInputStream` and displaying each record. (Part 3 of 3.)

The program reads records from the file in method `readRecords` (lines 37–66). Line 46 calls `ObjectInputStream` method `readObject` to read an `Object` from the file. To use `Account`-specific methods, we *downcast* the returned `Object` to type `Account`. Method `readObject` throws an `EOFException` (processed at lines 54–57) if an attempt is made to read beyond the end of the file. Method `readObject` throws a `ClassNotFoundException` if the class for the object being read cannot be located. This may occur if the file is accessed on a computer that does not have the class.



### Software Engineering Observation 15.1

*This section introduced object serialization and demonstrated basic serialization techniques. Serialization is a deep subject with many traps and pitfalls. Before implementing object serialization in industrial-strength applications, carefully read the online Java documentation for object serialization.*

## 15.6 Opening Files with `JFileChooser`

Class `JFileChooser` displays a dialog that enables the user to easily select files or directories. To demonstrate `JFileChooser`, we enhance the example in Section 15.3, as shown in Figs. 15.12–15.13. The example now contains a graphical user interface, but still displays the same data as before. The constructor calls method `analyzePath` in line 24. This method then calls method `getFileOrDirectoryPath` in line 31 to retrieve a `Path` object representing the selected file or directory.

Method `getFileOrDirectoryPath` (lines 71–85 of Fig. 15.12) creates a `JFileChooser` (line 74). Lines 75–76 call method `setFileSelectionMode` to specify what the user can select from the `fileChooser`. For this program, we use `JFileChooser` static constant `FILES_AND_DIRECTORIES` to indicate that files and directories can be selected. Other static constants include `FILES_ONLY` (the default) and `DIRECTORIES_ONLY`.

Line 77 calls method `showOpenDialog` to display the `JFileChooser` dialog titled `Open`. Argument `this` specifies the `JFileChooser` dialog's parent window, which determines the position of the dialog on the screen. If `null` is passed, the dialog is displayed in the center of the screen—otherwise, the dialog is centered over the application window (specified by the argument `this`). A `JFileChooser` dialog is a *modal dialog* that does not allow the user to interact with any other window in the program until the dialog is closed. The user selects the drive, directory or filename, then clicks `Open`. Method `showOpenDialog` returns an integer specifying which button (`Open` or `Cancel`) the user clicked to close the dialog. Line

48 tests whether the user clicked **Cancel** by comparing the result with static constant **CANCEL\_OPTION**. If they're equal, the program terminates. Line 84 calls **JFileChooser** method **getSelectedFile** to retrieve a **File** object (package **java.io**) representing the file or directory that the user selected, then calls **File** method **toPath** to return a **Path** object. The program then displays information about the selected file or directory.

---

```

1 // Fig. 15.12: JFileChooserDemo.java
2 // Demonstrating JFileChooser.
3 import java.io.IOException;
4 import java.nio.file.DirectoryStream;
5 import java.nio.file.Files;
6 import java.nio.file.Path;
7 import java.nio.file.Paths;
8 import javax.swing.JFileChooser;
9 import javax.swing.JFrame;
10 import javax.swing.JOptionPane;
11 import javax.swing.JScrollPane;
12 import javax.swing.JTextArea;
13
14 public class JFileChooserDemo extends JFrame
15 {
16 private final JTextArea outputArea; // displays file contents
17
18 // set up GUI
19 public JFileChooserDemo() throws IOException
20 {
21 super("JFileChooser Demo");
22 outputArea = new JTextArea();
23 add(new JScrollPane(outputArea)); // outputArea is scrollable
24 analyzePath(); // get Path from user and display info
25 }
26
27 // display information about file or directory user specifies
28 public void analyzePath() throws IOException
29 {
30 // get Path to user-selected file or directory
31 Path path = getFileOrDirectoryPath();
32
33 if (path != null && Files.exists(path)) // if exists, display info
34 {
35 // gather file (or directory) information
36 StringBuilder builder = new StringBuilder();
37 builder.append(String.format("%s:%n", path.getFileName()));
38 builder.append(String.format("%s a directory%n",
39 Files.isDirectory(path) ? "Is" : "Is not"));
40 builder.append(String.format("%s an absolute path%n",
41 path.isAbsolute() ? "Is" : "Is not"));
42 builder.append(String.format("Last modified: %s%n",
43 Files.getLastModifiedTime(path)));
44 builder.append(String.format("Size: %s%n", Files.size(path)));
45 builder.append(String.format("Path: %s%n", path));

```

---

**Fig. 15.12** | Demonstrating JFileChooser. (Part 1 of 2.)

---

```

46 builder.append(String.format("Absolute path: %s\n",
47 path.toAbsolutePath()));
48
49 if (Files.isDirectory(path)) // output directory listing
50 {
51 builder.append(String.format("%nDirectory contents:%n"));
52
53 // object for iterating through a directory's contents
54 DirectoryStream<Path> directoryStream =
55 Files.newDirectoryStream(path);
56
57 for (Path p : directoryStream)
58 builder.append(String.format("%s\n", p));
59 }
60
61 outputArea.setText(builder.toString()); // display String content
62 }
63 else // Path does not exist
64 {
65 JOptionPane.showMessageDialog(this, path.getFileName() +
66 " does not exist.", "ERROR", JOptionPane.ERROR_MESSAGE);
67 }
68 } // end method analyzePath
69
70 // allow user to specify file or directory name
71 private Path getFileOrDirectoryPath()
72 {
73 // configure dialog allowing selection of a file or directory
74 JFileChooser fileChooser = new JFileChooser();
75 fileChooser.setFileSelectionMode(
76 JFileChooser.FILES_AND_DIRECTORIES);
77 int result = fileChooser.showOpenDialog(this);
78
79 // if user clicked Cancel button on dialog, return
80 if (result == JFileChooser.CANCEL_OPTION)
81 System.exit(1);
82
83 // return Path representing the selected file
84 return fileChooser.getSelectedFile().toPath();
85 }
86 } // end class JFileChooserDemo

```

---

**Fig. 15.12** | Demonstrating JFileChooser. (Part 2 of 2.)

---

```

1 // Fig. 15.13: JFileChooserTest.java
2 // Tests class JFileChooserDemo.
3 import java.io.IOException;
4 import javax.swing.JFrame;
5
6 public class JFileChooserTest
7 {

```

---

**Fig. 15.13** | Testing class FileDemonstration. (Part 1 of 2.)




```

8 public static void main(String[] args) throws IOException
9 {
10 JFileChooserDemo application = new JFileChooserDemo();
11 application.setSize(400, 400);
12 application.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
13 application.setVisible(true);
14 }
15 } // end class JFileChooserTest

```


a) Use this dialog to locate and select a file or directory

Files and directories are displayed here



Click **Open** to submit file or directory name to program

b) Selected file's or directory's information; if it's a directory, the contents of that directory are displayed



**Fig. 15.13** | Testing class FileDemonstration. (Part 2 of 2.)

## 15.7 (Optional) Additional java.io Classes

This section overviews additional interfaces and classes (from package java.io).

### 15.7.1 Interfaces and Classes for Byte-Based Input and Output

InputStream and OutputStream are abstract classes that declare methods for performing byte-based input and output, respectively.

#### *Pipe Streams*

Pipes are synchronized communication channels between threads. We discuss threads in Chapter 23. Java provides **PipedOutputStream** (a subclass of OutputStream) and **Piped-**

**InputStream** (a subclass of `InputStream`) to establish pipes between two threads in a program. One thread sends data to another by writing to a `PipedOutputStream`. The target thread reads information from the pipe via a `PipedInputStream`.

### *Filter Streams*

A **FilterInputStream** filters an `InputStream`, and a `FilterOutputStream` filters an `OutputStream`. **Filtering** means simply that the filter stream provides additional functionality, such as aggregating bytes into meaningful primitive-type units. `FilterInputStream` and `FilterOutputStream` are typically used as superclasses, so some of their filtering capabilities are provided by their subclasses.

A **PrintStream** (a subclass of `FilterOutputStream`) performs text output to the specified stream. Actually, we've been using `PrintStream` output throughout the text to this point—`System.out` and `System.err` are `PrintStream` objects.

### *Data Streams*

Reading data as raw bytes is fast, but crude. Usually, programs read data as aggregates of bytes that form ints, floats, doubles and so on. Java programs can use several classes to input and output data in aggregate form.

Interface `DataInput` describes methods for reading primitive types from an input stream. Classes **`DataInputStream`** and `RandomAccessFile` each implement this interface to read sets of bytes and view them as primitive-type values. Interface `DataInput` includes methods such as `readBoolean`, `readByte`, `readChar`, `readDouble`, `readFloat`, `readFully` (for byte arrays), `readInt`, `readLong`, `readShort`, `readUnsignedByte`, `readUnsignedShort`, `readUTF` (for reading Unicode characters encoded by Java—we discuss UTF encoding in Appendix H) and `skipBytes`.

Interface `DataOutput` describes a set of methods for writing primitive types to an output stream. Classes **`DataOutputStream`** (a subclass of `FilterOutputStream`) and `RandomAccessFile` each implement this interface to write primitive-type values as bytes. Interface `DataOutput` includes overloaded versions of method `write` (for a byte or for a byte array) and methods `writeBoolean`, `writeByte`, `writeBytes`, `writeChar`, `writeChars` (for Unicode Strings), `writeDouble`, `writeFloat`, `writeInt`, `writeLong`, `writeShort` and `writeUTF` (to output text modified for Unicode).

### *Buffered Streams*

**Buffering** is an I/O-performance-enhancement technique. With a **`BufferedOutputStream`** (a subclass of class `FilterOutputStream`), each output statement does *not* necessarily result in an actual physical transfer of data to the output device (which is a slow operation compared to processor and main memory speeds). Rather, each output operation is directed to a region in memory called a **buffer** that's large enough to hold the data of many output operations. Then, actual transfer to the output device is performed in one large **physical output operation** each time the buffer fills. The output operations directed to the output buffer in memory are often called **logical output operations**. With a `BufferedOutputStream`, a partially filled buffer can be forced out to the device at any time by invoking the stream object's **`flush`** method.

Using buffering can greatly increase the performance of an application. Typical I/O operations are extremely slow compared with the speed of accessing data in computer

memory. Buffering reduces the number of I/O operations by first combining smaller outputs together in memory. The number of actual physical I/O operations is small compared with the number of I/O requests issued by the program. Thus, the program that's using buffering is more efficient.



### Performance Tip 15.1

*Buffered I/O can yield significant performance improvements over unbuffered I/O.*

With a **BufferedInputStream** (a subclass of class `FilterInputStream`), many “logical” chunks of data from a file are read as one large **physical input operation** into a memory buffer. As a program requests each new chunk of data, it's taken from the buffer. (This procedure is sometimes referred to as a **logical input operation**.) When the buffer is empty, the next actual physical input operation from the input device is performed to read in the next group of “logical” chunks of data. Thus, the number of actual physical input operations is small compared with the number of read requests issued by the program.

### Memory-Based **byte** Array Streams

Java stream I/O includes capabilities for inputting from byte arrays in memory and outputting to byte arrays in memory. A `ByteArrayInputStream` (a subclass of `InputStream`) reads from a byte array in memory. A `ByteArrayOutputStream` (a subclass of `OutputStream`) outputs to a byte array in memory. One use of byte-array I/O is *data validation*. A program can input an entire line at a time from the input stream into a byte array. Then a validation routine can scrutinize the contents of the byte array and correct the data if necessary. Finally, the program can proceed to input from the byte array, “knowing” that the input data is in the proper format. Outputting to a byte array is a nice way to take advantage of the powerful output-formatting capabilities of Java streams. For example, data can be stored in a byte array, using the same formatting that will be displayed at a later time, and the byte array can then be output to a file to preserve the formatting.

### Sequencing Input from Multiple Streams

A `SequenceInputStream` (a subclass of `InputStream`) logically concatenates several `InputStream`s—the program sees the group as one continuous `InputStream`. When the program reaches the end of one input stream, that stream closes, and the next stream in the sequence opens.

## 15.7.2 Interfaces and Classes for Character-Based Input and Output

In addition to the byte-based streams, Java provides the **Reader** and **Writer** abstract classes, which are character-based streams like those you used for text-file processing in Section 15.4. Most of the byte-based streams have corresponding character-based concrete `Reader` or `Writer` classes.

### Character-Based Buffering Readers and Writers

Classes **BufferedReader** (a subclass of abstract class `Reader`) and **BufferedWriter** (a subclass of abstract class `Writer`) enable buffering for character-based streams. Remember that character-based streams use Unicode characters—such streams can process data in any language that the Unicode character set represents.

*Memory-Based **char** Array Readers and Writers*

Classes **CharArrayReader** and **CharArrayWriter** read and write, respectively, a stream of characters to a char array. A **LineNumberReader** (a subclass of **BufferedReader**) is a buffered character stream that keeps track of the number of lines read—newlines, returns and carriage-return–line-feed combinations increment the line count. Keeping track of line numbers can be useful if the program needs to inform the reader of an error on a specific line.

*Character-Based File, Pipe and String Readers and Writers*

An **InputStream** can be converted to a **Reader** via class **InputStreamReader**. Similarly, an **OutputStream** can be converted to a **Writer** via class **OutputStreamWriter**. Class **FileReader** (a subclass of **InputStreamReader**) and class **FileWriter** (a subclass of **OutputStreamWriter**) read characters from and write characters to a file, respectively. Class **PipedReader** and class **PipedWriter** implement piped-character streams for transferring data between threads. Class **StringReader** and **StringWriter** read characters from and write characters to **Strings**, respectively. A **PrintWriter** writes characters to a stream.

## 15.8 Wrap-Up

In this chapter, you learned how to manipulate persistent data. We compared byte-based and character-based streams, and introduced several classes from packages **java.io** and **java.nio.file**. You used classes **Files** and **Paths** and interfaces **Path** and **DirectoryStream** to retrieve information about files and directories. You used sequential-access file processing to manipulate records that are stored in order by the record-key field. You learned the differences between text-file processing and object serialization, and used serialization to store and retrieve entire objects. The chapter concluded with a small example of using a **JFileChooser** dialog to allow users to easily select files from a GUI. The next chapter discusses Java's classes for manipulating collections of data—such as class **ArrayList**, which we introduced in Section 6.13.

## Summary

*Section 15.1 Introduction*

- Computers use files for long-term retention of large amounts of persistent data (p. 637), even after the programs that created the data terminate.
- Computers store files on secondary storage devices (p. 637) such as hard disks.

*Section 15.2 Files and Streams*

- Java views each file as a sequential stream of bytes (p. 637).
- Every operating system provides a mechanism to determine the end of a file, such as an end-of-file marker (p. 637) or a count of the total bytes in the file.
- Byte-based streams (p. 638) represent data in binary format.
- Character-based streams (p. 638) represent data as sequences of characters.
- Files created using byte-based streams are binary files (p. 638). Files created using character-based streams are text files (p. 638). Text files can be read by text editors, whereas binary files are read by a program that converts the data to a human-readable format.

- Java also can associate streams with different devices. Three stream objects are associated with devices when a Java program begins executing—`System.in`, `System.out` and `System.err`.

### *Section 15.3 Using NIO Classes and Interfaces to Get File and Directory Information*

- A `Path` (p. 639) represents the location of a file or directory. Path objects do not open files or provide any file-processing capabilities.
- `Class Paths` (p. 639) is used to get a `Path` object representing a file or directory location.
- `Class Files` (p. 639) provides static methods for common file and directory manipulations, including methods for copying files; creating and deleting files and directories; getting information about files and directories; reading the contents of files; getting objects that allow you to manipulate the contents of files and directories; and more.
- A `DirectoryStream` (p. 639) enables a program to iterate through the contents of a directory.
- The static method `get` (p. 639) of class `Paths` converts a `String` representing a file's or directory's location into a `Path` object.
- Character-based input and output can be performed with classes `Scanner` and `Formatter`.
- `Class Formatter` (p. 639) enables formatted data to be output to the screen or to a file in a manner similar to `System.out.printf`.
- An absolute path (p. 639) contains all the directories, starting with the root directory (p. 639), that lead to a specific file or directory. Every file or directory on a disk drive has the same root directory in its path.
- A relative path (p. 639) starts from the directory in which the application began executing.
- `Files` static method `exists` (p. 640) receives a `Path` and determines whether it exists (either as a file or as a directory) on disk.
- `Path` method `getFileName` (p. 640) gets the `String` name of a file or directory without any location information.
- `Files` static method `isDirectory` (p. 640) receives a `Path` and returns a `boolean` indicating whether that `Path` represents a directory on disk.
- `Path` method `isAbsolute` (p. 640) returns a `boolean` indicating whether a `Path` represents an absolute path to a file or directory.
- `Files` static method `getLastModifiedTime` (p. 640) receives a `Path` and returns a `FileTime` (package `java.nio.file.attribute`) indicating when the file was last modified.
- `Files` static method `size` (p. 640) receives a `Path` and returns a `long` representing the number of bytes in the file or directory. For directories, the value returned is platform specific.
- `Path` method `toString` (p. 640) returns a `String` representation of the `Path`.
- `Path` method `toAbsolutePath` (p. 640) converts the `Path` on which it's called to an absolute path.
- `Files` static method `newDirectoryStream` (p. 640) returns a `DirectoryStream<Path>` containing `Path` objects for a directory's contents.
- A separator character (p. 642) is used to separate directories and files in the path.

### *Section 15.4 Sequential-Access Text Files*

- Java imposes no structure on a file. You must structure files to meet your application's needs.
- To retrieve data sequentially from a file, programs normally start from the beginning of the file and read all the data consecutively until the desired information is found.
- Data in many sequential files cannot be modified without the risk of destroying other data in the file. Records in a sequential-access file are usually updated by rewriting the entire file.

*Section 15.5 Object Serialization*

- Java provides a mechanism called object serialization (p. 654) that enables entire objects to be written to or read from a stream.
- A serialized object (p. 654) is represented as a sequence of bytes that includes the object's data as well as information about the object's type and the types of data it stores.
- After a serialized object has been written into a file, it can be read from the file and deserialized (p. 654) to recreate the object in memory.
- Classes `ObjectInputStream` (p. 654) and `ObjectOutputStream` (p. 654) enable entire objects to be read from or written to a stream (possibly a file).
- Only classes that implement interface `Serializable` (p. 655) can be serialized and deserialized.
- The `ObjectOutputStream` interface (p. 654) contains method `writeObject` (p. 655), which takes an `Object` as an argument and writes its information to an `OutputStream`. A class that implements this interface, such as `ObjectOutputStream`, would ensure that the `Object` is `Serializable`.
- The `ObjectInputStream` interface (p. 654) contains method `readObject` (p. 655), which reads and returns a reference to an `Object` from an `InputStream`. After an object has been read, its reference can be cast to the object's actual type.

*Section 15.6 Opening Files with JFileChooser*

- Class `JFileChooser` (p. 662) is used to display a dialog that enables users of a program to easily select files or directories from a GUI.

*Section 15.7 (Optional) Additional java.io Classes*

- `InputStream` and `OutputStream` are abstract classes for performing byte-based I/O.
- Pipes (p. 665) are synchronized communication channels between threads. One thread sends data via a `PipedOutputStream` (p. 665). The target thread reads information from the pipe via a `PipedInputStream` (p. 665).
- A filter stream (p. 666) provides additional functionality, such as aggregating data bytes into meaningful primitive-type units. `FilterInputStream` (p. 666) and `FilterOutputStream` are typically extended, so some of their filtering capabilities are provided by their concrete subclasses.
- A `PrintStream` (p. 666) performs text output. `System.out` and `System.err` are `PrintStreams`.
- Interface `DataInput` describes methods for reading primitive types from an input stream. Classes `DataInputStream` (p. 666) and `RandomAccessFile` each implement this interface.
- Interface `DataOutput` describes methods for writing primitive types to an output stream. Classes `DataOutputStream` (p. 666) and `RandomAccessFile` each implement this interface.
- Buffering is an I/O-performance-enhancement technique. Buffering reduces the number of I/O operations by combining smaller outputs together in memory. The number of physical I/O operations is much smaller than the number of I/O requests issued by the program.
- With a `BufferedOutputStream` (p. 666) each output operation is directed to a buffer (p. 666) large enough to hold the data of many output operations. Transfer to the output device is performed in one large physical output operation (p. 666) when the buffer fills. A partially filled buffer can be forced out to the device at any time by invoking the stream object's `flush` method (p. 666).
- With a `BufferedInputStream` (p. 667), many "logical" chunks of data from a file are read as one large physical input operation (p. 667) into a memory buffer. As a program requests data, it's taken from the buffer. When the buffer is empty, the next actual physical input operation is performed.
- A `ByteArrayInputStream` reads from a byte array in memory. A `ByteArrayOutputStream` outputs to a byte array in memory.

- A `SequenceInputStream` concatenates several `InputStreams`. When the program reaches the end of an input stream, that stream closes, and the next stream in the sequence opens.
- The `Reader` (p. 667) and `Writer` (p. 667) abstract classes are Unicode character-based streams. Most byte-based streams have corresponding character-based concrete `Reader` or `Writer` classes.
- Classes `BufferedReader` (p. 667) and `BufferedWriter` (p. 667) buffer character-based streams.
- Classes `CharArrayReader` (p. 668) and `CharArrayWriter` (p. 668) manipulate char arrays.
- A `LineNumberReader` (p. 668) is a buffered character stream that tracks the number of lines read.
- Classes `FileReader` (p. 668) and `FileWriter` (p. 668) perform character-based file I/O.
- Class `PipedReader` (p. 668) and class `PipedWriter` (p. 668) implement piped-character streams for transferring data between threads.
- Class `StringReader` (p. 668) and `StringWriter` (p. 668) read characters from and write characters to `Strings`, respectively. A `PrintWriter` (p. 646) writes characters to a stream.

## Self-Review Exercises

- 15.1** Determine whether each of the following statements is *true* or *false*. If *false*, explain why.
- a) You must explicitly create the stream objects `System.in`, `System.out` and `System.err`.
  - b) When reading data from a file using class `Scanner`, if you wish to read data in the file multiple times, the file must be closed and reopened to read from the beginning of the file.
  - c) `Files` static method `exists` receives a `Path` and determines whether it exists (either as a file or as a directory) on disk
  - d) Binary files are human readable in a text editor.
  - e) An absolute path contains all the directories, starting with the root directory, that lead to a specific file or directory.
  - f) Class `Formatter` contains method `printf`, which enables formatted data to be output to the screen or to a file.
- 15.2** Complete the following tasks, assuming that each applies to the same program:
- a) Write a statement that opens file `"oldmast.txt"` for input—use `Scanner` variable `inOldMaster`.
  - b) Write a statement that opens file `"trans.txt"` for input—use `Scanner` variable `inTransaction`.
  - c) Write a statement that opens file `"newmast.txt"` for output (and creation)—use `formatter` variable `outNewMaster`.
  - d) Write the statements needed to read a record from the file `"oldmast.txt"`. Use the data to create an object of class `Account`—use `Scanner` variable `inOldMaster`. Assume that class `Account` is the same as the `Account` class in Fig. 15.9.
  - e) Write the statements needed to read a record from the file `"trans.txt"`. The record is an object of class `TransactionRecord`—use `Scanner` variable `inTransaction`. Assume that class `TransactionRecord` contains method `setAccount` (which takes an `int`) to set the account number and method `setAmount` (which takes a `double`) to set the amount of the transaction.
  - f) Write a statement that outputs a record to the file `"newmast.txt"`. The record is an object of type `Account`—use `Formatter` variable `outNewMaster`.
- 15.3** Complete the following tasks, assuming that each applies to the same program:
- a) Write a statement that opens file `"oldmast.ser"` for input—use `ObjectInputStream` variable `inOldMaster` to wrap an `InputStream` object.
  - b) Write a statement that opens file `"trans.ser"` for input—use `ObjectInputStream` variable `inTransaction` to wrap an `InputStream` object.

- c) Write a statement that opens file "newmast.ser" for output (and creation)—use `ObjectOutputStream` variable `outNewMaster` to wrap an `OutputStream`.
- d) Write a statement that reads a record from the file "oldmast.ser". The record is an object of class `Account`—use `ObjectInputStream` variable `inOldMaster`. Assume class `Account` is the same as the `Account` class in Fig. 15.9
- e) Write a statement that reads a record from the file "trans.ser". The record is an object of class `TransactionRecord`—use `ObjectInputStream` variable `inTransaction`.
- f) Write a statement that outputs a record of type `Account` to the file "newmast.ser"—use `ObjectOutputStream` variable `outNewMaster`.

## Answers to Self-Review Exercises

**15.1** a) False. These three streams are created for you when a Java application begins executing. b) True. c) True. d) False. Text files are human readable in a text editor. Binary files might be human readable, but only if the bytes in the file represent ASCII characters. e) True. f) False. Class `Formatter` contains method `format`, which enables formatted data to be output to the screen or to a file.

**15.2**

- a) `Scanner inOldMaster = new Scanner(Paths.get("oldmast.txt"));`
- b) `Scanner inTransaction = new Scanner(Paths.get("trans.txt"));`
- c) `Formatter outNewMaster = new Formatter("newmast.txt");`
- d) `Account account = new Account();`  
`account.setAccount(inOldMaster.nextInt());`  
`account.setFirstName(inOldMaster.next());`  
`account.setLastName(inOldMaster.next());`  
`account.setBalance(inOldMaster.nextDouble());`
- e) `TransactionRecord transaction = new Transaction();`  
`transaction.setAccount(inTransaction.nextInt());`  
`transaction.setAmount(inTransaction.nextDouble());`
- f) `outNewMaster.format("%d %s %s %.2f%n",`  
`account.getAccount(), account.getFirstName(),`  
`account.getLastName(), account.getBalance());`

**15.3**

- a) `ObjectInputStream inOldMaster = new ObjectInputStream(`  
`Files.newInputStream(Paths.get("oldmast.ser")));`
- b) `ObjectInputStream inTransaction = new ObjectInputStream(`  
`Files.newOutputStream(Paths.get("trans.ser")));`
- c) `ObjectOutputStream outNewMaster = new ObjectOutputStream(`  
`Files.newOutputStream(Paths.get("newmast.ser")));`
- d) `Account = (Account) inOldMaster.readObject();`
- e) `transactionRecord = (TransactionRecord) inTransaction.readObject();`
- f) `outNewMaster.writeObject(newAccount);`

## Exercises

**15.4 (File Matching)** Self-Review Exercise 15.2 asked you to write a series of single statements. Actually, these statements form the core of an important type of file-processing program—namely, a file-matching program. In commercial data processing, it's common to have several files in each application system. In an accounts receivable system, for example, there's generally a master file containing detailed information about each customer, such as the customer's name, address, telephone number, outstanding balance, credit limit, discount terms, contract arrangements and possibly a condensed history of recent purchases and cash payments.



As transactions occur (i.e., sales are made and payments arrive in the mail), information about them is entered into a file. At the end of each business period (a month for some companies, a week for others, and a day in some cases), the file of transactions (called "trans.txt") is applied to the master file (called "oldmast.txt") to update each account's purchase and payment record. During an update, the master file is rewritten as the file "newmast.txt", which is then used at the end of the next business period to begin the updating process again.

File-matching programs must deal with certain problems that do not arise in single-file programs. For example, a match does not always occur. If a customer on the master file has not made any purchases or cash payments in the current business period, no record for this customer will appear on the transaction file. Similarly, a customer who did make some purchases or cash payments could have just moved to this community, and if so, the company may not have had a chance to create a master record for this customer.

Write a complete file-matching accounts receivable program. Use the account number on each file as the record key for matching purposes. Assume that each file is a sequential text file with records stored in increasing account-number order.

- Define class `TransactionRecord`. Objects of this class contain an account number and amount for the transaction. Provide methods to modify and retrieve these values.
- Modify class `Account` in Fig. 15.9 to include method `combine`, which takes a `TransactionRecord` object and combines the balance of the `Account` object and the amount value of the `TransactionRecord` object.
- Write a program to create data for testing the program. Use the sample account data in Figs. 15.14 and 15.15. Run the program to create the files `trans.txt` and `oldmast.txt` to be used by your file-matching program.

| Master file<br>account number | Name       | Balance |
|-------------------------------|------------|---------|
| 100                           | Alan Jones | 348.17  |
| 300                           | Mary Smith | 27.19   |
| 500                           | Sam Sharp  | 0.00    |
| 700                           | Suzy Green | -14.22  |

**Fig. 15.14** | Sample data for master file.

| Transaction file<br>account number | Transaction<br>amount |
|------------------------------------|-----------------------|
| 100                                | 27.14                 |
| 300                                | 62.11                 |
| 400                                | 100.56                |
| 900                                | 82.17                 |

**Fig. 15.15** | Sample data for transaction file.

- Create class `FileMatch` to perform the file-matching functionality. The class should contain methods that read `oldmast.txt` and `trans.txt`. When a match occurs (i.e., records with the same account number appear in both the master file and the transaction file), add the dollar amount in the transaction record to the current balance in the mas-

ter record, and write the "newmast.txt" record. (Assume that purchases are indicated by positive amounts in the transaction file and payments by negative amounts.) When there's a master record for a particular account, but no corresponding transaction record, merely write the master record to "newmast.txt". When there's a transaction record, but no corresponding master record, print to a log file the message "Unmatched transaction record for account number..." (fill in the account number from the transaction record). The log file should be a text file named "log.txt".

**15.5 (File Matching with Multiple Transactions)** It's possible (and actually common) to have several transaction records with the same record key. This situation occurs, for example, when a customer makes several purchases and cash payments during a business period. Rewrite your accounts receivable file-matching program from Exercise 15.4 to provide for the possibility of handling several transaction records with the same record key. Modify the test data of `CreateData.java` to include the additional transaction records in Fig. 15.16.

| Account number | Dollar amount |
|----------------|---------------|
| 300            | 83.89         |
| 700            | 80.78         |
| 700            | 1.53          |

**Fig. 15.16** | Additional transaction records.

**15.6 (File Matching with Object Serialization)** Recreate your solution for Exercise 15.5 using object serialization. Use the statements from Exercise 15.3 as your basis for this program. You may want to create applications to read the data stored in the .ser files—the code in Section 15.5.2 can be modified for this purpose.

**15.7 (Telephone-Number Word Generator)** Standard telephone keypads contain the digits zero through nine. The numbers two through nine each have three letters associated with them (Fig. 15.17). Many people find it difficult to memorize phone numbers, so they use the correspondence between digits and letters to develop seven-letter words that correspond to their phone numbers. For example, a person whose telephone number is 686-2377 might use the correspondence indicated in Fig. 15.17 to develop the seven-letter word "NUMBERS." Every seven-letter word corresponds to exactly one seven-digit telephone number. A restaurant wishing to increase its takeout business could surely do so with the number 825-3688 (i.e., "TAKEOUT").

| Digit | Letters | Digit | Letters | Digit | Letters |
|-------|---------|-------|---------|-------|---------|
| 2     | A B C   | 5     | J K L   | 8     | T U V   |
| 3     | D E F   | 6     | M N O   | 9     | W X Y   |
| 4     | G H I   | 7     | P R S   |       |         |

**Fig. 15.17** | Telephone keypad digits and letters.

Every seven-letter phone number corresponds to many different seven-letter words, but most of these words represent unrecognizable juxtapositions of letters. It's possible, however, that the owner of a barbershop would be pleased to know that the shop's telephone number, 424-7288, corresponds to "HAIRCUT." A veterinarian with the phone number 738-2273 would be pleased to

know that the number corresponds to the letters “PETCARE.” An automotive dealership would be pleased to know that the dealership number, 639-2277, corresponds to “NEWCARS.”

Write a program that, given a seven-digit number, uses a `PrintStream` object to write to a file every possible seven-letter word combination corresponding to that number. There are 2,187 ( $3^7$ ) such combinations. Avoid phone numbers with the digits 0 and 1.

**15.8 (Student Poll)** Figure 6.8 contains an array of survey responses that’s hard coded into the program. Suppose we wish to process survey results that are stored in a file. This exercise requires two separate programs. First, create an application that prompts the user for survey responses and outputs each response to a file. Use a `Formatter` to create a file called `numbers.txt`. Each integer should be written using method `format`. Then modify the program in Fig. 6.8 to read the survey responses from `numbers.txt`. The responses should be read from the file by using a `Scanner`. Use method `nextInt` to input one integer at a time from the file. The program should continue to read responses until it reaches the end of the file. The results should be output to the text file “`output.txt`”.

**15.9 (Adding Object Serialization to the MyShape Drawing Application)** Modify Exercise 12.17 to allow the user to save a drawing into a file or load a prior drawing from a file using object serialization. Add buttons **Load** (to read objects from a file) and **Save** (to write objects to a file). Use an `ObjectOutputStream` to write to the file and an `ObjectInputStream` to read from the file. Write the array of `MyShape` objects using method `writeObject` (class `ObjectOutputStream`), and read the array using method `readObject` (`ObjectInputStream`). The object-serialization mechanism can read or write entire arrays—it’s not necessary to manipulate each element of the array of `MyShape` objects individually. It’s simply required that all the shapes be `Serializable`. For both the **Load** and **Save** buttons, use a `JFileChooser` to allow the user to select the file in which the shapes will be stored or from which they’ll be read. When the user first runs the program, no shapes should be displayed on the screen. The user can display shapes by opening a previously saved file or by drawing new shapes. Once there are shapes on the screen, users can save them to a file using the **Save** button.

## Making a Difference

**15.10 (Phishing Scanner)** Phishing is a form of identity theft in which, in an e-mail, a sender posing as a trustworthy source attempts to acquire private information, such as your user names, passwords, credit-card numbers and social security number. Phishing e-mails claiming to be from popular banks, credit-card companies, auction sites, social networks and online payment services may look quite legitimate. These fraudulent messages often provide links to spoofed (fake) websites where you’re asked to enter sensitive information.

Search online for phishing scams. Also check out the Anti-Phishing Working Group ([www.antiphishing.org](http://www.antiphishing.org)), and the FBI’s Cyber Investigations website ([www.fbi.gov/about-us/investigate/cyber/cyber](http://www.fbi.gov/about-us/investigate/cyber/cyber)), where you’ll find information about the latest scams and how to protect yourself.

Create a list of 30 words, phrases and company names commonly found in phishing messages. Assign a point value to each based on your estimate of its likeliness to be in a phishing message (e.g., one point if it’s somewhat likely, two points if moderately likely, or three points if highly likely). Write an application that scans a file of text for these terms and phrases. For each occurrence of a keyword or phrase within the text file, add the assigned point value to the total points for that word or phrase. For each keyword or phrase found, output one line with the word or phrase, the number of occurrences and the point total. Then show the point total for the entire message. Does your program assign a high point total to some actual phishing e-mails you’ve received? Does it assign a high point total to some legitimate e-mails you’ve received?

# 16

## Generic Collections

*I think this is the most extraordinary collection of talent, of human knowledge, that has ever been gathered together at the White House—with the possible exception of when Thomas Jefferson dined alone.*

—John F. Kennedy

### Objectives

In this chapter you'll:

- Learn what collections are.
- Use class `Arrays` for array manipulations.
- Learn the type-wrapper classes that enable programs to process primitive data values as objects.
- Use prebuilt generic data structures from the collections framework.
- Use iterators to “walk through” a collection.
- Use persistent hash tables manipulated with objects of class `Properties`.
- Learn about synchronization and modifiability wrappers.



|        |                                                                                                              |        |                                                                                |
|--------|--------------------------------------------------------------------------------------------------------------|--------|--------------------------------------------------------------------------------|
| 16.1   | Introduction                                                                                                 | 16.7.4 | Method <code>binarySearch</code>                                               |
| 16.2   | Collections Overview                                                                                         | 16.7.5 | Methods <code>addAll</code> , <code>frequency</code> and <code>disjoint</code> |
| 16.3   | Type-Wrapper Classes                                                                                         | 16.8   | Stack Class of Package <code>java.util</code>                                  |
| 16.4   | Autoboxing and Auto-Unboxing                                                                                 | 16.9   | Class <code>PriorityQueue</code> and Interface <code>Queue</code>              |
| 16.5   | Interface <code>Collection</code> and Class <code>Collections</code>                                         | 16.10  | Sets                                                                           |
| 16.6   | Lists                                                                                                        | 16.11  | Maps                                                                           |
| 16.6.1 | <code>ArrayList</code> and <code>Iterator</code>                                                             | 16.12  | <code>Properties</code> Class                                                  |
| 16.6.2 | <code>LinkedList</code>                                                                                      | 16.13  | Synchronized Collections                                                       |
| 16.7   | Collections Methods                                                                                          | 16.14  | Unmodifiable Collections                                                       |
| 16.7.1 | Method <code>sort</code>                                                                                     | 16.15  | Abstract Implementations                                                       |
| 16.7.2 | Method <code>shuffle</code>                                                                                  | 16.16  | Wrap-Up                                                                        |
| 16.7.3 | Methods <code>reverse</code> , <code>fill</code> , <code>copy</code> , <code>max</code> and <code>min</code> |        |                                                                                |

Summary | Self-Review Exercises | Answers to Self-Review Exercises | Exercises

## 16.1 Introduction

In Section 6.13, we introduced the generic `ArrayList` collection—a dynamically resizable array-like data structure that stores references to objects of a type that you specify when you create the `ArrayList`. In this chapter, we continue our discussion of the Java **collections framework**, which contains many other *prebuilt* generic data-structures.

Some examples of collections are your favorite songs stored on your smartphone or media player, your contacts list, the cards you hold in a card game, the members of your favorite sports team and the courses you take at once in school.

We discuss the collections-framework interfaces that declare the capabilities of each collection type, various classes that implement these interfaces, methods that process collection objects, and **iterators** that “walk through” collections.

### Java SE 8

After reading Chapter 17, Java SE 8 Lambdas and Streams, you’ll be able to reimplement many of Chapter 16’s examples in a more concise and elegant manner, and in a way that makes them easier to parallelize to improve performance on today’s multi-core systems. In Chapter 23, Concurrency, you’ll learn how to improve performance on multi-core systems using Java’s *concurrent collections* and *parallel stream* operations.

## 16.2 Collections Overview

A **collection** is a data structure—actually, an object—that can hold references to other objects. Usually, collections contain references to objects of any type that has the *is-a* relationship with the type stored in the collection. The collections-framework interfaces declare the operations to be performed generically on various types of collections. Figure 16.1 lists some of the collections framework interfaces. Several implementations of these interfaces are provided within the framework. You may also provide your own implementations.

| Interface         | Description                                                                                                                                           |
|-------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------|
| <b>Collection</b> | The root interface in the collections hierarchy from which interfaces <code>Set</code> , <code>Queue</code> and <code>List</code> are derived.        |
| <b>Set</b>        | A collection that does <i>not</i> contain duplicates.                                                                                                 |
| <b>List</b>       | An ordered collection that <i>can</i> contain duplicate elements.                                                                                     |
| <b>Map</b>        | A collection that associates keys to values and <i>cannot</i> contain duplicate keys. <code>Map</code> does not derive from <code>Collection</code> . |
| <b>Queue</b>      | Typically a <i>first-in, first-out</i> collection that models a <i>waiting line</i> ; other orders can be specified.                                  |

**Fig. 16.1** | Some collections-framework interfaces.

### Object-Based Collections

The collections framework classes and interfaces are members of package `java.util`. In early Java versions, the collections framework classes stored and manipulated *only* `Object` references, enabling you to store *any* object in a collection, because all classes directly or indirectly derive from class `Object`. Programs normally need to process *specific* types of objects. As a result, the `Object` references obtained from a collection need to be *downcast* to an appropriate type to allow the program to process the objects correctly. As we discussed in Chapter 10, downcasting generally should be avoided.

### Generic Collections

To eliminate this problem, the collections framework was enhanced with the *generics* capabilities that we introduced with generic `ArrayLists` in Chapter 6 and that we discuss in more detail in Chapter 20, Generic Classes and Methods. Generics enable you to specify the *exact type* that will be stored in a collection and give you the benefits of *compile-time type checking*—the compiler issues error messages if you use inappropriate types in your collections. Once you specify the type stored in a generic collection, any reference you retrieve from the collection will have that type. This eliminates the need for explicit type casts that can throw `ClassCastException`s if the referenced object is *not* of the appropriate type. In addition, the generic collections are *backward compatible* with Java code that was written before generics were introduced.



#### Good Programming Practice 16.1

*Avoid reinventing the wheel—rather than building your own data structures, use the interfaces and collections from the Java collections framework, which have been carefully tested and tuned to meet most application requirements.*

### Choosing a Collection

The documentation for each collection discusses its memory requirements and its methods' performance characteristics for operations such as adding and removing elements, searching for elements, sorting elements and more. Before choosing a collection, review the online documentation for the collection category you're considering (`Set`, `List`, `Map`, `Queue`, etc.), then choose the implementation that best meets your application's needs. Chapter 19, Searching, Sorting and Big O, discusses a means for describing how hard an

algorithm works to perform its task—based on the number of data items to be processed. After reading Chapter 19, you'll better understand each collection's performance characteristics as described in the online documentation.

## 16.3 Type-Wrapper Classes

Each primitive type (listed in Appendix D) has a corresponding **type-wrapper class** (in package `java.lang`). These classes are called **Boolean**, **Byte**, **Character**, **Double**, **Float**, **Integer**, **Long** and **Short**. These enable you to manipulate primitive-type values as objects. This is important because the data structures that we reuse or develop in Chapters 16–21 manipulate and share *objects*—they cannot manipulate variables of primitive types. However, they can manipulate objects of the type-wrapper classes, because every class ultimately derives from `Object`.

Each of the numeric type-wrapper classes—`Byte`, `Short`, `Integer`, `Long`, `Float` and `Double`—extends class `Number`. Also, the type-wrapper classes are `final` classes, so you cannot extend them. Primitive types do not have methods, so the methods related to a primitive type are located in the corresponding type-wrapper class (e.g., method `parseInt`, which converts a `String` to an `int` value, is located in class `Integer`).

## 16.4 Autoboxing and Auto-Unboxing

Java provides boxing and unboxing conversions that automatically convert between primitive-type values and type-wrapper objects. A **boxing conversion** converts a value of a primitive type to an object of the corresponding type-wrapper class. An **unboxing conversion** converts an object of a type-wrapper class to a value of the corresponding primitive type. These conversions are performed automatically—called **autoboxing** and **auto-unboxing**. Consider the following statements:

```
Integer[] integerArray = new Integer[5]; // create integerArray
integerArray[0] = 10; // assign Integer 10 to integerArray[0]
int value = integerArray[0]; // get int value of Integer
```

In this case, autoboxing occurs when assigning an `int` value (10) to `integerArray[0]`, because `integerArray` stores references to `Integer` objects, not `int` values. Auto-unboxing occurs when assigning `integerArray[0]` to `int` variable `value`, because variable `value` stores an `int` value, not a reference to an `Integer` object. Boxing conversions also occur in conditions, which can evaluate to primitive `boolean` values or `Boolean` objects. Many of the examples in Chapters 16–21 use these conversions to store primitive values in and retrieve them from data structures.

## 16.5 Interface Collection and Class Collections

Interface `Collection` contains **bulk operations** (i.e., operations performed on an *entire* collection) for operations such as *adding*, *clearing* and *comparing* objects (or elements) in a collection. A `Collection` can also be converted to an array. In addition, interface `Collection` provides a method that returns an **Iterator** object, which allows a program to walk through the collection and remove elements from it during the iteration. We discuss class `Iterator` in Section 16.6.1. Other methods of interface `Collection` enable a program to determine a collection's *size* and whether a collection is *empty*.



### Software Engineering Observation 16.1

*Collection is used commonly as a parameter type in methods to allow polymorphic processing of all objects that implement interface Collection.*



### Software Engineering Observation 16.2

*Most collection implementations provide a constructor that takes a Collection argument, thereby allowing a new collection to be constructed containing the elements of the specified collection.*

Class **Collections** provides static methods that *search*, *sort* and perform other operations on collections. Section 16.7 discusses more about **Collections** methods. We also cover **Collections**' **wrapper methods** that enable you to treat a collection as a *synchronized collection* (Section 16.13) or an *unmodifiable collection* (Section 16.14). Synchronized collections are for use with multithreading (discussed in Chapter 23), which enables programs to perform operations *in parallel*. When two or more threads of a program *share* a collection, problems might occur. As an analogy, consider a traffic intersection. If all cars were allowed to access the intersection at the same time, collisions might occur. For this reason, traffic lights are provided to control access to the intersection. Similarly, we can *synchronize* access to a collection to ensure that only *one* thread manipulates the collection at a time. The synchronization wrapper methods of class **Collections** return synchronized versions of collections that can be shared among threads in a program. Unmodifiable collections are useful when clients of a class need to *view* a collection's elements, but they should *not* be allowed to *modify* the collection by adding and removing elements.

## 16.6 Lists

A **List** (sometimes called a **sequence**) is an *ordered* **Collection** that can contain duplicate elements. Like array indices, **List** indices are zero based (i.e., the first element's index is zero). In addition to the methods inherited from **Collection**, **List** provides methods for manipulating elements via their indices, manipulating a specified range of elements, searching for elements and obtaining a **ListIterator** to access the elements.

Interface **List** is implemented by several classes, including **ArrayList**, **LinkedList** and **Vector**. Autoboxing occurs when you add primitive-type values to objects of these classes, because they store only references to objects. Classes **ArrayList** and **Vector** are resizable-array implementations of **List**. Inserting an element between existing elements of an **ArrayList** or **Vector** is an *inefficient* operation—all elements after the new one must be moved out of the way, which could be an expensive operation in a collection with a large number of elements. A **LinkedList** enables *efficient* insertion (or removal) of elements in the middle of a collection, but is much less efficient than an **ArrayList** for jumping to a specific element in the collection. We discuss the architecture of linked lists in Chapter 21.

**ArrayList** and **Vector** have nearly identical behaviors. Operations on **Vectors** are *synchronized* by default, whereas those on **ArrayLists** are not. Also, class **Vector** is from Java 1.0, before the collections framework was added to Java. As such, **Vector** has some methods that are not part of interface **List** and are not implemented in class **ArrayList**. For example, **Vector** methods **addElement** and **add** both append an element to a **Vector**, but only method **add** is specified in interface **List** and implemented by **ArrayList**. *Unsynchro-*



nized collections provide better performance than synchronized ones. For this reason, ArrayList is typically preferred over Vector in programs that do not share a collection among threads. Separately, the Java collections API provides *synchronization wrappers* (Section 16.13) that can be used to add synchronization to the unsynchronized collections, and several powerful synchronized collections are available in the Java concurrency APIs.



### Performance Tip 16.1

*ArrayLists behave like Vectors without synchronization and therefore execute faster than Vectors, because ArrayLists do not have the overhead of thread synchronization.*



### Software Engineering Observation 16.3

*LinkedLists can be used to create stacks, queues and dequeues (double-ended queues, pronounced “decks”). The collections framework provides implementations of some of these data structures.*

The following three subsections demonstrate the List and Collection capabilities. Section 16.6.1 removes elements from an ArrayList with an Iterator. Section 16.6.2 uses ListIterator and several List- and LinkedList-specific methods.

## 16.6.1 ArrayList and Iterator

Figure 16.2 uses an ArrayList (introduced in Section 6.13) to demonstrate several capabilities of interface Collection. The program places two Color arrays in ArrayLists and uses an Iterator to remove elements in the second ArrayList collection from the first.

---

```

1 // Fig. 16.2: CollectionTest.java
2 // Collection interface demonstrated via an ArrayList object.
3 import java.util.List;
4 import java.util.ArrayList;
5 import java.util.Collection;
6 import java.util.Iterator;
7
8 public class CollectionTest
9 {
10 public static void main(String[] args)
11 {
12 // add elements in colors array to list
13 String[] colors = {"MAGENTA", "RED", "WHITE", "BLUE", "CYAN"};
14 List<String> list = new ArrayList<String>();
15
16 for (String color : colors)
17 list.add(color); // adds color to end of list
18
19 // add elements in removeColors array to removeList
20 String[] removeColors = {"RED", "WHITE", "BLUE"};
21 List<String> removeList = new ArrayList<String>();
22
23 for (String color : removeColors)
24 removeList.add(color);
25

```

---

**Fig. 16.2** | Collection interface demonstrated via an ArrayList object. (Part 1 of 2.)

```

26 // output list contents
27 System.out.println("ArrayList: ");
28
29 for (int count = 0; count < list.size(); count++)
30 System.out.printf("%s ", list.get(count));
31
32 // remove from list the colors contained in removeList
33 removeColors(list, removeList);
34
35 // output list contents
36 System.out.printf("%n\nArrayList after calling removeColors:%n");
37
38 for (String color : list)
39 System.out.printf("%s ", color);
40 }
41
42 // remove colors specified in collection2 from collection1
43 private static void removeColors(Collection<String> collection1,
44 Collection<String> collection2)
45 {
46 // get iterator
47 Iterator<String> iterator = collection1.iterator();
48
49 // loop while collection has items
50 while (iterator.hasNext())
51 {
52 if (collection2.contains(iterator.next()))
53 iterator.remove(); // remove current element
54 }
55 }
56 } // end class CollectionTest

```

```

ArrayList:
MAGENTA RED WHITE BLUE CYAN

```

```

ArrayList after calling removeColors:
MAGENTA CYAN

```

**Fig. 16.2** | Collection interface demonstrated via an ArrayList object. (Part 2 of 2.)

Lines 13 and 20 declare and initialize String arrays `colors` and `removeColors`. Lines 14 and 21 create `ArrayList<String>` objects and assign their references to `List<String>` variables `list` and `removeList`, respectively. Recall that `ArrayList` is a *generic* class, so we can specify a *type argument* (`String` in this case) to indicate the type of the elements in each list. Because you specify the type to store in a collection at compile time, generic collections provide compile-time *type safety* that allows the compiler to catch attempts to use invalid types. For example, you cannot store `Employees` in a collection of `Strings`.

Lines 16–17 populate `list` with Strings stored in array `colors`, and lines 23–24 populate `removeList` with Strings stored in array `removeColors` using **List method** `add`. Lines 29–30 output each element of `list`. Line 29 calls **List method** `size` to get the number of elements in the `ArrayList`. Line 30 uses **List method** `get` to retrieve indi-

vidual element values. Lines 29–30 also could have used the enhanced for statement (which we’ll demonstrate with collections in other examples).

Line 33 calls method `removeColors` (lines 43–55), passing `list` and `removeList` as arguments. Method `removeColors` deletes the Strings in `removeList` from the Strings in `list`. Lines 38–39 print `list`’s elements after `removeColors` completes its task.

Method `removeColors` declares two `Collection<String>` parameters (lines 43–44)—any two Collections containing Strings can be passed as arguments. The method accesses the elements of the first Collection (`collection1`) via an Iterator. Line 47 calls **Collection method iterator** to get an Iterator for the Collection. Interfaces `Collection` and `Iterator` are generic types. The loop-continuation condition (line 50) calls **Iterator method hasNext** to determine whether there are more elements to iterate through. Method `hasNext` returns true if another element exists and false otherwise.

The if condition in line 52 calls **Iterator method next** to obtain a reference to the next element, then uses method `contains` of the second Collection (`collection2`) to determine whether `collection2` contains the element returned by `next`. If so, line 53 calls **Iterator method remove** to remove the element from the Collection `collection1`.



### Common Programming Error 16.1

*If a collection is modified by one of its methods after an iterator is created for that collection, the iterator immediately becomes invalid—any operation performed with the iterator fails immediately and throws a `ConcurrentModificationException`. For this reason, iterators are said to be “fail fast.” Fail-fast iterators help ensure that a modifiable collection is not manipulated by two or more threads at the same time, which could corrupt the collection. In Chapter 23, *Concurrency*, you’ll learn about concurrent collections (package `java.util.concurrent`) that can be safely manipulated by multiple concurrent threads.*



### Software Engineering Observation 16.4

*We refer to the ArrayLists in this example via `List` variables. This makes our code more flexible and easier to modify—if we later determine that `LinkedLists` would be more appropriate, only the lines where we created the ArrayList objects (lines 14 and 21) need to be modified. In general, when you create a collection object, refer to that object with a variable of the corresponding collection interface type.*

### Type Inference with the <> Notation

Lines 14 and 21 specify the type stored in the ArrayList (that is, `String`) on the left and right sides of the initialization statements. Java SE 7 introduced *type inferencing* with the <> notation—known as the **diamond notation**—in statements that declare and create generic type variables and objects. For example, line 14 can be written as:

```
List<String> list = new ArrayList<>();
```

In this case, Java uses the type in angle brackets on the left of the declaration (that is, `String`) as the type stored in the ArrayList created on the right side of the declaration. We’ll use this syntax for the remaining examples in this chapter.

## 16.6.2 LinkedList

Figure 16.3 demonstrates various operations on `LinkedLists`. The program creates two `LinkedLists` of Strings. The elements of one List are added to the other. Then all the Strings are converted to uppercase, and a range of elements is deleted.

---

```

1 // Fig. 16.3: ListTest.java
2 // Lists, LinkedLists and ListIterators.
3 import java.util.List;
4 import java.util.LinkedList;
5 import java.util.ListIterator;
6
7 public class ListTest
8 {
9 public static void main(String[] args)
10 {
11 // add colors elements to list1
12 String[] colors =
13 {"black", "yellow", "green", "blue", "violet", "silver"};
14 List<String> list1 = new LinkedList<>();
15
16 for (String color : colors)
17 list1.add(color);
18
19 // add colors2 elements to list2
20 String[] colors2 =
21 {"gold", "white", "brown", "blue", "gray", "silver"};
22 List<String> list2 = new LinkedList<>();
23
24 for (String color : colors2)
25 list2.add(color);
26
27 list1.addAll(list2); // concatenate lists
28 list2 = null; // release resources
29 printList(list1); // print list1 elements
30
31 convertToUppercaseStrings(list1); // convert to uppercase string
32 printList(list1); // print list1 elements
33
34 System.out.printf("%nDeleting elements 4 to 6...");
35 removeItems(list1, 4, 7); // remove items 4-6 from list
36 printList(list1); // print list1 elements
37 printReversedList(list1); // print list in reverse order
38 }
39
40 // output List contents
41 private static void printList(List<String> list)
42 {
43 System.out.printf("%nlist:%n");
44
45 for (String color : list)
46 System.out.printf("%s ", color);
47
48 System.out.println();
49 }
50
51 // locate String objects and convert to uppercase
52 private static void convertToUppercaseStrings(List<String> list)
53 {

```

---

**Fig. 16.3** | Lists, LinkedLists and ListIterators. (Part I of 2.)

```

54 ListIterator<String> iterator = list.listIterator();
55
56 while (iterator.hasNext())
57 {
58 String color = iterator.next(); // get item
59 iterator.set(color.toUpperCase()); // convert to upper case
60 }
61 }
62
63 // obtain sublist and use clear method to delete sublist items
64 private static void removeItems(List<String> list,
65 int start, int end)
66 {
67 list.subList(start, end).clear(); // remove items
68 }
69
70 // print reversed list
71 private static void printReversedList(List<String> list)
72 {
73 ListIterator<String> iterator = list.listIterator(list.size());
74
75 System.out.printf("%nReversed List:%n");
76
77 // print list in reverse order
78 while (iterator.hasPrevious())
79 System.out.printf("%s ", iterator.previous());
80 }
81 } // end class ListTest

```

```

list:
black yellow green blue violet silver gold white brown blue gray silver

list:
BLACK YELLOW GREEN BLUE VIOLET SILVER GOLD WHITE BROWN BLUE GRAY SILVER

Deleting elements 4 to 6...
list:
BLACK YELLOW GREEN BLUE WHITE BROWN BLUE GRAY SILVER

Reversed List:
SILVER GRAY BLUE BROWN WHITE BLUE GREEN YELLOW BLACK

```

**Fig. 16.3** | Lists, LinkedLists and ListIterators. (Part 2 of 2.)

Lines 14 and 22 create `LinkedLists` `list1` and `list2` of type `String`. `LinkedList` is a generic class that has one type parameter for which we specify the type argument `String` in this example. Lines 16–17 and 24–25 call `List` method `add` to *append* elements from arrays `colors` and `colors2` to the *ends* of `list1` and `list2`, respectively.

Line 27 calls **List method `addAll`** to *append all elements* of `list2` to the end of `list1`. Line 28 sets `list2` to `null`, because `list2` is no longer needed. Line 29 calls method `printList` (lines 41–49) to output `list1`'s contents. Line 31 calls method `convertToUppercaseStrings` (lines 52–61) to convert each `String` element to uppercase, then line 32 calls `printList` again to display the modified `Strings`. Line 35 calls method

`removeItems` (lines 64–68) to remove the range of elements starting at index 4 up to, but not including, index 7 of the list. Line 37 calls method `printReversedList` (lines 71–80) to print the list in reverse order.

### **Method `convertToUppercaseStrings`**

Method `convertToUppercaseStrings` (lines 52–61) changes lowercase `String` elements in its `List` argument to uppercase `Strings`. Line 54 calls **List method `listIterator`** to get the List's **bidirectional iterator** (i.e., one that can traverse a List *backward* or *forward*). `ListIterator` is also a generic class. In this example, the `ListIterator` references `String` objects, because method `listIterator` is called on a List of `Strings`. Line 56 calls method `hasNext` to determine whether the List *contains another element*. Line 58 gets the next `String` in the List. Line 59 calls **String method `toUpperCase`** to get an uppercase version of the `String` and calls **ListIterator method `set`** to replace the current `String` to which iterator refers with the `String` returned by method `toUpperCase`. Like method `toUpperCase`, **String method `toLowerCase`** returns a lowercase version of the `String`.

### **Method `removeItems`**

Method `removeItems` (lines 64–68) *removes a range of items* from the list. Line 67 calls **List method `subList`** to obtain a portion of the List (called a **sublist**). This is called a **range-view method**, which enables the program to view a portion of the list. The sublist is simply a view into the List on which `subList` is called. Method `subList` takes as arguments the beginning and ending index for the sublist. The ending index is *not* part of the range of the sublist. In this example, line 35 passes 4 for the beginning index and 7 for the ending index to `subList`. The sublist returned is the set of elements with indices 4 through 6. Next, the program calls **List method `clear`** on the sublist to remove the elements of the sublist from the List. Any changes made to a sublist are also made to the original List.

### **Method `printReversedList`**

Method `printReversedList` (lines 71–80) prints the list backward. Line 73 calls List method `listIterator` with the starting position as an argument (in our case, the last element in the list) to get a *bidirectional iterator* for the list. **List method `size`** returns the number of items in the List. The `while` condition (line 78) calls **ListIterator's `hasPrevious` method** to determine whether there are more elements while traversing the list *backward*. Line 79 calls **ListIterator's `previous` method** to get the previous element from the list and outputs it to the standard output stream.

### **Views into Collections and Arrays Method `asList`**

Class `Arrays` provides static method **`asList`** to *view* an array (sometimes called the **backing array**) as a **List** collection. A List view allows you to manipulate the array as if it were a list. This is useful for adding the elements in an array to a collection and for sorting array elements. The next example demonstrates how to create a `LinkedList` with a List view of an array, because we cannot pass the array to a `LinkedList` constructor. Sorting array elements with a List view is demonstrated in Fig. 16.7. Any modifications made through the List view change the array, and any modifications made to the array change the List view. The only operation permitted on the view returned by `asList` is *set*, which changes the value of the view and the backing array. Any other attempts to change the view (such as adding or removing elements) result in an **`UnsupportedOperationException`**.

*Viewing Arrays as Lists and Converting Lists to Arrays*

Figure 16.4 uses `Arrays` method `asList` to view an array as a `List` and uses `List` method `toArray` to get an array from a `LinkedList` collection. The program calls method `asList` to create a `List` view of an array, which is used to initialize a `LinkedList` object, then adds a series of `Strings` to the `LinkedList` and calls method `toArray` to obtain an array containing references to the `Strings`.

---

```

1 // Fig. 16.4: UsingToArray.java
2 // Viewing arrays as Lists and converting Lists to arrays.
3 import java.util.LinkedList;
4 import java.util.Arrays;
5
6 public class UsingToArray
7 {
8 // creates a LinkedList, adds elements and converts to array
9 public static void main(String[] args)
10 {
11 String[] colors = {"black", "blue", "yellow"};
12 LinkedList<String> links = new LinkedList<>(Arrays.asList(colors));
13
14 links.addLast("red"); // add as last item
15 links.add("pink"); // add to the end
16 links.add(3, "green"); // add at 3rd index
17 links.addFirst("cyan"); // add as first item
18
19 // get LinkedList elements as an array
20 colors = links.toArray(new String[links.size()]);
21
22 System.out.println("colors: ");
23
24 for (String color : colors)
25 System.out.println(color);
26 }
27 } // end class UsingToArray

```

```

colors:
cyan
black
blue
yellow
green
red
pink

```

**Fig. 16.4** | Viewing arrays as Lists and converting Lists to arrays.

Line 12 constructs a `LinkedList` of `Strings` containing the elements of array `colors`. `Arrays` method `asList` returns a `List` view of the array, then uses that to initialize the `LinkedList` with its constructor that receives a `Collection` as an argument (a `List` is a `Collection`). Line 14 calls `LinkedList` method `addLast` to add "red" to the end of `links`. Lines 15–16 call `LinkedList` method `add` to add "pink" as the last element and "green" as the element at index 3 (i.e., the fourth element). Method `addLast` (line 14) functions

identically to method `add` (line 15). Line 17 calls **LinkedList** method `addFirst` to add "cyan" as the new first item in the `LinkedList`. The add operations are permitted because they operate on the `LinkedList` object, not the view returned by `asList`. [Note: When "cyan" is added as the first element, "green" becomes the fifth element in the `LinkedList`.]

Line 20 calls the `List` interface's `toArray` method to get a `String` array from `links`. The array is a copy of the list's elements—modifying the array's contents does *not* modify the list. The array passed to method `toArray` is of the same type that you'd like method `toArray` to return. If the number of elements in that array is greater than or equal to the number of elements in the `LinkedList`, `toArray` copies the list's elements into its array argument and returns that array. If the `LinkedList` has more elements than the number of elements in the array passed to `toArray`, `toArray` *allocates a new array* of the same type it receives as an argument, *copies* the list's elements into the new array and returns the new array.



### Common Programming Error 16.2

*Passing an array that contains data to `toArray` can cause logic errors. If the number of elements in the array is smaller than the number of elements in the list on which `toArray` is called, a new array is allocated to store the list's elements—without preserving the array argument's elements. If the number of elements in the array is greater than the number of elements in the list, the elements of the array (starting at index zero) are overwritten with the list's elements. Array elements that are not overwritten retain their values.*

## 16.7 Collections Methods

Class `Collections` provides several high-performance algorithms for manipulating collection elements. The algorithms (Fig. 16.5) are implemented as static methods. The methods `sort`, `binarySearch`, `reverse`, `shuffle`, `fill` and `copy` operate on `Lists`. Methods `min`, `max`, `addAll`, `frequency` and `disjoint` operate on `Collections`.

| Method                    | Description                                                                                                                                                              |
|---------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>sort</code>         | Sorts the elements of a <code>List</code> .                                                                                                                              |
| <code>binarySearch</code> | Locates an object in a <code>List</code> , using the high-performance binary search algorithm which we introduced in Section 6.12 and discuss in detail in Section 19.4. |
| <code>reverse</code>      | Reverses the elements of a <code>List</code> .                                                                                                                           |
| <code>shuffle</code>      | Randomly orders a <code>List</code> 's elements.                                                                                                                         |
| <code>fill</code>         | Sets every <code>List</code> element to refer to a specified object.                                                                                                     |
| <code>copy</code>         | Copies references from one <code>List</code> into another.                                                                                                               |
| <code>min</code>          | Returns the smallest element in a <code>Collection</code> .                                                                                                              |
| <code>max</code>          | Returns the largest element in a <code>Collection</code> .                                                                                                               |
| <code>addAll</code>       | Appends all elements in an array to a <code>Collection</code> .                                                                                                          |
| <code>frequency</code>    | Calculates how many collection elements are equal to the specified element.                                                                                              |
| <code>disjoint</code>     | Determines whether two collections have no elements in common.                                                                                                           |

**Fig. 16.5** | Collections methods.





### Software Engineering Observation 16.5

*The collections framework methods are polymorphic. That is, each can operate on objects that implement specific interfaces, regardless of the underlying implementations.*

## 16.7.1 Method sort

**Method sort** sorts the elements of a `List`, which must implement the **Comparable** interface. The order is determined by the natural order of the elements' type as implemented by a `compareTo` method. For example, the natural order for numeric values is ascending order, and the natural order for `Strings` is based on their lexicographical ordering (Section 14.3). Method `compareTo` is declared in interface `Comparable` and is sometimes called the **natural comparison method**. The sort call may specify as a second argument a **Comparator** object that determines an alternative ordering of the elements.

### Sorting in Ascending Order

Figure 16.6 uses `Collections` method `sort` to order the elements of a `List` in *ascending* order (line 17). Method `sort` performs an iterative merge sort (we demonstrated a recursive merge sort in Section 19.8). Line 14 creates `list` as a `List` of `Strings`. Lines 15 and 18 each use an *implicit* call to the `list`'s `toString` method to output the list contents in the format shown in the output.

```

1 // Fig. 16.6: Sort1.java
2 // Collections method sort.
3 import java.util.List;
4 import java.util.Arrays;
5 import java.util.Collections;
6
7 public class Sort1
8 {
9 public static void main(String[] args)
10 {
11 String[] suits = {"Hearts", "Diamonds", "Clubs", "Spades"};
12
13 // Create and display a list containing the suits array elements
14 List<String> list = Arrays.asList(suits);
15 System.out.printf("Unsorted array elements: %s\n", list);
16
17 Collections.sort(list); // sort ArrayList
18 System.out.printf("Sorted array elements: %s\n", list);
19 }
20 } // end class Sort1

```

```

Unsorted array elements: [Hearts, Diamonds, Clubs, Spades]
Sorted array elements: [Clubs, Diamonds, Hearts, Spades]

```

**Fig. 16.6** | Collections method sort.

### Sorting in Descending Order

Figure 16.7 sorts the same list of strings used in Fig. 16.6 in *descending* order. The example introduces the `Comparator` interface, which is used for sorting a `Collection`'s elements in

a different order. Line 18 calls `Collections`'s method `sort` to order the `List` in descending order. The static `Collections` method `reverseOrder` returns a `Comparator` object that orders the collection's elements in reverse order.

---

```

1 // Fig. 16.7: Sort2.java
2 // Using a Comparator object with method sort.
3 import java.util.List;
4 import java.util.Arrays;
5 import java.util.Collections;
6
7 public class Sort2
8 {
9 public static void main(String[] args)
10 {
11 String[] suits = {"Hearts", "Diamonds", "Clubs", "Spades"};
12
13 // Create and display a list containing the suits array elements
14 List<String> list = Arrays.asList(suits); // create List
15 System.out.printf("Unsorted array elements: %s\n", list);
16
17 // sort in descending order using a comparator
18 Collections.sort(list, Collections.reverseOrder());
19 System.out.printf("Sorted list elements: %s\n", list);
20 }
21 } // end class Sort2

```

```

Unsorted array elements: [Hearts, Diamonds, Clubs, Spades]
Sorted list elements: [Spades, Hearts, Diamonds, Clubs]

```

**Fig. 16.7** | `Collections` method `sort` with a `Comparator` object.

### *Sorting with a Comparator*

Figure 16.8 creates a custom `Comparator` class, named `TimeComparator`, that implements interface `Comparator` to compare two `Time2` objects. Class `Time2`, declared in Fig. 8.5, represents times with hours, minutes and seconds.

---

```

1 // Fig. 16.8: TimeComparator.java
2 // Custom Comparator class that compares two Time2 objects.
3 import java.util.Comparator;
4
5 public class TimeComparator implements Comparator<Time2>
6 {
7 @Override
8 public int compare(Time2 time1, Time2 time2)
9 {
10 int hourDifference = time1.getHour() - time2.getHour();
11
12 if (hourDifference != 0) // test the hour first
13 return hourCompare;

```

**Fig. 16.8** | Custom `Comparator` class that compares two `Time2` objects. (Part I of 2.)

---

```

14
15 int minuteDifference = time1.getMinute() - time2.getMinute();
16
17 if (minuteDifference != 0) // then test the minute
18 return minuteDifference;
19
20 int secondDifference = time1.getSecond() - time2.getSecond();
21 return secondDifference;
22 }
23 } // end class TimeComparator

```

---

**Fig. 16.8** | Custom Comparator class that compares two Time2 objects. (Part 2 of 2.)

Class `TimeComparator` implements interface `Comparator`, a generic type that takes one type argument (in this case `Time2`). A class that implements `Comparator` must declare a `compare` method that receives two arguments and returns a *negative* integer if the first argument is *less than* the second, 0 if the arguments are *equal* or a *positive* integer if the first argument is *greater than* the second. Method `compare` (lines 7–22) performs comparisons between `Time2` objects. Line 10 calculates the difference between the hours of the two `Time2` objects. If the hours are different (line 12), then we return this value. If this value is *positive*, then the first hour is greater than the second and the first time is greater than the second. If this value is *negative*, then the first hour is less than the second and the first time is less than the second. If this value is zero, the hours are the same and we must test the minutes (and maybe the seconds) to determine which time is greater.

Figure 16.9 sorts a list using the custom `Comparator` class `TimeComparator`. Line 11 creates an `ArrayList` of `Time2` objects. Recall that both `ArrayList` and `List` are generic types and accept a type argument that specifies the element type of the collection. Lines 13–17 create five `Time2` objects and add them to this list. Line 23 calls method `sort`, passing it an object of our `TimeComparator` class (Fig. 16.8).

---

```

1 // Fig. 16.9: Sort3.java
2 // Collections method sort with a custom Comparator object.
3 import java.util.List;
4 import java.util.ArrayList;
5 import java.util.Collections;
6
7 public class Sort3
8 {
9 public static void main(String[] args)
10 {
11 List<Time2> list = new ArrayList<>(); // create List
12
13 list.add(new Time2(6, 24, 34));
14 list.add(new Time2(18, 14, 58));
15 list.add(new Time2(6, 05, 34));
16 list.add(new Time2(12, 14, 58));
17 list.add(new Time2(6, 24, 22));
18

```

---

**Fig. 16.9** | Collections method `sort` with a custom `Comparator` object. (Part 1 of 2.)

---

```

19 // output List elements
20 System.out.printf("Unsorted array elements:%n%s%n", list);
21
22 // sort in order using a comparator
23 Collections.sort(list, new TimeComparator());
24
25 // output List elements
26 System.out.printf("Sorted list elements:%n%s%n", list);
27 }
28 } // end class Sort3

```

```

Unsorted array elements:
[6:24:34 AM, 6:14:58 PM, 6:05:34 AM, 12:14:58 PM, 6:24:22 AM]
Sorted list elements:
[6:05:34 AM, 6:24:22 AM, 6:24:34 AM, 12:14:58 PM, 6:14:58 PM]

```

**Fig. 16.9** | Collections method sort with a custom Comparator object. (Part 2 of 2.)

### 16.7.2 Method shuffle

Method **shuffle** randomly orders a List's elements. Chapter 6 presented a card shuffling and dealing simulation that shuffled a deck of cards with a loop. Figure 16.10 uses method **shuffle** to shuffle a deck of Card objects that might be used in a card-game simulator.

---

```

1 // Fig. 16.10: DeckOfCards.java
2 // Card shuffling and dealing with Collections method shuffle.
3 import java.util.List;
4 import java.util.Arrays;
5 import java.util.Collections;
6
7 // class to represent a Card in a deck of cards
8 class Card
9 {
10 public static enum Face {Ace, Deuce, Three, Four, Five, Six,
11 Seven, Eight, Nine, Ten, Jack, Queen, King };
12 public static enum Suit {Clubs, Diamonds, Hearts, Spades};
13
14 private final Face face;
15 private final Suit suit;
16
17 // constructor
18 public Card(Face face, Suit suit)
19 {
20 this.face = face;
21 this.suit = suit;
22 }
23
24 // return face of the card
25 public Face getFace()
26 {

```

**Fig. 16.10** | Card shuffling and dealing with Collections method shuffle. (Part 1 of 3.)

---

```

27 return face;
28 }
29
30 // return suit of Card
31 public Suit getSuit()
32 {
33 return suit;
34 }
35
36 // return String representation of Card
37 public String toString()
38 {
39 return String.format("%s of %s", face, suit);
40 }
41 } // end class Card
42
43 // class DeckOfCards declaration
44 public class DeckOfCards
45 {
46 private List<Card> list; // declare List that will store Cards
47
48 // set up deck of Cards and shuffle
49 public DeckOfCards()
50 {
51 Card[] deck = new Card[52];
52 int count = 0; // number of cards
53
54 // populate deck with Card objects
55 for (Card.Suit suit: Card.Suit.values())
56 {
57 for (Card.Face face: Card.Face.values())
58 {
59 deck[count] = new Card(face, suit);
60 ++count;
61 }
62 }
63
64 list = Arrays.asList(deck); // get List
65 Collections.shuffle(list); // shuffle deck
66 } // end DeckOfCards constructor
67
68 // output deck
69 public void printCards()
70 {
71 // display 52 cards in two columns
72 for (int i = 0; i < list.size(); i++)
73 System.out.printf("%-19s%s", list.get(i),
74 ((i + 1) % 4 == 0) ? "%n" : "");
75 }
76
77 public static void main(String[] args)
78 {

```

---

**Fig. 16.10** | Card shuffling and dealing with Collections method `shuffle`. (Part 2 of 3.)

```

79 DeckOfCards cards = new DeckOfCards();
80 cards.printCards();
81 }
82 } // end class DeckOfCards

```

|                   |                  |                   |                  |
|-------------------|------------------|-------------------|------------------|
| Deuce of Clubs    | Six of Spades    | Nine of Diamonds  | Ten of Hearts    |
| Three of Diamonds | Five of Clubs    | Deuce of Diamonds | Seven of Clubs   |
| Three of Spades   | Six of Diamonds  | King of Clubs     | Jack of Hearts   |
| Ten of Spades     | King of Diamonds | Eight of Spades   | Six of Hearts    |
| Nine of Clubs     | Ten of Diamonds  | Eight of Diamonds | Eight of Hearts  |
| Ten of Clubs      | Five of Hearts   | Ace of Clubs      | Deuce of Hearts  |
| Queen of Diamonds | Ace of Diamonds  | Four of Clubs     | Nine of Hearts   |
| Ace of Spades     | Deuce of Spades  | Ace of Hearts     | Jack of Diamonds |
| Seven of Diamonds | Three of Hearts  | Four of Spades    | Four of Diamonds |
| Seven of Spades   | King of Hearts   | Seven of Hearts   | Five of Diamonds |
| Eight of Clubs    | Three of Clubs   | Queen of Clubs    | Queen of Spades  |
| Six of Clubs      | Nine of Spades   | Four of Hearts    | Jack of Clubs    |
| Five of Spades    | King of Spades   | Jack of Spades    | Queen of Hearts  |

**Fig. 16.10** | Card shuffling and dealing with `Collections` method `shuffle`. (Part 3 of 3.)

Class `Card` (lines 8–41) represents a card in a deck of cards. Each `Card` has a face and a suit. Lines 10–12 declare two enum types—`Face` and `Suit`—which represent the face and the suit of the card, respectively. Method `toString` (lines 37–40) returns a `String` containing the face and suit of the `Card` separated by the string " of ". When an enum constant is converted to a `String`, the constant's identifier is used as the `String` representation. Normally we would use all uppercase letters for enum constants. In this example, we chose to use capital letters for only the first letter of each enum constant because we want the card to be displayed with initial capital letters for the face and the suit (e.g., "Ace of Spades").

Lines 55–62 populate the deck array with cards that have unique face and suit combinations. Both `Face` and `Suit` are public static enum types of class `Card`. To use these enum types outside of class `Card`, you must qualify each enum's type name with the name of the class in which it resides (i.e., `Card`) and a dot (.) separator. Hence, lines 55 and 57 use `Card.Suit` and `Card.Face` to declare the control variables of the `for` statements. Recall that method values of an enum type returns an array that contains all the constants of the enum type. Lines 55–62 use enhanced `for` statements to construct 52 new `Cards`.

The shuffling occurs in line 65, which calls static method `shuffle` of class `Collections` to shuffle the elements of the array. Method `shuffle` requires a `List` argument, so we must obtain a `List` view of the array before we can shuffle it. Line 64 invokes static method `asList` of class `Arrays` to get a `List` view of the deck array.

Method `printCards` (lines 69–75) displays the deck of cards in four columns. In each iteration of the loop, lines 73–74 output a card left justified in a 19-character field followed by either a newline or an empty string based on the number of cards output so far. If the number of cards is divisible by 4, a newline is output; otherwise, the empty string is output.

### 16.7.3 Methods `reverse`, `fill`, `copy`, `max` and `min`

Class `Collections` provides methods for *reversing*, *filling* and *copying* `Lists`. **`Collections` method `reverse`** reverses the order of the elements in a `List`, and **`method fill`** *overwrites*

elements in a `List` with a specified value. The `fill` operation is useful for reinitializing a `List`. Method `copy` takes two arguments—a destination `List` and a source `List`. Each source `List` element is copied to the destination `List`. The destination `List` must be at least as long as the source `List`; otherwise, an `IndexOutOfBoundsException` occurs. If the destination `List` is longer, the elements not overwritten are unchanged.

Each method we've seen so far operates on `Lists`. Methods `min` and `max` each operate on any `Collection`. Method `min` returns the smallest element in a `Collection`, and method `max` returns the largest element in a `Collection`. Both of these methods can be called with a `Comparator` object as a second argument to perform *custom comparisons* of objects, such as the `TimeComparator` in Fig. 16.9. Figure 16.11 demonstrates methods `reverse`, `fill`, `copy`, `max` and `min`.

---

```

1 // Fig. 16.11: Algorithms1.java
2 // Collections methods reverse, fill, copy, max and min.
3 import java.util.List;
4 import java.util.Arrays;
5 import java.util.Collections;
6
7 public class Algorithms1
8 {
9 public static void main(String[] args)
10 {
11 // create and display a List<Character>
12 Character[] letters = {'P', 'C', 'M'};
13 List<Character> list = Arrays.asList(letters); // get List
14 System.out.println("list contains: ");
15 output(list);
16
17 // reverse and display the List<Character>
18 Collections.reverse(list); // reverse order the elements
19 System.out.printf("%nAfter calling reverse, list contains:%n");
20 output(list);
21
22 // create copyList from an array of 3 Characters
23 Character[] lettersCopy = new Character[3];
24 List<Character> copyList = Arrays.asList(lettersCopy);
25
26 // copy the contents of list into copyList
27 Collections.copy(copyList, list);
28 System.out.printf("%nAfter copying, copyList contains:%n");
29 output(copyList);
30
31 // fill list with Rs
32 Collections.fill(list, 'R');
33 System.out.printf("%nAfter calling fill, list contains:%n");
34 output(list);
35 }
36
37 // output List information
38 private static void output(List<Character> listRef)
39 {

```

---

**Fig. 16.11** | Collections methods `reverse`, `fill`, `copy`, `max` and `min`. (Part 1 of 2.)

```

40 System.out.print("The list is: ");
41
42 for (Character element : listRef)
43 System.out.printf("%s ", element);
44
45 System.out.printf("\nMax: %s", Collections.max(listRef));
46 System.out.printf(" Min: %s\n", Collections.min(listRef));
47 }
48 } // end class Algorithms1

```

```

list contains:
The list is: P C M
Max: P Min: C

After calling reverse, list contains:
The list is: M C P
Max: P Min: C

After copying, copyList contains:
The list is: M C P
Max: P Min: C

After calling fill, list contains:
The list is: R R R
Max: R Min: R

```

**Fig. 16.11** | Collections methods reverse, fill, copy, max and min. (Part 2 of 2.)

Line 13 creates `List<Character>` variable `list` and initializes it with a `List` view of the `Character` array `letters`. Lines 14–15 output the current contents of the `List`. Line 18 calls `Collections` method `reverse` to reverse the order of `list`. Method `reverse` takes one `List` argument. Since `list` is a `List` view of array `letters`, the array's elements are now in reverse order. The reversed contents are output in lines 19–20. Line 27 uses `Collections` method `copy` to copy `list`'s elements into `copyList`. Changes to `copyList` do not change `letters`, because `copyList` is a separate `List` that's not a `List` view of the array `letters`. Method `copy` requires two `List` arguments—the destination `List` and the source `List`. Line 32 calls `Collections` method `fill` to place the character 'R' in each `list` element. Because `list` is a `List` view of the array `letters`, this operation changes each element in `letters` to 'R'. Method `fill` requires a `List` for the first argument and an `Object` for the second argument—in this case, the `Object` is the *boxed* version of the character 'R'. Lines 45–46 call `Collections` methods `max` and `min` to find the largest and the smallest element of a `Collection`, respectively. Recall that interface `List` extends interface `Collection`, so a `List` *is a* `Collection`.

### 16.7.4 Method `binarySearch`

The high-speed binary search algorithm—which we discuss in detail in Section 19.4—is built into the Java collections framework as a static **`Collections` method `binarySearch`**. This method locates an object in a `List` (e.g., a `LinkedList` or an `ArrayList`). If the object is found, its index is returned. If the object is not found, `binarySearch` returns a negative



value. Method `binarySearch` determines this negative value by first calculating the insertion point and making its sign negative. Then, `binarySearch` subtracts 1 from the insertion point to obtain the return value, which guarantees that method `binarySearch` returns positive numbers ( $\geq 0$ ) if and only if the object is found. If multiple elements in the list match the search key, there's no guarantee which one will be located first. Figure 16.12 uses method `binarySearch` to search for a series of strings in an `ArrayList`.

---

```

1 // Fig. 16.12: BinarySearchTest.java
2 // Collections method binarySearch.
3 import java.util.List;
4 import java.util.Arrays;
5 import java.util.Collections;
6 import java.util.ArrayList;
7
8 public class BinarySearchTest
9 {
10 public static void main(String[] args)
11 {
12 // create an ArrayList<String> from the contents of colors array
13 String[] colors = {"red", "white", "blue", "black", "yellow",
14 "purple", "tan", "pink"};
15 List<String> list =
16 new ArrayList<>(Arrays.asList(colors));
17
18 Collections.sort(list); // sort the ArrayList
19 System.out.printf("Sorted ArrayList: %s\n", list);
20
21 // search list for various values
22 printSearchResults(list, "black"); // first item
23 printSearchResults(list, "red"); // middle item
24 printSearchResults(list, "pink"); // last item
25 printSearchResults(list, "aqua"); // below lowest
26 printSearchResults(list, "gray"); // does not exist
27 printSearchResults(list, "teal"); // does not exist
28 }
29
30 // perform search and display result
31 private static void printSearchResults(
32 List<String> list, String key)
33 {
34 int result = 0;
35
36 System.out.printf("\nSearching for: %s\n", key);
37 result = Collections.binarySearch(list, key);
38
39 if (result >= 0)
40 System.out.printf("Found at index %d\n", result);
41 else
42 System.out.printf("Not Found (%d)\n", result);
43 }
44 } // end class BinarySearchTest

```

---

**Fig. 16.12** | Collections method `binarySearch`. (Part I of 2.)

```
Sorted ArrayList: [black, blue, pink, purple, red, tan, white, yellow]
Searching for: black
Found at index 0

Searching for: red
Found at index 4

Searching for: pink
Found at index 2

Searching for: aqua
Not Found (-1)

Searching for: gray
Not Found (-3)

Searching for: teal
Not Found (-7)
```

**Fig. 16.12** | Collections method `binarySearch`. (Part 2 of 2.)

Lines 15–16 initialize `list` with an `ArrayList` containing a copy of the elements in array `colors`. Collections method `binarySearch` expects its `List` argument's elements to be sorted in *ascending* order, so line 18 uses Collections method `sort` to sort the list. If the `List` argument's elements are *not* sorted, the result of using `binarySearch` is *undefined*. Line 19 outputs the sorted list. Lines 22–27 call method `printSearchResults` (lines 31–43) to perform searches and output the results. Line 37 calls Collections method `binarySearch` to search `list` for the specified key. Method `binarySearch` takes a `List` as the first argument and an `Object` as the second argument. Lines 39–42 output the results of the search. An overloaded version of `binarySearch` takes a `Comparator` object as its third argument, which specifies how `binarySearch` should compare the search key to the `List`'s elements.

### 16.7.5 Methods `addAll`, `frequency` and `disjoint`

Class Collections also provides the methods `addAll`, `frequency` and `disjoint`. **Collections method `addAll`** takes two arguments—a Collection into which to *insert* the new element(s) and an array that provides elements to be inserted. **Collections method `frequency`** takes two arguments—a Collection to be searched and an `Object` to be searched for in the collection. Method `frequency` returns the number of times that the second argument appears in the collection. **Collections method `disjoint`** takes two Collections and returns `true` if they have *no elements in common*. Figure 16.13 demonstrates the use of methods `addAll`, `frequency` and `disjoint`.

---

```
1 // Fig. Fig. 16.13: Algorithms2.java
2 // Collections methods addAll, frequency and disjoint.
3 import java.util.ArrayList;
4 import java.util.List;
5 import java.util.Arrays;
6 import java.util.Collections;
```

---

**Fig. 16.13** | Collections methods `addAll`, `frequency` and `disjoint`. (Part 1 of 2.)

```

7
8 public class Algorithms2
9 {
10 public static void main(String[] args)
11 {
12 // initialize list1 and list2
13 String[] colors = {"red", "white", "yellow", "blue"};
14 List<String> list1 = Arrays.asList(colors);
15 ArrayList<String> list2 = new ArrayList<>();
16
17 list2.add("black"); // add "black" to the end of list2
18 list2.add("red"); // add "red" to the end of list2
19 list2.add("green"); // add "green" to the end of list2
20
21 System.out.print("Before addAll, list2 contains: ");
22
23 // display elements in list2
24 for (String s : list2)
25 System.out.printf("%s ", s);
26
27 Collections.addAll(list2, colors); // add colors Strings to list2
28
29 System.out.printf("\nAfter addAll, list2 contains: ");
30
31 // display elements in list2
32 for (String s : list2)
33 System.out.printf("%s ", s);
34
35 // get frequency of "red"
36 int frequency = Collections.frequency(list2, "red");
37 System.out.printf(
38 "\nFrequency of red in list2: %d\n", frequency);
39
40 // check whether list1 and list2 have elements in common
41 boolean disjoint = Collections.disjoint(list1, list2);
42
43 System.out.printf("list1 and list2 %s elements in common\n",
44 (disjoint ? "do not have" : "have"));
45 }
46 } // end class Algorithms2

```

```

Before addAll, list2 contains: black red green
After addAll, list2 contains: black red green red white yellow blue
Frequency of red in list2: 2
list1 and list2 have elements in common

```

**Fig. 16.13** | Collections methods addAll, frequency and disjoint. (Part 2 of 2.)

Line 14 initializes list1 with elements in array colors, and lines 17–19 add Strings "black", "red" and "green" to list2. Line 27 invokes method addAll to add elements in array colors to list2. Line 36 gets the frequency of String "red" in list2 using method frequency. Line 41 invokes method disjoint to test whether Collections list1 and list2 have elements in common, which they do in this example.

## 16.8 Stack Class of Package `java.util`

We introduced the concept of a *stack* in Section 5.6 when we discussed the method-call stack. In Chapter 21, Custom Generic Data Structures, we'll learn how to build data structures, including *linked lists*, *stacks*, *queues* and *trees*. In a world of software reuse, rather than building data structures as we need them, we can often take advantage of existing data structures. In this section, we investigate class **Stack** in the Java utilities package (`java.util`).

Class **Stack** extends class **Vector** to implement a stack data structure. Figure 16.14 demonstrates several **Stack** methods. For the details of class **Stack**, visit <http://docs.oracle.com/javase/7/docs/api/java/util/Stack.html>.

---

```

1 // Fig. 16.14: StackTest.java
2 // Stack class of package java.util.
3 import java.util.Stack;
4 import java.util.EmptyStackException;
5
6 public class StackTest
7 {
8 public static void main(String[] args)
9 {
10 Stack<Number> stack = new Stack<>(); // create a Stack
11
12 // use push method
13 stack.push(12L); // push long value 12L
14 System.out.println("Pushed 12L");
15 printStack(stack);
16 stack.push(34567); // push int value 34567
17 System.out.println("Pushed 34567");
18 printStack(stack);
19 stack.push(1.0F); // push float value 1.0F
20 System.out.println("Pushed 1.0F");
21 printStack(stack);
22 stack.push(1234.5678); // push double value 1234.5678
23 System.out.println("Pushed 1234.5678 ");
24 printStack(stack);
25
26 // remove items from stack
27 try
28 {
29 Number removedObject = null;
30
31 // pop elements from stack
32 while (true)
33 {
34 removedObject = stack.pop(); // use pop method
35 System.out.printf("Popped %s\n", removedObject);
36 printStack(stack);
37 }
38 }
39 catch (EmptyStackException emptyStackException)
40 {

```

---

**Fig. 16.14** | Stack class of package `java.util`. (Part 1 of 2.)

```

41 emptyStackException.printStackTrace();
42 }
43 }
44
45 // display Stack contents
46 private static void printStack(Stack<Number> stack)
47 {
48 if (stack.isEmpty())
49 System.out.printf("stack is empty%n%n"); // the stack is empty
50 else // stack is not empty
51 System.out.printf("stack contains: %s (top)%n", stack);
52 }
53 } // end class StackTest

```

```

Pushed 12L
stack contains: [12] (top)
Pushed 34567
stack contains: [12, 34567] (top)
Pushed 1.0F
stack contains: [12, 34567, 1.0] (top)
Pushed 1234.5678
stack contains: [12, 34567, 1.0, 1234.5678] (top)
Popped 1234.5678
stack contains: [12, 34567, 1.0] (top)
Popped 1.0
stack contains: [12, 34567] (top)
Popped 34567
stack contains: [12] (top)
Popped 12
stack is empty

java.util.EmptyStackException
 at java.util.Stack.peek(Unknown Source)
 at java.util.Stack.pop(Unknown Source)
 at StackTest.main(StackTest.java:34)

```

**Fig. 16.14** | Stack class of package java.util. (Part 2 of 2.)



### Error-Prevention Tip 16.1

*Because Stack extends Vector, all public Vector methods can be called on Stack objects, even if the methods do not represent conventional stack operations. For example, Vector method add can be used to insert an element anywhere in a stack—an operation that could “corrupt” the stack. When manipulating a Stack, only methods push and pop should be used to add elements to and remove elements from the Stack, respectively. In Section 21.5, we create a Stack class using composition so that the Stack provides in its public interface only the capabilities that should be allowed by a Stack.*

Line 10 creates an empty Stack of Numbers. Class Number (in package java.lang) is the superclass of the type-wrapper classes for the primitive numeric types (e.g., Integer, Double). By creating a Stack of Numbers, objects of any class that extends Number can be pushed onto the Stack. Lines 13, 16, 19 and 22 each call Stack method **push** to add a Number object to the *top* of the stack. Note the literals 12L (line 13) and 1.0F (line 19). Any integer literal that has the **suffix L** is a long value. An integer literal without a suffix

is an `int` value. Similarly, any floating-point literal that has the suffix `F` is a `float` value. A floating-point literal without a suffix is a `double` value. You can learn more about numeric literals in the *Java Language Specification* at <http://docs.oracle.com/javase/7/specs/jls/se7/html/jls-15.html#jls-15.8.1>.

An infinite loop (lines 32–37) calls **Stack method pop** to remove the *top* element of the stack. The method returns a `Number` reference to the removed element. If there are no elements in the `Stack`, method `pop` throws an **EmptyStackException**, which terminates the loop. Class `Stack` also declares **method peek**. This method returns the *top* element of the stack *without* popping the element off the stack.

Method `printStack` (lines 46–52) displays the stack's contents. The current *top* of the stack (the last value pushed onto the stack) is the *first* value printed. Line 48 calls **Stack method isEmpty** (inherited by `Stack` from class `Vector`) to determine whether the stack is empty. If it's empty, the method returns `true`; otherwise, `false`.

## 16.9 Class `PriorityQueue` and Interface `Queue`

Recall that a queue is a collection that represents a waiting line—typically, *insertions* are made at the back of a queue and *deletions* are made from the front. In Section 21.6, we'll discuss and implement a queue data structure. In this section, we investigate Java's **Queue** interface and **PriorityQueue** class from package `java.util`. Interface `Queue` extends interface `Collection` and provides additional operations for *inserting*, *removing* and *inspecting* elements in a queue. `PriorityQueue`, which implements the `Queue` interface, orders elements by their natural ordering as specified by `Comparable` elements' `compareTo` method or by a `Comparator` object that's supplied to the constructor.

Class `PriorityQueue` provides functionality that enables *insertions in sorted order* into the underlying data structure and *deletions from the front* of the underlying data structure. When adding elements to a `PriorityQueue`, the elements are inserted in priority order such that the *highest-priority element* (i.e., the largest value) will be the first element removed from the `PriorityQueue`.

The common `PriorityQueue` operations are **offer** to *insert* an element at the appropriate location based on priority order, **poll** to *remove* the highest-priority element of the priority queue (i.e., the head of the queue), **peek** to get a reference to the highest-priority element of the priority queue (without removing that element), **clear** to *remove all elements* in the priority queue and **size** to get the number of elements in the priority queue.

Figure 16.15 demonstrates the `PriorityQueue` class. Line 10 creates a `PriorityQueue` that stores `Doubles` with an *initial capacity* of 11 elements and orders the elements according to the object's natural ordering (the defaults for a `PriorityQueue`). `PriorityQueue` is a generic class. Line 10 instantiates a `PriorityQueue` with a type argument `Double`. Class `PriorityQueue` provides five additional constructors. One of these takes an `int` and a `Comparator` object to create a `PriorityQueue` with the *initial capacity* specified by the `int` and the *ordering* by the `Comparator`. Lines 13–15 use method `offer` to add elements to the priority queue. Method `offer` throws a `NullPointerException` if the program attempts to add a `null` object to the queue. The loop in lines 20–24 uses method `size` to determine whether the priority queue is *empty* (line 20). While there are more elements, line 22 uses `PriorityQueue` method `peek` to retrieve the *highest-priority element* in the queue for output (*without* actually removing it from the queue). Line 23 removes the highest-priority element in the queue with method `poll`, which returns the removed element.

---

```

1 // Fig. 16.15: PriorityQueueTest.java
2 // PriorityQueue test program.
3 import java.util.PriorityQueue;
4
5 public class PriorityQueueTest
6 {
7 public static void main(String[] args)
8 {
9 // queue of capacity 11
10 PriorityQueue<Double> queue = new PriorityQueue<>();
11
12 // insert elements to queue
13 queue.offer(3.2);
14 queue.offer(9.8);
15 queue.offer(5.4);
16
17 System.out.print("Polling from queue: ");
18
19 // display elements in queue
20 while (queue.size() > 0)
21 {
22 System.out.printf("%.1f ", queue.peek()); // view top element
23 queue.poll(); // remove top element
24 }
25 }
26 } // end class PriorityQueueTest

```

Polling from queue: 3.2 5.4 9.8

**Fig. 16.15** | PriorityQueue test program.

## 16.10 Sets

A **Set** is an *unordered* Collection of unique elements (i.e., *no duplicates*). The collections framework contains several Set implementations, including **HashSet** and **TreeSet**. HashSet stores its elements in a *hash table*, and TreeSet stores its elements in a *tree*. Hash tables are presented in Section 16.11. Trees are discussed in Section 21.7.

Figure 16.16 uses a HashSet to *remove duplicate strings* from a List. Recall that both List and Collection are generic types, so line 16 creates a List that contains String objects, and line 20 passes a Collection of Strings to method printNonDuplicates. Method printNonDuplicates (lines 24–35) takes a Collection argument. Line 27 constructs a HashSet<String> from the Collection<String> argument. By definition, Sets do *not* contain duplicates, so when the HashSet is constructed, it *removes any duplicates* in the Collection. Lines 31–32 output elements in the Set.

---

```

1 // Fig. 16.16: SetTest.java
2 // HashSet used to remove duplicate values from array of strings.
3 import java.util.List;
4 import java.util.Arrays;

```

---

**Fig. 16.16** | HashSet used to remove duplicate values from an array of strings. (Part I of 2.)

```

5 import java.util.HashSet;
6 import java.util.Set;
7 import java.util.Collection;
8
9 public class SetTest
10 {
11 public static void main(String[] args)
12 {
13 // create and display a List<String>
14 String[] colors = {"red", "white", "blue", "green", "gray",
15 "orange", "tan", "white", "cyan", "peach", "gray", "orange"};
16 List<String> list = Arrays.asList(colors);
17 System.out.printf("List: %s\n", list);
18
19 // eliminate duplicates then print the unique values
20 printNonDuplications(list);
21 }
22
23 // create a Set from a Collection to eliminate duplicates
24 private static void printNonDuplications(Collection<String> values)
25 {
26 // create a HashSet
27 Set<String> set = new HashSet<>(values);
28
29 System.out.printf("%nNonduplications are: ");
30
31 for (String value : set)
32 System.out.printf("%s ", value);
33
34 System.out.println();
35 }
36 } // end class SetTest

```

List: [red, white, blue, green, gray, orange, tan, white, cyan, peach, gray, orange]

Nonduplications are: orange green white peach gray cyan red blue tan

**Fig. 16.16** | HashSet used to remove duplicate values from an array of strings. (Part 2 of 2.)

### Sorted Sets

The collections framework also includes the **SortedSet** interface (which extends **Set**) for sets that maintain their elements in *sorted* order—either the *elements' natural order* (e.g., numbers are in *ascending* order) or an order specified by a **Comparator**. Class **TreeSet** implements **SortedSet**. The program in Fig. 16.17 places Strings into a **TreeSet**. The Strings are sorted as they're added to the **TreeSet**. This example also demonstrates *range-view* methods, which enable a program to view a portion of a collection.

Line 14 creates a **TreeSet<String>** that contains the elements of array **colors**, then assigns the new **TreeSet<String>** to **SortedSet<String>** variable **tree**. Line 17 outputs the initial set of strings using method **printSet** (lines 33–39), which we discuss momentarily. Line 31 calls **TreeSet** method **headSet** to get a subset of the **TreeSet** in which every



element is less than "orange". The view returned from `headSet` is then output with `printSet`. If any changes are made to the subset, they'll *also* be made to the original `TreeSet`, because the subset returned by `headSet` is a view of the `TreeSet`.

Line 25 calls **TreeSet method tailSet** to get a subset in which each element is greater than or equal to "orange", then outputs the result. Any changes made through the `tailSet` view are made to the original `TreeSet`. Lines 28–29 call **SortedSet methods first** and **last** to get the smallest and largest elements of the set, respectively.

Method `printSet` (lines 33–39) accepts a `SortedSet` as an argument and prints it. Lines 35–36 print each element of the `SortedSet` using the enhanced for statement.

---

```

1 // Fig. 16.17: SortedSetTest.java
2 // Using SortedSets and TreeSets.
3 import java.util.Arrays;
4 import java.util.SortedSet;
5 import java.util.TreeSet;
6
7 public class SortedSetTest
8 {
9 public static void main(String[] args)
10 {
11 // create TreeSet from array colors
12 String[] colors = {"yellow", "green", "black", "tan", "grey",
13 "white", "orange", "red", "green"};
14 SortedSet<String> tree = new TreeSet<>(Arrays.asList(colors));
15
16 System.out.print("sorted set: ");
17 printSet(tree);
18
19 // get headSet based on "orange"
20 System.out.print("headSet (\"orange\"): ");
21 printSet(tree.headSet("orange"));
22
23 // get tailSet based upon "orange"
24 System.out.print("tailSet (\"orange\"): ");
25 printSet(tree.tailSet("orange"));
26
27 // get first and last elements
28 System.out.printf("first: %s\n", tree.first());
29 System.out.printf("last : %s\n", tree.last());
30 }
31
32 // output SortedSet using enhanced for statement
33 private static void printSet(SortedSet<String> set)
34 {
35 for (String s : set)
36 System.out.printf("%s ", s);
37
38 System.out.println();
39 }
40 } // end class SortedSetTest

```

---

**Fig. 16.17** | Using `SortedSets` and `TreeSets`. (Part I of 2.)

```
sorted set: black green grey orange red tan white yellow
headSet ("orange"): black green grey
tailSet ("orange"): orange red tan white yellow
first: black
last : yellow
```

**Fig. 16.17** | Using SortedSets and TreeSets. (Part 2 of 2.)

## 16.11 Maps

**Maps** associate *keys* to *values*. The keys in a Map must be *unique*, but the associated values need not be. If a Map contains both unique keys and unique values, it's said to implement a **one-to-one mapping**. If only the keys are unique, the Map is said to implement a **many-to-one mapping**—many keys can map to one value.

Maps differ from Sets in that Maps contain keys and values, whereas Sets contain only values. Three of the several classes that implement interface Map are **Hashtable**, **HashMap** and **TreeMap**. Hashtables and HashMaps store elements in hash tables, and TreeMaps store elements in trees. This section discusses hash tables and provides an example that uses a HashMap to store key–value pairs. **Interface SortedMap** extends Map and maintains its keys in *sorted* order—either the elements' *natural* order or an order specified by a Comparator. Class TreeMap implements SortedMap.

### Map Implementation with Hash Tables

When a program creates objects, it may need to store and retrieve them efficiently. Storing and retrieving information with arrays is efficient if some aspect of your data directly matches a numerical key value and if the *keys are unique* and tightly packed. If you have 100 employees with nine-digit social security numbers and you want to store and retrieve employee data by using the social security number as a key, the task will require an array with over 800 million elements, because nine-digit Social Security numbers must begin with 001–899 (excluding 666) as per the Social Security Administration's website

```
http://www.socialsecurity.gov/employer/randomization.html
```

This is impractical for virtually all applications that use social security numbers as keys. A program having an array that large could achieve high performance for both storing and retrieving employee records by simply using the social security number as the array index.

Numerous applications have this problem—namely, that either the keys are of the wrong type (e.g., not positive integers that correspond to array subscripts) or they're of the right type, but *sparsely* spread over a *huge range*. What is needed is a high-speed scheme for converting keys such as social security numbers, inventory part numbers and the like into unique array indices. Then, when an application needs to store something, the scheme could convert the application's key rapidly into an index, and the record could be stored at that slot in the array. Retrieval is accomplished the same way: Once the application has a key for which it wants to retrieve a data record, the application simply applies the conversion to the key—this produces the array index where the data is stored and retrieved.

The scheme we describe here is the basis of a technique called **hashing**. Why the name? When we convert a key into an array index, we literally scramble the bits, forming

a kind of “mishmashed,” or hashed, number. The number actually has no real significance beyond its usefulness in storing and retrieving a particular data record.

A glitch in the scheme is called a **collision**—this occurs when two different keys “hash into” the same cell (or element) in the array. We cannot store two values in the same space, so we need to find an alternative home for all values beyond the first that hash to a particular array index. There are many schemes for doing this. One is to “hash again” (i.e., to apply another hashing transformation to the key to provide a next candidate cell in the array). The hashing process is designed to *distribute* the values throughout the table, so the assumption is that an available cell will be found with just a few hashes.

Another scheme uses one hash to locate the first candidate cell. If that cell is occupied, successive cells are searched in order until an available cell is found. Retrieval works the same way: The key is hashed once to determine the initial location and check whether it contains the desired data. If it does, the search is finished. If it does not, successive cells are searched linearly until the desired data is found.

The most popular solution to hash-table collisions is to have each cell of the table be a hash “bucket,” typically a linked list of all the key–value pairs that hash to that cell. This is the solution that Java’s `Hashtable` and `HashMap` classes (from package `java.util`) implement. Both `Hashtable` and `HashMap` implement the `Map` interface. The primary differences between them are that `HashMap` is *unsynchronized* (multiple threads should not modify a `HashMap` concurrently) and allows `null` keys and `null` values.

A hash table’s **load factor** affects the performance of hashing schemes. The load factor is the ratio of the number of occupied cells in the hash table to the total number of cells in the hash table. The closer this ratio gets to 1.0, the greater the chance of collisions.



### Performance Tip 16.2

*The load factor in a hash table is a classic example of a memory-space/execution-time trade-off: By increasing the load factor, we get better memory utilization, but the program runs slower, due to increased hashing collisions. By decreasing the load factor, we get better program speed, because of reduced hashing collisions, but we get poorer memory utilization, because a larger portion of the hash table remains empty.*

Computer science students study hashing schemes in courses called “Data Structures” and “Algorithms.” Classes `Hashtable` and `HashMap` enable you to use hashing without having to implement hash-table mechanisms—a classic example of reuse. This concept is profoundly important in our study of object-oriented programming. As discussed in earlier chapters, classes encapsulate and hide complexity (i.e., implementation details) and offer user-friendly interfaces. Properly crafting classes to exhibit such behavior is one of the most valued skills in the field of object-oriented programming. Figure 16.18 uses a `HashMap` to count the number of occurrences of each word in a string.

---

```

1 // Fig. 16.18: WordTypeCount.java
2 // Program counts the number of occurrences of each word in a String.
3 import java.util.Map;
4 import java.util.HashMap;
5 import java.util.Set;
6 import java.util.TreeSet;
```

---

**Fig. 16.18** | Program counts the number of occurrences of each word in a `String`. (Part 1 of 3.)

---

```

7 import java.util.Scanner;
8
9 public class WordTypeCount
10 {
11 public static void main(String[] args)
12 {
13 // create HashMap to store String keys and Integer values
14 Map<String, Integer> myMap = new HashMap<>();
15
16 createMap(myMap); // create map based on user input
17 displayMap(myMap); // display map content
18 }
19
20 // create map from user input
21 private static void createMap(Map<String, Integer> map)
22 {
23 Scanner scanner = new Scanner(System.in); // create scanner
24 System.out.println("Enter a string:"); // prompt for user input
25 String input = scanner.nextLine();
26
27 // tokenize the input
28 String[] tokens = input.split(" ");
29
30 // processing input text
31 for (String token : tokens)
32 {
33 String word = token.toLowerCase(); // get lowercase word
34
35 // if the map contains the word
36 if (map.containsKey(word)) // is word in map
37 {
38 int count = map.get(word); // get current count
39 map.put(word, count + 1); // increment count
40 }
41 else
42 map.put(word, 1); // add new word with a count of 1 to map
43 }
44 }
45
46 // display map content
47 private static void displayMap(Map<String, Integer> map)
48 {
49 Set<String> keys = map.keySet(); // get keys
50
51 // sort keys
52 TreeSet<String> sortedKeys = new TreeSet<>(keys);
53
54 System.out.printf("%nMap contains:%nKey\t\tValue%n");
55
56 // generate output for each key in map
57 for (String key : sortedKeys)
58 System.out.printf("%-10s%10s%n", key, map.get(key));
59 }

```

---

**Fig. 16.18** | Program counts the number of occurrences of each word in a String. (Part 2 of 3.)

```

60 System.out.printf(
61 "%nsize: %d%nisEmpty: %b%n", map.size(), map.isEmpty());
62 }
63 } // end class WordTypeCount

```

Enter a string:

this is a sample sentence with several words this is another sample sentence with several different words

Map contains:

| Key       | Value |
|-----------|-------|
| a         | 1     |
| another   | 1     |
| different | 1     |
| is        | 2     |
| sample    | 2     |
| sentence  | 2     |
| several   | 2     |
| this      | 2     |
| with      | 2     |
| words     | 2     |

size: 10  
isEmpty: false

**Fig. 16.18** | Program counts the number of occurrences of each word in a `String`. (Part 3 of 3.)

Line 14 creates an empty `HashMap` with a *default initial capacity* (16 elements) and a default load factor (0.75)—these defaults are built into the implementation of `HashMap`. When the number of occupied slots in the `HashMap` becomes greater than the capacity times the load factor, the capacity is doubled automatically. `HashMap` is a generic class that takes two type arguments—the type of key (i.e., `String`) and the type of value (i.e., `Integer`). Recall that the type arguments passed to a generic class must be reference types, hence the second type argument is `Integer`, not `int`.

Line 16 calls method `createMap` (lines 21–44), which uses a `Map` to store the number of occurrences of each word in the sentence. Line 25 obtains the user input, and line 28 tokenizes it. Lines 31–43 convert the next token to lowercase letters (line 33), then call **Map method `containsKey`** (line 36) to determine whether the word is in the map (and thus has occurred previously in the string). If the `Map` does *not* contain the word, line 42 uses **Map method `put`** to create a new entry, with the word as the key and an `Integer` object containing 1 as the value. Autoboxing occurs when the program passes integer 1 to method `put`, because the map stores the number of occurrences as an `Integer`. If the word does exist in the map, line 38 uses **Map method `get`** to obtain the key's associated value (the count) in the map. Line 39 increments that value and uses `put` to replace the key's associated value. Method `put` returns the key's prior associated value, or `null` if the key was not in the map.



### Error-Prevention Tip 16.2

*Always use immutable keys with a `Map`. The key determines where the corresponding value is placed. If the key has changed since the insert operation, when you subsequently attempt to retrieve that value, it might not be found. In this chapter's examples, we use `Strings` as keys and `Strings` are immutable.*

Method `displayMap` (lines 47–62) displays all the entries in the map. It uses **HashMap method `keySet`** (line 49) to get a set of the keys. The keys have type `String` in the map, so method `keySet` returns a generic type `Set` with type parameter specified to be `String`. Line 52 creates a `TreeSet` of the keys, in which the keys are sorted. The loop in lines 57–58 accesses each key and its value in the map. Line 58 displays each key and its value using format specifier `%-10s` to *left align* each key and format specifier `%10s` to *right align* each value. The keys are displayed in *ascending* order. Line 61 calls **Map method `size`** to get the number of key–value pairs in the Map. Line 61 also calls **Map method `isEmpty`**, which returns a `boolean` indicating whether the Map is empty.

## 16.12 Properties Class

A **Properties** object is a *persistent* `Hashtable` that stores *key–value pairs* of `Strings`—assuming that you use methods **`setProperty`** and **`getProperty`** to manipulate the table rather than inherited `Hashtable` methods `put` and `get`. By “persistent,” we mean that the `Properties` object can be written to an output stream (possibly a file) and read back in through an input stream. A common use of `Properties` objects in prior versions of Java was to maintain application-configuration data or user preferences for applications. [Note: The **Preferences API** (package `java.util.prefs`) is meant to replace this particular use of class `Properties` but is beyond the scope of this book. To learn more, visit <http://bit.ly/JavaPreferences>.] Class `Properties` extends class `Hashtable<Object, Object>`. Figure 16.19 demonstrates several methods of class `Properties`.

Line 13 creates an empty `Properties` table with no default properties. Class `Properties` also provides an overloaded constructor that receives a reference to a `Properties` object containing default property values. Lines 16 and 17 each call `Properties` method `setProperty` to store a value for the specified key. If the key does not exist in the table, `setProperty` returns `null`; otherwise, it returns the previous value for that key.

---

```

1 // Fig. 16.19: PropertiesTest.java
2 // Demonstrates class Properties of the java.util package.
3 import java.io.FileOutputStream;
4 import java.io.FileInputStream;
5 import java.io.IOException;
6 import java.util.Properties;
7 import java.util.Set;
8
9 public class PropertiesTest
10 {
11 public static void main(String[] args)
12 {
13 Properties table = new Properties();
14
15 // set properties
16 table.setProperty("color", "blue");
17 table.setProperty("width", "200");
18
19 System.out.println("After setting properties");
20 listProperties(table);

```

---

**Fig. 16.19** | `Properties` class of package `java.util`. (Part 1 of 3.)

---

```

21
22 // replace property value
23 table.setProperty("color", "red");
24
25 System.out.println("After replacing properties");
26 listProperties(table);
27
28 saveProperties(table);
29
30 table.clear(); // empty table
31
32 System.out.println("After clearing properties");
33 listProperties(table);
34
35 loadProperties(table);
36
37 // get value of property color
38 Object value = table.getProperty("color");
39
40 // check if value is in table
41 if (value != null)
42 System.out.printf("Property color's value is %s\n", value);
43 else
44 System.out.println("Property color is not in table");
45 }
46
47 // save properties to a file
48 private static void saveProperties(Properties props)
49 {
50 // save contents of table
51 try
52 {
53 FileOutputStream output = new FileOutputStream("props.dat");
54 props.store(output, "Sample Properties"); // save properties
55 output.close();
56 System.out.println("After saving properties");
57 listProperties(props);
58 }
59 catch (IOException ioException)
60 {
61 ioException.printStackTrace();
62 }
63 }
64
65 // load properties from a file
66 private static void loadProperties(Properties props)
67 {
68 // load contents of table
69 try
70 {
71 FileInputStream input = new FileInputStream("props.dat");
72 props.load(input); // load properties
73 input.close();

```

---

**Fig. 16.19** | Properties class of package java.util. (Part 2 of 3.)

```

74 System.out.println("After loading properties");
75 listProperties(props);
76 }
77 catch (IOException ioException)
78 {
79 ioException.printStackTrace();
80 }
81 }
82
83 // output property values
84 private static void listProperties(Properties props)
85 {
86 Set<Object> keys = props.keySet(); // get property names
87
88 // output name/value pairs
89 for (Object key : keys)
90 System.out.printf(
91 "%s\t%s\n", key, props.getProperty((String) key));
92
93 System.out.println();
94 }
95 } // end class PropertiesTest

```

```

After setting properties
color blue
width 200

After replacing properties
color red
width 200

After saving properties
color red
width 200

After clearing properties

After loading properties
color red
width 200

Property color's value is red

```

**Fig. 16.19** | Properties class of package `java.util`. (Part 3 of 3.)

Line 38 calls `Properties` method `getProperty` to locate the value associated with the specified key. If the key is *not* found in this `Properties` object, `getProperty` returns `null`. An overloaded version of this method receives a second argument that specifies the default value to return if `getProperty` cannot locate the key.

Line 54 calls **Properties method store** to save the `Properties` object's contents to the `OutputStream` specified as the first argument (in this case, a `FileOutputStream`). The second argument, a `String`, is a description written into the file. **Properties method list**, which takes a `PrintStream` argument, is useful for displaying the list of properties.



Line 72 calls **Properties** method **load** to restore the contents of the Properties object from the InputStream specified as the first argument (in this case, a FileInputStream). Line 86 calls Properties method **keySet** to obtain a Set of the property names. Because class Properties stores its contents as Objects, a Set of Object references is returned. Line 91 obtains the value of a property by passing a key to method **getProperty**.

## 16.13 Synchronized Collections

In Chapter 23, we discuss *multithreading*. Except for Vector and Hashtable, the collections in the collections framework are *unsynchronized* by default, so they can operate efficiently when multithreading is not required. Because they're unsynchronized, however, concurrent access to a Collection by multiple threads could cause indeterminate results or fatal errors—as we demonstrate in Chapter 23. To prevent potential threading problems, **synchronization wrappers** are used for collections that might be accessed by multiple threads. A **wrapper** object receives method calls, adds thread synchronization (to prevent concurrent access to the collection) and *delegates* the calls to the wrapped collection object. The Collections API provides a set of static methods for wrapping collections as synchronized versions. Method headers for the synchronization wrappers are listed in Fig. 16.20. Details about these methods are available at <http://docs.oracle.com/javase/7/docs/api/java/util/Collections.html>. All these methods take a generic type and return a *synchronized view* of the generic type. For example, the following code creates a synchronized List (list2) that stores String objects:

```
List<String> list1 = new ArrayList<>();
List<String> list2 = Collections.synchronizedList(list1);
```

### public static method headers

```
<T> Collection<T> synchronizedCollection(Collection<T> c)
<T> List<T> synchronizedList(List<T> aList)
<T> Set<T> synchronizedSet(Set<T> s)
<T> SortedSet<T> synchronizedSortedSet(SortedSet<T> s)
<K, V> Map<K, V> synchronizedMap(Map<K, V> m)
<K, V> SortedMap<K, V> synchronizedSortedMap(SortedMap<K, V> m)
```

**Fig. 16.20** | Synchronization wrapper methods.

## 16.14 Unmodifiable Collections

The Collections class provides a set of static methods that create **unmodifiable wrappers** for collections. Unmodifiable wrappers throw UnsupportedOperationExceptions if attempts are made to modify the collection. In an unmodifiable collection, the references stored in the collection are not modifiable, but the objects they refer *are modifiable* unless they belong to an immutable class like String. Headers for these methods are listed in Fig. 16.21. Details about these methods are available at <http://docs.oracle.com/javase/7/docs/api/java/util/Collections.html>. All these methods take a generic

type and return an unmodifiable view of the generic type. For example, the following code creates an unmodifiable `List` (`list2`) that stores `String` objects:

```
List<String> list1 = new ArrayList<>();
List<String> list2 = Collections.unmodifiableList(list1);
```



### Software Engineering Observation 16.6

*You can use an unmodifiable wrapper to create a collection that offers read-only access to others, while allowing read–write access to yourself. You do this simply by giving others a reference to the unmodifiable wrapper while retaining for yourself a reference to the original collection.*

#### public static method headers

```
<T> Collection<T> unmodifiableCollection(Collection<T> c)
<T> List<T> unmodifiableList(List<T> aList)
<T> Set<T> unmodifiableSet(Set<T> s)
<T> SortedSet<T> unmodifiableSortedSet(SortedSet<T> s)
<K, V> Map<K, V> unmodifiableMap(Map<K, V> m)
<K, V> SortedMap<K, V> unmodifiableSortedMap(SortedMap<K, V> m)
```

**Fig. 16.21** | Unmodifiable wrapper methods.

## 16.15 Abstract Implementations

The collections framework provides various abstract implementations of `Collection` interfaces from which you can quickly “flesh out” complete customized implementations. These abstract implementations include a thin `Collection` implementation called an **AbstractCollection**, a `List` implementation that allows *array-like access* to its elements called an **AbstractList**, a `Map` implementation called an **AbstractMap**, a `List` implementation that allows *sequential access* (from beginning to end) to its elements called an **AbstractSequentialList**, a `Set` implementation called an **AbstractSet** and a `Queue` implementation called **AbstractQueue**. You can learn more about these classes at <http://docs.oracle.com/javase/7/docs/api/java/util/package-summary.html>. To write a *custom* implementation, you can extend the abstract implementation that best meets your needs, implement each of the class’s abstract methods and override the class’s concrete methods as necessary.

## 16.16 Wrap-Up

This chapter introduced the Java collections framework. You learned the collection hierarchy and how to use the collections-framework interfaces to program with collections polymorphically. You used classes `ArrayList` and `LinkedList`, which both implement the `List` interface. We presented Java’s built-in interfaces and classes for manipulating stacks and queues. You used several predefined methods for manipulating collections. You learned how to use the `Set` interface and class `HashSet` to manipulate an unordered collection of unique values. We continued our presentation of sets with the `SortedSet` interface and class `TreeSet` for manipulating a sorted collection of unique values. You then learned

about Java's interfaces and classes for manipulating key-value pairs—`Map`, `SortedMap`, `Hashtable`, `HashMap` and `TreeMap`. We discussed the specialized `Properties` class for manipulating key-value pairs of `Strings` that can be stored to a file and retrieved from a file. Finally, we discussed the `Collections` class's static methods for obtaining unmodifiable and synchronized views of collections. For additional information on the collections framework, visit <http://docs.oracle.com/javase/7/docs/technotes/guides/collections>. In Chapter 17, Java SE 8 Lambdas and Streams, you'll use Java SE 8's new functional programming capabilities to simplify collection operations. In Chapter 23, Concurrency, you'll learn how to improve performance on multi-core systems using Java's concurrent collections and parallel stream operations.

## Summary

### *Section 16.1 Introduction*

- The Java collections framework provides prebuilt data structures and methods to manipulate them.

### *Section 16.2 Collections Overview*

- A collection is an object that can hold references to other objects.
- The classes and interfaces of the collections framework are in package `java.util`.

### *Section 16.3 Type-Wrapper Classes*

- Type-wrapper classes (e.g., `Integer`, `Double`, `Boolean`) enable programmers to manipulate primitive-type values as objects (p. 679). Objects of these classes can be used in collections.

### *Section 16.4 Autoboxing and Auto-Unboxing*

- Boxing (p. 679) converts a primitive value to an object of the corresponding type-wrapper class. Unboxing (p. 679) converts a type-wrapper object to the corresponding primitive value.
- Java performs boxing conversions and unboxing conversions automatically.

### *Section 16.5 Interface `Collection` and Class `Collections`*

- Interfaces `Set` and `List` extend `Collection` (p. 678), which contains operations for adding, clearing, comparing and retaining objects in a collection, and method `iterator` (p. 683) to obtain a collection's `Iterator` (p. 679).
- Class `Collections` (p. 680) provides static methods for manipulating collections.

### *Section 16.6 Lists*

- A `List` (p. 686) is an ordered `Collection` that can contain duplicate elements.
- Interface `List` is implemented by classes `ArrayList`, `LinkedList` and `Vector`. `ArrayList` (p. 680) is a resizable-array implementation. `LinkedList` (p. 680) is a linkedlist implementation of a `List`.
- Java SE 7 supports type inferencing with the `<>` notation in statements that declare and create generic type variables and objects.
- `Iterator` method `hasNext` (p. 683) determines whether a `Collection` contains another element. Method `next` returns a reference to the next object in the `Collection` and advances the `Iterator`.
- Method `subList` (p. 686) returns a view into a `List`. Changes made to this view are also made to the `List`.

- Method `clear` (p. 686) removes elements from a `List`.
- Method `toArray` (p. 687) returns the contents of a collection as an array.

### ***Section 16.7 Collections Methods***

- Algorithms `sort` (p. 689), `binarySearch`, `reverse` (p. 694), `shuffle` (p. 692), `fill` (p. 694), `copy`, `addAll` (p. 685), `frequency` and `disjoint` operate on `Lists`. Algorithms `min` and `max` (p. 695) operate on `Collections`.
- Algorithm `addAll` appends all the elements in an array to a collection (p. 698), `frequency` (p. 698) calculates how many elements in the collection are equal to the specified element, and `disjoint` (p. 698) determines whether two collections have elements in common.
- Algorithms `min` and `max` find the smallest and largest items in a collection.
- The `Comparator` interface (p. 689) provides a means of sorting a `Collection`'s elements in an order other than their natural order.
- `Collections` method `reverseOrder` (p. 690) returns a `Comparator` object that can be used with `sort` to sort a collection's elements in reverse order.
- Algorithm `shuffle` (p. 692) randomly orders the elements of a `List`.
- Algorithm `binarySearch` (p. 696) locates an `Object` in a sorted `List`.

### ***Section 16.8 Stack Class of Package `java.util`***

- Class `Stack` (p. 700) extends `Vector`. `Stack` method `push` (p. 701) adds its argument to the top of the stack. Method `pop` (p. 702) removes the top element of the stack. Method `peek` returns a reference to the top element without removing it. `Stack` method `isEmpty` (p. 702) determines whether the stack is empty.

### ***Section 16.9 Class `PriorityQueue` and Interface `Queue`***

- Interface `Queue` (p. 702) extends interface `Collection` and provides additional operations for inserting, removing and inspecting elements in a queue.
- `PriorityQueue` (p. 702) implements interface `Queue` and orders elements by their natural ordering or by a `Comparator` object that's supplied to the constructor.
- `PriorityQueue` method `offer` (p. 702) inserts an element at the appropriate location based on priority order. Method `poll` (p. 702) removes the highest-priority element of the priority queue. Method `peek` (`peek`) gets a reference to the highest-priority element of the priority queue. Method `clear` (p. 702) removes all elements in the priority queue. Method `size` (p. 702) gets the number of elements in the priority queue.

### ***Section 16.10 Sets***

- A `Set` (p. 703) is an unordered `Collection` that contains no duplicate elements. `HashSet` (p. 703) stores its elements in a hash table. `TreeSet` (p. 703) stores its elements in a tree.
- Interface `SortedSet` (p. 704) extends `Set` and represents a set that maintains its elements in sorted order. Class `TreeSet` implements `SortedSet`.
- `TreeSet` method `headSet` (p. 704) gets a `TreeSet` view containing elements that are less than a specified element. Method `tailSet` (p. 705) gets a `TreeSet` view containing elements that are greater than or equal to a specified element. Any changes made to these views are made to the original `TreeSet`.

### ***Section 16.11 Maps***

- `Maps` (p. 706) store key–value pairs and cannot contain duplicate keys. `HashMaps` (p. 706) and `Hashtable`s (p. 706) store elements in a hash table, and `TreeMaps` (p. 706) store elements in a tree.

- `HashMap` takes two type arguments—the type of key and the type of value.
- `HashMap` method `put` (p. 709) adds a key–value pair to a `HashMap`. Method `get` (p. 709) locates the value associated with the specified key. Method `isEmpty` (p. 710) determines if the map is empty.
- `HashMap` method `keySet` (p. 710) returns a set of the keys. `Map` method `size` (p. 710) returns the number of key–value pairs in the `Map`.
- Interface `SortedMap` (p. 706) extends `Map` and represents a map that maintains its keys in sorted order. Class `TreeMap` implements `SortedMap`.

### Section 16.12 *Properties Class*

- A `Properties` object (p. 710) is a persistent subclass of `Hashtable`.
- The `Properties` no-argument constructor creates an empty `Properties` table. An overloaded constructor receives a `Properties` object containing default property values.
- `Properties` method `setProperty` (p. 710) specifies the value associated with its key argument. Method `getProperty` (p. 710) locates the value of the key specified as an argument. Method `store` (p. 712) saves the contents of a `Properties` object to specified `OutputStream`. Method `load` (p. 713) restores the contents of a `Properties` object from the specified `InputStream`.

### Section 16.13 *Synchronized Collections*

- Collections from the collections framework are unsynchronized. Synchronization wrappers (p. 713) are provided for collections that can be accessed by multiple threads simultaneously.

### Section 16.14 *Unmodifiable Collections*

- Unmodifiable collection wrappers (p. 713) throw `UnsupportedOperationException` (p. 686) if attempts are made to modify the collection.

### Section 16.15 *Abstract Implementations*

- The collections framework provides various abstract implementations of collection interfaces from which you can quickly flesh out complete customized implementations.

## Self-Review Exercises

**16.1** Fill in the blanks in each of the following statements:

- `A(n) _____` is used to iterate through a collection and can remove elements from the collection during the iteration.
- An element in a `List` can be accessed by using the element's \_\_\_\_\_.
- Assuming that `myArray` contains references to `Double` objects, \_\_\_\_\_ occurs when the statement `"myArray[0] = 1.25;"` executes.
- Java classes \_\_\_\_\_ and \_\_\_\_\_ provide the capabilities of arraylike data structures that can resize themselves dynamically.
- If you do not specify a capacity increment, the system will \_\_\_\_\_ the size of the `Vector` each time additional capacity is needed.
- You can use a(n) \_\_\_\_\_ to create a collection that offers only read-only access to others while allowing read–write access to yourself.
- Assuming that `myArray` contains references to `Double` objects, \_\_\_\_\_ occurs when the statement `"double number = myArray[0];"` executes.
- Collections algorithm \_\_\_\_\_ determines if two collections have elements in common.

**16.2** Determine whether each statement is *true* or *false*. If *false*, explain why.

- Values of primitive types may be stored directly in a collection.
- A `Set` can contain duplicate values.

- c) A Map can contain duplicate keys.
- d) A LinkedList can contain duplicate values.
- e) Collections is an interface.
- f) Iterators can remove elements.
- g) With hashing, as the load factor increases, the chance of collisions decreases.
- h) A PriorityQueue permits null elements.

## Answers to Self-Review Exercises

**16.1** a) Iterator. b) index. c) autoboxing. d) ArrayList, Vector. e) double. f) unmodifiable wrapper. g) auto-unboxing. h) disjoint.

**16.2** a) False. Autoboxing occurs when adding a primitive type to a collection, which means the primitive type is converted to its corresponding type-wrapper class.

- b) False. A Set cannot contain duplicate values.
- c) False. A Map cannot contain duplicate keys.
- d) True.
- e) False. Collections is a class; Collection is an interface.
- f) True.
- g) False. As the load factor increases, fewer slots are available relative to the total number of slots, so the chance of a collision increases.
- h) False. Attempting to insert a null element causes a NullPointerException.

## Exercises

**16.3** Define each of the following terms:

- a) Collection
- b) Collections
- c) Comparator
- d) List
- e) load factor
- f) collision
- g) space/time trade-off in hashing
- h) HashMap

**16.4** Explain briefly the operation of each of the following methods of class Vector:

- a) add
- b) set
- c) remove
- d) removeAllElements
- e) removeElementAt
- f) firstElement
- g) lastElement
- h) contains
- i) indexOf
- j) size
- k) capacity

**16.5** Explain why inserting additional elements into a Vector object whose current size is less than its capacity is a relatively fast operation and why inserting additional elements into a Vector object whose current size is at capacity is a relatively slow operation.

**16.6** By extending class Vector, Java's designers were able to create class Stack quickly. What are the negative aspects of this use of inheritance, particularly for class Stack?

- 16.7** Briefly answer the following questions:
- What is the primary difference between a Set and a Map?
  - What happens when you add a primitive type (e.g., `double`) value to a collection?
  - Can you print all the elements in a collection without using an Iterator? If yes, how?
- 16.8** Explain briefly the operation of each of the following Iterator-related methods:
- `iterator`
  - `hasNext`
  - `next`
- 16.9** Explain briefly the operation of each of the following methods of class `HashMap`:
- `put`
  - `get`
  - `isEmpty`
  - `containsKey`
  - `keySet`
- 16.10** Determine whether each of the following statements is *true* or *false*. If *false*, explain why.
- Elements in a `Collection` must be sorted in ascending order before a `binarySearch` may be performed.
  - Method `first` gets the first element in a `TreeSet`.
  - A `List` created with `Arrays` method `asList` is resizable.
- 16.11** Explain the operation of each of the following methods of the `Properties` class:
- `load`
  - `store`
  - `getProperty`
  - `list`
- 16.12** Rewrite lines 16–25 in Fig. 16.3 to be more concise by using the `asList` method and the `LinkedList` constructor that takes a `Collection` argument.
- 16.13** (*Duplicate Elimination*) Write a program that reads in a series of first names and eliminates duplicates by storing them in a `Set`. Allow the user to search for a first name.
- 16.14** (*Counting Letters*) Modify the program of Fig. 16.18 to count the number of occurrences of each letter rather than of each word. For example, the string "HELLO THERE" contains two Hs, three Es, two Ls, one O, one T and one R. Display the results.
- 16.15** (*Color Chooser*) Use a `HashMap` to create a reusable class for choosing one of the 13 predefined colors in class `Color`. The names of the colors should be used as keys, and the predefined `Color` objects should be used as values. Place this class in a package that can be imported into any Java program. Use your new class in an application that allows the user to select a color and draw a shape in that color.
- 16.16** (*Counting Duplicate Words*) Write a program that determines and prints the number of duplicate words in a sentence. Treat uppercase and lowercase letters the same. Ignore punctuation.
- 16.17** (*Inserting Elements in a LinkedList in Sorted Order*) Write a program that inserts 25 random integers from 0 to 100 in order into a `LinkedList` object. The program should sort the elements, then calculate the sum of the elements and the floating-point average of the elements.
- 16.18** (*Copying and Reversing LinkedLists*) Write a program that creates a `LinkedList` object of 10 characters, then creates a second `LinkedList` object containing a copy of the first list, but in reverse order.
- 16.19** (*Prime Numbers and Prime Factors*) Write a program that takes a whole number input from a user and determines whether it's prime. If the number is not prime, display its unique prime

factors. Remember that a prime number's factors are only 1 and the prime number itself. Every number that's not prime has a unique prime factorization. For example, consider the number 54. The prime factors of 54 are 2, 3, 3 and 3. When the values are multiplied together, the result is 54. For the number 54, the prime factors output should be 2 and 3. Use Sets as part of your solution.

**16.20** (*Sorting Words with a TreeSet*) Write a program that uses a String method `split` to tokenize a line of text input by the user and places each token in a `TreeSet`. Print the elements of the `TreeSet`. [Note: This should cause the elements to be printed in ascending sorted order.]

**16.21** (*Changing a PriorityQueue's Sort Order*) The output of Fig. 16.15 shows that `PriorityQueue` orders `Double` elements in ascending order. Rewrite Fig. 16.15 so that it orders `Double` elements in descending order (i.e., 9.8 should be the highest-priority element rather than 3.2).



# Java SE 8 Lambdas and Streams

# 17



*Oh, could I flow like thee,  
and make thy stream  
My great example,  
as it is my theme!*

—Sir John Denham

## Objectives

In this chapter you'll:

- Learn what functional programming is and how it complements object-oriented programming.
- Use functional programming to simplify programming tasks you've performed with other techniques.
- Write lambda expressions that implement functional interfaces.
- Learn what streams are and how stream pipelines are formed from stream sources, intermediate operations and terminal operations.
- Perform operations on `IntStreams`, including `forEach`, `count`, `min`, `max`, `sum`, `average`, `reduce`, `filter` and `sorted`.
- Perform operations on `Streams`, including `filter`, `map`, `sorted`, `collect`, `forEach`, `findFirst`, `distinct`, `mapToDouble` and `reduce`.
- Create streams representing ranges of `int` values and random `int` values.

- 17.1 Introduction
- 17.2 Functional Programming Technologies Overview
  - 17.2.1 Functional Interfaces
  - 17.2.2 Lambda Expressions
  - 17.2.3 Streams
- 17.3 IntStream Operations
  - 17.3.1 Creating an IntStream and Displaying Its Values with the `forEach` Terminal Operation
  - 17.3.2 Terminal Operations `count`, `min`, `max`, `sum` and `average`
  - 17.3.3 Terminal Operation `reduce`
  - 17.3.4 Intermediate Operations: Filtering and Sorting `IntStream` Values
  - 17.3.5 Intermediate Operation: Mapping
  - 17.3.6 Creating Streams of `ints` with `IntStream` Methods `range` and `rangeClosed`
- 17.4 Stream<Integer> Manipulations
  - 17.4.1 Creating a Stream<Integer>
  - 17.4.2 Sorting a Stream and Collecting the Results
  - 17.4.3 Filtering a Stream and Storing the Results for Later Use
  - 17.4.4 Filtering and Sorting a Stream and Collecting the Results
  - 17.4.5 Sorting Previously Collected Results
- 17.5 Stream<String> Manipulations
  - 17.5.1 Mapping Strings to Uppercase Using a Method Reference
  - 17.5.2 Filtering Strings Then Sorting Them in Case-Insensitive Ascending Order
  - 17.5.3 Filtering Strings Then Sorting Them in Case-Insensitive Descending Order
- 17.6 Stream<Employee> Manipulations
  - 17.6.1 Creating and Displaying a List<Employee>
  - 17.6.2 Filtering Employees with Salaries in a Specified Range
  - 17.6.3 Sorting Employees By Multiple Fields
  - 17.6.4 Mapping Employees to Unique Last Name Strings
  - 17.6.5 Grouping Employees By Department
  - 17.6.6 Counting the Number of Employees in Each Department
  - 17.6.7 Summing and Averaging Employee Salaries
- 17.7 Creating a Stream<String> from a File
- 17.8 Generating Streams of Random Values
- 17.9 Lambda Event Handlers
- 17.10 Additional Notes on Java SE 8 Interfaces
- 17.11 Java SE 8 and Functional Programming Resources
- 17.12 Wrap-Up

Summary | Self-Review Exercises | Answers to Self-Review Exercises | Exercises

## 17.1 Introduction

The way you think about Java programming is about to change profoundly. Prior to Java SE 8, Java supported three programming paradigms—*procedural programming*, *object-oriented programming* and *generic programming*. Java SE 8 adds *functional programming*. The new language and library capabilities that support this paradigm were added to Java as part of *Project Lambda*:

<http://openjdk.java.net/projects/lambda>

In this chapter, we'll define functional programming and show how to use it to write programs faster, more concisely and with fewer bugs than programs written with previous techniques. In Chapter 23, Concurrency, you'll see that functional programs are easier to *parallelize* (i.e., perform multiple operations simultaneously) so that your programs can take advantage of multi-core architectures to enhance performance. Before reading this chapter, you should review Section 10.10, which introduced Java SE 8's new interface fea-

tures (the ability to include default and static methods) and discussed the concept of functional interfaces.

This chapter presents many examples of functional programming, often showing simpler ways to implement tasks that you programmed in earlier chapters (Fig. 17.1)

| Pre-Java-SE-8 topics                                                 | Corresponding Java SE 8 discussions and examples                                                                                                                                                                                                                                                                     |
|----------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Chapter 6, Arrays and ArrayLists                                     | Sections 17.3—17.4 introduce basic lambda and streams capabilities that process one-dimensional arrays.                                                                                                                                                                                                              |
| Chapter 10, Object-Oriented Programming: Polymorphism and Interfaces | Section 10.10 introduced the new Java SE 8 interface features (default methods, static methods and the concept of functional interfaces) that support functional programming.                                                                                                                                        |
| Chapter 12, GUI Components: Part 1                                   | Section 17.9 shows how to use a lambda to implement a Swing event-listener functional interface.                                                                                                                                                                                                                     |
| Chapter 14, Strings, Characters and Regular Expressions              | Section 17.5 shows how to use lambdas and streams to process collections of String objects.                                                                                                                                                                                                                          |
| Chapter 15, Files, Streams and Object Serialization                  | Section 17.7 shows how to use lambdas and streams to process lines of text from a file.                                                                                                                                                                                                                              |
| Chapter 22, GUI Components: Part 2                                   | Discusses using lambdas to implement Swing event-listener functional interfaces.                                                                                                                                                                                                                                     |
| Chapter 23, Concurrency                                              | Shows that functional programs are easier to parallelize so that they can take advantage of multi-core architectures to enhance performance. Demonstrates parallel stream processing. Shows that Arrays method <code>parallelSort</code> improves performance on multi-core architectures when sorting large arrays. |
| Chapter 25, JavaFX GUI: Part 1                                       | Discusses using lambdas to implement JavaFX event-listener functional interfaces.                                                                                                                                                                                                                                    |

**Fig. 17.1** | Java SE 8 lambdas and streams discussions and examples.

## 17.2 Functional Programming Technologies Overview

In the preceding chapters, you learned various procedural, object-oriented and generic programming techniques. Though you often used Java library classes and interfaces to perform various tasks, you typically determine *what* you want to accomplish in a task then specify precisely *how* to accomplish it. For example, let's assume that *what* you'd like to accomplish is to sum the elements of an array named `values` (the *data source*). You might use the following code:

```
int sum = 0;
for (int counter = 0; counter < values.length; counter++)
 sum += values[counter];
```

This loop specifies *how* we'd like to add each array element's value to the `sum`—with a `for` repetition statement that processes each element one at a time, adding each element's value to the `sum`. This iteration technique is known as **external iteration** (because you specify how to iterate, not the library) and requires you to access the elements sequentially from

beginning to end in a single thread of execution. To perform the preceding task, you also create two variables (`sum` and `counter`) that are *mutated* repeatedly—that is, their values change—while the task is performed. You performed many similar array and collection tasks, such as displaying the elements of an array, summarizing the faces of a die that was rolled 6,000,000 times, calculating the average of an array’s elements and more.

### *External Iteration Is Error Prone*

Most Java programmers are comfortable with external iteration. However, there are several opportunities for error. For example, you could initialize variable `sum` incorrectly, initialize control variable `counter` incorrectly, use the wrong loop-continuation condition, increment control variable `counter` incorrectly or incorrectly add each value in the array to the `sum`.

### *Internal Iteration*

In **functional programming**, you specify *what* you want to accomplish in a task, but *not how* to accomplish it. As you’ll see in this chapter, to sum a numeric data source’s elements (such as those in an array or collection), you can use new Java SE 8 library capabilities that allow you to say, “Here’s a data source, give me the sum of its elements.” You do *not* need to specify *how* to iterate through the elements or declare and use *any* mutable variables. This is known as **internal iteration**, because the *library* determines how to access all the elements to perform the task. With internal iteration, you can easily tell the library that you want to perform this task with *parallel processing* to take advantage of your computer’s multi-core architecture—this can significantly improve the task’s performance. As you’ll learn in Chapter 23, it’s hard to create parallel tasks that operate correctly if those tasks modify a program’s state information (that is, its variable values). So the functional programming capabilities that you’ll learn here focus on **immutability**—not modifying the data source being processed or any other program state.

## 17.2.1 Functional Interfaces

Section 10.10 introduced Java SE 8’s new interface features—default methods and static methods—and discussed the concept of a *functional interface*—an interface that contains exactly one abstract method (and may also contain default and static methods). Such interfaces are also known as *single abstract method* (SAM) interfaces. Functional interfaces are used extensively in functional programming, because they act as an object-oriented model for a function.

### *Functional Interfaces in Package `java.util.function`*

Package `java.util.function` contains several functional interfaces. Figure 17.2 shows the six basic generic functional interfaces. Throughout the table, T and R are generic type names that represent the type of the object on which the functional interface operates and the return type of a method, respectively. There are many other functional interfaces in package `java.util.function` that are specialized versions of those in Fig. 17.2. Most are for use with `int`, `long` and `double` primitive values, but there are also generic customizations of `Consumer`, `Function` and `Predicate` for binary operations—that is, methods that take two arguments.

| Interface                            | Description                                                                                                                                                                                                                                                                                                     |
|--------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>BinaryOperator&lt;T&gt;</code> | Contains method <code>apply</code> that takes two <code>T</code> arguments, performs an operation on them (such as a calculation) and returns a value of type <code>T</code> . You'll see several examples of <code>BinaryOperators</code> starting in Section 17.3.                                            |
| <code>Consumer&lt;T&gt;</code>       | Contains method <code>accept</code> that takes a <code>T</code> argument and returns <code>void</code> . Performs a task with its <code>T</code> argument, such as outputting the object, invoking a method of the object, etc. You'll see several examples of <code>Consumers</code> starting in Section 17.3. |
| <code>Function&lt;T,R&gt;</code>     | Contains method <code>apply</code> that takes a <code>T</code> argument and returns a value of type <code>R</code> . Calls a method on the <code>T</code> argument and returns that method's result. You'll see several examples of <code>Functions</code> starting in Section 17.5.                            |
| <code>Predicate&lt;T&gt;</code>      | Contains method <code>test</code> that takes a <code>T</code> argument and returns a <code>boolean</code> . Tests whether the <code>T</code> argument satisfies a condition. You'll see several examples of <code>Predicates</code> starting in Section 17.3.                                                   |
| <code>Supplier&lt;T&gt;</code>       | Contains method <code>get</code> that takes no arguments and produces a value of type <code>T</code> . Often used to create a collection object in which a stream operation's results are placed. You'll see several examples of <code>Suppliers</code> starting in Section 17.7.                               |
| <code>UnaryOperator&lt;T&gt;</code>  | Contains method <code>get</code> that takes no arguments and returns a value of type <code>T</code> . You'll see several examples of <code>UnaryOperators</code> starting in Section 17.3.                                                                                                                      |

**Fig. 17.2** | The six basic generic functional interfaces in package `java.util.function`.

### 17.2.2 Lambda Expressions

Functional programming is accomplished with lambda expressions. A **lambda expression** represents an *anonymous method*—a shorthand notation for implementing a functional interface, similar to an anonymous inner class (Section 12.11). The type of a lambda expression is the type of the functional interface that the lambda expression implements. Lambda expressions can be used anywhere functional interfaces are expected. From this point forward, we'll refer to lambda expressions simply as *lambdas*. We show basic lambda syntax in this section and discuss additional lambda features as we use them throughout this and later chapters.

#### *Lambda Syntax*

A lambda consists of a *parameter list* followed by the **arrow token** (`->`) and a body, as in:

```
(parameterList) -> {statements}
```

The following lambda receives two `ints` and returns their sum:

```
(int x, int y) -> {return x + y;}
```

In this case, the body is a *statement block* that may contain *one or more* statements enclosed in curly braces. There are several variations of this syntax. For example, the parameter types usually may be omitted, as in:

```
(x, y) -> {return x + y;}
```

in which case, the compiler determines the parameter and return types by the lambda's context—we'll say more about this later.

When the body contains only one expression, the `return` keyword and curly braces may be omitted, as in:

```
(x, y) -> x + y
```

in this case, the expression's value is *implicitly* returned. When the parameter list contains only one parameter, the parentheses may be omitted, as in:

```
value -> System.out.printf("%d ", value)
```

To define a lambda with an empty parameter list, specify the parameter list as empty parentheses to the left of the arrow token (`->`), as in:

```
() -> System.out.println("Welcome to Lambdas!")
```

In addition, to the preceding lambda syntax, there are specialized shorthand forms of lambdas that are known as *method references*, which we introduce in Section 17.5.1.

### 17.2.3 Streams

Java SE 8 introduces the concept of **streams**, which are similar to the iterators you learned in Chapter 16. Streams are objects of classes that implement interface **Stream** (from the package `java.util.stream`) or one of the specialized stream interfaces for processing collections of `int`, `long` or `double` values (which we introduce in Section 17.3). Together with lambdas, streams enable you to perform tasks on collections of elements—often from an array or collection object.

#### *Stream Pipelines*

Streams move elements through a sequence of processing steps—known as a **stream pipeline**—that begins with a *data source* (such as an array or collection), performs various *intermediate operations* on the data source's elements and ends with a *terminal operation*. A stream pipeline is formed by *chaining* method calls. Unlike collections, streams do *not* have their own storage—once a stream is processed, it cannot be reused, because it does not maintain a copy of the original data source.

#### *Intermediate and Terminal Operations*

An **intermediate operation** specifies tasks to perform on the stream's elements and always results in a new stream. Intermediate operations are **lazy**—they aren't performed until a terminal operation is invoked. This allows library developers to optimize stream-processing performance. For example, if you have a collection of 1,000,000 `Person` objects and you're looking for the *first* one with the last name "Jones", stream processing can terminate as soon as the first such `Person` object is found.

A **terminal operation** initiates processing of a stream pipeline's intermediate operations and produces a result. Terminal operations are **eager**—they perform the requested operation when they are called. We say more about lazy and eager operations as we encounter them throughout the chapter and you'll see how lazy operations can improve performance. Figure 17.3 shows some common intermediate operations. Figure 17.4 shows some common terminal operations.

| Intermediate Stream operations |                                                                                                                                                                                                                                                                    |
|--------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>filter</code>            | Results in a stream containing only the elements that satisfy a condition.                                                                                                                                                                                         |
| <code>distinct</code>          | Results in a stream containing only the unique elements.                                                                                                                                                                                                           |
| <code>limit</code>             | Results in a stream with the specified number of elements from the beginning of the original stream.                                                                                                                                                               |
| <code>map</code>               | Results in a stream in which each element of the original stream is mapped to a new value (possibly of a different type)—e.g., mapping numeric values to the squares of the numeric values. The new stream has the same number of elements as the original stream. |
| <code>sorted</code>            | Results in a stream in which the elements are in sorted order. The new stream has the same number of elements as the original stream.                                                                                                                              |

**Fig. 17.3** | Common intermediate Stream operations.

| Terminal Stream operations                                                                                         |                                                                                                                                                                           |
|--------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>forEach</code>                                                                                               | Performs processing on every element in a stream (e.g., display each element).                                                                                            |
| <b><i>Reduction operations—Take all values in the stream and return a single value</i></b>                         |                                                                                                                                                                           |
| <code>average</code>                                                                                               | Calculates the <i>average</i> of the elements in a numeric stream.                                                                                                        |
| <code>count</code>                                                                                                 | Returns the <i>number of elements</i> in the stream.                                                                                                                      |
| <code>max</code>                                                                                                   | Locates the <i>largest</i> value in a numeric stream.                                                                                                                     |
| <code>min</code>                                                                                                   | Locates the <i>smallest</i> value in a numeric stream.                                                                                                                    |
| <code>reduce</code>                                                                                                | Reduces the elements of a collection to a <i>single value</i> using an associative accumulation function (e.g., a lambda that adds two elements).                         |
| <b><i>Mutable reduction operations—Create a container (such as a collection or <code>StringBuilder</code>)</i></b> |                                                                                                                                                                           |
| <code>collect</code>                                                                                               | Creates a <i>new collection</i> of elements containing the results of the stream's prior operations.                                                                      |
| <code>toArray</code>                                                                                               | Creates an <i>array</i> containing the results of the stream's prior operations.                                                                                          |
| <b><i>Search operations</i></b>                                                                                    |                                                                                                                                                                           |
| <code>findFirst</code>                                                                                             | Finds the <i>first</i> stream element based on the prior intermediate operations; immediately terminates processing of the stream pipeline once such an element is found. |
| <code>findAny</code>                                                                                               | Finds <i>any</i> stream element based on the prior intermediate operations; immediately terminates processing of the stream pipeline once such an element is found.       |
| <code>anyMatch</code>                                                                                              | Determines whether <i>any</i> stream elements match a specified condition; immediately terminates processing of the stream pipeline if an element matches.                |
| <code>allMatch</code>                                                                                              | Determines whether <i>all</i> of the elements in the stream match a specified condition.                                                                                  |

**Fig. 17.4** | Common terminal Stream operations.***Stream in File Processing vs. Stream in Functional Programming***

Throughout this chapter, we use the term *stream* in the context of functional programming—this is not the same concept as the I/O streams we discussed in Chapter 15, Files,

Streams and Object Serialization, in which a program reads a stream of bytes from a file or outputs a stream of bytes to a file. As you'll see in Section 17.7, you also can use functional programming to manipulate the contents of a file.

## 17.3 IntStream Operations

*[This section demonstrates how lambdas and streams can be used to simplify programming tasks that you learned in Chapter 6, Arrays and ArrayLists.]*

Figure 17.5 demonstrates operations on an **IntStream** (package **java.util.stream**)—a specialized stream for manipulating int values. The techniques shown in this example also apply to **LongStreams** and **DoubleStreams** for long and double values, respectively.

---

```

1 // Fig. 17.5: IntStreamOperations.java
2 // Demonstrating IntStream operations.
3 import java.util.Arrays;
4 import java.util.stream.IntStream;
5
6 public class IntStreamOperations
7 {
8 public static void main(String[] args)
9 {
10 int[] values = {3, 10, 6, 1, 4, 8, 2, 5, 9, 7};
11
12 // display original values
13 System.out.print("Original values: ");
14 IntStream.of(values)
15 .forEach(value -> System.out.printf("%d ", value));
16 System.out.println();
17
18 // count, min, max, sum and average of the values
19 System.out.printf("\nCount: %d\n", IntStream.of(values).count());
20 System.out.printf("Min: %d\n",
21 IntStream.of(values).min().getAsInt());
22 System.out.printf("Max: %d\n",
23 IntStream.of(values).max().getAsInt());
24 System.out.printf("Sum: %d\n", IntStream.of(values).sum());
25 System.out.printf("Average: %.2f\n",
26 IntStream.of(values).average().getAsDouble());
27
28 // sum of values with reduce method
29 System.out.printf("\nSum via reduce method: %d\n",
30 IntStream.of(values)
31 .reduce(0, (x, y) -> x + y));
32
33 // sum of squares of values with reduce method
34 System.out.printf("Sum of squares via reduce method: %d\n",
35 IntStream.of(values)
36 .reduce(0, (x, y) -> x + y * y));

```

---

**Fig. 17.5** | Demonstrating IntStream operations. (Part I of 2.)



```

37
38 // product of values with reduce method
39 System.out.printf("Product via reduce method: %d%n",
40 IntStream.of(values)
41 .reduce(1, (x, y) -> x * y));
42
43 // even values displayed in sorted order
44 System.out.printf("%nEven values displayed in sorted order: ");
45 IntStream.of(values)
46 .filter(value -> value % 2 == 0)
47 .sorted()
48 .forEach(value -> System.out.printf("%d ", value));
49 System.out.println();
50
51 // odd values multiplied by 10 and displayed in sorted order
52 System.out.printf(
53 "Odd values multiplied by 10 displayed in sorted order: ");
54 IntStream.of(values)
55 .filter(value -> value % 2 != 0)
56 .map(value -> value * 10)
57 .sorted()
58 .forEach(value -> System.out.printf("%d ", value));
59 System.out.println();
60
61 // sum range of integers from 1 to 10, exclusive
62 System.out.printf("%nSum of integers from 1 to 9: %d%n",
63 IntStream.range(1, 10).sum());
64
65 // sum range of integers from 1 to 10, inclusive
66 System.out.printf("Sum of integers from 1 to 10: %d%n",
67 IntStream.rangeClosed(1, 10).sum());
68 }
69 } // end class IntStreamOperations

```

Original values: 3 10 6 1 4 8 2 5 9 7

Count: 10  
 Min: 1  
 Max: 10  
 Sum: 55  
 Average: 5.50

Sum via reduce method: 55  
 Sum of squares via reduce method: 385  
 Product via reduce method: 3628800

Even values displayed in sorted order: 2 4 6 8 10  
 Odd values multiplied by 10 displayed in sorted order: 10 30 50 70 90

Sum of integers from 1 to 9: 45  
 Sum of integers from 1 to 10: 55

**Fig. 17.5** | Demonstrating IntStream operations. (Part 2 of 2.)

### 17.3.1 Creating an `IntStream` and Displaying Its Values with the `forEach` Terminal Operation

`IntStream` static method `of` (line 14) receives an `int` array as an argument and returns an `IntStream` for processing the array's values. Once you create a stream, you can *chain* together multiple method calls to create a *stream pipeline*. The statement in lines 14–15 creates an `IntStream` for the values array, then uses `IntStream` method `forEach` (a terminal operation) to perform a task on each stream element. Method `forEach` receives as its argument an object that implements the `IntConsumer` functional interface (package `java.util.function`)—this is an `int`-specific version of the generic `Consumer` functional interface. This interface's `accept` method receives one `int` value and performs a task with it—in this case, displaying the value and a space. Prior to Java SE 8, you'd typically implement interface `IntConsumer` using an anonymous inner class like:

```
new IntConsumer()
{
 public void accept(int value)
 {
 System.out.printf("%d ", value);
 }
}
```

but in Java SE 8, you simply write the lambda

```
value -> System.out.printf("%d ", value)
```

The `accept` method's parameter name (`value`) becomes the lambda's parameter, and the `accept` method's body statement becomes the lambda expression's body. As you can see, the lambda syntax is clearer and more concise than the anonymous inner class.

#### *Type Inference and a Lambda's Target Type*

The Java compiler can usually *infer* the types of a lambda's parameters and the type returned by a lambda from the context in which the lambda is used. This is determined by the lambda's **target type**—the functional interface type that is expected where the lambda appears in the code. In line 15, the target type is `IntConsumer`. In this case, the lambda parameter's type is *inferred* to be `int`, because interface `IntConsumer`'s `accept` method expects to receive an `int`. You can *explicitly* declare the parameter's type, as in:

```
(int value) -> System.out.printf("%d ", value)
```

When doing so, the lambda's parameter list *must* be enclosed in parentheses. We generally let the compiler *infer* the lambda parameter's type in our examples.

#### *final Local Variables, Effectively final Local Variables and Capturing Lambdas*

Prior to Java SE 8, when implementing an anonymous inner class, you could use local variables from the enclosing method (known as the *lexical scope*), but you were required to declare those local variables `final`. Lambdas may also use `final` local variables. In Java SE 8, anonymous inner classes and lambdas can also use **effectively final local variables**—that is, local variables that are *not* modified after they're initially declared and initialized. A lambda that refers to a local variable in the enclosing lexical scope is known as a **capturing lambda**. The compiler captures the local variable's value and ensures that the value can be used when the lambda *eventually* executes, which may be *after* its lexical scope *no longer exists*.

*Using this in a Lambda That Appears in an Instance Method*

As in an anonymous inner class, a lambda can use the outer class's `this` reference. In an anonymous inner class, you must use the syntax `OuterClassName.this`—otherwise, the `this` reference would refer to *the object of the anonymous inner class*. In a lambda, you refer to the object of the outer class, simply as `this`.

*Parameter and Variable Names in a Lambda*

The parameter names and variable names that you use in lambdas cannot be the same as any other local variables in the lambda's lexical scope; otherwise, a compilation error occurs.

**17.3.2 Terminal Operations count, min, max, sum and average**

Class `IntStream` provides various terminal operations for common stream reductions on streams of `int` values. Terminal operations are *eager*—they immediately process the items in the stream. Common reduction operations for `IntStreams` include:

- **count** (line 19) returns the number of elements in the stream.
- **min** (line 21) returns the smallest `int` in the stream.
- **max** (line 23) returns the largest `int` in the stream.
- **sum** (line 24) returns the sum of all the `ints` in the stream.
- **average** (line 26) returns an **`OptionalDouble`** (package `java.util`) containing the average of the `ints` in the stream as a value of type `double`. For any stream, it's possible that there are *no elements* in the stream. Returning `OptionalDouble` enables method `average` to return the average if the stream contains *at least one element*. In this example, we know the stream has 10 elements, so we call class `OptionalDouble`'s **`getAsDouble`** method to obtain the average. If there were no *elements*, the `OptionalDouble` would not contain the average and `getAsDouble` would throw a `NoSuchElementException`. To prevent this exception, you can instead call method **`orElse`**, which returns the `OptionalDouble`'s value if there is one, or the value you pass to `orElse`, otherwise.

Class `IntStream` also provides method `summaryStatistics` that performs the `count`, `min`, `max`, `sum` and `average` operations *in one pass* of an `IntStream`'s elements and returns the results as an `IntSummaryStatistics` object (package `java.util`). This provides a significant performance boost over reprocessing an `IntStream` repeatedly for each individual operation. This object has methods for obtaining each result and a `toString` method that summarizes all the results. For example, the statement:

```
System.out.println(IntStream.of(values).summaryStatistics());
```

produces:

```
IntSummaryStatistics{count=10, sum=55, min=1, average=5.500000,
max=10}
```

for the array values in Fig. 17.5.

**17.3.3 Terminal Operation reduce**

You can define your own reductions for an `IntStream` by calling its **`reduce`** method as shown in lines 29–31 of Fig. 17.5. Each of the terminal operations in Section 17.3.2 is a

specialized implementation of `reduce`. For example, line 31 shows how to sum an `IntStream`'s values using `reduce`, rather than `sum`. The first argument (0) is a value that helps you begin the reduction operation and the second argument is an object that implements the `IntBinaryOperator` functional interface (package `java.util.function`). The lambda:

```
(x, y) -> x + y
```

implements the interface's `applyAsInt` method, which receives two `int` values (representing the left and right operands of a binary operator) and performs a calculation with the values—in this case, adding the values. A lambda with two or more parameters *must* enclose them in parentheses. Evaluation of the reduction proceeds as follows:

- On the first call to `reduce`, lambda parameter `x`'s value is the identity value (0) and lambda parameter `y`'s value is the *first* `int` in the stream (3), producing the sum 3 (0 + 3).
- On the next call to `reduce`, lambda parameter `x`'s value is the result of the first calculation (3) and lambda parameter `y`'s value is the *second* `int` in the stream (10), producing the sum 13 (3 + 10).
- On the next call to `reduce`, lambda parameter `x`'s value is the result of the previous calculation (13) and lambda parameter `y`'s value is the *third* `int` in the stream (6), producing the sum 19 (13 + 6).

This process continues producing a running total of the `IntStream`'s values until they've all been used, at which point the final sum is returned.

#### *Method `reduce`'s Identity Value Argument*

Method `reduce`'s first argument is formally called an **identity value**—a value that, when combined with any stream element using the `IntBinaryOperator` produces that element's original value. For example, when summing the elements, the identity value is 0 (any `int` value added to 0 results in the original value) and when getting the product of the elements the identity value is 1 (any `int` value multiplied by 1 results in the original value).

#### *Summing the Squares of the Values with Method `reduce`*

Lines 34–36 of Fig. 17.5 use method `reduce` to calculate the sums of the squares of the `IntStream`'s values. The lambda in this case, adds the *square* of the current value to the running total. Evaluation of the reduction proceeds as follows:

- On the first call to `reduce`, lambda parameter `x`'s value is the identity value (0) and lambda parameter `y`'s value is the *first* `int` in the stream (3), producing the value 9 (0 + 3<sup>2</sup>).
- On the next call to `reduce`, lambda parameter `x`'s value is the result of the first calculation (9) and lambda parameter `y`'s value is the *second* `int` in the stream (10), producing the sum 109 (9 + 10<sup>2</sup>).
- On the next call to `reduce`, lambda parameter `x`'s value is the result of the previous calculation (109) and lambda parameter `y`'s value is the *third* `int` in the stream (6), producing the sum 145 (109 + 6<sup>2</sup>).

This process continues producing a running total of the squares of the `IntStream`'s values until they've all been used, at which point the final sum is returned.

### *Calculating the Product of the Values with Method **reduce***

Lines 39–41 of Fig. 17.5 use method `reduce` to calculate the product of the `IntStream`'s values. In this case, the lambda multiplies its two arguments. Because we're producing a product, we begin with the identity value 1 in this case. Evaluation of the reduction proceeds as follows:

- On the first call to `reduce`, lambda parameter `x`'s value is the identity value (1) and lambda parameter `y`'s value is the *first* `int` in the stream (3), producing the value 3 ( $1 * 3$ ).
- On the next call to `reduce`, lambda parameter `x`'s value is the result of the first calculation (3) and lambda parameter `y`'s value is the *second* `int` in the stream (10), producing the sum 30 ( $3 * 10$ ).
- On the next call to `reduce`, lambda parameter `x`'s value is the result of the previous calculation (30) and lambda parameter `y`'s value is the *third* `int` in the stream (6), producing the sum 180 ( $30 * 6$ ).

This process continues producing a running product of the `IntStream`'s values until they've all been used, at which point the final product is returned.

### **17.3.4 Intermediate Operations: Filtering and Sorting IntStream Values**

Lines 45–48 of Fig. 17.5 create a stream pipeline that *locates* the even integers in an `IntStream`, *sorts* them in ascending order and *displays* each value followed by a space.

#### *Intermediate Operation **filter***

You *filter* elements to produce a stream of intermediate results that match a condition—known as a *predicate*. `IntStream` method `filter` (line 46) receives an object that implements the `IntPredicate` functional interface (package `java.util.function`). The lambda in line 46:

```
value -> value % 2 == 0
```

implements the interface's `test` method, which receives an `int` and returns a `boolean` indicating whether the `int` satisfies the predicate—in this case, the `IntPredicate` returns `true` if the value it receives is divisible by 2. Calls to `filter` and other intermediate streams are *lazy*—they aren't evaluated until a *terminal operation* (which is *eager*) is performed—and produce new streams of elements. In lines 45–48, this occurs when `forEach` is called (line 48).

#### *Intermediate Operation **sorted***

`IntStream` method `sorted` orders the elements of the stream into *ascending* order. Like `filter`, `sorted` is a *lazy* operation; however, when the sorting is eventually performed, all prior intermediate operations in the stream pipeline must be complete so that method `sorted` knows which elements to sort.

#### *Processing the Stream Pipeline and Stateless vs. Stateful Intermediate Operations*

When `forEach` is called, the stream pipeline is processed. Line 46 produces an intermediate `IntStream` containing only the even integers, then line 47 sorts them and line 48 displays each element.

Method `filter` is a **stateless intermediate operation**—it does not require any information about other elements in the stream in order to test whether the current element satisfies the predicate. Similarly method `map` (discussed shortly) is a stateless intermediate operation. Method `sorted` is a **stateful intermediate operation** that requires information about *all* of the other elements in the stream in order to sort them. Similarly method `distinct` is a stateful intermediate operation. The online documentation for each intermediate stream operation specifies whether it is a stateless or stateful operation.

### *Other Methods of the `IntPredicate` Functional Interface*

Interface `IntPredicate` also contains three default methods:

- **and**—performs a *logical AND* with *short-circuit evaluation* (Section 4.8) between the `IntPredicate` on which it's called and the `IntPredicate` it receives as an argument.
- **negate**—*reverses* the boolean value of the `IntPredicate` on which it's called.
- **or**—performs a *logical OR* with *short-circuit evaluation* between the `IntPredicate` on which it's called and the `IntPredicate` it receives as an argument.

### *Composing Lambda Expressions*

You can use these methods and `IntPredicate` objects to compose more complex conditions. For example, consider the following two `IntPredicates`:

```
IntPredicate even = value -> value % 2 == 0;
IntPredicate greaterThan5 = value -> value > 5;
```

To locate all the even integers greater than 5, you could replace the lambda in line 46 with the `IntPredicate`

```
even.and(greaterThan5)
```

## 17.3.5 Intermediate Operation: Mapping

Lines 54–58 of Fig. 17.5 create a stream pipeline that *locates* the odd integers in an `IntStream`, *multiplies* each odd integer by 10, *sorts* the values in ascending order and *displays* each value followed by a space.

### *Intermediate Operation `map`*

The new feature here is the *mapping* operation that takes each value and multiplies it by 10. Mapping is an *intermediate operation* that transforms a stream's elements to new values and produces a stream containing the resulting elements. Sometimes these are of different types from the original stream's elements.

`IntStream` method `map` (line 56) receives an object that implements the **`IntUnaryOperator`** functional interface (package `java.util.function`). The lambda in line 55:

```
value -> value * 10
```

implements the interface's **`applyAsInt`** method, which receives an `int` and maps it to a new `int` value. Calls to `map` are *lazy*. Method `map` is a *stateless* stream operation.

*Processing the Stream Pipeline*

When `forEach` is called (line 58), the stream pipeline is processed. First, line 55 produces an intermediate `IntStream` containing only the odd values. Next, line 56 multiplies each odd integer by 10. Then, line 57 sorts the values and line 58 displays each element.

**17.3.6 Creating Streams of ints with `IntStream` Methods `range` and `rangeClosed`**

If you need an *ordered sequence* of `int` values, you can create an `IntStream` containing such values with `IntStream` methods `range` (line 63 of Fig. 17.5) and `rangeClosed` (line 67). Both methods take two `int` arguments representing the range of values. Method **`range`** produces a sequence of values from its first argument up to, but *not* including its second argument. Method **`rangeClosed`** produces a sequence of values including *both* of its arguments. Lines 63 and 67 demonstrate these methods for producing sequences of `int` values from 1–9 and 1–10, respectively. For the complete list of `IntStream` methods, visit:

<http://download.java.net/jdk8/docs/api/java/util/stream/IntStream.html>

**17.4 Stream<Integer> Manipulations**

*[This section demonstrates how lambdas and streams can be used to simplify programming tasks that you learned in Chapter 6, Arrays and ArrayLists.]*

Just as class `IntStream`'s method `of` can create an `IntStream` from an array of `ints`, class `Array`'s **`stream`** method can be used to create a `Stream` from an array of objects. Figure 17.6 performs *filtering* and *sorting* on a `Stream<Integer>`, using the same techniques you learned in Section 17.3. The program also shows how to *collect* the results of a stream pipeline's operations into a new collection that you can process in subsequent statements. Throughout this example, we use the `Integer` array values (line 12) that's initialized with `int` values—the compiler *boxes* each `int` into an `Integer` object. Line 15 displays the contents of values before we perform any stream processing.

---

```

1 // Fig. 17.6: ArraysAndStreams.java
2 // Demonstrating lambdas and streams with an array of Integers.
3 import java.util.Arrays;
4 import java.util.Comparator;
5 import java.util.List;
6 import java.util.stream.Collectors;
7
8 public class ArraysAndStreams
9 {
10 public static void main(String[] args)
11 {
12 Integer[] values = {2, 9, 5, 0, 3, 7, 1, 4, 8, 6};
13
14 // display original values
15 System.out.printf("Original values: %s\n", Arrays.asList(values));

```

---

**Fig. 17.6** | Demonstrating lambdas and streams with an array of `Integers`. (Part I of 2.)

```

16
17 // sort values in ascending order with streams
18 System.out.printf("Sorted values: %s\n",
19 Arrays.stream(values)
20 .sorted()
21 .collect(Collectors.toList()));
22
23 // values greater than 4
24 List<Integer> greaterThan4 =
25 Arrays.stream(values)
26 .filter(value -> value > 4)
27 .collect(Collectors.toList());
28 System.out.printf("Values greater than 4: %s\n", greaterThan4);
29
30 // filter values greater than 4 then sort the results
31 System.out.printf("Sorted values greater than 4: %s\n",
32 Arrays.stream(values)
33 .filter(value -> value > 4)
34 .sorted()
35 .collect(Collectors.toList()));
36
37 // greaterThan4 List sorted with streams
38 System.out.printf(
39 "Values greater than 4 (ascending with streams): %s\n",
40 greaterThan4.stream()
41 .sorted()
42 .collect(Collectors.toList()));
43 }
44 } // end class ArraysAndStreams

```

```

Original values: [2, 9, 5, 0, 3, 7, 1, 4, 8, 6]
Sorted values: [0, 1, 2, 3, 4, 5, 6, 7, 8, 9]
Values greater than 4: [9, 5, 7, 8, 6]
Sorted values greater than 4: [5, 6, 7, 8, 9]
Values greater than 4 (ascending with streams): [5, 6, 7, 8, 9]

```

**Fig. 17.6** | Demonstrating lambdas and streams with an array of `Integers`. (Part 2 of 2.)

### 17.4.1 Creating a `Stream<Integer>`

When you pass an array of objects to class `Arrays`'s static method `stream`, the method returns a `Stream` of the appropriate type—e.g., line 19 produces a `Stream<Integer>` from an `Integer` array. Interface **Stream** (package `java.util.stream`) is a generic interface for performing stream operations on any *non-primitive* type. The types of objects that are processed are determined by the `Stream`'s source.

Class `Arrays` also provides overloaded versions of method `stream` for creating `IntStreams`, `LongStreams` and `DoubleStreams` from entire `int`, `long` and `double` arrays or from ranges of elements in the arrays. The specialized `IntStream`, `LongStream` and `DoubleStream` classes provide various methods for common operations on numerical streams, as you learned in Section 17.3.



### 17.4.2 Sorting a Stream and Collecting the Results

In Section 6.12, you learned how to sort arrays with the `sort` and `parallelSort` static methods of class `Arrays`. You'll often sort the results of stream operations, so in lines 18–21 we'll sort the `values` array using stream techniques and display the sorted values. First, line 19 creates a `Stream<Integer>` from `values`. Next, line 20 calls `Stream` method `sorted` which sort the elements—this results in an intermediate `Stream<Integers>` with the values in *ascending* order.

To display the sorted results, we could output each value using `Stream` terminal operation `forEach` (as in line 15 of Fig. 17.5). However, when processing streams, you often create *new* collections containing the results so that you can perform additional operations on them. To create a collection, you can use `Stream` method `collect` (Fig. 17.6, line 21), which is a *terminal operation*. As the stream pipeline is processed, method `collect` performs a **mutable reduction** operation that places the results into an object which subsequently *can be modified*—often a collection, such as a `List`, `Map` or `Set`. The version of method `collect` in line 21 receives as its argument an object that implements interface **Collector** (package `java.util.stream`), which specifies how to perform the mutable reduction. Class **Collectors** (package `java.util.stream`) provides static methods that return predefined `Collector` implementations. For example, `Collectors` method `toList` (line 21) transforms the `Stream<Integer>` into a `List<Integer>` collection. In lines 18–21, the resulting `List<Integer>` is then displayed with an *implicit* call to its `toString` method.

We demonstrate another version of method `collect` in Section 17.6. For more details on class `Collectors`, visit:

```
http://download.java.net/jdk8/docs/api/java/util/stream/
Collectors.html
```

### 17.4.3 Filtering a Stream and Storing the Results for Later Use

Lines 24–27 of Fig. 17.6 create a `Stream<Integer>`, call `Stream` method `filter` (which receives a `Predicate`) to locate all the values greater than 4 and collect the results into a `List<Integer>`. Like `IntPredicate` (Section 17.3.4), functional interface `Predicate` has a test method that returns a `boolean` indicating whether the argument satisfies a condition, as well as methods **and**, **negate** and **or**.

We assign the stream pipeline's resulting `List<Integer>` to variable `greaterThan4`, which is used in line 28 to display the values greater than 4 and used again in lines 40–42 to perform additional operations on only the values greater than 4.

### 17.4.4 Filtering and Sorting a Stream and Collecting the Results

Lines 31–35 display the values greater than 4 in sorted order. First, line 32 creates a `Stream<Integer>`. Then line 33 filters the elements to locate all the values greater than 4. Next, line 34 indicates that we'd like the results sorted. Finally, line 35 collects the results into a `List<Integer>`, which is then displayed as a `String`.

### 17.4.5 Sorting Previously Collected Results

Lines 40–42 use the `greaterThan4` collection that was created in lines 24–27 to show additional processing on a collection containing the results of a prior stream pipeline. In this

case, we use streams to sort the values in `greaterThan4`, collect the results into a new `List<Integers>` and display the sorted values.

## 17.5 Stream<String> Manipulations

*[This section demonstrates how lambdas and streams can be used to simplify programming tasks that you learned in Chapter 14, Strings, Characters and Regular Expressions.]*

Figure 17.7 performs some of the same stream operations you learned in Sections 17.3—17.4 but on a `Stream<String>`. In addition, we demonstrate *case-insensitive sorting* and sorting in *descending* order. Throughout this example, we use the `String` array `strings` (lines 11–12) that's initialized with color names—some with an initial uppercase letter. Line 15 displays the contents of `strings` *before* we perform any stream processing.

---

```

1 // Fig. 17.7: ArraysAndStreams2.java
2 // Demonstrating lambdas and streams with an array of Strings.
3 import java.util.Arrays;
4 import java.util.Comparator;
5 import java.util.stream.Collectors;
6
7 public class ArraysAndStreams2
8 {
9 public static void main(String[] args)
10 {
11 String[] strings =
12 {"Red", "orange", "Yellow", "green", "Blue", "indigo", "Violet"};
13
14 // display original strings
15 System.out.printf("Original strings: %s\n", Arrays.asList(strings));
16
17 // strings in uppercase
18 System.out.printf("strings in uppercase: %s\n",
19 Arrays.stream(strings)
20 .map(String::toUpperCase)
21 .collect(Collectors.toList()));
22
23 // strings less than "n" (case insensitive) sorted ascending
24 System.out.printf("strings greater than m sorted ascending: %s\n",
25 Arrays.stream(strings)
26 .filter(s -> s.compareToIgnoreCase("n") < 0)
27 .sorted(String.CASE_INSENSITIVE_ORDER)
28 .collect(Collectors.toList()));
29
30 // strings less than "n" (case insensitive) sorted descending
31 System.out.printf("strings greater than m sorted descending: %s\n",
32 Arrays.stream(strings)
33 .filter(s -> s.compareToIgnoreCase("n") < 0)
34 .sorted(String.CASE_INSENSITIVE_ORDER.reversed())
35 .collect(Collectors.toList()));
36 }
37 } // end class ArraysAndStreams2

```

---

**Fig. 17.7** | Demonstrating lambdas and streams with an array of Strings. (Part I of 2.)

```
Original strings: [Red, orange, Yellow, green, Blue, indigo, Violet]
strings in uppercase: [RED, ORANGE, YELLOW, GREEN, BLUE, INDIGO, VIOLET]
strings greater than m sorted ascending: [orange, Red, Violet, Yellow]
strings greater than m sorted descending: [Yellow, Violet, Red, orange]
```

**Fig. 17.7** | Demonstrating lambdas and streams with an array of Strings. (Part 2 of 2.)

### 17.5.1 Mapping Strings to Uppercase Using a Method Reference

Lines 18–21 display the Strings in uppercase letters. To do so, line 19 creates a `Stream<String>` from the array `strings`, then line 20 calls `Stream` method `map` to map each `String` to its uppercase version by calling `String` instance method `toUpperCase`. `String::toUpperCase` is known as a **method reference** and is a shorthand notation for a lambda expression—in this case, for a lambda expression like:

```
(String s) -> {return s.toUpperCase();}
```

or

```
s -> s.toUpperCase()
```

`String::toUpperCase` is a method reference for `String` instance method `toUpperCase`. Figure 17.8 shows the four method reference types.

| Lambda                           | Description                                                                                                                                                                                                                                                                           |
|----------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>String::toUpperCase</code> | Method reference for an instance method of a class. Creates a one-parameter lambda that invokes the instance method on the lambda's argument and returns the method's result. Used in Fig. 17.7.                                                                                      |
| <code>System.out::println</code> | Method reference for an instance method that should be called on a specific object. Creates a one-parameter lambda that invokes the instance method on the specified object—passing the lambda's argument to the instance method—and returns the method's result. Used in Fig. 17.10. |
| <code>Math::sqrt</code>          | Method reference for a static method of a class. Creates a one-parameter lambda in which the lambda's argument is passed to the specified a static method and the lambda returns the method's result.                                                                                 |
| <code>TreeMap::new</code>        | Constructor reference. Creates a lambda that invokes the no-argument constructor of the specified class to create and initialize a new object of that class. Used in Fig. 17.17.                                                                                                      |

**Fig. 17.8** | Types of method references.

`Stream` method `map` receives as an argument an object that implements the functional interface `Function`—the instance method reference `String::toUpperCase` is treated as a lambda that implements interface `Function`. This interface's **apply** method receives one parameter and returns a result—in this case, method `apply` receives a `String` and returns the uppercase version of the `String`. Line 21 *collects* the results into a `List<String>` that we output as a `String`.

### 17.5.2 Filtering Strings Then Sorting Them in Case-Insensitive Ascending Order

Lines 24–28 filter and sort the Strings. Line 25 creates a `Stream<String>` from the array strings, then line 26 calls `Stream` method `filter` to locate all the Strings that are greater than "m", using a *case-insensitive* comparison in the Predicate lambda. Line 27 sorts the results and line 28 collects them into a `List<String>` that we output as a String. In this case, line 27 invokes the version of `Stream` method `sorted` that receives a `Comparator` as an argument. As you learned in Section 16.7.1, a `Comparator` defines a `compare` method that returns a negative value if the first value being compared is less than the second, 0 if they're equal and a positive value if the first value is greater than the second. By default, method `sorted` uses the *natural order* for the type—for Strings, the natural order is case sensitive, which means that "Z" is less than "a". Passing the predefined `Comparator String.CASE_INSENSITIVE_ORDER` performs a *case-insensitive* sort.

### 17.5.3 Filtering Strings Then Sorting Them in Case-Insensitive Descending Order

Lines 31–35 perform the same tasks as lines 24–28, but sort the Strings in *descending* order. Functional interface `Comparator` contains default method `reversed`, which reverses an existing `Comparator`'s ordering. When applied to `String.CASE_INSENSITIVE_ORDER`, the Strings are sorted in *descending* order.

## 17.6 Stream<Employee> Manipulations

The example in Figs. 17.9–17.16 demonstrates various lambda and stream capabilities using a `Stream<Employee>`. Class `Employee` (Fig. 17.9) represents an employee with a first name, last name, salary and department and provides methods for manipulating these values. In addition, the class provides a `getName` method (lines 69–72) that returns the combined first and last name as a String, and a `toString` method (lines 75–80) that returns a formatted String containing the employee's first name, last name, salary and department.

---

```

1 // Fig. 17.9: Employee.java
2 // Employee class.
3 public class Employee
4 {
5 private String firstName;
6 private String lastName;
7 private double salary;
8 private String department;
9
10 // constructor
11 public Employee(String firstName, String lastName,
12 double salary, String department)
13 {
14 this.firstName = firstName;
15 this.lastName = lastName;

```

---

**Fig. 17.9** | Employee class for use in Figs. 17.10–17.16. (Part I of 3.)

---

```
16 this.salary = salary;
17 this.department = department;
18 }
19
20 // set firstName
21 public void setFirstName(String firstName)
22 {
23 this.firstName = firstName;
24 }
25
26 // get firstName
27 public String getFirstName()
28 {
29 return firstName;
30 }
31
32 // set lastName
33 public void setLastName(String lastName)
34 {
35 this.lastName = lastName;
36 }
37
38 // get lastName
39 public String getLastName()
40 {
41 return lastName;
42 }
43
44 // set salary
45 public void setSalary(double salary)
46 {
47 this.salary = salary;
48 }
49
50 // get salary
51 public double getSalary()
52 {
53 return salary;
54 }
55
56 // set department
57 public void setDepartment(String department)
58 {
59 this.department = department;
60 }
61
62 // get department
63 public String getDepartment()
64 {
65 return department;
66 }
67
```

---

**Fig. 17.9** | Employee class for use in Figs. 17.10–17.16. (Part 2 of 3.)

---

```

68 // return Employee's first and last name combined
69 public String getName()
70 {
71 return String.format("%s %s", getFirstName(), getLastName());
72 }
73
74 // return a String containing the Employee's information
75 @Override
76 public String toString()
77 {
78 return String.format("%-8s %-8s %8.2f %s",
79 getFirstName(), getLastName(), getSalary(), getDepartment());
80 } // end method toString
81 } // end class Employee

```

---

**Fig. 17.9** | Employee class for use in Figs. 17.10–17.16. (Part 3 of 3.)

### 17.6.1 Creating and Displaying a List<Employee>

Class ProcessingEmployees (Figs. 17.10–17.16) is split into several figures so we can show you the lambda and streams operations with their corresponding outputs. Figure 17.10 creates an array of Employees (lines 17–24) and gets its List view (line 27).

---

```

1 // Fig. 17.10: ProcessingEmployees.java
2 // Processing streams of Employee objects.
3 import java.util.Arrays;
4 import java.util.Comparator;
5 import java.util.List;
6 import java.util.Map;
7 import java.util.TreeMap;
8 import java.util.function.Function;
9 import java.util.function.Predicate;
10 import java.util.stream.Collectors;
11
12 public class ProcessingEmployees
13 {
14 public static void main(String[] args)
15 {
16 // initialize array of Employees
17 Employee[] employees = {
18 new Employee("Jason", "Red", 5000, "IT"),
19 new Employee("Ashley", "Green", 7600, "IT"),
20 new Employee("Matthew", "Indigo", 3587.5, "Sales"),
21 new Employee("James", "Indigo", 4700.77, "Marketing"),
22 new Employee("Luke", "Indigo", 6200, "IT"),
23 new Employee("Jason", "Blue", 3200, "Sales"),
24 new Employee("Wendy", "Brown", 4236.4, "Marketing")};
25
26 // get List view of the Employees
27 List<Employee> list = Arrays.asList(employees);

```

---

**Fig. 17.10** | Creating an array of Employees, converting it to a List and displaying the List. (Part 1 of 2.)

```

28
29 // display all Employees
30 System.out.println("Complete Employee list:");
31 list.stream().forEach(System.out::println);
32

```

|                         |        |         |           |
|-------------------------|--------|---------|-----------|
| Complete Employee list: |        |         |           |
| Jason                   | Red    | 5000.00 | IT        |
| Ashley                  | Green  | 7600.00 | IT        |
| Matthew                 | Indigo | 3587.50 | Sales     |
| James                   | Indigo | 4700.77 | Marketing |
| Luke                    | Indigo | 6200.00 | IT        |
| Jason                   | Blue   | 3200.00 | Sales     |
| Wendy                   | Brown  | 4236.40 | Marketing |

**Fig. 17.10** | Creating an array of `Employee`s, converting it to a `List` and displaying the `List`.  
(Part 2 of 2.)

Line 31 creates a `Stream<Employee>`, then uses `Stream` method `forEach` to display each `Employee`'s `String` representation. The instance method reference `System.out::println` is converted by the compiler into an object that implements the `Consumer` functional interface. This interface's **accept** method receives one argument and returns `void`. In this example, the `accept` method passes each `Employee` to the `System.out` object's `println` instance method, which implicitly calls class `Employee`'s `toString` method to get the `String` representation. The output at the end of Fig. 17.10 shows the results of displaying all the `Employees`.

### 17.6.2 Filtering Employees with Salaries in a Specified Range

Figure 17.11 demonstrates filtering `Employees` with an object that implements the functional interface `Predicate<Employee>`, which is defined with a lambda in lines 34–35. Defining lambdas in this manner enables you to reuse them multiple times, as we do in lines 42 and 49. Lines 41–44 output the `Employees` with salaries in the range 4000–6000 sorted by salary as follows:

- Line 41 creates a `Stream<Employee>` from the `List<Employee>`.
- Line 42 filters the stream using the `Predicate` named `fourToSixThousand`.
- Line 43 sorts by salary the `Employees` that remain in the stream. To specify a `Comparator` for salaries, we use the `Comparator` interface's static method `comparing`. The method reference `Employee::getSalary` that's passed as an argument is converted by the compiler into an object that implements the `Function` interface. This `Function` is used to extract a value from an object in the stream for use in comparisons. Method `comparing` returns a `Comparator` object that calls `getSalary` on each of two `Employee` objects, then returns a negative value if the first `Employee`'s salary is less than the second, 0 if they're equal and a positive value if the first `Employee`'s salary is greater than the second.
- Finally, line 44 performs the terminal `forEach` operation that processes the stream pipeline and outputs the `Employees` sorted by salary.

```

33 // Predicate that returns true for salaries in the range $4000-$6000
34 Predicate<Employee> fourToSixThousand =
35 e -> (e.getSalary() >= 4000 && e.getSalary() <= 6000);
36
37 // Display Employees with salaries in the range $4000-$6000
38 // sorted into ascending order by salary
39 System.out.printf(
40 "%nEmployees earning $4000-$6000 per month sorted by salary:%n");
41 list.stream()
42 .filter(fourToSixThousand)
43 .sorted(Comparator.comparing(Employee::getSalary))
44 .forEach(System.out::println);
45
46 // Display first Employee with salary in the range $4000-$6000
47 System.out.printf("%nFirst employee who earns $4000-$6000:%n%s%n",
48 list.stream()
49 .filter(fourToSixThousand)
50 .findFirst()
51 .get());
52

```

```

Employees earning $4000-$6000 per month sorted by salary:
Wendy Brown 4236.40 Marketing
James Indigo 4700.77 Marketing
Jason Red 5000.00 IT

First employee who earns $4000-$6000:
Jason Red 5000.00 IT

```

**Fig. 17.11** | Filtering Employees with salaries in the range \$4000–\$6000.

### Short-Circuit Stream Pipeline Processing

In Section 4.8, you studied short-circuit evaluation with the logical AND (&&) and logical OR (||) operators. One of the nice performance features of lazy evaluation is the ability to perform *short circuit evaluation*—that is, to stop processing the stream pipeline as soon as the desired result is available. Line 50 demonstrates Stream method **findFirst**—a *short-circuiting terminal operation* that processes the stream pipeline and terminates processing as soon as the *first* object from the stream pipeline is found. Based on the original list of Employees, the processing of the stream in lines 48–51—which filters Employees with salaries in the range \$4000–\$6000—proceeds as follows: The Predicate `fourToSixThousand` is applied to the first Employee (Jason Red). His salary (\$5000.00) is in the range \$4000–\$6000, so the Predicate returns true and processing of the stream terminates *immediately*, having processed only one of the eight objects in the stream. Method `findFirst` then returns an `Optional` (in this case, an `Optional<Employee>`) containing the object that was found, if any. The call to `Optional` method `get` (line 51) returns the matching Employee object in this example. Even if the stream contained millions of Employee objects, the filter operation would be performed only until a match is found.

## 17.6.3 Sorting Employees By Multiple Fields

Figure 17.12 shows how to use streams to sort objects by *multiple* fields. In this example, we sort Employees by last name, then, for Employees with the same last name, we also sort



them by first name. To do so, we begin by creating two Functions that each receive an Employee and return a String:

- `byFirstName` (line 54) is assigned a method reference for Employee instance method `getFirstName`
- `byLastName` (line 55) is assigned a method reference for Employee instance method `getLastName`

Next, we use these Functions to create a Comparator (`lastThenFirst`; lines 58–59) that first compares two Employees by last name, then compares them by first name. We use Comparator method `comparing` to create a Comparator that calls Function `byLastName` on an Employee to get its last name. On the resulting Comparator, we call Comparator method **`thenComparing`** to create a Comparator that first compares Employees by last name and, *if the last names are equal*, then compares them by first name. Lines 64–65 use this new `lastThenFirst` Comparator to sort the Employees in *ascending* order, then display the results. We reuse the Comparator in lines 71–73, but call its `reversed` method to indicate that the Employees should be sorted in *descending* order by last name, then first name.

```

53 // Functions for getting first and last names from an Employee
54 Function<Employee, String> byFirstName = Employee::getFirstName;
55 Function<Employee, String> byLastName = Employee::getLastName;
56
57 // Comparator for comparing Employees by first name then last name
58 Comparator<Employee> lastThenFirst =
59 Comparator.comparing(byLastName).thenComparing(byFirstName);
60
61 // sort employees by last name, then first name
62 System.out.printf(
63 "%nEmployees in ascending order by last name then first:%n");
64 list.stream()
65 .sorted(lastThenFirst)
66 .forEach(System.out::println);
67
68 // sort employees in descending order by last name, then first name
69 System.out.printf(
70 "%nEmployees in descending order by last name then first:%n");
71 list.stream()
72 .sorted(lastThenFirst.reversed())
73 .forEach(System.out::println);
74

```

|                                                       |        |         |           |
|-------------------------------------------------------|--------|---------|-----------|
| Employees in ascending order by last name then first: |        |         |           |
| Jason                                                 | Blue   | 3200.00 | Sales     |
| Wendy                                                 | Brown  | 4236.40 | Marketing |
| Ashley                                                | Green  | 7600.00 | IT        |
| James                                                 | Indigo | 4700.77 | Marketing |
| Luke                                                  | Indigo | 6200.00 | IT        |
| Matthew                                               | Indigo | 3587.50 | Sales     |
| Jason                                                 | Red    | 5000.00 | IT        |

**Fig. 17.12** | Sorting Employees by last name then first name. (Part I of 2.)

|                                                        |        |         |           |
|--------------------------------------------------------|--------|---------|-----------|
| Employees in descending order by last name then first: |        |         |           |
| Jason                                                  | Red    | 5000.00 | IT        |
| Matthew                                                | Indigo | 3587.50 | Sales     |
| Luke                                                   | Indigo | 6200.00 | IT        |
| James                                                  | Indigo | 4700.77 | Marketing |
| Ashley                                                 | Green  | 7600.00 | IT        |
| Wendy                                                  | Brown  | 4236.40 | Marketing |
| Jason                                                  | Blue   | 3200.00 | Sales     |

**Fig. 17.12** | Sorting Employees by last name then first name. (Part 2 of 2.)

### 17.6.4 Mapping Employees to Unique Last Name Strings

You previously used map operations to perform calculations on int values and to convert Strings to uppercase letters. In both cases, the resulting streams contained values of the same types as the original streams. Figure 17.13 shows how to map objects of one type (Employee) to objects of a different type (String). Lines 77–81 perform the following tasks:

- Line 77 creates a Stream<Employee>.
- Line 78 maps the Employees to their last names using the instance method reference Employee::getName as method map's Function argument. The result is a Stream<String>.
- Line 79 calls Stream method **distinct** on the Stream<String> to eliminate any duplicate String objects in a Stream<String>.
- Line 80 sorts the unique last names.
- Finally, line 81 performs a terminal forEach operation that processes the stream pipeline and outputs the unique last names in sorted order.

Lines 86–89 sort the Employees by last name then first name, then map the Employees to Strings with Employee instance method getName (line 88) and display the sorted names in a terminal forEach operation.

```

75 // display unique employee last names sorted
76 System.out.printf("%nUnique employee last names:%n");
77 list.stream()
78 .map(Employee::getLastName)
79 .distinct()
80 .sorted()
81 .forEach(System.out::println);
82
83 // display only first and last names
84 System.out.printf(
85 "%nEmployee names in order by last name then first name:%n");
86 list.stream()
87 .sorted(lastThenFirst)
88 .map(Employee::getName)
89 .forEach(System.out::println);
90

```

**Fig. 17.13** | Mapping Employee objects to last names and whole names. (Part 1 of 2.)

```

Unique employee last names:
Blue
Brown
Green
Indigo
Red

Employee names in order by last name then first name:
Jason Blue
Wendy Brown
Ashley Green
James Indigo
Luke Indigo
Matthew Indigo
Jason Red

```

**Fig. 17.13** | Mapping Employee objects to last names and whole names. (Part 2 of 2.)

### 17.6.5 Grouping Employees By Department

Figure 17.14 uses Stream method `collect` (line 95) to group Employees by department. Method `collect`'s argument is a Collector that specifies how to summarize the data into a useful form. In this case, we use the Collector returned by Collectors static method **groupingBy**, which receives a Function that classifies the objects in the stream—the values returned by this function are used as the keys in a Map. The corresponding values, by default, are Lists containing the stream elements in a given category. When method `collect` is used with this Collector, the result is a Map<String, List<Employee>> in which each String key is a department and each List<Employee> contains the Employees in that department. We assign this Map to variable `groupedByDepartment`, which is used in lines 96–103 to display the Employees grouped by department. Map method **forEach** performs an operation on each of the Map's key–value pairs. The argument to the method is an object that implements functional interface **BiConsumer**. This interface's `accept` method has two parameters. For Maps, the first parameter represents the key and the second represents the corresponding value.

```

91 // group Employees by department
92 System.out.printf("%nEmployees by department:%n");
93 Map<String, List<Employee>> groupedByDepartment =
94 list.stream()
95 .collect(Collectors.groupingBy(Employee::getDepartment));
96 groupedByDepartment.forEach(
97 (department, employeesInDepartment) ->
98 {
99 System.out.println(department);
100 employeesInDepartment.forEach(
101 employee -> System.out.printf(" %s%n", employee));
102 }
103);
104

```

**Fig. 17.14** | Grouping Employees by department. (Part 1 of 2.)

```

Employees by department:
Sales
 Matthew Indigo 3587.50 Sales
 Jason Blue 3200.00 Sales
IT
 Jason Red 5000.00 IT
 Ashley Green 7600.00 IT
 Luke Indigo 6200.00 IT
Marketing
 James Indigo 4700.77 Marketing
 Wendy Brown 4236.40 Marketing

```

**Fig. 17.14** | Grouping Employees by department. (Part 2 of 2.)

### 17.6.6 Counting the Number of Employees in Each Department

Figure 17.15 once again demonstrates Stream method `collect` and Collectors static method `groupingBy`, but in this case we count the number of Employees in each department. Lines 107–110 produce a `Map<String, Long>` in which each `String` key is a department name and the corresponding `Long` value is the number of Employees in that department. In this case, we use a version of Collectors static method `groupingBy` that receives two arguments—the first is a `Function` that classifies the objects in the stream and the second is another Collector (known as the **downstream Collector**). In this case, we use a call to Collectors static method `counting` as the second argument. This method returns a Collector that counts the number of objects in a given classification, rather than collecting them into a `List`. Lines 111–113 then output the key–value pairs from the resulting `Map<String, Long>`.

```

105 // count number of Employees in each department
106 System.out.printf("\nCount of Employees by department:\n");
107 Map<String, Long> employeeCountByDepartment =
108 list.stream()
109 .collect(Collectors.groupingBy(Employee::getDepartment,
110 Collectors.counting()));
111 employeeCountByDepartment.forEach(
112 (department, count) -> System.out.printf(
113 "%s has %d employee(s)\n", department, count));
114

```

```

Count of Employees by department:
IT has 3 employee(s)
Marketing has 2 employee(s)
Sales has 2 employee(s)

```

**Fig. 17.15** | Counting the number of Employees in each department.

### 17.6.7 Summing and Averaging Employee Salaries

Figure 17.16 demonstrates Stream method `mapToDouble` (lines 119, 126 and 132), which maps objects to double values and returns a `DoubleStream`. In this case, we map Employee

objects to their salaries so that we can calculate the *sum* and *average*. Method `mapToDouble` receives an object that implements the functional interface **ToDoubleFunction** (package `java.util.function`). This interface's **applyAsDouble** method invokes an instance method on an object and returns a double value. Lines 119, 126 and 132 each pass to `mapToDouble` the `Employee` instance method reference `Employee::getSalary`, which returns the current `Employee`'s salary as a `double`. The compiler converts this method reference into an object that implements the functional interface `ToDoubleFunction`.

```

115 // sum of Employee salaries with DoubleStream sum method
116 System.out.printf(
117 "%nSum of Employees' salaries (via sum method): %.2f%n",
118 list.stream()
119 .mapToDouble(Employee::getSalary)
120 .sum());
121
122 // calculate sum of Employee salaries with Stream reduce method
123 System.out.printf(
124 "Sum of Employees' salaries (via reduce method): %.2f%n",
125 list.stream()
126 .mapToDouble(Employee::getSalary)
127 .reduce(0, (value1, value2) -> value1 + value2));
128
129 // average of Employee salaries with DoubleStream average method
130 System.out.printf("Average of Employees' salaries: %.2f%n",
131 list.stream()
132 .mapToDouble(Employee::getSalary)
133 .average()
134 .getAsDouble());
135 } // end main
136 } // end class ProcessingEmployees

```

```

Sum of Employees' salaries (via sum method): 34524.67
Sum of Employees' salaries (via reduce method): 34525.67
Average of Employees' salaries: 4932.10

```

**Fig. 17.16** | Summing and averaging Employee salaries.

Lines 118–120 create a `Stream<Employee>`, map it to a `DoubleStream`, then invoke `DoubleStream` method `sum` to calculate the sum of the `Employees`' salaries. Lines 125–127 also sum the `Employees`' salaries, but do so using `DoubleStream` method `reduce` rather than `sum`—we introduced method `reduce` in Section 17.3 with `IntStreams`. Finally, lines 131–134 calculate the average of the `Employees`' salaries using `DoubleStream` method `average`, which returns an `OptionalDouble` in case the `DoubleStream` does not contain any elements. In this case, we know the stream has elements, so we simply call method `OptionalDouble` method `getAsDouble` to get the result. Recall that you can also use method `orElse` to specify a value that should be used if the `average` method was called on an empty `DoubleStream`, and thus could not calculate the average.

## 17.7 Creating a Stream<String> from a File

Figure 17.17 uses lambdas and streams to summarize the number of occurrences of each word in a file then display a summary of the words in alphabetical order grouped by starting letter. This is commonly called a concordance ([http://en.wikipedia.org/wiki/Concordance\\_\(publishing\)](http://en.wikipedia.org/wiki/Concordance_(publishing))). Concordances are often used to analyze published works. For example, concordances of William Shakespeare's and Christopher Marlowe's works have been used to question whether they are the same person. Figure 17.18 shows the program's output. Line 16 of Fig. 17.17 creates a regular expression `Pattern` that we'll use to split lines of text into their individual words. This `Pattern` represents one or more consecutive white-space characters. (We introduced regular expressions in Section 14.7.)

---

```

1 // Fig. 17.17: StreamOfLines.java
2 // Counting word occurrences in a text file.
3 import java.io.IOException;
4 import java.nio.file.Files;
5 import java.nio.file.Paths;
6 import java.util.Map;
7 import java.util.TreeMap;
8 import java.util.regex.Pattern;
9 import java.util.stream.Collectors;
10
11 public class StreamOfLines
12 {
13 public static void main(String[] args) throws IOException
14 {
15 // Regex that matches one or more consecutive whitespace characters
16 Pattern pattern = Pattern.compile("\\s+");
17
18 // count occurrences of each word in a Stream<String> sorted by word
19 Map<String, Long> wordCounts =
20 Files.lines(Paths.get("Chapter2Paragraph.txt"))
21 .map(line -> line.replaceAll("(?!')\\p{P}", ""))
22 .flatMap(line -> pattern.splitAsStream(line))
23 .collect(Collectors.groupingBy(String::toLowerCase,
24 TreeMap::new, Collectors.counting()));
25
26 // display the words grouped by starting letter
27 wordCounts.entrySet()
28 .stream()
29 .collect(
30 Collectors.groupingBy(entry -> entry.getKey().charAt(0),
31 TreeMap::new, Collectors.toList()))
32 .forEach((letter, wordList) ->
33 {
34 System.out.printf("%n%C%n", letter);
35 wordList.stream().forEach(word -> System.out.printf(
36 "%13s: %d%n", word.getKey(), word.getValue()));
37 });
38 }
39 } // end class StreamOfLines

```

---

**Fig. 17.17** | Counting word occurrences in a text file.

|                 |                |            |
|-----------------|----------------|------------|
| A               | I              | R          |
| a: 2            | inputs: 1      | result: 1  |
| and: 3          | instruct: 1    | results: 2 |
| application: 2  | introduces: 1  | run: 1     |
| arithmetic: 1   |                |            |
| B               | J              | S          |
| begin: 1        | java: 1        | save: 1    |
|                 | jdk: 1         | screen: 1  |
|                 |                | show: 1    |
|                 |                | sum: 1     |
| C               | L              | T          |
| calculates: 1   | last: 1        | that: 3    |
| calculations: 1 | later: 1       | the: 7     |
| chapter: 1      | learn: 1       | their: 2   |
| chapters: 1     |                | then: 2    |
| commandline: 1  | M              | this: 2    |
| compares: 1     | make: 1        | to: 4      |
| comparison: 1   | messages: 2    | tools: 1   |
| compile: 1      |                | two: 2     |
| computer: 1     | N              |            |
| D               | numbers: 2     |            |
| decisions: 1    |                | U          |
| demonstrates: 1 | O              | use: 2     |
| display: 1      | obtains: 1     | user: 1    |
| displays: 2     | of: 1          |            |
|                 | on: 1          |            |
| E               | output: 1      | W          |
| example: 1      |                | we: 2      |
| examples: 1     | P              | with: 1    |
|                 | perform: 1     |            |
| F               | present: 1     | Y          |
| for: 1          | program: 1     | you'll: 2  |
| from: 1         | programming: 1 |            |
|                 | programs: 2    |            |
| H               |                |            |
| how: 2          |                |            |

**Fig. 17.18** | Output for the program of Fig. 17.17 arranged in three columns.

### *Summarizing the Occurrences of Each Word in the File*

Lines 19–24 summarize contents of the text file "Chapter2Paragraph.txt" (which is located in the folder with the example) into a Map<String, Long> in which each String key is a word in the file and the corresponding Long value is the number of occurrences of that word. The statement performs the following tasks:

- Line 20 uses Files method **lines** to create a Stream<String> for reading the lines of text from a file. Class Files (package java.nio.file) is one of many classes throughout the Java APIs that have been enhanced to support Streams.
- Line 21 uses Stream method map to remove all the punctuation, except apostrophes, in the lines of text. The lambda argument represents a Function that invokes String method replaceAll on its String argument. This method receives two arguments—the first is a regular expression String to match and the second is a String with which every match is replaced. In the regular expression,

"(?!')" indicates that the rest of the regular expression should ignore apostrophes (such as in a contraction, like "you'll") and "\\p{P}" matches any punctuation character. For any match, the call to `replaceAll` removes the punctuation by replacing it with an empty `String`. The result of line 21 is an intermediate `Stream<String>` containing the lines without punctuation.

- Line 22 uses `Stream` method **flatMap** to break each line of text into its separate words. Method `flatMap` receives a `Function` that maps an object into a stream of elements. In this case, the object is a `String` containing words and the result is another intermediate `Stream<String>` for the individual words. The lambda in line 22 passes the `String` representing a line of text to `Pattern` method **splitAsStream** (new in Java SE 8), which uses the regular expression specified in the `Pattern` (line 16) to tokenize the `String` into its individual words.
- Lines 23–24 use `Stream` method `collect` to count the frequency of each word and place the words and their counts into the `TreeMap<String, Long>`. Here, we use a version of `Collectors` method `groupingBy` that receives three arguments—a classifier, a `Map` factory and a downstream `Collector`. The classifier is a `Function` that returns objects for use as keys in the resulting `Map`—the method reference `String::toLowerCase` converts each word in the `Stream<String>` to lowercase. The `Map` factory is an object that implements interface `Supplier` and returns a new `Map` collection—the *constructor reference* `TreeMap::new` returns a `TreeMap` that maintains its keys in sorted order. `Collectors.counting()` is the downstream `Collector` that determines the number of occurrences of each key in the stream.

### *Displaying the Summary Grouped by Starting Letter*

Next, lines 27–37 group the key–value pairs in the `Map` `wordCounts` by the keys' first letter. This produces a new `Map` in which each key is a `Character` and the corresponding value is a `List` of the key–value pairs in `wordCounts` in which the key starts with the `Character`. The statement performs the following tasks:

- First we need to get a `Stream` for processing the key–value pairs in `wordCounts`. Interface `Map` does not contain any methods that return `Streams`. So, line 27 calls `Map` method `entrySet` on `wordCounts` to get a `Set` of **Map.Entry** objects that each contain one key–value pair from `wordCounts`. This produces an object of type `Set<Map.Entry<String, Long>>`.
- Line 28 calls `Set` method `stream` to get a `Stream<Map.Entry<String, Long>>`.
- Lines 29–31 call `Stream` method `collect` with three arguments—a classifier, a `Map` factory and a downstream `Collector`. The classifier `Function` in this case gets the key from the `Map.Entry` then uses `String` method `charAt` to get the key's first character—this becomes a `Character` key in the resulting `Map`. Once again, we use the constructor reference `TreeMap::new` as the `Map` factory to create a `TreeMap` that maintains its keys in sorted order. The downstream `Collector` (`Collectors.toList()`) places the `Map.Entry` objects into a `List` collection. The result of `collect` is a `Map<Character, List<Map.Entry<String, Long>>>`.



- Finally, to display the summary of the words and their counts by letter (i.e., the concordance), lines 32–37 pass a lambda to Map method `forEach`. The lambda (a `BiConsumer`) receives two parameters—`letter` and `wordList` represent the `Character` key and the `List` value, respectively, for each key–value pair in the Map produced by the preceding `collect` operation. The body of this lambda has two statements, so it *must* be enclosed in curly braces. The statement in line 34 displays the `Character` key on its own line. The statement in lines 35–36 gets a `Stream<Map.Entry<String, Long>>` from the `wordList`, then calls `Stream` method `forEach` to display the key and value from each `Map.Entry` object.

## 17.8 Generating Streams of Random Values

In Fig. 5.7, we demonstrated rolling a six-sided die 6,000,000 times and summarizing the frequencies of each face using *external iteration* (a `for` loop) and a `switch` statement that determined which counter to increment. We then displayed the results using separate statements that performed external iteration. In Fig. 6.7, we reimplemented Fig. 5.7, replacing the entire `switch` statement with a single statement that incremented counters in an array—that version of rolling the die still used external iteration to produce and summarize 6,000,000 random rolls and to display the final results. Both prior versions of this example, used mutable variables to control the external iteration and to summarize the results. Figure 17.19 reimplements those programs with a *single statement* that does it all, using lambdas, streams, internal iteration and no mutable variables to roll the die 6,000,000 times, calculate the frequencies and display the results.

---

```

1 // Fig. 17.19: RandomIntStream.java
2 // Rolling a die 6,000,000 times with streams
3 import java.security.SecureRandom;
4 import java.util.Map;
5 import java.util.function.Function;
6 import java.util.stream.IntStream;
7 import java.util.stream.Collectors;
8
9 public class RandomIntStream
10 {
11 public static void main(String[] args)
12 {
13 SecureRandom random = new SecureRandom();
14
15 // roll a die 6,000,000 times and summarize the results
16 System.out.printf("%-6s%s%n", "Face", "Frequency");
17 random.ints(6_000_000, 1, 7)
18 .boxed()
19 .collect(Collectors.groupingBy(Function.identity(),
20 Collectors.counting()))
21 .forEach((face, frequency) ->
22 System.out.printf("%-6d%d%n", face, frequency));
23 }
24 } // end class RandomIntStream

```

---

**Fig. 17.19** | Rolling a die 6,000,000 times with streams. (Part I of 2.)

| Face | Frequency |
|------|-----------|
| 1    | 999339    |
| 2    | 999937    |
| 3    | 1000302   |
| 4    | 999323    |
| 5    | 1000183   |
| 6    | 1000916   |

**Fig. 17.19** | Rolling a die 6,000,000 times with streams. (Part 2 of 2.)

### *Creating an **IntStream** of Random Values*

In Java SE 8, class `SecureRandom` has overloaded methods **ints**, **longs** and **doubles**, which it inherits from class `Random` (package `java.util`). These methods return `IntStream`, `LongStream` and `DoubleStream`, respectively, that represent streams of random numbers. Each method has four overloads. We describe the **ints** overloads here—methods **longs** and **doubles** perform the same tasks for streams of long and double values, respectively:

- **ints()**—creates an `IntStream` for an *infinite stream* of random ints. An **infinite stream** has an *unknown* number of elements—you use a short-circuiting terminal operation to complete processing on an infinite stream. We'll use an infinite stream in Chapter 23 to find prime numbers with the Sieve of Eratosthenes.
- **ints(long)**—creates an `IntStream` with the specified number of random ints.
- **ints(int, int)**—creates an `IntStream` for an *infinite stream* of random int values in the range starting with the first argument and up to, but not including, the second argument.
- **ints(long, int, int)**—creates an `IntStream` with the specified number of random int values in the range starting with the first argument and up to, but not including, the second argument.

Line 17 uses the last overloaded version of **ints** to create an `IntStream` of 6,000,000 random integer values in the range 1–6.

### *Converting an **IntStream** to a **Stream<Integer>***

We summarize the roll frequencies in this example by collecting them into a `Map<Integer, Long>` in which each `Integer` key is a side of the die and each `Long` value is the frequency of that side. Unfortunately, Java does not allow primitive values in collections, so to summarize the results in a `Map`, we must first convert the `IntStream` to a `Stream<Integer>`. We do this by calling `IntStream` method **boxed**.

### *Summarizing the Die Frequencies*

Lines 19–20 call `Stream` method **collect** to summarize the results into a `Map<Integer, Long>`. The first argument to `Collectors` method **groupingBy** (line 19) calls static method **identity** from interface `Function`, which creates a `Function` that simply returns its argument. This allows the actual random values to be used as the `Map`'s keys. The second argument to method **groupingBy** counts the number of occurrences of each key.

### *Displaying the Results*

Lines 21–22 call the resulting `Map`'s **forEach** method to display the summary of the results. This method receives an object that implements the `BiConsumer` functional interface as an

argument. Recall that for Maps, the first parameter represents the key and the second represents the corresponding value. The lambda in lines 21–22 uses parameter *face* as the key and *frequency* as the value, and displays the *face* and *frequency*.

## 17.9 Lambda Event Handlers

In Section 12.11, you learned how to implement an event handler using an anonymous inner class. Some event-listener interfaces—such as `ActionListener` and `ItemListener`—are functional interfaces. For such interfaces, you can implement event handlers with lambdas. For example, the following statement from Fig. 12.21:

```
imagesJComboBox.addItemListener(
 new ItemListener() // anonymous inner class
 {
 // handle JComboBox event
 @Override
 public void itemStateChanged(ItemEvent event)
 {
 // determine whether item selected
 if (event.getStateChange() == ItemEvent.SELECTED)
 label.setIcon(icons[
 imagesJComboBox.getSelectedIndex()]);
 }
 } // end anonymous inner class
); // end call to addItemListener
```

which registers an event handler for a `JComboBox` can be implemented more concisely as

```
imagesJComboBox.addItemListener(event -> {
 if (event.getStateChange() == ItemEvent.SELECTED)
 label.setIcon(icons[imagesJComboBox.getSelectedIndex()]);
});
```

For a simple event handler like this one, a lambda significantly reduces the amount of code you need to write.

## 17.10 Additional Notes on Java SE 8 Interfaces

### *Java SE 8 Interfaces Allow Inheritance of Method Implementations*

Functional interfaces *must* contain only one abstract method, but may also contain default methods and static methods that are fully implemented in the interface declarations. For example, the `Function` interface—which is used extensively in functional programming—has methods `apply` (abstract), `compose` (default), and `then` (default) and `identity` (static).

When a class implements an interface with default methods and does *not* override them, the class inherits the default methods' implementations. An interface's designer can now evolve an interface by adding new default and static methods without breaking existing code that implements the interface. For example, interface `Comparator` (Section 16.7.1) now contains many default and static methods, but older classes that implement this interface will still compile and operate properly in Java SE 8.

If one class inherits the same default method from two unrelated interfaces, the class *must* override that method; otherwise, the compiler will not know which method to use, so it will generate a compilation error.

**Java SE 8: @FunctionalInterface Annotation**

You can create your own functional interfaces by ensuring that each contains only one abstract method and zero or more default or static methods. Though not required, you can declare that an interface is a functional interface by preceding it with the **@FunctionalInterface** annotation. The compiler will then ensure that the interface contains only one abstract method; otherwise, it'll generate a compilation error.

**17.11 Java SE 8 and Functional Programming Resources**

Check out the book's web page at

<http://www.deitel.com/books/jhttp10LOV>

for links to the online Deitel Resource Centers that we built as we were writing *Java How to Program, 10/e, Late Objects Version*.

**17.12 Wrap-Up**

In this chapter, you learned about Java SE 8's new functional programming capabilities. We presented many examples, often showing simpler ways to implement tasks that you programmed in earlier chapters.

We overviewed the key functional programming technologies—functional interfaces, lambdas and streams. You learned how to process elements in an `IntStream`—a stream of `int` values. You created an `IntStream` from an array of `ints`, then used intermediate and terminal stream operations to create and process a stream pipeline that produced a result. You used lambdas to create anonymous methods that implemented functional interfaces.

We showed how to use a `forEach` terminal operation to perform an operation on each stream element. We used reduction operations to count the number of stream elements, determine the minimum and maximum values, and sum and average the values. You also learned how to use method `reduce` to create your own reduction operations.

You used intermediate operations to filter elements that matched a predicate and map elements to new values—in each case, these operations produced intermediate streams on which you could perform additional processing. You also learned how to sort elements in ascending and descending order and how to sort objects by multiple fields.

We demonstrated how to store the results of a stream pipeline into a collection for later use. To do so, you took advantage of various predefined `Collector` implementations provided by class `Collectors`. You also learned how to use a `Collector` to group elements into categories.

You learned that various Java SE 8 classes have been enhanced to support functional programming. You then used `Files` method `lines` to get a `Stream<String>` that read lines of text from a file and used `SecureRandom` method `ints` to get an `IntStream` of random values. You also learned how to convert an `IntStream` into a `Stream<Integer>` (via method `boxed`) so that you could use `Stream` method `collect` to summarize the frequencies of the `Integer` values and store the results in a `Map`.

Next, you learned how to implement an event-handling functional interface using a lambda. Finally, we presented some additional information about Java SE 8 interfaces and streams. In the next chapter, we discuss recursive programming in which methods call themselves either directly or indirectly.

## Summary

### *Section 17.1 Introduction*

- Prior to Java SE 8, Java supported three programming paradigms—procedural programming, object-oriented programming and generic programming. Java SE 8 adds functional programming.
- The new language and library capabilities that support functional programming were added to Java as part of Project Lambda.

### *Section 17.2 Functional Programming Technologies Overview*

- Prior to functional programming, you typically determined what you wanted to accomplish, then specified the precise steps to accomplish that task.
- Using a loop to iterate over a collection of elements is known as external iteration (p. 723) and requires accessing the elements sequentially. Such iteration also requires mutable variables.
- In functional programming (p. 724), you specify what you want to accomplish in a task, but not how to accomplish it.
- Letting the library determine how to iterate over a collection of elements is known as internal iteration (p. 724). Internal iteration is easier to parallelize.
- Functional programming focuses on immutability (p. 724)—not modifying the data source being processed or any other program state.

#### *Section 17.2.1 Functional Interfaces*

- Functional interfaces are also known as single abstract method (SAM) interfaces.
- Package `java.util.function` contains six basic functional interfaces `BinaryOperator`, `Consumer`, `Function`, `Predicate`, `Supplier` and `UnaryOperator`.
- There are many specialized versions of the six basic functional interfaces for use with `int`, `long` and `double` primitive values. There are also generic customizations of `Consumer`, `Function` and `Predicate` for binary operations—that is, methods that take two arguments.

#### *Section 17.2.2 Lambda Expressions*

- A lambda expression (p. 725) represents an anonymous method—a shorthand notation for implementing a functional interface.
- The type of a lambda is the type of the functional interface that the lambda implements.
- Lambda expressions can be used anywhere functional interfaces are expected.
- A lambda consists of a parameter list followed by the arrow token (`->`, p. 725) and a body, as in:

*(parameterList) -> {statements}*

For example, the following lambda receives two `ints` and returns their sum:

```
(int x, int y) -> {return x + y;}
```

This lambda's body is a statement block that may contain one or more statements enclosed in curly braces.

- A lambda's parameter types may be omitted, as in:

```
(x, y) -> {return x + y;}
```

in which case, the parameter and return types are determined by the lambda's context.

- A lambda with a one-expression body can be written as:

```
(x, y) -> x + y
```

In this case, the expression's value is implicitly returned.

- When the parameter list contains only one parameter, the parentheses may be omitted, as in:  
`value -> System.out.printf("%d ", value)`
- A lambda with an empty parameter list is defined with `()` to the left of the arrow token (`->`), as in:  
`() -> System.out.println("Welcome to lambdas!")`
- There are also specialized shorthand forms of lambdas that are known as method references.

### Section 17.2.3 Streams

- Streams (p. 726) are objects that implement interface `Stream` (from the package `java.util.stream`) and enable you to perform functional programming tasks. There are also specialized stream interfaces for processing `int`, `long` or `double` values.
- Streams move elements through a sequence of processing steps—known as a stream pipeline—that begins with a data source, performs various intermediate operations on the data source's elements and ends with a terminal operation. A stream pipeline is formed by chaining method calls.
- Unlike collections, streams do not have their own storage—once a stream is processed, it cannot be reused, because it does not maintain a copy of the original data source.
- An intermediate operation (p. 726) specifies tasks to perform on the stream's elements and always results in a new stream.
- Intermediate operations are lazy (p. 726)—they aren't performed until a terminal operation is invoked. This allows library developers to optimize stream-processing performance.
- A terminal operation (p. 726) initiates processing of a stream pipeline's intermediate operations and produces a result. Terminal operations are eager (p. 726)—they perform the requested operation when they are called.

### Section 17.3 *IntStream Operations*

- An `IntStream` (package `java.util.stream`) is a specialized stream for manipulating `int` values.

#### Section 17.3.1 *Creating an IntStream and Displaying Its Values with the forEach Terminal Operation*

- `IntStream` static method `of` (p. 730) receives an `int` array as an argument and returns an `IntStream` for processing the array's values.
- `IntStream` method `forEach` (a terminal operation; p. 730) receives as its argument an object that implements the `IntConsumer` functional interface (package `java.util.function`). This interface's `accept` method receives one `int` value and performs a task with it.
- The Java compiler can infer the types of a lambda's parameters and the type returned by a lambda from the context in which the lambda is used. This is determined by the lambda's target type (p. 730)—the functional interface type that is expected where the lambda appears in the code.
- Lambdas may use `final` local variables or effectively `final` (p. 730) local variables.
- A lambda that refers to a local variable in the enclosing lexical scope is known as a capturing lambda.
- A lambda can use the outer class's `this` reference without qualifying it with the outer class's name.
- The parameter names and variable names that you use in lambdas cannot be the same as any other local variables in the lambda's lexical scope; otherwise, a compilation error occurs.

#### Section 17.3.2 *Terminal Operations **count**, **min**, **max**, **sum** and **average***

- Class `IntStream` provides terminal operations for common stream reductions—`count` (p. 731) returns the number of elements, `min` returns the smallest `int`, `max` returns the largest `int`, `sum` returns the sum of all the `ints` and `average` returns an `OptionalDouble` (package `java.util`) containing the average of the `ints` as a value of type `double`.

- Class `OptionalDouble`'s `getAsDouble` method returns the `double` in the object or throws a `NoSuchElementException`. To prevent this exception, you can call method `orElse`, which returns the `OptionalDouble`'s value if there is one, or the value you pass to `orElse`, otherwise.
- `IntStream` method `summaryStatistics` performs the count, min, max, sum and average operations in one pass of an `IntStream`'s elements and returns the results as an `IntSummaryStatistics` object (package `java.util`).

### *Section 17.3.3 Terminal Operation **reduce***

- You can define your own reductions for an `IntStream` by calling its `reduce` method. The first argument is a value that helps you begin the reduction operation and the second argument is an object that implements the `IntBinaryOperator` (p. 732) functional interface.
- Method `reduce`'s first argument is formally called an identity value (p. 732)—a value that, when combined with any stream element using the `IntBinaryOperator` produces that element's original value.

### *Section 17.3.4 Intermediate Operations: Filtering and Sorting **IntStream** Values*

- You filter elements to produce a stream of intermediate results that match a predicate. `IntStream` method `filter` (p. 733) receives an object that implements the `IntPredicate` functional interface (package `java.util.function`).
- `IntStream` method `sorted` (a lazy operation) orders the elements of the stream into ascending order (by default). All prior intermediate operations in the stream pipeline must be complete so that method `sorted` knows which elements to sort.
- Method `filter` a stateless intermediate operation—it does not require any information about other elements in the stream in order to test whether the current element satisfies the predicate.
- Method `sorted` is a stateful intermediate operation that requires information about all of the other elements in the stream in order to sort them.
- Interface `IntPredicate`'s default method `and` (p. 733) performs a logical AND operation with short-circuit evaluation between the `IntPredicate` on which it's called and its `IntPredicate` argument.
- Interface `IntPredicate`'s default method `negate` (p. 733) reverses the `boolean` value of the `IntPredicate` on which it's called.
- Interface `IntPredicate` default method `or` (p. 733) performs a logical OR operation with short-circuit evaluation between the `IntPredicate` on which it's called and its `IntPredicate` argument.
- You can use the interface `IntPredicate` default methods to compose more complex conditions.

### *Section 17.3.5 Intermediate Operation: Mapping*

- Mapping is an intermediate operation that transforms a stream's elements to new values and produces a stream containing the resulting (possibly different type) elements.
- `IntStream` method `map` (a stateless intermediate operation; p. 734) receives an object that implements the `IntUnaryOperator` functional interface (package `java.util.function`).

### *Section 17.3.6 Creating Streams of ints with **IntStream** Methods **range** and **rangeClosed***

- `IntStream` methods `range` (p. 735) and `rangeClosed` each produce an ordered sequence of `int` values. Both methods take two `int` arguments representing the range of values. Method `range` produces a sequence of values from its first argument up to, but not including, its second argument. Method `rangeClosed` produces a sequence of values including both of its arguments.

## *Section 17.4 **Stream<Integer>** Manipulations*

- Class `Array`'s `stream` method is used to create a `Stream` from an array of objects.

**Section 17.4.1 Creating a *Stream<Integer>***

- Interface `Stream` (package `java.util.stream`; p. 736) is a generic interface for performing stream operations on objects. The types of objects that are processed are determined by the `Stream`'s source.
- Class `Arrays` provides overloaded stream methods for creating `IntStreams`, `LongStreams` and `DoubleStreams` from `int`, `long` and `double` arrays or from ranges of elements in the arrays.

**Section 17.4.2 Sorting a *Stream* and Collecting the Results**

- `Stream` method `sorted` (p. 737) sorts a stream's elements into ascending order by default.
- To create a collection containing a stream pipeline's results, you can use `Stream` method `collect` (a terminal operation). As the stream pipeline is processed, method `collect` performs a mutable reduction operation that places the results into an object, such as a `List`, `Map` or `Set`.
- Method `collect` with one argument receives an object that implements interface `Collector` (package `java.util.stream`), which specifies how to perform the mutable reduction.
- Class `Collectors` (package `java.util.stream`) provides static methods that return predefined `Collector` implementations.
- `Collectors` method `toList` transforms a `Stream<T>` into a `List<T>` collection.

**Section 17.4.3 Filtering a *Stream* and Storing the Results for Later Use**

- `Stream` method `filter` (p. 737) receives a `Predicate` and results in a stream of objects that match the `Predicate`. `Predicate` method `test` returns a `boolean` indicating whether the argument satisfies a condition. Interface `Predicate` also has methods `and`, `negate` and `or`.

**Section 17.4.5 Sorting Previously Collected Results**

- Once you place the results of a stream pipeline into a collection, you can create a new stream from the collection for performing additional stream operations on the prior results.

**Section 17.5.1 Mapping Strings to Uppercase Using a Method Reference**

- `Stream` method `map` (p. 739) maps each element to a new value and produces a new stream with the same number of elements as the original stream.
- A method reference (p. 739) is a shorthand notation for a lambda expression.
- `ClassName::instanceMethodName` represents a method reference for an instance method of a class. Creates a one-parameter lambda that invokes the instance method on the lambda's argument and returns the method's result.
- `objectName::instanceMethodName` represents a method reference for an instance method that should be called on a specific object. Creates a one-parameter lambda that invokes the instance method on the specified object—passing the lambda's argument to the instance method—and returns the method's result.
- `ClassName::staticMethodName` represents a method reference for a static method of a class. Creates a one-parameter lambda in which the lambda's argument is passed to the specified a static method and the lambda returns the method's result.
- `ClassName::new` represents a constructor reference. Creates a lambda that invokes the no-argument constructor of the specified class to create and initialize a new object of that class.

**Section 17.5.2 Filtering Strings Then Sorting Them in Case-Insensitive Ascending Order**

- `Stream` method `sorted` (p. 740) can receive a `Comparator` as an argument to specify how to compare stream elements for sorting.
- By default, method `sorted` uses the natural order for the stream's element type.



- For Strings, the natural order is case sensitive, which means that "Z" is less than "a". Passing the predefined Comparator `String.CASE_INSENSITIVE_ORDER` performs a case-insensitive sort.

### *Section 17.5.3 Filtering Strings Then Sorting Them in Case-Insensitive Descending Order*

- Functional interface `Comparator`'s default method `reversed` (p. 740) reverses an existing `Comparator`'s ordering.

### *Section 17.6.1 Creating and Displaying a List<Employee>*

- When the instance method reference `System.out::println` is passed to `Stream` method `forEach`, it's converted by the compiler into an object that implements the `Consumer` functional interface. This interface's `accept` method receives one argument and returns `void`. In this case, the `accept` method passes the argument to the `System.out` object's `println` instance method.

### *Section 17.6.2 Filtering Employees with Salaries in a Specified Range*

- To reuse a lambda, you can assign it to a variable of the appropriate functional interface type.
- The `Comparator` interface's static method `comparing` (p. 745) receives a `Function` that's used to extract a value from an object in the stream for use in comparisons and returns a `Comparator` object.
- A nice performance feature of lazy evaluation is the ability to perform short circuit evaluation—that is, to stop processing the stream pipeline as soon as the desired result is available.
- `Stream` method `findFirst` is a short-circuiting terminal operation that processes the stream pipeline and terminates processing as soon as the first object from the stream pipeline is found. The method returns an `Optional` containing the object that was found, if any.

### *Section 17.6.3 Sorting Employees By Multiple Fields*

- To sort objects by two fields, you create a `Comparator` that uses two `Functions`. First you call `Comparator` method `comparing` to create a `Comparator` with the first `Function`. On the resulting `Comparator`, you call method `thenComparing` with the second `Function`. The resulting `Comparator` compares objects using the first `Function` then, for objects that are equal, compares them by the second `Function`.

### *Section 17.6.4 Mapping Employees to Unique Last Name Strings*

- You can map objects in a stream to different types to produce another stream with the same number of elements as the original stream.
- `Stream` method `distinct` (p. 746) eliminates duplicate objects in a stream.

### *Section 17.6.5 Grouping Employees By Department*

- `Collectors` static method `groupingBy` (p. 747) with one argument receives a `Function` that classifies objects in the stream—the values returned by this function are used as the keys in a `Map`. The corresponding values, by default, are `Lists` containing the stream elements in a given category.
- `Map` method `forEach` performs an operation on each key–value pair. The method receives an object that implements functional interface `BiConsumer`. This interface's `accept` method has two parameters. For `Maps`, the first represents the key and the second the corresponding value.

### *Section 17.6.6 Counting the Number of Employees in Each Department*

- `Collectors` static method `groupingBy` with two arguments receives a `Function` that classifies the objects in the stream and another `Collector` (known as the downstream `Collector`; p. 748).
- `Collectors` static method `counting` returns a `Collector` that counts the number of objects in a given classification, rather than collecting them into a `List`.

*Section 17.6.7 Summing and Averaging Employee Salaries*

- Stream method `mapToDouble` (p. 748) maps objects to double values and returns a `DoubleStream`. The method receives an object that implements the functional interface `ToDoubleFunction` (package `java.util.function`). This interface's `applyAsDouble` method invokes an instance method on an object and returns a double value.

*Section 17.7 Creating a Stream<String> from a File*

- Files method `lines` creates a `Stream<String>` for reading the lines of text from a file.
- Stream method `flatMap` (p. 752) receives a `Function` that maps an object into a stream—e.g., a line of text into words.
- Pattern method `splitAsStream` (p. 752) uses a regular expression to tokenize a `String`.
- Collectors method `groupingBy` with three arguments receives a classifier, a `Map` factory and a downstream `Collector`. The classifier is a `Function` that returns objects which are used as keys in the resulting `Map`. The `Map` factory is an object that implements interface `Supplier` and returns a new `Map` collection. The downstream `Collector` determines how to collect each group's elements.
- Map method `entrySet` returns a `Set` of `Map.Entry` objects containing the `Map`'s key–value pairs.
- Set method `stream` returns a stream for processing the `Set`'s elements.

*Section 17.8 Generating Streams of Random Values*

- Class `SecureRandom`'s methods `ints` (p. 754), `longs` and `doubles` (inherited from class `Random`) return `IntStream`, `LongStream` and `DoubleStream`, respectively, for streams of random numbers.
- Method `ints` with no arguments creates an `IntStream` for an infinite stream (p. 754) of random `int` values. An infinite stream is a stream with an unknown number of elements—you use a short-circuiting terminal operation to complete processing on an infinite stream.
- Method `ints` with a `long` argument creates an `IntStream` with the specified number of random `int` values.
- Method `ints` with two `int` arguments creates an `IntStream` for an infinite stream of random `int` values in the range starting with the first argument and up to, but not including, the second.
- Method `ints` with a `long` and two `int` arguments creates an `IntStream` with the specified number of random `int` values in the range starting with the first argument and up to, but not including, the second.
- To convert an `IntStream` to a `Stream<Integer>` call `IntStream` method `boxed`.
- Function static method `identity` creates a `Function` that simply returns its argument.

*Section 17.9 Lambda Event Handlers*

- Some event-listener interfaces are functional interfaces (p. 755). For such interfaces, you can implement event handlers with lambdas. For a simple event handler, a lambda significantly reduces the amount of code you need to write.

*Section 17.10 Additional Notes on Java SE 8 Interfaces*

- Functional interfaces must contain only one abstract method, but may also contain default methods and static methods that are fully implemented in the interface declarations.
- When a class implements an interface with default methods and does not override them, the class inherits the default methods' implementations. An interface's designer can now evolve an interface by adding new default and static methods without breaking existing code that implements the interface.

- If one class inherits the same default method from two interfaces, the class must override that method; otherwise, the compiler will generate a compilation error.
- You can create your own functional interfaces by ensuring that each contains only one abstract method and zero or more default or static methods.
- You can declare that an interface is a functional interface by preceding it with the `@FunctionalInterface` annotation. The compiler will then ensure that the interface contains only one abstract method; otherwise, it'll generate a compilation error.

## Self-Review Exercises

**17.1** Fill in the blanks in each of the following statements:

- Lambda expressions implement \_\_\_\_\_.
- Functional programs are easier to \_\_\_\_\_ (i.e., perform multiple operations simultaneously) so that your programs can take advantage of multi-core architectures to enhance performance.
- With \_\_\_\_\_ iteration the library determines how to access all the elements in a collection to perform a task.
- The functional interface \_\_\_\_\_ contains method `apply` that takes two `T` arguments, performs an operation on them (such as a calculation) and returns a value of type `T`.
- The functional interface \_\_\_\_\_ contains method `test` that takes a `T` argument and returns a `boolean`, and tests whether the `T` argument satisfies a condition.
- A(n) \_\_\_\_\_ represents an anonymous method—a shorthand notation for implementing a functional interface.
- Intermediate stream operations are \_\_\_\_\_—they aren't performed until a terminal operation is invoked.
- The terminal stream operation \_\_\_\_\_ performs processing on every element in a stream.
- \_\_\_\_\_ lambdas use local variables from the enclosing lexical scope.
- A performance feature of lazy evaluation is the ability to perform \_\_\_\_\_ evaluation—that is, to stop processing the stream pipeline as soon as the desired result is available.
- For `Maps`, a `BiConsumer`'s first parameter represents the \_\_\_\_\_ and its second represents the corresponding \_\_\_\_\_.

**17.2** State whether each of the following is *true* or *false*. If *false*, explain why.

- Lambda expressions can be used anywhere functional interfaces are expected.
- Terminal operations are lazy—they perform the requested operation when they are called.
- Method `reduce`'s first argument is formally called an identity value—a value that, when combined with a stream element using the `IntBinaryOperator` produces the stream element's original value. For example, when summing the elements, the identity value is 1 and when getting the product of the elements the identity value is 0.
- Stream method `findFirst` is a short-circuiting terminal operation that processes the stream pipeline but terminates processing as soon as an object is found.
- Stream method `flatMap` receives a `Function` that maps a stream into an object. For example, the object could be a `String` containing words and the result could be another intermediate `Stream<String>` for the individual words.
- When a class implements an interface with default methods and overrides them, the class inherits the default methods' implementations. An interface's designer can now evolve an interface by adding new default and static methods without breaking existing code that implements the interface.

**17.3** Write a lambda or method reference for each of the following tasks:

a) Write a lambda that can be used in place of the following anonymous inner class:

```
new IntConsumer()
{
 public void accept(int value)
 {
 System.out.printf("%d ", value);
 }
}
```

b) Write a method reference that can be used in place of the following lambda:

```
(String s) -> {return s.toUpperCase();}
```

c) Write a no-argument lambda that implicitly returns the String "Welcome to lambdas!".

d) Write a method reference for Math method sqrt.

e) Create a one-parameter lambda that returns the cube of its argument.

## Answers to Self-Review Exercises

**17.1** a) functional interfaces. b) parallelize. c) internal. d) BinaryOperator<T>. e) Predicate<T>. f) lambda expression. g) lazy. h) forEach. i) Capturing. j) short circuit. k) key, value.

**17.2** a) True. b) False. Terminal operations are *eager*—they perform the requested operation when they are called. c) False. When summing the elements, the identity value is 0 and when getting the product of the elements the identity value is 1. d) True. e) False. Stream method flatMap receives a Function that maps an object into a stream. f) False. Should say: "...does not override them, ..." instead of "overrides them."

**17.3** a) value -> System.out.printf("%d ", value)

b) String::toUpperCase

c) () -> "Welcome to lambdas!"

d) Math::sqrt

e) value -> value \* value \* value

## Exercises

**17.4** Fill in the blanks in each of the following statements:

a) Stream \_\_\_\_\_ are formed from stream sources, intermediate operations and terminal operations.

b) The following code uses the technique of \_\_\_\_\_ iteration:

```
int sum = 0;

for (int counter = 0; counter < values.length; counter++)
 sum += values[counter];
```

c) Functional programming capabilities focus on \_\_\_\_\_—not modifying the data source being processed or any other program state.

d) The functional interface \_\_\_\_\_ contains method accept that takes a T argument and returns void; accept performs a task with its T argument, such as outputting the object, invoking a method of the object, etc.

e) The functional interface \_\_\_\_\_ contains method get that takes no arguments and produces a value of type T—this is often used to create a collection object in which a stream operation's results are placed.

- f) Streams are objects that implement interface `Stream` and enable you to perform functional programming tasks on \_\_\_\_\_ of elements.
- g) The intermediate stream operation \_\_\_\_\_ results in a stream containing only the elements that satisfy a condition.
- h) \_\_\_\_\_ place the results of processing a stream pipeline into a collection such as a `List`, `Set` or `Map`.
- i) Calls to `filter` and other intermediate streams are lazy—they aren't evaluated until an eager \_\_\_\_\_ operation is performed.
- j) Pattern method \_\_\_\_\_ (new in Java SE 8) uses a regular expression to tokenize a `String`.
- k) Functional interfaces *must* contain only one \_\_\_\_\_ method, but may also contain \_\_\_\_\_ methods and static methods that are fully implemented in the interface declarations.

**17.5** State whether each of the following is *true* or *false*. If *false*, explain why.

- a) An intermediate operation specifies tasks to perform on the stream's elements; this is efficient because it avoids creating a new stream.
- b) Reduction operations take all values in the stream and turn them into a new stream.
- c) If you need an ordered sequence of `int` values, you can create an `IntStream` containing such values with `IntStream` methods `range` and `rangeClosed`. Both methods take two `int` arguments representing the range of values. Method `rangeClosed` produces a sequence of values from its first argument up to, but not including, its second argument. Method `range` produces a sequence of values including both of its arguments.
- d) Class `Files` (package `java.nio.file`) is one of many classes throughout the Java APIs that have been enhanced to support Streams.
- e) Interface `Map` does not contain any methods that return Streams.
- f) The `Function` functional interface—which is used extensively in functional programming—has methods `apply` (abstract), `compose` (abstract), `andThen` (default) and `identity` (static).
- g) If one class inherits the same default method from two interfaces, the class *must* override that method; otherwise, the compiler does not know which method to use, so it generates a compilation error.

**17.6** Write a lambda or method reference for each of the following tasks:

- a) Write a lambda expression that receives two `double` parameters `a` and `b` and returns their product. Use the lambda form that explicitly lists the type of each parameter.
- b) Rewrite the lambda expression in Part (a) using the lambda form that does not list the type of each parameter.
- c) Rewrite the lambda expression in Part (b) using the lambda form that implicitly returns the value of the lambda's body expression.
- d) Write a no-argument lambda that implicitly returns the string `"Welcome to lambdas!"`.
- e) Write a constructor reference for class `ArrayList`.
- f) Reimplement the following statement using a lambda as the event handler:

```
button.addActionListener(
 new ActionListener()
 {
 public void actionPerformed(ActionEvent event)
 {
 JOptionPane.showMessageDialog(ParentFrame.this,
 "JButton event handler");
 }
 }
);
```

**17.7** Assuming that `list` is a `List<Integer>`, explain in detail the stream pipeline:

```
list.stream()
 .filter(value -> value % 2 != 0)
 .sum()
```

**17.8** Assuming that `random` is a `SecureRandom` object, explain in detail the stream pipeline:

```
random.ints(1000000, 1, 3)
 .boxed()
 .collect(Collectors.groupingBy(Function.identity(),
 Collectors.counting()))
 .forEach((side, frequency) ->
 System.out.printf("%-6d%d%n", side, frequency));
```

**17.9** (*Summarizing the Characters in a File*) Modify the program of Fig. 17.17 to summarize the number of occurrences of every character in the file.

**17.10** (*Summarizing the File Types in a Directory*) Section 15.3 demonstrated how to get information about files and directories on disk. In addition, you used a `DirectoryStream` to display the contents of a directory. Interface `DirectoryStream` now contains default method entries, which returns a `Stream`. Use the techniques from Section 15.3, `DirectoryStream` method entries, lambdas and streams to summarize the types of files in a specified directory.

**17.11** (*Manipulating a Stream<Invoice>*) Use the class `Invoice` provided in the exercises folder with this chapter's examples to create an array of `Invoice` objects. Use the sample data shown in Fig. 17.20. Class `Invoice` includes four properties—a `PartNumber` (type `int`), a `PartDescription` (type `String`), a `Quantity` of the item being purchased (type `int`) and a `Price` (type `double`). Perform the following queries on the array of `Invoice` objects and display the results:

- Use lambdas and streams to sort the `Invoice` objects by `PartDescription`, then display the results.
- Use lambdas and streams to sort the `Invoice` objects by `Price`, then display the results.
- Use lambdas and streams to map each `Invoice` to its `PartDescription` and `Quantity`, sort the results by `Quantity`, then display the results.
- Use lambdas and streams to map each `Invoice` to its `PartDescription` and the value of the `Invoice` (i.e., `Quantity * Price`). Order the results by `Invoice` value.
- Modify Part (d) to select the `Invoice` values in the range \$200 to \$500.

| Part number | Part description | Quantity | Price |
|-------------|------------------|----------|-------|
| 83          | Electric sander  | 7        | 57.98 |
| 24          | Power saw        | 18       | 99.99 |
| 7           | Sledge hammer    | 11       | 21.50 |
| 77          | Hammer           | 76       | 11.99 |
| 39          | Lawn mower       | 3        | 79.50 |
| 68          | Screwdriver      | 106      | 6.99  |
| 56          | Jig saw          | 21       | 11.00 |
| 3           | Wrench           | 34       | 7.50  |

**Fig. 17.20** | Sample data for Exercise 17.11.

**17.12** (*Duplicate Word Removal*) Write a program that inputs a sentence from the user (assume no punctuation), then determines and displays the unique words in alphabetical order. Treat uppercase and lowercase letters the same.

**17.13** (*Sorting Letters and Removing Duplicates*) Write a program that inserts 30 random letters into a `List<Character>`. Perform the following operations and display your results:

- a) Sort the `List` in ascending order.
- b) Sort the `List` in descending order.
- c) Display the `List` in ascending order with duplicates removed.

**17.14** (*Mapping Then Reducing An `IntStream` for Parallelization*) The lambda you pass to a stream's `reduce` method should be *associative*—that is, regardless of the order in which its subexpressions are evaluated, the result should be the same. The lambda expression in lines 34–36 of Fig. 17.5 is *not* associative. If you were to use parallel streams (Chapter 23, Concurrency) with that lambda, you might get incorrect results for the sum of the squares, depending on the order in which the subexpressions are evaluated. The proper way to implement lines 34–36 would be *first* to map each `int` value to the square of that value, *then* to reduce the stream to the sum of the squares. Modify Fig. 17.5 to implement lines 34–36 in this manner.

# 18

## Recursion

*O! thou hast damnable iteration, and art indeed able to corrupt a saint.*

—William Shakespeare

*It's a poor sort of memory that only works backwards.*

—Lewis Carroll

*Life can only be understood backwards; but it must be lived forwards.*

—Soren Kierkegaard

### Objectives

In this chapter you'll:

- Learn the concept of recursion.
- Write and use recursive methods.
- Determine the base case and recursion step in a recursive algorithm.
- Learn how recursive method calls are handled by the system.
- Learn the differences between recursion and iteration, and when to use each.
- Learn what fractals are and how to draw them using recursion.
- Learn what recursive backtracking is and why it's an effective problem-solving technique.





|      |                                                                       |        |                                              |
|------|-----------------------------------------------------------------------|--------|----------------------------------------------|
| 18.1 | Introduction                                                          | 18.7   | Recursion vs. Iteration                      |
| 18.2 | Recursion Concepts                                                    | 18.8   | Towers of Hanoi                              |
| 18.3 | Example Using Recursion: Factorials                                   | 18.9   | Fractals                                     |
| 18.4 | Reimplementing Class<br>FactorialCalculator Using<br>Class BigInteger | 18.9.1 | Koch Curve Fractal                           |
| 18.5 | Example Using Recursion: Fibonacci<br>Series                          | 18.9.2 | (Optional) Case Study: Lo Feather<br>Fractal |
| 18.6 | Recursion and the Method-Call Stack                                   | 18.10  | Recursive Backtracking                       |
|      |                                                                       | 18.11  | Wrap-Up                                      |

Summary | Self-Review Exercises | Answers to Self-Review Exercises | Exercises

## 18.1 Introduction

The programs we've discussed so far are generally structured as methods that call one another in a hierarchical manner. For some problems, it's useful to have a method *call itself*. A method that does so is known as a **recursive method**. A recursive method can call itself either *directly* or *indirectly through another method*. Recursion is an important topic discussed at length in upper-level computer science courses. In this chapter, we consider recursion conceptually, then present several programs containing recursive methods. Figure 18.1 summarizes the recursion examples and exercises in this book.

| Chapter | Recursion examples and exercises in this book                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |
|---------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 18      | Factorial Method (Figs. 18.3 and 18.4)<br>Fibonacci Method (Fig. 18.5)<br>Towers of Hanoi (Fig. 18.11)<br>Fractals (Figs. 18.18 and 18.19)<br>What Does This Code Do? (Exercise 18.7, Exercise 18.12 and Exercise 18.13)<br>Find the Error in the Following Code (Exercise 18.8)<br>Raising an Integer to an Integer Power (Exercise 18.9)<br>Visualizing Recursion (Exercise 18.10)<br>Greatest Common Divisor (Exercise 18.11)<br>Determine Whether a String Is a Palindrome (Exercise 18.14)<br>Eight Queens (Exercise 18.15)<br>Print an Array (Exercise 18.16)<br>Print an Array Backward (Exercise 18.17)<br>Minimum Value in an Array (Exercise 18.18)<br>Star Fractal (Exercise 18.19)<br>Maze Traversal Using Recursive Backtracking (Exercise 18.20)<br>Generating Mazes Randomly (Exercise 18.21)<br>Mazes of Any Size (Exercise 18.22)<br>Time to Calculate a Fibonacci Number (Exercise 18.23) |

**Fig. 18.1** | Summary of the recursion examples and exercises in this text. (Part I of 2.)

| Chapter | Recursion examples and exercises in this book                                                                                                                                                                                                                                         |
|---------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 19      | Merge Sort (Fig. 19.6)<br>Linear Search (Exercise 19.8)<br>Binary Search (Exercise 19.9)<br>Quicksort (Exercise 19.10)                                                                                                                                                                |
| 21      | Binary-Tree Insert (Fig. 21.17)<br>Preorder Traversal of a Binary Tree (Fig. 21.17)<br>Inorder Traversal of a Binary Tree (Fig. 21.17)<br>Postorder Traversal of a Binary Tree (Fig. 21.17)<br>Print a Linked List Backward (Exercise 21.20)<br>Search a Linked List (Exercise 21.21) |

**Fig. 18.1** | Summary of the recursion examples and exercises in this text. (Part 2 of 2.)

## 18.2 Recursion Concepts

Recursive problem-solving approaches have a number of elements in common. When a recursive method is called to solve a problem, it actually is capable of solving only the *simplest case(s)*, or **base case(s)**. If the method is called with a *base case*, it returns a result. If the method is called with a more complex problem, it divides the problem into two conceptual pieces—a piece that the method knows how to do and a piece that it does not know how to do. To make recursion feasible, the latter piece must resemble the original problem, but be a slightly simpler or smaller version of it. Because this new problem resembles the original problem, the method calls a fresh *copy* of itself to work on the smaller problem—this is referred to as a **recursive call** and is also called the **recursion step**. The recursion step normally includes a **return** statement, because its result will be combined with the portion of the problem the method knew how to solve to form a result that will be passed back to the original caller. This concept of separating the problem into two smaller portions is a form of the *divide-and-conquer* approach introduced in Chapter 5.

The recursion step executes while the original method call is still active (i.e., it has not finished executing). It can result in many more recursive calls as the method divides each new subproblem into two conceptual pieces. For the recursion to eventually terminate, each time the method calls itself with a simpler version of the original problem, the sequence of smaller and smaller problems must *converge on a base case*. When the method recognizes the base case, it returns a result to the previous copy of the method. A sequence of returns ensues until the original method call returns the final result to the caller. We'll illustrate this process with a concrete example in Section 18.3.

A recursive method may call another method, which may in turn make a call back to the recursive method. This is known as an **indirect recursive call** or **indirect recursion**. For example, method A calls method B, which makes a call back to method A. This is still recursion, because the second call to method A is made while the first call to method A is active—that is, the first call to method A has not yet finished executing (because it's waiting on method B to return a result to it) and has not returned to method A's original caller.

To better understand the concept of recursion, let's look at an example that's quite familiar to computer users—the recursive definition of a file system directory on a computer. A computer normally stores related files in a directory. A directory can be empty, can contain files and/or can contain other directories (usually referred to as subdirectories). Each of these subdirectories, in turn, may also contain both files and directories. If we want to list each file in a directory (including all the files in the directory's subdirectories), we need to create a method that first lists the initial directory's files, then makes recursive calls to list the files in each of that directory's subdirectories. The base case occurs when a directory is reached that does not contain any subdirectories. At this point, all the files in the original directory have been listed and no further recursion is necessary.

### 18.3 Example Using Recursion: Factorials

Let's write a recursive program to perform a popular mathematical calculation. Consider the *factorial* of a positive integer  $n$ , written  $n!$  (pronounced “ $n$  factorial”), which is the product

$$n \cdot (n-1) \cdot (n-2) \cdot \dots \cdot 1$$

with  $1!$  equal to 1 and  $0!$  defined to be 1. For example,  $5!$  is the product  $5 \cdot 4 \cdot 3 \cdot 2 \cdot 1$ , which is equal to 120.

The factorial of integer number (where  $\text{number} \geq 0$ ) can be calculated *iteratively* (non-recursively) using a **for** statement as follows:

```
factorial = 1;
for (int counter = number; counter >= 1; counter--)
 factorial *= counter;
```

A recursive declaration of the factorial calculation for integers greater than 1 is arrived at by observing the following relationship:

$$n! = n \cdot (n-1)!$$

For example,  $5!$  is clearly equal to  $5 \cdot 4!$ , as shown by the following equations:

$$\begin{aligned} 5! &= 5 \cdot 4 \cdot 3 \cdot 2 \cdot 1 \\ 5! &= 5 \cdot (4 \cdot 3 \cdot 2 \cdot 1) \\ 5! &= 5 \cdot (4!) \end{aligned}$$

The evaluation of  $5!$  would proceed as shown in Fig. 18.2. Figure 18.2(a) shows how the succession of recursive calls proceeds until  $1!$  (the base case) is evaluated to be 1, which terminates the recursion. Figure 18.2(b) shows the values returned from each recursive call to its caller until the final value is calculated and returned.

Figure 18.3 uses recursion to calculate and print the factorials of the integers 0 through 21. The recursive method `factorial` (lines 7–13) first tests to determine whether a *terminating condition* (line 9) is true. If `number` is less than or equal to 1 (the base case), `factorial` returns 1, no further recursion is necessary and the method returns. (A precondition of calling method `factorial` in this example is that its argument must be non-negative.) If `number` is greater than 1, line 12 expresses the problem as the product of `number` and a recursive call to `factorial` evaluating the factorial of `number - 1`, which is a slightly smaller problem than the original calculation, `factorial(number)`.




Fig. 18.2 | Recursive evaluation of 5!.

```

1 // Fig. 18.3: FactorialCalculator.java
2 // Recursive factorial method.
3
4 public class FactorialCalculator
5 {
6 // recursive method factorial (assumes its parameter is >= 0)
7 public static long factorial(long number)
8 {
9 if (number <= 1) // test for base case
10 return 1; // base cases: 0! = 1 and 1! = 1
11 else // recursion step
12 return number * factorial(number - 1);
13 }
14
15 // output factorials for values 0-21
16 public static void main(String[] args)
17 {
18 // calculate the factorials of 0 through 21
19 for (int counter = 0; counter <= 21; counter++)
20 System.out.printf("%d! = %d\n", counter, factorial(counter));
21 }
22 } // end class FactorialCalculator

```

```

0! = 1
1! = 1
2! = 2
3! = 6
4! = 24
5! = 120

```

Fig. 18.3 | Recursive factorial method. (Part I of 2.)

```

...
12! = 479001600 — 12! causes overflow for int variables
...
20! = 2432902008176640000
21! = -4249290049419214848 — 21! causes overflow for long variables

```

**Fig. 18.3** | Recursive factorial method. (Part 2 of 2.)



### Common Programming Error 18.1

*Either omitting the base case or writing the recursion step incorrectly so that it does not converge on the base case can cause a logic error known as **infinite recursion**, where recursive calls are continuously made until memory is exhausted or the method-call stack overflows. This error is analogous to the problem of an infinite loop in an iterative (non-recursive) solution.*

Method `main` (lines 16–21) displays the factorials of 0–21. The call to the `factorial` method occurs in line 20. Method `factorial` receives a parameter of type `long` and returns a result of type `long`. The program's output shows that factorial values become large quickly. We use type `long` (which can represent relatively large integers) so the program can calculate factorials greater than 12!. Unfortunately, the `factorial` method produces large values so quickly that we exceed the largest `long` value when we attempt to calculate 21!, as you can see in the last line of the program's output.

Due to the limitations of integral types, `float` or `double` variables may ultimately be needed to calculate factorials of larger numbers. This points to a weakness in some programming languages—namely, that they aren't easily *extended with new types* to handle unique application requirements. As we saw in Chapter 9, Java is an *extensible* language that allows us to create arbitrarily large integers if we wish. In fact, package `java.math` provides classes `BigInteger` and `BigDecimal` explicitly for arbitrary precision calculations that cannot be performed with primitive types. You can learn more about these classes at

[docs.oracle.com/javase/7/docs/api/java/math/BigInteger.html](https://docs.oracle.com/javase/7/docs/api/java/math/BigInteger.html)  
[docs.oracle.com/javase/7/docs/api/java/math/BigDecimal.html](https://docs.oracle.com/javase/7/docs/api/java/math/BigDecimal.html)

## 18.4 Reimplementing Class FactorialCalculator Using Class BigInteger

Figure 18.4 reimplements class `FactorialCalculator` using `BigInteger` variables. To demonstrate larger values than what `long` variables can store, we calculate the factorials of the numbers 0–50. Line 3 imports class `BigInteger` from package `java.math`. The new `factorial` method (lines 8–15) receives a `BigInteger` as an argument and returns a `BigInteger`.

```

1 // Fig. 18.4: FactorialCalculator.java
2 // Recursive factorial method.
3 import java.math.BigInteger;
4

```

**Fig. 18.4** | Factorial calculations with a recursive method. (Part 1 of 2.)

```

5 public class FactorialCalculator
6 {
7 // recursive method factorial (assumes its parameter is >= 0)
8 public static BigInteger factorial(BigInteger number)
9 {
10 if (number.compareTo(BigInteger.ONE) <= 0) // test base case
11 return BigInteger.ONE; // base cases: 0! = 1 and 1! = 1
12 else // recursion step
13 return number.multiply(
14 factorial(number.subtract(BigInteger.ONE)));
15 }
16
17 // output factorials for values 0-50
18 public static void main(String[] args)
19 {
20 // calculate the factorials of 0 through 50
21 for (int counter = 0; counter <= 50; counter++)
22 System.out.printf("%d! = %d%n", counter,
23 factorial(BigInteger.valueOf(counter)));
24 }
25 } // end class FactorialCalculator

```

```

0! = 1
1! = 1
2! = 2
3! = 6
...
21! = 51090942171709440000 — 21! and larger values no longer cause overflow
22! = 112400072777607680000
...
47! = 258623241511168180642964355153611979969197632389120000000000
48! = 12413915592536072670862289047373375038521486354677760000000000
49! = 608281864034267560872252163321295376887552831379210240000000000
50! = 30414093201713378043612608166064768844377641568960512000000000000

```

**Fig. 18.4** | Factorial calculations with a recursive method. (Part 2 of 2.)

Since `BigInteger` is *not* a primitive type, we can't use the arithmetic, relational and equality operators with `BigIntegers`; instead, we must use `BigInteger` methods to perform these tasks. Line 10 tests for the base case using `BigInteger` method `compareTo`. This method compares the `BigInteger` `number` that calls the method to the method's `BigInteger` argument. The method returns `-1` if the `BigInteger` that calls the method is less than the argument, `0` if they're equal or `1` if the `BigInteger` that calls the method is greater than the argument. Line 10 compares the `BigInteger` `number` with the `BigInteger` constant `ONE`, which represents the integer value 1. If `compareTo` returns `-1` or `0`, then `number` is less than or equal to 1 (the base case) and the method returns the constant `BigInteger.ONE`. Otherwise, lines 13–14 perform the recursion step using `BigInteger` methods `multiply` and `subtract` to implement the calculations required to multiply `number` by the factorial of `number - 1`. The program's output shows that `BigInteger` handles the large values produced by the factorial calculation.

## 18.5 Example Using Recursion: Fibonacci Series

The **Fibonacci** series,

0, 1, 1, 2, 3, 5, 8, 13, 21, ...

begins with 0 and 1 and has the property that each subsequent Fibonacci number is the sum of the previous two. This series occurs in nature and describes a form of spiral. The ratio of successive Fibonacci numbers converges on a constant value of 1.618..., a number that has been called the **golden ratio** or the **golden mean**. Humans tend to find the golden mean aesthetically pleasing. Architects often design windows, rooms and buildings whose length and width are in the ratio of the golden mean. Postcards are often designed with a golden-mean length-to-width ratio.

The Fibonacci series may be defined recursively as follows:

```
fibonacci(0) = 0
fibonacci(1) = 1
fibonacci(n) = fibonacci(n - 1) + fibonacci(n - 2)
```

There are *two base cases* for the Fibonacci calculation: `fibonacci(0)` is defined to be 0, and `fibonacci(1)` to be 1. The program in Fig. 18.5 calculates the *i*th Fibonacci number recursively, using method `fibonacci` (lines 10–18). Method `main` (lines 21–26) tests `fibonacci`, displaying the Fibonacci values of 0–40. The variable `counter` created in the `for` header (line 23) indicates which Fibonacci number to calculate for each iteration of the loop. Fibonacci numbers tend to become large quickly (though not as quickly as factorials). Therefore, we use type `BigInteger` as the parameter type and the return type of method `fibonacci`.

---

```
1 // Fig. 18.5: FibonacciCalculator.java
2 // Recursive fibonacci method.
3 import java.math.BigInteger;
4
5 public class FibonacciCalculator
6 {
7 private static BigInteger TWO = BigInteger.valueOf(2);
8
9 // recursive declaration of method fibonacci
10 public static BigInteger fibonacci(BigInteger number)
11 {
12 if (number.equals(BigInteger.ZERO) ||
13 number.equals(BigInteger.ONE)) // base cases
14 return number;
15 else // recursion step
16 return fibonacci(number.subtract(BigInteger.ONE)).add(
17 fibonacci(number.subtract(TWO)));
18 }
19
20 // displays the fibonacci values from 0-40
21 public static void main(String[] args)
22 {
```

---

**Fig. 18.5** | Recursive fibonacci method. (Part I of 2.)

```

23 for (int counter = 0; counter <= 40; counter++)
24 System.out.printf("Fibonacci of %d is: %d\n", counter,
25 fibonacci(BigInteger.valueOf(counter)));
26 }
27 } // end class FibonacciCalculator

```

```

Fibonacci of 0 is: 0
Fibonacci of 1 is: 1
Fibonacci of 2 is: 1
Fibonacci of 3 is: 2
Fibonacci of 4 is: 3
Fibonacci of 5 is: 5
Fibonacci of 6 is: 8
Fibonacci of 7 is: 13
Fibonacci of 8 is: 21
Fibonacci of 9 is: 34
Fibonacci of 10 is: 55
...
Fibonacci of 37 is: 24157817
Fibonacci of 38 is: 39088169
Fibonacci of 39 is: 63245986
Fibonacci of 40 is: 102334155

```

**Fig. 18.5** | Recursive fibonacci method. (Part 2 of 2.)


The call to method `fibonacci` (line 25) from `main` is *not* a recursive call, but all subsequent calls to `fibonacci` performed from lines 16–17 of Fig. 18.5 are recursive, because at that point the calls are initiated by method `fibonacci` itself. Each time `fibonacci` is called, it immediately tests for the *base cases*—number equal to 0 or number equal to 1 (lines 12–13). We use `BigInteger` constants `ZERO` and `ONE` to represent the values 0 and 1, respectively. If the condition in lines 12–13 is true, `fibonacci` simply returns `number`, because `fibonacci(0)` is 0 and `fibonacci(1)` is 1. Interestingly, if `number` is greater than 1, the recursion step generates *two* recursive calls (lines 16–17), each for a slightly smaller problem than the original call to `fibonacci`. Lines 16–17 use `BigInteger` methods `add` and `subtract` to help implement the recursive step. We also use a constant of type `BigInteger` named `TWO` that we defined at line 7.

### Analyzing the Calls to Method `Fibonacci`

Figure 18.6 shows how method `fibonacci` evaluates `fibonacci(3)`. At the bottom of the figure we're left with the values 1, 0 and 1—the results of evaluating the *base cases*. The first two return values (from left to right), 1 and 0, are returned as the values for the calls `fibonacci(1)` and `fibonacci(0)`. The sum 1 plus 0 is returned as the value of `fibonacci(2)`. This is added to the result (1) of the call to `fibonacci(1)`, producing the value 2. This final value is then returned as the value of `fibonacci(3)`.

Figure 18.6 raises some interesting issues about *the order in which Java compilers evaluate the operands of operators*. This order is different from that in which operators are applied to their operands—namely, the order dictated by the rules of operator precedence. From Figure 18.6, it appears that while `fibonacci(3)` is being evaluated, two recursive calls will be made—`fibonacci(2)` and `fibonacci(1)`. But in what order will they be





**Fig. 18.6** | Set of recursive calls for `fibonacci(3)`.

made? *The Java language specifies that the order of evaluation of the operands is from left to right.* Thus, the call `fibonacci(2)` is made first and the call `fibonacci(1)` second.

A word of caution is in order about recursive programs like the one we use here to generate Fibonacci numbers. Each invocation of the `fibonacci` method that does not match one of the *base cases* (0 or 1) results in *two more recursive calls* to the `fibonacci` method. Hence, this set of recursive calls rapidly gets out of hand. Calculating the Fibonacci value of 20 with the program in Fig. 18.5 requires 21,891 calls to the `fibonacci` method; calculating the Fibonacci value of 30 requires 2,692,537 calls! As you try to calculate larger Fibonacci values, you'll notice that each consecutive Fibonacci number you use the application to calculate results in a substantial increase in calculation time and in the number of calls to the `fibonacci` method. For example, the Fibonacci value of 31 requires 4,356,617 calls, and the Fibonacci value of 32 requires 7,049,155 calls! As you can see, the number of calls to `fibonacci` increases quickly—1,664,080 additional calls between Fibonacci values of 30 and 31 and 2,692,538 additional calls between Fibonacci values of 31 and 32! The difference in the number of calls made between Fibonacci values of 31 and 32 is more than 1.5 times the difference in the number of calls for Fibonacci values between 30 and 31. Problems of this nature can humble even the world's most powerful computers. [Note: In the field of complexity theory, computer scientists study how hard algorithms work to complete their tasks. Complexity issues are discussed in detail in the upper-level computer science curriculum course generally called "Algorithms." We introduce various complexity issues in Chapter 19, Searching, Sorting and Big O.] In this chapter's exercises, you'll be asked to enhance the Fibonacci program of Fig. 18.5 so that it calculates the approximate amount of time required to perform the calculation. For this purpose, you'll call static `System` method `currentTimeMillis`, which takes no arguments and returns the computer's current time in milliseconds.




#### Performance Tip 18.1

*Avoid Fibonacci-style recursive programs, because they result in an exponential "explosion" of method calls.*

## 18.6 Recursion and the Method-Call Stack


In Chapter 5, the *stack* data structure was introduced in the context of understanding how Java performs method calls. We discussed both the *method-call stack* and *stack frames*. In this section, we'll use these concepts to demonstrate how the program-execution stack handles *recursive* method calls.

Let's begin by returning to the Fibonacci example—specifically, calling method `fibonacci` with the value 3, as in Fig. 18.6. To show the *order* in which the method calls' stack frames are placed on the stack, we've lettered the method calls in Fig. 18.7.



**Fig. 18.7** | Method calls made within the call `fibonacci(3)`.

When the first method call (A) is made, a *stack frame* containing the value of the local variable `number` (3, in this case) is *pushed* onto the *program-execution stack*. This stack, including the stack frame for method call A, is illustrated in part (a) of Fig. 18.8. [Note: We use a simplified stack here. An actual program-execution stack and its stack frames would be more complex than in Fig. 18.8, containing such information as where the method call is to *return* to when it has completed execution.]



**Fig. 18.8** | Method calls on the program-execution stack.

Within method call A, method calls B and E are made. The original method call has not yet completed, so its stack frame remains on the stack. The first method call to be made from within A is method call B, so the stack frame for method call B is pushed onto the stack on top of the one for method call A. Method call B must execute and complete before method call E is made. Within method call B, method calls C and D will be made. Method call C is made first, and its stack frame is pushed onto the stack [part (b) of Fig. 18.8]. Method call B has not yet finished, and its stack frame is still on the method-call stack. When method call C executes, it makes no further method calls, but simply returns the value 1. When this method returns, its stack frame is popped off the top of the stack. The method call at the top of the stack is now B, which continues to execute by performing method call D. The stack frame for method call D is pushed onto the stack [part (c) of Fig. 18.8]. Method call D completes without making any more method calls and returns the value 0. The stack frame for this method call is then popped off the stack. Now, both method calls made from within method call B have returned. Method call B continues to execute, returning the value 1. Method call B completes, and its stack frame is popped off the stack. At this point, the stack frame for method call A is at the top of the stack and the method continues its execution. This method makes method call E, whose stack frame is now pushed onto the stack [part (d) of Fig. 18.8]. Method call E completes and returns the value 1. The stack frame for this method call is popped off the stack, and once again method call A continues to execute. At this point, method call A will not be making any other method calls and can finish its execution, returning the value 2 to A's caller ( $\text{fibonacci}(3) = 2$ ). A's stack frame is popped off the stack. The executing method is always the one whose stack frame is at the top of the stack, and the stack frame for that method contains the values of its local variables.

## 18.7 Recursion vs. Iteration

We've studied methods `factorial` and `fibonacci`, which can easily be implemented either recursively or iteratively. In this section, we compare the two approaches and discuss why you might choose one approach over the other in a particular situation.

Both iteration and recursion are *based on a control statement*: Iteration uses a repetition statement (e.g., `for`, `while` or `do...while`), whereas recursion uses a selection statement (e.g., `if`, `if...else` or `switch`). Both iteration and recursion involve *repetition*: Iteration explicitly uses a repetition statement, whereas recursion achieves repetition through repeated method calls. Iteration and recursion each involve a *termination test*: Iteration terminates when the loop-continuation condition fails, whereas recursion terminates when a base case is reached. Iteration with counter-controlled repetition and recursion both *gradually approach termination*: Iteration keeps modifying a counter until the counter assumes a value that makes the loop-continuation condition fail, whereas recursion keeps producing smaller versions of the original problem until the base case is reached. Both iteration and recursion *can occur infinitely*: An infinite loop occurs with iteration if the loop-continuation test never becomes false, whereas infinite recursion occurs if the recursion step does not reduce the problem each time in a manner that converges on the base case, or if the base case is not tested.

To illustrate the differences between iteration and recursion, let's examine an iterative solution to the factorial problem (Fig. 18.9). A repetition statement is used (lines 12–13) rather than the selection statement of the recursive solution (lines 9–12 of Fig. 18.3). Both

solutions use a termination test. In the recursive solution (Fig. 18.3), line 9 tests for the *base case*. In the iterative solution, line 12 of Fig. 18.9 tests the loop-continuation condition—if the test fails, the loop terminates. Finally, instead of producing smaller versions of the original problem, the iterative solution uses a counter that is modified until the loop-continuation condition becomes false.

---

```

1 // Fig. 18.9: FactorialCalculator.java
2 // Iterative factorial method.
3
4 public class FactorialCalculator
5 {
6 // recursive declaration of method factorial
7 public long factorial(long number)
8 {
9 long result = 1;
10
11 // iterative declaration of method factorial
12 for (long i = number; i >= 1; i--)
13 result *= i;
14
15 return result;
16 }
17
18 // output factorials for values 0-10
19 public static void main(String[] args)
20 {
21 // calculate the factorials of 0 through 10
22 for (int counter = 0; counter <= 10; counter++)
23 System.out.printf("%d! = %d\n", counter, factorial(counter));
24 }
25 } // end class FactorialCalculator

```

```

0! = 1
1! = 1
2! = 2
3! = 6
4! = 24
5! = 120
6! = 720
7! = 5040
8! = 40320
9! = 362880
10! = 3628800

```

**Fig. 18.9** | Iterative factorial method.

Recursion has many *negatives*. It repeatedly invokes the mechanism, and consequently the *overhead, of method calls*. This repetition can be *expensive* in terms of both processor time and memory space. Each recursive call causes another *copy* of the method (actually, only the method's variables, stored in the stack frame) to be created—this set of copies *can consume considerable memory space*. Since iteration occurs within a method, repeated method calls and extra memory assignment are avoided.



### Software Engineering Observation 18.1

*Any problem that can be solved recursively can also be solved iteratively. A recursive approach is normally preferred over an iterative approach when the recursive approach more naturally mirrors the problem and results in a program that is easier to understand and debug. A recursive approach can often be implemented with fewer lines of code. Another reason to choose a recursive approach is that an iterative one might not be apparent.*



### Performance Tip 18.2

*Avoid using recursion in situations requiring high performance. Recursive calls take time and consume additional memory.*



### Common Programming Error 18.2


*Accidentally having a nonrecursive method call itself either directly or indirectly through another method can cause infinite recursion.*

## 18.8 Towers of Hanoi

Earlier in this chapter we studied methods that can be easily implemented both recursively and iteratively. Now, we present a problem whose recursive solution demonstrates the elegance of recursion, and whose iterative solution may not be as apparent.

The **Towers of Hanoi** is one of the classic problems every budding computer scientist must grapple with. Legend has it that in a temple in the Far East, priests are attempting to move a stack of golden disks from one diamond peg to another (Fig. 18.10). The initial stack has 64 disks threaded onto one peg and arranged from bottom to top by decreasing size. The priests are attempting to move the stack from one peg to another under the constraints that exactly one disk is moved at a time and at no time may a larger disk be placed above a smaller disk. Three pegs are provided, one being used for temporarily holding disks. Supposedly, the world will end when the priests complete their task, so there's little incentive for us to facilitate their efforts.

Let's assume that the priests are attempting to move the disks from peg 1 to peg 3. We wish to develop an algorithm that prints the precise sequence of peg-to-peg disk transfers.



**Fig. 18.10** | Towers of Hanoi for the case with four disks.

If we try to find an iterative solution, we'll likely find ourselves hopelessly “knotted up” in managing the disks. Instead, attacking this problem recursively quickly yields a solution. Moving  $n$  disks can be viewed in terms of moving only  $n - 1$  disks (hence the recursion) as follows:

1. Move  $n - 1$  disks from peg 1 to peg 2, using peg 3 as a temporary holding area.
2. Move the last disk (the largest) from peg 1 to peg 3.
3. Move  $n - 1$  disks from peg 2 to peg 3, using peg 1 as a temporary holding area.

The process ends when the last task involves moving  $n = 1$  disk (i.e., the base case). This task is accomplished by moving the disk, without using a temporary holding area.

In Fig. 18.11, method `solveTowers` (lines 6–25) solves the Towers of Hanoi, given the total number of disks (in this case 3), the starting peg, the ending peg, and the temporary holding peg as parameters. The base case (lines 10–14) occurs when only one disk needs to be moved from the starting peg to the ending peg. In the recursion step (lines 18–24), line 18 moves disks - 1 disks from the first peg (`sourcePeg`) to the temporary holding peg (`tempPeg`). When all but one of the disks have been moved to the temporary peg, line 21 moves the largest disk from the start peg to the destination peg. Line 24 finishes the rest of the moves by calling the method `solveTowers` to recursively move disks - 1 disks from the temporary peg (`tempPeg`) to the destination peg (`destinationPeg`), this time using the first peg (`sourcePeg`) as the temporary peg. Line 35 in `main` calls the recursive `solveTowers` method, which outputs the steps to the command prompt.

---

```

1 // Fig. 18.11: TowersOfHanoi.java
2 // Towers of Hanoi solution with a recursive method.
3 public class TowersOfHanoi
4 {
5 // recursively move disks between towers
6 public static void solveTowers(int disks, int sourcePeg,
7 int destinationPeg, int tempPeg)
8 {
9 // base case -- only one disk to move
10 if (disks == 1)
11 {
12 System.out.printf("%n%d --> %d", sourcePeg, destinationPeg);
13 return;
14 }
15
16 // recursion step -- move (disk - 1) disks from sourcePeg
17 // to tempPeg using destinationPeg
18 solveTowers(disks - 1, sourcePeg, tempPeg, destinationPeg);
19
20 // move last disk from sourcePeg to destinationPeg
21 System.out.printf("%n%d --> %d", sourcePeg, destinationPeg);
22
23 // move (disks - 1) disks from tempPeg to destinationPeg
24 solveTowers(disks - 1, tempPeg, destinationPeg, sourcePeg);
25 }
26

```

---

**Fig. 18.11** | Towers of Hanoi solution with a recursive method. (Part 1 of 2.)

```

27 public static void main(String[] args)
28 {
29 int startPeg = 1; // value 1 used to indicate startPeg in output
30 int endPeg = 3; // value 3 used to indicate endPeg in output
31 int tempPeg = 2; // value 2 used to indicate tempPeg in output
32 int totalDisks = 3; // number of disks
33
34 // initial nonrecursive call: move all disks.
35 solveTowers(totalDisks, startPeg, endPeg, tempPeg);
36 }
37 } // end class TowersOfHanoi

```

```

1 --> 3
1 --> 2
3 --> 2
1 --> 3
2 --> 1
2 --> 3
1 --> 3

```


**Fig. 18.11** | Towers of Hanoi solution with a recursive method. (Part 2 of 2.)

## 18.9 Fractals

A **fractal** is a geometric figure that can be generated from a pattern repeated recursively (Fig. 18.12). The figure is modified by recursively applying the pattern to each segment of the original figure. Although such figures had been studied before the 20th century, it was the mathematician Benoit Mandelbrot who in the 1970s introduced the term “fractal,” along with the specifics of how a fractal is created and the practical applications of fractals. Mandelbrot’s fractal geometry provides mathematical models for many complex forms found in nature, such as mountains, clouds and coastlines. Fractals have many uses in mathematics and science. They can be used to better understand systems or patterns that appear in nature (e.g., ecosystems), in the human body (e.g., in the folds of the brain), or in the universe (e.g., galaxy clusters). Not all fractals resemble objects in nature. Drawing fractals has become a popular art form. Fractals have a **self-similar property**—when subdivided into parts, each resembles a reduced-size copy of the whole. Many fractals yield an exact copy of the original when a portion of the fractal is magnified—such a fractal is said to be **strictly self-similar**.

### 18.9.1 Koch Curve Fractal

As an example, let’s look at the strictly self-similar **Koch Curve** fractal (Fig. 18.12). It’s formed by removing the middle third of each line in the drawing and replacing it with two lines that form a point, such that if the middle third of the original line remained, an equilateral triangle would be formed. Formulas for creating fractals often involve removing all or part of the previous fractal image. This pattern has already been determined for this fractal—we focus here on how to use those formulas in a recursive solution.



**Fig. 18.12** | Koch Curve fractal.

We start with a straight line (Fig. 18.12(a)) and apply the pattern, creating a triangle from the middle third (Fig. 18.12(b)). We then apply the pattern again to each straight line, resulting in Fig. 18.12(c). Each time the pattern is applied, we say that the fractal is at a new **level**, or **depth** (sometimes the term **order** is also used). Fractals can be displayed at many levels—for instance, a fractal at level 3 has had three iterations of the pattern applied (Fig. 18.12(d)). After only a few iterations, this fractal begins to look like a portion of a snowflake (Fig. 18.12(e and f)). Since this is a strictly self-similar fractal, each portion of it contains an exact copy of the fractal. In Fig. 18.12(f), for example, we’ve highlighted a portion of the fractal with a dashed box. If the image in this box were increased in size, it would look exactly like the entire fractal of part (f).

A similar fractal, the **Koch Snowflake**, is similar to the Koch Curve but begins with a triangle rather than a line. The same pattern is applied to each side of the triangle, resulting in an image that looks like an enclosed snowflake. For simplicity, we’ve chosen to focus on the Koch Curve.


### 18.9.2 (Optional) Case Study: Lo Feather Fractal

We now demonstrate the use of recursion to draw fractals by writing a program to create a strictly self-similar fractal. We call this the “Lo feather fractal,” named for Sin Han Lo, a Deitel & Associates colleague who created it. The fractal will eventually resemble one-half of a feather (see the outputs in Fig. 18.19). The base case, or fractal level of 0, begins as a line between two points, A and B (Fig. 18.13). To create the next higher level, we find the mid-point (C) of the line. To calculate the location of point C, use the following formula:

$$\begin{aligned} xC &= (xA + xB) / 2; \\ yC &= (yA + yB) / 2; \end{aligned}$$



[*Note:* The  $x$  and  $y$  to the left of each letter refer to the  $x$ -coordinate and  $y$ -coordinate of that point, respectively. For instance,  $x_A$  refers to the  $x$ -coordinate of point A, while  $y_C$  refers to the  $y$ -coordinate of point C. In our diagrams we denote the point by its letter, followed by two numbers representing the  $x$ - and  $y$ -coordinates.]




**Fig. 18.13** | “Lo feather fractal” at level 0.


To create this fractal, we also must find a point D that lies left of segment AC and creates an isosceles right triangle ADC. To calculate point D’s location, use the following formulas:

$$\begin{aligned} x_D &= x_A + (x_C - x_A) / 2 - (y_C - y_A) / 2; \\ y_D &= y_A + (y_C - y_A) / 2 + (x_C - x_A) / 2; \end{aligned}$$


We now move from level 0 to level 1 as follows: First, add points C and D (as in Fig. 18.14). Then, remove the original line and add segments DA, DC and DB. The remaining lines will curve at an angle, causing our fractal to look like a feather. For the next level of the fractal, this algorithm is repeated on each of the three lines in level 1. For each line, the formulas above are applied, where the former point D is now considered to be point A, while the other end of each line is considered to be point B. Figure 18.15 contains the line from level 0 (now a dashed line) and the three added lines from level 1. We’ve changed point D to be point A, and the original points A, C and B to B1, B2 and B3, respectively. The preceding formulas have been used to find the new points C and D on each line. These points are also numbered 1–3 to keep track of which point is associated with each line. The points C1 and D1, for instance, represent points C and D associated with the line formed from points A to B1. To achieve level 2, the three lines in Fig. 18.15 are removed and replaced with new lines from the C and D points just added. Figure 18.16 shows the new lines (the lines from level 2 are shown as dashed lines for your convenience). Figure 18.17 shows level 2 without the dashed lines from level 1. Once this process has been repeated several times, the fractal created will begin to look like one-half of a feather, as shown in the output of Fig. 18.19. We’ll present the code for this application shortly.




**Fig. 18.14** | Determining points C and D for level 1 of the “Lo feather fractal.”



**Fig. 18.15** | “Lo feather fractal” at level 1, with C and D points determined for level 2. [Note: The fractal at level 0 is included as a dashed line as a reminder of where the line was located in relation to the current fractal.]



**Fig. 18.16** | “Lo feather fractal” at level 2, with dashed lines from level 1 provided.



**Fig. 18.17** | “Lo feather fractal” at level 2.

The application in Fig. 18.18 defines the user interface for drawing this fractal (shown at the end of Fig. 18.19). The interface consists of three buttons—one for the user to change the color of the fractal, one to increase the level of recursion and one to decrease the level of recursion. A `JLabel` keeps track of the current level of recursion, which is modified by calling method `setLevel`, to be discussed shortly. Lines 15–16 specify constants `WIDTH` and `HEIGHT` to be 400 and 480, respectively, for the size of the `JFrame`. The user triggers an `ActionEvent` by clicking the **Color** button. The event handler for this button is registered in lines 37–54. The method `actionPerformed` displays a `JColorChooser`. This dialog returns the selected `Color` object or blue (if the user presses **Cancel** or closes the dialog without pressing **OK**). Line 51 calls the `setColor` method in class `FractalJPanel` to update the color.

```

1 // Fig. 18.18: Fractal.java
2 // Fractal user interface.
3 import java.awt.Color;
4 import java.awt.FlowLayout;
5 import java.awt.event.ActionEvent;
6 import java.awt.event.ActionListener;
7 import javax.swing.JFrame;
8 import javax.swing.JButton;
9 import javax.swing.JLabel;
10 import javax.swing.JPanel;
11 import javax.swing.JColorChooser;
12
13 public class Fractal extends JFrame
14 {
15 private static final int WIDTH = 400; // define width of GUI
16 private static final int HEIGHT = 480; // define height of GUI
17 private static final int MIN_LEVEL = 0;
18 private static final int MAX_LEVEL = 15;
19
20 // set up GUI
21 public Fractal()
22 {

```

**Fig. 18.18** | Fractal user interface. (Part I of 3.)

---

```

23 super("Fractal");
24
25 // set up levelJLabel to add to controlJPanel
26 final JLabel levelJLabel = new JLabel("Level: 0");
27
28 final FractalJPanel drawSpace = new FractalJPanel(0);
29
30 // set up control panel
31 final JPanel controlJPanel = new JPanel();
32 controlJPanel.setLayout(new FlowLayout());
33
34 // set up color button and register listener
35 final JButton changeColorJButton = new JButton("Color");
36 controlJPanel.add(changeColorJButton);
37 changeColorJButton.addActionListener(
38 new ActionListener() // anonymous inner class
39 {
40 // process changeColorJButton event
41 @Override
42 public void actionPerformed(ActionEvent event)
43 {
44 Color color = JColorChooser.showDialog(
45 Fractal.this, "Choose a color", Color.BLUE);
46
47 // set default color, if no color is returned
48 if (color == null)
49 color = Color.BLUE;
50
51 drawSpace.setColor(color);
52 }
53 } // end anonymous inner class
54); // end addActionListener
55
56 // set up decrease level button to add to control panel and
57 // register listener
58 final JButton decreaseLevelJButton = new JButton("Decrease Level");
59 controlJPanel.add(decreaseLevelJButton);
60 decreaseLevelJButton.addActionListener(
61 new ActionListener() // anonymous inner class
62 {
63 // process decreaseLevelJButton event
64 @Override
65 public void actionPerformed(ActionEvent event)
66 {
67 int level = drawSpace.getLevel();
68 --level;
69
70 // modify level if possible
71 if ((level >= MIN_LEVEL) &&
72 (level <= MAX_LEVEL))
73 {
74 levelJLabel.setText("Level: " + level);

```

---

**Fig. 18.18** | Fractal user interface. (Part 2 of 3.)

```

75 drawSpace.setLevel(level);
76 repaint();
77 }
78 }
79 } // end anonymous inner class
80); // end addActionListener
81
82 // set up increase level button to add to control panel
83 // and register listener
84 final JButton increaseLevelJButton = new JButton("Increase Level");
85 controlJPanel.add(increaseLevelJButton);
86 increaseLevelJButton.addActionListener(
87 new ActionListener() // anonymous inner class
88 {
89 // process increaseLevelJButton event
90 @Override
91 public void actionPerformed(ActionEvent event)
92 {
93 int level = drawSpace.getLevel();
94 ++level;
95
96 // modify level if possible
97 if ((level >= MIN_LEVEL) &&
98 (level <= MAX_LEVEL))
99 {
100 levelJLabel.setText("Level: " + level);
101 drawSpace.setLevel(level);
102 repaint();
103 }
104 }
105 } // end anonymous inner class
106); // end addActionListener
107
108 controlJPanel.add(levelJLabel);
109
110 // create mainJPanel to contain controlJPanel and drawSpace
111 final JPanel mainJPanel = new JPanel();
112 mainJPanel.add(controlJPanel);
113 mainJPanel.add(drawSpace);
114
115 add(mainJPanel); // add JPanel to JFrame
116
117 setSize(WIDTH, HEIGHT); // set size of JFrame
118 setVisible(true); // display JFrame
119 } // end Fractal constructor
120
121 public static void main(String[] args)
122 {
123 Fractal demo = new Fractal();
124 demo.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
125 }
126 } // end class Fractal

```

**Fig. 18.18** | Fractal user interface. (Part 3 of 3.)

The **Decrease Level** button's event handler is registered in lines 60–80. Method `actionPerformed` retrieves the current level of recursion and decrements it by 1 (lines 67–68). Lines 71–72 ensure that the level is greater than or equal to `MIN_LEVEL` and less than or equal to `MAX_LEVEL`—the fractal is not defined for recursion levels less than `MIN_LEVEL` and you can't see the additional detail above `MAX_LEVEL`. You can go up to any desired level, but around level 10 and higher, the fractal rendering becomes *slow* due to the details to be drawn. Lines 74–76 reset the level label to reflect the change—the new level is set and the `repaint` method is called to update the image to show the fractal at the new level.

The **Increase Level** `JButton` works like the **Decrease Level** `JButton`, but the level is incremented rather than decremented to show more details of the fractal (lines 93–94). When the application is first executed, the level will be set to 0, which will display a blue line between two points that were specified in the `FractalJPanel` class.

Class `FractalJPanel` (Fig. 18.19) specifies the drawing `JPanel`'s dimensions as 400 by 400 (lines 13–14). The `FractalJPanel` constructor (lines 18–24) takes the current level as a parameter and assigns it to its instance variable `level`. Instance variable `color` is set to blue by default. Lines 22–23 change the `JPanel`'s background color to white (so the fractal is easy to see), and set the drawing `FractalJPanel`'s dimensions.

---

```

1 // Fig. 18.19: FractalJPanel.java
2 // Drawing the "Lo feather fractal" using recursion.
3 import java.awt.Graphics;
4 import java.awt.Color;
5 import java.awt.Dimension;
6 import javax.swing.JPanel;
7
8 public class FractalJPanel extends JPanel
9 {
10 private Color color; // stores color used to draw fractal
11 private int level; // stores current level of fractal
12
13 private static final int WIDTH = 400; // defines width of JPanel
14 private static final int HEIGHT = 400; // defines height of JPanel
15
16 // set the initial fractal level to the value specified
17 // and set up JPanel specifications
18 public FractalJPanel(int currentLevel)
19 {
20 color = Color.BLUE; // initialize drawing color to blue
21 level = currentLevel; // set initial fractal level
22 setBackground(Color.WHITE);
23 setPreferredSize(new Dimension(WIDTH, HEIGHT));
24 }
25
26 // draw fractal recursively
27 public void drawFractal(int level, int xA, int yA, int xB,
28 int yB, Graphics g)
29 {

```

---


**Fig. 18.19** | Drawing the “Lo feather fractal” using recursion. (Part I of 4.)

```

30 // base case: draw a line connecting two given points
31 if (level == 0)
32 g.drawLine(xA, yA, xB, yB);
33 else // recursion step: determine new points, draw next level
34 {
35 // calculate midpoint between (xA, yA) and (xB, yB)
36 int xC = (xA + xB) / 2;
37 int yC = (yA + yB) / 2;
38
39 // calculate the fourth point (xD, yD) which forms an
40 // isosceles right triangle between (xA, yA) and (xC, yC)
41 // where the right angle is at (xD, yD)
42 int xD = xA + (xC - xA) / 2 - (yC - yA) / 2;
43 int yD = yA + (yC - yA) / 2 + (xC - xA) / 2;
44
45 // recursively draw the Fractal
46 drawFractal(level - 1, xD, yD, xA, yA, g);
47 drawFractal(level - 1, xD, yD, xC, yC, g);
48 drawFractal(level - 1, xD, yD, xB, yB, g);
49 }
50 }
51
52 // start drawing the fractal
53 @Override
54 public void paintComponent(Graphics g)
55 {
56 super.paintComponent(g);
57
58 // draw fractal pattern
59 g.setColor(color);
60 drawFractal(level, 100, 90, 290, 200, g);
61 }
62
63 // set the drawing color to c
64 public void setColor(Color c)
65 {
66 color = c;
67 }
68
69 // set the new level of recursion
70 public void setLevel(int currentLevel)
71 {
72 level = currentLevel;
73 }
74
75 // returns level of recursion
76 public int getLevel()
77 {
78 return level;
79 }
80 } // end class FractalJPanel


```

**Fig. 18.19** | Drawing the “Lo feather fractal” using recursion. (Part 2 of 4.)



**Fig. 18.19** | Drawing the “Lo feather fractal” using recursion. (Part 3 of 4.)





**Fig. 18.19** | Drawing the “Lo feather fractal” using recursion. (Part 4 of 4.)

Lines 27–50 define the recursive method that creates the fractal. This method takes six parameters: the level, four integers that specify the  $x$ - and  $y$ -coordinates of two points, and the `Graphics` object `g`. The base case for this method (line 31) occurs when `level` equals 0, at which time a line will be drawn between the two points given as parameters. Lines 36–43 calculate  $(xC, yC)$ , the midpoint between  $(xA, yA)$  and  $(xB, yB)$ , and  $(xD, yD)$ , the point that creates a right isosceles triangle with  $(xA, yA)$  and  $(xC, yC)$ . Lines 46–48 make three recursive calls on three different sets of points.

In method `paintComponent`, line 60 makes the first call to method `drawFractal` to start the drawing. This method call is not recursive, but all subsequent calls to `drawFractal` performed from the body of `drawFractal` are. Since the lines will not be drawn until the base case is reached, the distance between two points decreases on each recursive call. As the level of recursion increases, the fractal becomes smoother and more detailed. The shape of this fractal stabilizes as the level approaches 11. Fractals will stabilize at different levels based on their shape and size.

The output of Fig. 18.19 shows the development of the fractal from levels 0 to 6. The last image shows the defining shape of the fractal at level 11. If we focus on one of the arms of this fractal, it will be identical to the whole image. This property defines the fractal to be strictly self-similar.

## 18.10 Recursive Backtracking

Our recursive methods all have a similar architecture—if the base case is reached, return a result; if not, make one or more recursive calls. This section explores a more complex recursive technique that finds a path through a maze, returning true if there’s a possible solution. The solution involves moving through the maze one step at a time, where moves can be made by going down, right, up or left (diagonal moves are not permitted). From the current location in the maze (starting with the entry point), the following steps are taken: For each possible direction, the move is made in that direction and a recursive call is made to solve the remainder of the maze from the new location. When a dead end is

reached (i.e., we cannot take any more steps forward without hitting a wall), we back up to the previous location and try to go in a different direction. If no other direction can be taken, we back up again. This process continues until we find a point in the maze where a move *can* be made in another direction. Once such a location is found, we move in the new direction and continue with another recursive call to solve the rest of the maze.

To back up to the previous location in the maze, our recursive method simply returns false, moving up the method-call chain to the previous recursive call (which references the previous location in the maze). Using recursion to return to an earlier decision point is known as **recursive backtracking**. If one set of recursive calls does not result in a solution to the problem, the program *backs up* to the previous decision point and makes a different decision, often resulting in another set of recursive calls. In this example, the previous decision point is the previous location in the maze, and the decision to be made is the direction that the next move should take. One direction has led to a *dead end*, so the search continues with a *different* direction. The recursive backtracking solution to the maze problem uses recursion to return only *partway* up the method-call chain, then try a different direction. If the backtracking reaches the entry location of the maze and the paths in all directions have been attempted, the maze does not have a solution.

The exercises ask you to implement recursive backtracking solutions to the maze problem (Exercises 18.20–18.22) and the Eight Queens problem (Exercise 18.15), which attempts to find a way to place eight queens on an empty chessboard so that no queen is “attacking” any other (i.e., no two queens are in the same row, in the same column or along the same diagonal).

## 18.11 Wrap-Up

In this chapter, you learned how to create recursive methods—i.e., methods that call themselves. You learned that recursive methods typically divide a problem into two conceptual pieces—a piece that the method knows how to do (the base case) and a piece that the method does not know how to do (the recursion step). The recursion step is a slightly smaller version of the original problem and is performed by a recursive method call. You saw some popular recursion examples, including calculating factorials and producing values in the Fibonacci series. You then learned how recursion works “under the hood,” including the order in which recursive method calls are pushed on or popped off the program-execution stack. Next, you compared recursive and iterative approaches. You learned how to use recursion to solve more complex problems—the Towers of Hanoi and displaying fractals. The chapter concluded with an introduction to recursive backtracking, a technique for solving problems that involves backing up through recursive calls to try different possible solutions. In the next chapter, you’ll learn numerous techniques for sorting lists of data and searching for an item in a list of data, and you’ll explore the circumstances under which each searching and sorting technique should be used.

## Summary

### Section 18.1 Introduction

- A recursive method (p. 769) calls itself directly or indirectly through another method.

**Section 18.2 Recursion Concepts**

- When a recursive method is called (p. 770) to solve a problem, it can solve only the simplest case(s), or base case(s). If called with a base case (p. 770), the method returns a result.
- If a recursive method is called with a more complex problem than a base case, it typically divides the problem into two conceptual pieces—a piece that the method knows how to do and a piece that it does not know how to do.
- To make recursion feasible, the piece that the method does not know how to do must resemble the original problem, but be a slightly simpler or smaller version of it. Because this new problem resembles the original problem, the method calls a fresh copy of itself to work on the smaller problem—this is called the recursion step (p. 770).
- For recursion to eventually terminate, each time a method calls itself with a simpler version of the original problem, the sequence of smaller and smaller problems must converge on a base case. When, the method recognizes the base case, it returns a result to the previous copy of the method.
- A recursive call may be a call to another method, which in turn makes a call back to the original method. Such a process still results in a recursive call to the original method. This is known as an indirect recursive call or indirect recursion (p. 770).

**Section 18.3 Example Using Recursion: Factorials**

- Either omitting the base case or writing the recursion step incorrectly so that it does not converge on the base case can cause infinite recursion (p. 773), eventually exhausting memory. This error is analogous to the problem of an infinite loop in an iterative (nonrecursive) solution.

**Section 18.5 Example Using Recursion: Fibonacci Series**

- The Fibonacci series (p. 775) begins with 0 and 1 and has the property that each subsequent Fibonacci number is the sum of the preceding two.
- The ratio of successive Fibonacci numbers converges on a constant value of 1.618..., a number that has been called the golden ratio or the golden mean (p. 775).
- Some recursive solutions, such as Fibonacci, result in an “explosion” of method calls.

**Section 18.6 Recursion and the Method-Call Stack**

- The executing method is always the one whose stack frame is at the top of the stack, and the stack frame for that method contains the values of its local variables.

**Section 18.7 Recursion vs. Iteration**

- Both iteration and recursion are based on a control statement: Iteration uses a repetition statement, recursion a selection statement.
- Both iteration and recursion involve repetition: Iteration explicitly uses a repetition statement, whereas recursion achieves repetition through repeated method calls.
- Iteration and recursion each involve a termination test: Iteration terminates when the loop-continuation condition fails, recursion when a base case is recognized.
- Iteration with counter-controlled repetition and recursion each gradually approach termination: Iteration keeps modifying a counter until the counter assumes a value that makes the loop-continuation condition fail, whereas recursion keeps producing simpler versions of the original problem until the base case is reached.
- Both iteration and recursion can occur infinitely: An infinite loop occurs with iteration if the loop-continuation test never becomes false, whereas infinite recursion occurs if the recursion step does not reduce the problem each time in a manner that converges on the base case.

- Recursion repeatedly invokes the mechanism, and consequently the overhead, of method calls.
- Any problem that can be solved recursively can also be solved iteratively.
- A recursive approach is normally preferred over an iterative approach when it more naturally mirrors the problem and results in a program that is easier to understand and debug.
- A recursive approach can often be implemented with few lines of code, but a corresponding iterative approach might take a large amount of code. Another reason to choose a recursive solution is that an iterative solution might not be apparent.

### Section 18.9 Fractals

- A fractal (p. 783) is a geometric figure that is generated from a pattern repeated recursively an infinite number of times.
- Fractals have a self-similar property (p. 783)—subparts are reduced-size copies of the whole.

### Section 18.10 Recursive Backtracking

- In recursive backtracking (p. 794), if one set of recursive calls does not result in a solution to the problem, the program backs up to the previous decision point and makes a different decision, often resulting in another set of recursive calls.

## Self-Review Exercises

- 18.1** State whether each of the following is *true* or *false*. If *false*, explain why.
- A method that calls itself indirectly is not an example of recursion.
  - Recursion can be efficient in computation because of reduced memory-space usage.
  - When a recursive method is called to solve a problem, it actually is capable of solving only the simplest case(s), or base case(s).
  - To make recursion feasible, the recursion step in a recursive solution must resemble the original problem, but be a slightly larger version of it.
- 18.2** A \_\_\_\_\_ is needed to terminate recursion.
- recursion step
  - break statement
  - void return type
  - base case
- 18.3** The first call to invoke a recursive method is \_\_\_\_\_.
- not recursive
  - recursive
  - the recursion step
  - none of the above
- 18.4** Each time a fractal's pattern is applied, the fractal is said to be at a new \_\_\_\_\_.
- width
  - height
  - level
  - volume
- 18.5** Iteration and recursion each involve a \_\_\_\_\_.
- repetition statement
  - termination test
  - counter variable
  - none of the above

**18.6** Fill in the blanks in each of the following statements:

- a) The ratio of successive Fibonacci numbers converges on a constant value of 1.618..., a number that has been called the \_\_\_\_\_ or the \_\_\_\_\_.
- b) Iteration normally uses a repetition statement, whereas recursion normally uses a(n) \_\_\_\_\_ statement.
- c) Fractals have a(n) \_\_\_\_\_ property—when subdivided into parts, each is a reduced-size copy of the whole.

## Answers to Self-Review Exercises

**18.1** a) False. A method that calls itself in this manner is an example of indirect recursion. b) False. Recursion can be inefficient in computation because of multiple method calls and memory-space usage. c) True. d) False. To make recursion feasible, the recursion step in a recursive solution must resemble the original problem, but be a slightly *smaller* version of it.

**18.2** d

**18.3** a

**18.4** c

**18.5** b

**18.6** a) golden ratio, golden mean. b) selection. c) self-similar.

## Exercises

**18.7** What does the following code do?

```
1 public int mystery(int a, int b)
2 {
3 if (b == 1)
4 return a;
5 else
6 return a + mystery(a, b - 1);
7 }
```

**18.8** Find the error(s) in the following recursive method, and explain how to correct it (them). This method should find the sum of the values from 0 to n.

```
1 public int sum(int n)
2 {
3 if (n == 0)
4 return 0;
5 else
6 return n + sum(n);
7 }
```

**18.9** (*Recursive power Method*) Write a recursive method `power(base, exponent)` that, when called, returns

*base*<sup>*exponent*</sup>

For example, `power(3,4) = 3 * 3 * 3 * 3`. Assume that `exponent` is an integer greater than or equal to 1. *Hint:* The recursion step should use the relationship

$$\text{base}^{\text{exponent}} = \text{base} \cdot \text{base}^{\text{exponent} - 1}$$

and the terminating condition occurs when exponent is equal to 1, because

$$\text{base}^1 = \text{base}$$

Incorporate this method into a program that enables the user to enter the base and exponent.

**18.10 (Visualizing Recursion)** It's interesting to watch recursion "in action." Modify the factorial method in Fig. 18.3 to print its local variable and recursive-call parameter. For each recursive call, display the outputs on a separate line and add a level of indentation. Do your utmost to make the outputs clear, interesting and meaningful. Your goal here is to design and implement an output format that makes it easier to understand recursion. You may want to add such display capabilities to other recursion examples and exercises throughout the text.

**18.11 (Greatest Common Divisor)** The greatest common divisor of integers  $x$  and  $y$  is the largest integer that evenly divides into both  $x$  and  $y$ . Write a recursive method `gcd` that returns the greatest common divisor of  $x$  and  $y$ . The `gcd` of  $x$  and  $y$  is defined recursively as follows: If  $y$  is equal to 0, then `gcd(x, y)` is  $x$ ; otherwise, `gcd(x, y)` is `gcd(y, x % y)`, where `%` is the remainder operator. Use this method to replace the one you wrote in the application of Exercise 5.27.

**18.12** What does the following program do?

```

1 // Exercise 18.12 Solution: MysteryClass.java
2 public class MysteryClass
3 {
4 public static int mystery(int[] array2, int size)
5 {
6 if (size == 1)
7 return array2[0];
8 else
9 return array2[size - 1] + mystery(array2, size - 1);
10 }
11
12 public static void main(String[] args)
13 {
14 int[] array = {1, 2, 3, 4, 5, 6, 7, 8, 9, 10};
15
16 int result = mystery(array, array.length);
17 System.out.printf("Result is: %d\n", result);
18 } // end method main
19 } // end class MysteryClass

```

**18.13** What does the following program do?

```

1 // Exercise 18.13 Solution: SomeClass.java
2 public class SomeClass
3 {
4 public static String someMethod(int[] array2, int x)
5 {
6 if (x < array2.length)
7 return String.format(
8 "%s%d ", someMethod(array2, x + 1), array2[x]);
9 else
10 return "";
11 }
12

```

```


13 public static void main(String[] args)
14 {
15 int[] array = {1, 2, 3, 4, 5, 6, 7, 8, 9, 10};
16 String results = someMethod(array, 0);
17 System.out.println(results);
18 }
19 } // end class SomeClass

```

**18.14 (Palindromes)** A palindrome is a string that is spelled the same way forward and backward. Some examples of palindromes are “radar,” “able was i ere i saw elba” and (if spaces are ignored) “a man a plan a canal panama.” Write a recursive method `testPalindrome` that returns `boolean` value `true` if the string stored in the array is a palindrome and `false` otherwise. The method should ignore spaces and punctuation in the string.

**18.15 (Eight Queens)** A puzzler for chess buffs is the Eight Queens problem, which asks: Is it possible to place eight queens on an empty chessboard so that no queen is “attacking” any other (i.e., no two queens are in the same row, in the same column or along the same diagonal)? For instance, if a queen is placed in the upper-left corner of the board, no other queens could be placed in any of the marked squares shown in Fig. 18.20. Solve the problem recursively. [Hint: Your solution should begin with the first column and look for a location in that column where a queen can be placed—initially, place the queen in the first row. The solution should then recursively search the remaining columns. In the first few columns, there will be several locations where a queen may be placed. Take the first available location. If a column is reached with no possible location for a queen, the program should return to the previous column, and move the queen in that column to a new row. This continuous backing up and trying new alternatives is an example of recursive backtracking.]

**18.16 (Print an Array)** Write a recursive method `printArray` that displays all the elements in an array of integers, separated by spaces.




**Fig. 18.20** | Squares eliminated by placing a queen in the upper-left corner of a chessboard.

**18.17 (Print an Array Backward)** Write a recursive method `stringReverse` that takes a character array containing a string as an argument and prints the string backward. [Hint: Use `String` method `toCharArray`, which takes no arguments, to get a `char` array containing the characters in the `String`.]

**18.18 (Find the Minimum Value in an Array)** Write a recursive method `recursiveMinimum` that determines the smallest element in an array of integers. The method should return when it receives an array of one element.

**18.19 (Fractals)** Repeat the fractal pattern in Section 18.9 to form a star. Begin with five lines (see Fig. 18.21) instead of one, where each line is a different arm of the star. Apply the “Lo feather fractal” pattern to each arm of the star.



**Fig. 18.21** | Sample outputs for Exercise 18.19.

**18.20** (*Maze Traversal Using Recursive Backtracking*) The grid of #s and dots (.) in Fig. 18.22 is a two-dimensional array representation of a maze. The #s represent the walls of the maze, and the dots represent locations in the possible paths through the maze. A move can be made only to a location in the array that contains a dot.

```

#
. . . #
. . # . # . # # # . #
. # . . . # .
. . . # # # . # . .
. # . # . # .
. . # . # . # . # .
. # . # . # . # .
. # .
. # # # .
. # . . .
#

```

**Fig. 18.22** | Two-dimensional array representation of a maze.

Write a recursive method (`mazeTraversal1`) to walk through mazes like the one in Fig. 18.22. The method should receive as arguments a 12-by-12 character array representing the maze and the current location in the maze (the first time this method is called, the current location should be the entry point of the maze). As `mazeTraversal1` attempts to locate the exit, it should place the character `x` in each square in the path. There's a simple algorithm for walking through a maze that guarantees finding the exit (assuming there's an exit). If there's no exit, you'll arrive at the starting location again. The algorithm is as follows: From the current location in the maze, try to move one space in any of the possible directions (down, right, up or left). If it's possible to move in at least one direction, call `mazeTraversal1` recursively, passing the new spot on the maze as the current spot.



If it's not possible to go in any direction, "back up" to a previous location in the maze and try a new direction for that location (this is an example of recursive backtracking). Program the method to display the maze after each move so the user can watch as the maze is solved. The final output of the maze should display only the path needed to solve the maze—if going in a particular direction results in a dead end, the x's going in that direction should not be displayed. [*Hint:* To display only the final path, it may be helpful to mark off spots that result in a dead end with another character (such as '0').]

**18.21** (*Generating Mazes Randomly*) Write a method `mazeGenerator` that takes as an argument a two-dimensional 12-by-12 character array and randomly produces a maze. The method should also provide the starting and ending locations of the maze. Test your method `mazeTraversal` from Exercise 18.20, using several randomly generated mazes.

**18.22** (*Mazes of Any Size*) Generalize methods `mazeTraversal` and `mazeGenerator` of Exercise 18.20 and Exercise 18.21 to process mazes of any width and height.

**18.23** (*Time to Calculate Fibonacci Numbers*) Enhance the Fibonacci program of Fig. 18.5 so that it calculates the approximate amount of time required to perform the calculation and the number of calls made to the recursive method. For this purpose, call static `System` method `currentTimeMillis`, which takes no arguments and returns the computer's current time in milliseconds. Call this method twice—once before and once after the call to `fibonacci`. Save each value and calculate the difference in the times to determine how many milliseconds were required to perform the calculation. Then, add a variable to the `FibonacciCalculator` class, and use this variable to determine the number of calls made to method `fibonacci`. Display your results.

# 19

## Searching, Sorting and Big O

*With sobs and tears  
he sorted out  
Those of the largest size ...*

—Lewis Carroll

*Attempt the end, and never  
stand to doubt;  
Nothing's so hard, but search  
will find it out.*

—Robert Herrick

*'Tis in my memory lock'd,  
And you yourself shall keep the  
key of it.*

—William Shakespeare

*It is an immutable law in  
business that words are words,  
explanations are explanations,  
promises are promises — but  
only performance is reality.*

—Harold S. Green

### Objectives

In this chapter you'll:

- Search for a given value in an array using linear search and binary search.
- Sort arrays using the iterative selection and insertion sort algorithms.
- Sort arrays using the recursive merge sort algorithm.
- Determine the efficiency of searching and sorting algorithms.
- Introduce Big O notation for comparing the efficiency of algorithms.



- 19.1 Introduction
- 19.2 Linear Search
- 19.3 Big O Notation
  - 19.3.1  $O(1)$  Algorithms
  - 19.3.2  $O(n)$  Algorithms
  - 19.3.3  $O(n^2)$  Algorithms
  - 19.3.4 Big O of the Linear Search
- 19.4 Binary Search
  - 19.4.1 Binary Search Implementation
  - 19.4.2 Efficiency of the Binary Search
- 19.5 Sorting Algorithms
- 19.6 Selection Sort
  - 19.6.1 Selection Sort Implementation
  - 19.6.2 Efficiency of the Selection Sort
- 19.7 Insertion Sort
  - 19.7.1 Insertion Sort Implementation
  - 19.7.2 Efficiency of the Insertion Sort
- 19.8 Merge Sort
  - 19.8.1 Merge Sort Implementation
  - 19.8.2 Efficiency of the Merge Sort
- 19.9 Big O Summary for This Chapter's Searching and Sorting Algorithms
- 19.10 Wrap-Up

Summary | Self-Review Exercises | Answers to Self-Review Exercises | Exercises

## 19.1 Introduction

Searching data involves determining whether a value (referred to as the **search key**) is present in the data and, if so, finding its location. Two popular search algorithms are the simple linear search and the faster but more complex binary search. **Sorting** places data in ascending or descending order, based on one or more **sort keys**. A list of names could be sorted alphabetically, bank accounts could be sorted by account number, employee payroll records could be sorted by social security number, and so on. This chapter introduces two simple sorting algorithms, the selection sort and the insertion sort, along with the more efficient but more complex merge sort. Figure 19.1 summarizes the searching and sorting algorithms discussed in the examples and exercises of this book.



### Software Engineering Observation 19.1

*In apps that require searching and sorting, use the pre-defined capabilities of the Java Collections API (Chapter 16). The techniques presented in this chapter are provided to introduce students to the concepts behind searching and sorting algorithms—upper-level computer science courses typically discuss such algorithms in detail.*

| Chapter                      | Algorithm                                | Location      |
|------------------------------|------------------------------------------|---------------|
| <i>Searching Algorithms:</i> |                                          |               |
| 16                           | binarySearch method of class Collections | Fig. 16.12    |
| 19                           | Linear search                            | Section 19.2  |
|                              | Binary search                            | Section 19.4  |
|                              | Recursive linear search                  | Exercise 19.8 |
|                              | Recursive binary search                  | Exercise 19.9 |

**Fig. 19.1** | Searching and sorting algorithms covered in this text. (Part I of 2.)

| Chapter                    | Algorithm                        | Location                |
|----------------------------|----------------------------------|-------------------------|
| 21                         | Linear search of a List          | Exercise 21.21          |
|                            | Binary tree search               | Exercise 21.23          |
| <i>Sorting Algorithms:</i> |                                  |                         |
| 16                         | sort method of class Collections | Figs. 16.6–16.9         |
|                            | SortedSet collection             | Fig. 16.17              |
| 19                         | Selection sort                   | Section 19.6            |
|                            | Insertion sort                   | Section 19.7            |
|                            | Recursive merge sort             | Section 19.8            |
|                            | Bubble sort                      | Exercises 19.5 and 19.6 |
|                            | Bucket sort                      | Exercise 19.7           |
|                            | Recursive quicksort              | Exercise 19.10          |
| 21                         | Binary tree sort                 | Section 21.7            |

**Fig. 19.1** | Searching and sorting algorithms covered in this text. (Part 2 of 2.)

## 19.2 Linear Search

Looking up a phone number, finding a website via a search engine and checking the definition of a word in a dictionary all involve searching large amounts of data. This section and Section 19.4 discuss two common search algorithms—one that’s easy to program yet relatively inefficient (linear search) and one that’s relatively efficient but more complex to program (binary search).

### *Linear Search Algorithm*

The **linear search algorithm** searches each element in an array sequentially. If the search key does not match an element in the array, the algorithm tests each element, and when the end of the array is reached, informs the user that the search key is not present. If the search key is in the array, the algorithm tests each element until it finds one that matches the search key and returns the index of that element.

As an example, consider an array containing the following values

|    |    |   |    |    |    |    |    |   |    |
|----|----|---|----|----|----|----|----|---|----|
| 34 | 56 | 2 | 10 | 77 | 51 | 93 | 30 | 5 | 52 |
|----|----|---|----|----|----|----|----|---|----|

and a program that’s searching for 51. Using the linear search algorithm, the program first checks whether 34 matches the search key. It does not, so the algorithm checks whether 56 matches the search key. The program continues moving through the array sequentially, testing 2, then 10, then 77. When the program tests 51, which matches the search key, the program returns the index 5, which is the location of 51 in the array. If, after checking every array element, the program determines that the search key does not match any element in the array, it returns a sentinel value (e.g., -1).

### *Linear Search Implementation*

Class `LinearSearchTest` (Fig. 19.2) contains static method `linearSearch` for performing searches of an `int` array and `main` for testing `linearSearch`.

---

```

1 // Fig. 19.2: LinearSearchTest.java
2 // Sequentially searching an array for an item.
3 import java.security.SecureRandom;
4 import java.util.Arrays;
5 import java.util.Scanner;
6
7 public class LinearSearchTest
8 {
9 // perform a linear search on the data
10 public static int linearSearch(int data[], int searchKey)
11 {
12 // loop through array sequentially
13 for (int index = 0; index < data.length; index++)
14 if (data[index] == searchKey)
15 return index; // return index of integer
16
17 return -1; // integer was not found
18 } // end method linearSearch
19
20 public static void main(String[] args)
21 {
22 Scanner input = new Scanner(System.in);
23 SecureRandom generator = new SecureRandom();
24
25 int[] data = new int[10]; // create array
26
27 for (int i = 0; i < data.length; i++) // populate array
28 data[i] = 10 + generator.nextInt(90);
29
30 System.out.printf("%s\n", Arrays.toString(data)); // display array
31
32 // get input from user
33 System.out.print("Please enter an integer value (-1 to quit): ");
34 int searchInt = input.nextInt();
35
36 // repeatedly input an integer; -1 terminates the program
37 while (searchInt != -1)
38 {
39 int position = linearSearch(data, searchInt); // perform search
40
41 if (position == -1) // not found
42 System.out.printf("%d was not found\n", searchInt);
43 else // found
44 System.out.printf("%d was found in position %d\n",
45 searchInt, position);
46
47 // get input from user
48 System.out.print("Please enter an integer value (-1 to quit): ");
49 searchInt = input.nextInt();
50 }
51 } // end main
52 } // end class LinearSearchTest

```

---

**Fig. 19.2** | Sequentially searching an array for an item. (Part I of 2.)

```
[59, 97, 34, 90, 79, 56, 24, 51, 30, 69]
Please enter an integer value (-1 to quit): 79
79 was found in position 4
Please enter an integer value (-1 to quit): 61
61 was not found
Please enter an integer value (-1 to quit): 51
51 was found in position 7
Please enter an integer value (-1 to quit): -1
```

**Fig. 19.2** | Sequentially searching an array for an item. (Part 2 of 2.)

### *Method linearSearch*

Method `linearSearch` (lines 10–18) performs the linear search. The method receives as parameters the array to search (`data`) and the `searchKey`. Lines 13–15 loop through the elements in the array `data`. Line 14 compares each with `searchKey`. If the values are equal, line 15 returns the *index* of the element. If there are *duplicate* values in the array, linear search returns the index of the *first* element in the array that matches the search key. If the loop ends without finding the value, line 17 returns `-1`.

### *Method main*

Method `main` (line 20–51) allows the user to search an array. Lines 25–28 create an array of 10 ints and populate it with random ints from 10–99. Then, line 30 displays the array's contents using Arrays static method `toString`, which returns a `String` representation of the array with the elements in square brackets (`[]`) and separated by commas.

Lines 33–34 prompt the user for and store the search key. Line 39 calls method `linearSearch` to determine whether `searchInt` is in the array `data`. If it's not, `linearSearch` returns `-1` and the program notifies the user (lines 41–42). If `searchInt` is in the array, `linearSearch` returns the position of the element, which the program outputs in lines 44–45. Lines 48–49 get the next search key from the user.

## 19.3 Big O Notation

Searching algorithms all accomplish the *same* goal—finding an element (or elements) that matches a given search key, if such an element does, in fact, exist. There are, however, a number of things that differentiate search algorithms from one another. *The major difference is the amount of effort they require to complete the search.* One way to describe this effort is with **Big O notation**, which indicates how hard an algorithm may have to work to solve a problem. For searching and sorting algorithms, this depends particularly on how many data elements there are. In this chapter, we use Big O to describe the worst-case run times for various searching and sorting algorithms.

### 19.3.1 O(1) Algorithms

Suppose an algorithm is designed to test whether the first element of an array is equal to the second. If the array has 10 elements, this algorithm requires one comparison. If the array has 1000 elements, it still requires one comparison. In fact, the algorithm is completely independent of the number of elements in the array. This algorithm is said to have

a **constant run time**, which is represented in Big O notation as  $O(1)$  and pronounced as “order one.” An algorithm that’s  $O(1)$  does not necessarily require only one comparison.  $O(1)$  just means that the number of comparisons is *constant*—it does not grow as the size of the array increases. An algorithm that tests whether the first element of an array is equal to any of the next three elements is still  $O(1)$  even though it requires three comparisons.

### 19.3.2 $O(n)$ Algorithms

An algorithm that tests whether the first array element is equal to *any* of the other array elements will require at most  $n - 1$  comparisons, where  $n$  is the number of array elements. If the array has 10 elements, this algorithm requires up to nine comparisons. If the array has 1000 elements, it requires up to 999 comparisons. As  $n$  grows larger, the  $n$  part of the expression “dominates,” and subtracting one becomes inconsequential. Big O is designed to highlight these dominant terms and ignore terms that become unimportant as  $n$  grows. For this reason, an algorithm that requires a total of  $n - 1$  comparisons (such as the one we described earlier) is said to be  $O(n)$ . An  $O(n)$  algorithm is referred to as having a **linear run time**.  $O(n)$  is often pronounced “on the order of  $n$ ” or simply “order  $n$ .”

### 19.3.3 $O(n^2)$ Algorithms

Now suppose you have an algorithm that tests whether *any* element of an array is duplicated elsewhere in the array. The first element must be compared with every other element in the array. The second element must be compared with every other element except the first (it was already compared to the first). The third element must be compared with every other element except the first two. In the end, this algorithm will end up making  $(n - 1) + (n - 2) + \dots + 2 + 1$  or  $n^2/2 - n/2$  comparisons. As  $n$  increases, the  $n^2$  term dominates and the  $n$  term becomes inconsequential. Again, Big O notation highlights the  $n^2$  term, leaving  $n/2$ . But, as we’ll soon see, constant factors are omitted in Big O notation.

Big O is concerned with how an algorithm’s run time grows in relation to the number of items processed. Suppose an algorithm requires  $n^2$  comparisons. With four elements, the algorithm requires 16 comparisons; with eight elements, 64 comparisons. With this algorithm, *doubling* the number of elements *quadruples* the number of comparisons. Consider a similar algorithm requiring  $n^2/2$  comparisons. With four elements, the algorithm requires eight comparisons; with eight elements, 32 comparisons. Again, *doubling* the number of elements *quadruples* the number of comparisons. Both of these algorithms grow as the square of  $n$ , so Big O ignores the constant and both algorithms are considered to be  $O(n^2)$ , which is referred to as **quadratic run time** and pronounced “on the order of  $n$ -squared” or more simply “order  $n$ -squared.”

When  $n$  is small,  $O(n^2)$  algorithms (running on today’s computers) will not noticeably affect performance. But as  $n$  grows, you’ll start to notice the performance degradation. An  $O(n^2)$  algorithm running on a million-element array would require a trillion “operations” (where each could actually require several machine instructions to execute). This could take several hours. A billion-element array would require a quintillion operations, a number so large that the algorithm could take decades!  $O(n^2)$  algorithms, unfortunately, are easy to write, as you’ll see in this chapter. You’ll also see algorithms with more favorable Big O measures. These efficient algorithms often take a bit more cleverness and work to create, but their superior performance can be well worth the extra effort, especially as  $n$  gets large and as algorithms are combined into larger programs.

### 19.3.4 Big O of the Linear Search

The linear search algorithm runs in  $O(n)$  time. The worst case in this algorithm is that every element must be checked to determine whether the search item exists in the array. If the size of the array is *doubled*, the number of comparisons that the algorithm must perform is also *doubled*. Linear search can provide outstanding performance if the element matching the search key happens to be at or near the front of the array. But we seek algorithms that perform well, on average, across *all* searches, including those where the element matching the search key is near the end of the array.

Linear search is easy to program, but it can be slow compared to other search algorithms. If a program needs to perform many searches on large arrays, it's better to implement a more efficient algorithm, such as the binary search, which we present next.



#### Performance Tip 19.1

*Sometimes the simplest algorithms perform poorly. Their virtue is that they're easy to program, test and debug. Sometimes more complex algorithms are required to realize maximum performance.*

## 19.4 Binary Search

The **binary search algorithm** is more efficient than linear search, but it requires that the array be sorted. The first iteration of this algorithm tests the *middle* element in the array. If this matches the search key, the algorithm ends. Assuming the array is sorted in *ascending* order, then if the search key is *less than* the middle element, it cannot match any element in the second half of the array and the algorithm continues with only the first half of the array (i.e., the first element up to, but not including, the middle element). If the search key is *greater than* the middle element, it cannot match any element in the first half of the array and the algorithm continues with only the second half (i.e., the element *after* the middle element through the last element). Each iteration tests the middle value of the remaining portion of the array. If the search key does not match the element, the algorithm eliminates half of the remaining elements. The algorithm ends by either finding an element that matches the search key or reducing the subarray to zero size.

#### Example

As an example consider the sorted 15-element array

2 3 5 10 27 30 34 51 56 65 77 81 82 93 99

and a search key of 65. A program implementing the binary search algorithm would first check whether 51 is the search key (because 51 is the *middle* element of the array). The search key (65) is larger than 51, so 51 is ignored along with the first half of the array (all elements smaller than 51), leaving

56 65 77 81 82 93 99

Next, the algorithm checks whether 81 (the middle element of the remainder of the array) matches the search key. The search key (65) is smaller than 81, so 81 is discarded along with the elements larger than 81. After just two tests, the algorithm has narrowed the number of values to check to only three (56, 65 and 77). It then checks 65 (which indeed matches the search key) and returns the index of the array element containing 65.



This algorithm required just three comparisons to determine whether the search key matched an element of the array. Using a linear search algorithm would have required 10 comparisons. [Note: In this example, we've chosen to use an array with 15 elements so that there will always be an obvious middle element in the array. With an even number of elements, the middle of the array lies between two elements. We implement the algorithm to choose the higher of those two elements.]

### 19.4.1 Binary Search Implementation

Class `BinarySearchTest` (Fig. 19.3) contains:

- static method `binarySearch` to search an `int` array for a specified key
- static method `remainingElements` to display the remaining elements in the array being searched, and
- `main` to test method `binarySearch`.

The `main` method (lines 57–90) is nearly identical to `main` in Fig. 19.2. In this program, we create a 15-element array (line 62) and line 67 calls the `Arrays` class's static method `sort` to sort the array data's elements in an array in ascending order (by default). Recall that the binary search algorithm will work only on a sorted array. The first line of output from this program shows the sorted array of `ints`. When the user instructs the program to search for 18, the program first tests the middle element, which is 57 (as indicated by \*). The search key is less than 57, so the program eliminates the second half of the array and tests the middle element from the first half. The search key is smaller than 36, so the program eliminates the second half of the array, leaving only three elements. Finally, the program checks 18 (which matches the search key) and returns the index 1.

---

```

1 // Fig. 19.3: BinarySearchTest.java
2 // Use binary search to locate an item in an array.
3 import java.security.SecureRandom;
4 import java.util.Arrays;
5 import java.util.Scanner;
6
7 public class BinarySearchTest
8 {
9 // perform a binary search on the data
10 public static int binarySearch(int[] data, int key)
11 {
12 int low = 0; // low end of the search area
13 int high = data.length - 1; // high end of the search area
14 int middle = (low + high + 1) / 2; // middle element
15 int location = -1; // return value; -1 if not found
16
17 do // loop to search for element
18 {
19 // print remaining elements of array
20 System.out.print(remainingElements(data, low, high));
21

```

---

**Fig. 19.3** | Use binary search to locate an item in an array (the \* in the output marks the middle element). (Part 1 of 3.)

---

```

22 // output spaces for alignment
23 for (int i = 0; i < middle; i++)
24 System.out.print(" ");
25 System.out.println(" * "); // indicate current middle
26
27 // if the element is found at the middle
28 if (key == data[middle])
29 location = middle; // location is the current middle
30 else if (key < data[middle]) // middle element is too high
31 high = middle - 1; // eliminate the higher half
32 else // middle element is too low
33 low = middle + 1; // eliminate the lower half
34
35 middle = (low + high + 1) / 2; // recalculate the middle
36 } while ((low <= high) && (location == -1));
37
38 return location; // return location of search key
39 } // end method binarySearch
40
41 // method to output certain values in array
42 private static String remainingElements(int[] data, int low, int high)
43 {
44 StringBuilder temporary = new StringBuilder();
45
46 // append spaces for alignment
47 for (int i = 0; i < low; i++)
48 temporary.append(" ");
49
50 // append elements left in array
51 for (int i = low; i <= high; i++)
52 temporary.append(data[i] + " ");
53
54 return String.format("%s%n", temporary);
55 } // end method remainingElements
56
57 public static void main(String[] args)
58 {
59 Scanner input = new Scanner(System.in);
60 SecureRandom generator = new SecureRandom();
61
62 int[] data = new int[15]; // create array
63
64 for (int i = 0; i < data.length; i++) // populate array
65 data[i] = 10 + generator.nextInt(90);
66
67 Arrays.sort(data); // binarySearch requires sorted array
68 System.out.printf("%s%n%n", Arrays.toString(data)); // display array
69
70 // get input from user
71 System.out.print("Please enter an integer value (-1 to quit): ");
72 int searchInt = input.nextInt();
73

```

---

**Fig. 19.3** | Use binary search to locate an item in an array (the \* in the output marks the middle element). (Part 2 of 3.)

```

74 // repeatedly input an integer; -1 terminates the program
75 while (searchInt != -1)
76 {
77 // perform search
78 int location = binarySearch(data, searchInt);
79
80 if (location == -1) // not found
81 System.out.printf("%d was not found\n\n", searchInt);
82 else // found
83 System.out.printf("%d was found in position %d\n\n",
84 searchInt, location);
85
86 // get input from user
87 System.out.print("Please enter an integer value (-1 to quit): ");
88 searchInt = input.nextInt();
89 }
90 } // end main
91 } // end class BinarySearchTest

```

```
[13, 18, 29, 36, 42, 47, 56, 57, 63, 68, 80, 81, 82, 88, 88]
```

```
Please enter an integer value (-1 to quit): 18
```

```
13 18 29 36 42 47 56 57 63 68 80 81 82 88 88
```

```
 *
```

```
13 18 29 36 42 47 56
```

```
 *
```

```
13 18 29
```

```
 *
```

```
18 was found in position 1
```

```
Please enter an integer value (-1 to quit): 82
```

```
13 18 29 36 42 47 56 57 63 68 80 81 82 88 88
```

```
 *
```

```
 63 68 80 81 82 88 88
```

```
 *
```

```
 82 88 88
```

```
 *
```

```
 82
```

```
 *
```

```
82 was found in position 12
```

```
Please enter an integer value (-1 to quit): 69
```

```
13 18 29 36 42 47 56 57 63 68 80 81 82 88 88
```

```
 *
```

```
 63 68 80 81 82 88 88
```

```
 *
```

```
 63 68 80
```

```
 *
```

```
 80
```

```
 *
```

```
69 was not found
```

```
Please enter an integer value (-1 to quit): -1
```

**Fig. 19.3** | Use binary search to locate an item in an array (the \* in the output marks the middle element). (Part 3 of 3.)

Lines 10–39 declare method `binarySearch`, which receives as parameters the array to search (`data`) and the search key (`key`). Lines 12–14 calculate the `low` end index, `high` end index and `middle` index of the portion of the array that the program is currently searching. At the beginning of the method, the `low` end is 0, the `high` end is the length of the array minus 1 and the `middle` is the average of these two values. Line 15 initializes the `location` of the element to -1—the value that will be returned if the key is not found. Lines 17–36 loop until `low` is greater than `high` (this occurs when the key is not found) or `location` does not equal -1 (indicating that the key was found). Line 28 tests whether the value in the `middle` element is equal to the key. If so, line 29 assigns `middle` to `location`, the loop terminates and `location` is returned to the caller. Each iteration of the loop tests a single value (line 28) and *eliminates half of the remaining values in the array* (line 31 or 33) if the value is not the key.

### 19.4.2 Efficiency of the Binary Search

In the worst-case scenario, searching a *sorted* array of 1023 elements takes *only 10 comparisons* when using a binary search. Repeatedly dividing 1023 by 2 (because after each comparison we can eliminate half the array) and rounding down (because we also remove the middle element) yields the values 511, 255, 127, 63, 31, 15, 7, 3, 1 and 0. The number 1023 ( $2^{10} - 1$ ) is divided by 2 only 10 times to get the value 0, which indicates that there are no more elements to test. Dividing by 2 is equivalent to one comparison in the binary search algorithm. Thus, an array of 1,048,575 ( $2^{20} - 1$ ) elements takes a *maximum of 20 comparisons* to find the key, and an array of over one billion elements takes a *maximum of 30 comparisons* to find the key. This is a tremendous improvement in performance over the linear search. For a one-billion-element array, this is a difference between an average of 500 million comparisons for the linear search and a maximum of only 30 comparisons for the binary search! The maximum number of comparisons needed for the binary search of any sorted array is the exponent of the first power of 2 greater than the number of elements in the array, which is represented as  $\log_2 n$ . All logarithms grow at roughly the same rate, so in big O notation the base can be omitted. This results in a big O of  $O(\log n)$  for a binary search, which is also known as **logarithmic run time** and pronounced as “order log n.”

## 19.5 Sorting Algorithms

Sorting data (i.e., placing the data into some particular order, such as ascending or descending) is one of the most important computing applications. A bank sorts all checks by account number so that it can prepare individual bank statements at the end of each month. Telephone companies sort their lists of accounts by last name and, further, by first name to make it easy to find phone numbers. Virtually every organization must sort some data, and often massive amounts of it. Sorting data is an intriguing, computer-intensive problem that has attracted intense research efforts.

An important item to understand about sorting is that the end result—the sorted array—will be the *same* no matter which algorithm you use to sort the array. The choice of algorithm affects only the run time and memory use of the program. The rest of this chapter introduces three common sorting algorithms. The first two—*selection sort* and *insertion sort*—are easy to program but *inefficient*. The last algorithm—*merge sort*—is

much *faster* than selection sort and insertion sort but *harder to program*. We focus on sorting arrays of primitive-type data, namely ints. It's possible to sort arrays of class objects as well, as we demonstrated in Section 16.7.1 by using the built-in sorting capabilities of the Collections API.

## 19.6 Selection Sort

**Selection sort** is a simple, but inefficient, sorting algorithm. If you're sorting in increasing order, its first iteration selects the *smallest* element in the array and swaps it with the first element. The second iteration selects the *second-smallest* item (which is the smallest item of the remaining elements) and swaps it with the second element. The algorithm continues until the last iteration selects the *second-largest* element and swaps it with the second-to-last index, leaving the largest element in the last index. After the *i*th iteration, the smallest *i* items of the array will be sorted into increasing order in the first *i* elements of the array.

As an example, consider the array

|    |    |   |    |    |    |    |    |   |    |
|----|----|---|----|----|----|----|----|---|----|
| 34 | 56 | 4 | 10 | 77 | 51 | 93 | 30 | 5 | 52 |
|----|----|---|----|----|----|----|----|---|----|

A program that implements selection sort first determines the smallest element (4) of this array, which is contained in index 2. The program swaps 4 with 34, resulting in

|   |    |    |    |    |    |    |    |   |    |
|---|----|----|----|----|----|----|----|---|----|
| 4 | 56 | 34 | 10 | 77 | 51 | 93 | 30 | 5 | 52 |
|---|----|----|----|----|----|----|----|---|----|

The program then determines the smallest value of the remaining elements (all elements except 4), which is 5, contained in index 8. The program swaps 5 with 56, resulting in

|   |   |    |    |    |    |    |    |    |    |
|---|---|----|----|----|----|----|----|----|----|
| 4 | 5 | 34 | 10 | 77 | 51 | 93 | 30 | 56 | 52 |
|---|---|----|----|----|----|----|----|----|----|

On the third iteration, the program determines the next smallest value (10) and swaps it with 34.

|   |   |    |    |    |    |    |    |    |    |
|---|---|----|----|----|----|----|----|----|----|
| 4 | 5 | 10 | 34 | 77 | 51 | 93 | 30 | 56 | 52 |
|---|---|----|----|----|----|----|----|----|----|

The process continues until the array is fully sorted.

|   |   |    |    |    |    |    |    |    |    |
|---|---|----|----|----|----|----|----|----|----|
| 4 | 5 | 10 | 30 | 34 | 51 | 52 | 56 | 77 | 93 |
|---|---|----|----|----|----|----|----|----|----|

After the first iteration, the smallest element is in the first position. After the second iteration, the two smallest elements are in order in the first two positions. After the third iteration, the three smallest elements are in order in the first three positions.

### 19.6.1 Selection Sort Implementation

Class `SelectionSortTest` (Fig. 19.4) contains:

- static method `selectionSort` to sort an `int` array using the selection sort algorithm
- static method `swap` to swap the values of two array elements
- static method `printPass` to display the array contents after each pass, and
- `main` to test method `selectionSort`.

As in the searching examples, `main` (lines 57–72) creates an array of `ints` named `data` and populates it with random `ints` in the range 10–99. Line 68 tests method `selectionSort`.

---

```

1 // Fig. 19.4: SelectionSortTest.java
2 // Sorting an array with selection sort.
3 import java.security.SecureRandom;
4 import java.util.Arrays;
5
6 public class SelectionSortTest
7 {
8 // sort array using selection sort
9 public static void selectionSort(int[] data)
10 {
11 // loop over data.length - 1 elements
12 for (int i = 0; i < data.length - 1; i++)
13 {
14 int smallest = i; // first index of remaining array
15
16 // loop to find index of smallest element
17 for (int index = i + 1; index < data.length; index++)
18 if (data[index] < data[smallest])
19 smallest = index;
20
21 swap(data, i, smallest); // swap smallest element into position
22 printPass(i + 1, smallest); // output pass of algorithm
23 }
24 } // end method selectionSort
25
26 // helper method to swap values in two elements
27 private static void swap(int[] data, int first, int second)
28 {
29 int temporary = data[first]; // store first in temporary
30 data[first] = data[second]; // replace first with second
31 data[second] = temporary; // put temporary in second
32 }
33
34 // print a pass of the algorithm
35 private static void printPass(int[] data, int pass, int index)
36 {
37 System.out.printf("after pass %2d: ", pass);
38
39 // output elements till selected item
40 for (int i = 0; i < index; i++)
41 System.out.printf("%d ", data[i]);
42
43 System.out.printf("%d* ", data[index]); // indicate swap
44
45 // finish outputting array
46 for (int i = index + 1; i < data.length; i++)
47 System.out.printf("%d ", data[i]);
48
49 System.out.printf("%n "); // for alignment
50
51 // indicate amount of array that's sorted
52 for (int j = 0; j < pass; j++)
53 System.out.print("-- ");

```

---

**Fig. 19.4** | Sorting an array with selection sort. (Part I of 2.)

```

54 System.out.println();
55 }
56
57 public static void main(String[] args)
58 {
59 SecureRandom generator = new SecureRandom();
60
61 int[] data = new int[10]; // create array
62
63 for (int i = 0; i < data.length; i++) // populate array
64 data[i] = 10 + generator.nextInt(90);
65
66 System.out.printf("Unsorted array:%n%s%n",
67 Arrays.toString(data)); // display array
68 selectionSort(data); // sort array
69
70 System.out.printf("Sorted array:%n%s%n",
71 Arrays.toString(data)); // display array
72 }
73 } // end class SelectionSortTest

```

```

Unsorted array:
[40, 60, 59, 46, 98, 82, 23, 51, 31, 36]

after pass 1: 23 60 59 46 98 82 40* 51 31 36
 --
after pass 2: 23 31 59 46 98 82 40 51 60* 36
 -- --
after pass 3: 23 31 36 46 98 82 40 51 60 59*
 -- -- --
after pass 4: 23 31 36 40 98 82 46* 51 60 59
 -- -- -- --
after pass 5: 23 31 36 40 46 82 98* 51 60 59
 -- -- -- -- --
after pass 6: 23 31 36 40 46 51 98 82* 60 59
 -- -- -- -- -- --
after pass 7: 23 31 36 40 46 51 59 82 60 98*
 -- -- -- -- -- -- --
after pass 8: 23 31 36 40 46 51 59 60 82* 98
 -- -- -- -- -- -- --
after pass 9: 23 31 36 40 46 51 59 60 82* 98
 -- -- -- -- -- -- --

Sorted array:
[23, 31, 36, 40, 46, 51, 59, 60, 82, 98]

```

**Fig. 19.4** | Sorting an array with selection sort. (Part 2 of 2.)

#### *Methods selectionSort and swap*

Lines 9–24 declare the `selectionSort` method. Lines 12–23 loop `data.length - 1` times. Line 14 declares and initializes (to the current index `i`) the variable `smallest`, which stores the index of the smallest element in the remaining array. Lines 17–19 loop over the remaining elements in the array. For each of these elements, line 18 compares its value to the value of the smallest element. If the current element is smaller than the smallest element, line 19 assigns the current element's index to `smallest`. When this loop finishes,

`smallest` will contain the index of the smallest element in the remaining array. Line 21 calls method `swap` (lines 27–32) to place the smallest remaining element in the next ordered spot in the array.

### Methods `printPass`

The output of method `printPass` uses dashes (lines 52–53) to indicate the portion of the array that's sorted after each pass. An asterisk is placed next to the position of the element that was swapped with the smallest element on that pass. On each pass, the element next to the asterisk (specified at line 43) and the element above the rightmost set of dashes were swapped.

### 19.6.2 Efficiency of the Selection Sort

The selection sort algorithm runs in  $O(n^2)$  time. Method `selectionSort` (lines 9–24) contains two for loops. The outer one (lines 12–23) iterates over the first  $n - 1$  elements in the array, swapping the smallest remaining item into its sorted position. The inner loop (lines 17–19) iterates over each item in the remaining array, searching for the smallest element. This loop executes  $n - 1$  times during the first iteration of the outer loop,  $n - 2$  times during the second iteration, then  $n - 3, \dots, 3, 2, 1$ . This inner loop will iterate a total of  $n(n - 1)/2$  or  $(n^2 - n)/2$ . In Big O notation, smaller terms drop out and constants are ignored, leaving a Big O of  $O(n^2)$ .

## 19.7 Insertion Sort

**Insertion sort** is another *simple, but inefficient*, sorting algorithm. The first iteration of this algorithm takes the *second element* in the array and, if it's *less than* the *first element*, *swaps it with the first element*. The second iteration looks at the third element and inserts it into the correct position with respect to the first two, so all three elements are in order. At the *i*th iteration of this algorithm, the first *i* elements in the original array will be sorted.

Consider as an example the following array, which is identical to the one used in the discussions of selection sort and merge sort.

```
34 56 4 10 77 51 93 30 5 52
```

A program that implements the insertion sort algorithm will first look at the first two elements of the array, 34 and 56. These are already in order, so the program continues. (If they were out of order, the program would swap them.)

In the next iteration, the program looks at the third value, 4. This value is less than 56, so the program stores 4 in a temporary variable and moves 56 one element to the right. The program then checks and determines that 4 is less than 34, so it moves 34 one element to the right. The program has now reached the beginning of the array, so it places 4 in the zeroth element. The array now is

```
4 34 56 10 77 51 93 30 5 52
```

In the next iteration, the program stores 10 in a temporary variable. Then it compares 10 to 56 and moves 56 one element to the right because it's larger than 10. The program then compares 10 to 34, moving 34 right one element. When the program compares 10 to 4, it observes that 10 is larger than 4 and places 10 in element 1. The array now is

```
4 10 34 56 77 51 93 30 5 52
```



Using this algorithm, at the  $i$ th iteration, the first  $i$  elements of the original array are sorted, but they may not be in their final locations—smaller values may be located later in the array.

### 19.7.1 Insertion Sort Implementation

Class `InsertionSortTest` (Fig. 19.5) contains:

- static method `insertionSort` to sort ints using the insertion sort algorithm
- static method `printPass` to display the array contents after each pass, and
- `main` to test method `insertionSort`.

Method `main` (lines 53–68) is identical to `main` in Fig. 19.4 except that line 64 calls method `insertionSort`.

---

```

1 // Fig. 19.5: InsertionSortTest.java
2 // Sorting an array with insertion sort.
3 import java.security.SecureRandom;
4 import java.util.Arrays;
5
6 public class InsertionSortTest
7 {
8 // sort array using insertion sort
9 public static void insertionSort(int[] data)
10 {
11 // loop over data.length - 1 elements
12 for (int next = 1; next < data.length; next++)
13 {
14 int insert = data[next]; // value to insert
15 int moveItem = next; // location to place element
16
17 // search for place to put current element
18 while (moveItem > 0 && data[moveItem - 1] > insert)
19 {
20 // shift element right one slot
21 data[moveItem] = data[moveItem - 1];
22 moveItem--;
23 }
24
25 data[moveItem] = insert; // place inserted element
26 printPass(data, next, moveItem); // output pass of algorithm
27 }
28 }
29
30 // print a pass of the algorithm
31 public static void printPass(int[] data, int pass, int index)
32 {
33 System.out.printf("after pass %2d: ", pass);
34
35 // output elements till swapped item
36 for (int i = 0; i < index; i++)
37 System.out.printf("%d ", data[i]);

```

---

**Fig. 19.5** | Sorting an array with insertion sort. (Part I of 3.)

```

38
39 System.out.printf("%d* ", data[index]); // indicate swap
40
41 // finish outputting array
42 for (int i = index + 1; i < data.length; i++)
43 System.out.printf("%d ", data[i]);
44
45 System.out.printf("%n "); // for alignment
46
47 // indicate amount of array that's sorted
48 for (int i = 0; i <= pass; i++)
49 System.out.print("-- ");
50 System.out.println();
51 }
52
53 public static void main(String[] args)
54 {
55 SecureRandom generator = new SecureRandom();
56
57 int[] data = new int[10]; // create array
58
59 for (int i = 0; i < data.length; i++) // populate array
60 data[i] = 10 + generator.nextInt(90);
61
62 System.out.printf("Unsorted array:%n%s%n%n",
63 Arrays.toString(data)); // display array
64 insertionSort(data); // sort array
65
66 System.out.printf("Sorted array:%n%s%n%n",
67 Arrays.toString(data)); // display array
68 }
69 } // end class InsertionSortTest

```

```

Unsorted array:
[34, 96, 12, 87, 40, 80, 16, 50, 30, 45]

after pass 1: 34 96* 12 87 40 80 16 50 30 45
 -- --
after pass 2: 12* 34 96 87 40 80 16 50 30 45
 -- --
after pass 3: 12 34 87* 96 40 80 16 50 30 45
 -- --
after pass 4: 12 34 40* 87 96 80 16 50 30 45
 -- --
after pass 5: 12 34 40 80* 87 96 16 50 30 45
 -- --
after pass 6: 12 16* 34 40 80 87 96 50 30 45
 -- --
after pass 7: 12 16 34 40 50* 80 87 96 30 45
 -- --
after pass 8: 12 16 30* 34 40 50 80 87 96 45
 -- --

```

**Fig. 19.5** | Sorting an array with insertion sort. (Part 2 of 3.)

```

after pass 9: 12 16 30 34 40 45* 50 80 87 96
 -- -- -- -- -- -- -- -- --
Sorted array:
[12, 16, 30, 34, 40, 45, 50, 80, 87, 96]

```

**Fig. 19.5** | Sorting an array with insertion sort. (Part 3 of 3.)

### *Method insertionSort*

Lines 9–28 declare the `insertionSort` method. Lines 12–27 loop over `data.length - 1` items in the array. In each iteration, line 14 declares and initializes variable `insert`, which holds the value of the element that will be inserted into the sorted portion of the array. Line 15 declares and initializes the variable `moveItem`, which keeps track of where to insert the element. Lines 18–23 loop to locate the correct position where the element should be inserted. The loop will terminate either when the program reaches the front of the array or when it reaches an element that's less than the value to be inserted. Line 21 moves an element to the right in the array, and line 22 decrements the position at which to insert the next element. After the loop ends, line 25 inserts the element into place.

### *Method printPass*

The output of method `printPass` (lines 31–51) uses dashes to indicate the portion of the array that's sorted after each pass. An asterisk is placed next to the element that was inserted into place on that pass.

## 19.7.2 Efficiency of the Insertion Sort

The insertion sort algorithm also runs in  $O(n^2)$  time. Like selection sort, the implementation of insertion sort (lines 9–28) contains two loops. The `for` loop (lines 12–27) iterates `data.length - 1` times, inserting an element into the appropriate position in the elements sorted so far. For the purposes of this application, `data.length - 1` is equivalent to  $n - 1$  (as `data.length` is the size of the array). The `while` loop (lines 18–23) iterates over the preceding elements in the array. In the worst case, this `while` loop will require  $n - 1$  comparisons. Each individual loop runs in  $O(n)$  time. In Big O notation, nested loops mean that you must *multiply* the number of comparisons. For each iteration of an outer loop, there will be a certain number of iterations of the inner loop. In this algorithm, for each  $O(n)$  iterations of the outer loop, there will be  $O(n)$  iterations of the inner loop. Multiplying these values results in a Big O of  $O(n^2)$ .

## 19.8 Merge Sort

**Merge sort** is an *efficient* sorting algorithm but is conceptually *more complex* than selection sort and insertion sort. The merge sort algorithm sorts an array by *splitting* it into two equal-sized subarrays, *sorting* each subarray, then *merging* them into one larger array. With an odd number of elements, the algorithm creates the two subarrays such that one has one more element than the other.

The implementation of merge sort in this example is recursive. The base case is an array with one element, which is, of course, sorted, so the merge sort immediately returns in this case. The recursion step splits the array into two approximately equal pieces, recursively sorts them, then merges the two sorted arrays into one larger, sorted array.

Suppose the algorithm has already merged smaller arrays to create sorted arrays A:

|   |    |    |    |    |
|---|----|----|----|----|
| 4 | 10 | 34 | 56 | 77 |
|---|----|----|----|----|

and B:

|   |    |    |    |    |
|---|----|----|----|----|
| 5 | 30 | 51 | 52 | 93 |
|---|----|----|----|----|

Merge sort combines these two arrays into one larger, sorted array. The smallest element in A is 4 (located in the zeroth index of A). The smallest element in B is 5 (located in the zeroth index of B). In order to determine the smallest element in the larger array, the algorithm compares 4 and 5. The value from A is smaller, so 4 becomes the first element in the merged array. The algorithm continues by comparing 10 (the second element in A) to 5 (the first element in B). The value from B is smaller, so 5 becomes the second element in the larger array. The algorithm continues by comparing 10 to 30, with 10 becoming the third element in the array, and so on.

### 19.8.1 Merge Sort Implementation

Figure 19.6 declares the `MergeSortTest` class, which contains:

- static method `mergeSort` to initiate the sorting of an `int` array using the merge sort algorithm
- static method `sortArray` to perform the recursive merge sort algorithm—this is called by method `mergeSort`
- static method `merge` to merge two sorted subarrays into a single sorted subarray
- static method `subarrayString` to get a subarray's `String` representation for output purposes, and
- `main` to test method `mergeSort`.

Method `main` (lines 101–116) is identical to `main` in Figs. 19.4–19.5 except that line 112 calls method `mergeSort`. The output from this program displays the splits and merges performed by merge sort, showing the progress of the sort at each step of the algorithm. It's well worth your time to step through these outputs to fully understand this elegant sorting algorithm.

---

```

1 // Fig. 19.6: MergeSortTest.java
2 // Sorting an array with merge sort.
3 import java.security.SecureRandom;
4 import java.util.Arrays;
5
6 public class MergeSortTest
7 {
8 // calls recursive split method to begin merge sorting
9 public static void mergeSort(int[] data)
10 {
11 sortArray(data, 0, data.length - 1); // sort entire array
12 } // end method sort
13

```

---

**Fig. 19.6** | Sorting an array with merge sort. (Part I of 5.)

---

```

14 // splits array, sorts subarrays and merges subarrays into sorted array
15 private static void sortArray(int[] data, int low, int high)
16 {
17 // test base case; size of array equals 1
18 if ((high - low) >= 1) // if not base case
19 {
20 int middle1 = (low + high) / 2; // calculate middle of array
21 int middle2 = middle1 + 1; // calculate next element over
22
23 // output split step
24 System.out.printf("split: %s\n",
25 subarrayString(data, low, high));
26 System.out.printf(" %s\n",
27 subarrayString(data, low, middle1));
28 System.out.printf(" %s\n\n",
29 subarrayString(data, middle2, high));
30
31 // split array in half; sort each half (recursive calls)
32 sortArray(data, low, middle1); // first half of array
33 sortArray(data, middle2, high); // second half of array
34
35 // merge two sorted arrays after split calls return
36 merge (data, low, middle1, middle2, high);
37 } // end if
38 } // end method sortArray
39
40 // merge two sorted subarrays into one sorted subarray
41 private static void merge(int[] data, int left, int middle1,
42 int middle2, int right)
43 {
44 int leftIndex = left; // index into left subarray
45 int rightIndex = middle2; // index into right subarray
46 int combinedIndex = left; // index into temporary working array
47 int[] combined = new int[data.length]; // working array
48
49 // output two subarrays before merging
50 System.out.printf("merge: %s\n",
51 subarrayString(data, left, middle1));
52 System.out.printf(" %s\n",
53 subarrayString(data, middle2, right));
54
55 // merge arrays until reaching end of either
56 while (leftIndex <= middle1 && rightIndex <= right)
57 {
58 // place smaller of two current elements into result
59 // and move to next space in arrays
60 if (data[leftIndex] <= data[rightIndex])
61 combined[combinedIndex++] = data[leftIndex++];
62 else
63 combined[combinedIndex++] = data[rightIndex++];
64 }
65

```

---

**Fig. 19.6** | Sorting an array with merge sort. (Part 2 of 5.)

---

```

66 // if left array is empty
67 if (leftIndex == middle2)
68 // copy in rest of right array
69 while (rightIndex <= right)
70 combined[combinedIndex++] = data[rightIndex++];
71 else // right array is empty
72 // copy in rest of left array
73 while (leftIndex <= middle1)
74 combined[combinedIndex++] = data[leftIndex++];
75
76 // copy values back into original array
77 for (int i = left; i <= right; i++)
78 data[i] = combined[i];
79
80 // output merged array
81 System.out.printf(" %s%n%n",
82 subarrayString(data, left, right));
83 } // end method merge
84
85 // method to output certain values in array
86 private static String subarrayString(int[] data, int low, int high)
87 {
88 StringBuilder temporary = new StringBuilder();
89
90 // output spaces for alignment
91 for (int i = 0; i < low; i++)
92 temporary.append(" ");
93
94 // output elements left in array
95 for (int i = low; i <= high; i++)
96 temporary.append(" " + data[i]);
97
98 return temporary.toString();
99 }
100
101 public static void main(String[] args)
102 {
103 SecureRandom generator = new SecureRandom();
104
105 int[] data = new int[10]; // create array
106
107 for (int i = 0; i < data.length; i++) // populate array
108 data[i] = 10 + generator.nextInt(90);
109
110 System.out.printf("Unsorted array:%n%s%n%n",
111 Arrays.toString(data)); // display array
112 mergeSort(data); // sort array
113
114 System.out.printf("Sorted array:%n%s%n%n",
115 Arrays.toString(data)); // display array
116 }
117 } // end class MergeSortTest

```

---

**Fig. 19.6** | Sorting an array with merge sort. (Part 3 of 5.)

```

Unsorted array:
[75, 56, 85, 90, 49, 26, 12, 48, 40, 47]

split: 75 56 85 90 49 26 12 48 40 47
 75 56 85 90 49
 26 12 48 40 47

split: 75 56 85 90 49
 75 56 85
 90 49

split: 75 56 85
 75 56
 85

split: 75 56
 75
 56

merge: 75
 56
 56 75

merge: 56 75
 85
 56 75 85

split: 90 49
 90
 49

merge: 90
 49
 49 90

merge: 56 75 85
 49 90
 49 56 75 85 90

split: 26 12 48 40 47
 26 12 48
 40 47

split: 26 12 48
 26 12
 48

split: 26 12
 26
 12

merge: 26
 12
 12 26

merge: 12 26
 48
 12 26 48

split: 40 47
 40
 47

```

**Fig. 19.6** | Sorting an array with merge sort. (Part 4 of 5.)

```

merge: 40
 47
 40 47

merge: 12 26 48
 40 47
 12 26 40 47 48

merge: 49 56 75 85 90
 12 26 40 47 48
 12 26 40 47 48 49 56 75 85 90

Sorted array:
[12, 26, 40, 47, 48, 49, 56, 75, 85, 90]

```

**Fig. 19.6** | Sorting an array with merge sort. (Part 5 of 5.)

### **Method `mergeSort`**

Lines 9–12 of Fig. 19.6 declare the `mergeSort` method. Line 11 calls method `sortArray` with 0 and `data.length - 1` as the arguments—corresponding to the beginning and ending indices, respectively, of the array to be sorted. These values tell method `sortArray` to operate on the entire array.

### **Method `sortArray`**

Recursive method `sortArray` (lines 15–38) performs the recursive merge sort algorithm. Line 18 tests the base case. If the size of the array is 1, the array is already sorted, so the method returns immediately. If the size of the array is greater than 1, the method splits the array in two, recursively calls method `sortArray` to sort the two subarrays, then merges them. Line 32 recursively calls method `sortArray` on the first half of the array, and line 33 recursively calls method `sortArray` on the second half. When these two method calls return, each half of the array has been sorted. Line 36 calls method `merge` (lines 41–83) on the two halves of the array to combine the two sorted arrays into one larger sorted array.

### **Method `merge`**

Lines 41–83 declare method `merge`. Lines 56–64 in merge loop until the end of either subarray is reached. Line 60 tests which element at the beginning of the arrays is smaller. If the element in the left array is smaller, line 61 places it in position in the combined array. If the element in the right array is smaller, line 63 places it in position in the combined array. When the `while` loop completes, one entire subarray has been placed in the combined array, but the other subarray still contains data. Line 67 tests whether the left array has reached the end. If so, lines 69–70 fill the combined array with the elements of the right array. If the left array has not reached the end, then the right array must have reached the end, and lines 73–74 fill the combined array with the elements of the left array. Finally, lines 77–78 copy the combined array into the original array.

## **19.8.2 Efficiency of the Merge Sort**

Merge sort is *far more efficient* than insertion or selection sort. Consider the first (non-recursive) call to `sortArray`. This results in two recursive calls to `sortArray` with subarrays each approximately half the original array's size, and a single call to `merge`, which requires, at worst,  $n - 1$  comparisons to fill the original array, which is  $O(n)$ . (Recall that each array element can be chosen by comparing one element from each subarray.) The two calls to `sort-`



Array result in four more recursive `sortArray` calls, each with a subarray approximately a quarter of the original array's size, along with two calls to `merge` that each require, at worst,  $n/2 - 1$  comparisons, for a total number of comparisons of  $O(n)$ . This process continues, each `sortArray` call generating two additional `sortArray` calls and a `merge` call, until the algorithm has *split* the array into one-element subarrays. At each level,  $O(n)$  comparisons are required to *merge* the subarrays. Each level splits the the arrays in half, so doubling the array size requires one more level. Quadrupling the array size requires two more levels. This pattern is logarithmic and results in  $\log_2 n$  levels. This results in a total efficiency of  $O(n \log n)$ .

## 19.9 Big O Summary for This Chapter's Searching and Sorting Algorithms

Figure 19.7 summarizes the searching and sorting algorithms covered in this chapter with the Big O for each. Figure 19.8 lists the Big O values we've covered in this chapter along with a number of values for  $n$  to highlight the differences in the growth rates.

| Algorithm                    | Location                | Big O         |
|------------------------------|-------------------------|---------------|
| <i>Searching Algorithms:</i> |                         |               |
| Linear search                | Section 19.2            | $O(n)$        |
| Binary search                | Section 19.4            | $O(\log n)$   |
| Recursive linear search      | Exercise 19.8           | $O(n)$        |
| Recursive binary search      | Exercise 19.9           | $O(\log n)$   |
| <i>Sorting Algorithms:</i>   |                         |               |
| Selection sort               | Section 19.6            | $O(n^2)$      |
| Insertion sort               | Section 19.7            | $O(n^2)$      |
| Merge sort                   | Section 19.8            | $O(n \log n)$ |
| Bubble sort                  | Exercises 19.5 and 19.6 | $O(n^2)$      |

**Fig. 19.7** | Searching and sorting algorithms with Big O values.

| $n =$         | $O(\log n)$ | $O(n)$        | $O(n \log n)$ | $O(n^2)$  |
|---------------|-------------|---------------|---------------|-----------|
| 1             | 0           | 1             | 0             | 1         |
| 2             | 1           | 2             | 2             | 4         |
| 3             | 1           | 3             | 3             | 9         |
| 4             | 1           | 4             | 4             | 16        |
| 5             | 1           | 5             | 5             | 25        |
| 10            | 1           | 10            | 10            | 100       |
| 100           | 2           | 100           | 200           | 10,000    |
| 1000          | 3           | 1000          | 3000          | $10^6$    |
| 1,000,000     | 6           | 1,000,000     | 6,000,000     | $10^{12}$ |
| 1,000,000,000 | 9           | 1,000,000,000 | 9,000,000,000 | $10^{18}$ |

**Fig. 19.8** | Number of comparisons for common Big O notations.

## 19.10 Wrap-Up

This chapter introduced searching and sorting. We discussed two searching algorithms—linear search and binary search—and three sorting algorithms—selection sort, insertion sort and merge sort. We introduced Big O notation, which helps you analyze the efficiency of an algorithm. The next two chapters continue our discussion of dynamic data structures that can grow or shrink at execution time. Chapter 20 demonstrates how to use Java’s generics capabilities to implement generic methods and classes. Chapter 21 discusses the details of implementing generic data structures. Each of the algorithms in this chapter is “single threaded”—in Chapter 23, Concurrency, we’ll discuss multithreading and how it can help you program for better performance on today’s multi-core systems.

### Summary

#### *Section 19.1 Introduction*

- Searching (p. 803) involves determining if a search key is in the data and, if so, finding its location.
- Sorting (p. 803) involves arranging data into order.

#### *Section 19.2 Linear Search*

- The linear search algorithm (p. 804) searches each element in the array sequentially until it finds the correct element, or until it reaches the end of the array without finding the element.

#### *Section 19.3 Big O Notation*

- A major difference among searching algorithms is the amount of effort they require.
- Big O notation (p. 806) describes an algorithm’s efficiency in terms of the work required to solve a problem. For searching and sorting algorithms typically it depends on the number of elements in the data.
- An algorithm that’s  $O(1)$  does not necessarily require only one comparison (p. 807). It just means that the number of comparisons does not grow as the size of the array increases.
- An  $O(n)$  algorithm is referred to as having a linear run time (p. 807).
- Big O highlights dominant factors and ignores terms that become unimportant with high  $n$  values.
- Big O notation is concerned with the growth rate of algorithm run times, so constants are ignored.
- The linear search algorithm runs in  $O(n)$  time.
- The worst case in linear search is that every element must be checked to determine whether the search key (p. 808) exists, which occurs if the search key is the last array element or is not present.

#### *Section 19.4 Binary Search*

- Binary search (p. 808) is more efficient than linear search, but it requires that the array be sorted.
- The first iteration of binary search tests the middle element in the array. If this is the search key, the algorithm returns its location. If the search key is less than the middle element, the search continues with the first half of the array. If the search key is greater than the middle element, the search continues with the second half of the array. Each iteration tests the middle value of the remaining array and, if the element is not found, eliminates half of the remaining elements.
- Binary search is a more efficient searching algorithm than linear search because each comparison eliminates from consideration half of the elements in the array.

- Binary search runs in  $O(\log n)$  time because each step removes half of the remaining elements; this is also known as logarithmic run time (p. 812).
- If the array size is doubled, binary search requires only one extra comparison.

### Section 19.6 Selection Sort

- Selection sort (p. 813) is a simple, but inefficient, sorting algorithm.
- The sort begins by selecting the smallest item and swaps it with the first element. The second iteration selects the second-smallest item (which is the smallest remaining item) and swaps it with the second element. The sort continues until the last iteration selects the second-largest element and swaps it with the second-to-last element, leaving the largest element in the last index. At the  $i$ th iteration of selection sort, the smallest  $i$  items of the whole array are sorted into the first  $i$  indices.
- The selection sort algorithm runs in  $O(n^2)$  time (p. 816).

### Section 19.7 Insertion Sort

- The first iteration of insertion sort (p. 816) takes the second element in the array and, if it's less than the first element, swaps it with the first element. The second iteration looks at the third element and inserts it in the correct position with respect to the first two elements. After the  $i$ th iteration of insertion sort, the first  $i$  elements in the original array are sorted.
- The insertion sort algorithm runs in  $O(n^2)$  time (p. 819).

### Section 19.8 Merge Sort

- Merge sort (p. 819) is a sorting algorithm that's faster, but more complex to implement, than selection sort and insertion sort. The merge sort algorithm sorts an array by splitting it into two equal-sized subarrays, sorting each subarray recursively and merging the subarrays into one larger array.
- Merge sort's base case is an array with one element. A one-element array is already sorted, so merge sort immediately returns when it's called with a one-element array. The merge part of merge sort takes two sorted arrays and combines them into one larger sorted array.
- Merge sort performs the merge by looking at the first element in each array, which is also the smallest element in the array. Merge sort takes the smallest of these and places it in the first element of the larger array. If there are still elements in the subarray, merge sort looks at the second of these (which is now the smallest element remaining) and compares it to the first element in the other subarray. Merge sort continues this process until the larger array is filled.
- In the worst case, the first call to merge sort has to make  $O(n)$  comparisons to fill the  $n$  slots in the final array.
- The merging portion of the merge sort algorithm is performed on two subarrays, each of approximately size  $n/2$ . Creating each of these subarrays requires  $n/2 - 1$  comparisons for each subarray, or  $O(n)$  comparisons total. This pattern continues as each level works on twice as many arrays, but each is half the size of the previous array.
- Similar to binary search, this halving results in  $\log n$  levels for a total efficiency of  $O(n \log n)$  (p. 825).

## Self-Review Exercises

- 19.1** Fill in the blanks in each of the following statements:
- a) A selection sort application would take approximately \_\_\_\_\_ times as long to run on a 128-element array as on a 32-element array.
  - b) The efficiency of merge sort is \_\_\_\_\_.
- 19.2** What key aspect of both the binary search and the merge sort accounts for the logarithmic portion of their respective Big Os?

**19.3** In what sense is the insertion sort superior to the merge sort? In what sense is the merge sort superior to the insertion sort?

**19.4** In the text, we say that after the merge sort splits the array into two subarrays, it then sorts these two subarrays and merges them. Why might someone be puzzled by our statement that “it then sorts these two subarrays”?

## Answers to Self-Review Exercises

**19.1** a) 16, because an  $O(n^2)$  algorithm takes 16 times as long to sort four times as much information. b)  $O(n \log n)$ .

**19.2** Both of these algorithms incorporate “halving”—somehow reducing something by half. The binary search eliminates from consideration one-half of the array after each comparison. The merge sort splits the array in half each time it’s called.

**19.3** The insertion sort is easier to understand and to program than the merge sort. The merge sort is far more efficient [ $O(n \log n)$ ] than the insertion sort [ $O(n^2)$ ].

**19.4** In a sense, it does not really sort these two subarrays. It simply keeps splitting the original array in half until it provides a one-element subarray, which is, of course, sorted. It then builds up the original two subarrays by merging these one-element arrays to form larger subarrays, which are then merged, and so on.

## Exercises

**19.5** (*Bubble Sort*) Implement bubble sort—another simple yet inefficient sorting technique. It’s called bubble sort or sinking sort because smaller values gradually “bubble” their way to the top of the array (i.e., toward the first element) like air bubbles rising in water, while the larger values sink to the bottom (end) of the array. The technique uses nested loops to make several passes through the array. Each pass compares successive pairs of elements. If a pair is in increasing order (or the values are equal), the bubble sort leaves the values as they are. If a pair is in decreasing order, the bubble sort swaps their values in the array. The first pass compares the first two elements of the array and swaps their values if necessary. It then compares the second and third elements in the array. The end of this pass compares the last two elements in the array and swaps them if necessary. After one pass, the largest element will be in the last index. After two passes, the largest two elements will be in the last two indices. Explain why bubble sort is an  $O(n^2)$  algorithm.

**19.6** (*Enhanced Bubble Sort*) Make the following simple modifications to improve the performance of the bubble sort you developed in Exercise 19.5:

- a) After the first pass, the largest number is guaranteed to be in the highest-numbered array element; after the second pass, the two highest numbers are “in place”; and so on. Instead of making nine comparisons on every pass for a ten-element array, modify the bubble sort to make eight comparisons on the second pass, seven on the third pass, and so on.
- b) The data in the array may already be in proper or near-proper order, so why make nine passes if fewer will suffice? Modify the sort to check at the end of each pass whether any swaps have been made. If there were none, the data must already be sorted, so the program should terminate. If swaps have been made, at least one more pass is needed.

**19.7** (*Bucket Sort*) A bucket sort begins with a one-dimensional array of positive integers to be sorted and a two-dimensional array of integers with rows indexed from 0 to 9 and columns indexed from 0 to  $n - 1$ , where  $n$  is the number of values to be sorted. Each row of the two-dimensional array

is referred to as a *bucket*. Write a class named `BucketSort` containing a method called `sort` that operates as follows:

- a) Place each value of the one-dimensional array into a row of the bucket array, based on the value's "ones" (rightmost) digit. For example, 97 is placed in row 7, 3 is placed in row 3 and 100 is placed in row 0. This procedure is called a *distribution pass*.
- b) Loop through the bucket array row by row, and copy the values back to the original array. This procedure is called a *gathering pass*. The new order of the preceding values in the one-dimensional array is 100, 3 and 97.
- c) Repeat this process for each subsequent digit position (tens, hundreds, thousands, etc.). On the second (tens digit) pass, 100 is placed in row 0, 3 is placed in row 0 (because 3 has no tens digit) and 97 is placed in row 9. After the gathering pass, the order of the values in the one-dimensional array is 100, 3 and 97. On the third (hundreds digit) pass, 100 is placed in row 1, 3 is placed in row 0 and 97 is placed in row 0 (after the 3). After this last gathering pass, the original array is in sorted order.

The two-dimensional array of buckets is 10 times the length of the integer array being sorted. This sorting technique provides better performance than a bubble sort, but requires much more memory—the bubble sort requires space for only one additional element of data. This comparison is an example of the space/time trade-off: The bucket sort uses more memory than the bubble sort, but performs better. This version of the bucket sort requires copying all the data back to the original array on each pass. Another possibility is to create a second two-dimensional bucket array and repeatedly swap the data between the two bucket arrays.

**19.8 (Recursive Linear Search)** Modify Fig. 19.2 to use recursive method `recursiveLinearSearch` to perform a linear search of the array. The method should receive the search key and starting index as arguments. If the search key is found, return its index in the array; otherwise, return -1. Each call to the recursive method should check one index in the array.

**19.9 (Recursive Binary Search)** Modify Fig. 19.3 to use recursive method `recursiveBinarySearch` to perform a binary search of the array. The method should receive the search key, starting index and ending index as arguments. If the search key is found, return its index in the array. If the search key is not found, return -1.

**19.10 (Quicksort)** The recursive sorting technique called quicksort uses the following basic algorithm for a one-dimensional array of values:

- a) *Partitioning Step*: Take the first element of the unsorted array and determine its final location in the sorted array (i.e., all values to the left of the element in the array are less than the element, and all values to the right of the element in the array are greater than the element—we show how to do this below). We now have one element in its proper location and two unsorted subarrays.
- b) *Recursive Step*: Perform *Step 1* on each unsorted subarray. Each time *Step 1* is performed on a subarray, another element is placed in its final location of the sorted array, and two unsorted subarrays are created. When a subarray consists of one element, that element is in its final location (because a one-element array is already sorted).

The basic algorithm seems simple enough, but how do we determine the final position of the first element of each subarray? As an example, consider the following set of values (the element in bold is the partitioning element—it will be placed in its final location in the sorted array):

37 2 6 4 89 8 10 12 68 45

Starting from the rightmost element of the array, compare each element with 37 until an element less than 37 is found; then swap 37 and that element. The first element less than 37 is 12, so 37 and 12 are swapped. The new array is

*12* 2 6 4 89 8 10 37 68 45

Element 12 is in italics to indicate that it was just swapped with 37.

Starting from the left of the array, but beginning with the element after 12, compare each element with 37 until an element greater than 37 is found—then swap 37 and that element. The first element greater than 37 is 89, so 37 and 89 are swapped. The new array is

12 2 6 4 37 8 10 89 68 45

Starting from the right, but beginning with the element before 89, compare each element with 37 until an element less than 37 is found—then swap 37 and that element. The first element less than 37 is 10, so 37 and 10 are swapped. The new array is

12 2 6 4 *10* 8 37 89 68 45

Starting from the left, but beginning with the element after 10, compare each element with 37 until an element greater than 37 is found—then swap 37 and that element. There are no more elements greater than 37, so when we compare 37 with itself, we know that 37 has been placed in its final location in the sorted array. Every value to the left of 37 is smaller than it, and every value to the right of 37 is larger than it.

Once the partition has been applied on the previous array, there are two unsorted subarrays. The subarray with values less than 37 contains 12, 2, 6, 4, 10 and 8. The subarray with values greater than 37 contains 89, 68 and 45. The sort continues recursively, with both subarrays being partitioned in the same manner as the original array.

Based on the preceding discussion, write recursive method `quickSortHelper` to sort a one-dimensional integer array. The method should receive as arguments a starting index and an ending index on the original array being sorted.

# Generic Classes and Methods

# 20



*...our special individuality, as distinguished from our generic humanity.*

—Oliver Wendell Holmes, Sr.

*Born under one law, to another bound.*

—Lord Brooke

## Objectives

In this chapter you'll:

- Create generic methods that perform identical tasks on arguments of different types.
- Create a generic `Stack` class that can be used to store objects of any class or interface type.
- Understand compile-time translation of generic methods and classes.
- Understand how to overload generic methods with nongeneric methods or other generic methods.
- Understand raw types.
- Use wildcards when precise type information about a parameter is not required in the method body.

- |                                                                                                              |                                                              |
|--------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------|
| <b>20.1</b> Introduction                                                                                     | <b>20.5</b> Overloading Generic Methods                      |
| <b>20.2</b> Motivation for Generic Methods                                                                   | <b>20.6</b> Generic Classes                                  |
| <b>20.3</b> Generic Methods: Implementation and Compile-Time Translation                                     | <b>20.7</b> Raw Types                                        |
| <b>20.4</b> Additional Compile-Time Translation Issues: Methods That Use a Type Parameter as the Return Type | <b>20.8</b> Wildcards in Methods That Accept Type Parameters |
|                                                                                                              | <b>20.9</b> Wrap-Up                                          |

Summary | Self-Review Exercises | Answers to Self-Review Exercises | Exercises

## 20.1 Introduction

You've used existing generic methods and classes in Chapters 6 and 16. In this chapter, you'll learn how to write your own.

It would be nice if we could write a single sort method to sort the elements in an `Integer` array, a `String` array or an array of any type that supports ordering (i.e., its elements can be compared). It would also be nice if we could write a single `Stack` class that could be used as a `Stack` of integers, a `Stack` of floating-point numbers, a `Stack` of `Strings` or a `Stack` of any other type. It would be even nicer if we could detect type mismatches at *compile time*—known as **compile-time type safety**. For example, if a `Stack` should store only integers, an attempt to push a `String` onto that `Stack` should issue a *compilation* error. This chapter discusses **generics**—specifically **generic methods** and **generic classes**—which provide the means to create the type-safe general models mentioned above.

## 20.2 Motivation for Generic Methods

Overloaded methods are often used to perform *similar* operations on *different* types of data. To motivate generic methods, let's begin with an example (Fig. 20.1) containing overloaded `printArray` methods (lines 22–29, 32–39 and 42–49) that print the `String` representations of the elements of an `Integer` array, a `Double` array and a `Character` array, respectively. We could have used arrays of primitive types `int`, `double` and `char`. We're using arrays of the type-wrapper classes to set up our generic method example, because *only reference types can be used to specify generic types in generic methods and classes*.

```

1 // Fig. 20.1: OverloadedMethods.java
2 // Printing array elements using overloaded methods.
3
4 public class OverloadedMethods
5 {
6 public static void main(String[] args)
7 {
8 // create arrays of Integer, Double and Character
9 Integer[] integerArray = {1, 2, 3, 4, 5, 6};
10 Double[] doubleArray = {1.1, 2.2, 3.3, 4.4, 5.5, 6.6, 7.7};
11 Character[] characterArray = {'H', 'E', 'L', 'L', 'O'};

```

**Fig. 20.1** | Printing array elements using overloaded methods. (Part 1 of 2.)



```

12
13 System.out.printf("Array integerArray contains:%n");
14 printArray(integerArray); // pass an Integer array
15 System.out.printf("%nArray doubleArray contains:%n");
16 printArray(doubleArray); // pass a Double array
17 System.out.printf("%nArray characterArray contains:%n");
18 printArray(characterArray); // pass a Character array
19 }
20
21 // method printArray to print Integer array
22 public static void printArray(Integer[] inputArray)
23 {
24 // display array elements
25 for (Integer element : inputArray)
26 System.out.printf("%s ", element);
27
28 System.out.println();
29 }
30
31 // method printArray to print Double array
32 public static void printArray(Double[] inputArray)
33 {
34 // display array elements
35 for (Double element : inputArray)
36 System.out.printf("%s ", element);
37
38 System.out.println();
39 }
40
41 // method printArray to print Character array
42 public static void printArray(Character[] inputArray)
43 {
44 // display array elements
45 for (Character element : inputArray)
46 System.out.printf("%s ", element);
47
48 System.out.println();
49 }
50 } // end class OverloadedMethods

```

```

Array integerArray contains:
1 2 3 4 5 6

Array doubleArray contains:
1.1 2.2 3.3 4.4 5.5 6.6 7.7

Array characterArray contains:
H E L L O

```

**Fig. 20.1** | Printing array elements using overloaded methods. (Part 2 of 2.)

The program begins by declaring and initializing three arrays—six-element `Integer` array `integerArray` (line 9), seven-element `Double` array `doubleArray` (line 10) and five-element `Character` array `characterArray` (line 11). Then lines 13–18 display the contents of each array.

When the compiler encounters a method call, it attempts to locate a method declaration with the same name and with parameters that match the argument types in the call. In this example, each `printArray` call matches one of the `printArray` method declarations. For example, line 14 calls `printArray` with `integerArray` as its argument. The compiler determines the argument's type (i.e., `Integer[]`) and attempts to locate a `printArray` method that specifies an `Integer[]` parameter (lines 22–29), then sets up a call to that method. Similarly, when the compiler encounters the call at line 16, it determines the argument's type (i.e., `Double[]`), then attempts to locate a `printArray` method that specifies a `Double[]` parameter (lines 32–39), then sets up a call to that method. Finally, when the compiler encounters the call at line 18, it determines the argument's type (i.e., `Character[]`), then attempts to locate a `printArray` method that specifies a `Character[]` parameter (lines 42–49), then sets up a call to that method.

### *Common Features in the Overloaded `printArray` Methods*

Study each `printArray` method. The array element type appears in each method's header (lines 22, 32 and 42) and `for`-statement header (lines 25, 35 and 45). If we were to replace the element types in each method with a generic name—`T` by convention—then all three methods would look like the one in Fig. 20.2. It appears that if we can replace the array element type in each of the three methods with a *single generic type*, then we should be able to declare *one* `printArray` method that can display the `String` representations of the elements of *any* array that contains objects. The method in Fig. 20.2 is similar to the generic `printArray` method declaration you'll see in Section 20.3. The one shown here *will not compile*—we use this simply to show that the three `printArray` methods of Fig. 20.1 are identical except for the types they process.

---

```

1 public static void printArray(T[] inputArray)
2 {
3 // display array elements
4 for (T element : inputArray)
5 System.out.printf("%s ", element);
6
7 System.out.println();
8 }
```

---

**Fig. 20.2** | `printArray` method in which actual type names are replaced with a generic type name (in this case `T`).

## 20.3 Generic Methods: Implementation and Compile-Time Translation

If the operations performed by several overloaded methods are *identical* for each argument type, the overloaded methods can be more conveniently coded using a generic method. You can write a single generic method declaration that can be called with arguments of different types. Based on the types of the arguments passed to the generic method, the compiler handles each method call appropriately. At *compilation time*, the compiler ensures the *type safety* of your code, preventing many runtime errors.

Figure 20.3 reimplements Fig. 20.1 using a generic `printArray` method (lines 22–29 of Fig. 20.3). The `printArray` calls in lines 14, 16 and 18 are identical to those of

Fig. 20.1 (lines 14, 16 and 18) and the outputs of the two applications are identical. This demonstrates the expressive power of generics.

```

1 // Fig. 20.3: GenericMethodTest.java
2 // Printing array elements using generic method printArray.
3
4 public class GenericMethodTest
5 {
6 public static void main(String[] args)
7 {
8 // create arrays of Integer, Double and Character
9 Integer[] intArray = {1, 2, 3, 4, 5};
10 Double[] doubleArray = {1.1, 2.2, 3.3, 4.4, 5.5, 6.6, 7.7};
11 Character[] charArray = {'H', 'E', 'L', 'L', 'O'};
12
13 System.out.printf("Array integerArray contains:\n");
14 printArray(integerArray); // pass an Integer array
15 System.out.printf("\nArray doubleArray contains:\n");
16 printArray(doubleArray); // pass a Double array
17 System.out.printf("\nArray characterArray contains:\n");
18 printArray(charArray); // pass a Character array
19 }
20
21 // generic method printArray
22 public static <T> void printArray(T[] inputArray)
23 {
24 // display array elements
25 for (T element : inputArray)
26 System.out.printf("%s ", element);
27
28 System.out.println();
29 }
30 } // end class GenericMethodTest

```

```

Array integerArray contains:
1 2 3 4 5 6

Array doubleArray contains:
1.1 2.2 3.3 4.4 5.5 6.6 7.7

Array characterArray contains:
H E L L O

```

**Fig. 20.3** | Printing array elements using generic method printArray.

### *Type Parameter Section of a Generic Method*

Line 22 begins method printArray's declaration. All generic method declarations have a **type-parameter section** (<T> in this example) delimited by **angle brackets** that precedes the method's return type. Each type-parameter section contains one or more **type parameters**, separated by commas. A type parameter, also known as a **type variable**, is an identifier that specifies a generic type name. The type parameters can be used to declare the return type, parameter types and local variable types in a generic method declaration, and

they act as placeholders for the types of the arguments passed to the generic method, which are known as **actual type arguments**. A generic method's body is declared like that of any other method. *Type parameters can represent only reference types*—not primitive types (like `int`, `double` and `char`). Note, too, that the type-parameter names throughout the method declaration must match those declared in the type-parameter section. For example, line 25 declares `element` as type `T`, which matches the type parameter (`T`) declared in line 22. Also, a type parameter can be declared only once in the type-parameter section but can appear more than once in the method's parameter list. For example, the type-parameter name `T` appears twice in the following method's parameter list:

```
public static <T> T maximum(T value1, T value2)
```

Type-parameter names need not be unique among different generic methods. In method `printArray`, `T` appears in the same two locations where the overloaded `printArray` methods of Fig. 20.1 specified `Integer`, `Double` or `Character` as the array element type. The remainder of `printArray` is identical to the versions presented in Fig. 20.1.



### Good Programming Practice 20.1

*The letters `T` (for “type”), `E` (for “element”), `K` (for “key”) and `V` (for “value”) are commonly used as type parameters. For other common ones, see <http://docs.oracle.com/javase/tutorial/java/generics/types.html>.*

### Testing the Generic `printArray` Method

As in Fig. 20.1, the program in Fig. 20.3 begins by declaring and initializing six-element `Integer` array `integerArray` (line 9), seven-element `Double` array `doubleArray` (line 10) and five-element `Character` array `characterArray` (line 11). Then each array is output by calling `printArray` (lines 14, 16 and 18)—once with argument `integerArray`, once with argument `doubleArray` and once with argument `characterArray`.

When the compiler encounters line 14, it first determines argument `integerArray`'s type (i.e., `Integer[]`) and attempts to locate a method named `printArray` that specifies a single `Integer[]` parameter. There's no such method in this example. Next, the compiler determines whether there's a generic method named `printArray` that specifies a single array parameter and uses a type parameter to represent the array element type. The compiler determines that `printArray` (lines 22–29) is a match and sets up a call to the method. The same process is repeated for the calls to method `printArray` at lines 16 and 18.



### Common Programming Error 20.1

*If the compiler cannot match a method call to a nongeneric or a generic method declaration, a compilation error occurs.*



### Common Programming Error 20.2

*If the compiler doesn't find a method declaration that matches a method call exactly, but does find two or more methods that can satisfy the method call, a compilation error occurs. For the complete details of resolving calls to overloaded and generic methods, see <http://docs.oracle.com/javase/specs/jls/se7/html/jls-15.html#jls-15.12>.*

In addition to setting up the method calls, the compiler also determines whether the operations in the method body can be applied to elements of the type stored in the array

argument. The only operation performed on the array elements in this example is to output their `String` representation. Line 26 performs an *implicit `toString` call* on every element. *To work with generics, every element of the array must be an object of a class or interface type.* Since all objects have a `toString` method, the compiler is satisfied that line 26 performs a *valid* operation for any object in `printArray`'s array argument. The `toString` methods of classes `Integer`, `Double` and `Character` return the `String` representation of the underlying `int`, `double` or `char` value, respectively.

### *Erasure at Compilation Time*

When the compiler translates generic method `printArray` into Java bytecodes, it removes the type-parameter section and *replaces the type parameters with actual types*. This process is known as **erasure**. By default all generic types are replaced with type `Object`. So the compiled version of method `printArray` appears as shown in Fig. 20.4—there's only *one* copy of this code, which is used for all `printArray` calls in the example. This is quite different from similar mechanisms in other programming languages, such as C++'s templates, in which a *separate copy of the source code* is generated and compiled for *every* type passed as an argument to the method. As you'll see in Section 20.4, the translation and compilation of generics is a bit more involved than what we've discussed in this section.

By declaring `printArray` as a generic method in Fig. 20.3, we eliminated the need for the overloaded methods of Fig. 20.1 and created a reusable method that can output the `String` representations of the elements in any array that contains objects. However, this particular example could have simply declared the `printArray` method as shown in Fig. 20.4, using an `Object` array as the parameter. This would have yielded the same results, because any `Object` can be output as a `String`. In a generic method, the benefits become more apparent when you place restrictions on the type parameters, as we demonstrate in the next section.

---

```

1 public static void printArray(Object[] inputArray)
2 {
3 // display array elements
4 for (Object element : inputArray)
5 System.out.printf("%s ", element);
6
7 System.out.println();
8 }
```

---

**Fig. 20.4** | Generic method `printArray` after the compiler performs erasure.

## 20.4 Additional Compile-Time Translation Issues: Methods That Use a Type Parameter as the Return Type

Let's consider a generic method in which type parameters are used in the return type and in the parameter list (Fig. 20.5). The application uses a generic method `maximum` to determine and return the largest of its three arguments of the same type. Unfortunately, *the relational operator `>` cannot be used with reference types*. However, it's possible to compare two objects of the same class if that class implements the generic interface `Comparable<T>` (from package `java.lang`). All the type-wrapper classes for primitive types implement this interface.

**Generic interfaces** enable you to specify, with a single interface declaration, a set of related types. `Comparable<T>` objects have a **compareTo method**. For example, if we have two `Integer` objects, `integer1` and `integer2`, they can be compared with the expression:

```
integer1.compareTo(integer2)
```

When you declare a class that implements `Comparable<T>`, you must implement method `compareTo` such that it compares the contents of two objects of that class and returns the comparison results. As specified in interface `Comparable<T>`'s documentation, `compareTo` *must* return 0 if the objects are equal, a negative integer if `object1` is less than `object2` or a positive integer if `object1` is greater than `object2`. For example, class `Integer`'s `compareTo` method compares the `int` values stored in two `Integer` objects. A benefit of implementing interface `Comparable<T>` is that `Comparable<T>` objects can be used with the sorting and searching methods of class `Collections` (package `java.util`). We discussed those methods in Chapter 16. In this example, we'll use method `compareTo` in method `maximum` to help determine the largest value.

---

```

1 // Fig. 20.5: MaximumTest.java
2 // Generic method maximum returns the largest of three objects.
3
4 public class MaximumTest
5 {
6 public static void main(String[] args)
7 {
8 System.out.printf("Maximum of %d, %d and %d is %d%n", 3, 4, 5,
9 maximum(3, 4, 5));
10 System.out.printf("Maximum of %.1f, %.1f and %.1f is %.1f%n",
11 6.6, 8.8, 7.7, maximum(6.6, 8.8, 7.7));
12 System.out.printf("Maximum of %s, %s and %s is %s%n", "pear",
13 "apple", "orange", maximum("pear", "apple", "orange"));
14 }
15
16 // determines the largest of three Comparable objects
17 public static <T extends Comparable<T>> T maximum(T x, T y, T z)
18 {
19 T max = x; // assume x is initially the largest
20
21 if (y.compareTo(max) > 0)
22 max = y; // y is the largest so far
23
24 if (z.compareTo(max) > 0)
25 max = z; // z is the largest
26
27 return max; // returns the largest object
28 }
29 } // end class MaximumTest

```

```

Maximum of 3, 4 and 5 is 5
Maximum of 6.6, 8.8 and 7.7 is 8.8
Maximum of pear, apple and orange is pear

```

**Fig. 20.5** | Generic method `maximum` with an upper bound on its type parameter.

*Generic Method **maximum** and Specifying a Type Parameter's Upper Bound*

Generic method `maximum` (lines 17–28) uses type parameter `T` as the return type of the method (line 17), as the type of method parameters `x`, `y` and `z` (line 17), and as the type of local variable `max` (line 19). The type-parameter section specifies that `T` extends `Comparable<T>`—only objects of classes that implement interface `Comparable<T>` can be used with this method. `Comparable<T>` is known as the type parameter's **upper bound**. By default, `Object` is the upper bound, meaning that an object of any type can be used. Type-parameter declarations that bound the parameter always use keyword `extends` regardless of whether the type parameter extends a class or implements an interface. The upper bound may be a comma-separated list that contains zero or one class and zero or more interfaces.

Method `maximum`'s type parameter is more restrictive than the one specified for `printArray` in Fig. 20.3, which was able to output arrays containing any type of object. The `Comparable<T>` restriction is important, because not all objects can be compared. However, `Comparable<T>` objects are guaranteed to have a `compareTo` method.

Method `maximum` uses the same algorithm that we used in Section 5.4 to determine the largest of its three arguments. The method assumes that its first argument (`x`) is the largest and assigns it to local variable `max` (line 19). Next, the `if` statement at lines 21–22 determines whether `y` is greater than `max`. The condition invokes `y`'s `compareTo` method with the expression `y.compareTo(max)`, which returns a negative integer, 0 or a positive integer, to determine `y`'s relationship to `max`. If the return value of the `compareTo` is greater than 0, then `y` is greater and is assigned to variable `max`. Similarly, the `if` statement at lines 24–25 determines whether `z` is greater than `max`. If so, line 25 assigns `z` to `max`. Then line 27 returns `max` to the caller.

*Calling Method **maximum***

In `main` (lines 6–14), line 9 calls `maximum` with the integers 3, 4 and 5. When the compiler encounters this call, it first looks for a `maximum` method that takes three arguments of type `int`. There's no such method, so the compiler looks for a generic method that can be used and finds generic method `maximum`. However, recall that the arguments to a generic method must be of a *reference type*. So the compiler autoboxes the three `int` values as `Integer` objects and specifies that the three `Integer` objects will be passed to `maximum`. Class `Integer` (package `java.lang`) implements the `Comparable<Integer>` interface such that method `compareTo` compares the `int` values in two `Integer` objects. Therefore, `Integers` are valid arguments to method `maximum`. When the `Integer` representing the maximum is returned, we attempt to output it with the `%d` format specifier, which outputs an `int` primitive-type value. So `maximum`'s return value is output as an `int` value.

A similar process occurs for the three `double` arguments passed to `maximum` in line 11. Each `double` is autoboxed as a `Double` object and passed to `maximum`. Again, this is allowed because class `Double` (package `java.lang`) implements the `Comparable<Double>` interface. The `Double` returned by `maximum` is output with the format specifier `%.1f`, which outputs a `double` primitive-type value. So `maximum`'s return value is auto-unboxed and output as a `double`. The call to `maximum` in line 13 receives three `Strings`, which are also `Comparable<String>` objects. We intentionally placed the largest value in a different position in each method call (lines 9, 11 and 13) to show that the generic method always finds the maximum value, regardless of its position in the argument list.

*Erasure and the Upper Bound of a Type Parameter*

When the compiler translates method `maximum` into bytecodes, it uses erasure to replace the type parameters with actual types. In Fig. 20.3, all generic types were replaced with type `Object`. Actually, all type parameters are replaced with the *upper bound* of the type parameter, which is specified in the type-parameter section. Figure 20.6 simulates the erasure of method `maximum`'s types by showing the method's source code after the type-parameter section is removed and type parameter `T` is replaced with the upper bound, `Comparable`, throughout the method declaration. The erasure of `Comparable<T>` is simply `Comparable`.

---

```

1 public static Comparable maximum(Comparable x, Comparable y, Comparable z)
2 {
3 Comparable max = x; // assume x is initially the largest
4
5 if (y.compareTo(max) > 0)
6 max = y; // y is the largest so far
7
8 if (z.compareTo(max) > 0)
9 max = z; // z is the largest
10
11 return max; // returns the largest object
12 }

```

---

**Fig. 20.6** | Generic method `maximum` after erasure is performed by the compiler.

After erasure, method `maximum` specifies that it returns type `Comparable`. However, the calling method does not expect to receive a `Comparable`. It expects to receive an object of the same type that was passed to `maximum` as an argument—`Integer`, `Double` or `String` in this example. When the compiler replaces the type-parameter information with the upper-bound type in the method declaration, it also inserts *explicit cast operations* in front of each method call to ensure that the returned value is of the type expected by the caller. Thus, the call to `maximum` in line 9 (Fig. 20.5) is preceded by an `Integer` cast, as in

```
(Integer) maximum(3, 4, 5)
```

the call to `maximum` in line 11 is preceded by a `Double` cast, as in

```
(Double) maximum(6.6, 8.8, 7.7)
```

and the call to `maximum` in line 13 is preceded by a `String` cast, as in

```
(String) maximum("pear", "apple", "orange")
```

In each case, the type of the cast for the return value is *inferred* from the types of the method arguments in the particular method call, because, according to the method declaration, the return type and the argument types match. Without generics, you'd be responsible for implementing the cast operation.

## 20.5 Overloading Generic Methods

*A generic method may be overloaded like any other method.* A class can provide two or more generic methods that specify the same method name but different method parameters. For example, generic method `printArray` of Fig. 20.3 could be overloaded with another



`printArray` generic method with the additional parameters `lowSubscript` and `highSubscript` to specify the portion of the array to output (see Exercise 20.5).

A generic method can also be overloaded by nongeneric methods. When the compiler encounters a method call, it searches for the method declaration that best matches the method name and the argument types specified in the call—an error occurs if two or more overloaded methods both could be considered best matches. For example, generic method `printArray` of Fig. 20.3 could be overloaded with a version that’s specific to `Strings`, which outputs the `Strings` in neat, tabular format (see Exercise 20.6).

## 20.6 Generic Classes

The concept of a data structure, such as a stack, can be understood *independently* of the element type it manipulates. Generic classes provide a means for describing the concept of a stack (or any other class) in a *type-independent* manner. We can then instantiate *type-specific* objects of the generic class. Generics provide a nice opportunity for software reusability.

Once you have a generic class, you can use a simple, concise notation to indicate the type(s) that should be used in place of the class’s type parameter(s). At compilation time, the compiler ensures the *type safety* of your code and uses the *erasure* techniques described in Sections 20.3—20.4 to enable your client code to interact with the generic class.

One generic `Stack` class, for example, could be the basis for creating many logical `Stack` classes (e.g., “`Stack of Double`,” “`Stack of Integer`,” “`Stack of Character`,” “`Stack of Employee`”). These classes are known as **parameterized classes** or **parameterized types** because they accept one or more type parameters. Recall that type parameters represent only *reference types*, which means the `Stack` generic class cannot be instantiated with primitive types. However, we can instantiate a `Stack` that stores objects of Java’s type-wrapper classes and allow Java to use *autoboxing* to convert the primitive values into objects. Recall that autoboxing occurs when a value of a primitive type (e.g., `int`) is pushed onto a `Stack` that contains wrapper-class objects (e.g., `Integer`). *Auto-unboxing* occurs when an object of the wrapper class is popped off the `Stack` and assigned to a primitive-type variable.

### *Implementing a Generic Stack Class*

Figure 20.7 declares a generic `Stack` class for demonstration purposes—the `java.util` package already contains a generic `Stack` class. A generic class declaration looks like a nongeneric one, but the class name is followed by a *type-parameter section* (line 5). In this case, type parameter `T` represents the element type the `Stack` will manipulate. As with generic methods, the type-parameter section of a generic class can have one or more type parameters separated by commas. (You’ll create a generic class with two type parameters in Exercise 20.8.) Type parameter `T` is used throughout the `Stack` class declaration to represent the element type. This example implements a `Stack` as an `ArrayList`.

Class `Stack` declares variable `elements` as an `ArrayList<T>` (line 7). This `ArrayList` will store the `Stack`’s elements. As you know, an `ArrayList` can grow dynamically, so objects of our `Stack` class can also grow dynamically. The `Stack` class’s no-argument constructor (lines 10–13) invokes the one-argument constructor (lines 16–20) to create a `Stack` in which the underlying `ArrayList` has a capacity of 10 elements. The one-argument constructor can also be called directly to create a `Stack` with a specified initial capacity. Line 18 validates the constructor’s argument. Line 19 creates the `ArrayList` of the specified capacity (or 10 if the capacity was invalid).

---

```

1 // Fig. 20.7: Stack.java
2 // Stack generic class declaration.
3 import java.util.ArrayList;
4
5 public class Stack<T>
6 {
7 private final ArrayList<T> elements; // ArrayList stores stack elements
8
9 // no-argument constructor creates a stack of the default size
10 public Stack()
11 {
12 this(10); // default stack size
13 }
14
15 // constructor creates a stack of the specified number of elements
16 public Stack(int capacity)
17 {
18 int initCapacity = capacity > 0 ? capacity : 10; // validate
19 elements = new ArrayList<T>(initCapacity); // create ArrayList
20 }
21
22 // push element onto stack
23 public void push(T pushValue)
24 {
25 elements.add(pushValue); // place pushValue on Stack
26 }
27
28 // return the top element if not empty; else throw EmptyStackException
29 public T pop()
30 {
31 if (elements.isEmpty()) // if stack is empty
32 throw new EmptyStackException("Stack is empty, cannot pop");
33
34 // remove and return top element of Stack
35 return elements.remove(elements.size() - 1);
36 }
37 } // end class Stack<T>

```

---

**Fig. 20.7** | Stack generic class declaration.

Method `push` (lines 23–26) uses `ArrayList` method `add` to append the pushed item to the end of the `ArrayList` `elements`. The last element in the `ArrayList` represents the *top* of the stack.

Method `pop` (lines 29–36) first determines whether an attempt is being made to pop an element from an empty `Stack`. If so, line 32 throws an `EmptyStackException` (declared in Fig. 20.8). Otherwise, line 35 in Fig. 20.7 returns the top element of the `Stack` by removing the last element in the underlying `ArrayList`.

Class `EmptyStackException` (Fig. 20.8) provides a no-argument constructor and a one-argument constructor. The no-argument constructor sets the default error message, and the one-argument constructor sets a custom error message.

As with generic methods, when a generic class is compiled, the compiler performs *erasure* on the class's type parameters and replaces them with their upper bounds. For class

Stack (Fig. 20.7), no upper bound is specified, so the default upper bound, `Object`, is used. The scope of a generic class's type parameter is the entire class. However, type parameters *cannot* be used in a class's static variable declarations.

---

```

1 // Fig. 20.8: EmptyStackException.java
2 // EmptyStackException class declaration.
3 public class EmptyStackException extends RuntimeException
4 {
5 // no-argument constructor
6 public EmptyStackException()
7 {
8 this("Stack is empty");
9 }
10
11 // one-argument constructor
12 public EmptyStackException(String message)
13 {
14 super(message);
15 }
16 } // end class EmptyStackException

```

---

**Fig. 20.8** | `EmptyStackException` class declaration.

### *Testing the Generic Stack Class of Fig. 20.7*

Now, let's consider the application (Fig. 20.9) that uses the `Stack` generic class (Fig. 20.7). Lines 12–13 in Fig. 20.9 create and initialize variables of type `Stack<Double>` (pronounced “Stack of Double”) and `Stack<Integer>` (pronounced “Stack of Integer”). The types `Double` and `Integer` are known as the Stack's **type arguments**. The compiler uses them to replace the type parameters so that it can perform type checking and insert cast operations as necessary. We'll discuss the cast operations in more detail shortly. Lines 12–13 instantiate `doubleStack` with a capacity of 5 and `integerStack` with a capacity of 10 (the default). Lines 16–17 and 20–21 call methods `testPushDouble` (lines 25–36), `testPopDouble` (lines 39–59), `testPushInteger` (lines 62–73) and `testPopInteger` (lines 76–96), respectively, to demonstrate the two Stacks in this example.

---

```

1 // Fig. 20.9: StackTest.java
2 // Stack generic class test program.
3
4 public class StackTest
5 {
6 public static void main(String[] args)
7 {
8 double[] doubleElements = {1.1, 2.2, 3.3, 4.4, 5.5};
9 int[] integerElements = {1, 2, 3, 4, 5, 6, 7, 8, 9, 10};
10
11 // Create a Stack<Double> and a Stack<Integer>
12 Stack<Double> doubleStack = new Stack<>(5);
13 Stack<Integer> integerStack = new Stack<>();
14

```

---

**Fig. 20.9** | Stack generic class test program. (Part I of 3.)

---

```

15 // push elements of doubleElements onto doubleStack
16 testPushDouble(doubleStack, doubleElements);
17 testPopDouble(doubleStack); // pop from doubleStack
18
19 // push elements of integerElements onto integerStack
20 testPushInteger(integerStack, integerElements);
21 testPopInteger(integerStack); // pop from integerStack
22 }
23
24 // test push method with double stack
25 private static void testPushDouble(
26 Stack<Double> stack, double[] values)
27 {
28 System.out.printf("%nPushing elements onto doubleStack%n");
29
30 // push elements to Stack
31 for (double value : values)
32 {
33 System.out.printf("%.1f ", value);
34 stack.push(value); // push onto doubleStack
35 }
36 }
37
38 // test pop method with double stack
39 private static void testPopDouble(Stack<Double> stack)
40 {
41 // pop elements from stack
42 try
43 {
44 System.out.printf("%nPopping elements from doubleStack%n");
45 double popValue; // store element removed from stack
46
47 // remove all elements from Stack
48 while (true)
49 {
50 popValue = stack.pop(); // pop from doubleStack
51 System.out.printf("%.1f ", popValue);
52 }
53 }
54 catch (EmptyStackException emptyStackException)
55 {
56 System.err.println();
57 emptyStackException.printStackTrace();
58 }
59 }
60
61 // test push method with integer stack
62 private static void testPushInteger(
63 Stack<Integer> stack, int[] values)
64 {
65 System.out.printf("%nPushing elements onto integerStack%n");
66

```

---

**Fig. 20.9** | Stack generic class test program. (Part 2 of 3.)

```

67 // push elements to Stack
68 for (int value : values)
69 {
70 System.out.printf("%d ", value);
71 stack.push(value); // push onto integerStack
72 }
73 }
74
75 // test pop method with integer stack
76 private static void testPopInteger(Stack<Integer> stack)
77 {
78 // pop elements from stack
79 try
80 {
81 System.out.printf("%nPopping elements from integerStack%n");
82 int popValue; // store element removed from stack
83
84 // remove all elements from Stack
85 while (true)
86 {
87 popValue = stack.pop(); // pop from intStack
88 System.out.printf("%d ", popValue);
89 }
90 }
91 catch (EmptyStackException emptyStackException)
92 {
93 System.err.println();
94 emptyStackException.printStackTrace();
95 }
96 }
97 } // end class StackTest

```

```

Pushing elements onto doubleStack
1.1 2.2 3.3 4.4 5.5
Popping elements from doubleStack
5.5 4.4 3.3 2.2 1.1
EmptyStackException: Stack is empty, cannot pop
 at Stack.pop(Stack.java:32)
 at StackTest.testPopDouble(StackTest.java:50)
 at StackTest.main(StackTest.java:17)

Pushing elements onto integerStack
1 2 3 4 5 6 7 8 9 10
Popping elements from integerStack
10 9 8 7 6 5 4 3 2 1
EmptyStackException: Stack is empty, cannot pop
 at Stack.pop(Stack.java:32)
 at StackTest.testPopInteger(StackTest.java:87)
 at StackTest.main(StackTest.java:21)

```

**Fig. 20.9** | Stack generic class test program. (Part 3 of 3.)

#### *Methods testPushDouble and testPopDouble*

Method `testPushDouble` (lines 25–36) invokes method `push` (line 34) to place the `double` values 1.1, 2.2, 3.3, 4.4 and 5.5 from array `doubleElements` onto `doubleStack`. *Autobox-*

ing occurs in line 34 when the program tries to push a primitive `double` value onto the `doubleStack`, which stores only references to `Double` objects.

Method `testPopDouble` (lines 39–59) invokes `Stack` method `pop` (line 50) in an infinite loop (lines 48–52) to remove all the values from the stack. The output shows that the values indeed pop off in last-in, first-out order (the defining characteristic of stacks). When the loop attempts to pop a sixth value, the `doubleStack` is empty, so `pop` throws an `EmptyStackException`, which causes the program to proceed to the catch block (lines 54–58). The stack trace indicates the exception that occurred and shows that method `pop` generated the exception at line 32 of the file `Stack.java` (Fig. 20.7). The trace also shows that `pop` was called by `StackTest` method `testPopDouble` at line 50 (Fig. 20.9) of `StackTest.java` and that method `testPopDouble` was called from method `main` at line 17 of `StackTest.java`. This information enables you to determine the methods that were on the method-call stack at the time that the exception occurred. Because the program catches the exception, the exception is considered to have been handled and the program can continue executing.

*Auto-unboxing* occurs in line 50 when the program assigns the `Double` object popped from the stack to a `double` primitive variable. Recall from Section 20.4 that the compiler inserts casts to ensure that the proper types are returned from generic methods. After erasure, `Stack` method `pop` returns type `Object`, but the client code in `testPopDouble` expects to receive a `double` when method `pop` returns. So the compiler inserts a `Double` cast, as in

```
popValue = (Double) stack.pop();
```

The value assigned to `popValue` will be *unboxed* from the `Double` object returned by `pop`.

### Methods `testPushInteger` and `testPopInteger`

Method `testPushInteger` (lines 62–73) invokes `Stack` method `push` to place values onto `integerStack` until it's full. Method `testPopInteger` (lines 76–96) invokes `Stack` method `pop` to remove values from `integerStack`. Once again, the values are popped in last-in, first-out order. During *erasure*, the compiler recognizes that the client code in method `testPopInteger` expects to receive an `int` when method `pop` returns. So the compiler inserts an `Integer` cast, as in

```
popValue = (Integer) stack.pop();
```

The value assigned to `popValue` will be unboxed from the `Integer` object returned by `pop`.

### Creating Generic Methods to Test Class `Stack<T>`

The code in methods `testPushDouble` and `testPushInteger` is *almost identical* for pushing values onto a `Stack<Double>` or a `Stack<Integer>`, respectively, and the code in methods `testPopDouble` and `testPopInteger` is almost identical for popping values from a `Stack<Double>` or a `Stack<Integer>`, respectively. This presents another opportunity to use generic methods. Figure 20.10 declares generic method `testPush` (lines 24–35) to perform the same tasks as `testPushDouble` and `testPushInteger` in Fig. 20.9—that is, push values onto a `Stack<T>`. Similarly, generic method `testPop` (Fig. 20.10, lines 38–58) performs the same tasks as `testPopDouble` and `testPopInteger` in Fig. 20.9—that is, pop values off a `Stack<T>`. The output of Fig. 20.10 precisely matches that of Fig. 20.9.

---

```

1 // Fig. 20.10: StackTest2.java
2 // Passing generic Stack objects to generic methods.
3 public class StackTest2
4 {
5 public static void main(String[] args)
6 {
7 Double[] doubleElements = {1.1, 2.2, 3.3, 4.4, 5.5};
8 Integer[] integerElements = {1, 2, 3, 4, 5, 6, 7, 8, 9, 10};
9
10 // Create a Stack<Double> and a Stack<Integer>
11 Stack<Double> doubleStack = new Stack<>(5);
12 Stack<Integer> integerStack = new Stack<>();
13
14 // push elements of doubleElements onto doubleStack
15 testPush("doubleStack", doubleStack, doubleElements);
16 testPop("doubleStack", doubleStack); // pop from doubleStack
17
18 // push elements of integerElements onto integerStack
19 testPush("integerStack", integerStack, integerElements);
20 testPop("integerStack", integerStack); // pop from integerStack
21 }
22
23 // generic method testPush pushes elements onto a Stack
24 public static <T> void testPush(String name, Stack<T> stack,
25 T[] elements)
26 {
27 System.out.printf("%nPushing elements onto %s%n", name);
28
29 // push elements onto Stack
30 for (T element : elements)
31 {
32 System.out.printf("%s ", element);
33 stack.push(element); // push element onto stack
34 }
35 }
36
37 // generic method testPop pops elements from a Stack
38 public static <T> void testPop(String name, Stack<T> stack)
39 {
40 // pop elements from stack
41 try
42 {
43 System.out.printf("%nPopping elements from %s%n", name);
44 T popValue; // store element removed from stack
45
46 // remove all elements from Stack
47 while (true)
48 {
49 popValue = stack.pop();
50 System.out.printf("%s ", popValue);
51 }
52 }

```

---

**Fig. 20.10** | Passing generic Stack objects to generic methods. (Part I of 2.)

```

53 catch(EmptyStackException emptyStackException)
54 {
55 System.out.println();
56 emptyStackException.printStackTrace();
57 }
58 }
59 } // end class StackTest2

```

```

Pushing elements onto doubleStack
1.1 2.2 3.3 4.4 5.5
Popping elements from doubleStack
5.5 4.4 3.3 2.2 1.1
EmptyStackException: Stack is empty, cannot pop
 at Stack.pop(Stack.java:32)
 at StackTest2.testPop(StackTest2.java:50)
 at StackTest2.main(StackTest2.java:17)

Pushing elements onto integerStack
1 2 3 4 5 6 7 8 9 10
Popping elements from integerStack
10 9 8 7 6 5 4 3 2 1
EmptyStackException: Stack is empty, cannot pop
 at Stack.pop(Stack.java:32)
 at StackTest2.testPop(StackTest2.java:50)
 at StackTest2.main(StackTest2.java:21)

```

**Fig. 20.10** | Passing generic Stack objects to generic methods. (Part 2 of 2.)

Lines 11–12 create the `Stack<Double>` and `Stack<Integer>` objects, respectively. Lines 15–16 and 19–20 invoke generic methods `testPush` and `testPop` to test the `Stack` objects. Because type parameters can represent only reference types, to be able to pass arrays `doubleElements` and `integerElements` to generic method `testPush`, the arrays declared in lines 7–8 must be declared with the wrapper types `Double` and `Integer`. When these arrays are initialized with primitive values, the compiler *autoboxes* each primitive value.

Generic method `testPush` (lines 24–35) uses type parameter `T` (specified at line 24) to represent the data type stored in the `Stack<T>`. The generic method takes three arguments—a `String` that represents the name of the `Stack<T>` object for output purposes, a reference to an object of type `Stack<T>` and an array of type `T`—the type of elements that will be pushed onto `Stack<T>`. The compiler enforces *consistency* between the type of the `Stack` and the elements that will be pushed onto the `Stack` when `push` is invoked, which is the real value of the generic method call. Generic method `testPop` (lines 38–58) takes two arguments—a `String` that represents the name of the `Stack<T>` object for output purposes and a reference to an object of type `Stack<T>`.

## 20.7 Raw Types

The test programs for generic class `Stack` in Section 20.6 instantiate `Stacks` with type arguments `Double` and `Integer`. It's also possible to instantiate generic class `Stack` without specifying a type argument, as follows:

```
Stack objectStack = new Stack(5); // no type argument specified
```



In this case, the `objectStack` has a **raw type**—the compiler implicitly uses type `Object` throughout the generic class for each type argument. Thus the preceding statement creates a `Stack` that can store objects of *any* type. This is important for *backward compatibility* with prior Java versions. For example, the data structures of the Java Collections Framework (Chapter 16) all stored references to `Objects`, but are now implemented as generic types.

A raw-type `Stack` variable can be assigned a `Stack` that specifies a type argument, such as a `Stack<Double>` object, as follows:

```
Stack rawTypeStack2 = new Stack<Double>(5);
```

because type `Double` is a subclass of `Object`. This assignment is allowed because the elements in a `Stack<Double>` (i.e., `Double` objects) are certainly objects—class `Double` is an indirect subclass of `Object`.

Similarly, a `Stack` variable that specifies a type argument in its declaration can be assigned a raw-type `Stack` object, as in:

```
Stack<Integer> integerStack = new Stack(10);
```

Although this assignment is permitted, it's *unsafe*, because a `Stack` of raw type might store types other than `Integer`. In this case, the compiler issues a warning message which indicates the unsafe assignment.

### Using Raw Types with Generic Class `Stack`

The test program of Fig. 20.11 uses the notion of raw type. Line 11 instantiates generic class `Stack` with raw type, which indicates that `rawTypeStack1` can hold objects of any type. Line 14 assigns a `Stack<Double>` to variable `rawTypeStack2`, which is declared as a `Stack` of raw type. Line 17 assigns a `Stack` of raw type to `Stack<Integer>` variable, which is legal but causes the compiler to issue a warning message (Fig. 20.12) indicating a *potentially unsafe assignment*—again, this occurs because a `Stack` of raw type might store types other than `Integer`. Also, the calls to generic methods `testPush` and `testPop` in lines 19–22 result in compiler warning messages (Fig. 20.12). These occur because `rawTypeStack1` and `rawTypeStack2` are declared as `Stacks` of raw type, but methods `testPush` and `testPop` each expect a second argument that is a `Stack` with a specific type argument. The warnings indicate that the compiler cannot guarantee the types manipulated by the stacks to be the correct types, since we did not supply a variable declared with a type argument. Methods `testPush` (Fig. 20.11, lines 28–39) and `testPop` (lines 42–62) are the same as in Fig. 20.10.

---

```

1 // Fig. 20.11: RawTypeTest.java
2 // Raw type test program.
3 public class RawTypeTest
4 {
5 public static void main(String[] args)
6 {
7 Double[] doubleElements = {1.1, 2.2, 3.3, 4.4, 5.5};
8 Integer[] integerElements = {1, 2, 3, 4, 5, 6, 7, 8, 9, 10};
9
10 // Stack of raw types assigned to Stack of raw types variable
11 Stack rawTypeStack1 = new Stack(5);

```

---

**Fig. 20.11** | Raw-type test program. (Part 1 of 3.)

```

12
13 // Stack<Double> assigned to Stack of raw types variable
14 Stack rawTypeStack2 = new Stack<Double>(5);
15
16 // Stack of raw types assigned to Stack<Integer> variable
17 Stack<Integer> integerStack = new Stack(10);
18
19 testPush("rawTypeStack1", rawTypeStack1, doubleElements);
20 testPop("rawTypeStack1", rawTypeStack1);
21 testPush("rawTypeStack2", rawTypeStack2, doubleElements);
22 testPop("rawTypeStack2", rawTypeStack2);
23 testPush("integerStack", integerStack, integerElements);
24 testPop("integerStack", integerStack);
25 }
26
27 // generic method pushes elements onto stack
28 public static <T> void testPush(String name, Stack<T> stack,
29 T[] elements)
30 {
31 System.out.printf("%nPushing elements onto %s%n", name);
32
33 // push elements onto Stack
34 for (T element : elements)
35 {
36 System.out.printf("%s ", element);
37 stack.push(element); // push element onto stack
38 }
39 }
40
41 // generic method testPop pops elements from stack
42 public static <T> void testPop(String name, Stack<T> stack)
43 {
44 // pop elements from stack
45 try
46 {
47 System.out.printf("%nPopping elements from %s%n", name);
48 T popValue; // store element removed from stack
49
50 // remove elements from Stack
51 while (true)
52 {
53 popValue = stack.pop(); // pop from stack
54 System.out.printf("%s ", popValue);
55 }
56 } // end try
57 catch (EmptyStackException emptyStackException)
58 {
59 System.out.println();
60 emptyStackException.printStackTrace();
61 }
62 }
63 } // end class RawTypeTest

```

**Fig. 20.11** | Raw-type test program. (Part 2 of 3.)

```

Pushing elements onto rawTypeStack1
1.1 2.2 3.3 4.4 5.5
Popping elements from rawTypeStack1
5.5 4.4 3.3 2.2 1.1
EmptyStackException: Stack is empty, cannot pop
 at Stack.pop(Stack.java:32)
 at RawTypeTest.testPop(RawTypeTest.java:53)
 at RawTypeTest.main(RawTypeTest.java:20)

Pushing elements onto rawTypeStack2
1.1 2.2 3.3 4.4 5.5
Popping elements from rawTypeStack2
5.5 4.4 3.3 2.2 1.1
EmptyStackException: Stack is empty, cannot pop
 at Stack.pop(Stack.java:32)
 at RawTypeTest.testPop(RawTypeTest.java:53)
 at RawTypeTest.main(RawTypeTest.java:22)

Pushing elements onto integerStack
1 2 3 4 5 6 7 8 9 10
Popping elements from integerStack
10 9 8 7 6 5 4 3 2 1
EmptyStackException: Stack is empty, cannot pop
 at Stack.pop(Stack.java:32)
 at RawTypeTest.testPop(RawTypeTest.java:53)
 at RawTypeTest.main(RawTypeTest.java:24)

```

**Fig. 20.11** | Raw-type test program. (Part 3 of 3.)

### *Compiler Warnings*

Figure 20.12 shows the warning messages generated by the compiler when the file `RawTypeTest.java` (Fig. 20.11) is compiled with the `-Xlint:unchecked` option, which provides more information about potentially unsafe operations in code that uses generics. The first warning in Fig. 20.11 is generated for line 17, which assigned a raw-type `Stack` to a `Stack<Integer>` variable—the compiler cannot ensure that all objects in the `Stack` will be `Integer` objects. The next warning occurs at line 19. The compiler determines method `testPush`'s type argument from the `Double` array passed as the third argument, because the second method argument is a raw-type `Stack` variable. In this case, `Double` is the type argument, so the compiler expects a `Stack<Double>` as the second argument. The warning occurs because the compiler cannot ensure that a raw-type `Stack` contains only `Doubles`. The warning at line 21 occurs for the same reason, even though the actual `Stack` that `rawTypeStack2` references is a `Stack<Double>`. The compiler cannot guarantee that the variable will always refer to the same `Stack` object, so it must use the variable's declared type to perform all type checking. Lines 20 and 22 each generate warnings because method `testPop` expects as an argument a `Stack` for which a type argument has been specified. However, in each call to `testPop`, we pass a raw-type `Stack` variable. Thus, the compiler indicates a warning because it cannot check the types used in the body of the method. In general, you should avoid using raw types.

```

RawTypeTest.java:17: warning: [unchecked] unchecked conversion
found : Stack
required: Stack<java.lang.Integer>
 Stack<Integer> integerStack = new Stack(10);
 ^
RawTypeTest.java:19: warning: [unchecked] unchecked conversion
found : Stack
required: Stack<java.lang.Double>
 testPush("rawTypeStack1", rawTypeStack1, doubleElements);
 ^
RawTypeTest.java:19: warning: [unchecked] unchecked method invocation:
<T>testPush(java.lang.String,Stack<T>,T[]) in RawTypeTest is applied to
(java.lang.String,Stack,java.lang.Double[])
 testPush("rawTypeStack1", rawTypeStack1, doubleElements);
 ^
RawTypeTest.java:20: warning: [unchecked] unchecked conversion
found : Stack
required: Stack<T>
 testPop("rawTypeStack1", rawTypeStack1);
 ^
RawTypeTest.java:20: warning: [unchecked] unchecked method invocation:
<T>testPop(java.lang.String,Stack<T>) in RawTypeTest is applied to
(java.lang.String,Stack)
 testPop("rawTypeStack1", rawTypeStack1);
 ^
RawTypeTest.java:21: warning: [unchecked] unchecked conversion
found : Stack
required: Stack<java.lang.Double>
 testPush("rawTypeStack2", rawTypeStack2, doubleElements);
 ^
RawTypeTest.java:21: warning: [unchecked] unchecked method invocation:
<T>testPush(java.lang.String,Stack<T>,T[]) in RawTypeTest is applied to
(java.lang.String,Stack,java.lang.Double[])
 testPush("rawTypeStack2", rawTypeStack2, doubleElements);
 ^
RawTypeTest.java:22: warning: [unchecked] unchecked conversion
found : Stack
required: Stack<T>
 testPop("rawTypeStack2", rawTypeStack2);
 ^
RawTypeTest.java:22: warning: [unchecked] unchecked method invocation:
<T>testPop(java.lang.String,Stack<T>) in RawTypeTest is applied to
(java.lang.String,Stack)
 testPop("rawTypeStack2", rawTypeStack2);
 ^
9 warnings

```

**Fig. 20.12** | Warning messages from the compiler.

## 20.8 Wildcards in Methods That Accept Type Parameters

In this section, we introduce a powerful generics concept known as **wildcards**. Let's consider an example that motivates wildcards. Suppose that you'd like to implement a generic method `sum` that totals the numbers in a collection, such as an `ArrayList`. You'd begin by

inserting the numbers in the collection. Because generic classes can be used only with class or interface types, the numbers would be *autoboxed* as objects of the type-wrapper classes. For example, any `int` value would be *autoboxed* as an `Integer` object, and any `double` value would be *autoboxed* as a `Double` object. We'd like to be able to total all the numbers in the `ArrayList` regardless of their type. For this reason, we'll declare the `ArrayList` with the type argument `Number`, which is the superclass of both `Integer` and `Double`. In addition, method `sum` will receive a parameter of type `ArrayList<Number>` and total its elements. Figure 20.13 demonstrates totaling the elements of an `ArrayList` of `Numbers`.

```

1 // Fig. 20.13: TotalNumbers.java
2 // Totaling the numbers in an ArrayList<Number>.
3 import java.util.ArrayList;
4
5 public class TotalNumbers
6 {
7 public static void main(String[] args)
8 {
9 // create, initialize and output ArrayList of Numbers containing
10 // both Integers and Doubles, then display total of the elements
11 Number[] numbers = {1, 2.4, 3, 4.1}; // Integers and Doubles
12 ArrayList<Number> numberList = new ArrayList<>();
13
14 for (Number element : numbers)
15 numberList.add(element); // place each number in numberList
16
17 System.out.printf("numberList contains: %s\n", numberList);
18 System.out.printf("Total of the elements in numberList: %.1f\n",
19 sum(numberList));
20 }
21
22 // calculate total of ArrayList elements
23 public static double sum(ArrayList<Number> list)
24 {
25 double total = 0; // initialize total
26
27 // calculate sum
28 for (Number element : list)
29 total += element.doubleValue();
30
31 return total;
32 }
33 } // end class TotalNumbers

```

```

numberList contains: [1, 2.4, 3, 4.1]
Total of the elements in numberList: 10.5

```

**Fig. 20.13** | Totaling the numbers in an `ArrayList<Number>`.

Line 11 declares and initializes an array of `Numbers`. Because the initializers are primitive values, Java *autoboxes* each primitive value as an object of its corresponding wrapper type. The `int` values 1 and 3 are *autoboxed* as `Integer` objects, and the `double` values 2.4

and 4.1 are *autoboxed* as `Double` objects. Line 12 declares and creates an `ArrayList` object that stores `Numbers` and assigns it to variable `numberList`.

Lines 14–15 traverse array `numbers` and place each element in `numberList`. Line 17 outputs the contents of the `ArrayList` as a `String`. This statement implicitly invokes the `ArrayList`’s `toString` method, which returns a `String` of the form “[*elements*]” in which *elements* is a comma-separated list of the elements’ `String` representations. Lines 18–19 display the sum of the elements that is returned by the call to method `sum`.

Method `sum` (lines 23–32) receives an `ArrayList` of `Numbers` and calculates the total of the `Numbers` in the collection. The method uses `double` values to perform the calculations and returns the result as a `double`. Lines 28–29 use the enhanced `for` statement, which is designed to work with both arrays and the collections of the `Collections` Framework, to total the elements of the `ArrayList`. The `for` statement assigns each `Number` in the `ArrayList` to variable `element`, then uses **Number method doubleValue** to obtain the `Number`’s underlying primitive value as a `double` value. The result is added to `total`. When the loop terminates, the method returns the `total`.

### *Implementing Method sum With a Wildcard Type Argument in Its Parameter*

Recall that the purpose of method `sum` in Fig. 20.13 was to total any type of `Numbers` stored in an `ArrayList`. We created an `ArrayList` of `Numbers` that contained both `Integer` and `Double` objects. The output of Fig. 20.13 demonstrates that method `sum` worked properly. Given that method `sum` can total the elements of an `ArrayList` of `Numbers`, you might expect that the method would also work for `ArrayList`s that contain elements of only one numeric type, such as `ArrayList<Integer>`. So we modified class `TotalNumbers` to create an `ArrayList` of `Integers` and pass it to method `sum`. When we compile the program, the compiler issues the following error message:

```
sum(java.util.ArrayList<java.lang.Number>) in TotalNumbersErrors
cannot be applied to (java.util.ArrayList<java.lang.Integer>)
```

Although `Number` is the superclass of `Integer`, the compiler doesn’t consider the type `ArrayList<Number>` to be a superclass of `ArrayList<Integer>`. If it were, then every operation we could perform on `ArrayList<Number>` would also work on an `ArrayList<Integer>`. Consider the fact that you can add a `Double` object to an `ArrayList<Number>` because a `Double` *is a Number*, but you cannot add a `Double` object to an `ArrayList<Integer>` because a `Double` *is not an Integer*. Thus, the subtype relationship does not hold.

How do we create a more flexible version of the `sum` method that can total the elements of any `ArrayList` containing elements of any subclass of `Number`? This is where **wildcard type arguments** are important. Wildcards enable you to specify method parameters, return values, variables or fields, and so on, that act as supertypes or subtypes of parameterized types. In Fig. 20.14, method `sum`’s parameter is declared in line 50 with the type:

```
ArrayList<? extends Number>
```

A wildcard type argument is denoted by a question mark (?), which by itself represents an “unknown type.” In this case, the wildcard extends class `Number`, which means that the wildcard has an upper bound of `Number`. Thus, the unknown-type argument must be either `Number` or a subclass of `Number`. With the parameter type shown here, method `sum` can receive an `ArrayList` argument that contains any type of `Number`, such as `ArrayList<Integer>` (line 20), `ArrayList<Double>` (line 33) or `ArrayList<Number>` (line 46).

```
1 // Fig. 20.14: WildcardTest.java
2 // Wildcard test program.
3 import java.util.ArrayList;
4
5 public class WildcardTest
6 {
7 public static void main(String[] args)
8 {
9 // create, initialize and output ArrayList of Integers, then
10 // display total of the elements
11 Integer[] integers = {1, 2, 3, 4, 5};
12 ArrayList<Integer> integerList = new ArrayList<>();
13
14 // insert elements in integerList
15 for (Integer element : integers)
16 integerList.add(element);
17
18 System.out.printf("integerList contains: %s\n", integerList);
19 System.out.printf("Total of the elements in integerList: %.0f\n\n",
20 sum(integerList));
21
22 // create, initialize and output ArrayList of Doubles, then
23 // display total of the elements
24 Double[] doubles = {1.1, 3.3, 5.5};
25 ArrayList<Double> doubleList = new ArrayList<>();
26
27 // insert elements in doubleList
28 for (Double element : doubles)
29 doubleList.add(element);
30
31 System.out.printf("doubleList contains: %s\n", doubleList);
32 System.out.printf("Total of the elements in doubleList: %.1f\n\n",
33 sum(doubleList));
34
35 // create, initialize and output ArrayList of Numbers containing
36 // both Integers and Doubles, then display total of the elements
37 Number[] numbers = {1, 2.4, 3, 4.1}; // Integers and Doubles
38 ArrayList<Number> numberList = new ArrayList<>();
39
40 // insert elements in numberList
41 for (Number element : numbers)
42 numberList.add(element);
43
44 System.out.printf("numberList contains: %s\n", numberList);
45 System.out.printf("Total of the elements in numberList: %.1f\n",
46 sum(numberList));
47 } // end main
48
49 // total the elements; using a wildcard in the ArrayList parameter
50 public static double sum(ArrayList<? extends Number> list)
51 {
52 double total = 0; // initialize total
53 }
```

**Fig. 20.14** | Wildcard test program. (Part I of 2.)

```

54 // calculate sum
55 for (Number element : list)
56 total += element.doubleValue();
57
58 return total;
59 }
60 } // end class WildcardTest

```

```

integerList contains: [1, 2, 3, 4, 5]
Total of the elements in integerList: 15

doubleList contains: [1.1, 3.3, 5.5]
Total of the elements in doubleList: 9.9

numberList contains: [1, 2.4, 3, 4.1]
Total of the elements in numberList: 10.5

```

**Fig. 20.14** | Wildcard test program. (Part 2 of 2.)

Lines 11–20 create and initialize an `ArrayList<Integer>`, output its elements and total them by calling method `sum` (line 20). Lines 24–33 perform the same operations for an `ArrayList<Double>`. Lines 37–46 perform the same operations for an `ArrayList<Number>` that contains `Integers` and `Doubles`.

In method `sum` (lines 50–59), although the `ArrayList` argument’s element types are not directly known by the method, they’re known to be at least of type `Number`, because the wildcard was specified with the upper bound `Number`. For this reason line 56 is allowed, because all `Number` objects have a `doubleValue` method.

Although wildcards provide flexibility when passing parameterized types to a method, they also have some disadvantages. Because the wildcard (?) in the method’s header (line 50) does not specify a type-parameter name, you cannot use it as a type name throughout the method’s body (i.e., you cannot replace `Number` with ? in line 55). You could, however, declare method `sum` as follows:

```
public static <T extends Number> double sum(ArrayList<T> list)
```

which allows the method to receive an `ArrayList` that contains elements of any `Number` subclass. You could then use the type parameter `T` throughout the method body.

If the wildcard is specified without an upper bound, then only the methods of type `Object` can be invoked on values of the wildcard type. Also, methods that use wildcards in their parameter’s type arguments cannot be used to add elements to a collection referenced by the parameter.



### Common Programming Error 20.3

*Using a wildcard in a method’s type-parameter section or using a wildcard as an explicit type of a variable in the method body is a syntax error.*

## 20.9 Wrap-Up

This chapter introduced generics. You learned how to declare generic methods and classes with type parameters specified in type-parameter sections. You also learned how to specify



the upper bound for a type parameter and how the Java compiler uses erasure and casts to support multiple types with generic methods and classes. We discussed how backward compatibility is achieved via raw types. You also learned how to use wildcards in a generic method or a generic class.

In Chapter 21, you'll learn how to implement your own custom dynamic data structures that can grow or shrink at execution time. In particular, you'll implement these data structures using the generics capabilities you learned in this chapter.

## Summary

### *Section 20.1 Introduction*

- Generic methods enable you to specify, with one method declaration, a set of related methods.
- Generic classes and interfaces enable you to specify sets of related types.

### *Section 20.2 Motivation for Generic Methods*

- Overloaded methods are often used to perform similar operations on different types of data.
- When the compiler encounters a method call, it attempts to locate a method declaration with a name and parameters that are compatible with the argument types in the method call.

### *Section 20.3 Generic Methods: Implementation and Compile-Time Translation*

- If the operations performed by several overloaded methods are identical for each argument type, they can be more compactly and conveniently coded using a generic method. A single generic method declaration can be called with arguments of different data types. Based on the types of the arguments passed to a generic method, the compiler handles each method call appropriately.
- All generic method declarations have a type-parameter section (p. 835) delimited by angle brackets (< and >) that precedes the method's return type (p. 835).
- A type-parameter section contains one or more type parameters separated by commas.
- A type parameter (p. 835) is an identifier that specifies a generic type name. Type parameters can be used as the return type, parameter types and local variable types in a generic method declaration, and they act as placeholders for the types of the arguments passed to the generic method, which are known as actual type arguments (p. 836). Type parameters can represent only reference types.
- Type-parameter names used throughout a method declaration must match those declared in the type-parameter section. A type-parameter name can be declared only once in the type-parameter section but can appear more than once in the method's parameter list.
- When the compiler encounters a method call, it determines the argument types and attempts to locate a method with the same name and parameters that match the argument types. If there's no such method, the compiler searches for methods with the same name and compatible parameters and for matching generic methods.
- Objects of a class that implements generic interface `Comparable` (`Comparable`) can be compared with method `compareTo` (p. 838), which returns 0 if the objects are equal, a negative integer if the first object is less than the second or a positive integer if the first object is greater than the second.
- All the type-wrapper classes for primitive types implement `Comparable`.
- `Comparable` objects can be used with the sorting and searching methods of class `Collections`.

**Section 20.4 Additional Compile-Time Translation Issues: Methods That Use a Type Parameter as the Return Type**

- When a generic method is compiled, the compiler performs erasure (p. 848) to remove the type-parameter section and replace the type parameters with actual types. By default each type parameter is replaced with its upper bound (p. 848), which is `Object` unless specified otherwise.
- When erasure is performed on a method that returns a type variable (p. 848), explicit casts are inserted in front of each method call to ensure that the returned value has the type expected by the caller.

**Section 20.5 Overloading Generic Methods**

- A generic method may be overloaded with other generic methods or with nongeneric methods.

**Section 20.6 Generic Classes**

- Generic classes provide a means for describing a class in a type-independent manner. We can then instantiate type-specific objects of the generic class.
- A generic class declaration looks like a nongeneric class declaration, except that the class name is followed by a type-parameter section. The type-parameter section of a generic class can have one or more type parameters separated by commas.
- When a generic class is compiled, the compiler performs erasure on the class's type parameters and replaces them with their upper bounds.
- Type parameters cannot be used in a class's `static` declarations.
- When instantiating an object of a generic class, the types specified in angle brackets after the class name are known as type arguments (p. 843). The compiler uses them to replace the type parameters so that it can perform type checking and insert cast operations as necessary.

**Section 20.7 Raw Types**

- It's possible to instantiate a generic class without specifying a type argument. In this case, the new object of the class is said to have a raw type (p. 849)—the compiler implicitly uses type `Object` (or the type parameter's upper bound) throughout the generic class for each type argument.

**Section 20.8 Wildcards in Methods That Accept Type Parameters**

- Class `Number` is the superclass of both `Integer` and `Double`.
- `Number` method `doubleValue` (p. 854) obtains the `Number`'s underlying primitive value as a `double` value.
- Wildcard type arguments enable you to specify method parameters, return values, variables, and so on, that act as supertypes of parameterized types. A wildcard-type argument is denoted by `?` (p. 854), which represents an “unknown type.” A wildcard can also have an upper bound.
- Because a wildcard (`?`) is not a type-parameter name, you cannot use it as a type name throughout a method's body.
- If a wildcard is specified without an upper bound, then only the methods of type `Object` can be invoked on values of the wildcard type.
- Methods that use wildcards as type arguments (p. 854) cannot be used to add elements to a collection referenced by the parameter.

**Self-Review Exercises**

- 20.1** State whether each of the following is *true* or *false*. If *false*, explain why.
- a) A generic method cannot have the same method name as a nongeneric method.

- b) All generic method declarations have a type-parameter section that immediately precedes the method name.
- c) A generic method can be overloaded by another generic method with the same method name but different method parameters.
- d) A type parameter can be declared only once in the type-parameter section but can appear more than once in the method's parameter list.
- e) Type-parameter names among different generic methods must be unique.
- f) The scope of a generic class's type parameter is the entire class except its static members.

**20.2** Fill in the blanks in each of the following:

- a) \_\_\_\_\_ and \_\_\_\_\_ enable you to specify, with a single method declaration, a set of related methods, or with a single class declaration, a set of related types, respectively.
- b) A type-parameter section is delimited by \_\_\_\_\_.
- c) A generic method's \_\_\_\_\_ can be used to specify the method's argument types, to specify the method's return type and to declare variables within the method.
- d) The statement "Stack objectStack = new Stack();" indicates that objectStack stores \_\_\_\_\_.
- e) In a generic class declaration, the class name is followed by a(n) \_\_\_\_\_.
- f) The syntax \_\_\_\_\_ specifies that the upper bound of a wildcard is type T.

## Answers to Self-Review Exercises

**20.1** a) False. Generic and nongeneric methods can have the same method name. A generic method can overload another generic method with the same method name but different method parameters. A generic method also can be overloaded by providing nongeneric methods with the same method name and number of arguments. b) False. All generic method declarations have a type-parameter section that immediately precedes the method's return type. c) True. d) True. e) False. Type-parameter names among different generic methods need not be unique. f) True.

**20.2** a) Generic methods, generic classes. b) angle brackets (< and >). c) type parameters. d) a raw type. e) type-parameter section. f) ? extends T.

## Exercises

**20.3** (*Explain Notation*) Explain the use of the following notation in a Java program:

```
public class Array<T> { }
```

**20.4** (*Generic Method selectionSort*) Write a generic method selectionSort based on the sort program of Fig. 19.4. Write a test program that inputs, sorts and outputs an Integer array and a Float array. [Hint: Use <T extends Comparable<T>> in the type-parameter section for method selectionSort, so that you can use method compareTo to compare the objects of the type that T represents.]

**20.5** (*Overloaded Generic Method printArray*) Overload generic method printArray of Fig. 20.3 so that it takes two additional integer arguments, lowSubscript and highSubscript. A call to this method prints only the designated portion of the array. Validate lowSubscript and highSubscript. If either is out of range, the overloaded printArray method should throw an InvalidSubscriptException; otherwise, printArray should return the number of elements printed. Then modify main to exercise both versions of printArray on arrays integerArray, doubleArray and characterArray. Test all capabilities of both versions of printArray.

**20.6** (*Overloading a Generic Method with a Nongeneric Method*) Overload generic method `printArray` of Fig. 20.3 with a nongeneric version that specifically prints an array of `Strings` in neat, tabular format, as shown in the sample output that follows:

```
Array stringArray contains:
one two three four
five six seven eight
```

**20.7** (*Generic `isEqualTo` Method*) Write a simple generic version of method `isEqualTo` that compares its two arguments with the `equals` method and returns `true` if they're equal and `false` otherwise. Use this generic method in a program that calls `isEqualTo` with a variety of built-in types, such as `Object` or `Integer`. What result do you get when you attempt to run this program?

**20.8** (*Generic Class `Pair`*) Write a generic class `Pair` which has two type parameters—`F` and `S`—each representing the type of the first and second element of the pair, respectively. Add `get` and `set` methods for the first and second elements of the pair. [*Hint:* The class header should be `public class Pair<F, S>`.]

**20.9** (*Overloading Generic Methods*) How can generic methods be overloaded?

**20.10** (*Overload Resolution*) The compiler performs a matching process to determine which method to call when a method is invoked. Under what circumstances does an attempt to make a match result in a compile-time error?

**20.11** (*What Does this Statement Do?*) Explain why a Java program might use the statement

```
ArrayList<Employee> workerList = new ArrayList<>();
```

# Custom Generic Data Structures

# 21



*Much that I bound,  
I could not free;  
Much that I freed  
returned to me.*  
—Lee Wilson Dodd

*There is always room at the top.*  
—Daniel Webster

*I think that I shall never see  
A poem lovely as a tree.*  
—Joyce Kilmer

## Objectives

In this chapter you'll learn:

- To form linked data structures using references, self-referential classes, recursion and generics.
- To create and manipulate dynamic data structures, such as linked lists, queues, stacks and binary trees.
- Various important applications of linked data structures.
- How to create reusable data structures with classes, inheritance and composition.
- To organize classes in packages to promote reuse.

- |                                                                    |                                                 |
|--------------------------------------------------------------------|-------------------------------------------------|
| 21.1 Introduction                                                  | 21.4.6 List Method <code>insertAtBack</code>    |
| 21.2 Self-Referential Classes                                      | 21.4.7 List Method <code>removeFromFront</code> |
| 21.3 Dynamic Memory Allocation                                     | 21.4.8 List Method <code>removeFromBack</code>  |
| 21.4 Linked Lists                                                  | 21.4.9 List Method <code>print</code>           |
| 21.4.1 Singly Linked Lists                                         | 21.4.10 Creating Your Own Packages              |
| 21.4.2 Implementing a Generic List Class                           | 21.5 Stacks                                     |
| 21.4.3 Generic Classes <code>ListNode</code> and <code>List</code> | 21.6 Queues                                     |
| 21.4.4 Class <code>ListTest</code>                                 | 21.7 Trees                                      |
| 21.4.5 List Method <code>insertAtFront</code>                      | 21.8 Wrap-Up                                    |

Summary | Self-Review Exercises | Answers to Self-Review Exercises | Exercises |  
 Special Section: Building Your Own Compiler

## 21.1 Introduction

This chapter shows how to build **dynamic data structures** that grow and shrink at execution time. **Linked lists** are collections of data items “linked up in a chain”—insertions and deletions can be made *anywhere* in a linked list. **Stacks** are important in compilers and operating systems; insertions and deletions are made only at one end of a stack—its **top**. **Queues** represent waiting lines; insertions are made at the back (also referred to as the **tail**) of a queue and deletions are made from the front (also referred to as the **head**). **Binary trees** facilitate high-speed searching and sorting of data, eliminating duplicate data items efficiently, representing file-system directories, compiling expressions into machine language and many other interesting applications.

We discuss each of these major data-structure types and implement programs that create and manipulate them. We use classes, inheritance and composition to create them for reusability and maintainability. We also explain how to organize classes into your own packages to promote reuse. We include this chapter for computer-science and computer-engineering students who need to know how to build linked data structures.



### Software Engineering Observation 21.1

*The vast majority of software developers should use the predefined generic collection classes that we discussed in Chapter 16, rather than developing customized linked data structures.*

### Optional Online “Building Your Own Compiler” Project

If you feel ambitious, you might want to attempt the major project described in the special section entitled Building Your Own Compiler, which we’ve posted online at <http://www.deitel.com/books/jhpt10LOV>. You’ve been using a Java compiler to translate your Java programs to bytecodes so that you could execute these programs. In this project, you’ll actually build your own compiler. It will read statements written in a simple, yet powerful high-level language similar to early versions of the popular language BASIC and translate these statements into Simpletron Machine Language (SML) instructions—SML is the language you learned in the Chapter 6 special section, Building Your Own Computer. Your Simpletron Simulator program will then execute the SML program produced by your compiler! Implementing this project by using an object-oriented approach will give you an opportunity to exercise most of what you’ve learned in this book. The special section carefully walks you through the specifications of the high-level language and describes

the algorithms you'll need to convert each high-level language statement into machine-language instructions. If you enjoy being challenged, you might attempt the enhancements to both the compiler and the Simpletron Simulator suggested in the exercises.

## 21.2 Self-Referential Classes

A **self-referential class** contains an instance variable that refers to another object of the same class type. For example, the generic `Node` class declaration

```
class Node<T>
{
 private T data;
 private Node<T> nextNode; // reference to next linked node
 public Node(T data) { /* constructor body */ }
 public void setData(T data) { /* method body */ }
 public T getData() { /* method body */ }
 public void setNext(Node<T> next) { /* method body */ }
 public Node<T> getNext() { /* method body */ }
}
```

has two private instance variables—`data` (of the generic type `T`) and `Node<T>` variable `nextNode`. Variable `nextNode` references a `Node<T>` object, an object of the same class being declared here—hence the term “self-referential class.” Field `nextNode` is a **link**—it “links” an object of type `Node<T>` to another object of the same type. Type `Node<T>` also has five methods: a constructor that receives a value to initialize `data`, a `setData` method to set the value of `data`, a `getData` method to return the value of `data`, a `setNext` method to set the value of `nextNode` and a `getNext` method to return a reference to the next node.

Programs can link self-referential objects together to form such useful data structures as lists, queues, stacks and trees. Figure 21.1 illustrates two self-referential objects linked together to form a list. A backslash—representing a null reference—is placed in the link member of the second self-referential object to indicate that the link does *not* refer to another object. The backslash is illustrative; it does not correspond to the backslash character in Java. By convention, in code we use the `null` reference to indicate the end of a data structure.



**Fig. 21.1** | Self-referential-class objects linked together.

## 21.3 Dynamic Memory Allocation

Creating and maintaining dynamic data structures requires **dynamic memory allocation**—allowing a program to obtain more memory space at execution time to hold new nodes and to release space no longer needed. Remember that Java does not require you to explicitly release dynamically allocated memory. Rather, Java performs automatic *garbage collection* of objects that are no longer referenced in a program.

The limit for dynamic memory allocation can be as large as the amount of available physical memory in the computer or the amount of available disk space in a virtual-

memory system. Often the limits are much smaller, because the computer's available memory must be shared among many applications.

The declaration and class-instance-creation expression

```
// 10 is nodeToAdd's data
Node<Integer> nodeToAdd = new Node<Integer>(10);
```

allocates a `Node<Integer>` object and returns a reference to it, which is assigned to `nodeToAdd`. If *insufficient memory* is available, the preceding expression throws an `OutOfMemoryError`. The sections that follow discuss lists, stacks, queues and trees—all of which use dynamic memory allocation and self-referential classes to create dynamic data structures.

## 21.4 Linked Lists

A linked list is a linear collection (i.e., a sequence) of self-referential-class objects, called **nodes**, connected by reference *links*—hence, the term “linked” list. Typically, a program accesses a linked list via a reference to its first node. The program accesses each subsequent node via the link reference stored in the previous node. By convention, the link reference in the last node of the list is set to `null` to indicate “end of list.” Data is stored in and removed from linked lists dynamically—the program creates and deletes nodes as necessary. Stacks and queues are also linear data structures and, as we’ll see, are constrained versions of linked lists. Trees are *nonlinear* data structures.

Lists of data can be stored in conventional Java arrays, but linked lists provide several advantages. A linked list is appropriate when the number of data elements to be represented in the data structure is *unpredictable*. Linked lists are dynamic, so the length of a list can increase or decrease as necessary, whereas the size of a conventional Java array cannot be altered—it’s fixed when the program creates the array. [Of course, `ArrayLists` *can* grow and shrink.] Conventional arrays can become full. Linked lists become full only when the system has *insufficient memory* to satisfy dynamic storage allocation requests. Package `java.util` contains class `LinkedList` (discussed in Chapter 16) for implementing and manipulating linked lists that grow and shrink during program execution.



### Performance Tip 21.1

*Insertion into a linked list is fast—only two references have to be modified (after locating the insertion point). All existing node objects remain at their current locations in memory.*

Linked lists can be maintained in sorted order simply by inserting each new element at the proper point in the list. (It does, of course, take time to *locate* the proper insertion point.) *Existing list elements do not need to be moved.*



### Performance Tip 21.2

*Insertion and deletion in a sorted array can be time consuming—all the elements following the inserted or deleted element must be shifted appropriately.*

### 21.4.1 Singly Linked Lists

Linked list nodes normally are *not stored contiguously* in memory. Rather, they’re logically contiguous. Figure 21.2 illustrates a linked list with several nodes. This diagram presents a **singly linked list**—each node contains one reference to the next node in the list. Often,




linked lists are implemented as *doubly linked lists*—each node contains a reference to the next node in the list *and* a reference to the preceding one.



### Performance Tip 21.3

*The elements of an array are contiguous in memory. This allows immediate access to any array element, because its address can be calculated directly as its offset from the beginning of the array. Linked lists do not afford such immediate access—an element can be accessed only by traversing the list from the front (or the back in a doubly linked list).*



**Fig. 21.2** | Linked-list graphical representation.

## 21.4.2 Implementing a Generic List Class

The program of Figs. 21.3–21.5 uses an object of our generic List class to manipulate a list of miscellaneous objects. The program consists of four classes—ListNode (Fig. 21.3, lines 6–37), List (Fig. 21.3, lines 40–147), EmptyListException (Fig. 21.4) and ListTest (Fig. 21.5). Encapsulated in each List object is a linked list of ListNode objects.

[*Note:* The List, ListNode and EmptyListException classes are placed in the package `com.deitel.datastructures`, so that they can be reused throughout this chapter. In Section 21.4.10, we discuss the package statement (line 3 of Figs. 21.3 and 21.4), and show how to compile and run programs that use classes in your own packages.]

```

1 // Fig. 21.3: List.java
2 // ListNode and List class declarations.
3 package com.deitel.datastructures;
4
5 // class to represent one node in a list
6 class ListNode<T>
7 {
8 // package access members; List can access these directly
9 T data; // data for this node
10 ListNode<T> nextNode; // reference to the next node in the list
11
12 // constructor creates a ListNode that refers to object
13 ListNode(T object)
14 {
15 this(object, null);
16 }
17

```

**Fig. 21.3** | ListNode and List class declarations. (Part I of 4.)

---

```

18 // constructor creates ListNode that refers to the specified
19 // object and to the next ListNode
20 ListNode(T object, ListNode<T> node)
21 {
22 data = object;
23 nextNode = node;
24 }
25
26 // return reference to data in node
27 T getData()
28 {
29 return data;
30 }
31
32 // return reference to next node in list
33 ListNode<T> getNext()
34 {
35 return nextNode;
36 }
37 } // end class ListNode<T>
38
39 // class List definition
40 public class List<T>
41 {
42 private ListNode<T> firstNode;
43 private ListNode<T> lastNode;
44 private String name; // string like "list" used in printing
45
46 // constructor creates empty List with "list" as the name
47 public List()
48 {
49 this("list");
50 }
51
52 // constructor creates an empty List with a name
53 public List(String listName)
54 {
55 name = listName;
56 firstNode = lastNode = null;
57 }
58
59 // insert item at front of List
60 public void insertAtFront(T insertItem)
61 {
62 if (isEmpty()) // firstNode and lastNode refer to same object
63 firstNode = lastNode = new ListNode<T>(insertItem);
64 else // firstNode refers to new node
65 firstNode = new ListNode<T>(insertItem, firstNode);
66 }
67
68 // insert item at end of List
69 public void insertAtBack(T insertItem)
70 {

```

---

**Fig. 21.3** | ListNode and List class declarations. (Part 2 of 4.)

---

```

71 if (isEmpty()) // firstNode and lastNode refer to same object
72 firstNode = lastNode = new ListNode<T>(insertItem);
73 else // lastNode's nextNode refers to new node
74 lastNode = lastNode.nextNode = new ListNode<T>(insertItem);
75 }
76
77 // remove first node from List
78 public T removeFromFront() throws EmptyListException
79 {
80 if (isEmpty()) // throw exception if List is empty
81 throw new EmptyListException(name);
82
83 T removedItem = firstNode.data; // retrieve data being removed
84
85 // update references firstNode and lastNode
86 if (firstNode == lastNode)
87 firstNode = lastNode = null;
88 else
89 firstNode = firstNode.nextNode;
90
91 return removedItem; // return removed node data
92 }
93
94 // remove last node from List
95 public T removeFromBack() throws EmptyListException
96 {
97 if (isEmpty()) // throw exception if List is empty
98 throw new EmptyListException(name);
99
100 T removedItem = lastNode.data; // retrieve data being removed
101
102 // update references firstNode and lastNode
103 if (firstNode == lastNode)
104 firstNode = lastNode = null;
105 else // locate new last node
106 {
107 ListNode<T> current = firstNode;
108
109 // loop while current node does not refer to lastNode
110 while (current.nextNode != lastNode)
111 current = current.nextNode;
112
113 lastNode = current; // current is new lastNode
114 current.nextNode = null;
115 }
116
117 return removedItem; // return removed node data
118 }
119

```

---

**Fig. 21.3** | ListNode and List class declarations. (Part 3 of 4.)

---

```

120 // determine whether list is empty
121 public boolean isEmpty()
122 {
123 return firstNode == null; // return true if list is empty
124 }
125
126 // output list contents
127 public void print()
128 {
129 if (isEmpty())
130 {
131 System.out.printf("Empty %s\n", name);
132 return;
133 }
134
135 System.out.printf("The %s is: ", name);
136 ListNode<T> current = firstNode;
137
138 // while not at end of list, output current node's data
139 while (current != null)
140 {
141 System.out.printf("%s ", current.data);
142 current = current.nextNode;
143 }
144
145 System.out.println();
146 }
147 } // end class List<T>

```

---

**Fig. 21.3** | ListNode and List class declarations. (Part 4 of 4.)

---

```

1 // Fig. 21.4: EmptyListException.java
2 // Class EmptyListException declaration.
3 package com.deitel.datastructures;
4
5 public class EmptyListException extends RuntimeException
6 {
7 // constructor
8 public EmptyListException()
9 {
10 this("List"); // call other EmptyListException constructor
11 }
12
13 // constructor
14 public EmptyListException(String name)
15 {
16 super(name + " is empty"); // call superclass constructor
17 }
18 } // end class EmptyListException

```

---

**Fig. 21.4** | Class EmptyListException declaration.

```

1 // Fig. 21.5: ListTest.java
2 // ListTest class to demonstrate List capabilities.
3 import com.deitel.datastructures.List;
4 import com.deitel.datastructures.EmptyListException;
5
6 public class ListTest
7 {
8 public static void main(String[] args)
9 {
10 List<Integer> list = new List<>();
11
12 // insert integers in list
13 list.insertAtFront(-1);
14 list.print();
15 list.insertAtFront(0);
16 list.print();
17 list.insertAtBack(1);
18 list.print();
19 list.insertAtBack(5);
20 list.print();
21
22 // remove objects from list; print after each removal
23 try
24 {
25 int removedItem = list.removeFromFront();
26 System.out.printf("%n%d removed%n", removedItem);
27 list.print();
28
29 removedItem = list.removeFromFront();
30 System.out.printf("%n%d removed%n", removedItem);
31 list.print();
32
33 removedItem = list.removeFromBack();
34 System.out.printf("%n%d removed%n", removedItem);
35 list.print();
36
37 removedItem = list.removeFromBack();
38 System.out.printf("%n%d removed%n", removedItem);
39 list.print();
40 }
41 catch (EmptyListException emptyListException)
42 {
43 emptyListException.printStackTrace();
44 }
45 }
46 } // end class ListTest

```

```

The list is: -1
The list is: 0 -1
The list is: 0 -1 1
The list is: 0 -1 1 5

```

**Fig. 21.5** | ListTest class to demonstrate List capabilities. (Part I of 2.)

```

0 removed
The list is: -1 1 5
-1 removed
The list is: 1 5
5 removed
The list is: 1
1 removed
Empty list

```

**Fig. 21.5** | ListTest class to demonstrate List capabilities. (Part 2 of 2.)

### 21.4.3 Generic Classes ListNode and List

Generic class `ListNode` (Fig. 21.3, lines 6–37) declares package-access fields `data` and `nextNode`. The `data` field is a reference of type `T`, so its type will be determined when the client code creates the corresponding `List` object. Variable `nextNode` stores a reference to the next `ListNode` object in the linked list (or `null` if the node is the last one in the list).

Lines 42–43 of class `List` (Fig. 21.3, lines 40–47) declare references to the first and last `ListNode`s in a `List` (`firstNode` and `lastNode`, respectively). The constructors (lines 47–50 and 53–57) initialize both references to `null`. The most important methods of class `List` are `insertAtFront` (lines 60–66), `insertAtBack` (lines 69–75), `removeFromFront` (lines 78–92) and `removeFromBack` (lines 95–118). Method `isEmpty` (lines 121–124) is a *predicate method* that determines whether the list is empty (i.e., the reference to the first node of the list is `null`). Predicate methods typically test a condition and do not modify the object on which they’re called. If the list is empty, method `isEmpty` returns `true`; otherwise, it returns `false`. Method `print` (lines 127–146) displays the list’s contents. We discuss class `List`’s methods in more detail after we discuss class `ListTest`.

### 21.4.4 Class ListTest

Method `main` of class `ListTest` (Fig. 21.5) creates a `List<Integer>` object (line 10), then inserts objects at the beginning of the list using method `insertAtFront`, inserts objects at the end of the list using method `insertAtBack`, deletes objects from the front of the list using method `removeFromFront` and deletes objects from the end of the list using method `removeFromBack`. After each insert and remove operation, `ListTest` calls `List` method `print` to display the current list contents. If an attempt is made to remove an item from an empty list, an `EmptyListException` (Fig. 21.4) is thrown, so the method calls to `removeFromFront` and `removeFromBack` are placed in a try block that’s followed by an appropriate exception handler. Notice in lines 13, 15, 17 and 19 (Fig. 21.5) that the application passes literal primitive `int` values to methods `insertAtFront` and `insertAtBack`. Each of these methods was declared with a parameter of the generic type `T` (Fig. 21.3, lines 60 and 69). Since this example manipulates a `List<Integer>`, the type `T` represents the type-wrapper class `Integer`. In this case, the JVM *autoboxes* each literal value in an `Integer` object, and that object is actually inserted into the list.


### 21.4.5 List Method insertAtFront

Now we discuss each method of class `List` (Fig. 21.3) in detail and provide diagrams showing the reference manipulations performed by methods `insertAtFront`, `insertAt-`

Back, `removeFromFront` and `removeFromBack`. Method `insertAtFront` (lines 60–66 of Fig. 21.3) places a new node at the front of the list. The steps are:

1. Call `isEmpty` to determine whether the list is empty (line 62).
2. If the list is empty, assign to `firstNode` and `lastNode` the new `ListNode` that was initialized with `insertItem` (line 63). (Recall that assignment operators evaluate right to left.) The `ListNode` constructor at lines 13–16 calls the `ListNode` constructor at lines 20–24 to set instance variable `data` to refer to the `insertItem` passed as an argument and to set reference `nextNode` to `null`, because this is the first and last node in the list.
3. If the list is not empty, the new node is “linked” into the list by setting `firstNode` to a new `ListNode` object and initializing that object with `insertItem` and `firstNode` (line 65). When the `ListNode` constructor (lines 20–24) executes, it sets instance variable `data` to refer to the `insertItem` passed as an argument and performs the insertion by setting the `nextNode` reference of the new node to the `ListNode` passed as an argument, which previously was the first node.

In Fig. 21.6, part (a) shows a list and a new node during the `insertAtFront` operation and before the program links the new node into the list. The dotted arrows in part (b) illustrate *Step 3* of the `insertAtFront` operation that enables the node containing 12 to become the new first node in the list.



**Fig. 21.6** | Graphical representation of operation `insertAtFront`.

### 21.4.6 List Method `insertAtBack`


Method `insertAtBack` (lines 69–75 of Fig. 21.3) places a new node at the back of the list. The steps are:

1. Call `isEmpty` to determine whether the list is empty (line 71).
2. If the list is empty, assign to `firstNode` and `lastNode` the new `ListNode` that was initialized with `insertItem` (line 72). The `ListNode` constructor at lines 13–16

calls the constructor at lines 20–24 to set instance variable `data` to refer to the `insertItem` passed as an argument and to set reference `nextNode` to `null`.

3. If the list is not empty, line 74 links the new node into the list by assigning to `lastNode` and `lastNode.nextNode` the reference to the new `ListNode` that was initialized with `insertItem`. `ListNode`'s constructor (lines 13–16) sets instance variable `data` to refer to the `insertItem` passed as an argument and sets reference `nextNode` to `null`, because this is the last node in the list.

In Fig. 21.7, part (a) shows a list and a new node during the `insertAtBack` operation and before linking the new node into the list. The dotted arrows in part (b) illustrate *Step 3* of method `insertAtBack`, which adds the new node to the end of a list that's not empty.



**Fig. 21.7** | Graphical representation of operation `insertAtBack`.


### 21.4.7 List Method `removeFromFront`

Method `removeFromFront` (lines 78–92 of Fig. 21.3) removes the first node of the list and returns a reference to the removed data. If the list is empty when the program calls this method, the method throws an `EmptyListException` (lines 80–81). Otherwise, the method returns a reference to the removed data. The steps are:

1. Assign `firstNode.data` (the data being removed) to `removedItem` (line 83).
2. If `firstNode` and `lastNode` refer to the same object (line 86), the list has only one element at this time. So, the method sets `firstNode` and `lastNode` to `null` (line 87) to remove the node from the list (leaving the list empty).
3. If the list has more than one node, then the method leaves reference `lastNode` as is and assigns the value of `firstNode.nextNode` to `firstNode` (line 89). Thus, `firstNode` references the node that was previously the second node in the list.
4. Return the `removedItem` reference (line 91).

In Fig. 21.8, part (a) illustrates the list before the removal operation. The dashed lines and arrows in part (b) show the reference manipulations.






**Fig. 21.8** | Graphical representation of operation `removeFromFront`.

### 21.4.8 List Method `removeFromBack`

Method `removeFromBack` (lines 95–118 of Fig. 21.3) removes the last node of a list and returns a reference to the removed data. The method throws an `EmptyListException` (lines 97–98) if the list is empty when the program calls this method. The steps are:

1. Assign `lastNode.data` (the data being removed) to `removedItem` (line 100).
2. If the `firstNode` and `lastNode` refer to the same object (line 103), the list has only one element at this time. So, line 104 sets `firstNode` and `lastNode` to `null` to remove that node from the list (leaving the list empty).
3. If the list has more than one node, create the `ListNode` reference `current` and assign it `firstNode` (line 107).
4. Now “walk the list” with `current` until it references the node before the last node. The `while` loop (lines 110–111) assigns `current.nextNode` to `current` as long as `current.nextNode` (the next node in the list) is not `lastNode`.
5. After locating the second-to-last node, assign `current` to `lastNode` (line 113) to update which node is last in the list.
6. Set the `current.nextNode` to `null` (line 114) to remove the last node from the list and terminate the list at the current node.
7. Return the `removedItem` reference (line 117).

In Fig. 21.9, part (a) illustrates the list before the removal operation. The dashed lines and arrows in part (b) show the reference manipulations. [We limited the `List` insertion



**Fig. 21.9** | Graphical representation of operation `removeFromBack`.

and removal operations to the front and the back of the list. In Exercise 21.26, you'll enhance the `List` class to enable insertions and deletions *anywhere* in the `List`.]

### 21.4.9 List Method `print`

Method `print` (lines 127–146 of Fig. 21.3) first determines whether the list is empty (lines 129–133). If so, `print` displays a message indicating that the list is empty and returns control to the calling method. Otherwise, `print` outputs the list's data. Line 136 creates `ListNode` `current` and initializes it with `firstNode`. While `current` is not null, there are more items in the list. Therefore, line 141 outputs a string representation of `current.data`. Line 142 moves to the next node in the list by assigning the value of reference `current.nextNode` to `current`. This printing algorithm is identical for linked lists, stacks and queues.

### 21.4.10 Creating Your Own Packages

As you know, the Java API types (classes, interfaces and enums) are organized in *packages* that group related types. Packages facilitate software reuse by enabling programs to *import* existing classes, rather than *copying* them into the folders of each program that uses them. Programmers use packages to organize program components, especially in large programs. For example, you might have one package containing the types that make up your program's graphical user interface, another for the types that manage your application's data and another for the types that communicate with servers over a network. In addition, packages help you specify unique names for every type you declare, which (as we'll discuss) helps prevent class-name conflicts. This section introduces how to create and use your own packages. Much of what we discuss here is handled for you by IDEs such as NetBeans, Eclipse and IntelliJ IDEA. We focus on creating and using packages with the JDK's command-line tools.

### Steps for Declaring a Reusable Class

Before a class can be imported into multiple programs, it must be placed in a package to make it reusable. The steps for creating a reusable class are:

1. Declare one or more `public` types (classes, interfaces and enums). Only `public` types can be reused outside the package in which they're declared.
2. Choose a unique package name and add a **package declaration** to the source-code file for each reusable type that should be part of the package.
3. Compile the types so that they're placed in the appropriate package directory.
4. Import the reusable types into a program and use them.

We'll now discuss each of these steps in more detail.

#### Step 1: Creating `public` Types for Reuse

For *Step 1*, you declare the types that will be placed in the package, including both the reusable types and any supporting types. In Fig. 21.3, class `List` is `public`, so it's reusable outside its package. Class `ListNode`, however, is not `public`, so it can be used *only* by class `List` and any other types declared in the *same* package. In Fig. 21.4, class `EmptyListException` is `public`, so it, too, is reusable. If a source-code file contains more than one type, all types in the file are placed in the same package when the file is compiled.

#### Step 2: Adding the package Statements

For *Step 2*, you provide a package declaration containing the package's name. All source-code files containing types that should be part of the same package must contain the *same* package declaration. Figures 21.3 and 21.4 each contain:

```
package com.deitel.datastructures;
```

indicating that all the types declared in those files—`ListNode` and `List` in Fig. 21.3 and `EmptyListException` in Fig. 21.4—are part of the `com.deitel.datastructures` package.

Each Java source-code file may contain only *one* package declaration, and it must *precede* all other declarations and statements. If no package statement is provided in a Java source-code file, the types declared in that file are placed in the so-called *default package* and are accessible only to other classes in the default package that are located in the *same directory*. All prior programs in this book have used this default package.

#### Package Naming Conventions

A package name's parts are separated by dots (`.`), and there typically are two or more parts. To ensure *unique* package names, you typically begin the name with your institution's or company's Internet domain name in reverse order—e.g., our domain name is `deitel.com`, so we begin our package names with `com.deitel`. For the domain name `yourcollege.edu`, you'd begin the package name with `edu.yourcollege`.

After the reversed domain name, you can specify additional parts in a package name. If you're part of a university with many schools or company with many divisions, you might use the school or division name as the next part of the package name. Similarly, if the types are for a specific project, you might include the project name as part of the package name. We chose `datastructures` as the next part in our package name to indicate that classes `ListNode`, `List` and `EmptyListException` are from this data structures chapter.

### Fully Qualified Names

The package name is part of the **fully qualified type name**, so the name of class `List` is actually `com.deitel.datastructures.List`. You can use this fully qualified name in your programs, or you can **import** the class and use its **simple name** (the class name by itself—`List`) in the program. If another package also contains a `List` class, the fully qualified class names can be used to distinguish between the classes in the program and prevent a **name conflict** (also called a **name collision**).

### Step 3: Compiling Packaged Types

*Step 3* is to compile the class so that it's stored in the appropriate package. When a Java file containing a package declaration is compiled, the resulting class file is placed in a directory specified by the declaration. Classes in the package `com.deitel.datastructures` are placed in the directory

```
com
 deitel
 datastructures
```

The names in the package declaration specify the exact location of the package's classes.

The `javac` command-line option `-d` causes the compiler to create the directories based on the package declaration. The option also specifies where the top-level directory in the package name should be placed on your system—you may specify a relative or complete path to this location. For example, the command

```
javac -d . List.java EmptyListException.java
```

specifies that the first directory in our package name (`com`) should be placed in the current directory. The period (`.`) after `-d` in the preceding command represents the *current directory* on the Windows, UNIX, Linux and Mac OS X operating systems (and several others as well). Similarly, the command

```
javac -d .. List.java EmptyListException.java
```

specifies that the first directory in our package name (`com`) should be placed in the *parent* directory—we did this for all the reusable classes in this chapter. Once you compile with the `-d` option, the package's `datastructures` directory contains the files `ListNode.class`, `List.class` and `EmptyListException.class`.

### Step 4: Importing Types from Your Package

Once types are compiled into a package, they can be imported (*Step 4*). Class `ListTest` (Fig. 21.5) is in the *default package* because its `.java` file does not contain a package declaration. Because class `ListTest` is in a *different* package from `List` and `EmptyListException`, you must either **import** these classes so that class `ListTest` can use them (lines 3–4 of Fig. 21.5) or you must *fully qualify* the names `List` and `EmptyListException` everywhere they're used throughout class `ListTest`. For example, line 10 of Fig. 21.5 could have been written as:

```
com.deitel.datastructures.List<Integer> list =
 new com.deitel.datastructures.List<>();
```

### Single-Type-Import vs. Type-Import-On-Demand Declarations

Lines 3–4 of Fig. 21.5 are **single-type-import declarations**—they each specify *one* class to import. When a source-code file uses *multiple* classes from a package, you can import those classes with a **type-import-on-demand declaration** of the form

```
import packagename.*;
```

which uses an asterisk (\*) at its end to inform the compiler that *all* public classes from the *packagename* package can be used in the file containing the import. Only those classes that are *used* are loaded at execution time. The preceding import allows you to use the simple name of any type from the *packagename* package. Throughout this book, we provide single-type-import declarations as a form of documentation to show you specifically which types are used in each program.



#### Common Programming Error 21.1

*Using the import declaration `import java.*;` causes a compilation error. You must specify the full package name from which you want to import classes.*



#### Error-Prevention Tip 21.1

*Using single-type-import declarations helps avoid naming conflicts by importing only the types you actually use in your code.*

### Specifying the Classpath When Compiling a Program

When compiling `ListTest`, `javac` must locate the `.class` files for classes `List` and `EmptyListException` to ensure that class `ListTest` uses them correctly. The compiler uses a special object called a **class loader** to locate the classes it needs. The class loader begins by searching the standard Java classes that are bundled with the JDK. Then it searches for **optional packages**. Java provides an **extension mechanism** that enables new (optional) packages to be added to Java for development and execution purposes. If the class is not found in the standard Java classes or in the extension classes, the class loader searches the **classpath**—a list of directories or **archive files** containing reusable types. Each directory or archive file is separated from the next by a **directory separator**—a semicolon (;) on Windows or a colon (:) on UNIX/Linux/Mac OS X. Archive files are individual files that contain directories of other files, typically in a compressed format. For example, the standard classes used by your programs are contained in the archive file `rt.jar`, which is installed with the JDK. Archive files normally end with the `.jar` or `.zip` file-name extensions.

By default, the classpath consists only of the current directory. However, the classpath can be modified by

1. providing the **`-classpath`** *listOfDirectories* option to the `javac` compiler or
2. setting the **CLASSPATH environment variable** (a special variable that you define and the operating system maintains so that programs can search for classes in the specified locations).

If you compile `ListTest.java` without specifying the `-classpath` option, as in

```
javac ListTest.java
```

the class loader assumes that the additional package(s) used by the `ListTest` program are in the *current directory*. As we mentioned, we placed our package in the *parent* directory so

that it could be used by other programs in this chapter. To compile `ListTest.java`, use the command

```
javac -classpath .;.. ListTest.java
```

on Windows or the command

```
javac -classpath .:... ListTest.java
```

on UNIX/Linux/Mac OS X. The `.` in the classpath enables the class loader to locate `ListTest` in the current directory. The `..` enables the class loader to locate the contents of package `com.deitel.datastructures` in the parent directory.



### Common Programming Error 21.2

*Specifying an explicit classpath eliminates the current directory from the classpath. This prevents classes in the current directory (including packages in the current directory) from loading properly. If classes must be loaded from the current directory, include a dot (`.`) in the classpath to specify the current directory.*



### Software Engineering Observation 21.2

*In general, it's a better practice to use the `-classpath` option of the compiler, rather than the `CLASSPATH` environment variable, to specify the classpath for a program. This enables each program to have its own classpath.*



### Error-Prevention Tip 21.2

*Specifying the classpath with the `CLASSPATH` environment variable can cause subtle and difficult-to-locate errors in programs that use different versions of the same package.*

## Specifying the Classpath When Executing a Program

When you execute a program, the JVM must be able to locate the `.class` files for the program's classes. Like the compiler, the `java` command uses a *class loader* that searches the standard classes and extension classes first, then searches the classpath (the current directory by default). The classpath can be specified explicitly by using the same techniques discussed for the compiler. As with the compiler, it's better to specify an individual program's classpath via command-line JVM options. You can specify the classpath in the `java` command via the `-classpath` or `-cp` command-line options, followed by a list of directories or archive files. Again, if classes must be loaded from the current directory, be sure to include a dot (`.`) in the classpath to specify the current directory. To execute the `ListTest` program, use the following command:

```
java -classpath .:... ListTest
```

You'll need to use similar `javac` and `java` commands for each of this chapter's remaining examples. For more information on the classpath, visit [docs.oracle.com/javase/7/docs/technotes/tools/index.html#general](https://docs.oracle.com/javase/7/docs/technotes/tools/index.html#general).

## 21.5 Stacks

A stack is a constrained version of a list—*new nodes can be added to and removed from a stack only at the top*. For this reason, a stack is referred to as a **last-in, first-out (LIFO)** data

structure. The link member in the bottom node is set to null to indicate the bottom of the stack. A stack is not required to be implemented as a linked list—it can also be implemented using an array.

The primary methods for manipulating a stack are **push** and **pop**, which add a new node to the top of the stack and remove a node from the top of the stack, respectively. Method **pop** also returns the data from the popped node.

Stacks have many interesting applications. For example, when a program calls a method, the called method must know how to return to its caller, so the return address of the calling method is pushed onto the program-execution stack (discussed in Section 5.6). If a series of method calls occurs, the successive return addresses are pushed onto the stack in last-in, first-out order so that each method can return to its caller. Stacks support recursive method calls in the *same* manner as they do conventional nonrecursive method calls.

The program-execution stack also contains the memory for local variables on each invocation of a method during a program's execution. When the method returns to its caller, the memory for that method's local variables is popped off the stack, and those variables are no longer known to the program. If the local variable is a reference and the object to which it referred has no other variables referring to it, the object can be garbage collected.

Compilers use stacks to evaluate arithmetic expressions and generate machine-language code to process them. The exercises in this chapter explore several applications of stacks, including using them to develop a complete working compiler. Also, package `java.util` contains class `Stack` (see Chapter 16) for implementing and manipulating stacks that can grow and shrink during program execution.

In this section, we take advantage of the close relationship between lists and stacks to implement a stack class by reusing the `List<T>` class of Fig. 21.3. We demonstrate two different forms of reusability. First, we implement the stack class by extending class `List`. Then we implement an identically performing stack class through *composition* by including a reference to a `List` object as a `private` instance variable. The list, stack and queue data structures in this chapter are implemented to store references to objects of any type to encourage further reusability.

### *Stack Class That Inherits from List<T>*

Figures 21.10 and 21.11 create and manipulate a stack class that extends the `List<T>` class of Fig. 21.3. We want the stack to have methods `push`, `pop`, `isEmpty` and `print`. Essentially, these are the `List<T>` methods `insertAtFront`, `removeFromFront`, `isEmpty` and `print`. Of course, class `List<T>` contains other methods (such as `insertAtBack` and `removeFromBack`) that we would rather not make accessible through the `public` interface to the stack class. It's important to remember that all methods in `List<T>`'s `public` interface class also are `public` methods of the subclass `StackInheritance<T>` (Fig. 21.10). Each method of `StackInheritance<T>` calls the appropriate `List<T>` method—for example, method `push` calls `insertAtFront` and method `pop` calls `removeFromFront`. `StackInheritance<T>` clients can call methods `isEmpty` and `print` because they're inherited from `List<T>`. Class `StackInheritance<T>` is declared in package `com.deitel.datastructures` (line 3) for reuse. `StackInheritance<T>` does not import `List<T>`—the classes are in the same package.

Class `StackInheritanceTest`'s method `main` (Fig. 21.11) creates an object of class `StackInheritance<T>` called `stack` (line 10). The program pushes integers onto the stack (lines 13, 15, 17 and 19). *Autoboxing* is used here to insert `Integer` objects into the data

---

```

1 // Fig. 21.10: StackInheritance.java
2 // StackInheritance extends class List.
3 package com.deitel.datastructures;
4
5 public class StackInheritance<T> extends List<T>
6 {
7 // constructor
8 public StackInheritance()
9 {
10 super("stack");
11 }
12
13 // add object to stack
14 public void push(T object)
15 {
16 insertAtFront(object);
17 }
18
19 // remove object from stack
20 public T pop() throws EmptyListException
21 {
22 return removeFromFront();
23 }
24 } // end class StackInheritance

```

---

**Fig. 21.10** | StackInheritance extends class List.

structure. Lines 27–32 pop the objects from the stack in an infinite while loop. If method pop is invoked on an empty stack, the method throws an `EmptyListException`. In this case, the program displays the exception's stack trace, which shows the methods on the program-execution stack at the time the exception occurred. The program uses method print (inherited from List) to output the contents of the stack.

---

```

1 // Fig. 21.11: StackInheritanceTest.java
2 // Stack manipulation program.
3 import com.deitel.datastructures.StackInheritance;
4 import com.deitel.datastructures.EmptyListException;
5
6 public class StackInheritanceTest
7 {
8 public static void main(String[] args)
9 {
10 StackInheritance<Integer> stack = new StackInheritance<>();
11
12 // use push method
13 stack.push(-1);
14 stack.print();
15 stack.push(0);
16 stack.print();
17 stack.push(1);

```

---

**Fig. 21.11** | Stack manipulation program. (Part I of 2.)



```

18 stack.print();
19 stack.push(5);
20 stack.print();
21
22 // remove items from stack
23 try
24 {
25 int removedItem;
26
27 while (true)
28 {
29 removedItem = stack.pop(); // use pop method
30 System.out.printf("%n%d popped%n", removedItem);
31 stack.print();
32 }
33 }
34 catch (EmptyListException emptyListException)
35 {
36 emptyListException.printStackTrace();
37 }
38 }
39 } // end class StackInheritanceTest

```

```

The stack is: -1
The stack is: 0 -1

The stack is: 1 0 -1
The stack is: 5 1 0 -1

5 popped
The stack is: 1 0 -1

1 popped
The stack is: 0 -1

0 popped
The stack is: -1

-1 popped
Empty stack
com.deitel.datastructures.EmptyListException: stack is empty
 at com.deitel.datastructures.List.removeFromFront(List.java:81)
 at com.deitel.datastructures.StackInheritance.pop(
 StackInheritance.java:22)
 at StackInheritanceTest.main(StackInheritanceTest.java:29)

```

**Fig. 21.11** | Stack manipulation program. (Part 2 of 2.)

### *Forming a Stack Class Via Composition Rather Than Inheritance*

A better way to implement a stack class is by reusing a list class through *composition*. Figure 21.12 uses a private `List<T>` (line 7) in class `StackComposition<T>`'s declaration. Composition enables us to hide the `List<T>` methods that should not be in our stack's public interface. We provide public interface methods that use only the required `List<T>` methods. Implementing each stack method as a call to a `List<T>` method is called

**delegation**—the stack method invoked delegates the call to the appropriate `List<T>` method. In particular, `StackComposition<T>` delegates calls to `List<T>` methods `insertAtFront`, `removeFromFront`, `isEmpty` and `print`. In this example, we do not show class `StackCompositionTest`, because the only difference is that we change the type of the stack from `StackInheritance` to `StackComposition` (lines 3 and 10 of Fig. 21.11).

---

```

1 // Fig. 21.12: StackComposition.java
2 // StackComposition uses a composed List object.
3 package com.deitel.datastructures;
4
5 public class StackComposition<T>
6 {
7 private List<T> stackList;
8
9 // constructor
10 public StackComposition()
11 {
12 stackList = new List<T>("stack");
13 }
14
15 // add object to stack
16 public void push(T object)
17 {
18 stackList.insertAtFront(object);
19 }
20
21 // remove object from stack
22 public T pop() throws EmptyListException
23 {
24 return stackList.removeFromFront();
25 }
26
27 // determine if stack is empty
28 public boolean isEmpty()
29 {
30 return stackList.isEmpty();
31 }
32
33 // output stack contents
34 public void print()
35 {
36 stackList.print();
37 }
38 } // end class StackComposition

```

---

**Fig. 21.12** | `StackComposition` uses a composed `List` object.

## 21.6 Queues

Another commonly used data structure is the queue. A queue is similar to a checkout line in a supermarket—the cashier services the person at the *beginning* of the line *first*. Other customers enter the line only at the end and wait for service. *Queue nodes are removed only from the head (or front) of the queue and are inserted only at the tail (or end)*. For this reason,

a queue is a **first-in, first-out (FIFO)** data structure. The insert and remove operations are known as **enqueue** and **dequeue**.

Queues have many uses in computer systems. Each CPU in a computer can service only one application at a time. Each application requiring processor time is placed in a queue. The application at the front of the queue is the next to receive service. Each application gradually advances to the front as the applications before it receive service.

Queues are also used to support **print spooling**. For example, a single printer might be shared by all users of a network. Many users can send print jobs to the printer, even when the printer is already busy. These print jobs are placed in a queue until the printer becomes available. A program called a **spooler** manages the queue to ensure that, as each print job completes, the next one is sent to the printer.

Information packets also *wait* in queues in computer networks. Each time a packet arrives at a network node, it must be routed to the next node along the path to the packet's final destination. The routing node routes one packet at a time, so additional packets are enqueued until the router can route them.

A file server in a computer network handles file-access requests from many clients throughout the network. Servers have a limited capacity to service requests from clients. When that capacity is exceeded, client requests *wait* in queues.

Figure 21.13 creates a `Queue<T>` class that contains a `List<T>` (Fig. 21.3) object and provides methods `enqueue`, `dequeue`, `isEmpty` and `print`. Class `List<T>` contains some methods (e.g., `insertAtFront` and `removeFromBack`) that we'd rather not make accessible through `Queue<T>`'s public interface. Using composition enables us to hide class `List<T>`'s other public methods from clients of class `Queue<T>`. Each `Queue<T>` method calls an appropriate `List<T>` method—method `enqueue` calls `List<T>` method `insertAtBack`, method `dequeue` calls `List<T>` method `removeFromFront`, method `isEmpty` calls `List<T>` method `isEmpty` and method `print` calls `List<T>` method `print`. For reuse, class `Queue<T>` is declared in package `com.deitel.datastructures`.

---

```

1 // Fig. 21.13: Queue.java
2 // Queue uses class List.
3 package com.deitel.datastructures;
4
5 public class Queue
6 {
7 private List<T> queueList;
8
9 // constructor
10 public Queue()
11 {
12 queueList = new List<T>("queue");
13 }
14
15 // add object to queue
16 public void enqueue(T object)
17 {
18 queueList.insertAtBack(object);
19 }

```

---

**Fig. 21.13** | Queue uses class List. (Part I of 2.)

---

```

20
21 // remove object from queue
22 public T dequeue() throws EmptyListException
23 {
24 return queueList.removeFromFront();
25 }
26
27 // determine if queue is empty
28 public boolean isEmpty()
29 {
30 return queueList.isEmpty();
31 }
32
33 // output queue contents
34 public void print()
35 {
36 queueList.print();
37 }
38 } // end class Queue

```

---

**Fig. 21.13** | Queue uses class List. (Part 2 of 2.)

Class QueueTest's (Fig. 21.14) main method creates and initializes Queue<T> variable queue (line 10). Lines 13, 15, 17 and 19 enqueue four integers, taking advantage of *auto-boxing* to insert Integer objects into the queue. Lines 27–32 use an infinite loop to dequeue the objects in first-in, first-out order. When the queue is empty, method dequeue throws an EmptyListException, and the program displays the exception's stack trace.

---

```

1 // Fig. 21.14: QueueTest.java
2 // Class QueueTest.
3 import com.deitel.datastructures.Queue;
4 import com.deitel.datastructures.EmptyListException;
5
6 public class QueueTest
7 {
8 public static void main(String[] args)
9 {
10 Queue<Integer> queue = new Queue<>();
11
12 // use enqueue method
13 queue.enqueue(-1);
14 queue.print();
15 queue.enqueue(0);
16 queue.print();
17 queue.enqueue(1);
18 queue.print();
19 queue.enqueue(5);
20 queue.print();
21

```

---

**Fig. 21.14** | Queue processing program. (Part 1 of 2.)

```

22 // remove objects from queue
23 try
24 {
25 int removedItem;
26
27 while (true)
28 {
29 removedItem = queue.dequeue(); // use dequeue method
30 System.out.printf("%n%d dequeued%n", removedItem);
31 queue.print();
32 }
33 }
34 catch (EmptyListException emptyListException)
35 {
36 emptyListException.printStackTrace();
37 }
38 }
39 } // end class QueueTest

```

```

The queue is: -1
The queue is: -1 0
The queue is: -1 0 1
The queue is: -1 0 1 5

-1 dequeued
The queue is: 0 1 5

0 dequeued
The queue is: 1 5

1 dequeued
The queue is: 5


5 dequeued
Empty queue
com.deitel.datastructures.EmptyListException: queue is empty
 at com.deitel.datastructures.List.removeFromFront(List.java:81)
 at com.deitel.datastructures.Queue.dequeue(Queue.java:24)
 at QueueTest.main(QueueTest.java:29)

```

**Fig. 21.14** | Queue processing program. (Part 2 of 2.)


## 21.7 Trees

Lists, stacks and queues are **linear data structures** (i.e., **sequences**). A tree is a nonlinear, two-dimensional data structure with special properties. Tree nodes contain two or more links. This section discusses binary trees (Fig. 21.15)—trees whose nodes each contain two links (one or both of which may be null). The **root node** is the first node in a tree. Each link in the root node refers to a **child**. The **left child** is the first node in the **left subtree** (also known as the root node of the left subtree), and the **right child** is the first node in the **right subtree** (also known as the root node of the right subtree). The children of a specific node are called **siblings**. A node with no children is called a **leaf node**. Computer scientists normally draw trees from the root node down—the opposite of the way most trees grow in nature.



**Fig. 21.15** | Binary tree graphical representation.

In our example, we create a special binary tree called a **binary search tree**. A binary search tree (with no duplicate node values) has the characteristic that the values in any left subtree are less than the value in that subtree's parent node, and the values in any right subtree are greater than the value in that subtree's parent node. Figure 21.16 illustrates a binary search tree with 12 integer values. The shape of the binary search tree that corresponds to a set of data can vary, depending on the order in which the values are inserted into the tree.



**Fig. 21.16** | Binary search tree containing 12 values.

Figures 21.17 and 21.18 create a generic binary search tree class and use it to manipulate a tree of integers. The application in Fig. 21.18 *traverses* the tree (i.e., walks through all its nodes) three ways—using recursive **inorder**, **preorder** and **postorder traversals** (trees are almost always processed recursively). The program generates 10 random numbers and inserts each into the tree. Class `Tree<T>` is declared in package `com.deitel.datastructures` for reuse.

```

1 // Fig. 21.17: Tree.java
2 // TreeNode and Tree class declarations for a binary search tree.
3 package com.deitel.datastructures;
4
```

**Fig. 21.17** | `TreeNode` and `Tree` class declarations for a binary search tree. (Part I of 4.)

---

```

5 // class TreeNode definition
6 class TreeNode<T extends Comparable<T>>
7 {
8 // package access members
9 TreeNode<T> leftNode;
10 T data; // node value
11 TreeNode<T> rightNode;
12
13 // constructor initializes data and makes this a leaf node
14 public TreeNode(T nodeData)
15 {
16 data = nodeData;
17 leftNode = rightNode = null; // node has no children
18 }
19
20 // locate insertion point and insert new node; ignore duplicate values
21 public void insert(T insertValue)
22 {
23 // insert in left subtree
24 if (insertValue.compareTo(data) < 0)
25 {
26 // insert new TreeNode
27 if (leftNode == null)
28 leftNode = new TreeNode<T>(insertValue);
29 else // continue traversing left subtree recursively
30 leftNode.insert(insertValue);
31 }
32 // insert in right subtree
33 else if (insertValue.compareTo(data) > 0)
34 {
35 // insert new TreeNode
36 if (rightNode == null)
37 rightNode = new TreeNode<T>(insertValue);
38 else // continue traversing right subtree recursively
39 rightNode.insert(insertValue);
40 }
41 }
42 } // end class TreeNode
43
44 // class Tree definition
45 public class Tree<T extends Comparable<T>>
46 {
47 private TreeNode<T> root;
48
49 // constructor initializes an empty Tree of integers
50 public Tree()
51 {
52 root = null;
53 }
54
55 // insert a new node in the binary search tree
56 public void insertNode(T insertValue)
57 {

```

---

**Fig. 21.17** | `TreeNode` and `Tree` class declarations for a binary search tree. (Part 2 of 4.)

---

```

58 if (root == null)
59 root = new TreeNode<T>(insertValue); // create root node
60 else
61 root.insert(insertValue); // call the insert method
62 }
63
64 // begin preorder traversal
65 public void preorderTraversal()
66 {
67 preorderHelper(root);
68 }
69
70 // recursive method to perform preorder traversal
71 private void preorderHelper(TreeNode<T> node)
72 {
73 if (node == null)
74 return;
75
76 System.out.printf("%s ", node.data); // output node data
77 preorderHelper(node.leftNode); // traverse left subtree
78 preorderHelper(node.rightNode); // traverse right subtree
79 }
80
81 // begin inorder traversal
82 public void inorderTraversal()
83 {
84 inorderHelper(root);
85 }
86
87 // recursive method to perform inorder traversal
88 private void inorderHelper(TreeNode<T> node)
89 {
90 if (node == null)
91 return;
92
93 inorderHelper(node.leftNode); // traverse left subtree
94 System.out.printf("%s ", node.data); // output node data
95 inorderHelper(node.rightNode); // traverse right subtree
96 }
97
98 // begin postorder traversal
99 public void postorderTraversal()
100 {
101 postorderHelper(root);
102 }
103
104 // recursive method to perform postorder traversal
105 private void postorderHelper(TreeNode<T> node)
106 {
107 if (node == null)
108 return;
109

```

---

**Fig. 21.17** | `TreeNode` and `Tree` class declarations for a binary search tree. (Part 3 of 4.)



---

```

110 postorderHelper(node.leftNode); // traverse left subtree
111 postorderHelper(node.rightNode); // traverse right subtree
112 System.out.printf("%s ", node.data); // output node data
113 }
114 } // end class Tree

```

---

**Fig. 21.17** | `TreeNode` and `Tree` class declarations for a binary search tree. (Part 4 of 4.)

---

```

1 // Fig. 21.18: TreeTest.java
2 // Binary tree test program.
3 import java.security.SecureRandom;
4 import com.deitel.datastructures.Tree;
5
6 public class TreeTest
7 {
8 public static void main(String[] args)
9 {
10 Tree<Integer> tree = new Tree<Integer>();
11 SecureRandom randomNumber = new SecureRandom();
12
13 System.out.println("Inserting the following values: ");
14
15 // insert 10 random integers from 0-99 in tree
16 for (int i = 1; i <= 10; i++)
17 {
18 int value = randomNumber.nextInt(100);
19 System.out.printf("%d ", value);
20 tree.insertNode(value);
21 }
22
23 System.out.printf("\n\nPreorder traversal\n");
24 tree.preorderTraversal();
25
26 System.out.printf("\n\nInorder traversal\n");
27 tree.inorderTraversal();
28
29 System.out.printf("\n\nPostorder traversal\n");
30 tree.postorderTraversal();
31 System.out.println();
32 }
33 } // end class TreeTest

```

```

Inserting the following values:
49 64 14 34 85 64 46 14 37 55

Preorder traversal
49 14 34 46 37 64 55 85

Inorder traversal
14 34 37 46 49 55 64 85

Postorder traversal
37 46 34 14 55 85 64 49

```

**Fig. 21.18** | Binary tree test program.

Let's walk through the binary tree program. Method `main` of class `TreeTest` (Fig. 21.18) begins by instantiating an empty `Tree<T>` object and assigning its reference to variable `tree` (line 10). Lines 16–21 randomly generate 10 integers, each of which is inserted into the binary tree by calling method `insertNode` (line 20). The program then performs preorder, inorder and postorder traversals (these will be explained shortly) of `tree` (lines 24, 27 and 30, respectively).

### ***Overview of Class Tree***

Class `Tree` (Fig. 21.17, lines 45–114) requires its type argument to implement interface `Comparable`, so that each value inserted in the tree can be *compared* with the existing values to find the insertion point. The class has private field `root` (line 47)—a `TreeNode` reference to the root node of the tree. `Tree`'s constructor (lines 50–53) initializes `root` to `null` to indicate that the tree is *empty*. The class contains method `insertNode` (lines 56–62) to insert a new node in the tree and methods `preorderTraversal` (lines 65–68), `inorderTraversal` (lines 82–85) and `postorderTraversal` (lines 99–102) to begin traversals of the tree. Each of these methods calls a recursive utility method to perform the traversal operations on the internal representation of the tree.

### ***Tree Method insertNode***

Class `Tree`'s method `insertNode` (lines 56–62) first determines whether the tree is empty. If so, line 59 allocates a new `TreeNode`, initializes the node with the value being inserted in the tree and assigns the new node to reference `root`. If the tree is not empty, line 61 calls `TreeNode` method `insert` (lines 21–41). This method uses recursion to determine the location for the new node in the tree and inserts the node at that location. A node can be inserted only as a leaf node in a binary search tree.

### ***TreeNode Method insert***

`TreeNode` method `insert` compares the value to insert with the data value in the root node. If the insert value is less than the root node data (line 24), the program determines whether the left subtree is empty (line 27). If so, line 28 allocates a new `TreeNode`, initializes it with the value being inserted and assigns the new node to reference `leftNode`. Otherwise, line 30 recursively calls `insert` for the left subtree to insert the value into the left subtree. If the insert value is greater than the root node data (line 33), the program determines whether the right subtree is empty (line 36). If so, line 37 allocates a new `TreeNode`, initializes it with the value being inserted and assigns the new node to reference `rightNode`. Otherwise, line 39 recursively calls `insert` for the right subtree to insert the value in the right subtree. If the `insertValue` is already in the tree, it's simply ignored.

### ***Tree Methods inorderTraversal, preorderTraversal and postorderTraversal***


Methods `inorderTraversal`, `preorderTraversal` and `postorderTraversal` call `Tree` helper methods `inorderHelper` (lines 88–96), `preorderHelper` (lines 71–79) and `postorderHelper` (lines 105–113), respectively, to traverse the tree and print the node values. The helper methods in class `Tree` enable you to start a traversal without having to pass the root node to the method. Reference `root` is an *implementation detail* that a programmer should not be able to access. Methods `inorderTraversal`, `preorderTraversal` and `postorderTraversal` simply take the private `root` reference and pass it to the appropriate helper method to initiate a traversal of the tree. The base case for each helper method determines whether the reference it receives is `null` and, if so, returns immediately.

Method `inorderHelper` (lines 88–96) defines the steps for an inorder traversal:

1. Traverse the left subtree with a call to `inorderHelper` (line 93).
2. Process the value in the node (line 94).
3. Traverse the right subtree with a call to `inorderHelper` (line 95).

*The inorder traversal does not process the value in a node until the values in that node's left subtree are processed.* The inorder traversal of the tree in Fig. 21.19 is

6 13 17 27 33 42 48



**Fig. 21.19** | Binary search tree with seven values.

The inorder traversal of a binary search tree prints the node values in *ascending order*. The process of creating a binary search tree actually sorts the data; thus, it's called the **binary tree sort**.

Method `preorderHelper` (lines 71–79) defines the steps for a preorder traversal:

1. Process the value in the node (line 76).
2. Traverse the left subtree with a call to `preorderHelper` (line 77).
3. Traverse the right subtree with a call to `preorderHelper` (line 78).

*The preorder traversal processes the value in each node as the node is visited.* After processing the value in a particular node, it processes the values in the left subtree, then processes the values in the right subtree. The preorder traversal of the tree in Fig. 21.19 is

27 13 6 17 42 33 48

Method `postorderHelper` (lines 105–113) defines the steps for a postorder traversal:

1. Traverse the left subtree with a call to `postorderHelper` (line 110).
2. Traverse the right subtree with a call to `postorderHelper` (line 111).
3. Process the value in the node (line 112).

*The postorder traversal processes the value in each node after the values of all that node's children are processed.* The `postorderTraversal` of the tree in Fig. 21.19 is

6 17 13 33 48 42 27

The binary search tree facilitates **duplicate elimination**. While building a tree, the insertion operation recognizes attempts to insert a duplicate value, because a duplicate follows the same “go left” or “go right” decisions on each comparison as the original value did. Thus, the insertion operation eventually compares the duplicate with a node containing the same value. At this point, the insertion operation can decide to *discard* the duplicate value (as we do in this example).

Searching a binary tree for a value that matches a key value is fast, especially for **tightly packed** (or **balanced**) **trees**. In a tightly packed tree, each level contains about twice as many elements as the previous level. Figure 21.19 is a tightly packed binary tree. A tightly packed binary search tree with  $n$  elements has  $\log_2 n$  levels. Thus, at most  $\log_2 n$  comparisons are required either to find a match or to determine that no match exists. Searching a (tightly packed) 1000-element binary search tree requires at most 10 comparisons, because  $2^{10} > 1000$ . Searching a (tightly packed) 1,000,000-element binary search tree requires at most 20 comparisons, because  $2^{20} > 1,000,000$ .

The chapter exercises present algorithms for several other binary tree operations, such as deleting an item from a binary tree, printing a binary tree in a two-dimensional tree format and performing a **level-order traversal of a binary tree**. The level-order traversal visits the nodes of the tree row by row, starting at the root node level. On each level of the tree, a level-order traversal visits the nodes from left to right. Other binary tree exercises include allowing a binary search tree to contain duplicate values, inserting string values in a binary tree and determining how many levels are contained in a binary tree.

## 21.8 Wrap-Up

This chapter completes our presentation of data structures. We began in Chapter 16 with an introduction to the built-in collections of the Java Collections Framework and continued in Chapter 20 by showing you how to implement generic methods and collections. In this chapter, you learned to build generic dynamic data structures that grow and shrink at execution time. You learned that linked lists are collections of data items that are “linked up in a chain.” You also saw that an application can perform insertions and deletions at the beginning and end of a linked list. You learned that the stack and queue data structures are constrained versions of lists. For stacks, you saw that insertions and deletions are made only at the top. For queues that represent waiting lines, you saw that insertions are made at the tail and deletions are made from the head. You also learned the binary tree data structure. You saw a binary search tree that facilitated high-speed searching and sorting of data and eliminating duplicate data items efficiently. Throughout the chapter, you learned how to create and package these data structures for reusability and maintainability.

In the next chapter, you’ll continue your study of Swing GUI concepts, building on the techniques you learned in Chapter 12. In Chapter 25, we’ll introduce JavaFX GUI and include in-depth treatments of JavaFX GUI, graphics and multimedia in the online chapters.

## Summary

### Section 21.1 Introduction

- Dynamic data structures (p. 862) can grow and shrink at execution time.
- Linked lists (p. 862) are collections of data items “linked up in a chain”—insertions and deletions can be made anywhere in a linked list.
- Stacks (p. 862) are important in compilers and operating systems—insertions and deletions are made only at the top (p. 862) of a stack.
- In a queue, insertions are made at the tail (p. 862) and deletions are made from the head (p. 862).
- Binary trees (p. 862) facilitate high-speed searching and sorting, eliminating duplicate data items efficiently, representing file-system directories and compiling expressions into machine language.

### *Section 21.2 Self-Referential Classes*

- A self-referential class (p. 863) contains a reference that refers to another object of the same class type. Self-referential objects can be linked together to form dynamic data structures.

### *Section 21.3 Dynamic Memory Allocation*

- The limit for dynamic memory allocation (p. 863) can be as large as the available physical memory in the computer or the available disk space in a virtual-memory system. Often the limits are much smaller, because the computer's available memory must be shared among many users.
- If no memory is available, an `OutOfMemoryError` is thrown.

### *Section 21.4 Linked Lists*

- A linked list is accessed via a reference to the first node of the list. Each subsequent node is accessed via the link-reference member stored in the previous node.
- By convention, the link reference in the last node of a list is set to `null` to mark the end of the list.
- A node can contain data of any type, including objects of other classes.
- A linked list is appropriate when the number of data elements to be stored is unpredictable. Linked lists are dynamic, so the length of a list can increase or decrease as necessary.
- The size of a “conventional” Java array cannot be altered—it's fixed at creation time.
- List nodes normally are not stored in contiguous memory. Rather, they're logically contiguous.
- Packages help manage program components and facilitate software reuse.
- Packages provide a convention for unique type names that helps prevent naming conflicts (p. 876).
- Before a type can be imported into multiple programs, it must be placed in a package. There can be only one package declaration (p. 875) in each Java source-code file, and it must precede all other declarations and statements in the file.
- Every package name should start with your Internet domain name in reverse order. After the domain name is reversed, you can choose any other names you want for your package.
- When compiling types in a package, the `javac` command-line option `-d` (p. 876) specifies where to store the package and causes the compiler to create the package's directories if they do not exist.
- The package name is part of the fully qualified type name (p. 876).
- A single-type-import declaration (p. 877) specifies one class to import. A type-import-on-demand declaration (p. 877) imports only the classes that the program uses from a particular package.
- The compiler uses a class loader (p. 877) to locate the classes it needs in the classpath. The classpath consists of a list of directories or archive files, each separated by a directory separator (p. 877).
- The classpath for the compiler and JVM can be specified by providing the `-classpath` option (p. 878) to the `javac` or `java` command, or by setting the `CLASSPATH` environment variable. If classes must be loaded from the current directory, include a dot (`.`) in the classpath.

### *Section 21.5 Stacks*

- A stack is a last-in, first-out (LIFO) data structure (p. 878). The primary methods used to manipulate a stack are `push` (p. 879) and `pop` (p. 879), which add a new node to the stack's top and remove a node from the top, respectively. Method `pop` returns the removed node's data.
- When a method call is made, the called method must know how to return to its caller, so the return address is pushed onto the program-execution stack. If a series of method calls occurs, the successive return values are pushed onto the stack in last-in, first-out order.
- The program-execution stack contains the space created for local variables on each invocation of a method. When the method returns to its caller, the space for that method's local variables is popped off the stack, and those variables are no longer available to the program.

- Stacks are used by compilers to evaluate arithmetic expressions and generate machine-language code to process the expressions.
- The technique of implementing each stack method as a call to a `List` method is called delegation—the stack method invoked delegates (p. 882) the call to the appropriate `List` method.

### Section 21.6 Queues

- A queue (p. 890) is similar to a checkout line in a supermarket—the first person in line is serviced first, and other customers enter the line only at the end and wait to be serviced.
- Queue nodes are removed only from the head (p. 890) of the queue and are inserted only at the tail. For this reason, a queue is referred to as a first-in, first-out FIFO data structure.
- The insert and remove operations for a queue are known as `enqueue` (p. 883) and `dequeue` (p. 883).
- Queues have many uses in computer systems. Most computers have only a single processor, so only one application at a time can be serviced. Entries for the other applications are placed in a queue. The entry at the front of the queue is the next to receive service. Each entry gradually advances to the front of the queue as applications receive service.

### Section 21.7 Trees

- A tree is a nonlinear, two-dimensional data structure. Tree nodes contain two or more links.
- A binary tree (p. 885) is a tree whose nodes all contain two links. The root node (p. 885) is the first node in a tree.
- Each link in the root node refers to a child (p. 885). The left child (p. 885) is the first node in the left subtree (p. 885), and the right child (p. 885) is the first node in the right subtree (p. 885).
- The children of a node are called siblings (p. 885). A node with no children is a leaf node (p. 885).
- In a binary search tree (p. 886) with no duplicate values, the values in any left subtree are less than the value in the subtree's parent node, and the values in any right subtree are greater than the value in the subtree's parent node. A node can be inserted only as a leaf node in a binary search tree.
- An inorder traversal (p. 886) of a binary search tree processes the node values in ascending order.
- In a preorder traversal (p. 886), the value in each node is processed as the node is visited. Then the values in the left subtree are processed, then the values in the right subtree.
- In a postorder traversal (p. 886), the value in each node is processed after the values of its children.
- The binary search tree facilitates duplicate elimination (p. 891). As the tree is created, attempts to insert a duplicate value are recognized, because a duplicate follows the same “go left” or “go right” decisions on each comparison as the original value did. Thus, the duplicate eventually is compared with a node containing the same value. The duplicate value can be discarded at this point.
- In a tightly packed tree (p. 892), each level contains about twice as many elements as the previous one. So a tightly packed binary search tree with  $n$  elements has  $\log_2 n$  levels, and thus at most  $\log_2 n$  comparisons would have to be made either to find a match or to determine that no match exists. Searching a (tightly packed) 1000-element binary search tree requires at most 10 comparisons, because  $2^{10} > 1000$ . Searching a (tightly packed) 1,000,000-element binary search tree requires at most 20 comparisons, because  $2^{20} > 1,000,000$ .

## Self-Review Exercises

**21.1** Fill in the blanks in each of the following statements:

- a self-\_\_\_\_\_ class is used to form dynamic data structures that can grow and shrink at execution time.

- b) A(n) \_\_\_\_\_ is a constrained version of a linked list in which nodes can be inserted and deleted only from the start of the list.
- c) A method that does not alter a linked list, but simply looks at it to determine whether it's empty, is referred to as a(n) \_\_\_\_\_ method.
- d) A queue is referred to as a(n) \_\_\_\_\_ data structure because the first nodes inserted are the first ones removed.
- e) The reference to the next node in a linked list is referred to as a(n) \_\_\_\_\_.
- f) Automatically reclaiming dynamically allocated memory in Java is called \_\_\_\_\_.
- g) A(n) \_\_\_\_\_ is a constrained version of a linked list in which nodes can be inserted only at the end of the list and deleted only from the start of the list.
- h) A(n) \_\_\_\_\_ is a nonlinear, two-dimensional data structure that contains nodes with two or more links.
- i) A stack is referred to as a(n) \_\_\_\_\_ data structure because the last node inserted is the first node removed.
- j) The nodes of a(n) \_\_\_\_\_ tree contain two link members.
- k) The first node of a tree is the \_\_\_\_\_ node.
- l) Each link in a tree node refers to a(n) \_\_\_\_\_ or \_\_\_\_\_ of that node.
- m) A tree node that has no children is called a(n) \_\_\_\_\_ node.
- n) The three traversal algorithms we mentioned in the text for binary search trees are \_\_\_\_\_, \_\_\_\_\_ and \_\_\_\_\_.
- o) When compiling types in a package, the javac command-line option \_\_\_\_\_ specifies where to store the package and causes the compiler to create the package's directories if they do not exist.
- p) The compiler uses a(n) \_\_\_\_\_ to locate the classes it needs in the classpath.
- q) The classpath for the compiler and JVM can be specified with the \_\_\_\_\_ option to the javac or java command, or by setting the \_\_\_\_\_ environment variable.
- r) There can be only one \_\_\_\_\_ in a Java source-code file, and it must precede all other declarations and statements in the file.


**21.2** What are the differences between a linked list and a stack?

**21.3** What are the differences between a stack and a queue?

**21.4** Comment on how each of the following entities or concepts contributes to the reusability of data structures:

- a) classes
- b) inheritance
- c) composition

**21.5** Provide the inorder, preorder and postorder traversals of the binary search tree of Fig. 21.20.



**Fig. 21.20** | Binary search tree with 15 nodes.

## Answers to Self-Review Exercises

**21.1** a) referential. b) stack. c) predicate. d) first-in, first-out (FIFO). e) link. f) garbage collection. g) queue. h) tree i) last-in, first-out (LIFO). j) binary. k) root. l) child or subtree. m) leaf. n) inorder, preorder, postorder. o) -d. p) class loader. q) -classpath, CLASSPATH. r) package declaration.

**21.2** It's possible to insert a node anywhere in a linked list and remove a node from anywhere in a linked list. Nodes in a stack may be inserted only at the top of the stack and removed only from the top.

**21.3** A queue is a FIFO data structure that has references to both its head and its tail, so that nodes may be inserted at the tail and deleted from the head. A stack is a LIFO data structure that has a single reference to the stack's top, where both insertion and deletion of nodes are performed.

- 21.4**
- a) Classes allow us to create as many data structure objects as we wish.
  - b) Inheritance enables a subclass to reuse the functionality from a superclass. Public and protected superclass methods can be accessed through a subclass to eliminate duplicate logic.
  - c) Composition enables a class to reuse code by storing a reference to an instance of another class in a field. Public methods of the instance can be called by methods in the class that contains the reference.

**21.5** The inorder traversal is

11 18 19 28 32 40 44 49 69 71 72 83 92 97 99

The preorder traversal is

49 28 18 11 19 40 32 44 83 71 69 72 97 92 99

The postorder traversal is

11 19 18 32 44 40 28 69 72 71 92 99 97 83 49

## Exercises

**21.6** (*Concatenating Lists*) Write a program that concatenates two linked list objects of characters. Class `ListConcatenate` should include a static method `concatenate` that takes references to both list objects as arguments and concatenates the second list to the first list.

**21.7** (*Inserting into an Ordered List*) Write a program that inserts 25 random integers from 0 to 100 in order into a linked-list object. For this exercise, you'll need to modify the `List<T>` class (Fig. 21.3) to maintain an ordered list. Name the new version of the class `SortedList`.

**21.8** (*Merging Ordered Lists*) Modify the `SortedList` class from Exercise 21.7 to include a merge method that can merge the `SortedList` it receives as an argument with the `SortedList` that calls the method. Write an application to test method `merge`.

**21.9** (*Copying a List Backward*) Write a static method `reverseCopy` that receives a `List<T>` as an argument and returns a copy of that `List<T>` with its elements reversed. Test this method in an application.

**21.10** (*Printing a Sentence in Reverse Using a Stack*) Write a program that inputs a line of text and uses a stack to display the words of the line in reverse order.

**21.11** (*Palindrome Tester*) Write a program that uses a stack to determine whether a string is a palindrome (i.e., the string is spelled identically backward and forward). The program should ignore spaces and punctuation.



**21.12 (Infix-to-Postfix Converter)** Stacks are used by compilers to help in the process of evaluating expressions and generating machine-language code. In this and the next exercise, we investigate how compilers evaluate arithmetic expressions consisting only of constants, operators and parentheses.

Humans generally write expressions like  $3 + 4$  and  $7 / 9$  in which the operator (+ or / here) is written between its operands—this is called *infix notation*. Computers “prefer” *postfix notation*, in which the operator is written to the right of its two operands. The preceding infix expressions would appear in postfix notation as  $3\ 4\ +$  and  $7\ 9\ /$ , respectively.

To evaluate a complex infix expression, a compiler would first convert the expression to postfix notation and evaluate the postfix version. Each of these algorithms requires only a single left-to-right pass of the expression. Each algorithm uses a stack object in support of its operation, but each uses the stack for a different purpose.

In this exercise, you’ll write a Java version of the infix-to-postfix conversion algorithm. In the next exercise, you’ll write a Java version of the postfix expression evaluation algorithm. In a later exercise, you’ll discover that code you write in this exercise can help you implement a complete working compiler.

Write class `InfixToPostfixConverter` to convert an ordinary infix arithmetic expression (assume a valid expression is entered) with single-digit integers such as

$(6 + 2) * 5 - 8 / 4$

to a postfix expression. The postfix version (no parentheses are needed) of the this infix expression is

$6\ 2\ +\ 5\ *\ 8\ 4\ /\ -$

The program should read the expression into `StringBuffer infix` and use one of the stack classes implemented in this chapter to help create the postfix expression in `StringBuffer postfix`. The algorithm for creating a postfix expression is as follows:

- a) Push a left parenthesis '(' onto the stack.
- b) Append a right parenthesis ')' to the end of `infix`.
- c) While the stack is not empty, read `infix` from left to right and do the following:
  - If the current character in `infix` is a digit, append it to `postfix`.
  - If the current character in `infix` is a left parenthesis, push it onto the stack.
  - If the current character in `infix` is an operator:
    - Pop operators (if there are any) at the top of the stack while they have equal or higher precedence than the current operator, and append the popped operators to `postfix`.
    - Push the current character in `infix` onto the stack.
  - If the current character in `infix` is a right parenthesis:
    - Pop operators from the top of the stack and append them to `postfix` until a left parenthesis is at the top of the stack.
    - Pop (and discard) the left parenthesis from the stack.

The following arithmetic operations are allowed in an expression:

- + addition
- subtraction
- \* multiplication
- / division
- ^ exponentiation
- % remainder

The stack should be maintained with stack nodes that each contain an instance variable and a reference to the next stack node. Some methods you may want to provide are as follows:

- a) Method `convertToPostfix`, which converts the infix expression to postfix notation.
- b) Method `isOperator`, which determines whether `c` is an operator.

- c) Method precedence, which determines whether the precedence of operator1 (from the infix expression) is less than, equal to or greater than that of operator2 (from the stack). The method returns true if operator1 has lower precedence than operator2. Otherwise, false is returned.
- d) Method peek (this should be added to the stack class), which returns the top value of the stack without popping the stack.

**21.13 (Postfix Evaluator)** Write class `PostfixEvaluator` that evaluates a postfix expression such as

6 2 + 5 \* 8 4 / -

The program should read a postfix expression consisting of digits and operators into a `StringBuffer`. Using modified versions of the stack methods implemented earlier in this chapter, the program should scan the expression and evaluate it (assume it's valid). The algorithm is as follows:

- a) Append a right parenthesis ')' to the end of the postfix expression. When the right-parenthesis character is encountered, no further processing is necessary.
- b) Until the right parenthesis is encountered, read the expression from left to right. If the current character is a digit, do the following:
  - Push its integer value onto the stack (the integer value of a digit character is its value in the Unicode character set minus the value of '0' in Unicode).
  - Otherwise, if the current character is an *operator*:
    - Pop the two top elements of the stack into variables x and y.
    - Calculate y *operator* x.
    - Push the result of the calculation onto the stack.
- c) When the right parenthesis is encountered in the expression, pop the top value of the stack. This is the result of the postfix expression.

[Note: In b) above (based on the sample expression at the beginning of this exercise), if the operator is '/', the top of the stack is 4 and the next element in the stack is 40, then pop 4 into x, pop 40 into y, evaluate 40 / 4 and push the result, 10, back on the stack. This note also applies to operator '-'.] The arithmetic operations allowed in an expression are: + (addition), - (subtraction), \* (multiplication), / (division), ^ (exponentiation) and % (remainder).

The stack should be maintained with one of the stack classes introduced in this chapter. You may want to provide the following methods:

- a) Method `evaluatePostfixExpression`, which evaluates the postfix expression.
- b) Method `calculate`, which evaluates the expression op1 operator op2.

**21.14 (Postfix Evaluator Modification)** Modify the postfix evaluator program of Exercise 21.13 so that it can process integer operands larger than 9.

**21.15 (Supermarket Simulation)** Write a program that simulates a checkout line at a supermarket. The line is a queue object. Customers (i.e., customer objects) arrive in random integer intervals of from 1 to 4 minutes. Also, each customer is serviced in random integer intervals of from 1 to 4 minutes. Obviously, the rates need to be balanced. If the average arrival rate is larger than the average service rate, the queue will grow infinitely. Even with "balanced" rates, randomness can still cause long lines. Run the supermarket simulation for a 12-hour day (720 minutes), using the following algorithm:

- a) Choose a random integer between 1 and 4 to determine the minute at which the first customer arrives.
- b) At the first customer's arrival time, do the following:
  - Determine customer's service time (random integer from 1 to 4).
  - Begin servicing the customer.
  - Schedule arrival time of next customer (random integer 1 to 4 added to the current time).

- c) For each simulated minute of the day, consider the following:
  - If the next customer arrives, proceed as follows:
    - Say so.
    - Enqueue the customer.
    - Schedule the arrival time of the next customer.
  - If service was completed for the last customer, do the following:
    - Say so.
    - Dequeue next customer to be serviced.
    - Determine customer's service completion time (random integer from 1 to 4 added to the current time).

Now run your simulation for 720 minutes and answer each of the following:

- a) What is the maximum number of customers in the queue at any time?
- b) What is the longest wait any one customer experiences?
- c) What happens if the arrival interval is changed from 1 to 4 minutes to 1 to 3 minutes?

**21.16** (*Allowing Duplicates in a Binary Tree*) Modify Figs. 21.17 and 21.18 to allow the binary tree to contain duplicates.

**21.17** (*Processing a Binary Search Tree of Strings*) Write a program based on the program of Figs. 21.17 and 21.18 that inputs a line of text, tokenizes it into separate words, inserts the words in a binary search tree and prints the inorder, preorder and postorder traversals of the tree.

**21.18** (*Duplicate Elimination*) In this chapter, we saw that duplicate elimination is straightforward when creating a binary search tree. Describe how you'd perform duplicate elimination when using only a one-dimensional array. Compare the performance of array-based duplicate elimination with the performance of binary-search-tree-based duplicate elimination.

**21.19** (*Depth of a Binary Tree*) Modify Figs. 21.17 and 21.18 so the `Tree` class provides a method `getDepth` that determines how many levels are in the tree. Test the method in an application that inserts 20 random integers in a `Tree`.

**21.20** (*Recursively Print a List Backward*) Modify the `List<T>` class of Fig. 21.3 to include method `printListBackward` that recursively outputs the items in a linked-list object in reverse order. Write a test program that creates a list of integers and prints the list in reverse order.

**21.21** (*Recursively Search a List*) Modify the `List<T>` class of Fig. 21.3 to include method `search` that recursively searches a linked-list object for a specified value. The method should return a reference to the value if it's found; otherwise, it should return `null`. Use your method in a test program that creates a list of integers. The program should prompt the user for a value to locate in the list.

**21.22** (*Binary Tree Delete*) In this exercise, we discuss deleting items from binary search trees. The deletion algorithm is not as straightforward as the insertion algorithm. Three cases are encountered when deleting an item—the item is contained in a leaf node (i.e., it has no children), or in a node that has one child or in a node that has two children.

If the item to be deleted is contained in a leaf node, the node is deleted and the reference in the parent node is set to `null`.

If the item to be deleted is contained in a node with one child, the reference in the parent node is set to reference the child node and the node containing the data item is deleted. This causes the child node to take the place of the deleted node in the tree.

The last case is the most difficult. When a node with two children is deleted, another node in the tree must take its place. However, the reference in the parent node cannot simply be assigned to reference one of the children of the node to be deleted. In most cases, the resulting binary search

tree would not embody the following characteristic of binary search trees (with no duplicate values): *The values in any left subtree are less than the value in the parent node, and the values in any right subtree are greater than the value in the parent node.*

Which node is used as a *replacement node* to maintain this characteristic? It's either the node containing the largest value in the tree less than the value in the node being deleted, or the node containing the smallest value in the tree greater than the value in the node being deleted. Let's consider the node with the smaller value. In a binary search tree, the largest value less than a parent's value is located in the left subtree of the parent node and is guaranteed to be contained in the rightmost node of the subtree. This node is located by walking down the left subtree to the right until the reference to the right child of the current node is null. We're now referencing the replacement node, which is either a leaf node or a node with one child to its left. If the replacement node is a leaf node, the steps to perform the deletion are as follows:

- a) Store the reference to the node to be deleted in a temporary reference variable.
- b) Set the reference in the parent of the node being deleted to reference the replacement node.
- c) Set the reference in the parent of the replacement node to null.
- d) Set the reference to the right subtree in the replacement node to reference the right subtree of the node to be deleted.
- e) Set the reference to the left subtree in the replacement node to reference the left subtree of the node to be deleted.

The deletion steps for a replacement node with a left child are similar to those for a replacement node with no children, but the algorithm also must move the child into the replacement node's position in the tree. If the replacement node is a node with a left child, the steps to perform the deletion are as follows:

- a) Store the reference to the node to be deleted in a temporary reference variable.
- b) Set the reference in the parent of the node being deleted to refer to the replacement node.
- c) Set the reference in the parent of the replacement node to reference the left child of the replacement node.
- d) Set the reference to the right subtree in the replacement node to reference the right subtree of the node to be deleted.
- e) Set the reference to the left subtree in the replacement node to reference the left subtree of the node to be deleted.

Write method `deleteNode`, which takes as its argument the value to delete. Method `deleteNode` should locate in the tree the node containing the value to delete and use the algorithms discussed here to delete the node. If the value is not found in the tree, the method should display a message saying so. Modify the program of Figs. 21.17 and 21.18 to use this method. After deleting an item, call the methods `inorderTraversal`, `preorderTraversal` and `postorderTraversal` to confirm that the delete operation was performed correctly.

**21.23 (Binary Tree Search)** Modify class `Tree` of Fig. 21.17 to include method `contains`, which attempts to locate a specified value in a binary-search-tree object. The method should take as an argument a search key to locate. If the node containing the search key is found, the method should return a reference to that node's data; otherwise, it should return null.

**21.24 (Level-Order Binary Tree Traversal)** The program of Figs. 21.17 and 21.18 illustrated three recursive methods of traversing a binary tree—inorder, preorder and postorder traversals. This exercise presents the *level-order traversal* of a binary tree, in which the node values are printed level by level, starting at the root node level. The nodes on each level are printed from left to right. The level-order traversal is not a recursive algorithm. It uses a queue object to control the output of the nodes. The algorithm is as follows:


- a) Insert the root node in the queue.

- b) While there are nodes left in the queue, do the following:
- Get the next node in the queue.
  - Print the node's value.
  - If the reference to the left child of the node is not null:
    - Insert the left child node in the queue.
  - If the reference to the right child of the node is not null:
    - Insert the right child node in the queue.

Write method `levelOrder` to perform a level-order traversal of a binary tree object. Modify the program of Figs. 21.17 and 21.18 to use this method. [Note: You'll also need to use the queue-processing methods of Fig. 21.13 in this program.]

**21.25 (Printing Trees)** Modify class `Tree` of Fig. 21.17 to include a recursive `outputTree` method to display a binary tree object. The method should output the tree row by row, with the top of the tree at the left of the screen and the bottom of the tree toward the right. Each row is output vertically. For example, the binary tree illustrated in Fig. 21.20 is output as shown in Fig. 21.21.

The rightmost leaf node appears at the top of the output in the rightmost column and the root node appears at the left of the output. Each column starts five spaces to the right of the preceding column. Method `outputTree` should receive an argument `totalSpaces` representing the number of spaces preceding the value to be output. (This variable should start at zero so that the root node is output at the left of the screen.) The method uses a modified inorder traversal to output the tree—it starts at the rightmost node in the tree and works back to the left. The algorithm is as follows:



**Fig. 21.21** | Sample output of recursive method `outputTree`.

- While the reference to the current node is not null, perform the following:
  - Recursively call `outputTree` with the right subtree of the current node and `totalSpaces + 5`.
  - Use a `for` statement to count from 1 to `totalSpaces` and output spaces.
  - Output the value in the current node.
  - Set the reference to the current node to refer to the left subtree of the current node.
  - Increment `totalSpaces` by 5.

**21.26 (Insert/Delete Anywhere in a Linked List)** Our linked-list class allowed insertions and deletions at only the front and the back of the linked list. These capabilities were convenient for us when we used inheritance or composition to produce a stack class and a queue class with minimal code simply by reusing the list class. Linked lists are normally more general than those we provided. Modify the linked-list class we developed in this chapter to handle insertions and deletions *anywhere* in the list. Create diagrams comparable to Figs. 21.6 (`insertAtFront`), 21.7 (`insertAtBack`), 21.8

(`removeFromFront`) and 21.9 (`removeFromBack`) that show how to insert a new node in the middle of a linked list and how to remove an existing node from the middle of a linked list.

**21.27** (*Lists and Queues without Tail References*) Our linked-list implementation (Fig. 21.3) used both a `firstNode` and a `lastNode`. The `lastNode` was useful for the `insertAtBack` and `removeFromBack` methods of the `List` class. The `insertAtBack` method corresponds to the `enqueue` method of the `Queue` class. Rewrite the `List` class so that it does not use a `lastNode`. Thus, any operations on the tail of a list must begin searching the list from the front. Does this affect our implementation of the `Queue` class (Fig. 21.13)?

**21.28** (*Performance of Binary Tree Sorting and Searching*) One problem with the binary tree sort is that the order in which the data is inserted affects the shape of the tree—for the same collection of data, different orderings can yield binary trees of dramatically different shapes. The performance of the binary tree sorting and searching algorithms is sensitive to the shape of the binary tree. What shape would a binary tree have if its data were inserted in increasing order? in decreasing order? What shape should the tree have to achieve maximal searching performance?

**21.29** (*Indexed Lists*) As presented in the text, linked lists must be searched sequentially. For large lists, this can result in poor performance. A common technique for improving list-searching performance is to create and maintain an index to the list. An index is a set of references to key places in the list. For example, an application that searches a large list of names could improve performance by creating an index with 26 entries—one for each letter of the alphabet. A search operation for a last name beginning with ‘Y’ would then first search the index to determine where the ‘Y’ entries began, then “jump into” the list at that point and search linearly until the desired name was found. This would be much faster than searching the linked list from the beginning. Use the `List` class of Fig. 21.3 as the basis of an `IndexedList` class. Write a program that demonstrates the operation of indexed lists. Be sure to include methods `insertInIndexedList`, `searchIndexedList` and `deleteFromIndexedList`.

**21.30** (*Queue Class that Inherits from a List Class*) In Section 21.5, we created a stack class from class `List` with inheritance (Fig. 21.10) and with composition (Fig. 21.12). In Section 21.6 we created a queue class from class `List` with composition (Fig. 21.13). Create a queue class by inheriting from class `List`. What are the differences between this class and the one we created with composition?

## Special Section: Building Your Own Compiler

In Exercises 6.30–6.32, we introduced Simpletron Machine Language (SML), and you implemented a Simpletron computer simulator to execute SML programs. In Exercises 21.31–21.35, we build a compiler that converts programs written in a high-level programming language to SML. This section “ties” together the entire programming process. You’ll write programs in this new high-level language, compile them on the compiler you build and run them on the simulator you built in Exercise 6.31. You should make every effort to implement your compiler in an object-oriented manner. [Note: Due to the size of the descriptions for Exercises 21.31–21.35, we’ve posted them in a PDF document located at [www.deitel.com/books/jhttp10LOV/](http://www.deitel.com/books/jhttp10LOV/)]

# GUI Components: Part 2

# 22



*...the force of events wakes  
slumberous talents.*

—Edward Hoagland

*You and I would see more  
interesting photography if they  
would stop worrying, and  
instead, apply horse-sense to the  
problem of recording the look  
and feel of their own era.*

—Jessie Tarbox Beals

## Objectives

In this chapter you'll:

- Create and manipulate sliders, menus, pop-up menus and windows.
- Programatically change the look-and-feel of a GUI, using Swing's pluggable look-and-feel.
- Create a multiple-document interface with `JDesktopPane` and `JInternalFrame`.
- Use additional layout managers `BoxLayout` and `GridBagLayout`.

|                                    |                                      |
|------------------------------------|--------------------------------------|
| 22.1 Introduction                  | 22.7 JDesktopPane and JInternalFrame |
| 22.2 JSlider                       | 22.8 JTabbedPane                     |
| 22.3 Understanding Windows in Java | 22.9 BoxLayout Layout Manager        |
| 22.4 Using Menus with Frames       | 22.10 GridBagLayout Layout Manager   |
| 22.5 JPopupMenu                    | 22.11 Wrap-Up                        |
| 22.6 Pluggable Look-and-Feel       |                                      |

Summary | Self-Review Exercises | Answers to Self-Review Exercises | Exercises

## 22.1 Introduction

In this chapter, we continue our study of Swing GUIs. We discuss additional components and layout managers and lay the groundwork for building more complex GUIs. We begin with sliders for selecting from a range of integer values, then discuss additional details of windows. Next, you'll use menus to organize an application's commands.

The look-and-feel of a Swing GUI can be uniform across all platforms on which a Java program executes, or the GUI can be customized by using Swing's **pluggable look-and-feel (PLAF)**. We provide an example that illustrates how to change between Swing's default metal look-and-feel (which looks and behaves the same across platforms), the Nimbus look-and-feel (introduced in Chapter 12), a look-and-feel that simulates **Motif** (a UNIX look-and-feel) and one that simulates the Microsoft Windows look-and-feel.

Many of today's applications use a multiple-document interface (MDI)—a main window (often called the *parent window*) containing other windows (often called *child windows*) to manage several open documents in parallel. For example, many e-mail programs allow you to have several e-mail windows open at the same time so that you can compose or read multiple e-mail messages. We demonstrate Swing's classes for creating multiple-document interfaces. Finally, you'll learn about additional layout managers for organizing graphical user interfaces. We use several more Swing GUI components in later chapters as they're needed.

Swing is now considered a legacy technology. For GUIs, graphics and multimedia in new Java apps, you should use the features presented in this book's JavaFX chapters.

### *Java SE 8: Implementing Event Listeners with Lambdas*

Throughout this chapter, we use anonymous inner classes and nested classes to implement event handlers so that the examples can compile and execute with both Java SE 7 and Java SE 8. In many of the examples, you could implement the functional event-listener interfaces with Java SE 8 lambdas (as demonstrated in Section 17.9).

## 22.2 JSlider

**JSliders** enable a user to select from a range of integer values. Class `JSlider` inherits from `JComponent`. Figure 22.1 shows a horizontal `JSlider` with **tick marks** and the **thumb** that allows a user to select a value. `JSliders` can be customized to display *major tick marks*, *minor tick marks* and labels for the tick marks. They also support **snap-to ticks**, which cause the *thumb*, when positioned between two tick marks, to snap to the closest one.





**Fig. 22.1** | JSlider component with horizontal orientation.

Most Swing GUI components support mouse and keyboard interactions—e.g., if a JSlider has the focus (i.e., it's the currently selected GUI component in the user interface), pressing the left arrow key or right arrow key causes the JSlider's thumb to decrease or increase by 1, respectively. The down arrow key and up arrow key also cause the thumb to decrease or increase by 1 tick, respectively. The *PgDn* (page down) *key* and *PgUp* (page up) *key* cause the thumb to decrease or increase by **block increments** of one-tenth of the range of values, respectively. The *Home* *key* moves the thumb to the minimum value of the JSlider, and the *End* *key* moves the thumb to the maximum value of the JSlider.

JSliders have either a horizontal or a vertical orientation. For a horizontal JSlider, the minimum value is at the left end and the maximum is at the right end. For a vertical JSlider, the minimum value is at the bottom and the maximum is at the top. The minimum and maximum value positions on a JSlider can be reversed by invoking JSlider method **setInverted** with boolean argument true. The relative position of the thumb indicates the current value of the JSlider.

The program in Figs. 22.2–22.4 allows the user to size a circle drawn on a subclass of JPanel called OvalPanel (Fig. 22.2). The user specifies the circle's diameter with a horizontal JSlider. Class OvalPanel knows how to draw a circle on itself, using its own instance variable *diameter* to determine the diameter of the circle—the *diameter* is used as the width and height of the bounding box in which the circle is displayed. The *diameter* value is set when the user interacts with the JSlider. The event handler calls method *setDiameter* in class OvalPanel to set the diameter and calls *repaint* to draw the new circle. The *repaint* call results in a call to OvalPanel's *paintComponent* method.

```

1 // Fig. 22.2: OvalPanel.java
2 // A customized JPanel class.
3 import java.awt.Graphics;
4 import java.awt.Dimension;
5 import javax.swing.JPanel;
6
7 public class OvalPanel extends JPanel
8 {
9 private int diameter = 10; // default diameter
10
11 // draw an oval of the specified diameter
12 @Override
13 public void paintComponent(Graphics g)
14 {
15 super.paintComponent(g);
16 g.fillOval(10, 10, diameter, diameter);
17 }
18

```

**Fig. 22.2** | JPanel subclass for drawing circles of a specified diameter. (Part 1 of 2.)

---

```

19 // validate and set diameter, then repaint
20 public void setDiameter(int newDiameter)
21 {
22 // if diameter invalid, default to 10
23 diameter = (newDiameter >= 0 ? newDiameter : 10);
24 repaint(); // repaint panel
25 }
26
27 // used by layout manager to determine preferred size
28 public Dimension getPreferredSize()
29 {
30 return new Dimension(200, 200);
31 }
32
33 // used by layout manager to determine minimum size
34 public Dimension getMinimumSize()
35 {
36 return getPreferredSize();
37 }
38 } // end class OvalPanel

```

---

**Fig. 22.2** | JPanel subclass for drawing circles of a specified diameter. (Part 2 of 2.)

---

```

1 // Fig. 22.3: SliderFrame.java
2 // Using JSliders to size an oval.
3 import java.awt.BorderLayout;
4 import java.awt.Color;
5 import javax.swing.JFrame;
6 import javax.swing.JSlider;
7 import javax.swing.SwingConstants;
8 import javax.swing.event.ChangeListener;
9 import javax.swing.event.ChangeEvent;
10
11 public class SliderFrame extends JFrame
12 {
13 private final JSlider diameterJSlider; // slider to select diameter
14 private final OvalPanel myPanel; // panel to draw circle
15
16 // no-argument constructor
17 public SliderFrame()
18 {
19 super("Slider Demo");
20
21 myPanel = new OvalPanel(); // create panel to draw circle
22 myPanel.setBackground(Color.YELLOW);
23
24 // set up JSlider to control diameter value
25 diameterJSlider =
26 new JSlider(SwingConstants.HORIZONTAL, 0, 200, 10);
27 diameterJSlider.setMajorTickSpacing(10); // create tick every 10
28 diameterJSlider.setPaintTicks(true); // paint ticks on slider
29

```

---

**Fig. 22.3** | JSlider value used to determine the diameter of a circle. (Part 1 of 2.)

```

30 // register JSlider event listener
31 diameterJSlider.addChangeListener(
32 new ChangeListener() // anonymous inner class
33 {
34 // handle change in slider value
35 @Override
36 public void stateChanged(ChangeEvent e)
37 {
38 myPanel.setDiameter(diameterJSlider.getValue());
39 }
40 }
41);
42
43 add(diameterJSlider, BorderLayout.SOUTH);
44 add(myPanel, BorderLayout.CENTER);
45 }
46 } // end class SliderFrame

```

**Fig. 22.3** | JSlider value used to determine the diameter of a circle. (Part 2 of 2.)

```


1 // Fig. 22.4: SliderDemo.java
2 // Testing SliderFrame.
3 import javax.swing.JFrame;
4
5 public class SliderDemo
6 {
7 public static void main(String[] args)
8 {
9 SliderFrame sliderFrame = new SliderFrame();
10 sliderFrame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
11 sliderFrame.setSize(220, 270);
12 sliderFrame.setVisible(true);
13 }
14 } // end class SliderDemo

```

a) Initial GUI with default circle



b) GUI after the user moves the JSlider's thumb to the right



**Fig. 22.4** | Test class for SliderFrame.

Class `OvalPanel` (Fig. 22.2) contains a `paintComponent` method (lines 12–17) that draws a filled oval (a circle in this example), a `setDiameter` method (lines 20–25) that changes the circle's diameter and repaints the `OvalPanel`, a `getPreferredSize` method

(lines 28–31) that returns the preferred width and height of an `OvalPanel` and a `getMinimumSize` method (lines 34–37) that returns an `OvalPanel`'s minimum width and height. Methods `getPreferredSize` and `getMinimumSize` are used by some layout managers to determine the size of a component.

Class `SliderFrame` (Fig. 22.3) creates the `JSlider` that controls the diameter of the circle. Class `SliderFrame`'s constructor (lines 17–45) creates `OvalPanel` object `myPanel` (line 21) and sets its background color (line 22). Lines 25–26 create `JSlider` object `diameterJSlider` to control the diameter of the circle drawn on the `OvalPanel`. The `JSlider` constructor takes four arguments. The first specifies the orientation of `diameterJSlider`, which is `HORIZONTAL` (a constant in interface `SwingConstants`). The second and third arguments indicate the minimum and maximum integer values in the range of values for this `JSlider`. The last argument indicates that the initial value of the `JSlider` (i.e., where the thumb is displayed) should be 10.

Lines 27–28 customize the appearance of the `JSlider`. Method **`setMajorTickSpacing`** indicates that each major tick mark represents 10 values in the range of values supported by the `JSlider`. Method **`setPaintTicks`** with a `true` argument indicates that the tick marks should be displayed (they aren't displayed by default). For other methods that are used to customize a `JSlider`'s appearance, see the `JSlider` online documentation ([docs.oracle.com/javase/7/docs/api/javax/swing/JSlider.html](https://docs.oracle.com/javase/7/docs/api/javax/swing/JSlider.html)).

`JSliders` generate **`ChangeEvent`**s (package `javax.swing.event`) in response to user interactions. An object of a class that implements interface **`ChangeListener`** (package `javax.swing.event`) and declares method **`stateChanged`** can respond to `ChangeEvent`s. Lines 31–41 register a `ChangeListener` to handle `diameterJSlider`'s events. When method `stateChanged` (lines 35–39) is called in response to a user interaction, line 38 calls `myPanel`'s `setDiameter` method and passes the current value of the `JSlider` as an argument. `JSlider` method **`getValue`** returns the current thumb position.

## 22.3 Understanding Windows in Java

A `JFrame` is a **window** with a **title bar** and a **border**. Class `JFrame` is a subclass of `Frame` (package `java.awt`), which is a subclass of `Window` (package `java.awt`). As such, `JFrame` is one of the *heavyweight* Swing GUI components. When you display a window from a Java program, the window is provided by the local platform's windowing toolkit, and therefore the window will look like every other window displayed on that platform. When a Java application executes on a Macintosh and displays a window, the window's title bar and borders will look like those of other Macintosh applications. When a Java application executes on a Microsoft Windows system and displays a window, the window's title bar and borders will look like those of other Microsoft Windows applications. And when a Java application executes on a UNIX platform and displays a window, the window's title bar and borders will look like those of other UNIX applications on that platform.

### *Returning Window Resources to the System*

By default, when the user closes a `JFrame` window, it's hidden (i.e., removed from the screen), but you can control this with `JFrame` method **`setDefaultCloseOperation`**. Interface **`WindowConstants`** (package `javax.swing`), which class `JFrame` implements, declares three constants—`DISPOSE_ON_CLOSE`, `DO_NOTHING_ON_CLOSE` and `HIDE_ON_CLOSE` (the default)—for use with this method. Some platforms allow only a limited number of windows

to be displayed on the screen. Thus, a window is a valuable resource that should be given back to the system when it's no longer needed. Class `Window` (an indirect superclass of `JFrame`) declares method **dispose** for this purpose. When a `Window` is no longer needed in an application, you should explicitly dispose of it. This can be done by calling the `Window`'s `dispose` method or by calling method `setDefaultCloseOperation` with the argument `WindowConstants.DISPOSE_ON_CLOSE`. Terminating an application also returns window resources to the system. Using `DO_NOTHING_ON_CLOSE` indicates that the program will determine what to do when the user attempts to close the window. For example, the program might want to ask whether to save a file's changes before closing a window.

### *Displaying and Positioning Windows*

By default, a window is not displayed on the screen until the program invokes the window's `setVisible` method (inherited from class `java.awt.Component`) with a true argument. A window's size should be set with a call to method `setSize` (inherited from class `java.awt.Component`). The position of a window when it appears on the screen is specified with method **setLocation** (inherited from class `java.awt.Component`).

### *Window Events*

When the user manipulates the window, this action generates **window events**. Event listeners are registered for window events with `Window` method **addWindowListener**. The **WindowListener** interface provides seven window-event-handling methods—**windowActivated** (called when the user makes a window the active window), **windowClosed** (called after the window is closed), **windowClosing** (called when the user initiates closing of the window), **windowDeactivated** (called when the user makes another window the active window), **windowDeiconified** (called when the user restores a minimized window), **windowIconified** (called when the user minimizes a window) and **windowOpened** (called when a program first displays a window on the screen).

## 22.4 Using Menus with Frames

**Menus** are an integral part of GUIs. They allow the user to perform actions without unnecessarily cluttering a GUI with extra components. In Swing GUIs, menus can be attached only to objects of the classes that provide method **setJMenuBar**. Two such classes are `JFrame` and `JApplet`. The classes used to declare menus are `JMenuBar`, `JMenu`, `JMenuItem`, `JCheckBoxMenuItem` and class `JRadioButtonMenuItem`.



### **Look-and-Feel Observation 22.1**

*Menus simplify GUIs because components can be hidden within them. These components will be visible only when the user looks for them by selecting the menu.*

### *Overview of Several Menu-Related Components*

Class **JMenuBar** (a subclass of `JComponent`) contains the methods necessary to manage a **menu bar**, which is a container for menus. Class **JMenu** (a subclass of `javax.swing.JMenuItem`) contains the methods necessary for managing menus. Menus contain menu items and are added to menu bars or to other menus as submenus. When a menu is clicked, it expands to show its list of menu items.

Class **JMenuItem** (a subclass of `javax.swing.AbstractButton`) contains the methods necessary to manage **menu items**. A menu item is a GUI component inside a menu that, when selected, causes an action event. A menu item can be used to initiate an action, or it can be a **submenu** that provides more menu items from which the user can select. Submenus are useful for grouping related menu items in a menu.

Class **JCheckBoxMenuItem** (a subclass of `javax.swing.JMenuItem`) contains the methods necessary to manage menu items that can be toggled on or off. When a `JCheckBoxMenuItem` is selected, a check appears to the left of the menu item. When the `JCheckBoxMenuItem` is selected again, the check is removed.

Class **JRadioButtonMenuItem** (a subclass of `javax.swing.JMenuItem`) contains the methods necessary to manage menu items that can be toggled on or off like `JCheckBoxMenuItem`s. When multiple `JRadioButtonMenuItem`s are maintained as part of a `ButtonGroup`, only one item in the group can be selected at a given time. When a `JRadioButtonMenuItem` is selected, a filled circle appears to the left of the menu item. When another `JRadioButtonMenuItem` is selected, the filled circle of the previously selected menu item is removed.

### *Using Menus in an Application*

Figures 22.5–22.6 demonstrate various menu items and how to specify special characters called **mnemonics** that can provide quick access to a menu or menu item from the keyboard. Mnemonics can be used with all subclasses of `javax.swing.AbstractButton`. Class `MenuFrame` (Fig. 22.5) creates the GUI and handles the menu-item events. Most of the code in this application appears in the class's constructor (lines 34–151).

---

```

1 // Fig. 22.5: MenuFrame.java
2 // Demonstrating menus.
3 import java.awt.Color;
4 import java.awt.Font;
5 import java.awt.BorderLayout;
6 import java.awt.event.ActionListener;
7 import java.awt.event.ActionEvent;
8 import java.awt.event.ItemListener;
9 import java.awt.event.ItemEvent;
10 import javax.swing.JFrame;
11 import javax.swing.JRadioButtonMenuItem;
12 import javax.swing.JCheckBoxMenuItem;
13 import javax.swing.JOptionPane;
14 import javax.swing.JLabel;
15 import javax.swing.SwingConstants;
16 import javax.swing.ButtonGroup;
17 import javax.swing.JMenu;
18 import javax.swing.JMenuItem;
19 import javax.swing.JMenuBar;
20
21 public class MenuFrame extends JFrame
22 {
23 private final Color[] colorValues =
24 {Color.BLACK, Color.BLUE, Color.RED, Color.GREEN};

```

---

**Fig. 22.5** | JMenus and mnemonics. (Part I of 5.)

```

25 private final JRadioButtonMenuItem[] colorItems; // color menu items
26 private final JRadioButtonMenuItem[] fonts; // font menu items
27 private final JCheckBoxMenuItem[] styleItems; // font style menu items
28 private final JLabel displayJLabel; // displays sample text
29 private final ButtonGroup fontButtonGroup; // manages font menu items
30 private final ButtonGroup colorButtonGroup; // manages color menu items
31 private int style; // used to create style for font
32
33 // no-argument constructor set up GUI
34 public MenuFrame()
35 {
36 super("Using JMenus");
37
38 JMenu fileMenu = new JMenu("File"); // create file menu
39 fileMenu.setMnemonic('F'); // set mnemonic to F
40
41 // create About... menu item
42 JMenuItem aboutItem = new JMenuItem("About...");
43 aboutItem.setMnemonic('A'); // set mnemonic to A
44 fileMenu.add(aboutItem); // add about item to file menu
45 aboutItem.addActionListener(
46 new ActionListener() // anonymous inner class
47 {
48 // display message dialog when user selects About...
49 @Override
50 public void actionPerformed(ActionEvent event)
51 {
52 JOptionPane.showMessageDialog(MenuFrame.this,
53 "This is an example\nof using menus",
54 "About", JOptionPane.PLAIN_MESSAGE);
55 }
56 }
57);
58
59 JMenuItem exitItem = new JMenuItem("Exit"); // create exit item
60 exitItem.setMnemonic('x'); // set mnemonic to x
61 fileMenu.add(exitItem); // add exit item to file menu
62 exitItem.addActionListener(
63 new ActionListener() // anonymous inner class
64 {
65 // terminate application when user clicks exitItem
66 @Override
67 public void actionPerformed(ActionEvent event)
68 {
69 System.exit(0); // exit application
70 }
71 }
72);
73
74 JMenuBar bar = new JMenuBar(); // create menu bar
75 setJMenuBar(bar); // add menu bar to application
76 bar.add(fileMenu); // add file menu to menu bar
77

```

**Fig. 22.5** | JMenus and mnemonics. (Part 2 of 5.)

```

78 JMenu formatMenu = new JMenu("Format"); // create format menu
79 formatMenu.setMnemonic('r'); // set mnemonic to r
80
81 // array listing string colors
82 String[] colors = { "Black", "Blue", "Red", "Green" };
83
84 JMenu colorMenu = new JMenu("Color"); // create color menu
85 colorMenu.setMnemonic('C'); // set mnemonic to C
86
87 // create radio button menu items for colors
88 colorItems = new JRadioButtonMenuItem[colors.length];
89 colorButtonGroup = new ButtonGroup(); // manages colors
90 ItemHandler itemHandler = new ItemHandler(); // handler for colors
91
92 // create color radio button menu items
93 for (int count = 0; count < colors.length; count++)
94 {
95 colorItems[count] =
96 new JRadioButtonMenuItem(colors[count]); // create item
97 colorMenu.add(colorItems[count]); // add item to color menu
98 colorButtonGroup.add(colorItems[count]); // add to group
99 colorItems[count].addActionListener(itemHandler);
100 }
101
102 colorItems[0].setSelected(true); // select first Color item
103
104 formatMenu.add(colorMenu); // add color menu to format menu
105 formatMenu.addSeparator(); // add separator in menu
106
107 // array listing font names
108 String[] fontNames = { "Serif", "Monospaced", "SansSerif" };
109 JMenu fontMenu = new JMenu("Font"); // create font menu
110 fontMenu.setMnemonic('n'); // set mnemonic to n
111
112 // create radio button menu items for font names
113 fonts = new JRadioButtonMenuItem[fontNames.length];
114 fontButtonGroup = new ButtonGroup(); // manages font names
115
116 // create Font radio button menu items
117 for (int count = 0; count < fonts.length; count++)
118 {
119 fonts[count] = new JRadioButtonMenuItem(fontNames[count]);
120 fontMenu.add(fonts[count]); // add font to font menu
121 fontButtonGroup.add(fonts[count]); // add to button group
122 fonts[count].addActionListener(itemHandler); // add handler
123 }
124
125 fonts[0].setSelected(true); // select first Font menu item
126 fontMenu.addSeparator(); // add separator bar to font menu
127
128 String[] styleNames = { "Bold", "Italic" }; // names of styles
129 styleItems = new JCheckBoxMenuItem[styleNames.length];
130 StyleHandler styleHandler = new StyleHandler(); // style handler

```

**Fig. 22.5** | JMenus and mnemonics. (Part 3 of 5.)



```

131
132 // create style checkbox menu items
133 for (int count = 0; count < styleNames.length; count++)
134 {
135 styleItems[count] =
136 new JCheckBoxMenuItem(styleNames[count]); // for style
137 fontMenu.add(styleItems[count]); // add to font menu
138 styleItems[count].addItemListener(styleHandler); // handler
139 }
140
141 formatMenu.add(fontMenu); // add Font menu to Format menu
142 bar.add(formatMenu); // add Format menu to menu bar
143
144 // set up label to display text
145 displayJLabel = new JLabel("Sample Text", SwingConstants.CENTER);
146 displayJLabel.setForeground(colorValues[0]);
147 displayJLabel.setFont(new Font("Serif", Font.PLAIN, 72));
148
149 getContentPane().setBackground(Color.CYAN); // set background
150 add(displayJLabel, BorderLayout.CENTER); // add displayJLabel
151 } // end MenuFrame constructor
152
153 // inner class to handle action events from menu items
154 private class ItemHandler implements ActionListener
155 {
156 // process color and font selections
157 @Override
158 public void actionPerformed(ActionEvent event)
159 {
160 // process color selection
161 for (int count = 0; count < colorItems.length; count++)
162 {
163 if (colorItems[count].isSelected())
164 {
165 displayJLabel.setForeground(colorValues[count]);
166 break;
167 }
168 }
169
170 // process font selection
171 for (int count = 0; count < fonts.length; count++)
172 {
173 if (event.getSource() == fonts[count])
174 {
175 displayJLabel.setFont(
176 new Font(fonts[count].getText(), style, 72));
177 }
178 }
179
180 repaint(); // redraw application
181 }
182 } // end class ItemHandler
183

```

**Fig. 22.5** | JMenus and mnemonics. (Part 4 of 5.)

---

```

184 // inner class to handle item events from checkbox menu items
185 private class StyleHandler implements ItemListener
186 {
187 // process font style selections
188 @Override
189 public void itemStateChanged(ItemEvent e)
190 {
191 String name = displayJLabel.getFont().getName(); // current Font
192 Font font; // new font based on user selections
193
194 // determine which items are checked and create Font
195 if (styleItems[0].isSelected() &&
196 styleItems[1].isSelected())
197 font = new Font(name, Font.BOLD + Font.ITALIC, 72);
198 else if (styleItems[0].isSelected())
199 font = new Font(name, Font.BOLD, 72);
200 else if (styleItems[1].isSelected())
201 font = new Font(name, Font.ITALIC, 72);
202 else
203 font = new Font(name, Font.PLAIN, 72);
204
205 displayJLabel.setFont(font);
206 repaint(); // redraw application
207 }
208 }
209 } // end class MenuFrame

```

---


**Fig. 22.5** | JMenus and mnemonics. (Part 5 of 5.)

---

```


1 // Fig. 22.6: MenuTest.java
2 // Testing MenuFrame.
3 import javax.swing.JFrame;
4
5 public class MenuTest
6 {
7 public static void main(String[] args)
8 {
9 MenuFrame menuFrame = new MenuFrame();
10 menuFrame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
11 menuFrame.setSize(500, 200);
12 menuFrame.setVisible(true);
13 }
14 } // end class MenuTest

```



**Fig. 22.6** | Test class for MenuFrame. (Part 1 of 2.)

---



**Fig. 22.6** | Test class for MenuFrame. (Part 2 of 2.)

### Setting Up the File Menu

Lines 38–76 set up the **File** menu and attach it to the menu bar. The **File** menu contains an **About...** menu item that displays a message dialog when the menu item is selected and an **Exit** menu item that can be selected to terminate the application. Line 38 creates a `JMenu` and passes to the constructor the string "File" as the name of the menu. Line 39 uses `JMenu` method `setMnemonic` (inherited from class `AbstractButton`) to indicate that *F* is the mnemonic for this menu. Pressing the *Alt* key and the letter *F* opens the menu, just as clicking the menu name with the mouse would. In the GUI, the mnemonic character in the menu's name is displayed with an underline. (See the screen captures in Fig. 22.6.)



#### Look-and-Feel Observation 22.2

*Mnemonics provide quick access to menu commands and button commands through the keyboard.*



#### Look-and-Feel Observation 22.3

*Different mnemonics should be used for each button or menu item. Normally, the first letter in the label on the menu item or button is used as the mnemonic. If several buttons or menu items start with the same letter, choose the next most prominent letter in the name (e.g., *x* is commonly chosen for an **Exit** button or menu item). Mnemonics are case insensitive.*

Lines 42–43 create `JMenuItem` `aboutItem` with the text "About..." and set its mnemonic to the letter *A*. This menu item is added to `fileMenu` at line 44 with `JMenu` method `add`. To access the **About...** menu item through the keyboard, press the *Alt* key and letter *F* to open the **File** menu, then press *A* to select the **About...** menu item. Lines 46–56 create an `ActionListener` to process `aboutItem`'s action event. Lines 52–54 display a message dialog box. In most prior uses of `showMessageDialog`, the first argument was `null`. The purpose of the first argument is to specify the **parent window** that helps determine where the dialog box will be displayed. If the parent window is specified as `null`, the dialog box appears in the center of the screen. Otherwise, it appears centered over the specified parent window. In this example, the program specifies the parent window with `MenuFrame.this`—the `this` reference of the `MenuFrame` object. When using the `this` reference in an inner class, specifying `this` by itself refers to the inner-class object. To reference the outer-class object's `this` reference, qualify `this` with the outer-class name and a dot (`.`).

Recall that dialog boxes are typically modal. A modal dialog box does not allow any other window in the application to be accessed until the dialog box is dismissed. The dialogs displayed with class `JOptionPane` are modal dialogs. Class `JDialog` can be used to create your own modal or nonmodal dialogs.

Lines 59–72 create menu item `exitItem`, set its mnemonic to `x`, add it to `fileMenu` and register an `ActionListener` that terminates the program when the user selects `exitItem`. Lines 74–76 create the `JMenuBar`, attach it to the window with `JFrame` method `setMenuBar` and use `JMenuBar` method **add** to attach the `fileMenu` to the `JMenuBar`.



#### Look-and-Feel Observation 22.4

*Menus appear left to right in the order they're added to a `JMenuBar`.*

#### Setting Up the Format Menu

Lines 78–79 create the `formatMenu` and set its mnemonic to `r`. `F` is not used because that's the **File** menu's mnemonic. Lines 84–85 create `colorMenu` (this will be a submenu in **Format**) and set its mnemonic to `C`. Line 88 creates `JRadioButtonMenuItem` array `colorItems`, which refers to the menu items in `colorMenu`. Line 89 creates `ButtonGroup` `colorButtonGroup`, which ensures that only one of the **Color** submenu items is selected at a time. Line 90 creates an instance of inner class `ItemHandler` (declared at lines 154–181) that responds to selections from the **Color** and **Font** submenus (discussed shortly). The loop at lines 93–100 creates each `JRadioButtonMenuItem` in array `colorItems`, adds each menu item to `colorMenu` and to `colorButtonGroup` and registers the `ActionListener` for each menu item.

Line 102 invokes `AbstractButton` method **setSelected** to select the first element in array `colorItems`. Line 104 adds `colorMenu` as a submenu of `formatMenu`. Line 105 invokes `JMenu` method **addSeparator** to add a horizontal separator line to the menu.



#### Look-and-Feel Observation 22.5

*A submenu is created by adding a menu as a menu item in another menu.*



#### Look-and-Feel Observation 22.6

*Separators can be added to a menu to group menu items logically.*



#### Look-and-Feel Observation 22.7

*Any `JComponent` can be added to a `JMenu` or to a `JMenuBar`.*

Lines 108–126 create the **Font** submenu and several `JRadioButtonMenuItem`s and select the first element of `JRadioButtonMenuItem` array `fonts`. Line 129 creates a `JCheckBoxMenuItem` array to represent the menu items for specifying bold and italic styles for the fonts. Line 130 creates an instance of inner class `StyleHandler` (declared at lines 185–208) to respond to the `JCheckBoxMenuItem` events. The `for` statement at lines 133–139 creates each `JCheckBoxMenuItem`, adds it to `fontMenu` and registers its `ItemListener`. Line 141 adds `fontMenu` as a submenu of `formatMenu`. Line 142 adds the `formatMenu` to `bar` (the menu bar).

#### Creating the Rest of the GUI and Defining the Event Handlers

Lines 145–147 create a `JLabel` for which the **Format** menu items control the font, font color and font style. The initial foreground color is set to the first element of array `colorValues` (`Color.BLACK`) by invoking `JComponent` method **setForeground**. The initial font is set to `Serif` with `PLAIN` style and 72-point size. Line 149 sets the background color of

the window's content pane to cyan, and line 150 attaches the JLabel to the CENTER of the content pane's BorderLayout.

ItemHandler method actionPerformed (lines 157–181) uses two for statements to determine which font or color menu item generated the event and sets the font or color of the JLabel displayLabel, respectively. The if condition at line 163 uses AbstractButton method **isSelected** to determine the selected JRadioButtonMenuItem. The if condition at line 173 invokes the event object's getSource method to get a reference to the JRadioButtonMenuItem that generated the event. Line 176 invokes AbstractButton method getText to obtain the name of the font from the menu item.

StyleHandler method itemStateChanged (lines 188–207) is called if the user selects a JCheckBoxMenuItem in the fontMenu. Lines 195–203 determine which JCheckBoxMenuItem are selected and use their combined state to determine the new font style.

## 22.5 JPopupMenu

Applications often provide **context-sensitive pop-up menus** for several reasons—they can be convenient, there might not be a menu bar and the options they display can be specific to individual on-screen components. In Swing, such menus are created with class **JPopupMenu** (a subclass of JComponent). These menus provide options that are specific to the component for which the **popup trigger event** occurred—on most systems, when the user presses and releases the right mouse button.



### Look-and-Feel Observation 22.8

*The pop-up trigger event is platform specific. On most platforms that use a mouse with multiple buttons, the pop-up trigger event occurs when the user clicks the right mouse button on a component that supports a pop-up menu.*

The application in Figs. 22.7–22.8 creates a JPopupMenu that allows the user to select one of three colors and change the background color of the window. When the user clicks the right mouse button on the PopupFrame window's background, a JPopupMenu containing colors appears. If the user clicks a JRadioButtonMenuItem for a color, ItemHandler method actionPerformed changes the background color of the window's content pane.

Line 25 of the PopupFrame constructor (Fig. 22.7, lines 21–70) creates an instance of class ItemHandler (declared in lines 73–89) that will process the item events from the menu items in the pop-up menu. Line 29 creates the JPopupMenu. The for statement (lines 33–39) creates a JRadioButtonMenuItem object (line 35), adds it to popupMenu (line 36), adds it to ButtonGroup colorGroup (line 37) to maintain one selected JRadioButtonMenuItem at a time and registers its ActionListener (line 38). Line 41 sets the initial background to white by invoking method setBackground.

---

```

1 // Fig. 22.7: PopupFrame.java
2 // Demonstrating JPopupMenu.
3 import java.awt.Color;
4 import java.awt.event.MouseAdapter;
5 import java.awt.event.MouseEvent;
6 import java.awt.event.ActionListener;

```

---

**Fig. 22.7** | JPopupMenu for selecting colors. (Part I of 3.)

---

```

7 import java.awt.event.ActionEvent;
8 import javax.swing.JFrame;
9 import javax.swing.JRadioButtonMenuItem;
10 import javax.swing.JPopupMenu;
11 import javax.swing.ButtonGroup;
12
13 public class PopupFrame extends JFrame
14 {
15 private final JRadioButtonMenuItem[] items; // holds items for colors
16 private final Color[] colorValues =
17 { Color.BLUE, Color.YELLOW, Color.RED }; // colors to be used
18 private final JPopupMenu popupMenu; // allows user to select color
19
20 // no-argument constructor sets up GUI
21 public PopupFrame()
22 {
23 super("Using JPopupMenu");
24
25 ItemHandler handler = new ItemHandler(); // handler for menu items
26 String[] colors = { "Blue", "Yellow", "Red" };
27
28 ButtonGroup colorGroup = new ButtonGroup(); // manages color items
29 popupMenu = new JPopupMenu(); // create pop-up menu
30 items = new JRadioButtonMenuItem[colors.length];
31
32 // construct menu item, add to pop-up menu, enable event handling
33 for (int count = 0; count < items.length; count++)
34 {
35 items[count] = new JRadioButtonMenuItem(colors[count]);
36 popupMenu.add(items[count]); // add item to pop-up menu
37 colorGroup.add(items[count]); // add item to button group
38 items[count].addActionListener(handler); // add handler
39 }
40
41 setBackground(Color.WHITE);
42
43 // declare a MouseListener for the window to display pop-up menu
44 addMouseListener(
45 new MouseAdapter() // anonymous inner class
46 {
47 // handle mouse press event
48 @Override
49 public void mousePressed(MouseEvent event)
50 {
51 checkForTriggerEvent(event);
52 }
53
54 // handle mouse release event
55 @Override
56 public void mouseReleased(MouseEvent event)
57 {
58 checkForTriggerEvent(event);
59 }

```

---

**Fig. 22.7** | JPopupMenu for selecting colors. (Part 2 of 3.)

---

```

60
61 // determine whether event should trigger pop-up menu
62 private void checkForTriggerEvent(MouseEvent event)
63 {
64 if (event.isPopupTrigger())
65 popupMenu.show(
66 event.getComponent(), event.getX(), event.getY());
67 }
68 }
69);
70 } // end PopupFrame constructor
71
72 // private inner class to handle menu item events
73 private class ItemHandler implements ActionListener
74 {
75 // process menu item selections
76 @Override
77 public void actionPerformed(ActionEvent event)
78 {
79 // determine which menu item was selected
80 for (int i = 0; i < items.length; i++)
81 {
82 if (event.getSource() == items[i])
83 {
84 getContentPane().setBackground(colorValues[i]);
85 return;
86 }
87 }
88 }
89 } // end private inner class ItemHandler
90 } // end class PopupFrame

```

---

**Fig. 22.7** | JPopupMenu for selecting colors. (Part 3 of 3.)

---


```

1 // Fig. 22.8: PopupTest.java
2 // Testing PopupFrame.
3 import javax.swing.JFrame;
4
5 public class PopupTest
6 {
7 public static void main(String[] args)
8 {
9 PopupFrame popupFrame = new PopupFrame();
10 popupFrame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
11 popupFrame.setSize(300, 200);
12 popupFrame.setVisible(true);
13 }
14 } // end class PopupTest

```

---

**Fig. 22.8** | Test class for PopupFrame. (Part 1 of 2.)



**Fig. 22.8** | Test class for PopupFrame. (Part 2 of 2.)

Lines 44–69 register a `MouseListener` to handle the mouse events of the application window. Methods `mousePressed` (lines 48–52) and `mouseReleased` (lines 55–59) check for the pop-up trigger event. Each method calls private utility method `checkForTriggerEvent` (lines 62–67) to determine whether the pop-up trigger event occurred. If it did, `MouseEvent` method `isPopupTrigger` returns true, and `JPopupMenu` method `show` displays the `JPopupMenu`. The first argument to method `show` specifies the **origin component**, whose position helps determine where the `JPopupMenu` will appear on the screen. The last two arguments are the *x-y* coordinates (measured from the origin component’s upper-left corner) at which the `JPopupMenu` is to appear.



### Look-and-Feel Observation 22.9

*Displaying a `JPopupMenu` for the pop-up trigger event of multiple GUI components requires registering mouse-event handlers for each of those GUI components.*

When the user selects a menu item from the pop-up menu, class `ItemHandler`’s method `actionPerformed` (lines 76–88) determines which `JRadioButtonMenuItem` the user selected and sets the background color of the window’s content pane.

## 22.6 Pluggable Look-and-Feel

A program that uses Java’s AWT GUI components (package `java.awt`) takes on the look-and-feel of the platform on which the program executes. A Java application running on a Mac OS X looks like other Mac OS X applications, one running on Microsoft Windows looks like other Windows applications, and one running on a Linux platform looks like other applications on that Linux platform. This is sometimes desirable, because it allows users of the application on each platform to use GUI components with which they’re already familiar. However, it also introduces interesting portability issues.



### Portability Tip 22.1

*GUI components often look different on different platforms (fonts, font sizes, component borders, etc.) and might require different amounts of space to display. This could change their layout and alignments.*



### Portability Tip 22.2

*GUI components on different platforms have might different default functionality—e.g., not all platforms allow a button with the focus to be “pressed” with the space bar.*



Swing's lightweight GUI components eliminate many of these issues by providing uniform functionality across platforms and by defining a uniform cross-platform look-and-feel. Section 12.2 introduced the *Nimbus* look-and-feel. Earlier versions of Java used the **metal look-and-feel**, which is still the default. Swing also provides the flexibility to customize the look-and-feel to appear as a Microsoft Windows-style look-and-feel (only on Windows systems), a Motif-style (UNIX) look-and-feel (across all platforms) or a Macintosh look-and-feel (only on Mac systems).

Figures 22.9–22.10 demonstrate a way to change the look-and-feel of a Swing GUI. It creates several GUI components, so you can see the change in their look-and-feel at the same time. The output windows show the Metal, Nimbus, CDE/Motif, Windows and Windows Classic look-and-feels that are available on Windows systems. The installed look-and-feels will vary by platform.

We've covered the GUI components and event-handling concepts in this example previously, so we focus here on the mechanism for changing the look-and-feel. Class **UIManager** (package `javax.swing`) contains nested class **LookAndFeelInfo** (a public static class) that maintains information about a look-and-feel. Line 20 (Fig. 22.9) declares an array of type `UIManager.LookAndFeelInfo` (note the syntax used to identify the static inner class `LookAndFeelInfo`). Line 34 uses `UIManager` static method **getInstalledLookAndFeels** to get the array of `UIManager.LookAndFeelInfo` objects that describe each look-and-feel available on your system.



### Performance Tip 22.1

*Each look-and-feel is represented by a Java class. `UIManager` method `getInstalledLookAndFeels` does not load each class. Rather, it provides the names of the available look-and-feel classes so that a choice can be made (presumably once at program start-up). This reduces the overhead of having to load all the look-and-feel classes even if the program will not use some of them.*

```

1 // Fig. 22.9: LookAndFeelFrame.java
2 // Changing the look-and-feel.
3 import java.awt.GridLayout;
4 import java.awt.BorderLayout;
5 import java.awt.event.ItemListener;
6 import java.awt.event.ItemEvent;
7 import javax.swing.JFrame;
8 import javax.swing.UIManager;
9 import javax.swing.JRadioButton;
10 import javax.swing.ButtonGroup;
11 import javax.swing.JButton;
12 import javax.swing.JLabel;
13 import javax.swing.JComboBox;
14 import javax.swing.JPanel;
15 import javax.swing.SwingConstants;
16 import javax.swing.SwingUtilities;
17
18 public class LookAndFeelFrame extends JFrame
19 {

```

**Fig. 22.9** | Look-and-feel of a Swing-based GUI. (Part 1 of 3.)

---

```

20 private final UIManager.LookAndFeelInfo[] looks;
21 private final String[] lookNames; // look-and-feel names
22 private final JRadioButton[] radio; // for selecting look-and-feel
23 private final ButtonGroup group; // group for radio buttons
24 private final JButton button; // displays look of button
25 private final JLabel label; // displays look of label
26 private final JComboBox<String> comboBox; // displays look of combo box
27
28 // set up GUI
29 public LookAndFeelFrame()
30 {
31 super("Look and Feel Demo");
32
33 // get installed look-and-feel information
34 looks = UIManager.getInstalledLookAndFeels();
35 lookNames = new String[looks.length];
36
37 // get names of installed look-and-feels
38 for (int i = 0; i < looks.length; i++)
39 lookNames[i] = looks[i].getName();
40
41 JPanel northPanel = new JPanel();
42 northPanel.setLayout(new GridLayout(3, 1, 0, 5));
43
44 label = new JLabel("This is a " + lookNames[0] + " look-and-feel",
45 SwingConstants.CENTER);
46 northPanel.add(label);
47
48 button = new JButton("JButton");
49 northPanel.add(button);
50
51 comboBox = new JComboBox<String>(lookNames);
52 northPanel.add(comboBox);
53
54 // create array for radio buttons
55 radio = new JRadioButton[looks.length];
56
57 JPanel southPanel = new JPanel();
58
59 // use a GridLayout with 3 buttons in each row
60 int rows = (int) Math.ceil(radio.length / 3.0);
61 southPanel.setLayout(new GridLayout(rows, 3));
62
63 group = new ButtonGroup(); // button group for look-and-feels
64 ItemHandler handler = new ItemHandler(); // look-and-feel handler
65
66 for (int count = 0; count < radio.length; count++)
67 {
68 radio[count] = new JRadioButton(lookNames[count]);
69 radio[count].addItemListener(handler); // add handler
70 group.add(radio[count]); // add radio button to group
71 southPanel.add(radio[count]); // add radio button to panel
72 }

```

---

**Fig. 22.9** | Look-and-feel of a Swing-based GUI. (Part 2 of 3.)

---

```

73
74 add(northPanel, BorderLayout.NORTH); // add north panel
75 add(southPanel, BorderLayout.SOUTH); // add south panel
76
77 radio[0].setSelected(true); // set default selection
78 } // end LookAndFeelFrame constructor
79
80 // use UIManager to change look-and-feel of GUI
81 private void changeTheLookAndFeel(int value)
82 {
83 try // change look-and-feel
84 {
85 // set look-and-feel for this application
86 UIManager.setLookAndFeel(looks[value].getClassName());
87
88 // update components in this application
89 SwingUtilities.updateComponentTreeUI(this);
90 }
91 catch (Exception exception)
92 {
93 exception.printStackTrace();
94 }
95 }
96
97 // private inner class to handle radio button events
98 private class ItemHandler implements ItemListener
99 {
100 // process user's look-and-feel selection
101 @Override
102 public void itemStateChanged(ItemEvent event)
103 {
104 for (int count = 0; count < radio.length; count++)
105 {
106 if (radio[count].isSelected())
107 {
108 label.setText(String.format(
109 "This is a %s look-and-feel", lookNames[count]));
110 comboBox.setSelectedIndex(count); // set combobox index
111 changeTheLookAndFeel(count); // change look-and-feel
112 }
113 }
114 }
115 } // end private inner class ItemHandler
116 } // end class LookAndFeelFrame

```

---

**Fig. 22.9** | Look-and-feel of a Swing-based GUI. (Part 3 of 3.)

---

```

1 // Fig. 22.10: LookAndFeelDemo.java
2 // Changing the look-and-feel.
3 import javax.swing.JFrame;
4

```

---

**Fig. 22.10** | Test class for LookAndFeelFrame. (Part 1 of 2.)

```

5 public class LookAndFeelDemo
6 {
7 public static void main(String[] args)
8 {
9 LookAndFeelFrame lookAndFeelFrame = new LookAndFeelFrame();
10 lookAndFeelFrame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
11 lookAndFeelFrame.setSize(400, 220);
12 lookAndFeelFrame.setVisible(true);
13 }
14 } // end class LookAndFeelDemo

```



**Fig. 22.10** | Test class for LookAndFeelFrame. (Part 2 of 2.)

Our utility method `changeTheLookAndFeel` (lines 81–95) is called by the event handler for the `JRadioButtons` at the bottom of the user interface. The event handler (declared in private inner class `ItemHandler` at lines 98–115) passes an integer representing the element in array `looks` that should be used to change the look-and-feel. Line 86 invokes static method `setLookAndFeel` of `UIManager` to change the look-and-feel. The `getClassName` method of class `UIManager.LookAndFeelInfo` determines the name of the look-and-feel class that corresponds to the `UIManager.LookAndFeelInfo` object. If the look-and-feel is not already loaded, it will be loaded as part of the call to `setLookAndFeel`. Line 89 invokes the static method `updateComponentTreeUI` of class `SwingUtilities` (package `javax.swing`) to change the look-and-feel of every GUI component attached to its argument (this instance of our application class `LookAndFeelFrame`) to the new look-and-feel.

## 22.7 JDesktopPane and JInternalFrame

A **multiple-document interface (MDI)** is a main window (called the **parent window**) containing other windows (called **child windows**) and is often used to manage several open documents. For example, many e-mail programs allow you to have several windows open at the same time, so you can compose or read multiple e-mail messages simultaneously. Similarly, many word processors allow the user to open multiple documents in separate windows within a main window, making it possible to switch between them without having to close one to open another. The application in Figs. 22.11–22.12 demonstrates Swing's **JDesktopPane** and **JInternalFrame** classes for implementing multiple-document interfaces.

---

```

1 // Fig. 22.11: DesktopFrame.java
2 // Demonstrating JDesktopPane.
3 import java.awt.BorderLayout;
4 import java.awt.Dimension;
5 import java.awt.Graphics;
6 import java.awt.event.ActionListener;
7 import java.awt.event.ActionEvent;
8 import java.util.Random;
9 import javax.swing.JFrame;
10 import javax.swing.JDesktopPane;
11 import javax.swing.JMenuBar;
12 import javax.swing.JMenu;
13 import javax.swing.JMenuItem;
14 import javax.swing.JInternalFrame;
15 import javax.swing.JPanel;
16 import javax.swing.ImageIcon;
17
18 public class DesktopFrame extends JFrame
19 {
20 private final JDesktopPane theDesktop;
21
22 // set up GUI
23 public DesktopFrame()
24 {
25 super("Using a JDesktopPane");
26
27 JMenuBar bar = new JMenuBar();
28 JMenu addMenu = new JMenu("Add");
29 JMenuItem newFrame = new JMenuItem("Internal Frame");
30
31 addMenu.add(newFrame); // add new frame item to Add menu
32 bar.add(addMenu); // add Add menu to menu bar
33 setJMenuBar(bar); // set menu bar for this application
34
35 theDesktop = new JDesktopPane();
36 add(theDesktop); // add desktop pane to frame
37
38 // set up listener for newFrame menu item
39 newFrame.addActionListener(

```

---

**Fig. 22.11** | Multiple-document interface. (Part 1 of 2.)

---

```

40 new ActionListener() // anonymous inner class
41 {
42 // display new internal window
43 @Override
44 public void actionPerformed(ActionEvent event)
45 {
46 // create internal frame
47 JInternalFrame frame = new JInternalFrame(
48 "Internal Frame", true, true, true, true);
49
50 MyJPanel panel = new MyJPanel();
51 frame.add(panel, BorderLayout.CENTER);
52 frame.pack(); // set internal frame to size of contents
53
54 theDesktop.add(frame); // attach internal frame
55 frame.setVisible(true); // show internal frame
56 }
57 }
58);
59 } // end DesktopFrame constructor
60 } // end class DesktopFrame
61
62 // class to display an ImageIcon on a panel
63 class MyJPanel extends JPanel
64 {
65 private static final SecureRandom generator = new SecureRandom();
66 private final ImageIcon picture; // image to be displayed
67 private final static String[] images = { "yellowflowers.png",
68 "purpleflowers.png", "redflowers.png", "redflowers2.png",
69 "lavenderflowers.png" };
70
71 // load image
72 public MyJPanel()
73 {
74 int randomNumber = generator.nextInt(images.length);
75 picture = new ImageIcon(images[randomNumber]); // set icon
76 }
77
78 // display ImageIcon on panel
79 @Override
80 public void paintComponent(Graphics g)
81 {
82 super.paintComponent(g);
83 picture.paintIcon(this, g, 0, 0); // display icon
84 }
85
86 // return image dimensions
87 public Dimension getPreferredSize()
88 {
89 return new Dimension(picture.getIconWidth(),
90 picture.getIconHeight());
91 }
92 } // end class MyJPanel

```

---

**Fig. 22.11** | Multiple-document interface. (Part 2 of 2.)

Lines 27–33 create a `JMenuBar`, a `JMenu` and a `JMenuItem`, add the `JMenuItem` to the `JMenu`, add the `JMenu` to the `JMenuBar` and set the `JMenuBar` for the application window. When the user selects the `JMenuItem` `newFrame`, the application creates and displays a new `JInternalFrame` object containing an image.

Line 35 assigns `JDesktopPane` (package `javax.swing`) variable `theDesktop` a new `JDesktopPane` object that will be used to manage the `JInternalFrame` child windows. Line 36 adds the `JDesktopPane` to the `JFrame`. By default, the `JDesktopPane` is added to the center of the content pane's `BorderLayout`, so the `JDesktopPane` expands to fill the entire application window.


---

```

1 // Fig. 22.12: DesktopTest.java
2 // Demonstrating JDesktopPane.
3 import javax.swing.JFrame;
4
5 public class DesktopTest
6 {
7 public static void main(String[] args)
8 {
9 DesktopFrame desktopFrame = new DesktopFrame();
10 desktopFrame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
11 desktopFrame.setSize(600, 480);
12 desktopFrame.setVisible(true);
13 }
14 } // end class DesktopTest


```

---




---

**Fig. 22.12** | Test class for `DesktopFrame`. (Part 1 of 2.)



**Fig. 22.12** | Test class for DeskTopFrame. (Part 2 of 2.)

Lines 39–58 register an `ActionListener` to handle the event when the user selects the `newFrame` menu item. When the event occurs, method `actionPerformed` (lines 43–56) creates a `JInternalFrame` object in lines 47–48. The `JInternalFrame` constructor used here takes five arguments—a `String` for the title bar of the internal window, a `boolean` indicating whether the internal frame can be resized by the user, a `boolean` indicating whether the internal frame can be closed by the user, a `boolean` indicating whether the internal frame can be maximized by the user and a `boolean` indicating whether the internal frame can be minimized by the user. For each of the `boolean` arguments, a `true` value indicates that the operation should be allowed (as is the case here).

As with `JFrames` and `JApplets`, a `JInternalFrame` has a content pane to which GUI components can be attached. Line 50 creates an instance of our class `MyJPanel` (declared at lines 63–91) that is added to the `JInternalFrame` at line 51.

Line 52 uses `JInternalFrame` method `pack` to set the size of the child window. Method `pack` uses the preferred sizes of the components to determine the window's size. Class `MyJPanel` declares method `getPreferredSize` (lines 87–91) to specify the panel's preferred size for use by the `pack` method. Line 54 adds the `JInternalFrame` to the `JDesktopPane`, and line 55 displays the `JInternalFrame`.

Classes `JInternalFrame` and `JDesktopPane` provide many methods for managing child windows. See the `JInternalFrame` and `JDesktopPane` online API documentation for complete lists of these methods:

[docs.oracle.com/javase/7/docs/api/javax/swing/JInternalFrame.html](https://docs.oracle.com/javase/7/docs/api/javax/swing/JInternalFrame.html)  
[docs.oracle.com/javase/7/docs/api/javax/swing/JDesktopPane.html](https://docs.oracle.com/javase/7/docs/api/javax/swing/JDesktopPane.html)

## 22.8 JTabbedPane

A `JTabbedPane` arranges GUI components into layers, of which only one is visible at a time. Users access each layer via a tab—similar to folders in a file cabinet. When the user clicks a tab, the appropriate layer is displayed. The tabs appear at the top by default but also can be positioned at the left, right or bottom of the `JTabbedPane`. Any component can



be placed on a tab. If the component is a container, such as a panel, it can use any layout manager to lay out several components on the tab. Class `JTabbedPane` is a subclass of `JComponent`. The application in Figs. 22.13–22.14 creates one tabbed pane with three tabs. Each tab displays one of the `JPanels`—`pane11`, `pane12` or `pane13`.

---

```

1 // Fig. 22.13: JTabbedPaneFrame.java
2 // Demonstrating JTabbedPane.
3 import java.awt.BorderLayout;
4 import java.awt.Color;
5 import javax.swing.JFrame;
6 import javax.swing.JTabbedPane;
7 import javax.swing.JLabel;
8 import javax.swing.JPanel;
9 import javax.swing.JButton;
10 import javax.swing.SwingConstants;
11
12 public class JTabbedPaneFrame extends JFrame
13 {
14 // set up GUI
15 public JTabbedPaneFrame()
16 {
17 super("JTabbedPane Demo ");
18
19 JTabbedPane tabbedPane = new JTabbedPane(); // create JTabbedPane
20
21 // set up pane11 and add it to JTabbedPane
22 JLabel label11 = new JLabel("panel one", SwingConstants.CENTER);
23 JPanel pane11 = new JPanel();
24 pane11.add(label11);
25 tabbedPane.addTab("Tab One", null, pane11, "First Panel");
26
27 // set up pane12 and add it to JTabbedPane
28 JLabel label12 = new JLabel("panel two", SwingConstants.CENTER);
29 JPanel pane12 = new JPanel();
30 pane12.setBackground(Color.YELLOW);
31 pane12.add(label12);
32 tabbedPane.addTab("Tab Two", null, pane12, "Second Panel");
33
34 // set up pane13 and add it to JTabbedPane
35 JLabel label13 = new JLabel("panel three");
36 JPanel pane13 = new JPanel();
37 pane13.setLayout(new BorderLayout());
38 pane13.add(new JButton("North"), BorderLayout.NORTH);
39 pane13.add(new JButton("West"), BorderLayout.WEST);
40 pane13.add(new JButton("East"), BorderLayout.EAST);
41 pane13.add(new JButton("South"), BorderLayout.SOUTH);
42 pane13.add(label13, BorderLayout.CENTER);
43 tabbedPane.addTab("Tab Three", null, pane13, "Third Panel");
44
45 add(tabbedPane); // add JTabbedPane to frame
46 }
47 } // end class JTabbedPaneFrame

```

---

**Fig. 22.13** | `JTabbedPane` used to organize GUI components.

---

```

1 // Fig. 22.14: JTabbedPaneDemo.java
2 // Demonstrating JTabbedPane.
3 import javax.swing.JFrame;
4
5 public class JTabbedPaneDemo
6 {
7 public static void main(String[] args)
8 {
9 JTabbedPaneFrame tabbedPaneFrame = new JTabbedPaneFrame();
10 tabbedPaneFrame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
11 tabbedPaneFrame.setSize(250, 200);
12 tabbedPaneFrame.setVisible(true);
13 }
14 } // end class JTabbedPaneDemo

```




---

**Fig. 22.14** | Test class for JTabbedPaneFrame.

The constructor (lines 15–46) builds the GUI. Line 19 creates an empty JTabbedPane with default settings—that is, tabs across the top. If the tabs do not fit on one line, they’ll wrap to form additional lines of tabs. Next the constructor creates the JPanels pane11, pane12 and pane13 and their GUI components. As we set up each panel, we add it to tabbedPane, using JTabbedPane method **addTab** with four arguments. The first argument is a String that specifies the title of the tab. The second argument is an Icon reference that specifies an icon to display on the tab. If the Icon is a null reference, no image is displayed. The third argument is a Component reference that represents the GUI component to display when the user clicks the tab. The last argument is a String that specifies the tool tip for the tab. For example, line 25 adds JPanel pane11 to tabbedPane with title “Tab One” and the tool tip “First Panel”. JPanels pane12 and pane13 are added to tabbedPane at lines 32 and 43. To view a tab, click it with the mouse or use the arrow keys to cycle through the tabs.

## 22.9 BorderLayout Layout Manager

In Chapter 12, we introduced three layout managers—FlowLayout, BorderLayout and GridLayout. This section and Section 22.10 present two additional layout managers (summarized in Fig. 22.15). We discuss them in the examples that follow.

| Layout manager | Description                                                                                                                                                                                                                       |
|----------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| BoxLayout      | Allows GUI components to be arranged left-to-right or top-to-bottom in a container. Class Box declares a container that uses BorderLayout and provides static methods to create a Box with a horizontal or vertical BorderLayout. |
| GridBagLayout  | Similar to GridLayout, but the components can vary in size and can be added in any order.                                                                                                                                         |

**Fig. 22.15** | Additional layout managers.

The BorderLayout layout manager (in package `javax.swing`) arranges GUI components horizontally along a container's *x*-axis or vertically along its *y*-axis. The application in Figs. 22.16–22.17 demonstrate BorderLayout and the container class `Box` that uses BorderLayout as its default layout manager.

```

1 // Fig. 22.16: BorderLayoutFrame.java
2 // Demonstrating BorderLayout.
3 import java.awt.Dimension;
4 import javax.swing.JFrame;
5 import javax.swing.Box;
6 import javax.swing.JButton;
7 import javax.swing.BoxLayout;
8 import javax.swing.JPanel;
9 import javax.swing.JTabbedPane;
10
11 public class BorderLayoutFrame extends JFrame
12 {
13 // set up GUI
14 public BorderLayoutFrame()
15 {
16 super("Demonstrating BorderLayout");
17
18 // create Box containers with BorderLayout
19 Box horizontal1 = Box.createHorizontalBox();
20 Box vertical1 = Box.createVerticalBox();
21 Box horizontal2 = Box.createHorizontalBox();
22 Box vertical2 = Box.createVerticalBox();
23
24 final int SIZE = 3; // number of buttons on each Box
25
26 // add buttons to Box horizontal1
27 for (int count = 0; count < SIZE; count++)
28 horizontal1.add(new JButton("Button " + count));
29
30 // create strut and add buttons to Box vertical1
31 for (int count = 0; count < SIZE; count++)
32 {
33 vertical1.add(Box.createVerticalStrut(25));
34 vertical1.add(new JButton("Button " + count));
35 }

```

**Fig. 22.16** | BorderLayout layout manager. (Part 1 of 2.)

---

```

36
37 // create horizontal glue and add buttons to Box horizontal2
38 for (int count = 0; count < SIZE; count++)
39 {
40 horizontal2.add(Box.createHorizontalGlue());
41 horizontal2.add(new JButton("Button " + count));
42 }
43
44 // create rigid area and add buttons to Box vertical2
45 for (int count = 0; count < SIZE; count++)
46 {
47 vertical2.add(Box.createRigidArea(new Dimension(12, 8)));
48 vertical2.add(new JButton("Button " + count));
49 }
50
51 // create vertical glue and add buttons to panel
52 JPanel panel = new JPanel();
53 panel.setLayout(new BoxLayout(panel, BoxLayout.Y_AXIS));
54
55 for (int count = 0; count < SIZE; count++)
56 {
57 panel.add(Box.createGlue());
58 panel.add(new JButton("Button " + count));
59 }
60
61 // create a JTabbedPane
62 JTabbedPane tabs = new JTabbedPane(
63 JTabbedPane.TOP, JTabbedPane.SCROLL_TAB_LAYOUT);
64
65 // place each container on tabbed pane
66 tabs.addTab("Horizontal Box", horizontal1);
67 tabs.addTab("Vertical Box with Struts", vertical1);
68 tabs.addTab("Horizontal Box with Glue", horizontal2);
69 tabs.addTab("Vertical Box with Rigid Areas", vertical2);
70 tabs.addTab("Vertical Box with Glue", panel);
71
72 add(tabs); // place tabbed pane on frame
73 } // end BoxLayoutFrame constructor
74 } // end class BoxLayoutFrame

```

---

**Fig. 22.16** | BoxLayout layout manager. (Part 2 of 2.)

---

```

1 // Fig. 22.17: BoxLayoutDemo.java
2 // Demonstrating BoxLayout.
3 import javax.swing.JFrame;
4
5 public class BoxLayoutDemo
6 {
7 public static void main(String[] args)
8 {
9 BoxLayoutFrame boxLayoutFrame = new BoxLayoutFrame();

```

---

**Fig. 22.17** | Test class for BoxLayoutFrame. (Part 1 of 2.)

```

10 boxLayoutFrame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
11 boxLayoutFrame.setSize(400, 220);
12 boxLayoutFrame.setVisible(true);
13 }
14 } // end class BorderLayoutDemo

```



**Fig. 22.17** | Test class for BorderLayoutFrame. (Part 2 of 2.)

### Creating Box Containers

Lines 19–22 create Box containers. References `horizontal1` and `horizontal2` are initialized with static Box method `createHorizontalBox`, which returns a Box container with a horizontal BorderLayout in which GUI components are arranged left-to-right. Variables `vertical1` and `vertical2` are initialized with static Box method `createVerticalBox`, which returns references to Box containers with a vertical BorderLayout in which GUI components are arranged top-to-bottom.

### Struts

The loop at lines 27–28 adds three JButtons to `horizontal1`. The for statement at lines 31–35 adds three JButtons to `vertical1`. Before adding each button, line 33 adds a **vertical strut** to the container with static Box method `createVerticalStrut`. A vertical strut is an invisible GUI component that has a fixed pixel height and is used to guarantee a fixed amount of space between GUI components. The `int` argument to method `createVerticalStrut` determines the height of the strut in pixels. When the container is resized, the distance between GUI components separated by struts does not change. Class Box also declares method `createHorizontalStrut` for horizontal BorderLayouts.

*Glue*

The `for` statement at lines 38–42 adds three `JButtons` to `horizontal2`. Before adding each button, line 40 adds **horizontal glue** to the container with static `Box` method **`createHorizontalGlue`**. Horizontal glue is an invisible GUI component that can be used between fixed-size GUI components to occupy additional space. Normally, extra space appears to the right of the last horizontal GUI component or below the last vertical one in a `BoxLayout`. Glue allows the extra space to be placed between GUI components. When the container is resized, components separated by glue components remain the same size, but the glue stretches or contracts to occupy the space between them. Class `Box` also declares method **`createVerticalGlue`** for vertical `BoxLayouts`.

*Rigid Areas*

The `for` statement at lines 45–49 adds three `JButtons` to `vertical2`. Before each button is added, line 47 adds a **rigid area** to the container with static `Box` method **`createRigidArea`**. A rigid area is an invisible GUI component that always has a fixed pixel width and height. The argument to method `createRigidArea` is a `Dimension` object that specifies the area's width and height.

*Setting a BoxLayout for a Container*

Lines 52–53 create a `JPanel` object and set its layout to a `BoxLayout` in the conventional manner, using `Container` method `setLayout`. The `BoxLayout` constructor receives a reference to the container for which it controls the layout and a constant indicating whether the layout is horizontal (**`BoxLayout.X_AXIS`**) or vertical (**`BoxLayout.Y_AXIS`**).

*Adding Glue and JButtons*

The `for` statement at lines 55–59 adds three `JButtons` to `panel`. Before adding each button, line 57 adds a glue component to the container with static `Box` method **`createGlue`**. This component expands or contracts based on the size of the `Box`.

*Creating the JTabbedPane*

Lines 62–63 create a `JTabbedPane` to display the five containers in this program. The argument **`JTabbedPane.TOP`** sent to the constructor indicates that the tabs should appear at the top of the `JTabbedPane`. The argument **`JTabbedPane.SCROLL_TAB_LAYOUT`** specifies that the tabs should wrap to a new line if there are too many to fit on one line.

*Attaching the Box Containers and JPanel to the JTabbedPane*


The `Box` containers and the `JPanel` are attached to the `JTabbedPane` at lines 66–70. Try executing the application. When the window appears, resize the window to see how the glue components, strut components and rigid area affect the layout on each tab.

## 22.10 GridBagLayout Layout Manager

One of the most powerful predefined layout managers is **`GridBagLayout`** (in package `java.awt`). This layout is similar to `GridLayout` in that it arranges components in a grid, but it's more flexible. The components can vary in size (i.e., they can occupy multiple rows and columns) and can be added in any order.

The first step in using `GridBagLayout` is determining the appearance of the GUI. For this step you need only a piece of paper. Draw the GUI, then draw a grid over it, dividing

the components into rows and columns. The initial row and column numbers should be 0, so that the GridBagLayout layout manager can use the row and column numbers to properly place the components in the grid. Figure 22.18 demonstrates drawing the lines for the rows and columns over a GUI.



**Fig. 22.18** | Designing a GUI that will use GridBagLayout.

### **GridBagConstraints**

A **GridBagConstraints** object describes how a component is placed in a GridBagLayout. Several GridBagConstraints fields are summarized in Fig. 22.19.

| Field      | Description                                                                                                                                                       |
|------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| anchor     | Specifies the relative position (NORTH, NORTHEAST, EAST, SOUTHEAST, SOUTH, SOUTHWEST, WEST, NORTHWEST, CENTER) of the component in an area that it does not fill. |
| fill       | Resizes the component in the specified direction (NONE, HORIZONTAL, VERTICAL, BOTH) when the display area is larger than the component.                           |
| gridx      | The column in which the component will be placed.                                                                                                                 |
| gridy      | The row in which the component will be placed.                                                                                                                    |
| gridwidth  | The number of columns the component occupies.                                                                                                                     |
| gridheight | The number of rows the component occupies.                                                                                                                        |
| weightx    | The amount of extra space to allocate horizontally. The grid slot can become wider when extra space is available.                                                 |
| weighty    | The amount of extra space to allocate vertically. The grid slot can become taller when extra space is available.                                                  |

**Fig. 22.19** | GridBagConstraints fields.

### **GridBagConstraints Field anchor**

GridBagConstraints field **anchor** specifies the relative position of the component in an area that it does not fill. The variable anchor is assigned one of the following GridBagConstraints constants: **NORTH**, **NORTHEAST**, **EAST**, **SOUTHEAST**, **SOUTH**, **SOUTHWEST**, **WEST**, **NORTHWEST** or **CENTER**. The default value is **CENTER**.

***GridBagConstraints Field fill***

`GridBagConstraints` field `fill` defines how the component grows if the area in which it can be displayed is larger than the component. The variable `fill` is assigned one of the following `GridBagConstraints` constants: **NONE**, **VERTICAL**, **HORIZONTAL** or **BOTH**. The default value is **NONE**, which indicates that the component will not grow in either direction. **VERTICAL** indicates that it will grow vertically. **HORIZONTAL** indicates that it will grow horizontally. **BOTH** indicates that it will grow in both directions.

***GridBagConstraints Fields gridx and gridy***

Variables `gridx` and `gridy` specify where the upper-left corner of the component is placed in the grid. Variable `gridx` corresponds to the column, and variable `gridy` corresponds to the row. In Fig. 22.18, the `JComboBox` (displaying “Iron”) has a `gridx` value of 1 and a `gridy` value of 2.

***GridBagConstraints Field gridwidth***

Variable `gridwidth` specifies the number of columns a component occupies. The `JComboBox` occupies two columns. Variable `gridheight` specifies the number of rows a component occupies. The `JTextArea` on the left side of Fig. 22.18 occupies three rows.

***GridBagConstraints Field weightx***

Variable `weightx` specifies how to distribute extra horizontal space to grid slots in a `GridBagLayout` when the container is resized. A zero value indicates that the grid slot does not grow horizontally on its own. However, if the component spans a column containing a component with nonzero `weightx` value, the component with zero `weightx` value will grow horizontally in the same proportion as the other component(s) in that column. This is because each component must be maintained in the same row and column in which it was originally placed.

***GridBagConstraints Field weighty***

Variable `weighty` specifies how to distribute extra vertical space to grid slots in a `GridBagLayout` when the container is resized. A zero value indicates that the grid slot does not grow vertically on its own. However, if the component spans a row containing a component with nonzero `weighty` value, the component with zero `weighty` value grows vertically in the same proportion as the other component(s) in the same row.

***Effects of weightx and weighty***


In Fig. 22.18, the effects of `weighty` and `weightx` cannot easily be seen until the container is resized and additional space becomes available. Components with larger weight values occupy more of the additional space than those with smaller weight values.

Components should be given nonzero positive weight values—otherwise they’ll “huddle” together in the middle of the container. Figure 22.20 shows the GUI of Fig. 22.18 with all weights set to zero.

***Demonstrating GridBagLayout***

The application in Figs. 22.21–22.22 uses the `GridBagLayout` layout manager to arrange the components of the GUI in Fig. 22.18. The application does nothing except demonstrate how to use `GridBagLayout`.





**Fig. 22.20** | GridBagLayout with the weights set to zero.

```

1 // Fig. 22.21: GridBagFrame.java
2 // Demonstrating GridBagLayout.
3 import java.awt.GridBagLayout;
4 import java.awt.GridBagConstraints;
5 import java.awt.Component;
6 import javax.swing.JFrame;
7 import javax.swing.JTextArea;
8 import javax.swing.JTextField;
9 import javax.swing.JButton;
10 import javax.swing.JComboBox;
11
12 public class GridBagFrame extends JFrame
13 {
14 private final GridBagLayout layout; // layout of this frame
15 private final GridBagConstraints constraints; // layout's constraints
16
17 // set up GUI
18 public GridBagFrame()
19 {
20 super("GridBagLayout");
21 layout = new GridBagLayout();
22 setLayout(layout); // set frame layout
23 constraints = new GridBagConstraints(); // instantiate constraints
24
25 // create GUI components
26 JTextArea textArea1 = new JTextArea("TextArea1", 5, 10);
27 JTextArea textArea2 = new JTextArea("TextArea2", 2, 2);
28
29 String[] names = { "Iron", "Steel", "Brass" };
30 JComboBox<String> comboBox = new JComboBox<String>(names);
31
32 JTextField textField = new JTextField("TextField");
33 JButton button1 = new JButton("Button 1");
34 JButton button2 = new JButton("Button 2");
35 JButton button3 = new JButton("Button 3");
36
37 // weightx and weighty for textArea1 are both 0: the default
38 // anchor for all components is CENTER: the default
39 constraints.fill = GridBagConstraints.BOTH;
40 addComponent(textArea1, 0, 0, 1, 3);

```

**Fig. 22.21** | GridBagLayout layout manager. (Part I of 2.)

---

```

41
42 // weightx and weighty for button1 are both 0: the default
43 constraints.fill = GridBagConstraints.HORIZONTAL;
44 addComponent(button1, 0, 1, 2, 1);
45
46 // weightx and weighty for comboBox are both 0: the default
47 // fill is HORIZONTAL
48 addComponent(comboBox, 2, 1, 2, 1);
49
50 // button2
51 constraints.weightx = 1000; // can grow wider
52 constraints.weighty = 1; // can grow taller
53 constraints.fill = GridBagConstraints.BOTH;
54 addComponent(button2, 1, 1, 1, 1);
55
56 // fill is BOTH for button3
57 constraints.weightx = 0;
58 constraints.weighty = 0;
59 addComponent(button3, 1, 2, 1, 1);
60
61 // weightx and weighty for textField are both 0, fill is BOTH
62 addComponent(textField, 3, 0, 2, 1);
63
64 // weightx and weighty for textArea2 are both 0, fill is BOTH
65 addComponent(textArea2, 3, 2, 1, 1);
66 } // end GridBagFrame constructor
67
68 // method to set constraints on
69 private void addComponent(Component component,
70 int row, int column, int width, int height)
71 {
72 constraints.gridx = column;
73 constraints.gridy = row;
74 constraints.gridwidth = width;
75 constraints.gridheight = height;
76 layout.setConstraints(component, constraints); // set constraints
77 add(component); // add component
78 }
79 } // end class GridBagFrame

```

---

**Fig. 22.21** | GridBagLayout layout manager. (Part 2 of 2.)

---

```

1 // Fig. 22.22: GridBagDemo.java
2 // Demonstrating GridBagLayout.
3 import javax.swing.JFrame;
4
5 public class GridBagDemo
6 {
7 public static void main(String[] args)
8 {
9 GridBagFrame gridBagFrame = new GridBagFrame();

```


---

**Fig. 22.22** | Test class for GridBagFrame. (Part 1 of 2.)

```

10 gridBagFrame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
11 gridBagFrame.setSize(300, 150);
12 gridBagFrame.setVisible(true);
13 }
14 } // end class GridBagDemo

```



**Fig. 22.22** | Test class for GridBagFrame. (Part 2 of 2.)

### GUI Overview

The GUI contains three `JButtons`, two `JTextAreas`, a `JComboBox` and a `JTextField`. The layout manager is `GridBagLayout`. Lines 21–22 create the `GridBagLayout` object and set the layout manager for the `JFrame` to `layout`. Line 23 creates the `GridBagConstraints` object used to determine the location and size of each component in the grid. Lines 26–35 create each GUI component that will be added to the content pane.

### *JTextArea textArea1*

Lines 39–40 configure `JTextArea textArea1` and add it to the content pane. The values for `weightx` and `weighty` values are not specified in constraints, so each has the value zero by default. Thus, the `JTextArea` will not resize itself even if space is available. However, it spans multiple rows, so the vertical size is subject to the `weighty` values of `JButtons button2` and `button3`. When either button is resized vertically based on its `weighty` value, the `JTextArea` is also resized.

Line 39 sets variable `fill` in constraints to `GridBagConstraints.BOTH`, causing the `JTextArea` to always fill its entire allocated area in the grid. An anchor value is not specified in constraints, so the default `CENTER` is used. We do not use variable anchor in this

application, so all the components will use the default. Line 40 calls our utility method `addComponent` (declared at lines 69–78). The `JTextArea` object, the row, the column, the number of columns to span and the number of rows to span are passed as arguments.

### ***JButton button1***

`JButton button1` is the next component added (lines 43–44). By default, the `weightx` and `weighty` values are still zero. The `fill` variable is set to `HORIZONTAL`—the component will always fill its area in the horizontal direction. The vertical direction is not filled. The `weighty` value is zero, so the button will become taller only if another component in the same row has a nonzero `weighty` value. `JButton button1` is located at row 0, column 1. One row and two columns are occupied.

### ***JComboBox comboBox***

`JComboBox comboBox` is the next component added (line 48). By default, the `weightx` and `weighty` values are zero, and the `fill` variable is set to `HORIZONTAL`. The `JComboBox` button will grow only in the horizontal direction. The `weightx`, `weighty` and `fill` variables retain the values set in constraints until they're changed. The `JComboBox` button is placed at row 2, column 1. One row and two columns are occupied.

### ***JButton button2***

`JButton button2` is the next component added (lines 51–54). It's given a `weightx` value of 1000 and a `weighty` value of 1. The area occupied by the button is capable of growing in the vertical and horizontal directions. The `fill` variable is set to `BOTH`, which specifies that the button will always fill the entire area. When the window is resized, `button2` will grow. The button is placed at row 1, column 1. One row and one column are occupied.

### ***JButton button3***

`JButton button3` is added next (lines 57–59). Both the `weightx` value and `weighty` value are set to zero, and the value of `fill` is `BOTH`. `JButton button3` will grow if the window is resized—it's affected by the weight values of `button2`. The `weightx` value for `button2` is much larger than that for `button3`. When resizing occurs, `button2` will occupy a larger percentage of the new space. The button is placed at row 1, column 2. One row and one column are occupied.

### ***JTextField textField and JTextArea textArea2***

Both the `JTextField textField` (line 62) and `JTextArea textArea2` (line 65) have a `weightx` value of 0 and a `weighty` value of 0. The value of `fill` is `BOTH`. The `JTextField` is placed at row 3, column 0, and the `JTextArea` at row 3, column 2. The `JTextField` occupies one row and two columns, the `JTextArea` one row and one column.

### ***Method addComponent***

Method `addComponent`'s parameters are a `Component` reference component and integers row, column, width and height. Lines 72–73 set the `GridBagConstraints` variables `gridx` and `gridy`. The `gridx` variable is assigned the column in which the `Component` will be placed, and the `gridy` value is assigned the row in which the `Component` will be placed. Lines 74–75 set the `GridBagConstraints` variables `gridwidth` and `gridheight`. The `gridwidth` variable specifies the number of columns the `Component` will span in the grid,

and the `gridheight` variable specifies the number of rows the Component will span in the grid. Line 76 sets the `GridBagConstraints` for a component in the `GridBagLayout`. Method `setConstraints` of class `GridBagLayout` takes a Component argument and a `GridBagConstraints` argument. Line 77 adds the component to the `JFrame`.

When you execute this application, try resizing the window to see how the constraints for each GUI component affect its position and size in the window.

### ***GridBagConstraints Constants RELATIVE and REMAINDER***

Instead of `gridx` and `gridy`, a variation of `GridBagLayout` uses `GridBagConstraints` constants **RELATIVE** and **REMAINDER**. **RELATIVE** specifies that the next-to-last component in a particular row should be placed to the right of the previous component in the row. **REMAINDER** specifies that a component is the last component in a row. Any component that is not the second-to-last or last component on a row must specify values for `GridBagConstraints` variables `gridwidth` and `gridheight`. The application in Figs. 22.23–22.24 arranges components in `GridBagLayout`, using these constants.

---

```

1 // Fig. 22.23: GridBagFrame2.java
2 // Demonstrating GridBagLayout constants.
3 import java.awt.GridBagLayout;
4 import java.awt.GridBagConstraints;
5 import java.awt.Component;
6 import javax.swing.JFrame;
7 import javax.swing.JComboBox;
8 import javax.swing.JTextField;
9 import javax.swing.JList;
10 import javax.swing.JButton;
11
12 public class GridBagFrame2 extends JFrame
13 {
14 private final GridBagLayout layout; // layout of this frame
15 private final GridBagConstraints constraints; // layout's constraints
16
17 // set up GUI
18 public GridBagFrame2()
19 {
20 super("GridBagLayout");
21 layout = new GridBagLayout();
22 setLayout(layout); // set frame layout
23 constraints = new GridBagConstraints(); // instantiate constraints
24
25 // create GUI components
26 String[] metals = { "Copper", "Aluminum", "Silver" };
27 JComboBox comboBox = new JComboBox(metals);
28
29 JTextField textField = new JTextField("TextField");
30
31 String[] fonts = { "Serif", "Monospaced" };
32 JList list = new JList(fonts);
33

```

---

**Fig. 22.23** | `GridBagConstraints` constants **RELATIVE** and **REMAINDER**. (Part I of 2.)

```

34 String[] names = { "zero", "one", "two", "three", "four" };
35 JButton[] buttons = new JButton[names.length];
36
37 for (int count = 0; count < buttons.length; count++)
38 buttons[count] = new JButton(names[count]);
39
40 // define GUI component constraints for textField
41 constraints.weightx = 1;
42 constraints.weighty = 1;
43 constraints.fill = GridBagConstraints.BOTH;
44 constraints.gridwidth = GridBagConstraints.REMAINDER;
45 addComponent(textField);
46
47 // buttons[0] -- weightx and weighty are 1: fill is BOTH
48 constraints.gridwidth = 1;
49 addComponent(buttons[0]);
50
51 // buttons[1] -- weightx and weighty are 1: fill is BOTH
52 constraints.gridwidth = GridBagConstraints.RELATIVE;
53 addComponent(buttons[1]);
54
55 // buttons[2] -- weightx and weighty are 1: fill is BOTH
56 constraints.gridwidth = GridBagConstraints.REMAINDER;
57 addComponent(buttons[2]);
58
59 // comboBox -- weightx is 1: fill is BOTH
60 constraints.weighty = 0;
61 constraints.gridwidth = GridBagConstraints.REMAINDER;
62 addComponent(comboBox);
63
64 // buttons[3] -- weightx is 1: fill is BOTH
65 constraints.weighty = 1;
66 constraints.gridwidth = GridBagConstraints.REMAINDER;
67 addComponent(buttons[3]);
68
69 // buttons[4] -- weightx and weighty are 1: fill is BOTH
70 constraints.gridwidth = GridBagConstraints.RELATIVE;
71 addComponent(buttons[4]);
72
73 // list -- weightx and weighty are 1: fill is BOTH
74 constraints.gridwidth = GridBagConstraints.REMAINDER;
75 addComponent(list);
76 } // end GridBagFrame2 constructor
77
78 // add a component to the container
79 private void addComponent(Component component)
80 {
81 layout.setConstraints(component, constraints);
82 add(component); // add component
83 }
84 } // end class GridBagFrame2

```


**Fig. 22.23** | GridBagConstraints constants RELATIVE and REMAINDER. (Part 2 of 2.)

---

```

1 // Fig. 22.24: GridBagDemo2.java
2 // Demonstrating GridBagLayout constants.
3 import javax.swing.JFrame;
4
5 public class GridBagDemo2
6 {
7 public static void main(String[] args)
8 {
9 GridBagFrame2 gridBagFrame = new GridBagFrame2();
10 gridBagFrame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
11 gridBagFrame.setSize(300, 200);
12 gridBagFrame.setVisible(true);
13 }
14 } // end class GridBagDemo2

```




---

**Fig. 22.24** | Test class for GridBagDemo2.

### *Setting the JFrame's Layout to a GridBagLayout*

Lines 21–22 create a GridBagLayout and use it to set the JFrame's layout manager. The components that are placed in GridBagLayout are created in lines 27–38—they are a JComboBox, a JTextField, a JList and five JButtons.

### *Configuring the JTextField*

The JTextField is added first (lines 41–45). The weightx and weighty values are set to 1. The fill variable is set to BOTH. Line 44 specifies that the JTextField is the last component on the line. The JTextField is added to the content pane with a call to our utility method addComponent (declared at lines 79–83). Method addComponent takes a Component argument and uses GridBagLayout method setConstraints to set the constraints for the Component. Method add attaches the component to the content pane.

### *Configuring JButton buttons[0]*

JButton buttons[0] (lines 48–49) has weightx and weighty values of 1. The fill variable is BOTH. Because buttons[0] is not one of the last two components on the row, it's given a gridwidth of 1 and so will occupy one column. The JButton is added to the content pane with a call to utility method addComponent.

***Configuring JButton buttons[1]***

JButton buttons[1] (lines 52–53) has `weightx` and `weighty` values of 1. The `fill` variable is `BOTH`. Line 52 specifies that the JButton is to be placed relative to the previous component. The Button is added to the JFrame with a call to `addComponent`.

***Configuring JButton buttons[2]***

JButton buttons[2] (lines 56–57) has `weightx` and `weighty` values of 1. The `fill` variable is `BOTH`. This JButton is the last component on the line, so `REMAINDER` is used. The JButton is added to the content pane with a call to `addComponent`.

***Configuring JComboBox***

The JComboBox (lines 60–62) has a `weightx` of 1 and a `weighty` of 0. The JComboBox will not grow vertically. The JComboBox is the only component on the line, so `REMAINDER` is used. The JComboBox is added to the content pane with a call to `addComponent`.

***Configuring JButton buttons[3]***

JButton buttons[3] (lines 65–67) has `weightx` and `weighty` values of 1. The `fill` variable is `BOTH`. This JButton is the only component on the line, so `REMAINDER` is used. The JButton is added to the content pane with a call to `addComponent`.

***Configuring JButton buttons[4]***

JButton buttons[4] (lines 70–71) has `weightx` and `weighty` values of 1. The `fill` variable is `BOTH`. This JButton is the next-to-last component on the line, so `RELATIVE` is used. The JButton is added to the content pane with a call to `addComponent`.

***Configuring JList***

The JList (lines 74–75) has `weightx` and `weighty` values of 1. The `fill` variable is `BOTH`. The JList is added to the content pane with a call to `addComponent`.

## 22.11 Wrap-Up

This chapter completes our introduction to GUIs. In this chapter, we discussed additional GUI topics, such as menus, sliders, pop-up menus, multiple-document interfaces, tabbed panes and Java's pluggable look-and-feel. All these components can be added to existing applications to make them easier to use and understand. We also presented additional layout managers for organizing and sizing GUI components. In the next chapter, you'll learn about multithreading, which allows you to specify that an application should perform multiple tasks at once.

## Summary

### Section 22.2 JSlider

- JSIiders (p. 904) enable you to select from a range of integer values. They can display major and minor tick marks, and labels for the tick marks (p. 904). They also support snap-to ticks (p. 904)—positioning the thumb (p. 904) between two tick marks snaps it to the closest tick mark.



- JSliders have either horizontal or vertical orientation. For a horizontal JSlider, the minimum value is at the extreme left and the maximum value at the extreme right. For a vertical JSlider, the minimum value is at the extreme bottom and the maximum value at the extreme top. The position of the thumb indicates the current value of the JSlider. Method `getValue` (p. 908) of class JSlider returns the current thumb position.
- JSlider method `setMajorTickSpacing()` sets the spacing for tick marks on a JSlider. Method `setPaintTicks` (p. 908) with a true argument indicates that the tick marks should be displayed.
- JSliders generate `ChangeEvent`s when the user interacts with a JSlider. A `ChangeListener` (p. 908) declares method `stateChanged` (p. 908) that can respond to `ChangeEvent`s.

### *Section 22.3 Understanding Windows in Java*

- A window's (p. 908) events can be handled by a `WindowListener` (p. 909), which provides seven window-event-handling methods—`windowActivated`, `windowClosed`, `windowClosing`, `windowDeactivated`, `windowDeiconified`, `windowIconified` and `windowOpened`.

### *Section 22.4 Using Menus with Frames*

- Menus neatly organize commands in a GUI. In Swing GUIs, menus can be attached only to objects of classes with method `setJMenuBar` (p. 909).
- A `JMenuBar` (p. 909) is a container for menus. A `JMenuItem` appears in a menu. A `JMenu` (p. 909) contains menu items and can be added to a `JMenuBar` or to other `JMenus` as submenus.
- When a menu is clicked, it expands to show its list of menu items.
- When a `JCheckBoxMenuItem` (p. 910) is selected, a check appears to the left of the menu item. When the `JCheckBoxMenuItem` is selected again, the check is removed.
- In a `ButtonGroup`, only one `JRadioButtonMenuItem` (p. 910) can be selected at a time.
- `AbstractButton` method `setMnemonic` (p. 915) specifies the mnemonic (p. 910) for a button. Mnemonic characters are normally displayed with an underline.
- A modal dialog box (p. 915) does not allow access to any other window in the application until the dialog is dismissed. The dialogs displayed with class `JOptionPane` are modal dialogs. Class `JDialog` (p. 915) can be used to create your own modal or nonmodal dialogs.

### *Section 22.5 JPopupMenu*

- Context-sensitive pop-up menus (p. 917) are created with class `JPopupMenu`. The pop-up trigger event occurs normally when the user presses and releases the right mouse button. `MouseEvent` method `isPopupTrigger` (p. 920) returns true if the pop-up trigger event occurred.
- `JPopupMenu` method `show` (p. 920) displays a `JPopupMenu`. The first argument specifies the origin component, which helps determine where the `JPopupMenu` will appear. The last two arguments are the coordinates from the origin component's upper-left corner, at which the `JPopupMenu` appears.

### *Section 22.6 Pluggable Look-and-Feel*

- Class `UIManager.LookAndFeelInfo` (p. 921) maintains information about a look-and-feel.
- `UIManager` (p. 921) static method `getInstalledLookAndFeels` (p. 921) returns an array of `UIManager.LookAndFeelInfo` objects that describe the available look-and-feels.
- `UIManager` static method `setLookAndFeel` (p. 924) changes the look-and-feel. `SwingUtilities` (p. 924) static method `updateComponentTreeUI` (p. 924) changes the look-and-feel of every component attached to its `Component` argument to the new look-and-feel.

**Section 22.7 JDesktopPane and JInternalFrame**

- Many of today's applications use a multiple-document interface (MDI; p. 925) to manage several open documents that are being processed in parallel. Swing's JDesktopPane (p. 925) and JInternalFrame (p. 925) classes provide support for creating multiple-document interfaces.

**Section 22.8 JTabbedPane**

- A JTabbedPane (p. 928) arranges GUI components into layers, of which only one is visible at a time. Users access each layer by clicking its tab.

**Section 22.9 BorderLayout Layout Manager**

- BoxLayout (p. 939) arranges GUI components left-to-right or top-to-bottom in a container.
- Class Box represents a container with BoxLayout as its default layout manager and provides static methods to create a Box with a horizontal or vertical BoxLayout.

**Section 22.10 GridBagLayout Layout Manager**

- GridBagLayout (p. 934) is similar to GridLayout, but each component size can vary.
- A GridBagConstraints object (p. 935) specifies how a component is placed in a GridBagLayout.

**Self-Review Exercises**

- 22.1** Fill in the blanks in each of the following statements:
- The \_\_\_\_\_ class is used to create a menu object.
  - The \_\_\_\_\_ method of class JMenu places a separator bar in a menu.
  - JSlider events are handled by the \_\_\_\_\_ method of interface \_\_\_\_\_.
  - The GridBagConstraints instance variable \_\_\_\_\_ is set to CENTER by default.
- 22.2** State whether each of the following is *true* or *false*. If *false*, explain why.
- When the programmer creates a JFrame, a minimum of one menu must be created and added to the JFrame.
  - The variable fill belongs to the GridBagLayout class.
  - Drawing on a GUI component is performed with respect to the (0, 0) upper-left corner coordinate of the component.
  - The default layout for a Box is BoxLayout.
- 22.3** Find the error(s) in each of the following and explain how to correct the error(s).
- JMenubar b;
  - mySlider = JSlider(1000, 222, 100, 450);
  - gbc.fill = GridBagConstraints.NORTHWEST; // set fill
  - // override to paint on a customized Swing component
 

```
public void paintcomponent(Graphics g)
{
 g.drawString("HELLO", 50, 50);
}
```
  - // create a JFrame and display it
 

```
JFrame f = new JFrame("A Window");
f.setVisible(true);
```

**Answers to Self-Review Exercises**

- 22.1** a) JMenu. b) addSeparator. c) stateChanged, ChangeListener. d) anchor.
- 22.2** a) False. A JFrame does not require any menus.

- b) False. The variable `fill` belongs to the `GridBagConstraints` class.
  - c) True.
  - d) True.
- 22.3**
- a) `JMenuBar` should be `JMenuBar`.
  - b) The first argument to the constructor should be `SwingConstants.HORIZONTAL` or `SwingConstants.VERTICAL`, and the keyword `new` must be used after the `=` operator. Also, the minimum value should be less than the maximum and the initial value should be in range.
  - c) The constant should be either `BOTH`, `HORIZONTAL`, `VERTICAL` or `NONE`.
  - d) `paintComponent` should be `paintComponent`, and the method should call `super.paintComponent(g)` as its first statement.
  - e) The `JFrame`'s `setSize` method must also be called to establish the size of the window.

## Exercises

- 22.4** (*Fill-in-the-Blanks*) Fill in the blanks in each of the following statements:
- a) A `JMenuItem` that is a `JMenu` is called a(n) \_\_\_\_\_.
  - b) Method \_\_\_\_\_ attaches a `JMenuBar` to a `JFrame`.
  - c) Container class \_\_\_\_\_ has a default `BoxLayout`.
  - d) A(n) \_\_\_\_\_ manages a set of child windows declared with class `JInternalFrame`.
- 22.5** (*True or False*) State whether each of the following is *true* or *false*. If *false*, explain why.
- a) Menus require a `JMenuBar` object so they can be attached to a `JFrame`.
  - b) `BoxLayout` is the default layout manager for a `JFrame`.
  - c) `JApplets` can contain menus.
- 22.6** (*Find the Code Errors*) Find the error(s) in each of the following. Explain how to correct the error(s).
- a) `x.add(new JMenuItem("Submenu Color")); // create submenu`
  - b) `container.setLayout(new GridbagLayout());`
- 22.7** (*Display a Circle and Its Attributes*) Write a program that displays a circle of random size and calculates and displays the area, radius, diameter and circumference. Use the following equations:  $diameter = 2 \times radius$ ,  $area = \pi \times radius^2$ ,  $circumference = 2 \times \pi \times radius$ . Use the constant `Math.PI` for pi ( $\pi$ ). All drawing should be done on a subclass of `JPanel`, and the results of the calculations should be displayed in a read-only `JTextArea`.
- 22.8** (*Using a JSlider*) Enhance the program in Exercise 22.7 by allowing the user to alter the radius with a `JSlider`. The program should work for all radii in the range from 100 to 200. As the radius changes, the diameter, area and circumference should be updated and displayed. The initial radius should be 150. Use the equations from Exercise 22.7. All drawing should be done on a subclass of `JPanel`, and the results of the calculations should be displayed in a read-only `JTextArea`.
- 22.9** (*Varying weightx and weighty*) Explore the effects of varying the `weightx` and `weighty` values of the program in Fig. 22.21. What happens when a slot has a nonzero weight but is not allowed to fill the whole area (i.e., the `fill` value is not `BOTH`)?
- 22.10** (*Synchronizing a JSlider and a JTextField*) Write a program that uses the `paintComponent` method to draw the current value of a `JSlider` on a subclass of `JPanel`. In addition, provide a `JTextField` where a specific value can be entered. The `JTextField` should display the current value of the `JSlider` at all times. Changing the value in the `JTextField` should also update the `JSlider`. A `JLabel` should be used to identify the `JTextField`. The `JSlider` methods `setValue` and `getValue` should be used. [Note: The `setValue` method is a public method that does not return a value and takes one integer argument, the `JSlider` value, which determines the position of the thumb.]

**22.11** (*Creating a Color Chooser*) Declare a subclass of `JPanel` called `MyColorChooser` that provides three `JSlider` objects and three `JTextField` objects. Each `JSlider` represents the values from 0 to 255 for the red, green and blue parts of a color. Use these values as the arguments to the `Color` constructor to create a new `Color` object. Display the current value of each `JSlider` in the corresponding `JTextField`. When the user changes the value of the `JSlider`, the `JTextField` should be changed accordingly. Use your new GUI component as part of an application that displays the current `Color` value by drawing a filled rectangle.

**22.12** (*Creating a Color Chooser: Modification*) Modify the `MyColorChooser` class of Exercise 22.11 to allow the user to enter an integer value into a `JTextField` to set the red, green or blue value. When the user presses *Enter* in the `JTextField`, the corresponding `JSlider` should be set to the appropriate value.

**22.13** (*Creating a Color Chooser: Modification*) Modify the application in Exercise 22.12 to draw the current color as a rectangle on an instance of a subclass of `JPanel` which provides its own `paintComponent` method to draw the rectangle and provides *set* methods to set the red, green and blue values for the current color. When any *set* method is invoked, the drawing panel should automatically repaint itself.

**22.14** (*Drawing Application*) Modify the application in Exercise 22.13 to allow the user to drag the mouse across the drawing panel (a subclass of `JPanel`) to draw a shape in the current color. Enable the user to choose what shape to draw.

**22.15** (*Drawing Application Modification*) Modify the application in Exercise 22.14 to allow the user to terminate the application by clicking the close box on the window that is displayed and by selecting *Exit* from a *File* menu. Use the techniques shown in Fig. 22.5.

**22.16** (*Complete Drawing Application*) Using the techniques developed in this chapter and Chapter 12, create a complete drawing application. The program should use the GUI components from Chapter 12 and this chapter to enable the user to select the shape, color and fill characteristics. Each shape should be stored in an array of `MyShape` objects, where `MyShape` is the superclass in your hierarchy of shape classes. Use a `JDesktopPane` and `JInternalFrame`s to allow the user to create multiple separate drawings in separate child windows. Create the user interface as a separate child window containing all the GUI components that allow the user to determine the characteristics of the shape to be drawn. The user can then click in any `JInternalFrame` to draw the shape.

# Concurrency

# 23



*The most general definition of beauty...Multeity in Unity.*

—Samuel Taylor Coleridge

*Do not block the way of inquiry.*

—Charles Sanders Peirce

*Learn to labor and to wait.*

—Henry Wadsworth Longfellow

## Objectives

In this chapter you'll:

- Understand concurrency, parallelism and multithreading.
- Learn the thread life cycle.
- Use `ExecutorService` to launch concurrent threads that execute `Runnable`s.
- Use `synchronized` methods to coordinate access to shared mutable data.
- Understand producer/consumer relationships.
- Use `SwingWorker` to update Swing GUIs in a thread-safe manner.
- Compare the performance of `Arrays` methods `sort` and `parallelSort` on a multi-core system.
- Use parallel streams for better performance on multi-core systems.
- Use `CompletableFuture`s to execute long calculations asynchronously and get the results in the future.

- 23.1 Introduction
- 23.2 Thread States and Life Cycle
  - 23.2.1 New and Runnable States
  - 23.2.2 Waiting State
  - 23.2.3 Timed Waiting State
  - 23.2.4 Blocked State
  - 23.2.5 Terminated State
  - 23.2.6 Operating-System View of the Runnable State
  - 23.2.7 Thread Priorities and Thread Scheduling
  - 23.2.8 Indefinite Postponement and Deadlock
- 23.3 Creating and Executing Threads with the **Executor** Framework
- 23.4 Thread Synchronization
  - 23.4.1 Immutable Data
  - 23.4.2 Monitors
  - 23.4.3 Unsynchronized Mutable Data Sharing
  - 23.4.4 Synchronized Mutable Data Sharing—Making Operations Atomic
- 23.5 Producer/Consumer Relationship without Synchronization
- 23.6 Producer/Consumer Relationship: **ArrayBlockingQueue**
- 23.7 (Advanced) Producer/Consumer Relationship with **synchronized**, **wait**, **notify** and **notifyAll**
- 23.8 (Advanced) Producer/Consumer Relationship: Bounded Buffers
- 23.9 (Advanced) Producer/Consumer Relationship: The **Lock** and **Condition** Interfaces
- 23.10 Concurrent Collections
- 23.11 Multithreading with GUI: **SwingWorker**
  - 23.11.1 Performing Computations in a Worker Thread: Fibonacci Numbers
  - 23.11.2 Processing Intermediate Results: Sieve of Eratosthenes
- 23.12 **sort/parallelSort** Timings with the Java SE 8 Date/Time API
- 23.13 Java SE 8: Sequential vs. Parallel Streams
- 23.14 (Advanced) Interfaces **Callable** and **Future**
- 23.15 (Advanced) Fork/Join Framework
- 23.16 Wrap-Up

Summary | Self-Review Exercises | Answers to Self-Review Exercises | Exercises

## 23.1 Introduction

[Note: Sections marked “Advanced” are intended for readers who wish a deeper treatment of concurrency and may be skipped by readers preferring only basic coverage.] It would be nice if we could focus our attention on performing only one task at a time and doing it well. That’s usually difficult to do in a complex world in which there’s so much going on at once. This chapter presents Java’s capabilities for developing programs that create and manage multiple tasks. As we’ll demonstrate, this can greatly improve program performance.

When we say that two tasks are operating **concurrently**, we mean that they’re both *making progress* at once. Until recently, most computers had only a single processor. Operating systems on such computers execute tasks concurrently by rapidly switching between them, doing a small portion of each before moving on to the next, so that all tasks keep progressing. For example, it’s common for personal computers to compile a program, send a file to a printer, receive electronic mail messages over a network and more, concurrently. Since its inception, Java has supported concurrency.

When we say that two tasks are operating **in parallel**, we mean that they’re executing *simultaneously*. In this sense, parallelism is a subset of concurrency. The human body performs a great variety of operations in parallel. Respiration, blood circulation, digestion, thinking and walking, for example, can occur in parallel, as can all the senses—sight, hearing, touch, smell and taste. It’s believed that this parallelism is possible because the

human brain is thought to contain billions of “processors.” Today’s multi-core computers have multiple processors that can perform tasks in parallel.

### *Java Concurrency*

Java makes concurrency available to you through the language and APIs. Java programs can have multiple **threads of execution**, where each thread has its own method-call stack and program counter, allowing it to execute concurrently with other threads while sharing with them application-wide resources such as memory and file handles. This capability is called **multithreading**.



#### **Performance Tip 23.1**

*A problem with single-threaded applications that can lead to poor responsiveness is that lengthy activities must complete before others can begin. In a multithreaded application, threads can be distributed across multiple cores (if available) so that multiple tasks execute in parallel and the application can operate more efficiently. Multithreading can also increase performance on single-processor systems—when one thread cannot proceed (because, for example, it’s waiting for the result of an I/O operation), another can use the processor.*

### *Concurrent Programming Uses*

We’ll discuss many applications of **concurrent programming**. For example, when streaming an audio or video over the Internet, the user may not want to wait until the entire audio or video downloads before starting the playback. To solve this problem, multiple threads can be used—one to download the audio or video (later in the chapter we’ll refer to this as a *producer*), and another to play it (later in the chapter we’ll refer to this as a *consumer*). These activities proceed concurrently. To avoid choppy playback, the threads are **synchronized** (that is, their actions are coordinated) so that the player thread doesn’t begin until there’s a sufficient amount of the audio or video in memory to keep the player thread busy. Producer and consumer threads *share memory*—we’ll show how to coordinate these threads to ensure correct execution. The Java Virtual Machine (JVM) creates threads to run programs and threads to perform housekeeping tasks such as garbage collection.

### *Concurrent Programming Is Difficult*

Writing multithreaded programs can be tricky. Although the human mind can perform functions concurrently, people find it difficult to jump between parallel trains of thought. To see why multithreaded programs can be difficult to write and understand, try the following experiment: Open three books to page 1, and try reading the books concurrently. Read a few words from the first book, then a few from the second, then a few from the third, then loop back and read the next few words from the first book, and so on. After this experiment, you’ll appreciate many of the challenges of multithreading—switching between the books, reading briefly, remembering your place in each book, moving the book you’re reading closer so that you can see it and pushing the books you’re not reading aside—and, amid all this chaos, trying to comprehend the content of the books!

### *Use the Prebuilt Classes of the Concurrency APIs Whenever Possible*

Programming concurrent applications is difficult and error prone. If you must use synchronization in a program, follow these guidelines:

1. *The vast majority of programmers should use existing collection classes and interfaces from the concurrency APIs that manage synchronization for you—such as the Array-*

*BlockingQueue* class (an implementation of interface *BlockingQueue*) we discuss in Section 23.6. Two other concurrency API classes that you'll use frequently are *LinkedBlockingQueue* and *ConcurrentHashMap* (each summarized in Fig. 23.22). The concurrency API classes are written by experts, have been thoroughly tested and debugged, operate efficiently and help you avoid common traps and pitfalls. Section 23.10 overviews Java's pre-built concurrent collections.


2. For advanced programmers who want to control synchronization, use the `synchronized` keyword and `Object` methods `wait`, `notify` and `notifyAll`, which we discuss in the optional Section 23.7.
3. Only the most advanced programmers should use `Locks` and `Conditions`, which we introduce in the optional Section 23.9, and classes like `LinkedTransferQueue`—an implementation of interface `TransferQueue`—which we summarize in Fig. 23.22.

You might want to read our discussions of the more advanced features in items 2 and 3 above, even though you most likely will not use them. We explain these because:

- They provide a solid basis for understanding how concurrent applications synchronize access to shared memory.
- By showing you the complexity involved in using these low-level features, we hope to impress upon you the message: *Use the simpler prebuilt concurrency capabilities whenever possible.*

## 23.2 Thread States and Life Cycle

At any time, a thread is said to be in one of several **thread states**—illustrated in the UML state diagram in Fig. 23.1. Several of the terms in the diagram are defined in later sections. We include this discussion to help you understand what's going on “under the hood” in a Java multithreaded environment. Java hides most of this detail from you, greatly simplifying the task of developing multithreaded applications.



**Fig. 23.1** | Thread life-cycle UML state diagram.



### 23.2.1 New and Runnable States

A new thread begins its life cycle in the *new* state. It remains in this state until the program starts the thread, which places it in the *runnable* state. A thread in the *runnable* state is considered to be executing its task.

### 23.2.2 Waiting State

Sometimes a *runnable* thread transitions to the *waiting* state while it waits for another thread to perform a task. A *waiting* thread transitions back to the *runnable* state only when another thread notifies it to continue executing.

### 23.2.3 Timed Waiting State

A *runnable* thread can enter the *timed waiting* state for a specified interval of time. It transitions back to the *runnable* state when that time interval expires or when the event it's waiting for occurs. *Timed waiting* threads and *waiting* threads cannot use a processor, even if one is available. A *runnable* thread can transition to the *timed waiting* state if it provides an optional wait interval when it's waiting for another thread to perform a task. Such a thread returns to the *runnable* state when it's notified by another thread or when the timed interval expires—whichever comes first. Another way to place a thread in the *timed waiting* state is to put a *runnable* thread to sleep—a **sleeping thread** remains in the *timed waiting* state for a designated period of time (called a **sleep interval**), after which it returns to the *runnable* state. Threads sleep when they momentarily do not have work to perform. For example, a word processor may contain a thread that periodically backs up (i.e., writes a copy of) the current document to disk for recovery purposes. If the thread did not sleep between successive backups, it would require a loop in which it continually tested whether it should write a copy of the document to disk. This loop would consume processor time without performing productive work, thus reducing system performance. In this case, it's more efficient for the thread to specify a sleep interval (equal to the period between successive backups) and enter the *timed waiting* state. This thread is returned to the *runnable* state when its sleep interval expires, at which point it writes a copy of the document to disk and reenters the *timed waiting* state.

### 23.2.4 Blocked State


A *runnable* thread transitions to the *blocked* state when it attempts to perform a task that cannot be completed immediately and it must temporarily wait until that task completes. For example, when a thread issues an input/output request, the operating system blocks the thread from executing until that I/O request completes—at that point, the *blocked* thread transitions to the *runnable* state, so it can resume execution. A *blocked* thread cannot use a processor, even if one is available.

### 23.2.5 Terminated State

A *runnable* thread enters the *terminated* state (sometimes called the *dead* state) when it successfully completes its task or otherwise terminates (perhaps due to an error). In the UML state diagram of Fig. 23.1, the *terminated* state is followed by the UML final state (the bull's-eye symbol) to indicate the end of the state transitions.

### 23.2.6 Operating-System View of the Runnable State

At the operating system level, Java's *runnable* state typically encompasses *two separate* states (Fig. 23.2). The operating system hides these states from the Java Virtual Machine (JVM), which sees only the *runnable* state. When a thread first transitions to the *runnable* state from the *new* state, it's in the *ready* state. A *ready* thread enters the *running* state (i.e., begins executing) when the operating system assigns it to a processor—also known as **dispatching the thread**. In most operating systems, each thread is given a small amount of processor time—called a **quantum** or **timeslice**—with which to perform its task. Deciding how large the quantum should be is a key topic in operating systems courses. When its quantum expires, the thread returns to the *ready* state, and the operating system assigns another thread to the processor. Transitions between the *ready* and *running* states are handled solely by the operating system. The JVM does not “see” the transitions—it simply views the thread as being *runnable* and leaves it up to the operating system to transition the thread between *ready* and *running*. The process that an operating system uses to determine which thread to dispatch is called **thread scheduling** and is dependent on thread priorities.



**Fig. 23.2** | Operating system's internal view of Java's *runnable* state.

### 23.2.7 Thread Priorities and Thread Scheduling

Every Java thread has a **thread priority** that helps determine the order in which threads are scheduled. Each new thread inherits the priority of the thread that created it. Informally, higher-priority threads are more important to a program and should be allocated processor time before lower-priority threads. *Nevertheless, thread priorities cannot guarantee the order in which threads execute.*

*It's recommended that you do not explicitly create and use Thread objects to implement concurrency, but rather use the Executor interface (which is described in Section 23.3).* The Thread class does contain some useful static methods, which you *will* use later in the chapter.

Most operating systems support timeslicing, which enables threads of equal priority to share a processor. Without timeslicing, each thread in a set of equal-priority threads runs to completion (unless it leaves the *runnable* state and enters the *waiting* or *timed waiting* state, or gets interrupted by a higher-priority thread) before other threads of equal priority get a chance to execute. With timeslicing, even if a thread has *not* finished executing when its quantum expires, the processor is taken away from the thread and given to the next thread of equal priority, if one is available.

An operating system's **thread scheduler** determines which thread runs next. One simple thread-scheduler implementation keeps the highest-priority thread *running* at all times and, if there's more than one highest-priority thread, ensures that all such threads execute for a quantum each in **round-robin** fashion. This process continues until all threads run to completion.



### Software Engineering Observation 23.1

*Java provides higher-level concurrency utilities to hide much of this complexity and make multithreaded programming less error prone. Thread priorities are used behind the scenes to interact with the operating system, but most programmers who use Java multithreading will not be concerned with setting and adjusting thread priorities.*



### Portability Tip 23.1

*Thread scheduling is platform dependent—the behavior of a multithreaded program could vary across different Java implementations.*

## 23.2.8 Indefinite Postponement and Deadlock

When a higher-priority thread enters the *ready* state, the operating system generally preempts the currently *running* thread (an operation known as **preemptive scheduling**). Depending on the operating system, a steady influx of higher-priority threads could postpone—possibly indefinitely—the execution of lower-priority threads. Such **indefinite postponement** is sometimes referred to more colorfully as **starvation**. Operating systems employ a technique called *aging* to prevent starvation—as a thread waits in the *ready* state, the operating system gradually increases the thread's priority to ensure that the thread will eventually run.

Another problem related to indefinite postponement is called **deadlock**. This occurs when a waiting thread (let's call this thread1) cannot proceed because it's waiting (either directly or indirectly) for another thread (let's call this thread2) to proceed, while simultaneously thread2 cannot proceed because it's waiting (either directly or indirectly) for thread1 to proceed. The two threads are waiting for each other, so the actions that would enable each thread to continue execution can never occur.

## 23.3 Creating and Executing Threads with the Executor Framework

This section demonstrates how to perform concurrent tasks in an application by using Executors and Runnable objects.

### *Creating Concurrent Tasks with the Runnable Interface*

You implement the **Runnable** interface (of package `java.lang`) to specify a task that can execute concurrently with other tasks. The **Runnable** interface declares the single method **run**, which contains the code that defines the task that a **Runnable** object should perform.

### *Executing Runnable Objects with an Executor*

To allow a **Runnable** to perform its task, you must execute it. An **Executor** object executes **Runnables**. It does this by creating and managing a group of threads called a **thread pool**. When an **Executor** begins executing a **Runnable**, the **Executor** calls the **Runnable** object's **run** method, which executes in the new thread.

The **Executor** interface declares a single method named **execute** which accepts a **Runnable** as an argument. The **Executor** assigns every **Runnable** passed to its **execute** method to one of the available threads in the thread pool. If there are no available threads, the **Executor** creates a new thread or waits for a thread to become available and assigns that thread the **Runnable** that was passed to method **execute**.

Using an Executor has many advantages over creating threads yourself. Executors can *reuse existing threads* to eliminate the overhead of creating a new thread for each task and can improve performance by *optimizing the number of threads* to ensure that the processor stays busy, without creating so many threads that the application runs out of resources.



### Software Engineering Observation 23.2

*Though it's possible to create threads explicitly, it's recommended that you use the Executor interface to manage the execution of Runnable objects.*

#### Using Class Executors to Obtain an ExecutorService

The **ExecutorService** interface (of package `java.util.concurrent`) *extends* **Executor** and declares various methods for managing the life cycle of an Executor. You obtain an **ExecutorService** object by calling one of the static methods declared in class **Executors** (of package `java.util.concurrent`). We use interface **ExecutorService** and a method of class **Executors** in our example, which executes three tasks.

#### Implementing the Runnable Interface

Class **PrintTask** (Fig. 23.3) implements **Runnable** (line 5), *so that multiple PrintTasks can execute concurrently*. Variable `sleepTime` (line 8) stores a random integer value from 0 to 5 seconds created in the **PrintTask** constructor (line 17). Each thread running a **PrintTask** sleeps for the amount of time specified by `sleepTime`, then outputs its task's name and a message indicating that it's done sleeping.

---

```

1 // Fig. 23.3: PrintTask.java
2 // PrintTask class sleeps for a random time from 0 to 5 seconds
3 import java.security.SecureRandom;
4
5 public class PrintTask implements Runnable
6 {
7 private static final SecureRandom generator = new SecureRandom();
8 private final int sleepTime; // random sleep time for thread
9 private final String taskName;
10
11 // constructor
12 public PrintTask(String taskName)
13 {
14 this.taskName = taskName;
15
16 // pick random sleep time between 0 and 5 seconds
17 sleepTime = generator.nextInt(5000); // milliseconds
18 }
19
20 // method run contains the code that a thread will execute
21 public void run()
22 {
23 try // put thread to sleep for sleepTime amount of time
24 {
25 System.out.printf("%s going to sleep for %d milliseconds.%n",
26 taskName, sleepTime);

```

---

**Fig. 23.3** | **PrintTask** class sleeps for a random time from 0 to 5 seconds. (Part 1 of 2.)

---

```

27 Thread.sleep(sleepTime); // put thread to sleep
28 }
29 catch (InterruptedException exception)
30 {
31 exception.printStackTrace();
32 Thread.currentThread().interrupt(); // re-interrupt the thread
33 }
34
35 // print task name
36 System.out.printf("%s done sleeping%n", taskName);
37 }
38 } // end class PrintTask

```

---

**Fig. 23.3** | PrintTask class sleeps for a random time from 0 to 5 seconds. (Part 2 of 2.)

A PrintTask executes when a thread calls the PrintTask's run method. Lines 25–26 display a message indicating the name of the currently executing task and that the task is going to sleep for sleepTime milliseconds. Line 27 invokes static method **sleep** of class Thread to place the thread in the *timed waiting* state for the specified amount of time. At this point, the thread loses the processor, and the system allows another thread to execute. When the thread awakens, it reenters the *runnable* state. When the PrintTask is assigned to a processor again, line 36 outputs a message indicating that the task is done sleeping, then method run terminates. The catch at lines 29–33 is required because method **sleep** might throw a *checked* exception of type **InterruptedException** if a sleeping thread's **interrupt** method is called.

#### *Let the Thread Handle InterruptedExceptions*

It's considered good practice to let the executing thread handle InterruptedExceptions. Normally, you'd do this by declaring that method run throws the exception, rather than catching the exception. However, recall from Chapter 11 that when you override a method, the throws may contain only the same exception types or a subset of the exception types declared in the original method's throws clause. Runnable method run does not have a throws clause in its original declaration, so we cannot provide one in line 21. To ensure that the executing thread receives the InterruptedException, line 32 first obtains a reference to the currently executing Thread by calling static method **currentThread**, then uses that Thread's **interrupt** method to deliver the InterruptedException to the current thread.<sup>1</sup>

#### *Using the ExecutorService to Manage Threads that Execute PrintTasks*

Figure 23.4 uses an ExecutorService object to manage threads that execute PrintTasks (as defined in Fig. 23.3). Lines 11–13 create and name three PrintTasks to execute. Line 18 uses Executors method **newCachedThreadPool** to obtain an ExecutorService that's capable of creating new threads as they're needed by the application. These threads are used by ExecutorService to execute the Runnables.

---

1. For detailed information on handling thread interruptions, see Chapter 7 of *Java Concurrency in Practice* by Brian Goetz, et al., Addison-Wesley Professional, 2006.

```

1 // Fig. 23.4: TaskExecutor.java
2 // Using an ExecutorService to execute Runnable's.
3 import java.util.concurrent.Executors;
4 import java.util.concurrent.ExecutorService;
5
6 public class TaskExecutor
7 {
8 public static void main(String[] args)
9 {
10 // create and name each runnable
11 PrintTask task1 = new PrintTask("task1");
12 PrintTask task2 = new PrintTask("task2");
13 PrintTask task3 = new PrintTask("task3");
14
15 System.out.println("Starting Executor");
16
17 // create ExecutorService to manage threads
18 ExecutorService executorService = Executors.newCachedThreadPool();
19
20 // start the three PrintTasks
21 executorService.execute(task1); // start task1
22 executorService.execute(task2); // start task2
23 executorService.execute(task3); // start task3
24
25 // shut down ExecutorService--it decides when to shut down threads
26 executorService.shutdown();
27
28 System.out.printf("Tasks started, main ends.%n%n");
29 }
30 } // end class TaskExecutor

```

Starting Executor  
Tasks started, main ends

task1 going to sleep for 4806 milliseconds  
task2 going to sleep for 2513 milliseconds  
task3 going to sleep for 1132 milliseconds  
task3 done sleeping  
task2 done sleeping  
task1 done sleeping

Starting Executor  
task1 going to sleep for 3161 milliseconds.  
task3 going to sleep for 532 milliseconds.  
task2 going to sleep for 3440 milliseconds.  
Tasks started, main ends.

task3 done sleeping  
task1 done sleeping  
task2 done sleeping

**Fig. 23.4** | Using an ExecutorService to execute Runnable's.

Lines 21–23 each invoke the `ExecutorService`’s `execute` method, which executes its `Runnable` argument (in this case a `PrintTask`) some time in the future. The specified task may execute in one of the threads in the `ExecutorService`’s thread pool, in a new thread created to execute it, or in the thread that called the `execute` method—the `ExecutorService` manages these details. Method `execute` returns immediately from each invocation—the program does *not* wait for each `PrintTask` to finish. Line 26 calls `ExecutorService` method **`shutdown`**, which notifies the `ExecutorService` to *stop accepting new tasks, but continues executing tasks that have already been submitted*. Once all of the previously submitted `Runnables` have completed, the `ExecutorService` terminates. Line 28 outputs a message indicating that the tasks were started and the `main` thread is finishing its execution.

### *Main Thread*

The code in `main` executes in the **main thread**, which is created by the JVM. The code in the `run` method of `PrintTask` (lines 21–37 of Fig. 23.3) executes whenever the `ExecutorService` starts each `PrintTask`—again, this is sometime after they’re passed to the `ExecutorService`’s `execute` method (Fig. 23.4, lines 21–23). When `main` terminates, the program itself continues running because there are still tasks that must finish executing. The program will not terminate until these tasks complete.

### *Sample Outputs*

The sample outputs show each task’s name and sleep time as the thread goes to sleep. The thread with the shortest sleep time *in most cases* awakens first, indicates that it’s done sleeping and terminates. In Section 23.8, we discuss multithreading issues that could prevent the thread with the shortest sleep time from awakening first. In the first output, the `main` thread terminates *before* any of the `PrintTasks` output their names and sleep times. This shows that the `main` thread runs to completion before any of the `PrintTasks` gets a chance to run. In the second output, all of the `PrintTasks` output their names and sleep times *before* the `main` thread terminates. This shows that the `PrintTasks` started executing before the `main` thread terminated. Also, notice in the second example output, `task3` goes to sleep before `task2` last, even though we passed `task2` to the `ExecutorService`’s `execute` method before `task3`. This illustrates the fact that *we cannot predict the order in which the tasks will start executing, even if we know the order in which they were created and started*.

### *Waiting for Previously Scheduled Tasks to Terminate*

After scheduling tasks to execute, you’ll typically want to *wait for the tasks to complete*—for example, so that you can use the tasks’ results. After calling method `shutdown`, you can call `ExecutorService` method `awaitTermination` to wait for scheduled tasks to complete. We demonstrate this in Fig. 23.7. We purposely did not call `awaitTermination` in Fig. 23.4 to demonstrate that a program can continue executing after the `main` thread terminates.

## 23.4 Thread Synchronization

When multiple threads share an object and it’s *modified* by one or more of them, indeterminate results may occur (as we’ll see in the examples) unless access to the shared object is managed properly. If one thread is in the process of updating a shared object and another thread also tries to update it, it’s uncertain which thread’s update takes effect. Similarly, if one thread is in the process of updating a shared object and another thread tries to read it, it’s uncertain whether the reading thread will see the old value or the new one. In such

cases, the program's behavior cannot be trusted—sometimes the program will produce the correct results, and sometimes it won't, and there won't be any indication that the shared object was manipulated incorrectly.

The problem can be solved by giving only one thread at a time *exclusive access* to code that accesses the shared object. During that time, other threads desiring to access the object are kept waiting. When the thread with exclusive access finishes accessing the object, one of the waiting threads is allowed to proceed. This process, called **thread synchronization**, coordinates access to shared data by multiple concurrent threads. By synchronizing threads in this manner, you can ensure that each thread accessing a shared object *excludes* all other threads from doing so simultaneously—this is called **mutual exclusion**.

### 23.4.1 Immutable Data

Actually, thread synchronization is necessary *only* for shared **mutable data**, i.e., data that may *change* during its lifetime. With shared **immutable data** that will *not* change, it's not possible for a thread to see old or incorrect values as a result of another thread's manipulation of that data.

When you share *immutable data* across threads, declare the corresponding data fields `final` to indicate that the values of the variables will *not* change after they're initialized. This prevents accidental modification of the shared data, which could compromise thread safety. *Labeling object references as `final` indicates that the reference will not change, but it does not guarantee that the referenced object is immutable—this depends entirely on the object's properties.* However, it's still good practice to mark references that will not change as `final`.



#### Software Engineering Observation 23.3

*Always declare data fields that you do not expect to change as `final`. Primitive variables that are declared as `final` can safely be shared across threads. An object reference that's declared as `final` ensures that the object it refers to will be fully constructed and initialized before it's used by the program, and prevents the reference from pointing to another object.*

### 23.4.2 Monitors

A common way to perform synchronization is to use Java's built-in **monitors**. Every object has a monitor and a **monitor lock** (or **intrinsic lock**). The monitor ensures that its object's monitor lock is held by a maximum of only one thread at any time. Monitors and monitor locks can thus be used to enforce mutual exclusion. If an operation requires the executing thread to *hold a lock* while the operation is performed, a thread must *acquire the lock* before proceeding with the operation. Other threads attempting to perform an operation that requires the same lock will be *blocked* until the first thread *releases the lock*, at which point the *blocked* threads may attempt to acquire the lock and proceed with the operation.

To specify that a thread must hold a monitor lock to execute a block of code, the code should be placed in a **synchronized statement**. Such code is said to be **guarded** by the monitor lock; a thread must **acquire the lock** to execute the guarded statements. The monitor allows only one thread at a time to execute statements within synchronized statements that lock on the same object, as only one thread at a time can hold the monitor lock. The synchronized statements are declared using the **synchronized keyword**:



```

synchronized (object)
{
 statements
}

```

where *object* is the object whose monitor lock will be acquired; *object* is normally this if it's the object in which the synchronized statement appears. If several synchronized statements in different threads are trying to execute on an object at the same time, only one of them may be active on the object—all the other threads attempting to enter a synchronized statement on the same object are placed in the *blocked* state.

When a synchronized statement finishes executing, the object's monitor lock is released and one of the *blocked* threads attempting to enter a synchronized statement can be allowed to acquire the lock to proceed. Java also allows **synchronized methods**. Before executing, a synchronized instance method must acquire the lock on the object that's used to call the method. Similarly, a static synchronized method must acquire the lock on the class that's used to call the method.



### Software Engineering Observation 23.4

*Using a synchronized block to enforce mutual exclusion is an example of the design pattern known as the Java Monitor Pattern (see section 4.2.1 of Java Concurrency in Practice by Brian Goetz, et al., Addison-Wesley Professional, 2006).*

## 23.4.3 Unsynchronized Mutable Data Sharing

First, we illustrate the dangers of sharing an object across threads *without* proper synchronization. In this example (Figs. 23.5–23.7), two `Runnable`s maintain references to a single integer array. Each `Runnable` writes three values to the array, then terminates. This may seem harmless, but we'll see that it can result in errors if the array is manipulated without synchronization.

### Class `SimpleArray`

A `SimpleArray` object (Fig. 23.5) will be *shared* across multiple threads. `SimpleArray` will enable those threads to place `int` values into array (declared at line 9). Line 10 initializes variable `writeIndex`, which will be used to determine the array element that should be written to next. The constructor (lines 13–16) creates an integer array of the desired size.

---

```

1 // Fig. 23.5: SimpleArray.java
2 // Class that manages an integer array to be shared by multiple threads.
3 import java.security.SecureRandom;
4 import java.util.Arrays;
5
6 public class SimpleArray // CAUTION: NOT THREAD SAFE!
7 {
8 private static final SecureRandom generator = new SecureRandom();
9 private final int[] array; // the shared integer array
10 private int writeIndex = 0; // shared index of next element to write
11

```

---

**Fig. 23.5** | Class that manages an integer array to be shared by multiple threads. (Caution: The example of Figs. 23.5–23.7 is *not* thread safe.) (Part I of 2.)

---

```

12 // construct a SimpleArray of a given size
13 public SimpleArray(int size)
14 {
15 array = new int[size];
16 }
17
18 // add a value to the shared array
19 public void add(int value)
20 {
21 int position = writeIndex; // store the write index
22
23 try
24 {
25 // put thread to sleep for 0-499 milliseconds
26 Thread.sleep(generator.nextInt(500));
27 }
28 catch (InterruptedException ex)
29 {
30 Thread.currentThread().interrupt(); // re-interrupt the thread
31 }
32
33 // put value in the appropriate element
34 array[position] = value;
35 System.out.printf("%s wrote %2d to element %d.%n",
36 Thread.currentThread().getName(), value, position);
37
38 ++writeIndex; // increment index of element to be written next
39 System.out.printf("Next write index: %d.%n", writeIndex);
40 }
41
42 // used for outputting the contents of the shared integer array
43 public String toString()
44 {
45 return Arrays.toString(array);
46 }
47 } // end class SimpleArray

```

---

**Fig. 23.5** | Class that manages an integer array to be shared by multiple threads. (*Caution:* The example of Figs. 23.5–23.7 is *not* thread safe.) (Part 2 of 2.)

Method `add` (lines 19–40) allows new values to be inserted at the end of the array. Line 21 stores the current `writeIndex` value. Line 26 puts the thread that invokes `add` to sleep for a random interval from 0 to 499 milliseconds. This is done to make the problems associated with *unsynchronized access to shared mutable data* more obvious. After the thread is done sleeping, line 34 inserts the value passed to `add` into the array at the element specified by `position`. Lines 35–36 output a message indicating the executing thread's name, the value that was inserted in the array and where it was inserted. The expression `Thread.currentThread().getName()` (line 36) first obtains a reference to the currently executing `Thread`, then uses that `Thread`'s `getName` method to obtain its name. Line 38 increments `writeIndex` so that the next call to `add` will insert a value in the array's next element. Lines 43–46 override method `toString` to create a `String` representation of the array's contents.

**Class *ArrayWriter***

Class *ArrayWriter* (Fig. 23.6) implements the interface *Runnable* to define a task for inserting values in a *SimpleArray* object. The constructor (lines 10–14) takes two arguments—an integer value, which is the first value this task will insert in the *SimpleArray* object, and a reference to the *SimpleArray* object. Line 20 invokes method *add* on the *SimpleArray* object. The task completes after three consecutive integers beginning with *startValue* are inserted in the *SimpleArray* object.

---

```

1 // Fig. 23.6: ArrayWriter.java
2 // Adds integers to an array shared with other Runnables
3 import java.lang.Runnable;
4
5 public class ArrayWriter implements Runnable
6 {
7 private final SimpleArray sharedSimpleArray;
8 private final int startValue;
9
10 public ArrayWriter(int value, SimpleArray array)
11 {
12 startValue = value;
13 sharedSimpleArray = array;
14 }
15
16 public void run()
17 {
18 for (int i = startValue; i < startValue + 3; i++)
19 {
20 sharedSimpleArray.add(i); // add an element to the shared array
21 }
22 }
23 } // end class ArrayWriter

```

---

**Fig. 23.6** | Adds integers to an array shared with other *Runnables*. (*Caution:* The example of Figs. 23.5–23.7 is *not* thread safe.)

**Class *SharedArrayTest***

Class *SharedArrayTest* (Fig. 23.7) executes two *ArrayWriter* tasks that add values to a single *SimpleArray* object. Line 12 constructs a six-element *SimpleArray* object. Lines 15–16 create two new *ArrayWriter* tasks, one that places the values 1–3 in the *SimpleArray* object, and one that places the values 11–13. Lines 19–21 create an *ExecutorService* and execute the two *ArrayWriters*. Line 23 invokes the *ExecutorService*’s *shutdown* method to *prevent additional tasks from starting* and to enable the application to terminate when the currently executing tasks complete execution.

---

```

1 // Fig. 23.7: SharedArrayTest.java
2 // Executing two Runnables to add elements to a shared SimpleArray.
3 import java.util.concurrent.Executors;

```

---

**Fig. 23.7** | Executing two *Runnables* to add elements to a shared array. (*Caution:* The example of Figs. 23.5–23.7 is *not* thread safe.) (Part 1 of 3.)

```

4 import java.util.concurrent.ExecutorService;
5 import java.util.concurrent.TimeUnit;
6
7 public class SharedArrayTest
8 {
9 public static void main(String[] arg)
10 {
11 // construct the shared object
12 SimpleArray sharedSimpleArray = new SimpleArray(6);
13
14 // create two tasks to write to the shared SimpleArray
15 ArrayWriter writer1 = new ArrayWriter(1, sharedSimpleArray);
16 ArrayWriter writer2 = new ArrayWriter(11, sharedSimpleArray);
17
18 // execute the tasks with an ExecutorService
19 ExecutorService executorService = Executors.newCachedThreadPool();
20 executorService.execute(writer1);
21 executorService.execute(writer2);
22
23 executorService.shutdown();
24
25 try
26 {
27 // wait 1 minute for both writers to finish executing
28 boolean tasksEnded =
29 executorService.awaitTermination(1, TimeUnit.MINUTES);
30
31 if (tasksEnded)
32 {
33 System.out.printf("%nContents of SimpleArray:%n");
34 System.out.println(sharedSimpleArray); // print contents
35 }
36 else
37 System.out.println(
38 "Timed out while waiting for tasks to finish.");
39 }
40 catch (InterruptedException ex)
41 {
42 ex.printStackTrace();
43 }
44 } // end main
45 } // end class SharedArrayTest

```

```

pool-1-thread-1 wrote 1 to element 0.
Next write index: 1
pool-1-thread-1 wrote 2 to element 1.
Next write index: 2
pool-1-thread-1 wrote 3 to element 2.
Next write index: 3
pool-1-thread-2 wrote 11 to element 0.
Next write index: 4

```

First `pool-1-thread-1` wrote the value 1 to element 0. Later `pool-1-thread-2` wrote the value 11 to element 0, thus *overwriting* the previously stored value.

**Fig. 23.7** | Executing two `Runnable`s to add elements to a shared array. (*Caution:* The example of Figs. 23.5–23.7 is *not* thread safe.) (Part 2 of 3.)

```
pool-1-thread-2 wrote 12 to element 4.
Next write index: 5
pool-1-thread-2 wrote 13 to element 5.
Next write index: 6
```

```
Contents of SimpleArray:
[11, 2, 3, 0, 12, 13]
```

**Fig. 23.7** | Executing two `Runnable`s to add elements to a shared array. (*Caution:* The example of Figs. 23.5–23.7 is *not* thread safe.) (Part 3 of 3.)

### ***ExecutorService Method awaitTermination***

Recall that `ExecutorService` method `shutdown` returns immediately. Thus any code that appears *after* the call to `ExecutorService` method `shutdown` in line 23 *will continue executing as long as the main thread is still assigned to a processor*. We'd like to output the `SimpleArray` object to show you the results *after* the threads complete their tasks. So, we need the program to wait for the threads to complete before `main` outputs the `SimpleArray` object's contents. Interface `ExecutorService` provides the **`awaitTermination`** method for this purpose. This method returns control to its caller either when all tasks executing in the `ExecutorService` complete or when the specified timeout elapses. If all tasks are completed before `awaitTermination` times out, this method returns `true`; otherwise it returns `false`. The two arguments to `awaitTermination` represent a timeout value and a unit of measure specified with a constant from class `TimeUnit` (in this case, `TimeUnit.MINUTES`).

Method `awaitTermination` throws an `InterruptedException` if the calling thread is interrupted while waiting for other threads to terminate. Because we catch this exception in the application's `main` method, there's no need to re-interrupt the `main` thread as this program will terminate as soon as `main` terminates.

In this example, if *both* tasks complete before `awaitTermination` times out, line 34 displays the `SimpleArray` object's contents. Otherwise, lines 37–38 display a message indicating that the tasks did not finish executing before `awaitTermination` timed out.

### ***Sample Program Output***

Figure 23.7's output shows the problems (highlighted in the output) that can be caused by *failure to synchronize access to shared mutable data*. The value 1 was written to element 0, then *overwritten* later by the value 11. Also, when `writeIndex` was incremented to 3, *nothing was written to that element*, as indicated by the 0 in that element of the printed array.

Recall that we added calls to `Thread` method `sleep` between operations on the shared mutable data to emphasize the *unpredictability of thread scheduling* and increase the likelihood of producing erroneous output. Even if these operations were allowed to proceed at their normal pace, you could still see errors in the program's output. However, modern processors can handle the simple operations of the `SimpleArray` method `add` so quickly that you might not see the errors caused by the two threads executing this method concurrently, even if you tested the program dozens of times. *One of the challenges of multi-threaded programming is spotting the errors—they may occur so infrequently and unpredictably that a broken program does not produce incorrect results during testing, creating the illusion that the program is correct.* This is all the more reason to use predefined collections that handle the synchronization for you.

### 23.4.4 Synchronized Mutable Data Sharing—Making Operations Atomic

The output errors of Fig. 23.7 can be attributed to the fact that the shared object, `SimpleArray`, is not **thread safe**—`SimpleArray` is susceptible to errors if it's *accessed concurrently by multiple threads*. The problem lies in method `add`, which stores the value of `writeIndex`, places a new value in that element, then increments `writeIndex`. Such a method would present no problem in a single-threaded program. However, if one thread obtains the value of `writeIndex`, there's no guarantee that another thread cannot come along and increment `writeIndex` *before* the first thread has had a chance to place a value in the array. If this happens, the first thread will be writing to the array based on a **stale value** of `writeIndex`—a value that's no longer valid. Another possibility is that one thread might obtain the value of `writeIndex` *after* another thread adds an element to the array but *before* `writeIndex` is incremented. In this case, too, the first thread would write to the array based on an invalid value for `writeIndex`.

`SimpleArray` is *not thread safe because it allows any number of threads to read and modify shared mutable data concurrently*, which can cause errors. To make `SimpleArray` thread safe, we must ensure that no two threads can access its shared mutable data at the same time. While one thread is in the process of storing `writeIndex`, adding a value to the array, and incrementing `writeIndex`, *no other thread* may read or change the value of `writeIndex` or modify the contents of the array at any point during these three operations. In other words, we want these three operations—storing `writeIndex`, writing to the array, incrementing `writeIndex`—to be an **atomic operation**, which cannot be divided into smaller suboperations. (As you'll see in later examples, read operations on shared mutable data should also be atomic.) We can simulate atomicity by ensuring that only one thread carries out the three operations at a time. Any other threads that need to perform the operation must *wait* until the first thread has finished the `add` operation in its entirety.

Atomicity can be achieved using the `synchronized` keyword. By placing our three suboperations in a `synchronized` statement or `synchronized` method, we allow only one thread at a time to acquire the lock and perform the operations. When that thread has completed all of the operations in the `synchronized` block and releases the lock, another thread may acquire the lock and begin executing the operations. This ensures that a thread executing the operations will see the actual values of the shared mutable data and that *these values will not change unexpectedly in the middle of the operations as a result of another thread's modifying them*.



#### Software Engineering Observation 23.5

*Place all accesses to mutable data that may be shared by multiple threads inside `synchronized` statements or `synchronized` methods that synchronize on the same lock. When performing multiple operations on shared mutable data, hold the lock for the entirety of the operation to ensure that the operation is effectively atomic.*

#### Class `SimpleArray` with Synchronization

Figure 23.8 displays class `SimpleArray` with the proper synchronization. Notice that it's identical to the `SimpleArray` class of Fig. 23.5, except that `add` is now a `synchronized` method (line 20). So, only one thread at a time can execute this method. We reuse classes `ArrayWriter` (Fig. 23.6) and `SharedArrayTest` (Fig. 23.7) from the previous example.

---

```

1 // Fig. 23.8: SimpleArray.java
2 // Class that manages an integer array to be shared by multiple
3 // threads with synchronization.
4 import java.security.SecureRandom;
5 import java.util.Arrays;
6
7 public class SimpleArray
8 {
9 private static final SecureRandom generator = new SecureRandom();
10 private final int[] array; // the shared integer array
11 private int writeIndex = 0; // index of next element to be written
12
13 // construct a SimpleArray of a given size
14 public SimpleArray(int size)
15 {
16 array = new int[size];
17 }
18
19 // add a value to the shared array
20 public synchronized void add(int value)
21 {
22 int position = writeIndex; // store the write index
23
24 try
25 {
26 // in real applications, you shouldn't sleep while holding a lock
27 Thread.sleep(generator.nextInt(500)); // for demo only
28 }
29 catch (InterruptedException ex)
30 {
31 Thread.currentThread().interrupt();
32 }
33
34 // put value in the appropriate element
35 array[position] = value;
36 System.out.printf("%s wrote %2d to element %d.%n",
37 Thread.currentThread().getName(), value, position);
38
39 ++writeIndex; // increment index of element to be written next
40 System.out.printf("Next write index: %d.%n", writeIndex);
41 }
42
43 // used for outputting the contents of the shared integer array
44 public synchronized String toString()
45 {
46 return Arrays.toString(array);
47 }
48 } // end class SimpleArray

```

---

**Fig. 23.8** | Class that manages an integer array to be shared by multiple threads with synchronization. (Part I of 2.)

```

pool-1-thread-1 wrote 1 to element 0.
Next write index: 1
pool-1-thread-2 wrote 11 to element 1.
Next write index: 2
pool-1-thread-2 wrote 12 to element 2.
Next write index: 3
pool-1-thread-2 wrote 13 to element 3.
Next write index: 4
pool-1-thread-1 wrote 2 to element 4.
Next write index: 5
pool-1-thread-1 wrote 3 to element 5.
Next write index: 6

```

```

Contents of SimpleArray:
[1, 11, 12, 13, 2, 3]

```

**Fig. 23.8** | Class that manages an integer array to be shared by multiple threads with synchronization. (Part 2 of 2.)

Line 20 declares method `add` as synchronized, making all of the operations in this method behave as a single, atomic operation. Line 22 performs the first suboperation—storing the value of `writeIndex`. Line 35 defines the second suboperation, writing an element to the element at the index position. Line 39 increments `writeIndex`. When the method finishes executing at line 41, the executing thread implicitly *releases* the `SimpleArray` lock, making it possible for another thread to begin executing the `add` method.

In the synchronized `add` method, we print messages to the console indicating the progress of threads as they execute this method, in addition to performing the actual operations required to insert a value in the array. We do this so that the messages will be printed in the correct order, allowing us to see whether the method is properly synchronized by comparing these outputs with those of the previous, unsynchronized example. We continue to output messages from synchronized blocks in later examples for demonstration purposes only; typically, however, I/O *should not* be performed in synchronized blocks, because it's important to minimize the amount of time that an object is “locked.” [Note: Line 27 in this example calls `Thread` method `sleep` (for demo purposes only) to emphasize the unpredictability of thread scheduling. You should never call `sleep` while holding a lock in a real application.]



### Performance Tip 23.2

*Keep the duration of synchronized statements as short as possible while maintaining the needed synchronization. This minimizes the wait time for blocked threads. Avoid performing I/O, lengthy calculations and operations that do not require synchronization while holding a lock.*

## 23.5 Producer/Consumer Relationship without Synchronization

In a **producer/consumer relationship**, the **producer** portion of an application generates data and *stores it in a shared object*, and the **consumer** portion of the application *reads data*



*from the shared object.* The producer/consumer relationship separates the task of identifying work to be done from the tasks involved in actually carrying out the work.

### ***Examples of Producer/Consumer Relationship***

One example of a common producer/consumer relationship is **print spooling**. Although a printer might not be available when you want to print from an application (i.e., the producer), you can still “complete” the print task, as the data is temporarily placed on disk until the printer becomes available. Similarly, when the printer (i.e., a consumer) is available, it doesn’t have to wait until a current user wants to print. The spooled print jobs can be printed as soon as the printer becomes available. Another example of the producer/consumer relationship is an application that copies data onto DVDs by placing data in a fixed-size buffer, which is emptied as the DVD drive “burns” the data onto the DVD.

### ***Synchronization and State Dependence***

In a multithreaded producer/consumer relationship, a **producer thread** generates data and places it in a shared object called a **buffer**. A **consumer thread** reads data from the buffer. This relationship requires *synchronization* to ensure that values are produced and consumed properly. All operations on *mutable* data that’s shared by multiple threads (e.g., the data in the buffer) must be guarded with a lock to prevent corruption, as discussed in Section 23.4. Operations on the buffer data shared by a producer and consumer thread are also **state dependent**—the operations should proceed only if the buffer is in the correct state. If the buffer is in a *not-full state*, the producer may produce; if the buffer is in a *not-empty state*, the consumer may consume. All operations that access the buffer must use synchronization to ensure that data is written to the buffer or read from the buffer only if the buffer is in the proper state. If the producer attempting to put the next data into the buffer determines that it’s full, the producer thread must *wait* until there’s space to write a new value. If a consumer thread finds the buffer empty or finds that the previous data has already been read, the consumer must also *wait* for new data to become available. Other examples of state dependence are that you can’t drive your car if its gas tank is empty and you can’t put more gas into the tank if it’s already full.

### ***Logic Errors from Lack of Synchronization***

Consider how logic errors can arise if we do not synchronize access among multiple threads manipulating shared mutable data. Our next example (Figs. 23.9–23.13) implements a producer/consumer relationship *without the proper synchronization*. A producer thread writes the numbers 1 through 10 into a shared buffer—a single memory location shared between two threads (a single `int` variable called `buffer` in line 6 of Fig. 23.12 in this example). The consumer thread reads this data from the shared buffer and displays the data. The program’s output shows the values that the producer writes (produces) into the shared buffer and the values that the consumer reads (consumes) from the shared buffer.

Each value the producer thread writes to the shared buffer must be consumed *exactly once* by the consumer thread. However, the threads in this example are not synchronized. Therefore, *data can be lost or garbled if the producer places new data into the shared buffer before the consumer reads the previous data*. Also, data can be incorrectly *duplicated* if the consumer consumes data again before the producer produces the next value. To show these possibilities, the consumer thread in the following example keeps a total of all the values it reads. The producer thread produces values from 1 through 10. If the consumer

reads each value produced once and only once, the total will be 55. However, if you execute this program several times, you'll see that the total is not always 55 (as shown in the outputs in Fig. 23.13). To emphasize the point, the producer and consumer threads in the example each sleep for random intervals of up to three seconds between performing their tasks. Thus, we do not know when the producer thread will attempt to write a new value, or when the consumer thread will attempt to read a value.

### Interface Buffer

The program consists of interface `Buffer` (Fig. 23.9) and classes `Producer` (Fig. 23.10), `Consumer` (Fig. 23.11), `UnsynchronizedBuffer` (Fig. 23.12) and `SharedBufferTest` (Fig. 23.13). Interface `Buffer` (Fig. 23.9) declares methods `blockingPut` (line 6) and `blockingGet` (line 9) that a `Buffer` (such as `UnsynchronizedBuffer`) must implement to enable the `Producer` thread to place a value in the `Buffer` and the `Consumer` thread to retrieve a value from the `Buffer`, respectively. In subsequent examples, methods `blockingPut` and `blockingGet` will call methods that throw `InterruptedExceptions`—typically this indicates that a method temporarily could be blocked from performing a task. We declare each method with a `throws` clause here so that we don't have to modify this interface for the later examples.

---

```

1 // Fig. 23.9: Buffer.java
2 // Buffer interface specifies methods called by Producer and Consumer.
3 public interface Buffer
4 {
5 // place int value into Buffer
6 public void blockingPut(int value) throws InterruptedException;
7
8 // return int value from Buffer
9 public int blockingGet() throws InterruptedException;
10 } // end interface Buffer

```

---

**Fig. 23.9** | Buffer interface specifies methods called by `Producer` and `Consumer`. (Caution: The example of Figs. 23.9–23.13 is *not* thread safe.)

### Class Producer

Class `Producer` (Fig. 23.10) implements the `Runnable` interface, allowing it to be executed as a task in a separate thread. The constructor (lines 11–14) initializes the `Buffer` reference `sharedLocation` with an object created in `main` (line 15 of Fig. 23.13) and passed to the constructor. As we'll see, this is an `UnsynchronizedBuffer` object that implements interface `Buffer` *without synchronizing access to the shared object*. The `Producer` thread in this program executes the tasks specified in the method `run` (Fig. 23.10, lines 17–39). Each iteration of the loop (lines 21–35) invokes `Thread` method `sleep` (line 25) to place the `Producer` thread into the *timed waiting* state for a random time interval between 0 and 3 seconds. When the thread awakens, line 26 passes the value of control variable `count` to the `Buffer` object's `blockingPut` method to set the shared buffer's value. Lines 27–28 keep a total of all the values produced so far and output that value. When the loop completes, lines 36–37 display a message indicating that the `Producer` has finished producing data and is terminating. Next, method `run` terminates, which indicates that the `Producer` completed its task. Any method called from a `Runnable`'s `run` method (e.g., `Buffer` method `blockingPut`) executes as part of

that task's thread of execution. This fact becomes important in Sections 23.6—23.8 when we add synchronization to the producer/consumer relationship.

---

```

1 // Fig. 23.10: Producer.java
2 // Producer with a run method that inserts the values 1 to 10 in buffer.
3 import java.security.SecureRandom;
4
5 public class Producer implements Runnable
6 {
7 private static final SecureRandom generator = new SecureRandom();
8 private final Buffer sharedLocation; // reference to shared object
9
10 // constructor
11 public Producer(Buffer sharedLocation)
12 {
13 this.sharedLocation = sharedLocation;
14 }
15
16 // store values from 1 to 10 in sharedLocation
17 public void run()
18 {
19 int sum = 0;
20
21 for (int count = 1; count <= 10; count++)
22 {
23 try // sleep 0 to 3 seconds, then place value in Buffer
24 {
25 Thread.sleep(generator.nextInt(3000)); // random sleep
26 sharedLocation.blockingPut(count); // set value in buffer
27 sum += count; // increment sum of values
28 System.out.printf("\t%2d\n", sum);
29 }
30 catch (InterruptedException exception)
31 {
32 Thread.currentThread().interrupt();
33 }
34 }
35
36 System.out.printf(
37 "Producer done producing\nTerminating Producer\n");
38 }
39 } // end class Producer

```

---

**Fig. 23.10** | Producer with a run method that inserts the values 1 to 10 in buffer. (*Caution:* The example of Figs. 23.9–23.13 is *not* thread safe.)

### *Class Consumer*

Class Consumer (Fig. 23.11) also implements interface `Runnable`, allowing the Consumer to execute concurrently with the Producer. Lines 11–14 initialize `Buffer` reference `sharedLocation` with an object that implements the `Buffer` interface (created in main, Fig. 23.13) and passed to the constructor as the parameter `shared`. As we'll see, this is the same `UnsynchronizedBuffer` object that's used to initialize the Producer object—thus,

the two threads share the same object. The Consumer thread in this program performs the tasks specified in method `run` (lines 17–39). Lines 21–34 iterate 10 times. Each iteration invokes Thread method `sleep` (line 26) to put the Consumer thread into the *timed waiting* state for up to 3 seconds. Next, line 27 uses the Buffer’s `blockingGet` method to retrieve the value in the shared buffer, then adds the value to variable `sum`. Line 28 displays the total of all the values consumed so far. When the loop completes, lines 36–37 display a line indicating the sum of the consumed values. Then method `run` terminates, which indicates that the Consumer completed its task. Once both threads enter the *terminated* state, the program ends.

```

1 // Fig. 23.11: Consumer.java
2 // Consumer with a run method that loops, reading 10 values from buffer.
3 import java.security.SecureRandom;
4
5 public class Consumer implements Runnable
6 {
7 private static final SecureRandom generator = new SecureRandom();
8 private final Buffer sharedLocation; // reference to shared object
9
10 // constructor
11 public Consumer(Buffer sharedLocation)
12 {
13 this.sharedLocation = sharedLocation;
14 }
15
16 // read sharedLocation's value 10 times and sum the values
17 public void run()
18 {
19 int sum = 0;
20
21 for (int count = 1; count <= 10; count++)
22 {
23 // sleep 0 to 3 seconds, read value from buffer and add to sum
24 try
25 {
26 Thread.sleep(generator.nextInt(3000));
27 sum += sharedLocation.blockingGet();
28 System.out.printf("\t\t\t%d\n", sum);
29 }
30 catch (InterruptedException exception)
31 {
32 Thread.currentThread().interrupt();
33 }
34 }
35
36 System.out.printf("\n%s %d\n%s\n",
37 "Consumer read values totaling", sum, "Terminating Consumer");
38 }
39 } // end class Consumer

```

**Fig. 23.11** | Consumer with a run method that loops, reading 10 values from buffer. (*Caution:* The example of Figs. 23.9–23.13 is *not* thread safe.)

*We Call Thread Method sleep Only for Demonstration Purposes*

We call method `sleep` in method `run` of the `Producer` and `Consumer` classes to emphasize the fact that, *in multithreaded applications, it's unpredictable when each thread will perform its task and for how long it will perform the task when it has a processor*. Normally, these thread scheduling issues are beyond the control of the Java developer. In this program, our thread's tasks are quite simple—the `Producer` writes the values 1 to 10 to the buffer, and the `Consumer` reads 10 values from the buffer and adds each value to variable `sum`. Without the `sleep` method call, and if the `Producer` executes first, given today's phenomenally fast processors, the `Producer` would likely complete its task before the `Consumer` got a chance to execute. If the `Consumer` executed first, it would likely consume garbage data ten times, then terminate before the `Producer` could produce the first real value.

*Class UnsynchronizedBuffer Does Not Synchronize Access to the Buffer*

Class `UnsynchronizedBuffer` (Fig. 23.12) implements interface `Buffer` (line 4), but does *not* synchronize access to the buffer's state—we purposely do this to demonstrate the problems that occur when multiple threads access *shared mutable data* in *without* synchronization. Line 6 declares instance variable `buffer` and initializes it to `-1`. This value is used to demonstrate the case in which the `Consumer` attempts to consume a value *before* the `Producer` ever places a value in `buffer`. Again, methods `blockingPut` (lines 9–13) and `blockingGet` (lines 16–20) do *not* synchronize access to the `buffer` instance variable. Method `blockingPut` simply assigns its argument to `buffer` (line 12), and method `blockingGet` simply returns the value of `buffer` (line 19). As you'll see in Fig. 23.13, `UnsynchronizedBuffer` object is shared between the `Producer` and the `Consumer`.

---

```

1 // Fig. 23.12: UnsynchronizedBuffer.java
2 // UnsynchronizedBuffer maintains the shared integer that is accessed by
3 // a producer thread and a consumer thread.
4 public class UnsynchronizedBuffer implements Buffer
5 {
6 private int buffer = -1; // shared by producer and consumer threads
7
8 // place value into buffer
9 public void blockingPut(int value) throws InterruptedException
10 {
11 System.out.printf("Producer writes\t%2d", value);
12 buffer = value;
13 }
14
15 // return value from buffer
16 public int blockingGet() throws InterruptedException
17 {
18 System.out.printf("Consumer reads\t%2d", buffer);
19 return buffer;
20 }
21 } // end class UnsynchronizedBuffer

```

---

**Fig. 23.12** | `UnsynchronizedBuffer` maintains the shared integer that is accessed by a producer thread and a consumer thread. (Caution: The example of Fig. 23.9–Fig. 23.13 is *not* thread safe.)



|                                  |    |    |    |                 |
|----------------------------------|----|----|----|-----------------|
| Consumer reads                   | 3  |    | 3  |                 |
| Producer writes                  | 4  | 10 |    |                 |
| Consumer reads                   | 4  |    | 7  |                 |
| Producer writes                  | 5  | 15 |    |                 |
| Producer writes                  | 6  | 21 |    | — 5 is lost     |
| Producer writes                  | 7  | 28 |    | — 6 is lost     |
| Consumer reads                   | 7  |    | 14 |                 |
| Consumer reads                   | 7  |    | 21 | — 7 read again  |
| Producer writes                  | 8  | 36 |    |                 |
| Consumer reads                   | 8  |    | 29 |                 |
| Consumer reads                   | 8  |    | 37 | — 8 read again  |
| Producer writes                  | 9  | 45 |    |                 |
| Producer writes                  | 10 | 55 |    | — 9 is lost     |
| Producer done producing          |    |    |    |                 |
| Terminating Producer             |    |    |    |                 |
| Consumer reads                   | 10 |    | 47 |                 |
| Consumer reads                   | 10 |    | 57 | — 10 read again |
| Consumer reads                   | 10 |    | 67 | — 10 read again |
| Consumer reads                   | 10 |    | 77 | — 10 read again |
| Consumer read values totaling 77 |    |    |    |                 |
| Terminating Consumer             |    |    |    |                 |

| Action                           | Value | Sum of Produced | Sum of Consumed |                     |
|----------------------------------|-------|-----------------|-----------------|---------------------|
| -----                            | ----- | -----           | -----           |                     |
| Consumer reads                   | -1    |                 | -1              | — reads -1 bad data |
| Producer writes                  | 1     | 1               |                 |                     |
| Consumer reads                   | 1     |                 | 0               |                     |
| Consumer reads                   | 1     |                 | 1               | — 1 read again      |
| Consumer reads                   | 1     |                 | 2               | — 1 read again      |
| Consumer reads                   | 1     |                 | 3               | — 1 read again      |
| Consumer reads                   | 1     |                 | 4               | — 1 read again      |
| Producer writes                  | 2     | 3               |                 |                     |
| Consumer reads                   | 2     |                 | 6               |                     |
| Producer writes                  | 3     | 6               |                 |                     |
| Consumer reads                   | 3     |                 | 9               |                     |
| Producer writes                  | 4     | 10              |                 |                     |
| Consumer reads                   | 4     |                 | 13              |                     |
| Producer writes                  | 5     | 15              |                 |                     |
| Producer writes                  | 6     | 21              |                 | — 5 is lost         |
| Consumer reads                   | 6     |                 | 19              |                     |
| Consumer read values totaling 19 |       |                 |                 |                     |
| Terminating Consumer             |       |                 |                 |                     |
| Producer writes                  | 7     | 28              |                 | — 7 never read      |
| Producer writes                  | 8     | 36              |                 | — 8 never read      |
| Producer writes                  | 9     | 45              |                 | — 9 never read      |
| Producer writes                  | 10    | 55              |                 | — 10 never read     |
| Producer done producing          |       |                 |                 |                     |
| Terminating Producer             |       |                 |                 |                     |

**Fig. 23.13** | Application with two threads manipulating an unsynchronized buffer. (*Caution:* The example of Figs. 23.9–23.13 is *not* thread safe.) (Part 2 of 2.)

Recall from this example's overview that the Producer should execute first and every value produced by the Producer should be consumed exactly once by the Consumer. However, when you study the first output of Fig. 23.13, notice that the Producer writes the values 1, 2 and 3 before the Consumer reads its first value (3). Therefore, the values 1 and 2 are *lost*. Later, the values 5, 6 and 9 are *lost*, while 7 and 8 are *read twice* and 10 is read four times. So the first output produces an incorrect total of 77, instead of the correct total of 55. In the second output, the Consumer reads the value -1 *before* the Producer ever writes a value. The Consumer reads the value 1 *five times* before the Producer writes the value 2. Meanwhile, the values 5, 7, 8, 9 and 10 are all *lost*—the last four because the Consumer terminates *before* the Producer. An incorrect consumer total of 19 is displayed. (Lines in the output where the Producer or Consumer has acted out of order are highlighted.)



### Error-Prevention Tip 23.1

*Access to a shared object by concurrent threads must be controlled carefully or a program may produce incorrect results.*

To solve the problems of *lost* and *duplicated* data, Section 23.6 presents an example in which we use an `ArrayBlockingQueue` (from package `java.util.concurrent`) to synchronize access to the shared object, guaranteeing that each and every value will be processed once and only once.

## 23.6 Producer/Consumer Relationship: `ArrayBlockingQueue`

The best way to synchronize producer and consumer threads is to use classes from Java's `java.util.concurrent` package that *encapsulate the synchronization for you*. Java includes the class `ArrayBlockingQueue`—a fully implemented, *thread-safe buffer class* that implements interface `BlockingQueue`. This interface extends the `Queue` interface discussed in Chapter 16 and declares methods `put` and `take`, the blocking equivalents of `Queue` methods `offer` and `poll`, respectively. Method `put` places an element at the end of the `BlockingQueue`, waiting if the queue is full. Method `take` removes an element from the head of the `BlockingQueue`, waiting if the queue is empty. These methods make class `ArrayBlockingQueue` a good choice for implementing a shared buffer. Because method `put` blocks until there's room in the buffer to write data, and method `take` blocks until there's new data to read, the producer must produce a value first, the consumer correctly consumes only after the producer writes a value and the producer correctly produces the next value (after the first) only after the consumer reads the previous (or first) value. `ArrayBlockingQueue` stores the shared mutable data in an array, the size of which is specified as an `ArrayBlockingQueue` constructor argument. Once created, an `ArrayBlockingQueue` is fixed in size and will not expand to accommodate extra elements.

### Class `BlockingBuffer`

Figures 23.14–23.15 demonstrate a Producer and a Consumer accessing an `ArrayBlockingQueue`. Class `BlockingBuffer` (Fig. 23.14) uses an `ArrayBlockingQueue` object that stores an `Integer` (line 7). Line 11 creates the `ArrayBlockingQueue` and passes 1 to the constructor so that the object holds a single value to mimic the `UnsynchronizedBuffer` example in Fig. 23.12. Lines 7 and 11 (Fig. 23.14) use generics, which we discussed in



Chapters 16–20. We discuss *multiple-element buffers* in Section 23.8. Because our BlockingBuffer class uses the *thread-safe* ArrayBlockingQueue class to manage all of its shared state (the shared buffer in this case), BlockingBuffer is itself *thread safe*, even though we have not implemented the synchronization ourselves.

---

```

1 // Fig. 23.14: BlockingBuffer.java
2 // Creating a synchronized buffer using an ArrayBlockingQueue.
3 import java.util.concurrent.ArrayBlockingQueue;
4
5 public class BlockingBuffer implements Buffer
6 {
7 private final ArrayBlockingQueue<Integer> buffer; // shared buffer
8
9 public BlockingBuffer()
10 {
11 buffer = new ArrayBlockingQueue<Integer>(1);
12 }
13
14 // place value into buffer
15 public void blockingPut(int value) throws InterruptedException
16 {
17 buffer.put(value); // place value in buffer
18 System.out.printf("%s%2d\t%s%d\n", "Producer writes ", value,
19 "Buffer cells occupied: ", buffer.size());
20 }
21
22 // return value from buffer
23 public int blockingGet() throws InterruptedException
24 {
25 int readValue = buffer.take(); // remove value from buffer
26 System.out.printf("%s %2d\t%s%d\n", "Consumer reads ",
27 readValue, "Buffer cells occupied: ", buffer.size());
28
29 return readValue;
30 }
31 } // end class BlockingBuffer

```

---

**Fig. 23.14** | Creating a synchronized buffer using an ArrayBlockingQueue.

BlockingBuffer implements interface Buffer (Fig. 23.9) and uses classes Producer (Fig. 23.10 modified to remove line 28) and Consumer (Fig. 23.11 modified to remove line 28) from the example in Section 23.5. This approach demonstrates encapsulated synchronization—the threads accessing the shared object are unaware that their buffer accesses are now synchronized. The synchronization is handled entirely in the blockingPut and blockingGet methods of BlockingBuffer by calling the synchronized ArrayBlockingQueue methods put and take, respectively. Thus, the Producer and Consumer Runnables are properly synchronized simply by calling the shared object's blockingPut and blockingGet methods.

Line 17 in method blockingPut (Fig. 23.14, lines 15–20) calls the ArrayBlockingQueue object's put method. This method call blocks if necessary until there's room in the buffer to place the value. Method blockingGet (lines 23–30) calls the ArrayBlocking-

Queue object's `take` method (line 25). This method call *blocks* if necessary until there's an element in the buffer to remove. Lines 18–19 and 26–27 use the `ArrayBlockingQueue` object's `size` method to display the total number of elements currently in the `ArrayBlockingQueue`.

### Class *BlockingBufferTest*

Class `BlockingBufferTest` (Fig. 23.15) contains the main method that launches the application. Line 13 creates an `ExecutorService`, and line 16 creates a `BlockingBuffer` object and assigns its reference to the `Buffer` variable `sharedLocation`. Lines 18–19 execute the `Producer` and `Consumer` `Runnable`s. Line 21 calls method `shutdown` to end the application when the threads finish executing the `Producer` and `Consumer` tasks and line 22 waits for the scheduled tasks to complete.

---

```

1 // Fig. 23.15: BlockingBufferTest.java
2 // Two threads manipulating a blocking buffer that properly
3 // implements the producer/consumer relationship.
4 import java.util.concurrent.ExecutorService;
5 import java.util.concurrent.Executors;
6 import java.util.concurrent.TimeUnit;
7
8 public class BlockingBufferTest
9 {
10 public static void main(String[] args) throws InterruptedException
11 {
12 // create new thread pool with two threads
13 ExecutorService executorService = Executors.newCachedThreadPool();
14
15 // create BlockingBuffer to store ints
16 Buffer sharedLocation = new BlockingBuffer();
17
18 executorService.execute(new Producer(sharedLocation));
19 executorService.execute(new Consumer(sharedLocation));
20
21 executorService.shutdown();
22 executorService.awaitTermination(1, TimeUnit.MINUTES);
23 }
24 } // end class BlockingBufferTest

```

|                 |   |                          |
|-----------------|---|--------------------------|
| Producer writes | 1 | Buffer cells occupied: 1 |
| Consumer reads  | 1 | Buffer cells occupied: 0 |
| Producer writes | 2 | Buffer cells occupied: 1 |
| Consumer reads  | 2 | Buffer cells occupied: 0 |
| Producer writes | 3 | Buffer cells occupied: 1 |
| Consumer reads  | 3 | Buffer cells occupied: 0 |
| Producer writes | 4 | Buffer cells occupied: 1 |
| Consumer reads  | 4 | Buffer cells occupied: 0 |
| Producer writes | 5 | Buffer cells occupied: 1 |
| Consumer reads  | 5 | Buffer cells occupied: 0 |
| Producer writes | 6 | Buffer cells occupied: 1 |

**Fig. 23.15** | Two threads manipulating a blocking buffer that properly implements the producer/consumer relationship. (Part I of 2.)

|                                  |    |                        |   |
|----------------------------------|----|------------------------|---|
| Consumer reads                   | 6  | Buffer cells occupied: | 0 |
| Producer writes                  | 7  | Buffer cells occupied: | 1 |
| Consumer reads                   | 7  | Buffer cells occupied: | 0 |
| Producer writes                  | 8  | Buffer cells occupied: | 1 |
| Consumer reads                   | 8  | Buffer cells occupied: | 0 |
| Producer writes                  | 9  | Buffer cells occupied: | 1 |
| Consumer reads                   | 9  | Buffer cells occupied: | 0 |
| Producer writes                  | 10 | Buffer cells occupied: | 1 |
| Producer done producing          |    |                        |   |
| Terminating Producer             |    |                        |   |
| Consumer reads                   | 10 | Buffer cells occupied: | 0 |
| Consumer read values totaling 55 |    |                        |   |
| Terminating Consumer             |    |                        |   |

**Fig. 23.15** | Two threads manipulating a blocking buffer that properly implements the producer/consumer relationship. (Part 2 of 2.)

While methods `put` and `take` of `ArrayBlockingQueue` are properly synchronized, `BlockingBuffer` methods `blockingPut` and `blockingGet` (Fig. 23.14) are not declared to be synchronized. Thus, the statements performed in method `blockingPut`—the `put` operation (line 17) and the output (lines 18–19)—are *not atomic*; nor are the statements in method `blockingGet`—the `take` operation (line 25) and the output (lines 26–27). So there’s no guarantee that each output will occur immediately after the corresponding `put` or `take` operation, and the outputs may appear out of order. Even if they do, the `ArrayBlockingQueue` object is properly synchronizing access to the data, as evidenced by the fact that the sum of values read by the consumer is always correct.

## 23.7 (Advanced) Producer/Consumer Relationship with `synchronized`, `wait`, `notify` and `notifyAll`

[*Note:* This section is intended for *advanced* programmers who want to control synchronization.<sup>2</sup>] The previous example showed how multiple threads can share a single-element buffer in a thread-safe manner by using the `ArrayBlockingQueue` class that encapsulates the synchronization necessary to protect the shared mutable data. For educational purposes, we now explain how you can implement a shared buffer yourself using the synchronized keyword and methods of class `Object`. *Using an `ArrayBlockingQueue` generally results in more-maintainable, better-performing code.*

After identifying the shared mutable data and the *synchronization policy* (i.e., associating the data with a lock that guards it), the next step in synchronizing access to the buffer is to implement methods `blockingGet` and `blockingPut` as synchronized methods. This requires that a thread obtain the *monitor lock* on the `Buffer` object before attempting to access the buffer data, but it does not automatically ensure that threads proceed with an operation only if the buffer is in the proper state. We need a way to allow our threads to *wait*, depending on whether certain conditions are true. In the case of placing a new item in the buffer, the condition that allows the operation to proceed is that the *buffer is not full*.

2. For detailed information on `wait`, `notify` and `notifyAll`, see Chapter 14 of *Java Concurrency in Practice* by Brian Goetz, et al., Addison-Wesley Professional, 2006.

In the case of fetching an item from the buffer, the condition that allows the operation to proceed is that the *buffer is not empty*. If the condition in question is true, the operation may proceed; if it's false, the thread must *wait* until it becomes true. When a thread is waiting on a condition, it's removed from contention for the processor and placed into the *waiting* state and the lock it holds is released.

### Methods **wait**, **notify** and **notifyAll**

Object methods **wait**, **notify** and **notifyAll** can be used with conditions to make threads *wait* when they cannot perform their tasks. If a thread obtains the *monitor lock* on an object, then determines that it cannot continue with its task on that object until some condition is satisfied, the thread can call Object method **wait** on the synchronized object; this *releases the monitor lock* on the object, and the thread waits in the *waiting* state while the other threads try to enter the object's synchronized statement(s) or method(s). When a thread executing a synchronized statement (or method) completes or satisfies the condition on which another thread may be waiting, it can call Object method **notify** on the synchronized object to allow a waiting thread to transition to the *runnable* state again. At this point, the thread that was transitioned from the *waiting* state to the *runnable* state can attempt to *reacquire the monitor lock* on the object. Even if the thread is able to reacquire the monitor lock, it still might not be able to perform its task at this time—in which case the thread will reenter the *waiting* state and implicitly *release the monitor lock*. If a thread calls **notifyAll** on the synchronized object, then *all* the threads waiting for the monitor lock become eligible to *reacquire the lock* (that is, they all transition to the *runnable* state).

Remember that only *one* thread at a time can obtain the monitor lock on the object—other threads that attempt to acquire the same monitor lock will be *blocked* until the monitor lock becomes available again (i.e., until no other thread is executing in a synchronized statement on that object).



### Common Programming Error 23.1

*It's an error if a thread issues a **wait**, a **notify** or a **notifyAll** on an object without having acquired a lock for it. This causes an **IllegalMonitorStateException**.*



### Error-Prevention Tip 23.2

*It's a good practice to use **notifyAll** to notify waiting threads to become runnable. Doing so avoids the possibility that your program would forget about waiting threads, which would otherwise starve.*

Figures 23.16 and 23.17 demonstrate a Producer and a Consumer accessing a shared buffer with synchronization. In this case, the Producer always produces a value *first*, the Consumer correctly consumes only *after* the Producer produces a value and the Producer correctly produces the next value only after the Consumer consumes the previous (or first) value. We reuse interface `Buffer` and classes `Producer` and `Consumer` from the example in Section 23.5, except that line 28 is removed from class `Producer` and class `Consumer`.

### Class **SynchronizedBuffer**

The synchronization is handled in class `SynchronizedBuffer`'s `blockingPut` and `blockingGet` methods (Fig. 23.16), which implements interface `Buffer` (line 4). Thus, the `Producer`'s and `Consumer`'s `run` methods simply call the shared object's synchronized `blockingPut` and

blockingGet methods. Again, we output messages from this class's synchronized methods for demonstration purposes only—I/O *should not* be performed in synchronized blocks, because it's important to minimize the amount of time that an object is "locked."

---

```

1 // Fig. 23.16: SynchronizedBuffer.java
2 // Synchronizing access to shared mutable data using Object
3 // methods wait and notifyAll.
4 public class SynchronizedBuffer implements Buffer
5 {
6 private int buffer = -1; // shared by producer and consumer threads
7 private boolean occupied = false;
8
9 // place value into buffer
10 public synchronized void blockingPut(int value)
11 throws InterruptedException
12 {
13 // while there are no empty locations, place thread in waiting state
14 while (occupied)
15 {
16 // output thread information and buffer information, then wait
17 System.out.println("Producer tries to write."); // for demo only
18 displayState("Buffer full. Producer waits."); // for demo only
19 wait();
20 }
21
22 buffer = value; // set new buffer value
23
24 // indicate producer cannot store another value
25 // until consumer retrieves current buffer value
26 occupied = true;
27
28 displayState("Producer writes " + buffer); // for demo only
29
30 notifyAll(); // tell waiting thread(s) to enter runnable state
31 } // end method blockingPut; releases lock on SynchronizedBuffer
32
33 // return value from buffer
34 public synchronized int blockingGet() throws InterruptedException
35 {
36 // while no data to read, place thread in waiting state
37 while (!occupied)
38 {
39 // output thread information and buffer information, then wait
40 System.out.println("Consumer tries to read."); // for demo only
41 displayState("Buffer empty. Consumer waits."); // for demo only
42 wait();
43 }
44
45 // indicate that producer can store another value
46 // because consumer just retrieved buffer value
47 occupied = false;

```

---

**Fig. 23.16** | Synchronizing access to shared mutable data using Object methods wait and notifyAll. (Part I of 2.)

---

```

48
49 displayState("Consumer reads " + buffer); // for demo only
50
51 notifyAll(); // tell waiting thread(s) to enter runnable state
52
53 return buffer;
54 } // end method blockingGet; releases lock on SynchronizedBuffer
55
56 // display current operation and buffer state; for demo only
57 private synchronized void displayState(String operation)
58 {
59 System.out.printf("%-40s%d\t\t%b%n\n", operation, buffer,
60 occupied);
61 }
62 } // end class SynchronizedBuffer

```

---

**Fig. 23.16** | Synchronizing access to shared mutable data using Object methods wait and notifyAll. (Part 2 of 2.)

### *Fields and Methods of Class SynchronizedBuffer*

Class `SynchronizedBuffer` contains fields `buffer` (line 6) and `occupied` (line 7)—you must synchronize access to *both* fields to ensure that class `SynchronizedBuffer` is thread safe. Methods `blockingPut` (lines 10–31) and `blockingGet` (lines 34–54) are declared as `synchronized`—only *one* thread can call either of these methods at a time on a particular `SynchronizedBuffer` object. Field `occupied` is used to determine whether it's the Producer's or the Consumer's turn to perform a task. This field is used in conditional expressions in both the `blockingPut` and `blockingGet` methods. If `occupied` is `false`, then `buffer` is empty, so the Consumer cannot read the value of `buffer`, but the Producer can place a value into `buffer`. If `occupied` is `true`, the Consumer can read a value from `buffer`, but the Producer cannot place a value into `buffer`.

### *Method blockingPut and the Producer Thread*

When the Producer thread's run method invokes `synchronized` method `blockingPut`, the thread implicitly attempts to acquire the `SynchronizedBuffer` object's monitor lock. If the monitor lock is available, the Producer thread *implicitly* acquires the lock. Then the loop at lines 14–20 first determines whether `occupied` is `true`. If so, `buffer` is *full* and we want to wait until the buffer is empty, so line 17 outputs a message indicating that the Producer thread is trying to write a value, and line 18 invokes method `displayState` (lines 57–61) to output another message indicating that `buffer` is *full* and that the Producer thread is *waiting* until there's space. Line 19 invokes method `wait` (inherited from `Object` by `SynchronizedBuffer`) to place the thread that called method `blockingPut` (i.e., the Producer thread) in the *waiting* state for the `SynchronizedBuffer` object. The call to `wait` causes the calling thread to *implicitly* release the lock on the `SynchronizedBuffer` object. This is important because the thread cannot currently perform its task and because other threads (in this case, the Consumer) should be allowed to access the object to allow the condition (`occupied`) to change. Now another thread can attempt to acquire the `SynchronizedBuffer` object's lock and invoke the object's `blockingPut` or `blockingGet` method.

The Producer thread remains in the *waiting* state until another thread *notifies* the Producer that it may proceed—at which point the Producer returns to the *runnable* state and attempts to implicitly reacquire the lock on the SynchronizedBuffer object. If the lock is available, the Producer thread reacquires it, and method `blockingPut` continues executing with the next statement after the `wait` call. Because `wait` is called in a loop, the loop-continuation condition is tested again to determine whether the thread can proceed. If not, then `wait` is invoked again—otherwise, method `blockingPut` continues with the next statement after the loop.

Line 22 in method `blockingPut` assigns the value to the buffer. Line 26 sets `occupied` to `true` to indicate that the buffer now contains a value (i.e., a consumer can read the value, but a Producer cannot yet put another value there). Line 28 invokes method `displayState` to output a message indicating that the Producer is writing a new value into the buffer. Line 30 invokes method `notifyAll` (inherited from `Object`). If any threads are *waiting* on the SynchronizedBuffer object's monitor lock, those threads enter the *runnable* state and can now attempt to *reacquire the lock*. Method `notifyAll` returns immediately, and method `blockingPut` then returns to the caller (i.e., the Producer's run method). When method `blockingPut` returns, it *implicitly releases the monitor lock* on the SynchronizedBuffer object.

### ***Method `blockingGet` and the Consumer Thread***

Methods `blockingGet` and `blockingPut` are implemented similarly. When the Consumer thread's run method invokes synchronized method `blockingGet`, the thread attempts to *acquire the monitor lock* on the SynchronizedBuffer object. If the lock is available, the Consumer thread acquires it. Then the `while` loop at lines 37–43 determines whether `occupied` is `false`. If so, the buffer is empty, so line 40 outputs a message indicating that the Consumer thread is trying to read a value, and line 41 invokes method `displayState` to output a message indicating that the buffer is *empty* and that the Consumer thread is *waiting*. Line 42 invokes method `wait` to place the thread that called method `blockingGet` (i.e., the Consumer) in the *waiting* state for the SynchronizedBuffer object. Again, the call to `wait` causes the calling thread to *implicitly release the lock* on the SynchronizedBuffer object, so another thread can attempt to acquire the SynchronizedBuffer object's lock and invoke the object's `blockingPut` or `blockingGet` method. If the lock on the SynchronizedBuffer is not available (e.g., if the Producer has not yet returned from method `blockingPut`), the Consumer is *blocked* until the lock becomes available.

The Consumer thread remains in the *waiting* state until it's *notified* by another thread that it may proceed—at which point the Consumer thread returns to the *runnable* state and attempts to *implicitly reacquire the lock* on the SynchronizedBuffer object. If the lock is available, the Consumer reacquires it, and method `blockingGet` continues executing with the next statement after `wait`. Because `wait` is called in a loop, the loop-continuation condition is tested again to determine whether the thread can proceed with its execution. If not, `wait` is invoked again—otherwise, method `blockingGet` continues with the next statement after the loop. Line 47 sets `occupied` to `false` to indicate that buffer is now empty (i.e., a Consumer cannot read the value, but a Producer can place another value in buffer), line 49 calls method `displayState` to indicate that the consumer is reading and line 51 invokes method `notifyAll`. If any threads are in the *waiting* state for the lock on

this `SynchronizedBuffer` object, they enter the *runnable* state and can now attempt to *reacquire the lock*. Method `notifyAll` returns immediately, then method `blockingGet` returns the value of `buffer` to its caller. When method `blockingGet` returns, the lock on the `SynchronizedBuffer` object is *implicitly released*.



### Error-Prevention Tip 23.3

*Always invoke method `wait` in a loop that tests the condition the task is waiting on. It's possible that a thread will reenter the *runnable* state (via a timed wait or another thread calling `notifyAll`) before the condition is satisfied. Testing the condition again ensures that the thread will not erroneously execute if it was notified early.*

### Method `displayState` Is Also *synchronized*

Notice that method `displayState` is a *synchronized* method. This is important because it, too, reads the `SynchronizedBuffer`'s shared mutable data. Though only one thread at a time may acquire a given object's lock, one thread may acquire the same object's lock *multiple* times—this is known as a **reentrant lock** and enables one *synchronized* method to invoke another on the same object.

### Testing Class `SynchronizedBuffer`

Class `SharedBufferTest2` (Fig. 23.17) is similar to class `SharedBufferTest` (Fig. 23.13). `SharedBufferTest2` contains method `main` (Fig. 23.17, lines 9–26), which launches the application. Line 12 creates an `ExecutorService` to run the `Producer` and `Consumer` tasks. Line 15 creates a `SynchronizedBuffer` object and assigns its reference to `Buffer` variable `sharedLocation`. This object stores the data that will be shared between the `Producer` and `Consumer`. Lines 17–18 display the column heads for the output. Lines 21–22 execute a `Producer` and a `Consumer`. Finally, line 24 calls method `shutdown` to end the application when the `Producer` and `Consumer` complete their tasks and line 25 waits for the scheduled tasks to complete. When method `main` ends (line 26), the main thread of execution terminates.

---

```

1 // Fig. 23.17: SharedBufferTest2.java
2 // Two threads correctly manipulating a synchronized buffer.
3 import java.util.concurrent.ExecutorService;
4 import java.util.concurrent.Executors;
5 import java.util.concurrent.TimeUnit;
6
7 public class SharedBufferTest2
8 {
9 public static void main(String[] args) throws InterruptedException
10 {
11 // create a newCachedThreadPool
12 ExecutorService executorService = Executors.newCachedThreadPool();
13
14 // create SynchronizedBuffer to store ints
15 Buffer sharedLocation = new SynchronizedBuffer();
16
17 System.out.printf("%-40s%\t\t%s%n%-40s%s%n", "Operation",
18 "Buffer", "Occupied", "-----", "-----\t\t-----");
19

```

---

**Fig. 23.17** | Two threads correctly manipulating a synchronized buffer. (Part I of 3.)



```

20 // execute the Producer and Consumer tasks
21 executorService.execute(new Producer(sharedLocation));
22 executorService.execute(new Consumer(sharedLocation));
23
24 executorService.shutdown();
25 executorService.awaitTermination(1, TimeUnit.MINUTES);
26 }
27 } // end class SharedBufferTest2

```

| Operation<br>-----                                       | Buffer<br>----- | Occupied<br>----- |
|----------------------------------------------------------|-----------------|-------------------|
| Consumer tries to read.<br>Buffer empty. Consumer waits. | -1              | false             |
| Producer writes 1                                        | 1               | true              |
| Consumer reads 1                                         | 1               | false             |
| Consumer tries to read.<br>Buffer empty. Consumer waits. | 1               | false             |
| Producer writes 2                                        | 2               | true              |
| Consumer reads 2                                         | 2               | false             |
| Producer writes 3                                        | 3               | true              |
| Consumer reads 3                                         | 3               | false             |
| Producer writes 4                                        | 4               | true              |
| Producer tries to write.<br>Buffer full. Producer waits. | 4               | true              |
| Consumer reads 4                                         | 4               | false             |
| Producer writes 5                                        | 5               | true              |
| Consumer reads 5                                         | 5               | false             |
| Producer writes 6                                        | 6               | true              |
| Producer tries to write.<br>Buffer full. Producer waits. | 6               | true              |
| Consumer reads 6                                         | 6               | false             |
| Producer writes 7                                        | 7               | true              |
| Producer tries to write.<br>Buffer full. Producer waits. | 7               | true              |
| Consumer reads 7                                         | 7               | false             |
| Producer writes 8                                        | 8               | true              |
| Consumer reads 8                                         | 8               | false             |
| Consumer tries to read.<br>Buffer empty. Consumer waits. | 8               | false             |

**Fig. 23.17** | Two threads correctly manipulating a synchronized buffer. (Part 2 of 3.)

|                                                          |    |       |
|----------------------------------------------------------|----|-------|
| Producer writes 9                                        | 9  | true  |
| Consumer reads 9                                         | 9  | false |
| Consumer tries to read.<br>Buffer empty. Consumer waits. | 9  | false |
| Producer writes 10                                       | 10 | true  |
| Consumer reads 10                                        | 10 | false |
| Producer done producing<br>Terminating Producer          |    |       |
| Consumer read values totaling 55<br>Terminating Consumer |    |       |

**Fig. 23.17** | Two threads correctly manipulating a synchronized buffer. (Part 3 of 3.)

Study the outputs in Fig. 23.17. Observe that *every integer produced is consumed exactly once—no values are lost, and no values are consumed more than once*. The synchronization ensures that the Producer produces a value only when the buffer is *empty* and the Consumer consumes only when the buffer is *full*. The Producer always goes first, the Consumer *waits* if the Producer has not produced since the Consumer last consumed, and the Producer waits if the Consumer has not yet consumed the value that the Producer most recently produced. Execute this program several times to confirm that every integer produced is consumed exactly *once*. In the sample output, note the highlighted lines indicating when the Producer and Consumer must *wait* to perform their respective tasks.

## 23.8 (Advanced) Producer/Consumer Relationship: Bounded Buffers

The program in Section 23.7 uses thread synchronization to guarantee that two threads manipulate data in a shared buffer correctly. However, the application may not perform optimally. If the two threads operate at different speeds, one of them will spend more (or most) of its time waiting. For example, in the program in Section 23.7 we shared a single integer variable between the two threads. If the Producer thread produces values *faster* than the Consumer can consume them, then the Producer thread *waits* for the Consumer, because there are no other locations in the buffer in which to place the next value. Similarly, if the Consumer consumes values *faster* than the Producer produces them, the Consumer *waits* until the Producer places the next value in the shared buffer. Even when we have threads that operate at the *same* relative speeds, those threads may occasionally become “out of sync” over a period of time, causing one of them to *wait* for the other.



### Performance Tip 23.3

We cannot make assumptions about the relative speeds of concurrent threads—interactions that occur with the operating system, the network, the user and other components can cause the threads to operate at different and ever-changing speeds. When this happens, threads wait. When threads wait excessively, programs become less efficient, interactive programs become less responsive and applications suffer longer delays.

### *Bounded Buffers*

To minimize the amount of waiting time for threads that share resources and operate at the same average speeds, we can implement a **bounded buffer** that provides a fixed number of buffer cells into which the Producer can place values, and from which the Consumer can retrieve those values. (In fact, we've already done this with the `ArrayBlockingQueue` class in Section 23.6.) If the Producer temporarily produces values faster than the Consumer can consume them, the Producer can write additional values into the extra buffer cells, if any are available. This capability enables the Producer to perform its task even though the Consumer is not ready to retrieve the current value being produced. Similarly, if the Consumer consumes faster than the Producer produces new values, the Consumer can read additional values (if there are any) from the buffer. This enables the Consumer to keep busy even though the Producer is not ready to produce additional values. An example of the producer/consumer relationship that uses a bounded buffer is video streaming, which we discussed in Section 23.1.

Even a *bounded buffer* is inappropriate if the Producer and the Consumer operate consistently at different speeds. If the Consumer always executes faster than the Producer, then a buffer containing one location is enough. If the Producer always executes faster, only a buffer with an “infinite” number of locations would be able to absorb the extra production. However, if the Producer and Consumer execute at about the same average speed, a bounded buffer helps to smooth the effects of any occasional speeding up or slowing down in either thread's execution.

The key to using a *bounded buffer* with a Producer and Consumer that operate at about the same speed is to provide the buffer with enough locations to handle the anticipated “extra” production. If, over a period of time, we determine that the Producer often produces as many as three more values than the Consumer can consume, we can provide a buffer of at least three cells to handle the extra production. Making the buffer too small would cause threads to wait longer.

[Note: As we mention in Fig. 23.22, `ArrayBlockingQueue` can work with multiple producers and multiple consumers. For example, a factory that produces its product very fast will need to have many more delivery trucks (i.e., consumers) to remove those products quickly from the warehousing area (i.e., the bounded buffer) so that the factory can continue to produce products at full capacity.]



#### **Performance Tip 23.4**

*Even when using a bounded buffer, it's possible that a producer thread could fill the buffer, which would force the producer to wait until a consumer consumed a value to free an element in the buffer. Similarly, if the buffer is empty at any given time, a consumer thread must wait until the producer produces another value. The key to using a bounded buffer is to optimize the buffer size to minimize the amount of thread wait time, while not wasting space.*

### ***Bounded Buffers Using `ArrayBlockingQueue`***

The simplest way to implement a bounded buffer is to use an `ArrayBlockingQueue` for the buffer so that *all of the synchronization details are handled for you*. This can be done by modifying the example from Section 23.6 to pass the desired size for the bounded buffer into the `ArrayBlockingQueue` constructor. Rather than repeat our previous `ArrayBlockingQueue` example with a different size, we instead present an example that illustrates how you can

build a bounded buffer yourself. Again, using an `ArrayBlockingQueue` will result in more-maintainable and better-performing code. In Exercise 23.13, we ask you to reimplement this section's example, using the Java Concurrency API techniques presented in Section 23.9.

### *Implementing Your Own Bounded Buffer as a Circular Buffer*

The program in Figs. 23.18 and 23.19 demonstrates a `Producer` and a `Consumer` accessing a *bounded buffer with synchronization*. Again, we reuse interface `Buffer` and classes `Producer` and `Consumer` from the example in Section 23.5, except that line 28 is removed from class `Producer` and class `Consumer`. We implement the bounded buffer in class `CircularBuffer` (Fig. 23.18) as a **circular buffer** that uses a shared array of three elements. A circular buffer writes into and reads from the array elements in order, beginning at the first cell and moving toward the last. When a `Producer` or `Consumer` reaches the last element, it returns to the first and begins writing or reading, respectively, from there. In this version of the producer/consumer relationship, the `Consumer` consumes a value only when the array is not empty and the `Producer` produces a value only when the array is not full. Once again, the output statements used in this class's synchronized methods are for *demonstration purposes only*.

---

```

1 // Fig. 23.18: CircularBuffer.java
2 // Synchronizing access to a shared three-element bounded buffer.
3 public class CircularBuffer implements Buffer
4 {
5 private final int[] buffer = {-1, -1, -1}; // shared buffer
6
7 private int occupiedCells = 0; // count number of buffers used
8 private int writeIndex = 0; // index of next element to write to
9 private int readIndex = 0; // index of next element to read
10
11 // place value into buffer
12 public synchronized void blockingPut(int value)
13 throws InterruptedException
14 {
15 // wait until buffer has space available, then write value;
16 // while no empty locations, place thread in blocked state
17 while (occupiedCells == buffer.length)
18 {
19 System.out.printf("Buffer is full. Producer waits.%n");
20 wait(); // wait until a buffer cell is free
21 } // end while
22
23 buffer[writeIndex] = value; // set new buffer value
24
25 // update circular write index
26 writeIndex = (writeIndex + 1) % buffer.length;
27
28 ++occupiedCells; // one more buffer cell is full
29 displayState("Producer writes " + value);
30 notifyAll(); // notify threads waiting to read from buffer
31 }

```

---

**Fig. 23.18** | Synchronizing access to a shared three-element bounded buffer. (Part I of 3.)

---

```

32
33 // return value from buffer
34 public synchronized int blockingGet() throws InterruptedException
35 {
36 // wait until buffer has data, then read value;
37 // while no data to read, place thread in waiting state
38 while (occupiedCells == 0)
39 {
40 System.out.printf("Buffer is empty. Consumer waits.%n");
41 wait(); // wait until a buffer cell is filled
42 } // end while
43
44 int readValue = buffer[readIndex]; // read value from buffer
45
46 // update circular read index
47 readIndex = (readIndex + 1) % buffer.length;
48
49 --occupiedCells; // one fewer buffer cells are occupied
50 displayState("Consumer reads " + readValue);
51 notifyAll(); // notify threads waiting to write to buffer
52
53 return readValue;
54 }
55
56 // display current operation and buffer state
57 public synchronized void displayState(String operation)
58 {
59 // output operation and number of occupied buffer cells
60 System.out.printf("%s%s%d)%n%s", operation,
61 " (buffer cells occupied: ", occupiedCells, "buffer cells: ");
62
63 for (int value : buffer)
64 System.out.printf(" %2d ", value); // output values in buffer
65
66 System.out.printf("%n
67 ");
68
69 for (int i = 0; i < buffer.length; i++)
70 System.out.print("---- ");
71
72 System.out.printf("%n
73 ");
74
75 for (int i = 0; i < buffer.length; i++)
76 {
77 if (i == writeIndex && i == readIndex)
78 System.out.print(" WR"); // both write and read index
79 else if (i == writeIndex)
80 System.out.print(" W "); // just write index
81 else if (i == readIndex)
82 System.out.print(" R "); // just read index
83 else
84 System.out.print(" "); // neither index
85 }
86 }

```

---

**Fig. 23.18** | Synchronizing access to a shared three-element bounded buffer. (Part 2 of 3.)

---

```

85 System.out.printf("%n%n");
86 }
87 } // end class CircularBuffer

```

---

**Fig. 23.18** | Synchronizing access to a shared three-element bounded buffer. (Part 3 of 3.)

Line 5 initializes array `buffer` as a three-element `int` array that represents the circular buffer. Variable `occupiedCells` (line 7) counts the number of elements in `buffer` that contain data to be read. When `occupiedCells` is 0, the circular buffer is *empty* and the Consumer must *wait*—when `occupiedCells` is 3 (the size of the circular buffer), the circular buffer is *full* and the Producer must *wait*. Variable `writeIndex` (line 8) indicates the next location in which a value can be placed by a Producer. Variable `readIndex` (line 9) indicates the position from which the next value can be read by a Consumer. `CircularBuffer`'s instance variables are *all* part of the class's shared mutable data, thus access to all of these variables must be synchronized to ensure that a `CircularBuffer` is thread safe.

#### ***CircularBuffer Method blockingPut***

`CircularBuffer` method `blockingPut` (lines 12–31) performs the same tasks as in Fig. 23.16, with a few modifications. The loop at lines 17–21 determines whether the Producer must *wait* (i.e., all buffer cells are *full*). If so, line 19 indicates that the Producer is *waiting* to perform its task. Then line 20 invokes method `wait`, causing the Producer thread to *release* the `CircularBuffer`'s *lock* and *wait* until there's space for a new value to be written into the buffer. When execution continues at line 23 after the `while` loop, the value written by the Producer is placed in the circular buffer at location `writeIndex`. Then line 26 updates `writeIndex` for the next call to `CircularBuffer` method `blockingPut`. This line is the key to the buffer's *circularity*. When `writeIndex` is incremented *past the end of the buffer*, the line sets it to 0. Line 28 increments `occupiedCells`, because there's now one more value in the buffer that the Consumer can read. Next, line 29 invokes method `displayState` (lines 57–86) to update the output with the value produced, the number of occupied buffer cells, the contents of the buffer cells and the current `writeIndex` and `readIndex`. Line 30 invokes method `notifyAll` to transition *waiting* threads to the *runnable* state, so that a waiting Consumer thread (if there is one) can now try again to read a value from the buffer.

#### ***CircularBuffer Method blockingGet***

`CircularBuffer` method `blockingGet` (lines 34–54) also performs the same tasks as it did in Fig. 23.16, with a few minor modifications. The loop at lines 38–42 (Fig. 23.18) determines whether the Consumer must *wait* (i.e., all buffer cells are *empty*). If the Consumer must *wait*, line 40 updates the output to indicate that the Consumer is *waiting* to perform its task. Then line 41 invokes method `wait`, causing the current thread to *release the lock* on the `CircularBuffer` and *wait* until data is available to read. When execution eventually continues at line 44 after a `notifyAll` call from the Producer, `readValue` is assigned the value at location `readIndex` in the circular buffer. Then line 47 updates `readIndex` for the next call to `CircularBuffer` method `blockingGet`. This line and line 26 implement the *circularity* of the buffer. Line 49 decrements `occupiedCells`, because there's now one more position in the buffer in which the Producer thread can place a value. Line 50 invokes method `displayState` to update the output with the consumed value, the number

of occupied buffer cells, the contents of the buffer cells and the current `writeIndex` and `readIndex`. Line 51 invokes method `notifyAll` to allow any `Producer` threads *waiting to write* into the `CircularBuffer` object to attempt to write again. Then line 53 returns the consumed value to the caller.

### ***CircularBuffer Method displayState***

Method `displayState` (lines 57–86) outputs the application's state. Lines 63–64 output the values of the buffer cells. Line 64 uses method `printf` with a "%2d" format specifier to print the contents of each buffer with a leading space if it's a single digit. Lines 71–83 output the current `writeIndex` and `readIndex` with the letters `W` and `R`, respectively. Once again, `displayState` is a synchronized method because it accesses class `CircularBuffer`'s shared mutable data.

### ***Testing Class CircularBuffer***

Class `CircularBufferTest` (Fig. 23.19) contains the main method that launches the application. Line 12 creates the `ExecutorService`, and line 15 creates a `CircularBuffer` object and assigns its reference to `CircularBuffer` variable `sharedLocation`. Line 18 invokes the `CircularBuffer`'s `displayState` method to show the initial state of the buffer. Lines 21–22 execute the `Producer` and `Consumer` tasks. Line 24 calls method `shutdown` to end the application when the threads complete the `Producer` and `Consumer` tasks and line 25 waits for the tasks to complete.

---

```

1 // Fig. 23.19: CircularBufferTest.java
2 // Producer and Consumer threads correctly manipulating a circular buffer.
3 import java.util.concurrent.ExecutorService;
4 import java.util.concurrent.Executors;
5 import java.util.concurrent.TimeUnit;
6
7 public class CircularBufferTest
8 {
9 public static void main(String[] args) throws InterruptedException
10 {
11 // create new thread pool with two threads
12 ExecutorService executorService = Executors.newCachedThreadPool();
13
14 // create CircularBuffer to store ints
15 CircularBuffer sharedLocation = new CircularBuffer();
16
17 // display the initial state of the CircularBuffer
18 sharedLocation.displayState("Initial State");
19
20 // execute the Producer and Consumer tasks
21 executorService.execute(new Producer(sharedLocation));
22 executorService.execute(new Consumer(sharedLocation));
23
24 executorService.shutdown();
25 executorService.awaitTermination(1, TimeUnit.MINUTES);
26 }
27 } // end class CircularBufferTest

```

---

**Fig. 23.19** | Producer and Consumer threads correctly manipulating a circular buffer. (Part I of 3.)

```

Initial State (buffer cells occupied: 0)
buffer cells: -1 -1 -1

 WR

Producer writes 1 (buffer cells occupied: 1)
buffer cells: 1 -1 -1

 R W

Consumer reads 1 (buffer cells occupied: 0)
buffer cells: 1 -1 -1

 WR

Buffer is empty. Consumer waits.
Producer writes 2 (buffer cells occupied: 1)
buffer cells: 1 2 -1

 R W

Consumer reads 2 (buffer cells occupied: 0)
buffer cells: 1 2 -1

 WR

Producer writes 3 (buffer cells occupied: 1)
buffer cells: 1 2 3

 W R

Consumer reads 3 (buffer cells occupied: 0)
buffer cells: 1 2 3

 WR

Producer writes 4 (buffer cells occupied: 1)
buffer cells: 4 2 3

 R W

Producer writes 5 (buffer cells occupied: 2)
buffer cells: 4 5 3

 R W

Consumer reads 4 (buffer cells occupied: 1)
buffer cells: 4 5 3

 R W

Producer writes 6 (buffer cells occupied: 2)
buffer cells: 4 5 6

 W R

```

**Fig. 23.19** | Producer and Consumer threads correctly manipulating a circular buffer. (Part 2 of 3.)



Producer writes 7 (buffer cells occupied: 3)

buffer cells:    7    5    6  
 -----  
                   WR

Consumer reads 5 (buffer cells occupied: 2)

buffer cells:    7    5    6  
 -----  
           W        R

Producer writes 8 (buffer cells occupied: 3)

buffer cells:    7    8    6  
 -----  
                   WR

Consumer reads 6 (buffer cells occupied: 2)

buffer cells:    7    8    6  
 -----  
           R        W

Consumer reads 7 (buffer cells occupied: 1)

buffer cells:    7    8    6  
 -----  
           R        W

Producer writes 9 (buffer cells occupied: 2)

buffer cells:    7    8    9  
 -----  
           W        R

Consumer reads 8 (buffer cells occupied: 1)

buffer cells:    7    8    9  
 -----  
           W        R

Consumer reads 9 (buffer cells occupied: 0)

buffer cells:    7    8    9  
 -----  
           WR

Producer writes 10 (buffer cells occupied: 1)

buffer cells:    10    8    9  
 -----  
           R        W

Producer done producing

Terminating Producer

Consumer reads 10 (buffer cells occupied: 0)

buffer cells:    10    8    9  
 -----  
           WR

Consumer read values totaling: 55

Terminating Consumer

**Fig. 23.19** | Producer and Consumer threads correctly manipulating a circular buffer. (Part 3 of 3.)

Each time the Producer writes a value or the Consumer reads a value, the program outputs a message indicating the action performed (a read or a write), the contents of buffer, and the location of `writeIndex` and `readIndex`. In the output of Fig. 23.19, the Producer first writes the value 1. The buffer then contains the value 1 in the first cell and the value -1 (the default value that we use for output purposes) in the other two cells. The write index is updated to the second cell, while the read index stays at the first cell. Next, the Consumer reads 1. The buffer contains the same values, but the read index has been updated to the second cell. The Consumer then tries to read again, but the buffer is empty and the Consumer is forced to wait. Only once in this execution of the program was it necessary for either thread to wait.

## 23.9 (Advanced) Producer/Consumer Relationship: The Lock and Condition Interfaces

Though the `synchronized` keyword provides for most basic thread-synchronization needs, Java provides other tools to assist in developing concurrent programs. In this section, we discuss the `Lock` and `Condition` interfaces. These interfaces give you more precise control over thread synchronization, but are more complicated to use. *Only the most advanced programmers should use these interfaces.*

### Interface `Lock` and Class `ReentrantLock`

Any object can contain a reference to an object that implements the `Lock` interface (of package `java.util.concurrent.locks`). A thread calls the `Lock`'s `lock` method (analogous to entering a `synchronized` block) to acquire the lock. Once a `Lock` has been obtained by one thread, the `Lock` object will not allow another thread to obtain the `Lock` until the first thread releases the `Lock` (by calling the `Lock`'s `unlock` method—analogous to exiting a `synchronized` block). If several threads are trying to call method `lock` on the same `Lock` object at the same time, only one of these threads can obtain the lock—all the others are placed in the *waiting* state for that lock. When a thread calls method `unlock`, the lock on the object is released and a waiting thread attempting to lock the object proceeds.



#### Error-Prevention Tip 23.4

*Place calls to `Lock` method `unlock` in a `finally` block. If an exception is thrown, `unlock` must still be called or deadlock could occur.*

Class `ReentrantLock` (of package `java.util.concurrent.locks`) is a basic implementation of the `Lock` interface. The constructor for a `ReentrantLock` takes a `boolean` argument that specifies whether the lock has a **fairness policy**. If the argument is `true`, the `ReentrantLock`'s fairness policy is “the longest-waiting thread will acquire the lock when it's available.” Such a fairness policy guarantees that *indefinite postponement* (also called *starvation*) cannot occur. If the fairness policy argument is set to `false`, there's no guarantee as to which waiting thread will acquire the lock when it's available.



#### Software Engineering Observation 23.6

*Using a `ReentrantLock` with a fairness policy avoids indefinite postponement.*



### Performance Tip 23.5

*In most cases, a non-fair lock is preferable, because using a fair lock can decrease program performance.*

### Condition Objects and Interface Condition

If a thread that owns a Lock determines that it cannot continue with its task until some condition is satisfied, the thread can wait on a **condition object**. Using Lock objects allows you to explicitly declare the condition objects on which a thread may need to wait. For example, in the producer/consumer relationship, producers can wait on *one* object and consumers can wait on *another*. This is not possible when using the synchronized keywords and an object's built-in monitor lock. Condition objects are associated with a specific Lock and are created by calling a Lock's **newCondition** method, which returns an object that implements the **Condition** interface (of package `java.util.concurrent.locks`). To wait on a condition object, the thread can call the Condition's **await** method (analogous to Object method `wait`). This immediately releases the associated Lock and places the thread in the *waiting* state for that Condition. Other threads can then try to obtain the Lock. When a *runnable* thread completes a task and determines that the *waiting* thread can now continue, the *runnable* thread can call Condition method **signal** (analogous to Object method `notify`) to allow a thread in that Condition's *waiting* state to return to the *runnable* state. At this point, the thread that transitioned from the *waiting* state to the *runnable* state can attempt to reacquire the Lock. Even if it's able to *reacquire* the Lock, the thread still might not be able to perform its task at this time—in which case the thread can call the Condition's **await** method to *release* the Lock and reenter the *waiting* state. If multiple threads are in a Condition's *waiting* state when **signal** is called, the default implementation of Condition signals the longest-waiting thread to transition to the *runnable* state. If a thread calls Condition method **signalAll** (analogous to Object method `notifyAll`), then all the threads waiting for that condition transition to the *runnable* state and become eligible to reacquire the Lock. Only one of those threads can obtain the Lock on the object—the others will wait until the Lock becomes available again. If the Lock has a *fairness policy*, the longest-waiting thread acquires the Lock. When a thread is finished with a shared object, it must call method `unlock` to release the Lock.



### Error-Prevention Tip 23.5

*When multiple threads manipulate a shared object using locks, ensure that if one thread calls method **await** to enter the waiting state for a condition object, a separate thread eventually will call Condition method **signal** to transition the thread waiting on the condition object back to the runnable state. If multiple threads may be waiting on the condition object, a separate thread can call Condition method **signalAll** as a safeguard to ensure that all the waiting threads have another opportunity to perform their tasks. If this is not done, starvation might occur.*



### Common Programming Error 23.2

*An `IllegalMonitorStateException` occurs if a thread issues an **await**, a **signal**, or a **signalAll** on a Condition object that was created from a `ReentrantLock` without having acquired the lock for that Condition object.*

**Lock and Condition vs. the synchronized Keyword**

In some applications, using `Lock` and `Condition` objects may be preferable to using the `synchronized` keyword. Locks allow you to *interrupt* waiting threads or to specify a *timeout* for waiting to acquire a lock, which is not possible using the `synchronized` keyword. Also, a `Lock` is *not* constrained to be acquired and released in the *same* block of code, which is the case with the `synchronized` keyword. `Condition` objects allow you to specify multiple conditions on which threads may *wait*. Thus, it's possible to indicate to waiting threads that a specific condition object is now true by calling `signal` or `signalAll` on that `Condition` object. With `synchronized`, there's no way to explicitly state the condition on which threads are waiting, and thus there's no way to notify threads waiting on one condition that they may proceed without also signaling threads waiting on any other conditions. There are other possible advantages to using `Lock` and `Condition` objects, but generally it's best to use the `synchronized` keyword unless your application requires advanced synchronization capabilities.

**Software Engineering Observation 23.7**

*Think of `Lock` and `Condition` as an advanced version of `synchronized`. `Lock` and `Condition` support timed waits, interruptible waits and multiple `Condition` queues per `Lock`—if you do not need one of these features, you do not need `Lock` and `Condition`.*

**Error-Prevention Tip 23.6**

*Using interfaces `Lock` and `Condition` is error prone—`unlock` is not guaranteed to be called, whereas the monitor in a `synchronized` statement will always be released when the statement completes execution. Of course, you can guarantee that `unlock` will be called if it's placed in a `finally` block, as we do in Fig. 23.20.*

**Using Locks and Conditions to Implement Synchronization**

We now implement the producer/consumer relationship using `Lock` and `Condition` objects to coordinate access to a shared single-element buffer (Figs. 23.20 and 23.21). In this case, each produced value is correctly consumed exactly once. Again, we reuse interface `Buffer` and classes `Producer` and `Consumer` from the example in Section 23.5, except that line 28 is removed from class `Producer` and class `Consumer`.

**Class SynchronizedBuffer**

Class `SynchronizedBuffer` (Fig. 23.20) contains five fields. Line 11 creates a new object of type `ReentrantLock` and assigns its reference to `Lock` variable `accessLock`. The `ReentrantLock` is created without the *fairness policy* because at any time only a single `Producer` or `Consumer` will be waiting to acquire the `Lock` in this example. Lines 14–15 create two `Conditions` using `Lock` method `newCondition`. `Condition` `canWrite` contains a queue for a `Producer` thread waiting while the buffer is *full* (i.e., there's data in the buffer that the `Consumer` has not read yet). If the buffer is *full*, the `Producer` calls method `await` on this `Condition`. When the `Consumer` reads data from a *full* buffer, it calls method `signal` on this `Condition`. `Condition` `canRead` contains a queue for a `Consumer` thread waiting while the buffer is *empty* (i.e., there's no data in the buffer for the `Consumer` to read). If the buffer is *empty*, the `Consumer` calls method `await` on this `Condition`. When the `Producer` writes to the *empty* buffer, it calls method `signal` on this `Condition`. The `int` variable `buffer` (line 17) holds the shared mutable data. The `boolean` variable `occupied` (line 18) keeps track of whether the buffer currently holds data (that the `Consumer` should read).

---

```

1 // Fig. 23.20: SynchronizedBuffer.java
2 // Synchronizing access to a shared integer using the Lock and Condition
3 // interfaces
4 import java.util.concurrent.locks.Lock;
5 import java.util.concurrent.locks.ReentrantLock;
6 import java.util.concurrent.locks.Condition;
7
8 public class SynchronizedBuffer implements Buffer
9 {
10 // Lock to control synchronization with this buffer
11 private final Lock accessLock = new ReentrantLock();
12
13 // conditions to control reading and writing
14 private final Condition canWrite = accessLock.newCondition();
15 private final Condition canRead = accessLock.newCondition();
16
17 private int buffer = -1; // shared by producer and consumer threads
18 private boolean occupied = false; // whether buffer is occupied
19
20 // place int value into buffer
21 public void blockingPut(int value) throws InterruptedException
22 {
23 accessLock.lock(); // lock this object
24
25 // output thread information and buffer information, then wait
26 try
27 {
28 // while buffer is not empty, place thread in waiting state
29 while (occupied)
30 {
31 System.out.println("Producer tries to write.");
32 displayState("Buffer full. Producer waits.");
33 canWrite.await(); // wait until buffer is empty
34 }
35
36 buffer = value; // set new buffer value
37
38 // indicate producer cannot store another value
39 // until consumer retrieves current buffer value
40 occupied = true;
41
42 displayState("Producer writes " + buffer);
43
44 // signal any threads waiting to read from buffer
45 canRead.signalAll();
46 }
47 finally
48 {
49 accessLock.unlock(); // unlock this object
50 }
51 }

```

---

**Fig. 23.20** | Synchronizing access to a shared integer using the Lock and Condition interfaces. (Part I of 2.)

---

```

52
53 // return value from buffer
54 public int blockingGet() throws InterruptedException
55 {
56 int readValue = 0; // initialize value read from buffer
57 accessLock.lock(); // lock this object
58
59 // output thread information and buffer information, then wait
60 try
61 {
62 // if there is no data to read, place thread in waiting state
63 while (!occupied)
64 {
65 System.out.println("Consumer tries to read.");
66 displayState("Buffer empty. Consumer waits.");
67 canRead.await(); // wait until buffer is full
68 }
69
70 // indicate that producer can store another value
71 // because consumer just retrieved buffer value
72 occupied = false;
73
74 readValue = buffer; // retrieve value from buffer
75 displayState("Consumer reads " + readValue);
76
77 // signal any threads waiting for buffer to be empty
78 canWrite.signalAll();
79 }
80 finally
81 {
82 accessLock.unlock(); // unlock this object
83 }
84
85 return readValue;
86 }
87
88 // display current operation and buffer state
89 private void displayState(String operation)
90 {
91 try
92 {
93 accessLock.lock(); // lock this object
94 System.out.printf("%-40s%d\t\t%b%n%n", operation, buffer,
95 occupied);
96 }
97 finally
98 {
99 accessLock.unlock(); // unlock this objects
100 }
101 }
102 } // end class SynchronizedBuffer

```

---

**Fig. 23.20** | Synchronizing access to a shared integer using the Lock and Condition interfaces. (Part 2 of 2.)

Line 23 in method `blockingPut` calls method `lock` on the `SynchronizedBuffer`'s `accessLock`. If the lock is *available* (i.e., no other thread has acquired it), this thread now owns the lock and the thread continues. If the lock is *unavailable* (i.e., it's held by another thread), method `lock` waits until the lock is released. After the lock is acquired, lines 26–46 execute. Line 29 tests `occupied` to determine whether buffer is full. If it is, lines 31–32 display a message indicating that the thread will *wait*. Line 33 calls `Condition` method `await` on the `canWrite` condition object, which temporarily releases the `SynchronizedBuffer`'s `Lock` and *waits* for a signal from the Consumer that buffer is available for writing. When buffer is available, the method proceeds, writing to buffer (line 36), setting `occupied` to true (line 40) and displaying a message indicating that the producer wrote a value (line 42). Line 45 calls `Condition` method `signal` on condition object `canRead` to notify the waiting Consumer (if there is one) that the buffer has new data to be read. Line 49 calls method `unlock` from a `finally` block to *release* the lock and allow the Consumer to proceed.

Line 57 of method `blockingGet` (lines 54–86) calls method `lock` to *acquire* the `Lock`. This method *waits* until the `Lock` is *available*. Once the `Lock` is *acquired*, line 63 tests whether `occupied` is false, indicating that the buffer is *empty*. If so, line 67 calls method `await` on condition object `canRead`. Recall that method `signal` is called on variable `canRead` in the `blockingPut` method (line 45). When the `Condition` object is *signaled*, the `blockingGet` method continues. Lines 72–74 set `occupied` to false, store the value of buffer in `readValue` and output the `readValue`. Then line 78 *signals* the condition object `canWrite`. This awakens the Producer if it's indeed *waiting* for the buffer to be *emptied*. Line 82 calls method `unlock` from a `finally` block to *release* the lock, and line 85 returns `readValue` to the caller.



### Common Programming Error 23.3

*Forgetting to signal a waiting thread is a logic error. The thread will remain in the waiting state, which will prevent it from proceeding. Such waiting can lead to indefinite postponement or deadlock.*

### Class `SharedBufferTest2`

Class `SharedBufferTest2` (Fig. 23.21) is identical to that of Fig. 23.17. Study the outputs in Fig. 23.21. *Observe that every integer produced is consumed exactly once—no values are lost, and no values are consumed more than once.* The `Lock` and `Condition` objects ensure that the Producer and Consumer cannot perform their tasks unless it's their turn. The Producer *must* go first, the Consumer *must wait* if the Producer has not produced since the Consumer last consumed and the Producer *must wait* if the Consumer has not yet consumed the value that the Producer most recently produced. Execute this program several times to confirm that every integer produced is consumed exactly once. In the sample output, note the highlighted lines indicating when the Producer and Consumer must *wait* to perform their respective tasks.

---

```

1 // Fig. 23.21: SharedBufferTest2.java
2 // Two threads manipulating a synchronized buffer.
3 import java.util.concurrent.ExecutorService;
```

---

**Fig. 23.21** | Two threads manipulating a synchronized buffer. (Part I of 3.)

```

4 import java.util.concurrent.Executors;
5 import java.util.concurrent.TimeUnit;
6
7 public class SharedBufferTest2
8 {
9 public static void main(String[] args) throws InterruptedException
10 {
11 // create new thread pool with two threads
12 ExecutorService executorService = Executors.newCachedThreadPool();
13
14 // create SynchronizedBuffer to store ints
15 Buffer sharedLocation = new SynchronizedBuffer();
16
17 System.out.printf("%-40s%s\t\t%s%n%-40s%s%n", "Operation",
18 "Buffer", "Occupied", "-----", "-----\t\t-----");
19
20 // execute the Producer and Consumer tasks
21 executorService.execute(new Producer(sharedLocation));
22 executorService.execute(new Consumer(sharedLocation));
23
24 executorService.shutdown();
25 executorService.awaitTermination(1, TimeUnit.MINUTES);
26 }
27 } // end class SharedBufferTest2

```

| Operation<br>-----                                       | Buffer<br>----- | Occupied<br>----- |
|----------------------------------------------------------|-----------------|-------------------|
| Producer writes 1                                        | 1               | true              |
| Producer tries to write.<br>Buffer full. Producer waits. | 1               | true              |
| Consumer reads 1                                         | 1               | false             |
| Producer writes 2                                        | 2               | true              |
| Producer tries to write.<br>Buffer full. Producer waits. | 2               | true              |
| Consumer reads 2                                         | 2               | false             |
| Producer writes 3                                        | 3               | true              |
| Consumer reads 3                                         | 3               | false             |
| Producer writes 4                                        | 4               | true              |
| Consumer reads 4                                         | 4               | false             |
| Consumer tries to read.<br>Buffer empty. Consumer waits. | 4               | false             |

**Fig. 23.21** | Two threads manipulating a synchronized buffer. (Part 2 of 3.)



|                                                          |    |       |
|----------------------------------------------------------|----|-------|
| Producer writes 5                                        | 5  | true  |
| Consumer reads 5                                         | 5  | false |
| Consumer tries to read.<br>Buffer empty. Consumer waits. | 5  | false |
| Producer writes 6                                        | 6  | true  |
| Consumer reads 6                                         | 6  | false |
| Producer writes 7                                        | 7  | true  |
| Consumer reads 7                                         | 7  | false |
| Producer writes 8                                        | 8  | true  |
| Consumer reads 8                                         | 8  | false |
| Producer writes 9                                        | 9  | true  |
| Consumer reads 9                                         | 9  | false |
| Producer writes 10                                       | 10 | true  |
| Producer done producing<br>Terminating Producer          |    |       |
| Consumer reads 10                                        | 10 | false |
| Consumer read values totaling 55<br>Terminating Consumer |    |       |

**Fig. 23.21** | Two threads manipulating a synchronized buffer. (Part 3 of 3.)

## 23.10 Concurrent Collections

In Chapter 16, we introduced various collections from the Java Collections API. We also mentioned that you can obtain *synchronized* versions of those collections to allow only one thread at a time to access a collection that might be shared among several threads. The collections from the `java.util.concurrent` package are specifically designed and optimized for sharing collections among multiple threads.

Figure 23.22 lists the many concurrent collections in package `java.util.concurrent`. The entries for `ConcurrentHashMap` and `LinkedBlockingQueue` are shown in bold because these are by far the most frequently used concurrent collections. Like the collections introduced in Chapter 16, the concurrent collections have been enhanced to support lambdas. However, rather than providing methods to support streams, the concurrent collections provide their own implementations of various stream-like operations—e.g., `ConcurrentHashMap` has methods `forEach`, `reduce` and `search`—that are designed and optimized for concurrent collections that are shared among threads. For more information on the concurrent collections, visit

*Java SE 7:*

<http://docs.oracle.com/javase/7/docs/api/java/util/concurrent/package-summary.html>

*Java SE 8*

<http://download.java.net/jdk8/docs/api/java/util/concurrent/package-summary.html>

| Collection                         | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |
|------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>ArrayBlockingQueue</code>    | A fixed-size queue that supports the producer/consumer relationship—possibly with many producers and consumers.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |
| <code>ConcurrentHashMap</code>     | A hash-based map (similar to the <code>HashMap</code> introduced in Chapter 16) that allows an arbitrary number of reader threads and a limited number of writer threads. This and the <code>LinkedBlockingQueue</code> are by far the most frequently used concurrent collections.                                                                                                                                                                                                                                                                                                               |
| <code>ConcurrentLinkedDeque</code> | A concurrent linked-list implementation of a double-ended queue.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |
| <code>ConcurrentLinkedQueue</code> | A concurrent linked-list implementation of a queue that can grow dynamically.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |
| <code>ConcurrentSkipListMap</code> | A concurrent map that is sorted by its keys.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |
| <code>ConcurrentSkipListSet</code> | A sorted concurrent set.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |
| <code>CopyOnWriteArrayList</code>  | A thread-safe <code>ArrayList</code> . Each operation that modifies the collection first creates a new copy of the contents. Used when the collection is traversed much more frequently than the collection's contents are modified.                                                                                                                                                                                                                                                                                                                                                              |
| <code>CopyOnWriteArraySet</code>   | A set that's implemented using <code>CopyOnWriteArrayList</code> .                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |
| <code>DelayQueue</code>            | A variable-size queue containing <code>Delayed</code> objects. An object can be removed only after its delay has expired.                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |
| <code>LinkedBlockingDeque</code>   | A double-ended blocking queue implemented as a linked list that can optionally be fixed in size.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |
| <code>LinkedBlockingQueue</code>   | A blocking queue implemented as a linked list that can optionally be fixed in size. This and the <code>ConcurrentHashMap</code> are by far the most frequently used concurrent collections.                                                                                                                                                                                                                                                                                                                                                                                                       |
| <code>LinkedTransferQueue</code>   | A linked-list implementation of interface <code>TransferQueue</code> . Each producer has the option of waiting for a consumer to take an element being inserted (via method <code>transfer</code> ) or simply placing the element into the queue (via method <code>put</code> ). Also provides overloaded method <code>tryTransfer</code> to immediately transfer an element to a waiting consumer or to do so within a specified timeout period. If the transfer cannot be completed, the element is not placed in the queue. Typically used in applications that pass messages between threads. |
| <code>PriorityBlockingQueue</code> | A variable-length priority-based blocking queue (like a <code>PriorityQueue</code> ).                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |
| <code>SynchronousQueue</code>      | [For experts.] A blocking queue implementation that does not have an internal capacity. Each insert operation by one thread must wait for a remove operation from another thread and vice versa.                                                                                                                                                                                                                                                                                                                                                                                                  |

**Fig. 23.22** | Concurrent collections summary (package `java.util.concurrent`).

## 23.11 Multithreading with GUI: SwingWorker

Swing applications present a unique set of challenges for multithreaded programming. All Swing applications have a single thread, called the **event dispatch thread**, to handle interactions with the application's GUI components. Typical interactions include *updating GUI components* or *processing user actions* such as mouse clicks. All tasks that require interaction with an application's GUI are placed in an *event queue* and are executed sequentially by the event dispatch thread.

*Swing GUI components are not thread safe—they cannot be manipulated by multiple threads without the risk of incorrect results that might corrupt the GUI.* Unlike the other examples presented in this chapter, thread safety in GUI applications is achieved not by synchronizing thread actions, but by *ensuring that Swing components are accessed from only the event dispatch thread*. This technique is called **thread confinement**. Allowing just one thread to access non-thread-safe objects eliminates the possibility of corruption due to multiple threads accessing these objects concurrently.

It's acceptable to perform brief calculations on the event dispatch thread in sequence with GUI component manipulations. If an application must perform a lengthy computation in response to a user interaction, the event dispatch thread cannot attend to other tasks in the event queue while the thread is tied up in that computation. This causes the GUI components to become unresponsive. It's preferable to handle a long-running computation in a separate thread, freeing the event dispatch thread to continue managing other GUI interactions. Of course, you must update the GUI with the computation's results from the event dispatch thread, rather than from the worker thread that performed the computation.

### Class *SwingWorker*

Class **SwingWorker** (in package `javax.swing`) enables you to perform an asynchronous task in a worker thread (such as a long-running computation) then update Swing components from the event dispatch thread based on the task's results. **SwingWorker** implements the `Runnable` interface, meaning that *a SwingWorker object can be scheduled to execute in a separate thread*. The **SwingWorker** class provides several methods to simplify performing a task in a worker thread and making its results available for display in a GUI. Some common **SwingWorker** methods are described in Fig. 23.23.

| Method                      | Description                                                                                                                                            |
|-----------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>doInBackground</code> | Defines a long computation and is called in a worker thread.                                                                                           |
| <code>done</code>           | Executes on the event dispatch thread when <code>doInBackground</code> returns.                                                                        |
| <code>execute</code>        | Schedules the <b>SwingWorker</b> object to be executed in a worker thread.                                                                             |
| <code>get</code>            | Waits for the computation to complete, then returns the result of the computation (i.e., the return value of <code>doInBackground</code> ).            |
| <code>publish</code>        | Sends intermediate results from the <code>doInBackground</code> method to the <code>process</code> method for processing on the event dispatch thread. |

**Fig. 23.23** | Commonly used **SwingWorker** methods. (Part 1 of 2.)

| Method                   | Description                                                                                                                  |
|--------------------------|------------------------------------------------------------------------------------------------------------------------------|
| <code>process</code>     | Receives intermediate results from the <code>publish</code> method and processes these results on the event dispatch thread. |
| <code>setProgress</code> | Sets the progress property to notify any property change listeners on the event dispatch thread of progress bar updates.     |

**Fig. 23.23** | Commonly used `SwingWorker` methods. (Part 2 of 2.)

### 23.11.1 Performing Computations in a Worker Thread: Fibonacci Numbers

In the next example, the user enters a number  $n$  and the program gets the  $n$ th Fibonacci number, which we calculate using the recursive algorithm discussed in Section 18.5. Since the algorithm is time consuming for large values, we use a `SwingWorker` object to perform the calculation in a worker thread. The GUI also provides a separate set of components that get the next Fibonacci number in the sequence with each click of a button, beginning with `fibonacci(1)`. This set of components performs its short computation directly in the event dispatch thread. This program is capable of producing up to the 92nd Fibonacci number—subsequent values are outside the range that can be represented by a `long`. Recall that you can use class `BigInteger` to represent arbitrarily large integer values.

Class `BackgroundCalculator` (Fig. 23.24) performs the recursive Fibonacci calculation in a *worker thread*. This class extends `SwingWorker` (line 8), overriding the methods `doInBackground` and `done`. Method `doInBackground` (lines 21–24) computes the  $n$ th Fibonacci number in a worker thread and returns the result. Method `done` (lines 27–43) displays the result in a `JLabel`.

---

```

1 // Fig. 23.24: BackgroundCalculator.java
2 // SwingWorker subclass for calculating Fibonacci numbers
3 // in a background thread.
4 import javax.swing.SwingWorker;
5 import javax.swing.JLabel;
6 import java.util.concurrent.ExecutionException;
7
8 public class BackgroundCalculator extends SwingWorker<Long, Object>
9 {
10 private final int n; // Fibonacci number to calculate
11 private final JLabel resultJLabel; // JLabel to display the result
12
13 // constructor
14 public BackgroundCalculator(int n, JLabel resultJLabel)
15 {
16 this.n = n;
17 this.resultJLabel = resultJLabel;
18 }

```

---

**Fig. 23.24** | `SwingWorker` subclass for calculating Fibonacci numbers in a background thread. (Part 1 of 2.)

---

```

19
20 // long-running code to be run in a worker thread
21 public Long doInBackground()
22 {
23 return nthFib = fibonacci(n);
24 }
25
26 // code to run on the event dispatch thread when doInBackground returns
27 protected void done()
28 {
29 try
30 {
31 // get the result of doInBackground and display it
32 resultJLabel.setText(get().toString());
33 }
34 catch (InterruptedException ex)
35 {
36 resultJLabel.setText("Interrupted while waiting for results.");
37 }
38 catch (ExecutionException ex)
39 {
40 resultJLabel.setText(
41 "Error encountered while performing calculation.");
42 }
43 }
44
45 // recursive method fibonacci; calculates nth Fibonacci number
46 public long fibonacci(long number)
47 {
48 if (number == 0 || number == 1)
49 return number;
50 else
51 return fibonacci(number - 1) + fibonacci(number - 2);
52 }
53 } // end class BackgroundCalculator

```

---

**Fig. 23.24** | SwingWorker subclass for calculating Fibonacci numbers in a background thread.  
(Part 2 of 2.)

SwingWorker is a *generic class*. In line 8, the first type parameter is Long and the second is Object. The first type parameter indicates the type returned by the `doInBackground` method; the second indicates the type that's passed between the `publish` and `process` methods to handle intermediate results. Since we do not use `publish` and `process` in this example, we simply use Object as the second type parameter. We discuss `publish` and `process` in Section 23.11.2.

A BackgroundCalculator object can be instantiated from a class that controls a GUI. A BackgroundCalculator maintains instance variables for an integer that represents the Fibonacci number to be calculated and a JLabel that displays the results of the calculation (lines 10–11). The BackgroundCalculator constructor (lines 14–18) initializes these instance variables with the arguments that are passed to the constructor.



### Software Engineering Observation 23.8

*Any GUI components that will be manipulated by SwingWorker methods, such as components that will be updated from methods process or done, should be passed to the SwingWorker subclass's constructor and stored in the subclass object. This gives these methods access to the GUI components they'll manipulate.*

When method `execute` is called on a `BackgroundCalculator` object, the object is scheduled for execution in a worker thread. Method `doInBackground` is called from the worker thread and invokes the `fibonacci` method (lines 46–52), passing instance variable `n` as an argument (line 23). Method `fibonacci` uses recursion to compute the Fibonacci of `n`. When `fibonacci` returns, method `doInBackground` returns the result.

After `doInBackground` returns, method `done` is called from the event dispatch thread. This method attempts to set the result `JLabel` to the return value of `doInBackground` by calling method `get` to retrieve this return value (line 32). Method `get` *waits* for the result to be ready if necessary, but since we call it from method `done`, the computation will be complete *before* `get` is called. Lines 34–37 catch `InterruptedException` if the current thread is interrupted while waiting for `get` to return. This exception will not occur in this example since the calculation will have already completed by the time `get` is called. Lines 38–42 catch `ExecutionException`, which is thrown if an exception occurs during the computation.

### Class `FibonacciNumbers`

Class `FibonacciNumbers` (Fig. 23.25) displays a window containing two sets of GUI components—one set to compute a Fibonacci number in a worker thread and another to get the next Fibonacci number in response to the user's clicking a `JButton`. The constructor (lines 38–109) places these components in separate titled `JPanels`. Lines 46–47 and 78–79 add two `JLabels`, a `JTextField` and a `JButton` to the `workerJPanel` to allow the user to enter an integer whose Fibonacci number will be calculated by the `BackgroundWorker`. Lines 84–85 and 103 add two `JLabels` and a `JButton` to the `eventThreadJPanel` to allow the user to get the next Fibonacci number in the sequence. Instance variables `n1` and `n2` contain the previous two Fibonacci numbers in the sequence and are initialized to 0 and 1, respectively (lines 29–30). Instance variable `count` stores the most recently computed sequence number and is initialized to 1 (line 31). The two `JLabels` display `count` and `n2` initially, so that the user will see the text `Fibonacci of 1: 1` in the `eventThreadJPanel` when the GUI starts.

---

```

1 // Fig. 23.25: FibonacciNumbers.java
2 // Using SwingWorker to perform a long calculation with
3 // results displayed in a GUI.
4 import java.awt.GridLayout;
5 import java.awt.event.ActionEvent;
6 import java.awt.event.ActionListener;
7 import javax.swing.JButton;
8 import javax.swing.JFrame;
9 import javax.swing.JPanel;
10 import javax.swing.JLabel;
```

---

**Fig. 23.25** | Using `SwingWorker` to perform a long calculation with results displayed in a GUI.  
(Part I of 4.)

---

```

11 import javax.swing.JTextField;
12 import javax.swing.border.TitledBorder;
13 import javax.swing.border.LineBorder;
14 import java.awt.Color;
15 import java.util.concurrent.ExecutionException;
16
17 public class FibonacciNumbers extends JFrame
18 {
19 // components for calculating the Fibonacci of a user-entered number
20 private final JPanel workerJPanel =
21 new JPanel(new GridLayout(2, 2, 5, 5));
22 private final JTextField numberJTextField = new JTextField();
23 private final JButton goJButton = new JButton("Go");
24 private final JLabel fibonacciJLabel = new JLabel();
25
26 // components and variables for getting the next Fibonacci number
27 private final JPanel eventThreadJPanel =
28 new JPanel(new GridLayout(2, 2, 5, 5));
29 private long n1 = 0; // initialize with first Fibonacci number
30 private long n2 = 1; // initialize with second Fibonacci number
31 private int count = 1; // current Fibonacci number to display
32 private final JLabel nJLabel = new JLabel("Fibonacci of 1: ");
33 private final JLabel nFibonacciJLabel =
34 new JLabel(String.valueOf(n2));
35 private final JButton nextNumberJButton = new JButton("Next Number");
36
37 // constructor
38 public FibonacciNumbers()
39 {
40 super("Fibonacci Numbers");
41 setLayout(new GridLayout(2, 1, 10, 10));
42
43 // add GUI components to the SwingWorker panel
44 workerJPanel.setBorder(new TitledBorder(
45 new LineBorder(Color.BLACK), "With SwingWorker"));
46 workerJPanel.add(new JLabel("Get Fibonacci of:"));
47 workerJPanel.add(numberJTextField);
48 goJButton.addActionListener(
49 new ActionListener()
50 {
51 public void actionPerformed(ActionEvent event)
52 {
53 int n;
54
55 try
56 {
57 // retrieve user's input as an integer
58 n = Integer.parseInt(numberJTextField.getText());
59 }

```

---

**Fig. 23.25** | Using SwingWorker to perform a long calculation with results displayed in a GUI.  
(Part 2 of 4.)

---

```

60 catch(NumberFormatException ex)
61 {
62 // display an error message if the user did not
63 // enter an integer
64 fibonacciJLabel.setText("Enter an integer.");
65 return;
66 }
67
68 // indicate that the calculation has begun
69 fibonacciJLabel.setText("Calculating...");
70
71 // create a task to perform calculation in background
72 BackgroundCalculator task =
73 new BackgroundCalculator(n, fibonacciJLabel);
74 task.execute(); // execute the task
75 }
76 } // end anonymous inner class
77); // end call to addActionListener
78 workerJPanel.add(goJButton);
79 workerJPanel.add(fibonacciJLabel);
80
81 // add GUI components to the event-dispatching thread panel
82 eventThreadJPanel.setBorder(new TitledBorder(
83 new LineBorder(Color.BLACK), "Without SwingWorker"));
84 eventThreadJPanel.add(nJLabel);
85 eventThreadJPanel.add(nFibonacciJLabel);
86 nextNumberJButton.addActionListener(
87 new ActionListener()
88 {
89 public void actionPerformed(ActionEvent event)
90 {
91 // calculate the Fibonacci number after n2
92 long temp = n1 + n2;
93 n1 = n2;
94 n2 = temp;
95 ++count;
96
97 // display the next Fibonacci number
98 nJLabel.setText("Fibonacci of " + count + ": ");
99 nFibonacciJLabel.setText(String.valueOf(n2));
100 }
101 } // end anonymous inner class
102); // end call to addActionListener
103 eventThreadJPanel.add(nextNumberJButton);
104
105 add(workerJPanel);
106 add(eventThreadJPanel);
107 setSize(275, 200);
108 setVisible(true);
109 } // end constructor

```

---

**Fig. 23.25** | Using `SwingWorker` to perform a long calculation with results displayed in a GUI.  
(Part 3 of 4.)




```


110
111 // main method begins program execution
112 public static void main(String[] args)
113 {
114 FibonacciNumbers application = new FibonacciNumbers();
115 application.setDefaultCloseOperation(EXIT_ON_CLOSE);
116 }
117 } // end class FibonacciNumbers

```


a) Begin calculating Fibonacci of 40 in the background



b) Calculating other Fibonacci values while Fibonacci of 40 continues calculating



c) Fibonacci of 40 calculation finishes



**Fig. 23.25** | Using SwingWorker to perform a long calculation with results displayed in a GUI. (Part 4 of 4.)

Lines 48–77 register the event handler for the `goJButton`. If the user clicks this `JButton`, line 58 gets the value entered in the `numberJTextField` and attempts to parse it as an integer. Lines 72–73 create a new `BackgroundCalculator` object, passing in the user-entered value and the `fibonacciJLabel` that's used to display the calculation's results. Line 74 calls method `execute` on the `BackgroundCalculator`, scheduling it for execution in a separate worker thread. Method `execute` does not wait for the `BackgroundCalculator` to finish executing. It returns immediately, allowing the GUI to continue processing other events while the computation is performed.

If the user clicks the `nextNumberJButton` in the `eventThreadJPanel`, the event handler registered in lines 86–102 executes. Lines 92–95 add the previous two Fibonacci numbers stored in `n1` and `n2` to determine the next number in the sequence, update `n1` and `n2` to their new values and increment count. Then lines 98–99 update the GUI to display the next number. The code for these calculations is in method `actionPerformed`, so they're performed on the *event dispatch thread*. Handling such short computations in the event dis-

patch thread does not cause the GUI to become unresponsive, as with the recursive algorithm for calculating the Fibonacci of a large number. Because the longer Fibonacci computation is performed in a separate worker thread using the `SwingWorker`, it's possible to get the next Fibonacci number while the recursive computation is still in progress.

### 23.1.1.2 Processing Intermediate Results: Sieve of Eratosthenes

We've presented an example that uses the `SwingWorker` class to execute a long process in a *background thread* and update the GUI when the process is finished. We now present an example of updating the GUI with intermediate results before the long process completes. Figure 23.26 presents class `PrimeCalculator`, which extends `SwingWorker` to compute the first  $n$  prime numbers in a *worker thread*. In addition to the `doInBackground` and `done` methods used in the previous example, this class uses `SwingWorker` methods `publish`, `process` and `setProgress`. In this example, method `publish` sends prime numbers to method `process` as they're found, method `process` displays these primes in a GUI component and method `setProgress` updates the progress property. We later show how to use this property to update a `JProgressBar`.

---

```

1 // Fig. 23.26: PrimeCalculator.java
2 // Calculates the first n primes, displaying them as they are found.
3 import javax.swing.JTextArea;
4 import javax.swing.JLabel;
5 import javax.swing.JButton;
6 import javax.swing.SwingWorker;
7 import java.security.SecureRandom;
8 import java.util.Arrays;
9 import java.util.List;
10 import java.util.concurrent.CancellationException;
11 import java.util.concurrent.ExecutionException;
12
13 public class PrimeCalculator extends SwingWorker<Integer, Integer>
14 {
15 private static final SecureRandom generator = new SecureRandom();
16 private final JTextArea intermediateJTextArea; // displays found primes
17 private final JButton getPrimesJButton;
18 private final JButton cancelJButton;
19 private final JLabel statusJLabel; // displays status of calculation
20 private final boolean[] primes; // boolean array for finding primes
21
22 // constructor
23 public PrimeCalculator(int max, JTextArea intermediateJTextArea,
24 JLabel statusJLabel, JButton getPrimesJButton,
25 JButton cancelJButton)
26 {
27 this.intermediateJTextArea = intermediateJTextArea;
28 this.statusJLabel = statusJLabel;
29 this.getPrimesJButton = getPrimesJButton;
30 this.cancelJButton = cancelJButton;
31 primes = new boolean[max];
32

```

---

**Fig. 23.26** | Calculates the first  $n$  primes, displaying them as they are found. (Part 1 of 3.)

```

33 Arrays.fill(primes, true); // initialize all primes elements to true
34 }
35
36 // finds all primes up to max using the Sieve of Eratosthenes
37 public Integer doInBackground()
38 {
39 int count = 0; // the number of primes found
40
41 // starting at the third value, cycle through the array and put
42 // false as the value of any greater number that is a multiple
43 for (int i = 2; i < primes.length; i++)
44 {
45 if (isCancelled()) // if calculation has been canceled
46 return count;
47 else
48 {
49 setProgress(100 * (i + 1) / primes.length);
50
51 try
52 {
53 Thread.sleep(generator.nextInt(5));
54 }
55 catch (InterruptedException ex)
56 {
57 statusJLabel.setText("Worker thread interrupted");
58 return count;
59 }
60
61 if (primes[i]) // i is prime
62 {
63 publish(i); // make i available for display in prime list
64 ++count;
65
66 for (int j = i + i; j < primes.length; j += i)
67 primes[j] = false; // i is not prime
68 }
69 }
70 }
71
72 return count;
73 }
74
75 // displays published values in primes list
76 protected void process(List<Integer> publishedVals)
77 {
78 for (int i = 0; i < publishedVals.size(); i++)
79 intermediateJTextArea.append(publishedVals.get(i) + "\n");
80 }
81
82 // code to execute when doInBackground completes
83 protected void done()
84 {
85 getPrimesJButton.setEnabled(true); // enable Get Primes button

```

**Fig. 23.26** | Calculates the first  $n$  primes, displaying them as they are found. (Part 2 of 3.)

---

```

86 cancelButton.setEnabled(false); // disable Cancel button
87
88 try
89 {
90 // retrieve and display doInBackground return value
91 statusJLabel.setText("Found " + get() + " primes.");
92 }
93 catch (InterruptedException | ExecutionException |
94 CancellationExcepion ex)
95 {
96 statusJLabel.setText(ex.getMessage());
97 }
98 }
99 } // end class PrimeCalculator

```

---

**Fig. 23.26** | Calculates the first  $n$  primes, displaying them as they are found. (Part 3 of 3.)

Class `PrimeCalculator` extends `SwingWorker` (line 13), with the first type parameter indicating the return type of method `doInBackground` and the second indicating the type of intermediate results passed between methods `publish` and `process`. In this case, both type parameters are `Integers`. The constructor (lines 23–34) takes as arguments an integer that indicates the upper limit of the prime numbers to locate, a `JTextArea` used to display primes in the GUI, one `JButton` for initiating a calculation and one for canceling it, and a `JLabel` used to display the status of the calculation.

### *Sieve of Eratosthenes*

Line 33 initializes the elements of the boolean array `primes` to `true` with `Arrays` method `fill`. `PrimeCalculator` uses this array and the **Sieve of Eratosthenes** algorithm (described in Exercise 6.27) to find all primes less than `max`. The Sieve of Eratosthenes takes a list of integers and, beginning with the first prime number, filters out all multiples of that prime. It then moves to the next prime, which will be the next number that's not yet filtered out, and eliminates all of its multiples. It continues until the end of the list is reached and all nonprimes have been filtered out. Algorithmically, we begin with element 2 of the boolean array and set the cells corresponding to all values that are multiples of 2 to `false` to indicate that they're divisible by 2 and thus not prime. We then move to the next array element, check whether it's `true`, and if so set all of its multiples to `false` to indicate that they're divisible by the current index. When the whole array has been traversed in this way, all indices that contain `true` are prime, as they have no divisors.

### *Method `doInBackground`*

In method `doInBackground` (lines 37–73), the control variable `i` for the loop (lines 43–70) controls the current index for implementing the Sieve of Eratosthenes. Line 45 calls the inherited `SwingWorker` method `isCancelled` to determine whether the user has clicked the **Cancel** button. If `isCancelled` returns `true`, method `doInBackground` returns the number of primes found so far (line 46) without finishing the computation.

If the calculation isn't canceled, line 49 calls `setProgress` to update the percentage of the array that's been traversed so far. Line 53 puts the currently executing thread to sleep for up to 4 milliseconds. We discuss the reason for this shortly. Line 61 tests whether the element of array `primes` at the current index is `true` (and thus prime). If so, line 63 passes

the index to method `publish` so that it can be displayed as an *intermediate result* in the GUI and line 64 increments the number of primes found. Lines 66–67 set all multiples of the current index to `false` to indicate that they’re not prime. When the entire array has been traversed, line 72 returns the number of primes found.

### Method process

Lines 76–80 declare method `process`, which executes in the event dispatch thread and receives its argument `publishedVals` from method `publish`. The passing of values between `publish` in the worker thread and `process` in the event dispatch thread is asynchronous; `process` might not be invoked for every call to `publish`. All `Integers` published since the last call to `process` are received as a `List` by method `process`. Lines 78–79 iterate through this list and display the published values in a `JTextArea`. Because the computation in method `doInBackground` progresses quickly, publishing values often, updates to the `JTextArea` can pile up on the event dispatch thread, causing the GUI to become sluggish. In fact, when searching for a large number of primes, the *event dispatch thread* may receive so many requests in quick succession to update the `JTextArea` that it *runs out of memory in its event queue*. This is why we put the worker thread to *sleep* for a few milliseconds between calls to `publish`. The calculation is slowed just enough to allow the event dispatch thread to keep up with requests to update the `JTextArea` with new primes, enabling the GUI to update smoothly and remain responsive.

### Method done

Lines 83–98 define method `done`. When the calculation is finished or canceled, method `done` enables the **Get Primes** button and disables the **Cancel** button (lines 85–86). Line 91 gets and displays the return value—the number of primes found—from method `doInBackground`. Lines 93–97 catch the exceptions thrown by method `get` and display an appropriate message in the `statusJLabel`.

### Class FindPrimes

Class `FindPrimes` (Fig. 23.27) displays a `JTextField` that allows the user to enter a number, a `JButton` to begin finding all primes less than that number and a `JTextArea` to display the primes. A `JButton` allows the user to cancel the calculation, and a `JProgressBar` shows the calculation’s progress. The constructor (lines 32–125) sets up the GUI.

---

```

1 // Fig. 23.27: FindPrimes.java
2 // Using a SwingWorker to display prime numbers and update a JProgressBar
3 // while the prime numbers are being calculated.
4 import javax.swing.JFrame;
5 import javax.swing.JTextField;
6 import javax.swing.JTextArea;
7 import javax.swing.JButton;
8 import javax.swing.JProgressBar;
9 import javax.swing.JLabel;
10 import javax.swing.JPanel;
11 import javax.swing.JScrollPane;
12 import javax.swing.ScrollPaneConstants;

```

---

**Fig. 23.27** | Using a `SwingWorker` to display prime numbers and update a `JProgressBar` while the prime numbers are being calculated. (Part 1 of 4.)

---

```

13 import java.awt.BorderLayout;
14 import java.awt.GridLayout;
15 import java.awt.event.ActionListener;
16 import java.awt.event.ActionEvent;
17 import java.util.concurrent.ExecutionException;
18 import java.beans.PropertyChangeListener;
19 import java.beans.PropertyChangeEvent;
20
21 public class FindPrimes extends JFrame
22 {
23 private final JTextField highestPrimeJTextField = new JTextField();
24 private final JButton getPrimesJButton = new JButton("Get Primes");
25 private final JTextArea displayPrimesJTextArea = new JTextArea();
26 private final JButton cancelJButton = new JButton("Cancel");
27 private final JProgressBar progressJProgressBar = new JProgressBar();
28 private final JLabel statusJLabel = new JLabel();
29 private PrimeCalculator calculator;
30
31 // constructor
32 public FindPrimes()
33 {
34 super("Finding Primes with SwingWorker");
35 setLayout(new BorderLayout());
36
37 // initialize panel to get a number from the user
38 JPanel northJPanel = new JPanel();
39 northJPanel.add(new JLabel("Find primes less than: "));
40 highestPrimeJTextField.setColumns(5);
41 northJPanel.add(highestPrimeJTextField);
42 getPrimesJButton.addActionListener(
43 new ActionListener()
44 {
45 public void actionPerformed(ActionEvent e)
46 {
47 progressJProgressBar.setValue(0); // reset JProgressBar
48 displayPrimesJTextArea.setText(""); // clear JTextArea
49 statusJLabel.setText(""); // clear JLabel
50
51 int number; // search for primes up through this value
52
53 try
54 {
55 // get user input
56 number = Integer.parseInt(
57 highestPrimeJTextField.getText());
58 }
59 catch (NumberFormatException ex)
60 {
61 statusJLabel.setText("Enter an integer.");
62 return;
63 }
64

```

---

**Fig. 23.27** | Using a `SwingWorker` to display prime numbers and update a `JProgressBar` while the prime numbers are being calculated. (Part 2 of 4.)

```

65 // construct a new PrimeCalculator object
66 calculator = new PrimeCalculator(number,
67 displayPrimesJTextArea, statusJLabel, getPrimesJButton,
68 cancelJButton);
69
70 // listen for progress bar property changes
71 calculator.addPropertyChangeListener(
72 new PropertyChangeListener()
73 {
74 public void propertyChange(PropertyChangeEvent e)
75 {
76 // if the changed property is progress,
77 // update the progress bar
78 if (e.getPropertyName().equals("progress"))
79 {
80 int newValue = (Integer) e.getNewValue();
81 progressJProgressBar.setValue(newValue);
82 }
83 }
84 } // end anonymous inner class
85); // end call to addPropertyChangeListener
86
87 // disable Get Primes button and enable Cancel button
88 getPrimesJButton.setEnabled(false);
89 cancelJButton.setEnabled(true);
90
91 calculator.execute(); // execute the PrimeCalculator object
92 }
93 } // end anonymous inner class
94); // end call to addActionListener
95 northJPanel.add(getPrimesJButton);
96
97 // add a scrollable JList to display results of calculation
98 displayPrimesJTextArea.setEditable(false);
99 add(new JScrollPane(displayPrimesJTextArea,
100 JScrollPaneConstants.VERTICAL_SCROLLBAR_ALWAYS,
101 JScrollPaneConstants.HORIZONTAL_SCROLLBAR_NEVER));
102
103 // initialize a panel to display cancelJButton,
104 // progressJProgressBar, and statusJLabel
105 JPanel southJPanel = new JPanel(new GridLayout(1, 3, 10, 10));
106 cancelJButton.setEnabled(false);
107 cancelJButton.addActionListener(
108 new ActionListener()
109 {
110 public void actionPerformed(ActionEvent e)
111 {
112 calculator.cancel(true); // cancel the calculation
113 }
114 } // end anonymous inner class
115); // end call to addActionListener


```

**Fig. 23.27** | Using a SwingWorker to display prime numbers and update a JProgressBar while the prime numbers are being calculated. (Part 3 of 4.)

```

116 southJPanel.add(cancelJButton);
117 progressJProgressBar.setStringPainted(true);
118 southJPanel.add(progressJProgressBar);
119 southJPanel.add(statusJLabel);
120
121 add(northJPanel, BorderLayout.NORTH);
122 add(southJPanel, BorderLayout.SOUTH);
123 setSize(350, 300);
124 setVisible(true);
125 } // end constructor
126
127 // main method begins program execution
128 public static void main(String[] args)
129 {
130 FindPrimes application = new FindPrimes();
131 application.setDefaultCloseOperation(EXIT_ON_CLOSE);
132 } // end main
133 } // end class FindPrimes

```



**Fig. 23.27** | Using a `SwingWorker` to display prime numbers and update a `JProgressBar` while the prime numbers are being calculated. (Part 4 of 4.)

Lines 42–94 register the event handler for the `getPrimesJButton`. When the user clicks this `JButton`, lines 47–49 reset the `JProgressBar` and clear the `displayPrimesJTextArea` and the `statusJLabel`. Lines 53–63 parse the value in the `JTextField` and display an error message if the value is not an integer. Lines 66–68 construct a new `PrimeCalculator` object, passing as arguments the integer the user entered, the `displayPrimesJTextArea` for displaying the primes, the `statusJLabel` and the two `JButtons`.

Lines 71–85 register a `PropertyChangeListener` for the `PrimeCalculator` object. **`PropertyChangeListener`** is an interface from package `java.beans` that defines a single method, `propertyChange`. Every time method `setProgress` is invoked on a `PrimeCalculator`, the `PrimeCalculator` generates a `PropertyChangeEvent` to indicate that the progress property has changed. Method `propertyChange` listens for these events. Line 78 tests whether a given `PropertyChangeEvent` indicates a change to the progress property. If so, line 80 gets the new value of the property and line 81 updates the `JProgressBar` with the new progress property value.

The **`Get Primes`** `JButton` is disabled (line 88) so only one calculation that updates the GUI can execute at a time, and the **`Cancel`** `JButton` is enabled (line 89) to allow the user



to stop the computation before it completes. Line 91 executes the `PrimeCalculator` to begin finding primes. If the user clicks the `cancelJButton`, the event handler registered at lines 107–115 calls `PrimeCalculator`'s method `cancel` (line 112), which is inherited from class `SwingWorker`, and the calculation returns early. The argument `true` to method `cancel` indicates that the thread performing the task should be interrupted in an attempt to cancel the task.

## 23.12 sort/parallelSort Timings with the Java SE 8 Date/Time API

In Section 6.12, we used class `Arrays`'s static method `sort` to sort an array and we introduced static method `parallelSort` for sorting large arrays more efficiently on multi-core systems. Figure 23.28 uses both methods to sort 15,000,000 element arrays of random `int` values so that we can demonstrate `parallelSort`'s performance improvement of over `sort` on a multi-core system (we ran this on a dual-core system).

---

```

1 // SortComparison.java
2 // Comparing performance of Arrays methods sort and parallelSort.
3 import java.time.Duration;
4 import java.time.Instant;
5 import java.text.NumberFormat;
6 import java.util.Arrays;
7 import java.security.SecureRandom;
8
9 public class SortComparison
10 {
11 public static void main(String[] args)
12 {
13 SecureRandom random = new SecureRandom();
14
15 // create array of random ints, then copy it
16 int[] array1 = random.ints(15_000_000).toArray();
17 int[] array2 = new int[array1.length];
18 System.arraycopy(array1, 0, array2, 0, array1.length);
19
20 // time the sorting of array1 with Arrays method sort
21 System.out.println("Starting sort");
22 Instant sortStart = Instant.now();
23 Arrays.sort(array1);
24 Instant sortEnd = Instant.now();
25
26 // display timing results
27 long sortTime = Duration.between(sortStart, sortEnd).toMillis();
28 System.out.printf("Total time in milliseconds: %d%n", sortTime);
29
30 // time the sorting of array2 with Arrays method parallelSort
31 System.out.println("Starting parallelSort");
32 Instant parallelSortStart = Instant.now();

```

---

**Fig. 23.28** | Comparing performance of `Arrays` methods `sort` and `parallelSort`. (Part I of 2.)

```

33 Arrays.parallelSort(array2);
34 Instant parallelSortEnd = Instant.now();
35
36 // display timing results
37 long parallelSortTime =
38 Duration.between(parallelSortStart, parallelSortEnd).toMillis();
39 System.out.printf("Total time in milliseconds: %d%n",
40 parallelSortTime);
41
42 // display time difference as a percentage
43 String percentage = NumberFormat.getPercentInstance().format(
44 (double) sortTime / parallelSortTime);
45 System.out.printf("%nsort took %s more time than parallelSort%n",
46 percentage);
47 }
48 } // end class SortComparison

```

```

Starting sort
Total time in milliseconds: 1319

Starting parallelSort
Total time in milliseconds: 323

sort took 408% more time than parallelSort

```

**Fig. 23.28** | Comparing performance of Arrays methods `sort` and `parallelSort`. (Part 2 of 2.)

### *Creating the Arrays*

Line 16 uses `SecureRandom` method `ints` to create an `IntStream` of 15,000,000 random `int` values, then calls `IntStream` method `toArray` to place the values into an array. Lines 17 and 18 copy the array so that the calls to both `sort` and `parallelSort` work with the same set of values.

### *Timing Arrays Method `sort` with Date/Time API Classes `Instant` and `Duration`*

Lines 22 and 24 each call class `Instant`'s static method `now` to get the current time before and after the call to `sort`. To determine the difference between two `Instant`s, line 27 uses class `Duration`'s static method `between`, which returns a `Duration` object containing the time difference. Next, we call `Duration` method `toMillis` to get the difference in milliseconds.

### *Timing Arrays Method `parallelSort` with Date/Time API Classes `Instant` and `Duration`*

Lines 32–34 time the call to `Arrays` method `parallelSort`. Then, lines 37–38 calculate the difference between the `Instant`s.

### *Displaying the Percentage Difference Between the Sorting Times*

Lines 43–44 use a `NumberFormat` (package `java.text`) to format the ratio of the sort times as a percentage. `NumberFormat` static method `getPercentInstance` returns a `NumberFormat` that's used to format a number as a percentage. `NumberFormat` method `format` performs the formatting. As you can see in the sample output, the `sort` method took over 400% more time to sort the 15,000,000 random `int` values.

### Other Parallel Array Operations

In addition to method `parallelSort`, class `Arrays` now contains methods `parallelSetAll` and `parallelPrefix`, which perform the following tasks:

- **`parallelSetAll`**—Fills an array with values produced by a generator function that receives an `int` and returns a value of type `int`, `long` or `double`. Depending on which overload of method `parallelSetAll` is used, the generator function is an object of a class that implements `IntToDoubleFunction` (for `double` arrays), `IntUnaryOperator` (for `int` arrays), `IntToLongFunction` (for `long` arrays) or `IntFunction` (for arrays of any non-primitive type).
- **`parallelPrefix`**—Applies a `BinaryOperator` to the current and previous array elements and stores the result in the current element. For example, consider:

```
int[] values = {1, 2, 3, 4, 5};
Arrays.parallelPrefix(values, (x, y) -> x + y);
```

This call to `parallelPrefix` uses a `BinaryOperator` that *adds* two values. After the call completes, the array contains 1, 3, 6, 10 and 15. Similarly, the following call to `parallelPrefix`, uses a `BinaryOperator` that *multiplies* two values. After the call completes, the array contains 1, 2, 6, 24 and 120:

```
int[] values = {1, 2, 3, 4, 5};
Arrays.parallelPrefix(values, (x, y) -> x * y);
```

## 23.13 Java SE 8: Sequential vs. Parallel Streams

In Chapter 17, you learned about Java SE 8 lambdas and streams. We mentioned that streams are easy to *parallelize*, enabling programs to benefit from enhanced performance on multi-core systems. Using the timing capabilities introduced in Section 23.12, Fig. 23.29 demonstrates both *sequential* and *parallel* stream operations on a 10,000,000-element array of random `long` values (created at line 17) to compare the performance.

```
1 // StreamStatisticsComparison.java
2 // Comparing performance of sequential and parallel stream operations.
3 import java.time.Duration;
4 import java.time.Instant;
5 import java.util.Arrays;
6 import java.util.LongSummaryStatistics;
7 import java.util.stream.LongStream;
8 import java.security.SecureRandom;
9
10 public class StreamStatisticsComparison
11 {
12 public static void main(String[] args)
13 {
14 SecureRandom random = new SecureRandom();
15
16 // create array of random long values
17 long[] values = random.longs(10_000_000, 1, 1001).toArray();
```

**Fig. 23.29** | Comparing performance of sequential and parallel stream operations. (Part 1 of 3.)

```

18
19 // perform calculations separately
20 Instant separateStart = Instant.now();
21 long count = Arrays.stream(values).count();
22 long sum = Arrays.stream(values).sum();
23 long min = Arrays.stream(values).min().getAsLong();
24 long max = Arrays.stream(values).max().getAsLong();
25 double average = Arrays.stream(values).average().getAsDouble();
26 Instant separateEnd = Instant.now();
27
28 // display results
29 System.out.println("Calculations performed separately");
30 System.out.printf(" count: %,d%n", count);
31 System.out.printf(" sum: %,d%n", sum);
32 System.out.printf(" min: %,d%n", min);
33 System.out.printf(" max: %,d%n", max);
34 System.out.printf(" average: %f%n", average);
35 System.out.printf("Total time in milliseconds: %d%n%n",
36 Duration.between(separateStart, separateEnd).toMillis());
37
38 // time sum operation with sequential stream
39 LongStream stream1 = Arrays.stream(values);
40 System.out.println("Calculating statistics on sequential stream");
41 Instant sequentialStart = Instant.now();
42 LongSummaryStatistics results1 = stream1.summaryStatistics();
43 Instant sequentialEnd = Instant.now();
44
45 // display results
46 displayStatistics(results1);
47 System.out.printf("Total time in milliseconds: %d%n%n",
48 Duration.between(sequentialStart, sequentialEnd).toMillis());
49
50 // time sum operation with parallel stream
51 LongStream stream2 = Arrays.stream(values).parallel();
52 System.out.println("Calculating statistics on parallel stream");
53 Instant parallelStart = Instant.now();
54 LongSummaryStatistics results2 = stream2.summaryStatistics();
55 Instant parallelEnd = Instant.now();
56
57 // display results
58 displayStatistics(results1);
59 System.out.printf("Total time in milliseconds: %d%n%n",
60 Duration.between(parallelStart, parallelEnd).toMillis());
61 }
62
63 // display's LongSummaryStatistics values
64 private static void displayStatistics(LongSummaryStatistics stats)
65 {
66 System.out.println("Statistics");
67 System.out.printf(" count: %,d%n", stats.getCount());
68 System.out.printf(" sum: %,d%n", stats.getSum());
69 System.out.printf(" min: %,d%n", stats.getMin());
70 System.out.printf(" max: %,d%n", stats.getMax());

```

**Fig. 23.29** | Comparing performance of sequential and parallel stream operations. (Part 2 of 3.)

```
71 System.out.printf(" average: %f%n", stats.getAverage());
72 }
73 } // end class StreamStatisticsComparison
```

```
Calculations performed separately
 count: 10,000,000
 sum: 5,003,695,285
 min: 1
 max: 1,000
 average: 500.369529
Total time in milliseconds: 173

Calculating statistics on sequential stream
Statistics
 count: 10,000,000
 sum: 5,003,695,285
 min: 1
 max: 1,000
 average: 500.369529
Total time in milliseconds: 69

Calculating statistics on parallel stream
Statistics
 count: 10,000,000
 sum: 5,003,695,285
 min: 1
 max: 1,000
 average: 500.369529
Total time in milliseconds: 38
```

**Fig. 23.29** | Comparing performance of sequential and parallel stream operations. (Part 3 of 3.)

### *Performing Stream Operations with Separate Passes of a Sequential Stream*

Section 17.3 demonstrated various numerical operations on `IntStreams`. Lines 20–26 perform and time the count, sum, min, max and average stream operations each performed individually on a `LongStream` returned by `Arrays` method `stream`. Lines 29–36 then display the results and the total time required to perform all five operations.

### *Performing Stream Operations with a Single Pass of a Sequential Stream*

Lines 39–48 demonstrate the performance improvement you get by using `LongStream` method `summaryStatistics` to determine the count, sum, minimum value, maximum value and average in one pass of a *sequential* `LongStream`—all streams are sequential by default. This operation took approximately 40% of the time required to perform the five operations separately.

### *Performing Stream Operations with a Single Pass of a Parallel Stream*

Lines 51–60 demonstrate the performance improvement you get by using `LongStream` method `summaryStatistics` on a *parallel* `LongStream`. To obtain a parallel stream that can take advantage of multi-core processors, simply invoke method `parallel` on an existing stream. As you can see from the sample output, performing the operations on a parallel stream decreased the total time required even further—taking approximately 55% of the

calculation time for the sequential `LongStream` and just 22% of the time required to perform the five operations separately.

## 23.14 (Advanced) Interfaces `Callable` and `Future`

Interface `Runnable` provides only the most basic functionality for multithreaded programming. In fact, this interface has limitations. Suppose a `Runnable` is performing a long calculation and the application wants to retrieve the result of that calculation. The `run` method cannot return a value, so *shared mutable data* would be required to pass the value back to the calling thread. As you now know, this would require thread synchronization. The `Callable` interface (of package `java.util.concurrent`) fixes this limitation. The interface declares a single method named `call` which returns a value representing the result of the `Callable`'s task—such as the result of a long running calculation.

An application that creates a `Callable` likely wants to run it concurrently with other `Runnables` and `Callables`. `ExecutorService` method `submit` executes its `Callable` argument and returns an object of type `Future` (of package `java.util.concurrent`), which represents the `Callable`'s future result. The `Future` interface `get` method *blocks* the calling thread, and waits for the `Callable` to complete and return its result. The interface also provides methods that enable you to cancel a `Callable`'s execution, determine whether the `Callable` was cancelled and determine whether the `Callable` completed its task.

### *Executing Asynchronous Tasks with `CompletableFuture`*

Java SE 8 introduces class `CompletableFuture` (package `java.util.concurrent`), which implements the `Future` interface and enables you to *asynchronously* execute `Runnables` that perform tasks or `Suppliers` that return values. Interface `Supplier`, like interface `Callable`, is a functional interface with a single method (in this case, `get`) that receives no arguments and returns a result. Class `CompletableFuture` provides many additional capabilities that for advanced programmers, such as creating `CompletableFuture`s without executing them immediately, composing one or more `CompletableFuture`s so that you can wait for any or all of them to complete, executing code after a `CompletableFuture` completes and more.

Figure 23.30 performs two long-running calculations sequentially, then performs them again asynchronously using `CompletableFuture`s to demonstrate the performance improvement from asynchronous execution on a multi-core system. For demonstration purposes, our long-running calculation is performed by a recursive `fibonacci` method (lines 73–79; similar to the one presented in Section 18.5). For larger Fibonacci values, the recursive implementation can require *significant* computation time—in practice, it's much faster to calculate Fibonacci values using a loop.

---

```

1 // FibonacciDemo.java
2 // Fibonacci calculations performed synchronously and asynchronously
3 import java.time.Duration;
4 import java.text.NumberFormat;
5 import java.time.Instant;
6 import java.util.concurrent.CompletableFuture;
7 import java.util.concurrent.ExecutionException;
8

```

---

**Fig. 23.30** | Fibonacci calculations performed synchronously and asynchronously. (Part 1 of 4.)

---

```

 9 // class that stores two Instants in time
10 class TimeData
11 {
12 public Instant start;
13 public Instant end;
14
15 // return total time in seconds
16 public double timeInSeconds()
17 {
18 return Duration.between(start, end).toMillis() / 1000.0;
19 }
20 } // end class TimeData
21
22 public class FibonacciDemo
23 {
24 public static void main(String[] args)
25 throws InterruptedException, ExecutionException
26 {
27 // perform synchronous fibonacci(45) and fibonacci(44) calculations
28 System.out.println("Synchronous Long Running Calculations");
29 TimeData synchronousResult1 = startFibonacci(45);
30 TimeData synchronousResult2 = startFibonacci(44);
31 double synchronousTime =
32 calculateTime(synchronousResult1, synchronousResult2);
33 System.out.printf(
34 " Total calculation time = %.3f seconds%n", synchronousTime);
35
36 // perform asynchronous fibonacci(45) and fibonacci(44) calculations
37 System.out.printf("%nAsynchronous Long Running Calculations%n");
38 CompletableFuture<TimeData> futureResult1 =
39 CompletableFuture.supplyAsync(() -> startFibonacci(45));
40 CompletableFuture<TimeData> futureResult2 =
41 CompletableFuture.supplyAsync(() -> startFibonacci(44));
42
43 // wait for results from the asynchronous operations
44 TimeData asynchronousResult1 = futureResult1.get();
45 TimeData asynchronousResult2 = futureResult2.get();
46 double asynchronousTime =
47 calculateTime(asynchronousResult1, asynchronousResult2);
48 System.out.printf(
49 " Total calculation time = %.3f seconds%n", asynchronousTime);
50
51 // display time difference as a percentage
52 String percentage = NumberFormat.getPercentInstance().format(
53 synchronousTime / asynchronousTime);
54 System.out.printf("%nSynchronous calculations took %s" +
55 " more time than the asynchronous calculations%n", percentage);
56 }
57
58 // executes function fibonacci asynchronously
59 private static TimeData startFibonacci(int n)
60 {

```

---

**Fig. 23.30** | Fibonacci calculations performed synchronously and asynchronously. (Part 2 of 4.)

```

61 // create a TimeData object to store times
62 TimeData timeData = new TimeData();
63
64 System.out.printf(" Calculating fibonacci(%d)%n", n);
65 timeData.start = Instant.now();
66 long fibonacciValue = fibonacci(n);
67 timeData.end = Instant.now();
68 displayResult(n, fibonacciValue, timeData);
69 return timeData;
70 }
71
72 // recursive method fibonacci; calculates nth Fibonacci number
73 private static long fibonacci(long n)
74 {
75 if (n == 0 || n == 1)
76 return n;
77 else
78 return fibonacci(n - 1) + fibonacci(n - 2);
79 }
80
81 // display fibonacci calculation result and total calculation time
82 private static void displayResult(int n, long value, TimeData timeData)
83 {
84 System.out.printf(" fibonacci(%d) = %d%n", n, value);
85 System.out.printf(
86 " Calculation time for fibonacci(%d) = %.3f seconds%n",
87 n, timeData.timeInSeconds());
88 }
89
90 // display fibonacci calculation result and total calculation time
91 private static double calculateTime(TimeData result1, TimeData result2)
92 {
93 TimeData bothThreads = new TimeData();
94
95 // determine earlier start time
96 bothThreads.start = result1.start.compareTo(result2.start) < 0 ?
97 result1.start : result2.start;
98
99 // determine later end time
100 bothThreads.end = result1.end.compareTo(result2.end) > 0 ?
101 result1.end : result2.end;
102
103 return bothThreads.timeInSeconds();
104 }
105 } // end class FibonacciDemo

```

Synchronous Long Running Calculations  
 Calculating fibonacci(45)  
 fibonacci(45) = 1134903170  
 Calculation time for fibonacci(45) = 5.884 seconds  
 Calculating fibonacci(44)  
 fibonacci(44) = 701408733

**Fig. 23.30** | Fibonacci calculations performed synchronously and asynchronously. (Part 3 of 4.)



```
Calculation time for fibonacci(44) = 3.605 seconds
Total calculation time = 9.506 seconds
```

#### Asynchronous Long Running Calculations

```
Calculating fibonacci(45)
Calculating fibonacci(44)
fibonacci(44) = 701408733
Calculation time for fibonacci(44) = 3.650 seconds
fibonacci(45) = 1134903170
Calculation time for fibonacci(45) = 5.911 seconds
Total calculation time = 5.911 seconds
```

Synchronous calculations took 161% more time than the asynchronous ones

**Fig. 23.30** | Fibonacci calculations performed synchronously and asynchronously. (Part 4 of 4.)

#### *Class TimeData*

Class `TimeData` (lines 10–20) stores two `Instant`s representing the start and end time of a task, and provides method `timeInSeconds` to calculate the total time between them. We use `TimeData` objects throughout this example to calculate the time required to perform Fibonacci calculations.

#### *Method startFibonacci for Performing and Timing Fibonacci Calculations*

Method `startFibonacci` (lines 59–70) is called several times in `main` (lines 29, 30, 39 and 41) to initiate Fibonacci calculations and to calculate the time each calculation requires. The method receives the Fibonacci number to calculate and performs the following tasks:

- Line 62 creates a `TimeData` object to store the calculation's start and end times.
- Line 64 displays the Fibonacci number to be calculated.
- Line 65 stores the current time before method `fibonacci` is called.
- Line 66 calls method `fibonacci` to perform the calculation.
- Line 67 stores the current time after the call to `fibonacci` completes.
- Line 68 displays the result and the total time required for the calculation.
- Line 69 returns the `TimeData` object for use in method `main`.

#### *Performing Fibonacci Calculations Synchronously*

Method `main` (lines 24–56) first demonstrates synchronous Fibonacci calculations. Line 29 calls `startFibonacci(45)` to initiate the `fibonacci(45)` calculation and store the `TimeData` object containing the calculation's start and end times. When this call completes, line 30 calls `startFibonacci(44)` to initiate the `fibonacci(44)` calculation and store its `TimeData`. Next, lines 31–32 pass both `TimeData` objects to method `calculateTime` (lines 91–104), which returns the total calculation time in seconds. Lines 33–34 display the total calculation time for the synchronous Fibonacci calculations.

#### *Performing Fibonacci Calculations Asynchronously*

Lines 38–41 in `main` launch the asynchronous Fibonacci calculations in separate threads. `CompletableFuture` static method `supplyAsync` executes an asynchronous task that returns a value. The method receives as its argument an object that implements interface `Sup-`

plier—in this case, we use a lambda with empty parameter lists to invoke `startFibonacci(45)` (line 39) and `startFibonacci(44)` (line 41). The compiler infers that `supplyAsync` returns a `CompletableFuture<TimeData>` because method `startFibonacci` returns type `TimeData`. Class `CompletableFuture` also provides static method `runAsync` to execute an asynchronous task that does not return a result—this method receives a `Runnable`.

### *Getting the Asynchronous Calculations' Results*

Class `CompletableFuture` implements interface `Future`, so we can obtain the asynchronous tasks' results by calling `Future` method `get` (lines 44–45). These are *blocking* calls—they cause the main thread to *wait* until the asynchronous tasks complete and return their results. In our case, the results are `TimeData` objects. Once both tasks return, lines 46–47 pass both `TimeData` objects to method `calculateTime` (lines 91–104) to get the total calculation time in seconds. Then, lines 48–49 display the total calculation time for the asynchronous Fibonacci calculations. Finally, lines 52–55 calculate and display the percentage difference in execution time for the synchronous and asynchronous calculations.

### *Program Outputs*

On our dual-core computer, the synchronous calculations took a total of 9.506 seconds. Though the individual asynchronous calculations took approximately the same amount of time as the corresponding synchronous calculations, the total time for the asynchronous calculations was only 5.911 seconds, because the two calculations were actually performed *in parallel*. As you can see in the output, the synchronous calculations took 161% more time to complete, so asynchronous execution provided a significant performance improvement.

## 23.15 (Advanced) Fork/Join Framework

Java's concurrency APIs include the fork/join framework, which helps programmers parallelize algorithms. The framework is beyond the scope of this book. Experts tell us that most Java programmers will nevertheless benefit by the fork/join framework's use “behind the scenes” in the Java API and other third party libraries. For example, the parallel capabilities of Java SE 8 streams are implemented using this framework.

The fork/join framework is particularly well suited to divide-and-conquer-style algorithms, such as the merge sort that we implemented in Section 19.8. Recall that the recursive merge-sort algorithm sorts an array by *splitting* it into two equal-sized subarrays, *sorting* each subarray, then *merging* them into one larger array. Each subarray is sorted by performing the same algorithm on the subarray. For algorithms like merge sort, the fork/join framework can be used to create concurrent tasks so that they can be distributed across multiple processors and be truly performed in parallel—the details of assigning the tasks to different processors are handled for you by the framework.

## 23.16 Wrap-Up

In this chapter, we presented Java's concurrency capabilities for enhancing application performance on multi-core systems. You learned the differences between concurrent and parallel execution. We discussed that Java makes concurrency available to you through multithreading. You also learned that the JVM itself creates threads to run a program, and that it also can create threads to perform housekeeping tasks such as garbage collection.

We discussed the life cycle of a thread and the states that a thread may occupy during its lifetime. Next, we presented the interface `Runnable`, which is used to specify a task that can execute concurrently with other tasks. This interface's `run` method is invoked by the thread executing the task. We showed how to execute a `Runnable` object by associating it with an object of class `Thread`. Then we showed how to use the `Executor` interface to manage the execution of `Runnable` objects via thread pools, which can reuse existing threads to eliminate the overhead of creating a new thread for each task and can improve performance by optimizing the number of threads to ensure that the processor stays busy.

You learned that when multiple threads share an object and one or more of them modify that object, indeterminate results may occur unless access to the shared object is managed properly. We showed you how to solve this problem via thread synchronization, which coordinates access to shared mutable data by multiple concurrent threads. You learned several techniques for performing synchronization—first with the built-in class `ArrayBlockingQueue` (which handles *all* the synchronization details for you), then with Java's built-in monitors and the `synchronized` keyword, and finally with interfaces `Lock` and `Condition`.

We discussed the fact that Swing GUIs are not thread safe, so all interactions with and modifications to the GUI must be performed in the event dispatch thread. We also discussed the problems associated with performing long-running calculations in the event dispatch thread. Then we showed how you can use the `SwingWorker` class to perform long-running calculations in worker threads. You learned how to display the results of a `SwingWorker` in a GUI when the calculation completed and how to display intermediate results while the calculation was still in process.

We revisited the `Arrays` class's `sort` and `parallelSort` methods to demonstrate the benefit of using a parallel sorting algorithm on a multi-core processor. We used the Java SE 8 Date/Time API's `Instant` and `Duration` classes to time the sort operations.

You learned that Java SE 8 streams are easy to parallelize, enabling programs to benefit from enhanced performance on multi-core systems, and that to obtain a parallel stream, you simply invoke method `parallel` on an existing stream.

We discussed the `Callable` and `Future` interfaces, which enable you to execute tasks that return results and to obtain those results, respectively. We then presented an example of performing long-running tasks synchronously and asynchronously using Java SE 8's new `CompletableFuture` class. We use the multithreading techniques introduced in this chapter again in Chapter 28, *Networking*, to help build multithreaded servers that can interact with multiple clients concurrently. In the next chapter, we introduce database-application development with Java's JDBC API.

## Summary

### Section 23.1 Introduction

- Two tasks that are operating concurrently are both making progress at once.
- Two tasks that are operating in parallel are executing simultaneously. In this sense, parallelism is a subset of concurrency. Today's multi-core computers have multiple processors that can perform tasks in parallel.
- Java makes concurrency available to you through the language and APIs.

- Java programs can have multiple threads of execution, where each thread has its own method-call stack and program counter, allowing it to execute concurrently with other threads. This capability is called multithreading.
- In a multithreaded application, threads can be distributed across multiple processors (if available) so that multiple tasks execute in parallel and the application can operate more efficiently.
- The JVM creates threads to run a program and for housekeeping tasks such as garbage collection.
- Multithreading can also increase performance on single-processor systems—when one thread cannot proceed (because, for example, it's waiting for the result of an I/O operation), another can use the processor.
- The vast majority of programmers should use existing collection classes and interfaces from the concurrency APIs that manage synchronization for you.

### Section 23.2 Thread States and Life Cycle

- A new thread begins its life cycle in the *new* state (p. 953). When the program starts the thread, it's placed in the *runnable* state. A thread in the *runnable* state is considered to be executing its task.
- A *runnable* thread transitions to the *waiting* state (p. 953) to wait for another thread to perform a task. A *waiting* thread transitions to *runnable* when another thread notifies it to continue executing.
- A *runnable* thread can enter the *timed waiting* state (p. 953) for a specified interval of time, transitioning back to *runnable* when that time interval expires or when the event it's waiting for occurs.
- A *runnable* thread can transition to the *timed waiting* state if it provides an optional wait interval when it's waiting for another thread to perform a task. Such a thread will return to the *runnable* state when it's notified by another thread or when the timed interval expires.
- A sleeping thread (p. 953) remains in the *timed waiting* state for a designated period of time, after which it returns to the *runnable* state.
- A *runnable* thread transitions to the *blocked* state (p. 953) when it attempts to perform a task that cannot be completed immediately and the thread must temporarily wait until that task completes. At that point, the *blocked* thread transitions to the *runnable* state, so it can resume execution.
- A *runnable* thread enters the *terminated* state (p. 953) when it successfully completes its task or otherwise terminates (perhaps due to an error).
- At the operating-system level, the *runnable* state (p. 954) encompasses two separate states. When a thread first transitions to the *runnable* state from the *new* state, it's in the *ready* state (p. 954). A *ready* thread enters the *running* state (p. 954) when the operating system dispatches it.
- Most operating systems allot a quantum (p. 954) in which a thread performs its task. When this expires, the thread returns to the *ready* state and another thread is assigned to the processor.
- Thread scheduling determines which thread to dispatch based on thread priorities.
- The job of an operating system's thread scheduler (p. 954) is to determine which thread runs next.
- When a higher-priority thread enters the *ready* state, the operating system generally preempts the currently *running* thread (an operation known as preemptive scheduling; p. 955).
- Depending on the operating system, higher-priority threads could postpone—possibly indefinitely (p. 955)—the execution of lower-priority threads.

### Section 23.3 Creating and Executing Threads with the **Executor Framework**

- A `Runnable` (p. 955) object represents a task that can execute concurrently with other tasks.
- Interface `Runnable` declares method `run` (p. 955) in which you place the code that defines the task to perform. The thread executing a `Runnable` calls method `run` to perform the task.
- A program will not terminate until its last thread completes execution.

- You cannot predict the order in which threads will be scheduled, even if you know the order in which they were created and started.
- It's recommended that you use the `Executor` interface (p. 955) to manage the execution of `Runnable` objects. An `Executor` object typically creates and manages a group of threads—called a thread pool (p. 955).
- `Executors` (p. 956) can reuse existing threads and can improve performance by optimizing the number of threads to ensure that the processor stays busy.
- `Executor` method `execute` (p. 955) receives a `Runnable` and assigns it to an available thread in a thread pool. If there are none, the `Executor` creates a new thread or waits for one to become available.
- Interface `ExecutorService` (of package `java.util.concurrent`; p. 956) extends interface `Executor` and declares other methods for managing the life cycle of an `Executor`.
- An object that implements the `ExecutorService` interface can be created using static methods declared in class `Executors` (of package `java.util.concurrent`).
- `Executors` method `newCachedThreadPool` (p. 957) returns an `ExecutorService` that creates new threads as they're needed by the application.
- `ExecutorService` method `execute` executes its `Runnable` sometime in the future. The method returns immediately from each invocation—the program does not wait for each task to finish.
- `ExecutorService` method `shutdown` (p. 959) notifies the `ExecutorService` to stop accepting new tasks, but continues executing existing tasks and terminates when those tasks complete execution.

### Section 23.4 Thread Synchronization

- Thread synchronization (p. 960) coordinates access to shared mutable data by multiple concurrent threads.
- By synchronizing threads, you can ensure that each thread accessing a shared object excludes all other threads from doing so simultaneously—this is called mutual exclusion (p. 960).
- A common way to perform synchronization is to use Java's built-in monitors. Every object has a monitor and a monitor lock (p. 960). The monitor ensures that its object's monitor lock is held by a maximum of only one thread at any time, and thus can be used to enforce mutual exclusion.
- If an operation requires the executing thread to hold a lock while the operation is performed, a thread must acquire the lock (p. 960) before it can proceed with the operation. Any other threads attempting to perform an operation that requires the same lock will be *blocked* until the first thread releases the lock, at which point the *blocked* threads may attempt to acquire the lock.
- To specify that a thread must hold a monitor lock to execute a block of code, the code should be placed in a `synchronized` statement (p. 960). Such code is said to be guarded by the monitor lock.
- The `synchronized` statements are declared using the `synchronized` keyword:

```
synchronized (object)
{
 statements
} // end synchronized statement
```

where *object* is the object whose monitor lock will be acquired; *object* is normally this if it's the object in which the `synchronized` statement appears.

- Java also allows `synchronized` methods (p. 961). Before executing, a `synchronized` instance method must acquire the lock on the object that's used to call the method. Similarly, a static `synchronized` method must acquire the lock on the class that's used to call the method.
- `ExecutorService` method `awaitTermination` (p. 965) forces a program to wait for threads to terminate. It returns control to its caller either when all tasks executing in the `ExecutorService`

complete or when the specified timeout elapses. If all tasks complete before the timeout elapses, the method returns `true`; otherwise, it returns `false`.

- You can simulate atomicity (p. 966) by ensuring that only one thread performs a set of operations at a time. Atomicity can be achieved with synchronized statements or synchronized methods.
- When you share immutable data across threads, you should declare the corresponding data fields `final` to indicate that variables' values will not change after they're initialized.

### ***Section 23.5 Producer/Consumer Relationship without Synchronization***

- In a multithreaded producer/consumer relationship (p. 968), a producer thread generates data and places it in a shared object called a buffer. A consumer thread reads data from the buffer.
- Operations on a buffer data shared by a producer and a consumer should proceed only if the buffer is in the correct state. If the buffer is not full, the producer may produce; if the buffer is not empty, the consumer may consume. If the buffer is full when the producer attempts to write into it, the producer must wait until there's space. If the buffer is empty or the previous value was already read, the consumer must wait for new data to become available.

### ***Section 23.6 Producer/Consumer Relationship: ArrayBlockingQueue***

- `ArrayBlockingQueue` (p. 976) is a fully implemented buffer class from package `java.util.concurrent` that implements the `BlockingQueue` interface.
- An `ArrayBlockingQueue` can implement a shared buffer in a producer/consumer relationship. Method `put` (p. 976) places an element at the end of the `BlockingQueue`, waiting if the queue is full. Method `take` (p. 976) removes an element from the head of the `BlockingQueue`, waiting if the queue is empty.
- `ArrayBlockingQueue` stores shared mutable data in an array that's sized with an argument passed to the constructor. Once created, an `ArrayBlockingQueue` is fixed in size.

### ***Section 23.7 (Advanced) Producer/Consumer Relationship with synchronized, wait, notify and notifyAll***

- You can implement a shared buffer yourself using the `synchronized` keyword and `Object` methods `wait`, `notify` and `notifyAll` (p. 980).
- A thread can call `Object` method `wait` to release an object's monitor lock, and wait in the *waiting* state while the other threads try to enter the object's `synchronized` statement(s) or method(s).
- When a thread executing a `synchronized` statement (or method) completes or satisfies the condition on which another thread may be waiting, it can call `Object` method `notify` (p. 980) to allow a waiting thread to transition to the *runnable* state. At this point, the thread that was transitioned can attempt to reacquire the monitor lock on the object.
- If a thread calls `notifyAll` (p. 980), then all the threads waiting for the monitor lock become eligible to reacquire the lock (that is, they all transition to the *runnable* state).

### ***Section 23.8 (Advanced) Producer/Consumer Relationship: Bounded Buffers***

- You cannot make assumptions about the relative speeds of concurrent threads.
- A bounded buffer (p. 987) can be used to minimize the amount of waiting time for threads that share resources and operate at the same average speeds. If the producer temporarily produces values faster than the consumer can consume them, the producer can write additional values into the extra buffer space (if any are available). If the consumer consumes faster than the producer produces new values, the consumer can read additional values (if there are any) from the buffer.
- The key to using a bounded buffer with a producer and consumer that operate at about the same speed is to provide the buffer with enough locations to handle the anticipated "extra" production.

- The simplest way to implement a bounded buffer is to use an `ArrayBlockingQueue` for the buffer so that all of the synchronization details are handled for you.

### *Section 23.9 (Advanced) Producer/Consumer Relationship: The Lock and Condition Interfaces*

- The `Lock` and `Condition` interfaces (p. 994) give programmers more precise control over thread synchronization, but are more complicated to use.
- Any object can contain a reference to an object that implements the `Lock` interface (of package `java.util.concurrent.locks`). A thread calls a `Lock`'s `lock` method (p. 994) to acquire the lock. Once a `Lock` has been obtained by one thread, the `Lock` will not allow another thread to obtain it until the first thread releases it (by calling the `Lock`'s `unlock` method; p. 994).
- If several threads are trying to call method `lock` on the same `Lock` object at the same time, only one thread can obtain the lock—the others are placed in the *waiting* state. When a thread calls `unlock`, the object's lock is released and a waiting thread attempting to lock the object proceeds.
- Class `ReentrantLock` (p. 994) is a basic implementation of the `Lock` interface.
- The `ReentrantLock` constructor takes a `boolean` that specifies whether the lock has a fairness policy (p. 994). If `true`, the `ReentrantLock`'s fairness policy is “the longest-waiting thread will acquire the lock when it's available”—this prevents indefinite postponement. If the argument is set to `false`, there's no guarantee as to which waiting thread will acquire the lock when it's available.
- If a thread that owns a `Lock` determines that it cannot continue with its task until some condition is satisfied, the thread can wait on a condition object (p. 995). Using `Lock` objects allows you to explicitly declare the condition objects on which a thread may need to wait.
- `Condition` (p. 995) objects are associated with a specific `Lock` and are created by calling `Lock` method `newCondition`, which returns a `Condition` object. To wait on a `Condition`, the thread can call the `Condition`'s `await` method. This immediately releases the associated `Lock` and places the thread in the *waiting* state for that `Condition`. Other threads can then try to obtain the `Lock`.
- When a *runnable* thread completes a task and determines that a *waiting* thread can now continue, the *runnable* thread can call `Condition` method `signal` to allow a thread in that `Condition`'s *waiting* state to return to the *runnable* state. At this point, the thread that transitioned from the *waiting* state to the *runnable* state can attempt to reacquire the `Lock`.
- If multiple threads are in a `Condition`'s *waiting* state when `signal` is called, the default implementation of `Condition` signals the longest-waiting thread to transition to the *runnable* state.
- If a thread calls `Condition` method `signalAll`, then all the threads waiting for that condition transition to the *runnable* state and become eligible to reacquire the `Lock`.
- When a thread is finished with a shared object, it must call method `unlock` to release the `Lock`.
- `Locks` allow you to interrupt waiting threads or to specify a timeout for waiting to acquire a lock—not possible with `synchronized`. Also, a `Lock` object is not constrained to be acquired and released in the same block of code, which is the case with the `synchronized` keyword.
- `Condition` objects allow you to specify multiple conditions on which threads may wait. Thus, it's possible to indicate to waiting threads that a specific condition object is now true by calling that `Condition` object's `signal` or `signalAll` methods (p. 995). With `synchronized`, there's no way to explicitly state the condition on which threads are waiting.

### *Section 23.11 Multithreading with GUI: SwingWorker*

- The event dispatch thread (p. 1003) handles interactions with the application's GUI components. All tasks that interact with the GUI are placed in an event queue and executed sequentially by this thread.

- Swing GUI components are not thread safe. Thread safety is achieved by ensuring that Swing components are accessed from only the event dispatch thread.
- Performing a lengthy computation in response to a user interface interaction ties up the event dispatch thread, preventing it from attending to other tasks and causing the GUI components to become unresponsive. Long-running computations should be handled in separate threads.
- You can extend generic class `SwingWorker` (package `javax.swing`; p. 1003), which implements `Runnable`, to perform a task in a worker thread then update Swing components from the event dispatch thread based on the task's results. You override its `doInBackground` and `done` methods. Method `doInBackground` performs the computation and returns the result. Method `done` displays the results in the GUI.
- Class `SwingWorker`'s first type parameter indicates the type returned by the `doInBackground` method; the second indicates the type that's passed between the `publish` and `process` methods to handle intermediate results.
- Method `doInBackground` is called from a worker thread. After `doInBackground` returns, method `done` is called from the event dispatch thread to display the results.
- An `ExecutionException` is thrown if an exception occurs during the computation.
- `SwingWorker` method `publish` repeatedly sends intermediate results to method `process`, which displays the results in a GUI component. Method `setProgress` updates the progress property.
- Method `process` executes in the event dispatch thread and receives data from method `publish`. The passing of values between `publish` in the worker thread and `process` in the event dispatch thread is asynchronous; `process` is not necessarily invoked for every call to `publish`.
- `PropertyChangeListener` (p. 1016) is an interface from package `java.beans` that defines a single method, `propertyChange`. Every time method `setProgress` is invoked, a `PropertyChangeEvent` is generated to indicate that the progress property has changed.

### ***Section 23.12 Timing sort and parallelSort with the Java SE 8 Date/Time API***

- Class `Instant`'s static method `now` gets the current time.
- To determine the difference between two `Instant`s, use class `Duration`'s static method `between`, which returns a `Duration` object containing the time difference.
- `Duration` method `toMillis` returns the `Duration` as a long value milliseconds.
- `NumberFormat` static method `getPercentInstance` returns a `NumberFormat` that's used to format a number as a percentage.
- `NumberFormat` method `format` returns a `String` representation of its argument in the specified numeric format.
- `Arrays` static method `parallelSetAll` fills an array with values produced by a generator function that receives an `int` and returns a value of type `int`, `long` or `double`. Depending on which overload of method `parallelSetAll` is used the generator function is an object of a class that implements `IntToDoubleFunction` (for double arrays), `IntUnaryOperator` (for int arrays), `IntToLongFunction` (for long arrays) or `IntFunction` (for arrays of any non-primitive type).
- `Arrays` static method `parallelPrefix` applies a `BinaryOperator` to the current and previous array elements and stores the result in the current element.

### ***Section 23.13 Java SE 8: Sequential vs. Parallel Streams***

- Streams are easy to parallelize, enabling programs to benefit from enhanced performance on multi-core systems.
- To obtain a parallel stream, simply invoke method `parallel` on an existing stream.



**Section 23.14 (Advanced) Interfaces *Callable* and *Future***

- The `Callable` (p. 1022) interface (of package `java.util.concurrent`) declares a single method named `call` that allows a task to return a value.
- `ExecutorService` method `submit` (p. 1022) executes a `Callable` passed in as its argument. Method `submit` returns an object of type `Future` (of package `java.util.concurrent`) that represents the future result of the executing `Callable`.
- Interface `Future` (p. 1022) declares method `get` to return the result of the `Callable`. The interface also provides methods that enable you to cancel a `Callable`'s execution, determine whether the `Callable` was cancelled and determine whether the `Callable` completed its task.
- Java SE 8 introduces a new `CompletableFuture` class (package `java.util.concurrent`; p. 1022), which implements the `Future` interface and enables you to asynchronously execute `Runnable`s that perform tasks or `Supplier`s that return values.
- Interface `Supplier` (p. 1022), like interface `Callable`, is a functional interface with a single method (in this case, `get`) that receives no arguments and returns a result.
- `CompletableFuture` static method `supplyAsync` (p. 1033) asynchronously executes a `Supplier` task that returns a value.
- `CompletableFuture` static method `runAsync` (p. 1034) asynchronously executes a `Runnable` task that does not return a result.
- `CompletableFuture` method `get` is a blocking method—it causes the calling thread to wait until the asynchronous task completes and returns its results.

**Section 23.15 (Advanced) Fork/Join Framework**

- Java's concurrency APIs include the fork/join framework, which helps programmers parallelize algorithms. The fork/join framework particularly well suited to divide-and-conquer-style algorithms, like the merge sort.

**Self-Review Exercises**

**23.1** Fill in the blanks in each of the following statements:

- A thread enters the *terminated* state when \_\_\_\_\_.
- To pause for a designated number of milliseconds and resume execution, a thread should call method \_\_\_\_\_ of class \_\_\_\_\_.
- A *runnable* thread can enter the \_\_\_\_\_ state for a specified interval of time.
- At the operating-system level, the *runnable* state actually encompasses two separate states, \_\_\_\_\_ and \_\_\_\_\_.
- `Runnable`s are executed using a class that implements the \_\_\_\_\_ interface.
- `ExecutorService` method \_\_\_\_\_ ends each thread in an `ExecutorService` as soon as it finishes executing its current `Runnable`, if any.
- In a(n) \_\_\_\_\_ relationship, the \_\_\_\_\_ generates data and stores it in a shared object, and the \_\_\_\_\_ reads data from the shared object.
- Keyword \_\_\_\_\_ indicates that only one thread at a time should execute on an object.

**23.2** (*Advanced Optional Sections*) Fill in the blanks in each of the following statements:

- Method \_\_\_\_\_ of class `Condition` moves a single thread in an object's *waiting* state to the *runnable* state.
- Method \_\_\_\_\_ of class `Condition` moves every thread in an object's *waiting* state to the *runnable* state.

- c) A thread can call method \_\_\_\_\_ on a Condition object to release the associated Lock and place that thread in the \_\_\_\_\_ state.
- d) Class \_\_\_\_\_ implements the BlockingQueue interface using an array.
- e) Class Instant's static method \_\_\_\_\_ gets the current time.
- f) Duration method \_\_\_\_\_ returns the Duration as a long value milliseconds.
- g) NumberFormat static method \_\_\_\_\_ returns a NumberFormat that's used to format a number as a percentage.
- h) NumberFormat method \_\_\_\_\_ returns a String representation of its argument in the specified numeric format.
- i) Arrays static method \_\_\_\_\_ fills an array with values produced by a generator function.
- j) Arrays static method \_\_\_\_\_ applies a BinaryOperator to the current and previous array elements and stores the result in the current element.
- k) To obtain a parallel stream, simply invoke method \_\_\_\_\_ on an existing stream.
- l) Among its many features a CompletableFuture enables you to asynchronously execute \_\_\_\_\_ that perform tasks or \_\_\_\_\_ that return values.

**23.3** State whether each of the following is *true* or *false*. If *false*, explain why.

- a) A thread is not *runnable* if it has terminated.
- b) Some operating systems use timeslicing with threads. Therefore, they can enable threads to preempt threads of the same priority.
- c) When the thread's quantum expires, the thread returns to the *running* state as the operating system assigns it to a processor.
- d) On a single-processor system without timeslicing, each thread in a set of equal-priority threads (with no other threads present) runs to completion before other threads of equal priority get a chance to execute.

**23.4** (*Advanced Optional Sections*) State whether each of the following is *true* or *false*. If *false*, explain why.

- a) To determine the difference between two Instants, use class Duration's static method difference, which returns a Duration object containing the time difference.
- b) Streams are easy to parallelize, enabling programs to benefit from enhanced performance on multi-core systems.
- c) Interface Supplier, like interface Callable, is a functional interface with a single method that receives no arguments and returns a result.
- d) CompletableFuture static method runAsync asynchronously executes a Supplier task that returns a value.
- e) CompletableFuture static method supplyAsync asynchronously executes a Runnable task that does not return a result.

## Answers to Self-Review Exercises

**23.1** a) its run method ends. b) sleep, Thread. c) *timed waiting*. d) *ready, running*. e) Executor. f) shutdown. g) producer/consumer, producer, consumer. h) synchronized.

**23.2** a) signal. b) signalAll. c) await, *waiting*. d) ArrayBlockingQueue. e) now. f) toMillis. g) getPercentInstance. h) format. i) parallelSetAll. j) parallelPrefix. k) parallel. l) Runnables, Suppliers.

**23.3** a) True. b) False. Timeslicing allows a thread to execute until its timeslice (or quantum) expires. Then other threads of equal priority can execute. c) False. When a thread's quantum expires, the thread returns to the *ready* state and the operating system assigns to the processor another thread. d) True.

**23.4** a) False. The `Duration` method for calculating the difference between two `Instant`s is named `between`. b) True. c) True. d) False. The method that asynchronously executes a `Supplier` is `supplyAsync`. e) False. The method that asynchronously executes a `Runnable` is `runAsync`.

## Exercises

- 23.5** (*True or False*) State whether each of the following is *true* or *false*. If *false*, explain why.
- a) Method `sleep` does not consume processor time while a thread sleeps.
  - b) Swing components are thread safe.
  - c) (*Advanced*) Declaring a method synchronized guarantees that deadlock cannot occur.
  - d) (*Advanced*) Once a `ReentrantLock` has been obtained by a thread, the `ReentrantLock` object will not allow another thread to obtain the lock until the first thread releases it.
- 23.6** (*Multithreading Terms*) Define each of the following terms.
- a) thread
  - b) multithreading
  - c) *runnable* state
  - d) *timed waiting* state
  - e) preemptive scheduling
  - f) `Runnable` interface
  - g) producer/consumer relationship
  - h) quantum
- 23.7** (*Advanced: Multithreading Terms*) Discuss each of the following terms in the context of Java's threading mechanisms:
- a) synchronized
  - b) wait
  - c) notify
  - d) notifyAll
  - e) Lock
  - f) Condition
- 23.8** (*Blocked State*) List the reasons for entering the *blocked* state. For each of these, describe how the program will normally leave the *blocked* state and enter the *runnable* state.
- 23.9** (*Deadlock and Indefinite Postponement*) Two problems that can occur in systems that allow threads to wait are deadlock, in which one or more threads will wait forever for an event that cannot occur, and indefinite postponement, in which one or more threads will be delayed for some unpredictably long time. Give an example of how each of these problems can occur in multithreaded Java programs.
- 23.10** (*Bouncing Ball*) Write a program that bounces a blue ball inside a `JPanel`. The ball should begin moving with a `mousePressed` event. When the ball hits the edge of the `JPanel`, it should bounce off the edge and continue in the opposite direction. The ball should be updated using a `Runnable`.
- 23.11** (*Bouncing Balls*) Modify the program in Exercise 23.10 to add a new ball each time the user clicks the mouse. Provide for a minimum of 20 balls. Randomly choose the color for each new ball.
- 23.12** (*Bouncing Balls with Shadows*) Modify the program in Exercise 23.11 to add shadows. As a ball moves, draw a solid black oval at the bottom of the `JPanel`. You may consider adding a 3-D effect by increasing or decreasing the size of each ball when it hits the edge of the `JPanel`.

**23.13** (*Advanced: Circular Buffer with Locks and Conditions*) Reimplement the example in Section 23.8 using the Lock and Condition concepts presented in Section 23.9.

**23.14** (*Bounded Buffer: A Real-World Example*) Describe how a highway off-ramp onto a local road is a good example of a producer/consumer relationship with a bounded buffer. In particular, discuss how the designers might choose the size of the off-ramp.

### *Parallel Streams*

For Exercises 23.15–23.17, you may need to create larger data sets to see a significant performance difference.

**23.15** (*Summarizing the Words in a File*) Reimplement Fig. 17.17 using parallel streams. Use the Date/Time API timing techniques you learned in Section 23.12 to compare the time required for the sequential and parallel versions of the program.

**23.16** (*Summarizing the Characters in a File*) Reimplement Exercise 17.9 using parallel streams. Use the Date/Time API timing techniques you learned in Section 23.12 to compare the time required for the sequential and parallel versions of the program.

**23.17** (*Summarizing the File Types in a Directory*) Reimplement Exercise 17.10 using parallel streams. Use the Date/Time API timing techniques you learned in Section 23.12 to compare the time required for the sequential and parallel versions of the program.

# Accessing Databases with JDBC

# 24



*It is a capital mistake to theorize before one has data.*

—Arthur Conan Doyle

*Now go, write it before them in a table, and note it in a book, that it may be for the time to come for ever and ever.*

—The Holy Bible, Isaiah 30:8

*Get your facts first, and then you can distort them as much as you please.*

—Mark Twain

*I like two kinds of men: domestic and foreign.*

—Mae West

## Objectives

In this chapter you'll learn:

- Relational database concepts.
- To use Structured Query Language (SQL) to retrieve data from and manipulate data in a database.
- To use the JDBC™ API to access databases.
- To use the RowSet interface from package `javax.sql` to manipulate databases.
- To use JDBC 4's automatic JDBC driver discovery.
- To create precompiled SQL statements with parameters via `PreparedStatement`.
- How transaction processing makes database applications more robust.

- 24.1 Introduction
- 24.2 Relational Databases
- 24.3 A books Database
- 24.4 SQL
  - 24.4.1 Basic SELECT Query
  - 24.4.2 WHERE Clause
  - 24.4.3 ORDER BY Clause
  - 24.4.4 Merging Data from Multiple Tables: INNER JOIN
  - 24.4.5 INSERT Statement
  - 24.4.6 UPDATE Statement
  - 24.4.7 DELETE Statement
- 24.5 Setting up a Java DB Database
  - 24.5.1 Creating the Chapter's Databases on Windows
  - 24.5.2 Creating the Chapter's Databases on Mac OS X
  - 24.5.3 Creating the Chapter's Databases on Linux
- 24.6 Manipulating Databases with JDBC
  - 24.6.1 Connecting to and Querying a Database
  - 24.6.2 Querying the books Database
- 24.7 RowSet Interface
- 24.8 PreparedStatements
- 24.9 Stored Procedures
- 24.10 Transaction Processing
- 24.11 Wrap-Up

Summary | Self-Review Exercise | Answers to Self-Review Exercise | Exercises

## 24.1 Introduction

A **database** is an organized collection of data. There are many different strategies for organizing data to facilitate easy access and manipulation. A **database management system** (DBMS) provides mechanisms for storing, organizing, retrieving and modifying data for many users. Database management systems allow for the access and storage of data without concern for the internal representation of data.

### Structured Query Language

Today's most popular database systems are *relational databases* (Section 24.2). A language called **SQL**—pronounced “sequel,” or as its individual letters—is the international standard language used almost universally with relational databases to perform **queries** (i.e., to request information that satisfies given criteria) and to manipulate data. [Note: As you learn about SQL, you'll see some authors writing “a SQL statement” (which assumes the pronunciation “sequel”) and others writing “an SQL statement” (which assumes that the individual letters are pronounced). In this book we pronounce SQL as “sequel.”]

### Popular Relational Database Management Systems

Some popular **relational database management systems** (RDBMSs) are Microsoft SQL Server®, Oracle®, Sybase®, IBM DB2®, Informix®, PostgreSQL and MySQL™. The JDK comes with a pure-Java RDBMS called Java DB—the Oracle-branded version of Apache Derby™.

### JDBC

Java programs interact with databases using the **Java Database Connectivity** (JDBC™) API. A **JDBC driver** enables Java applications to connect to a database in a particular DBMS and allows you to manipulate that database using the JDBC API.



### Software Engineering Observation 24.1

*The JDBC API is portable—the same code can manipulate databases in various RDBMSs.*

Most popular database management systems provide JDBC drivers. In this chapter, we introduce JDBC and use it to manipulate Java DB databases. The techniques we demonstrate here can be used to manipulate other databases that have JDBC drivers. If not, third-party vendors provide JDBC drivers for many DBMSs. This chapter's examples were tested with Java DB using both the Java SE 7 and Java SE 8 JDKs.

### *Java Persistence API (JPA)*

In online Chapter 29, we introduce Java Persistence API (JPA). In that chapter, you'll learn how to autogenerate Java classes that represent the tables in a database and the relationships between them—known as object-relational mapping—then use objects of those classes to interact with a database. As you'll see, storing data in and retrieving data from a database will be handled for you—the techniques you learn in this chapter will typically be hidden from you by JPA.

## 24.2 Relational Databases

A **relational database** is a logical representation of data that allows the data to be accessed without consideration of its physical structure. A relational database stores data in **tables**. Figure 24.1 illustrates a sample table that might be used in a personnel system. The table name is `Employee`, and its primary purpose is to store the attributes of employees. Tables are composed of **rows**, each describing a single entity—in Fig. 24.1, an employee. Rows are composed of **columns** in which values are stored. This table consists of six rows. The **Number** column of each row is the table's **primary key**—a column (or group of columns) with a value that is *unique* for each row. This guarantees that each row can be identified by its primary key. Good examples of primary-key columns are a social security number, an employee ID number and a part number in an inventory system, as values in each of these columns are guaranteed to be unique. The rows in Fig. 24.1 are displayed in order by primary key. In this case, the rows are listed in ascending order by primary key, but they could be listed in descending order or in no particular order at all.

---

|       | Number      | Name     | Department | Salary | Location    |
|-------|-------------|----------|------------|--------|-------------|
|       | 23603       | Jones    | 413        | 1100   | New Jersey  |
|       | 24568       | Kerwin   | 413        | 2000   | New Jersey  |
| Row { | 34589       | Larson   | 642        | 1800   | Los Angeles |
|       | 35761       | Myers    | 611        | 1400   | Orlando     |
|       | 47132       | Neumann  | 413        | 9000   | New Jersey  |
|       | 78321       | Stephens | 611        | 8500   | Orlando     |
|       | Primary key |          | Column     |        |             |

---

**Fig. 24.1** | `Employee` table sample data.

Each column represents a different data attribute. Rows are unique (by primary key) within a table, but particular column values may be duplicated between rows. For example, three different rows in the `Employee` table's `Department` column contain number 413.

### Selecting Data Subsets

Different users of a database are often interested in different data and different relationships among the data. Most users require only subsets of the rows and columns. Queries specify which subsets of the data to select from a table. You use SQL to define queries. For example, you might select data from the `Employee` table to create a result that shows where each department is located, presenting the data sorted in increasing order by department number. This result is shown in Fig. 24.2. SQL is discussed in Section 24.4.

| Department | Location    |
|------------|-------------|
| 413        | New Jersey  |
| 611        | Orlando     |
| 642        | Los Angeles |

**Fig. 24.2** | Distinct Department and Location data from the `Employee` table.

## 24.3 A books Database

We introduce relational databases in the context of this chapter's `books` database, which you'll use in several examples. Before we discuss SQL, we discuss the *tables* of the `books` database. We use this database to introduce various database concepts, including how to use SQL to obtain information from the database and to manipulate the data. We provide a script to create the database. You can find the script in the examples directory for this chapter. Section 24.5 explains how to use this script.

### Authors Table

The database consists of three tables: `Authors`, `AuthorISBN` and `Titles`. The `Authors` table (described in Fig. 24.3) consists of three columns that maintain each author's unique ID number, first name and last name. Figure 24.4 contains sample data from the `Authors` table.

| Column                 | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |
|------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>AuthorID</code>  | Author's ID number in the database. In the <code>books</code> database, this integer column is defined as <b>autoincremented</b> —for each row inserted in this table, the <code>AuthorID</code> value is increased by 1 automatically to ensure that each row has a unique <code>AuthorID</code> . This column represents the table's primary key. Autoincremented columns are so-called identity columns. The SQL script we provide for this database uses the SQL <b>IDENTITY</b> keyword to mark the <code>AuthorID</code> column as an identity column. For more information on using the <b>IDENTITY</b> keyword and creating databases, see the Java DB Developer's Guide at <a href="http://docs.oracle.com/javadb/10.10.1.1/devguide/derbydev.pdf">http://docs.oracle.com/javadb/10.10.1.1/devguide/derbydev.pdf</a> . |
| <code>FirstName</code> | Author's first name (a string).                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |
| <code>LastName</code>  | Author's last name (a string).                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |

**Fig. 24.3** | `Authors` table from the `books` database.



| AuthorID | FirstName | LastName |
|----------|-----------|----------|
| 1        | Paul      | Deitel   |
| 2        | Harvey    | Deitel   |
| 3        | Abbey     | Deitel   |
| 4        | Dan       | Quirk    |
| 5        | Michael   | Morgano  |

**Fig. 24.4** | Sample data from the Authors table.

### *Titles Table*

The Titles table described in Fig. 24.5 consists of four columns that maintain information about each book in the database, including its ISBN, title, edition number and copyright year. Figure 24.8 contains the data from the Titles table.

| Column        | Description                                                                                                                                                                                                      |
|---------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| ISBN          | ISBN of the book (a string). The table's primary key. ISBN is an abbreviation for "International Standard Book Number"—a numbering scheme that publishers use to give every book a unique identification number. |
| Title         | Title of the book (a string).                                                                                                                                                                                    |
| EditionNumber | Edition number of the book (an integer).                                                                                                                                                                         |
| Copyright     | Copyright year of the book (a string).                                                                                                                                                                           |

**Fig. 24.5** | Titles table from the books database.

| ISBN       | Title                                                     | EditionNumber | Copyright |
|------------|-----------------------------------------------------------|---------------|-----------|
| 0132151006 | Internet & World Wide Web How to Program                  | 5             | 2012      |
| 0133807800 | Java How to Program                                       | 10            | 2015      |
| 0132575655 | Java How to Program, Late Objects Version                 | 10            | 2015      |
| 013299044X | C How to Program                                          | 7             | 2013      |
| 0132990601 | Simply Visual Basic 2010                                  | 4             | 2013      |
| 0133406954 | Visual Basic 2012 How to Program                          | 6             | 2014      |
| 0133379337 | Visual C# 2012 How to Program                             | 5             | 2014      |
| 0136151574 | Visual C++ 2008 How to Program                            | 2             | 2008      |
| 0133378713 | C++ How to Program                                        | 9             | 2014      |
| 0133570924 | Android How to Program                                    | 2             | 2015      |
| 0133570924 | Android for Programmers: An App-Driven Approach, Volume 1 | 2             | 2014      |
| 0132121360 | Android for Programmers: An App-Driven Approach           | 1             | 2012      |

**Fig. 24.6** | Sample data from the Titles table of the books database .

**AuthorISBN Table**

The AuthorISBN table (described in Fig. 24.7) consists of two columns that maintain ISBNs for each book and their corresponding authors' ID numbers. This table associates authors with their books. The AuthorID column is a **foreign key**—a column in this table that matches the primary-key column in another table (that is, AuthorID in the Authors table). The ISBN column is also a foreign key—it matches the primary-key column (that is, ISBN) in the Titles table. A database might consist of many tables. A goal when designing a database is to *minimize* the amount of *duplicated* data among the database's tables. Foreign keys, which are specified when a database table is created in the database, link the data in *multiple* tables. Together the AuthorID and ISBN columns in this table form a *composite primary key*. Every row in this table *uniquely* matches *one* author to *one* book's ISBN. Figure 24.8 contains the data from the AuthorISBN table of the books database.

| Column   | Description                                                 |
|----------|-------------------------------------------------------------|
| AuthorID | The author's ID number, a foreign key to the Authors table. |
| ISBN     | The ISBN for a book, a foreign key to the Titles table.     |

**Fig. 24.7** | AuthorISBN table from the books database.

| AuthorID | ISBN       | AuthorID | ISBN       |
|----------|------------|----------|------------|
| 1        | 0132151006 | 2        | 0133379337 |
| 2        | 0132151006 | 1        | 0136151574 |
| 3        | 0132151006 | 2        | 0136151574 |
| 1        | 0133807800 | 4        | 0136151574 |
| 2        | 0133807800 | 1        | 0133378713 |
| 1        | 0132575655 | 2        | 0133378713 |
| 2        | 0132575655 | 1        | 0133764036 |
| 1        | 013299044X | 2        | 0133764036 |
| 2        | 013299044X | 3        | 0133764036 |
| 1        | 0132990601 | 1        | 0133570924 |
| 2        | 0132990601 | 2        | 0133570924 |
| 3        | 0132990601 | 3        | 0133570924 |
| 1        | 0133406954 | 1        | 0132121360 |
| 2        | 0133406954 | 2        | 0132121360 |
| 3        | 0133406954 | 3        | 0132121360 |
| 1        | 0133379337 | 5        | 0132121360 |

**Fig. 24.8** | Sample data from the AuthorISBN table of books.


Every foreign-key value must appear as another table's primary-key value so the DBMS can ensure that the foreign key value is valid—this is known as the **Rule of Referential Integrity**. For example, the DBMS ensures that the AuthorID value for a particular

row of the AuthorISBN table is valid by checking that there is a row in the Authors table with that AuthorID as the primary key.

Foreign keys also allow *related* data in *multiple* tables to be *selected* from those tables—this is known as **joining** the data. There is a **one-to-many relationship** between a primary key and a corresponding foreign key (for example, one author can write many books and one book can be written by many authors). This means that a foreign key can appear *many* times in its own table but only *once* (as the primary key) in another table. For example, the ISBN 0132151006 can appear in several rows of AuthorISBN (because this book has several authors) but only once in Titles, where ISBN is the primary key.

### Entity-Relationship (ER) Diagram

There's a one-to-many relationship between a primary key and a corresponding foreign key (e.g., one author can write many books). A foreign key can appear many times in its own table, but only once (as the primary key) in another table. Figure 24.9 is an **entity-relationship (ER) diagram** for the books database. This diagram shows the *database tables* and the *relationships* among them. The first compartment in each box contains the table's name and the remaining compartments contain the table's columns. The names in *italic* are primary keys. *A table's primary key uniquely identifies each row in the table.* Every row must have a primary-key value, and that value must be unique in the table. This is known as the **Rule of Entity Integrity**. Again, for the AuthorISBN table, the primary key is the combination of both columns—this is known as a composite primary key.



**Fig. 24.9** | Table relationships in the books database.

The lines connecting the tables in Fig. 24.9 represent the *relationships* among the tables. Consider the line between the Authors and AuthorISBN tables. On the Authors end of the line, there's a 1, and on the AuthorISBN end, an infinity symbol ( $\infty$ ). This indicates a *one-to-many relationship*—for *each* author in the Authors table, there can be an *arbitrary number* of ISBNs for books written by that author in the AuthorISBN table (that is, an author can write *any* number of books). Note that the relationship line links the AuthorID column in the Authors table (where AuthorID is the primary key) to the AuthorID column in the AuthorISBN table (where AuthorID is a foreign key)—the line between the tables links the primary key to the matching foreign key.

The line between the Titles and AuthorISBN tables illustrates a *one-to-many relationship*—one book can be written by many authors. Note that the line between the tables links the primary key ISBN in table Titles to the corresponding foreign key in table AuthorISBN. The relationships in Fig. 24.9 illustrate that the sole purpose of the AuthorISBN table is to provide a **many-to-many relationship** between the Authors and Titles tables—an author can write *many* books, and a book can have *many* authors.

## 24.4 SQL

We now discuss SQL in the context of our books database. You'll be able to use the SQL discussed here in the examples later in the chapter. The next several subsections demonstrate SQL queries and statements using the SQL keywords in Fig. 24.10. Other SQL keywords are beyond this text's scope.

| SQL keyword | Description                                                                                                                     |
|-------------|---------------------------------------------------------------------------------------------------------------------------------|
| SELECT      | Retrieves data from one or more tables.                                                                                         |
| FROM        | Tables involved in the query. Required in every SELECT.                                                                         |
| WHERE       | Criteria for selection that determine the rows to be retrieved, deleted or updated. Optional in a SQL query or a SQL statement. |
| GROUP BY    | Criteria for grouping rows. Optional in a SELECT query.                                                                         |
| ORDER BY    | Criteria for ordering rows. Optional in a SELECT query.                                                                         |
| INNER JOIN  | Merge rows from multiple tables.                                                                                                |
| INSERT      | Insert rows into a specified table.                                                                                             |
| UPDATE      | Update rows in a specified table.                                                                                               |
| DELETE      | Delete rows from a specified table.                                                                                             |

**Fig. 24.10** | SQL query keywords.

### 24.4.1 Basic SELECT Query

Let's consider several SQL queries that extract information from database books. A SQL query "selects" rows and columns from one or more tables in a database. Such selections are performed by queries with the **SELECT** keyword. The basic form of a SELECT query is

```
SELECT * FROM tableName
```

in which the **asterisk (\*) wildcard character** indicates that all columns from the *tableName* table should be retrieved. For example, to retrieve all the data in the Authors table, use

```
SELECT * FROM Authors
```

Most programs do not require all the data in a table. To retrieve only specific columns, replace the \* with a comma-separated list of column names. For example, to retrieve only the columns AuthorID and LastName for all rows in the Authors table, use the query

```
SELECT AuthorID, LastName FROM Authors
```

This query returns the data listed in Fig. 24.11.

| AuthorID | LastName | AuthorID | LastName |
|----------|----------|----------|----------|
| 1        | Deitel   | 4        | Quirk    |
| 2        | Deitel   | 5        | Morgano  |
| 3        | Deitel   |          |          |

**Fig. 24.11** | Sample AuthorID and LastName data from the Authors table.



### Software Engineering Observation 24.2

*In general, you process results by knowing in advance the order of the columns in the result—for example, selecting AuthorID and LastName from table Authors ensures that the columns will appear in the result with AuthorID as the first column and LastName as the second column. Programs typically process result columns by specifying the column number in the result (starting from number 1 for the first column). Selecting columns by name avoids returning unneeded columns and protects against changes in the actual order of the columns in the table(s) by returning the columns in the exact order specified.*



### Common Programming Error 24.1

*If you assume that the columns are always returned in the same order from a query that uses the asterisk (\*), the program may process the results incorrectly. If the column order in the table(s) changes or if additional columns are added at a later time, the order of the columns in the result will change accordingly.*

## 24.4.2 WHERE Clause

In most cases, it's necessary to locate rows in a database that satisfy certain **selection criteria**. Only rows that satisfy the selection criteria (formally called **predicates**) are selected. SQL uses the optional **WHERE clause** in a query to specify the selection criteria for the query. The basic form of a query with selection criteria is

```
SELECT columnName1, columnName2, ... FROM tableName WHERE criteria
```

For example, to select the Title, EditionNumber and Copyright columns from table Titles for which the Copyright date is greater than 2013, use the query

```
SELECT Title, EditionNumber, Copyright
FROM Titles
WHERE Copyright > '2013'
```

Strings in SQL are delimited by single (') rather than double (") quotes. Figure 24.12 shows the result of the preceding query.

| Title                                                     | EditionNumber | Copyright |
|-----------------------------------------------------------|---------------|-----------|
| Java How to Program                                       | 10            | 2015      |
| Java How to Program, Late Objects Version                 | 10            | 2015      |
| Visual Basic 2012 How to Program                          | 6             | 2014      |
| Visual C# 2012 How to Program                             | 5             | 2014      |
| C++ How to Program                                        | 9             | 2014      |
| Android How to Program                                    | 2             | 2015      |
| Android for Programmers: An App-Driven Approach, Volume 1 | 2             | 2014      |

**Fig. 24.12** | Sampling of titles with copyrights after 2005 from table Titles.

### Pattern Matching: Zero or More Characters

The WHERE clause criteria can contain the operators <, >, <=, >=, =, <> and LIKE. Operator **LIKE** is used for **pattern matching** with wildcard characters **percent (%)** and **underscore (\_)**. Pattern matching allows SQL to search for strings that match a given pattern.

A pattern that contains a percent character (%) searches for strings that have zero or more characters at the percent character's position in the pattern. For example, the next query locates the rows of all the authors whose last name starts with the letter D:

```
SELECT AuthorID, FirstName, LastName
FROM Authors
WHERE LastName LIKE 'D%'
```

This query selects the two rows shown in Fig. 24.13—three of the five authors have a last name starting with the letter D (followed by zero or more characters). The % symbol in the WHERE clause's LIKE pattern indicates that any number of characters can appear after the letter D in the LastName. The pattern string is surrounded by single-quote characters.

| AuthorID | FirstName | LastName |
|----------|-----------|----------|
| 1        | Paul      | Deitel   |
| 2        | Harvey    | Deitel   |
| 3        | Abbey     | Deitel   |

**Fig. 24.13** | Authors whose last name starts with D from the Authors table.



#### Portability Tip 24.1

*See the documentation for your database system to determine whether SQL is case sensitive on your system and to determine the syntax for SQL keywords.*



#### Portability Tip 24.2

*Read your database system's documentation carefully to determine whether it supports the LIKE operator as discussed here.*

#### Pattern Matching: Any Character

An underscore (\_) in the pattern string indicates a single wildcard character at that position in the pattern. For example, the following query locates the rows of all the authors whose last names start with any character (specified by \_), followed by the letter o, followed by any number of additional characters (specified by %):

```
SELECT AuthorID, FirstName, LastName
FROM Authors
WHERE LastName LIKE '_o%'
```

The preceding query produces the row shown in Fig. 24.14, because only one author in our database has a last name that contains the letter o as its second letter.

| AuthorID | FirstName | LastName |
|----------|-----------|----------|
| 5        | Michael   | Morgano  |

**Fig. 24.14** | The only author from the Authors table whose last name contains o as the second letter.

### 24.4.3 ORDER BY Clause

The rows in the result of a query can be sorted into ascending or descending order by using the optional **ORDER BY clause**. The basic form of a query with an ORDER BY clause is

```
SELECT columnName1, columnName2, ... FROM tableName ORDER BY column ASC
SELECT columnName1, columnName2, ... FROM tableName ORDER BY column DESC
```

where ASC specifies ascending order (lowest to highest), DESC specifies descending order (highest to lowest) and *column* specifies the column on which the sort is based. For example, to obtain the list of authors in ascending order by last name (Fig. 24.15), use the query

```
SELECT AuthorID, FirstName, LastName
FROM Authors
ORDER BY LastName ASC
```

| AuthorID | FirstName | LastName |
|----------|-----------|----------|
| 1        | Paul      | Deitel   |
| 2        | Harvey    | Deitel   |
| 3        | Abbey     | Deitel   |
| 5        | Michael   | Morgano  |
| 4        | Dan       | Quirk    |

**Fig. 24.15** | Sample data from table Authors in ascending order by LastName.

#### *Sorting in Descending Order*

The default sorting order is ascending, so ASC is optional. To obtain the same list of authors in descending order by last name (Fig. 24.16), use the query

```
SELECT AuthorID, FirstName, LastName
FROM Authors
ORDER BY LastName DESC
```

| AuthorID | FirstName | LastName |
|----------|-----------|----------|
| 4        | Dan       | Quirk    |
| 5        | Michael   | Morgano  |
| 1        | Paul      | Deitel   |
| 2        | Harvey    | Deitel   |
| 3        | Abbey     | Deitel   |

**Fig. 24.16** | Sample data from table Authors in descending order by LastName.

#### *Sorting By Multiple Columns*

Multiple columns can be used for sorting with an ORDER BY clause of the form

```
ORDER BY column1 sortingOrder, column2 sortingOrder, ...
```

where *sortingOrder* is either ASC or DESC. The *sortingOrder* does not have to be identical for each column. The query

```
SELECT AuthorID, FirstName, LastName
FROM Authors
ORDER BY LastName, FirstName
```

sorts all the rows in ascending order by last name, then by first name. If any rows have the same last-name value, they're returned sorted by first name (Fig. 24.17).

| AuthorID | FirstName | LastName |
|----------|-----------|----------|
| 3        | Abbey     | Deitel   |
| 2        | Harvey    | Deitel   |
| 1        | Paul      | Deitel   |
| 5        | Michael   | Morgano  |
| 4        | Dan       | Quirk    |

**Fig. 24.17** | Sample data from Authors in ascending order by LastName and FirstName.

### *Combining the WHERE and ORDER BY Clauses*

The WHERE and ORDER BY clauses can be combined in one query, as in

```
SELECT ISBN, Title, EditionNumber, Copyright
FROM Titles
WHERE Title LIKE '%How to Program'
ORDER BY Title ASC
```

which returns the ISBN, Title, EditionNumber and Copyright of each book in the Titles table that has a Title ending with "How to Program" and sorts them in ascending order by Title. The query results are shown in Fig. 24.18.

| ISBN       | Title                                    | EditionNumber | Copyright |
|------------|------------------------------------------|---------------|-----------|
| 0133764036 | Android How to Program                   | 2             | 2015      |
| 013299044X | C How to Program                         | 7             | 2013      |
| 0133378713 | C++ How to Program                       | 9             | 2014      |
| 0132151006 | Internet & World Wide Web How to Program | 5             | 2012      |
| 0133807800 | Java How to Program                      | 10            | 2015      |
| 0133406954 | Visual Basic 2012 How to Program         | 6             | 2014      |
| 0133379337 | Visual C# 2012 How to Program            | 5             | 2014      |
| 0136151574 | Visual C++ 2008 How to Program           | 2             | 2008      |

**Fig. 24.18** | Sampling of books from table Titles whose titles end with How to Program in ascending order by Title.

## 24.4.4 Merging Data from Multiple Tables: INNER JOIN

Database designers often split related data into separate tables to ensure that a database does not store data redundantly. For example, in the books database, we use an AuthorISBN table to store the relationship data between authors and their corresponding titles. If we did not separate this information into individual tables, we'd need to include author information with each entry in the Titles table. This would result in the database's storing *duplicate* au-



thor information for authors who wrote multiple books. Often, it's necessary to merge data from multiple tables into a single result. Referred to as joining the tables, this is specified by an **INNER JOIN** operator, which merges rows from two tables by matching values in columns that are common to the tables. The basic form of an **INNER JOIN** is:

```
SELECT columnName1, columnName2, ...
FROM table1
INNER JOIN table2
 ON table1.columnName = table2.columnName
```

The **ON** clause of the **INNER JOIN** specifies the columns from each table that are compared to determine which rows are merged—these fields almost always correspond to the foreign-key fields in the tables being joined. For example, the following query produces a list of authors accompanied by the ISBNs for books written by each author:

```
SELECT FirstName, LastName, ISBN
FROM Authors
INNER JOIN AuthorISBN
 ON Authors.AuthorID = AuthorISBN.AuthorID
ORDER BY LastName, FirstName
```

The query merges the `FirstName` and `LastName` columns from table `Authors` with the `ISBN` column from table `AuthorISBN`, sorting the results in ascending order by `LastName` and `FirstName`. Note the use of the syntax `tableName.columnName` in the **ON** clause. This syntax, called a **qualified name**, specifies the columns from each table that should be compared to join the tables. The “`tableName.`” syntax is required if the columns have the same name in both tables. The same syntax can be used in any SQL statement to distinguish columns in different tables that have the same name. In some systems, table names qualified with the database name can be used to perform cross-database queries. As always, the query can contain an **ORDER BY** clause. Figure 24.19 shows the results of the preceding query, ordered by `LastName` and `FirstName`. [Note: To save space, we split the result of the query into two columns, each containing the `FirstName`, `LastName` and `ISBN` columns.]



### Common Programming Error 24.2

*Failure to qualify names for columns that have the same name in two or more tables is an error. In such cases, the statement must precede those column names with their table names and a dot (e.g., `Authors.AuthorID`).*

| FirstName | LastName | ISBN       | FirstName | LastName | ISBN       |
|-----------|----------|------------|-----------|----------|------------|
| Abbey     | Deitel   | 0132121360 | Harvey    | Deitel   | 0133764036 |
| Abbey     | Deitel   | 0133570924 | Harvey    | Deitel   | 0133378713 |
| Abbey     | Deitel   | 0133764036 | Harvey    | Deitel   | 0136151574 |
| Abbey     | Deitel   | 0133406954 | Harvey    | Deitel   | 0133379337 |
| Abbey     | Deitel   | 0132990601 | Harvey    | Deitel   | 0133406954 |
| Abbey     | Deitel   | 0132151006 | Harvey    | Deitel   | 0132990601 |
| Harvey    | Deitel   | 0132121360 | Harvey    | Deitel   | 013299044X |
| Harvey    | Deitel   | 0133570924 | Harvey    | Deitel   | 0132575655 |

**Fig. 24.19** | Sampling of authors and ISBNs for the books they have written in ascending order by `LastName` and `FirstName`. (Part I of 2.)

| FirstName | LastName | ISBN       | FirstName | LastName | ISBN       |
|-----------|----------|------------|-----------|----------|------------|
| Harvey    | Deitel   | 0133807800 | Paul      | Deitel   | 0133406954 |
| Harvey    | Deitel   | 0132151006 | Paul      | Deitel   | 0132990601 |
| Paul      | Deitel   | 0132121360 | Paul      | Deitel   | 013299044X |
| Paul      | Deitel   | 0133570924 | Paul      | Deitel   | 0132575655 |
| Paul      | Deitel   | 0133764036 | Paul      | Deitel   | 0133807800 |
| Paul      | Deitel   | 0133378713 | Paul      | Deitel   | 0132151006 |
| Paul      | Deitel   | 0136151574 | Michael   | Morgano  | 0132121360 |
| Paul      | Deitel   | 0133379337 | Dan       | Quirk    | 0136151574 |

**Fig. 24.19** | Sampling of authors and ISBNs for the books they have written in ascending order by LastName and FirstName. (Part 2 of 2.)

### 24.4.5 INSERT Statement

The **INSERT** statement inserts a row into a table. The basic form of this statement is

```
INSERT INTO tableName (columnName1, columnName2, ..., columnNameN)
VALUES (value1, value2, ..., valueN)
```

where *tableName* is the table in which to insert the row. The *tableName* is followed by a comma-separated list of column names in parentheses (this list is not required if the **INSERT** operation specifies a value for every column of the table in the correct order). The list of column names is followed by the SQL keyword **VALUES** and a comma-separated list of values in parentheses. The values specified here must match the columns specified after the table name in both order and type (e.g., if *columnName1* is supposed to be the **FirstName** column, then *value1* should be a string in single quotes representing the first name). Always explicitly list the columns when inserting rows. If the table's column order changes or a new column is added, using only **VALUES** may cause an error. The **INSERT** statement

```
INSERT INTO Authors (FirstName, LastName)
VALUES ('Sue', 'Red')
```

inserts a row into the **Authors** table. The statement indicates that values are provided for the **FirstName** and **LastName** columns. The corresponding values are 'Sue' and 'Smith'. We do not specify an **AuthorID** in this example because **AuthorID** is an autoincremented column in the **Authors** table. For every row added to this table, the DBMS assigns a unique **AuthorID** value that is the next value in the autoincremented sequence (i.e., 1, 2, 3 and so on). In this case, Sue Red would be assigned **AuthorID** number 6. Figure 24.20 shows the **Authors** table after the **INSERT** operation. [Note: Not every database management system supports autoincremented columns. Check the documentation for your DBMS for alternatives to autoincremented columns.]



#### Common Programming Error 24.3

SQL delimits strings with single quotes ('). A string containing a single quote (e.g., O'Malley) must have two single quotes in the position where the single quote appears (e.g., 'O'Malley'). The first acts as an escape character for the second. Not escaping single-quote characters in a string that's part of a SQL statement is a SQL syntax error.



### Common Programming Error 24.4

*It's normally an error to specify a value for an autoincrement column.*

| AuthorID | FirstName | LastName |
|----------|-----------|----------|
| 1        | Paul      | Deitel   |
| 2        | Harvey    | Deitel   |
| 3        | Abbey     | Deitel   |
| 4        | Dan       | Quirk    |
| 5        | Michael   | Morgano  |
| 6        | Sue       | Red      |

**Fig. 24.20** | Sample data from table Authors after an INSERT operation.

### 24.4.6 UPDATE Statement

An **UPDATE** statement modifies data in a table. Its basic form is

```
UPDATE tableName
SET columnName1 = value1, columnName2 = value2, ..., columnNameN = valueN
WHERE criteria
```

where *tableName* is the table to update. The *tableName* is followed by keyword **SET** and a comma-separated list of *columnName* = *value* pairs. The optional **WHERE** clause provides criteria that determine which rows to update. Though not required, the **WHERE** clause is typically used, unless a change is to be made to every row. The **UPDATE** statement

```
UPDATE Authors
SET LastName = 'Black'
WHERE LastName = 'Red' AND FirstName = 'Sue'
```

updates a row in the Authors table. The statement indicates that **LastName** will be assigned the value **Black** for the row where **LastName** is **Red** and **FirstName** is **Sue**. [Note: If there are multiple matching rows, this statement will modify *all* such rows to have the last name “Black.”] If we know the **AuthorID** in advance of the **UPDATE** operation (possibly because we searched for it previously), the **WHERE** clause can be simplified as follows:

```
WHERE AuthorID = 6
```

Figure 24.21 shows the Authors table after the **UPDATE** operation has taken place.

| AuthorID | FirstName | LastName |
|----------|-----------|----------|
| 1        | Paul      | Deitel   |
| 2        | Harvey    | Deitel   |
| 3        | Abbey     | Deitel   |
| 4        | Dan       | Quirk    |
| 5        | Michael   | Morgano  |
| 6        | Sue       | Black    |

**Fig. 24.21** | Sample data from table Authors after an UPDATE operation.

### 24.4.7 DELETE Statement

A SQL **DELETE** statement removes rows from a table. Its basic form is

```
DELETE FROM tableName WHERE criteria
```

where *tableName* is the table from which to delete. The optional **WHERE** clause specifies the criteria used to determine which rows to delete. If this clause is omitted, all the table's rows are deleted. The **DELETE** statement

```
DELETE FROM Authors
WHERE LastName = 'Black' AND FirstName = 'Sue'
```

deletes the row for Sue Black in the Authors table. If we know the **AuthorID** in advance of the **DELETE** operation, the **WHERE** clause can be simplified as follows:

```
WHERE AuthorID = 5
```

Figure 24.22 shows the Authors table after the **DELETE** operation has taken place.

| AuthorID | FirstName | LastName |
|----------|-----------|----------|
| 1        | Paul      | Deitel   |
| 2        | Harvey    | Deitel   |
| 3        | Abbey     | Deitel   |
| 4        | Dan       | Quirk    |
| 5        | Michael   | Morgano  |

**Fig. 24.22** | Sample data from table Authors after a **DELETE** operation.

## 24.5 Setting up a Java DB Database

This chapter's examples use Oracle's pure Java database **Java DB**, which is installed with Oracle's JDK on Windows, Mac OS X and Linux. Before you can execute this chapter's applications, you must set up in Java DB the books database that's used in Sections 24.6–24.7 and the addressbook database that's used in Section 24.8.

For this chapter, you'll be using the embedded version of Java DB. This means that the database you manipulate in each example must be located in that example's folder. This chapter's examples are located in two subfolders of the ch24 examples folder—**books\_examples** and **addressbook\_example**. Java DB may also act as a server that can receive database requests over a network, but that is beyond this chapter's scope.

### *JDK Installation Folders*

The Java DB software is located in the **db** subdirectory of your JDK's installation directory. The directories listed below are for Oracle's JDK 7 update 51:

- 32-bit JDK on Windows:  
C:\Program Files (x86)\Java\jdk1.7.0\_51
- 64-bit JDK on Windows:  
C:\Program Files\Java\jdk1.7.0\_51

- Mac OS X:  
/Library/Java/JavaVirtualMachines/jdk1.7.0\_51.jdk/Contents/Home
- Ubuntu Linux:  
/usr/lib/jvm/java-7-oracle

For Linux, the install location depends on the installer you use and possibly the version of Linux that you use. We used Ubuntu Linux for testing purposes.

Depending on your platform, the JDK installation folder's name might differ if you're using a different update of JDK 7 or using JDK 8. In the following instructions, you should update the JDK installation folder's name based on the JDK version you're using.

### *Java DB Configuration*

Java DB comes with several files that enable you to configure and run it. Before executing these files from a command window, you must set the environment variable `JAVA_HOME` to refer to the JDK's exact installation directory listed above (or the location where you installed the JDK if it differs from those listed above). See the Before You Begin section of this book for information on setting environment variables.

#### 24.5.1 Creating the Chapter's Databases on Windows

After setting the `JAVA_HOME` environment variable, perform the following steps:

1. Run Notepad as an administrator. To do this on Windows 7, select **Start > All Programs > Accessories**, right click Notepad and select **Run as administrator**. On Windows 8, search for Notepad, right click it in the search results and select **Advanced** in the app bar, then select **Run as administrator**.
2. From Notepad, open the batch file `setEmbeddedCP.bat` that is located in the JDK installation folder's `db\bin` folder.
3. Locate the line

```
@rem set DERBY_INSTALL=
```

and change it to

```
@set DERBY_INSTALL=%JAVA_HOME%\db
```

Save your changes and close this file.

4. Open a Command Prompt window and change directories to the JDK installation folder's `db\bin` folder. Then, type `setEmbeddedCP.bat` and press *Enter* to set the environment variables required by Java DB.
5. Use the `cd` command to change to this chapter's `books_examples` directory. This directory contains a SQL script `books.sql` that builds the books database.
6. Execute the following command (with the quotation marks):

```
"%JAVA_HOME%\db\bin\ij"
```

to start the command-line tool for interacting with Java DB. The double quotes are necessary because the path that the environment variable `%JAVA_HOME%` represents contains a space. This will display the `ij>` prompt.

- At the `ij>` prompt type

```
connect 'jdbc:derby:books;create=true;user=deitel';
password=deitel';
```

and press *Enter* to create the books database in the current directory and to create the user `deitel` with the password `deitel` for accessing the database.

- To create the database table and insert sample data in it, we've provided the file `address.sql` in this example's directory. To execute this SQL script, type

```
run 'books.sql';
```

Once you create the database, you can execute the SQL statements presented in Section 24.4 to confirm their execution. Each command you enter at the `ij>` prompt must be terminated with a semicolon (;).

- To terminate the Java DB command-line tool, type

```
exit;
```

- Change directories to the `addressbook_example` subfolder of the `ch24` examples folder, which contains the SQL script `addressbook.sql` that builds the `addressbook` database. Repeat Steps 6–9. In each step, replace `books` with `addressbook`.

You're now ready to execute this chapter's examples.

## 24.5.2 Creating the Chapter's Databases on Mac OS X

After setting the `JAVA_HOME` environment variable, perform the following steps:

- Open a Terminal, then type:

```
DERBY_HOME=/Library/Java/JavaVirtualMachines/jdk1.7.0_51.jdk/
Contents/Home/db
```

and press *Enter*. Then type

```
export DERBY_HOME
```

and press *Enter*. This specifies where Java DB is located on your Mac.

- In the Terminal window, change directories to the JDK installation folder's `db/bin` folder. Then, type `./setEmbeddedCP` and press *Enter* to set the environment variables required by Java DB.
- In the Terminal window, use the `cd` command to change to the `books_examples` directory. This directory contains a SQL script `books.sql` that builds the books database.
- Execute the following command (with the quotation marks):

```
$JAVA_HOME/db/bin/ij
```

to start the command-line tool for interacting with Java DB. This will display the `ij>` prompt.

- Perform Steps 7–9 of Section 24.5.1 to create the books database.
- Use the `cd` command to change to the `addressbook_example` directory. This directory contains a SQL script `addressbook.sql` that builds the `addressbook` database.

7. Perform Steps 7–9 of Section 24.5.1 to create the addressbook database. In each step, replace books with addressbook.

You're now ready to execute this chapter's examples.

### 24.5.3 Creating the Chapter's Databases on Linux

After setting the JAVA\_HOME environment variable, perform the following steps:

1. Open a shell window.
2. Perform the steps in Section 24.5.2, but in Step 1, set DERBY\_HOME to

```
DERBY_HOME=YourLinuxJDKInstallationFolder/db
```

On our Ubuntu Linux system, this was:

```
DERBY_HOME=/usr/lib/jvm/java-7-oracle/db
```

You're now ready to execute this chapter's examples.

## 24.6 Manipulating Databases with JDBC

This section presents two examples. The first introduces how to connect to a database and query it. The second demonstrates how to display the result of the query in a JTable.

### 24.6.1 Connecting to and Querying a Database

The example of Fig. 24.23 performs a simple query on the books database that retrieves the entire Authors table and displays the data. The program illustrates connecting to the database, querying the database and processing the result. The discussion that follows presents the key JDBC aspects of the program.

Lines 3–8 import the JDBC interfaces and classes from package java.sql used in this program. Method main (lines 12–48) connects to the books database, queries the database, displays the query result and closes the database connection. Line 14 declares a String constant for the database URL. This identifies the name of the database to connect to, as well as information about the protocol used by the JDBC driver (discussed shortly). Lines 15–16 declare a String constant representing the SQL query that will select the authorID, firstName and lastName columns in the database's authors table.

---

```

1 // Fig. 24.23: DisplayAuthors.java
2 // Displaying the contents of the Authors table.
3 import java.sql.Connection;
4 import java.sql.Statement;
5 import java.sql.DriverManager;
6 import java.sql.ResultSet;
7 import java.sql.ResultSetMetaData;
8 import java.sql.SQLException;
9
10 public class DisplayAuthors
11 {
```

---

**Fig. 24.23** | Displaying the contents of the Authors table. (Part 1 of 2.)

```

12 public static void main(String args[])
13 {
14 final String DATABASE_URL = "jdbc:derby:books";
15 final String SELECT_QUERY =
16 "SELECT authorID, firstName, lastName FROM authors";
17
18 // use try-with-resources to connect to and query the database
19 try (
20 Connection connection = DriverManager.getConnection(
21 DATABASE_URL, "deitel", "deitel");
22 Statement statement = connection.createStatement();
23 ResultSet resultSet = statement.executeQuery(SELECT_QUERY))
24 {
25 // get ResultSet's meta data
26 ResultSetMetaData metaData = resultSet.getMetaData();
27 int numberOfColumns = metaData.getColumnCount();
28
29 System.out.printf("Authors Table of Books Database:%n%n");
30
31 // display the names of the columns in the ResultSet
32 for (int i = 1; i <= numberOfColumns; i++)
33 System.out.printf("%-8s\t", metaData.getColumnName(i));
34 System.out.println();
35
36 // display query results
37 while (resultSet.next())
38 {
39 for (int i = 1; i <= numberOfColumns; i++)
40 System.out.printf("%-8s\t", resultSet.getObject(i));
41 System.out.println();
42 }
43 // AutoCloseable objects' close methods are called now
44 } catch (SQLException sqlException)
45 {
46 sqlException.printStackTrace();
47 }
48 }
49 } // end class DisplayAuthors

```

Authors Table of Books Database:

| AUTHORID | FIRSTNAME | LASTNAME |
|----------|-----------|----------|
| 1        | Paul      | Deitel   |
| 2        | Harvey    | Deitel   |
| 3        | Abbey     | Deitel   |
| 4        | Dan       | Quirk    |
| 5        | Michael   | Morgano  |

**Fig. 24.23** | Displaying the contents of the Authors table. (Part 2 of 2.)

JDBC supports **automatic driver discovery**—it loads the database driver into memory for you. To ensure that the program can locate the driver class, you must include the class's location in the program's classpath when you execute the program. You did this for Java DB in Section 24.5 when you executed the `setEmbeddedCP.bat` or `setEmbeddedCP` file on your



system—that step configured a CLASSPATH environment variable in the command window for your platform. After doing so, you can run this application simply using the command

```
java DisplayAuthors
```

### Connecting to the Database

The JDBC interfaces we use in this example each extend the `AutoCloseable` interface, so you can use objects that implement these interfaces with the `try-with-resources` statement (introduced in Section 11.12). Lines 19–23 create this example’s `AutoCloseable` objects in the parentheses following keyword `try`—such objects are automatically closed when the `try` block terminates (line 43) or if an exception occurs during the `try` block’s execution. Each object created in the parentheses following keyword `try` must be separated from the next by a semicolon (;).

Lines 20–21 create a **Connection** object (package `java.sql`) referenced by `connection`. An object that implements interface `Connection` manages the connection between the Java program and the database. `Connection` objects enable programs to create SQL statements that manipulate databases. The program initializes `connection` with the result of a call to static method **getConnection** of class **DriverManager** (package `java.sql`), which attempts to connect to the database specified by its URL.

Method `getConnection` takes three arguments

- a `String` that specifies the database URL,
- a `String` that specifies the username and
- a `String` that specifies the password.

The username and password for the `books` database were set in Section 24.5. If you used a different username and password there, you’ll need to replace the username (second argument) and password (third argument) passed to method `getConnection` in line 21.

The URL locates the database (possibly on a network or in the local file system of the computer). The URL `jdbc:derby:books` specifies the protocol for communication (`jdbc`), the **subprotocol** for communication (`derby`) and the location of the database (`books`). The subprotocol `derby` indicates that the program uses a Java DB/Apache Derby-specific subprotocol to connect to the database—recall that Java DB is simply the Oracle branded version of Apache Derby. If the `DriverManager` cannot connect to the database, method `getConnection` throws a **SQLException** (package `java.sql`). Figure 24.24 lists the JDBC driver names and database URL formats of several popular RDBMSs.

| RDBMS                | Database URL format                                                                                                     |
|----------------------|-------------------------------------------------------------------------------------------------------------------------|
| MySQL                | <code>jdbc:mysql://hostname:portNumber/databaseName</code>                                                              |
| ORACLE               | <code>jdbc:oracle:thin:@hostname:portNumber:databaseName</code>                                                         |
| DB2                  | <code>jdbc:db2:hostname:portNumber/databaseName</code>                                                                  |
| PostgreSQL           | <code>jdbc:postgresql://hostname:portNumber/databaseName</code>                                                         |
| Java DB/Apache Derby | <code>jdbc:derby:databaseName (embedded)</code><br><code>jdbc:derby://hostname:portNumber/databaseName (network)</code> |

**Fig. 24.24** | Popular JDBC database URL formats. (Part 1 of 2.)

| RDBMS                | Database URL format                                                         |
|----------------------|-----------------------------------------------------------------------------|
| Microsoft SQL Server | <code>jdbc:sqlserver://hostname:portNumber;databaseName=DataBaseName</code> |
| Sybase               | <code>jdbc:sybase:Tds:hostname:portNumber/databaseName</code>               |

**Fig. 24.24** | Popular JDBC database URL formats. (Part 2 of 2.)**Software Engineering Observation 24.3**

*Most database management systems require the user to log in before accessing the database contents. DriverManager method `getConnection` is overloaded with versions that enable the program to supply the username and password to gain access.*

**Creating a Statement for Executing Queries**

Line 22 of Fig. 24.23 invokes Connection method `createStatement` to obtain an object that implements interface `Statement` (package `java.sql`). The program uses the **Statement** object to submit SQL statements to the database.

**Executing a Query**

Line 23 use the Statement object's `executeQuery` method to submit a query that selects all the author information from table `Authors`. This method returns an object that implements interface **ResultSet** and contains the query results. The `ResultSet` methods enable the program to manipulate the query result.

**Processing a Query's ResultSet**

Lines 26–42 process the `ResultSet`. Line 26 obtains the `ResultSet`'s **ResultSetMetaData** (package `java.sql`) object. The **metadata** describes the `ResultSet`'s contents. Programs can use metadata programmatically to obtain information about the `ResultSet`'s column names and types. Line 27 uses `ResultSetMetaData` method `getColumnCount` to retrieve the number of columns in the `ResultSet`. Lines 32–33 display the column names.

**Software Engineering Observation 24.4**

*Metadata enables programs to process `ResultSet` contents dynamically when detailed information about the `ResultSet` is not known in advance.*

Lines 37–42 display the data in each `ResultSet` row. First, the program positions the `ResultSet` cursor (which points to the row being processed) to the first row in the `ResultSet` with method `next` (line 37). Method `next` returns `boolean` value `true` if it's able to position to the next row; otherwise, the method returns `false`.

**Common Programming Error 24.5**

*Initially, a `ResultSet` cursor is positioned before the first row. A `SQLException` occurs if you attempt to access a `ResultSet`'s contents before positioning the `ResultSet` cursor to the first row with method `next`.*

If there are rows in the `ResultSet`, lines 39–40 extract and display the contents of each column in the current row. When a `ResultSet` is processed, each column can be extracted as a specific Java type—`ResultSetMetaData` method `getColumnType` returns a

constant integer from class **Types** (package `java.sql`) indicating the type of a specified column. Programs can use these values in a switch statement to invoke `ResultSet` methods that return the column values as appropriate Java types. For example, if the type of a column is `Types.INTEGER`, `ResultSet` method **getInt** can be used to get the column value as an `int`. For simplicity, this example treats each value as an `Object`. We retrieve each column value with `ResultSet` method **getObject** (line 40), then print the `Object`'s `String` representation. `ResultSet` *get* methods typically receive as an argument either a column number (as an `int`) or a column name (as a `String`) indicating which column's value to obtain. Unlike array indices, `ResultSet` *column numbers start at 1*.



#### Performance Tip 24.1

*If a query specifies the exact columns to select from the database, the `ResultSet` contains the columns in the specified order. In this case, using the column number to obtain the column's value is more efficient than using the column name. The column number provides direct access to the specified column. Using the column name requires a search of the column names to locate the appropriate column.*



#### Error-Prevention Tip 24.1

*Using column names to obtain values from a `ResultSet` produces code that is less error prone than obtaining values by column number—you don't need to remember the column order. Also, if the column order changes, your code does not have to change.*



#### Common Programming Error 24.6

*Specifying column index 0 when obtaining values from a `ResultSet` causes a `SQLException`—the first column index in a `ResultSet` is always 1.*

When the end of the try block is reached (line 43), the close method is called on the `ResultSet`, `Statement` and `Connection` that were obtained by the try-with-resources statement.



#### Common Programming Error 24.7

*A `SQLException` occurs if you attempt to manipulate a `ResultSet` after closing the `Statement` that created it. The `ResultSet` is discarded when the `Statement` is closed.*



#### Software Engineering Observation 24.5

*Each `Statement` object can open only one `ResultSet` object at a time. When a `Statement` returns a new `ResultSet`, the `Statement` closes the prior `ResultSet`. To use multiple `ResultSet`s in parallel, separate `Statement` objects must return the `ResultSet`s.*

### 24.6.2 Querying the books Database

The next example (Figs. 24.25 and 24.28) allows the user to enter any query into the program. The example displays the result of a query in a `JTable`, using a `TableModel` object to provide the `ResultSet` data to the `JTable`. A `JTable` is a swing GUI component that can be bound to a database to display the results of a query. Class `ResultSetTableModel` (Fig. 24.25) performs the connection to the database via a `TableModel` and maintains the `ResultSet`. Class `DisplayQueryResults` (Fig. 24.28) creates the GUI and specifies an instance of class `ResultSetTableModel` to provide data for the `JTable`.

**ResultSetTableModel Class**

Class `ResultSetTableModel` (Fig. 24.25) extends class `AbstractTableModel` (package `javax.swing.table`), which implements interface `TableModel`. `ResultSetTableModel` overrides `TableModel` methods `getColumnClass`, `getColumnCount`, `getColumnName`, `getRowCount` and `getValueAt`. The default implementations of `TableModel` methods `isCellEditable` and `setValueAt` (provided by `AbstractTableModel`) are not overridden, because this example does not support editing the `JTable` cells. The default implementations of `TableModel` methods `addTableModelListener` and `removeTableModelListener` (provided by `AbstractTableModel`) are not overridden, because the implementations of these methods in `AbstractTableModel` properly add and remove event listeners.

---

```

1 // Fig. 24.25: ResultSetTableModel.java
2 // A TableModel that supplies ResultSet data to a JTable.
3 import java.sql.Connection;
4 import java.sql.Statement;
5 import java.sql.DriverManager;
6 import java.sql.ResultSet;
7 import java.sql.ResultSetMetaData;
8 import java.sql.SQLException;
9 import javax.swing.table.AbstractTableModel;
10
11 // ResultSet rows and columns are counted from 1 and JTable
12 // rows and columns are counted from 0. When processing
13 // ResultSet rows or columns for use in a JTable, it is
14 // necessary to add 1 to the row or column number to manipulate
15 // the appropriate ResultSet column (i.e., JTable column 0 is
16 // ResultSet column 1 and JTable row 0 is ResultSet row 1).
17 public class ResultSetTableModel extends AbstractTableModel
18 {
19 private final Connection connection;
20 private final Statement statement;
21 private ResultSet resultSet;
22 private ResultSetMetaData metaData;
23 private int numberOfRows;
24
25 // keep track of database connection status
26 private boolean connectedToDatabase = false;
27
28 // constructor initializes resultSet and obtains its metadata object;
29 // determines number of rows
30 public ResultSetTableModel(String url, String username,
31 String password, String query) throws SQLException
32 {
33 // connect to database
34 connection = DriverManager.getConnection(url, username, password);
35
36 // create Statement to query database
37 statement = connection.createStatement(
38 ResultSet.TYPE_SCROLL_INSENSITIVE,
39 ResultSet.CONCUR_READ_ONLY);

```

---

**Fig. 24.25** | A `TableModel` that supplies `ResultSet` data to a `JTable`. (Part I of 4.)

---

```

40
41 // update database connection status
42 connectedToDatabase = true;
43
44 // set query and execute it
45 setQuery(query);
46 }
47
48 // get class that represents column type
49 public Class getColumnClass(int column) throws IllegalStateException
50 {
51 // ensure database connection is available
52 if (!connectedToDatabase)
53 throw new IllegalStateException("Not Connected to Database");
54
55 // determine Java class of column
56 try
57 {
58 String className = metaData.getColumnClassName(column + 1);
59
60 // return Class object that represents className
61 return Class.forName(className);
62 }
63 catch (Exception exception)
64 {
65 exception.printStackTrace();
66 }
67
68 return Object.class; // if problems occur above, assume type Object
69 }
70
71 // get number of columns in ResultSet
72 public int getColumnCount() throws IllegalStateException
73 {
74 // ensure database connection is available
75 if (!connectedToDatabase)
76 throw new IllegalStateException("Not Connected to Database");
77
78 // determine number of columns
79 try
80 {
81 return metaData.getColumnCount();
82 }
83 catch (SQLException sqlException)
84 {
85 sqlException.printStackTrace();
86 }
87
88 return 0; // if problems occur above, return 0 for number of columns
89 }
90

```

---

**Fig. 24.25** | A `TableModel` that supplies `ResultSet` data to a `JTable`. (Part 2 of 4.)

---

```

91 // get name of a particular column in ResultSet
92 public String getColumnName(int column) throws IllegalStateException
93 {
94 // ensure database connection is available
95 if (!connectedToDatabase)
96 throw new IllegalStateException("Not Connected to Database");
97
98 // determine column name
99 try
100 {
101 return metaData.getColumnName(column + 1);
102 }
103 catch (SQLException sqlException)
104 {
105 sqlException.printStackTrace();
106 }
107
108 return ""; // if problems, return empty string for column name
109 }
110
111 // return number of rows in ResultSet
112 public int getRowCount() throws IllegalStateException
113 {
114 // ensure database connection is available
115 if (!connectedToDatabase)
116 throw new IllegalStateException("Not Connected to Database");
117
118 return numberOfRows;
119 }
120
121 // obtain value in particular row and column
122 public Object getValueAt(int row, int column)
123 throws IllegalStateException
124 {
125 // ensure database connection is available
126 if (!connectedToDatabase)
127 throw new IllegalStateException("Not Connected to Database");
128
129 // obtain a value at specified ResultSet row and column
130 try
131 {
132 resultSet.absolute(row + 1);
133 return resultSet.getObject(column + 1);
134 }
135 catch (SQLException sqlException)
136 {
137 sqlException.printStackTrace();
138 }
139
140 return ""; // if problems, return empty string object
141 }

```

---

**Fig. 24.25** | A `TableModel` that supplies `ResultSet` data to a `JTable`. (Part 3 of 4.)

```

142
143 // set new database query string
144 public void setQuery(String query)
145 throws SQLException, IllegalStateException
146 {
147 // ensure database connection is available
148 if (!connectedToDatabase)
149 throw new IllegalStateException("Not Connected to Database");
150
151 // specify query and execute it
152 resultSet = statement.executeQuery(query);
153
154 // obtain metadata for ResultSet
155 metaData = resultSet.getMetaData();
156
157 // determine number of rows in ResultSet
158 resultSet.last(); // move to last row
159 numberOfRows = resultSet.getRow(); // get row number
160
161 // notify JTable that model has changed
162 fireTableStructureChanged();
163 }
164
165 // close Statement and Connection
166 public void disconnectFromDatabase()
167 {
168 if (connectedToDatabase)
169 {
170 // close Statement and Connection
171 try
172 {
173 resultSet.close();
174 statement.close();
175 connection.close();
176 }
177 catch (SQLException sqlException)
178 {
179 sqlException.printStackTrace();
180 }
181 finally // update database connection status
182 {
183 connectedToDatabase = false;
184 }
185 }
186 }
187 } // end class ResultSetTableModel

```

**Fig. 24.25** | A `TableModel` that supplies `ResultSet` data to a `JTable`. (Part 4 of 4.)

#### *ResultSetTableModel Constructor*

The `ResultSetTableModel` constructor (lines 30–46) accepts four `String` arguments—the URL of the database, the username, the password and the default query to perform. The constructor throws any exceptions that occur in its body back to the application that created the `ResultSetTableModel` object, so that the application can determine how to

handle the exception (e.g., report an error and terminate the application). Line 34 establishes a connection to the database. Lines 37–39 invoke `Connection` method `createStatement` to create a `Statement` object. This example uses a version of method `createStatement` that takes two arguments—the result set type and the result set concurrency. The **result set type** (Fig. 24.26) specifies whether the `ResultSet`’s cursor is able to scroll in both directions or forward only and whether the `ResultSet` is sensitive to changes made to the underlying data.

| ResultSet constant                   | Description                                                                                                                                                                                                                                                               |
|--------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>TYPE_FORWARD_ONLY</code>       | Specifies that a <code>ResultSet</code> ’s cursor can move only in the forward direction (i.e., from the first to the last row in the <code>ResultSet</code> ).                                                                                                           |
| <code>TYPE_SCROLL_INSENSITIVE</code> | Specifies that a <code>ResultSet</code> ’s cursor can scroll in either direction and that the changes made to the underlying data during <code>ResultSet</code> processing are not reflected in the <code>ResultSet</code> unless the program queries the database again. |
| <code>TYPE_SCROLL_SENSITIVE</code>   | Specifies that a <code>ResultSet</code> ’s cursor can scroll in either direction and that the changes made to the underlying data during <code>ResultSet</code> processing are reflected immediately in the <code>ResultSet</code> .                                      |

**Fig. 24.26** | `ResultSet` constants for specifying `ResultSet` type.



### Portability Tip 24.3

*Some JDBC drivers do not support scrollable `ResultSet`s. In such cases, the driver typically returns a `ResultSet` in which the cursor can move only forward. For more information, see your database driver documentation.*



### Common Programming Error 24.8

*Attempting to move the cursor backward through a `ResultSet` when the database driver does not support backward scrolling causes a `SQLFeatureNotSupportedException`.*

`ResultSet`s that are sensitive to changes reflect those changes immediately after they’re made with methods of interface `ResultSet`. If a `ResultSet` is insensitive to changes, the query that produced the `ResultSet` must be executed again to reflect any changes made. The **result set concurrency** (Fig. 24.27) specifies whether the `ResultSet` can be updated with `ResultSet`’s update methods.

| ResultSet static concurrency constant | Description                                                                                                                                                                                |
|---------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>CONCUR_READ_ONLY</code>         | Specifies that a <code>ResultSet</code> can’t be updated—changes to the <code>ResultSet</code> contents cannot be reflected in the database with <code>ResultSet</code> ’s update methods. |
| <code>CONCUR_UPDATABLE</code>         | Specifies that a <code>ResultSet</code> can be updated (i.e., changes to its contents can be reflected in the database with <code>ResultSet</code> ’s update methods).                     |

**Fig. 24.27** | `ResultSet` constants for specifying result properties.





#### Portability Tip 24.4

*Some JDBC drivers do not support updatable ResultSets. In such cases, the driver typically returns a read-only ResultSet. For more information, see your database driver documentation.*



#### Common Programming Error 24.9

*Attempting to update a ResultSet when the database driver does not support updatable ResultSets causes SQLFeatureNotSupportedException.*

This example uses a ResultSet that is scrollable, insensitive to changes and read only. Line 45 (Fig. 24.25) invokes method `setQuery` (lines 144–163) to perform the default query.

#### **ResultSetTableModel Method getColumnClass**

Method `getColumnClass` (lines 49–69) returns a `Class` object that represents the superclass of all objects in a particular column. The `JTable` uses this information to configure the default cell renderer and cell editor for that column in the `JTable`. Line 58 uses `ResultSetMetaData` method `getColumnClassName` to obtain the fully qualified class name for the specified column. Line 61 loads the class and returns the corresponding `Class` object. If an exception occurs, the catch in lines 63–66 prints a stack trace and line 68 returns `Object.class`—the `Class` instance that represents class `Object`—as the default type. [Note: Line 58 uses the argument `column + 1`. Like arrays, `JTable` row and column numbers are counted from 0. However, `ResultSet` row and column numbers are counted from 1. Thus, when processing `ResultSet` rows or columns for use in a `JTable`, it's necessary to add 1 to the row or column number to manipulate the appropriate `ResultSet` row or column.]

#### **ResultSetTableModel Method getColumnCount**

Method `getColumnCount` (lines 72–89) returns the number of columns in the model's underlying `ResultSet`. Line 81 uses `ResultSetMetaData` method `getColumnCount` to obtain the number of columns in the `ResultSet`. If an exception occurs, the catch in lines 83–86 prints a stack trace and line 88 returns 0 as the default number of columns.

#### **ResultSetTableModel Method getColumnName**

Method `getColumnName` (lines 92–109) returns the name of the column in the model's underlying `ResultSet`. Line 101 uses `ResultSetMetaData` method `getColumnName` to obtain the column name from the `ResultSet`. If an exception occurs, the catch in lines 103–106 prints a stack trace and line 108 returns the empty string as the default column name.

#### **ResultSetTableModel Method getRowCount**

Method `getRowCount` (lines 112–119) returns the number of rows in the model's underlying `ResultSet`. When method `setQuery` (lines 144–163) performs a query, it stores the number of rows in variable `numberOfRows`.

#### **ResultSetTableModel Method getValueAt**

Method `getValueAt` (lines 122–141) returns the `Object` in a particular row and column of the model's underlying `ResultSet`. Line 132 uses `ResultSet` method `absolute` to position the `ResultSet` cursor at a specific row. Line 133 uses `ResultSet` method `getObject` to obtain the `Object` in a specific column of the current row. If an exception occurs, the catch in lines 135–138 prints a stack trace and line 140 returns an empty string as the default value.

**ResultSetTableModel Method setQuery**

Method `setQuery` (lines 144–163) executes the query it receives as an argument to obtain a new `ResultSet` (line 152). Line 155 gets the `ResultSetMetaData` for the new `ResultSet`. Line 158 uses `ResultSet` method `last` to position the `ResultSet` cursor at the last row in the `ResultSet`. [Note: This can be slow if the table contains many rows.] Line 159 uses `ResultSet` method `getRow` to obtain the row number for the current row in the `ResultSet`. Line 162 invokes method `fireTableStructureChanged` (inherited from class `AbstractTableModel`) to notify any `JTable` using this `ResultSetTableModel` object as its model that the structure of the model has changed. This causes the `JTable` to repopulate its rows and columns with the new `ResultSet` data. Method `setQuery` throws any exceptions that occur in its body back to the application that invoked `setQuery`.

**ResultSetTableModel Method disconnectFromDatabase**

Method `disconnectFromDatabase` (lines 166–186) implements an appropriate termination method for class `ResultSetTableModel`. A class designer should provide a `public` method that clients of the class must invoke explicitly to free resources that an object has used. In this case, method `disconnectFromDatabase` closes the `ResultSet`, `Statement` and `Connection` (lines 173–175), which are considered limited resources. Clients of the `ResultSetTableModel` class should always invoke this method when the instance of this class is no longer needed. Before releasing resources, line 168 verifies whether the connection is already terminated. If not, the method proceeds. The other methods in class `ResultSetTableModel` each throw an `IllegalStateException` if `connectedToDatabase` is `false`. Method `disconnectFromDatabase` sets `connectedToDatabase` to `false` (line 183) to ensure that clients do not use an instance of `ResultSetTableModel` after that instance has already been terminated. `IllegalStateException` is an exception from the Java libraries that is appropriate for indicating this error condition.

**DisplayQueryResults Class**

Class `DisplayQueryResults` (Fig. 24.28) implements the application's GUI and interacts with the `ResultSetTableModel` via a `JTable` object. This application also demonstrates the `JTable` sorting and filtering capabilities.

---

```

1 // Fig. 24.28: DisplayQueryResults.java
2 // Display the contents of the Authors table in the books database.
3 import java.awt.BorderLayout;
4 import java.awt.event.ActionListener;
5 import java.awt.event.ActionEvent;
6 import java.awt.event.WindowAdapter;
7 import java.awt.event.WindowEvent;
8 import java.sql.SQLException;
9 import java.util.regex.PatternSyntaxException;
10 import javax.swing.JFrame;
11 import javax.swing.JTextArea;
12 import javax.swing.JScrollPane;
13 import javax.swing.ScrollPaneConstants;
14 import javax.swing.JTable;
15 import javax.swing.JOptionPane;

```

---

**Fig. 24.28** | Display the contents of the Authors table in the books database. (Part 1 of 5.)

---

```

16 import javax.swing.JButton;
17 import javax.swing.Box;
18 import javax.swing.JLabel;
19 import javax.swing.JTextField;
20 import javax.swing.RowFilter;
21 import javax.swing.table.TableRowSorter;
22 import javax.swing.table.TableModel;
23
24 public class DisplayQueryResults extends JFrame
25 {
26 // database URL, username and password
27 private static final String DATABASE_URL = "jdbc:derby:books";
28 private static final String USERNAME = "deitel";
29 private static final String PASSWORD = "deitel";
30
31 // default query retrieves all data from Authors table
32 private static final String DEFAULT_QUERY = "SELECT * FROM Authors";
33
34 private static ResultSetTableModel tableModel;
35
36 public static void main(String args[])
37 {
38 // create ResultSetTableModel and display database table
39 try
40 {
41 // create TableModel for results of query SELECT * FROM Authors
42 tableModel = new ResultSetTableModel(DATABASE_URL,
43 USERNAME, PASSWORD, DEFAULT_QUERY);
44
45 // set up JTextArea in which user types queries
46 final JTextArea queryArea = new JTextArea(DEFAULT_QUERY, 3, 100);
47 queryArea.setWrapStyleWord(true);
48 queryArea.setLineWrap(true);
49
50 JScrollPane scrollPane = new JScrollPane(queryArea,
51 ScrollPaneConstants.VERTICAL_SCROLLBAR_AS_NEEDED,
52 ScrollPaneConstants.HORIZONTAL_SCROLLBAR_NEVER);
53
54 // set up JButton for submitting queries
55 JButton submitButton = new JButton("Submit Query");
56
57 // create Box to manage placement of queryArea and
58 // submitButton in GUI
59 Box boxNorth = Box.createHorizontalBox();
60 boxNorth.add(scrollPane);
61 boxNorth.add(submitButton);
62
63 // create JTable based on the tableModel
64 JTable resultTable = new JTable(tableModel);
65
66 JLabel filterLabel = new JLabel("Filter:");
67 final JTextField filterText = new JTextField();
68 JButton filterButton = new JButton("Apply Filter");

```

---

**Fig. 24.28** | Display the contents of the Authors table in the books database. (Part 2 of 5.)

---

```

69 Box boxSouth = Box.createHorizontalBox();
70
71 boxSouth.add(filterLabel);
72 boxSouth.add(filterText);
73 boxSouth.add(filterButton);
74
75 // place GUI components on JFrame's content pane
76 JFrame window = new JFrame("Displaying Query Results");
77 add(boxNorth, BorderLayout.NORTH);
78 add(new JScrollPane(resultTable), BorderLayout.CENTER);
79 add(boxSouth, BorderLayout.SOUTH);
80
81 // create event listener for submitButton
82 submitButton.addActionListener(
83 new ActionListener()
84 {
85 public void actionPerformed(ActionEvent event)
86 {
87 // perform a new query
88 try
89 {
90 tableModel.setQuery(queryArea.getText());
91 }
92 catch (SQLException sqlException)
93 {
94 JOptionPane.showMessageDialog(null,
95 sqlException.getMessage(), "Database error",
96 JOptionPane.ERROR_MESSAGE);
97
98 // try to recover from invalid user query
99 // by executing default query
100 try
101 {
102 tableModel.setQuery(DEFAULT_QUERY);
103 queryArea.setText(DEFAULT_QUERY);
104 }
105 catch (SQLException sqlException2)
106 {
107 JOptionPane.showMessageDialog(null,
108 sqlException2.getMessage(), "Database error",
109 JOptionPane.ERROR_MESSAGE);
110
111 // ensure database connection is closed
112 tableModel.disconnectFromDatabase();
113
114 System.exit(1); // terminate application
115 }
116 }
117 }
118 }
119);
120

```

---

**Fig. 24.28** | Display the contents of the Authors table in the books database. (Part 3 of 5.)

```

121 final TableRowSorter<TableModel> sorter =
122 new TableRowSorter<TableModel>(tableModel);
123 resultTable.setRowSorter(sorter);
124
125 // create listener for filterButton
126 filterButton.addActionListener(
127 new ActionListener()
128 {
129 // pass filter text to listener
130 public void actionPerformed(ActionEvent e)
131 {
132 String text = filterText.getText();
133
134 if (text.length() == 0)
135 sorter.setRowFilter(null);
136 else
137 {
138 try
139 {
140 sorter.setRowFilter(
141 RowFilter.regexFilter(text));
142 }
143 catch (PatternSyntaxException pse)
144 {
145 JOptionPane.showMessageDialog(null,
146 "Bad regex pattern", "Bad regex pattern",
147 JOptionPane.ERROR_MESSAGE);
148 }
149 }
150 }
151 }
152);
153 // dispose of window when user quits application (this overrides
154 // the default of HIDE_ON_CLOSE)
155 window.setDefaultCloseOperation(DISPOSE_ON_CLOSE);
156 window.setSize(500, 250);
157 window.setVisible(true);
158
159 // ensure database is closed when user quits application
160 addWindowListener(
161 new WindowAdapter()
162 {
163 // disconnect from database and exit when window has closed
164 public void windowClosed(WindowEvent event)
165 {
166 tableModel.disconnectFromDatabase();
167 System.exit(0);
168 }
169 }
170);
171 }
172 catch (SQLException sqlException)
173 {

```


**Fig. 24.28** | Display the contents of the Authors table in the books database. (Part 4 of 5.)

```


174 JOptionPane.showMessageDialog(null, sqlException.getMessage(),
175 "Database error", JOptionPane.ERROR_MESSAGE);
176 tableModel.disconnectFromDatabase();
177 System.exit(1); // terminate application
178 }
179 }
180 } // end class DisplayQueryResults

```


a) Displaying all authors from the Authors table



b) Displaying the the authors' first and last names joined with the titles and edition numbers of the books they've authored



c) Filtering the results of the previous query to show only the books with Java in the title



**Fig. 24.28** | Display the contents of the Authors table in the books database. (Part 5 of 5.)

Lines 27–29 and 32 declare the URL, username, password and default query that are passed to the `ResultSetTableModel` constructor to make the initial connection to the database and perform the default query. The main method (lines 36–179) creates a

`ResultSetTableModel` object and the GUI for the application and displays the GUI in a `JFrame`. Line 64 creates the `JTable` object and passes a `ResultSetTableModel` object (created at lines 42–43) to the `JTable` constructor, which then registers the `JTable` as a listener for `TableModelEvents` generated by the `ResultSetTableModel`.

The local variables `queryArea` (line 46), `filterText` (line 67) and `sorter` (lines 121–122) are declared `final` because they're used from anonymous inner classes. Recall that any local variable that will be used in an anonymous inner class must be declared `final`; otherwise, a compilation error occurs. (In Java SE 8, this program would compile without declaring these variables `final` because these variables would be effectively `final`, as discussed in Chapter 17.)

Lines 82–119 register an event handler for the `submitButton` that the user clicks to submit a query to the database. When the user clicks the button, method `actionPerformed` (lines 85–117) invokes method `setQuery` from the class `ResultSetTableModel` to execute the new query (line 90). If the user's query fails (e.g., because of a syntax error in the user's input), lines 102–103 execute the default query. If the default query also fails, there could be a more serious error, so line 112 ensures that the database connection is closed and line 114 exits the program. The screen captures in Fig. 24.28 show the results of two queries. The first screen capture shows the default query that retrieves all the data from table `Authors` of database `books`. The second screen capture shows a query that selects each author's first name and last name from the `Authors` table and combines that information with the title and edition number from the `Titles` table. Try entering your own queries in the text area and clicking the **Submit Query** button to execute the query.

Lines 161–170 register a `WindowListener` for the `windowClosed` event, which occurs when the user closes the window. Since `WindowListeners` can handle several window events, we extend class `WindowAdapter` and override only the `windowClosed` event handler.

### *Sorting Rows in a JTable*

`JTables` allow users to sort rows by the data in a specific column. Lines 121–122 use the `TableRowSorter` class (from package `javax.swing.table`) to create an object that uses our `ResultSetTableModel` to sort rows in the `JTable` that displays query results. When the user clicks the title of a particular `JTable` column, the `TableRowSorter` interacts with the underlying `TableModel` to reorder the rows based on the data in that column. Line 123 uses `JTable` method `setRowSorter` to specify the `TableRowSorter` for `resultTable`.

### *Filtering Rows in a JTable*

`JTables` can now show subsets of the data from the underlying `TableModel`. This is known as filtering the data. Lines 126–152 register an event handler for the `filterButton` that the user clicks to filter the data. In method `actionPerformed` (lines 130–150), line 132 obtains the filter text. If the user did not specify filter text, line 135 uses `JTable` method `setRowFilter` to remove any prior filter by setting the filter to `null`. Otherwise, lines 140–141 use `setRowFilter` to specify a `RowFilter` (from package `javax.swing`) based on the user's input. Class `RowFilter` provides several methods for creating filters. The static method `regexFilter` receives a `String` containing a regular expression pattern as its argument and an optional set of indices that specify which columns to filter. If no indices are specified, then all the columns are searched. In this example, the regular expression pattern is the text the user typed. Once the filter is set, the data displayed in the `JTable` is updated based on the filtered `TableModel`.

## 24.7 RowSet Interface

In the preceding examples, you learned how to query a database by explicitly establishing a `Connection` to the database, preparing a `Statement` for querying the database and executing the query. In this section, we demonstrate the **RowSet interface**, which configures the database connection and prepares query statements automatically. The interface `RowSet` provides several *set* methods that allow you to specify the properties needed to establish a connection (such as the database URL, username and password of the database) and create a `Statement` (such as a query). `RowSet` also provides several *get* methods that return these properties.

### *Connected and Disconnected RowSets*

There are two types of `RowSet` objects—connected and disconnected. A **connected RowSet** object connects to the database once and remains connected while the object is in use. A **disconnected RowSet** object connects to the database, executes a query to retrieve the data from the database and then closes the connection. A program may change the data in a disconnected `RowSet` while it's disconnected. Modified data can be updated in the database after a disconnected `RowSet` reestablishes the connection with the database.

Package `javax.sql.rowset` contains two subinterfaces of `RowSet`—`JdbcRowSet` and `CachedRowSet`. **`JdbcRowSet`**, a connected `RowSet`, acts as a wrapper around a `ResultSet` object and allows you to scroll through and update the rows in the `ResultSet`. Recall that by default, a `ResultSet` object is nonscrollable and read only—you must explicitly set the result-set type constant to `TYPE_SCROLL_INSENSITIVE` and set the result-set concurrency constant to `CONCUR_UPDATABLE` to make a `ResultSet` object scrollable and updatable. A `JdbcRowSet` object is scrollable and updatable by default. **`CachedRowSet`**, a disconnected `RowSet`, caches the data of a `ResultSet` in memory and disconnects from the database. Like `JdbcRowSet`, a `CachedRowSet` object is scrollable and updatable by default. A `CachedRowSet` object is also *serializable*, so it can be passed between Java applications through a network, such as the Internet. However, `CachedRowSet` has a limitation—the amount of data that can be stored in memory is limited. Package `javax.sql.rowset` contains three other subinterfaces of `RowSet`.



### Portability Tip 24.5

*A `RowSet` can provide scrolling capability for drivers that do not support scrollable `ResultSet`s.*

### *Using a RowSet*

Figure 24.29 reimplements the example of Fig. 24.23 using a `RowSet`. Rather than establish the connection and create a `Statement` explicitly, Fig. 24.29 uses a `JdbcRowSet` object to create a `Connection` and a `Statement` automatically.

Class **`RowSetProvider`** (package `javax.sql.rowset`) provides static method **`newFactory`** which returns an object that implements interface **`RowSetFactory`** (package `javax.sql.rowset`) that can be used to create various types of `RowSets`. Lines 18–19 in the try-with-resources statement use `RowSetFactory` method **`createJdbcRowSet`** to obtain a `JdbcRowSet` object.

Lines 22–24 set the `RowSet` properties that the `DriverManager` uses to establish a database connection. Line 22 invokes `JdbcRowSet` method **`setUrl`** to specify the database



---

```

1 // Fig. 24.29: JdbcRowSetTest.java
2 // Displaying the contents of the Authors table using JdbcRowSet.
3 import java.sql.ResultSetMetaData;
4 import java.sql.SQLException;
5 import javax.sql.rowset.JdbcRowSet;
6 import javax.sql.rowset.RowSetProvider;
7
8 public class JdbcRowSetTest
9 {
10 // JDBC driver name and database URL
11 private static final String DATABASE_URL = "jdbc:derby:books";
12 private static final String USERNAME = "deitel";
13 private static final String PASSWORD = "deitel";
14
15 public static void main(String args[])
16 {
17 // connect to database books and query database
18 try (JdbcRowSet rowSet =
19 RowSetProvider.newFactory().createJdbcRowSet())
20 {
21 // specify JdbcRowSet properties
22 rowSet.setUrl(DATABASE_URL);
23 rowSet.setUsername(USERNAME);
24 rowSet.setPassword(PASSWORD);
25 rowSet.setCommand("SELECT * FROM Authors"); // set query
26 rowSet.execute(); // execute query
27
28 // process query results
29 ResultSetMetaData metaData = rowSet.getMetaData();
30 int numberOfColumns = metaData.getColumnCount();
31 System.out.printf("Authors Table of Books Database:%n%n");
32
33 // display rowset header
34 for (int i = 1; i <= numberOfColumns; i++)
35 System.out.printf("%-8s\t", metaData.getColumnName(i));
36 System.out.println();
37
38 // display each row
39 while (rowSet.next())
40 {
41 for (int i = 1; i <= numberOfColumns; i++)
42 System.out.printf("%-8s\t", rowSet.getObject(i));
43 System.out.println();
44 }
45 }
46 catch (SQLException sqlException)
47 {
48 sqlException.printStackTrace();
49 System.exit(1);
50 }
51 }
52 } // end class JdbcRowSetTest

```

---

**Fig. 24.29** | Displaying the contents of the Authors table using JdbcRowSet. (Part 1 of 2.)

Authors Table of Books Database:

| AUTHORID | FIRSTNAME | LASTNAME |
|----------|-----------|----------|
| 1        | Paul      | Deitel   |
| 2        | Harvey    | Deitel   |
| 3        | Abbey     | Deitel   |
| 4        | Dan       | Quirk    |
| 5        | Michael   | Morgano  |

**Fig. 24.29** | Displaying the contents of the Authors table using `JdbcRowSet`. (Part 2 of 2.)

URL. Line 23 invokes `JdbcRowSet` method **`setUsername`** to specify the username. Line 24 invokes `JdbcRowSet` method **`setPassword`** to specify the password. Line 25 invokes `JdbcRowSet` method **`setCommand`** to specify the SQL query that will be used to populate the `RowSet`. Line 26 invokes `JdbcRowSet` method **`execute`** to execute the SQL query. Method `execute` performs four actions—it establishes a `Connection` to the database, prepares the query `Statement`, executes the query and stores the `ResultSet` returned by query. The `Connection`, `Statement` and `ResultSet` are encapsulated in the `JdbcRowSet` object.

The remaining code is almost identical to Fig. 24.23, except that line 29 (Fig. 24.29) obtains a `ResultSetMetaData` object from the `JdbcRowSet`, line 39 uses the `JdbcRowSet`'s `next` method to get the next row of the result and line 42 uses the `JdbcRowSet`'s `getObject` method to obtain a column's value. When the end of the try block is reached, the try-with-resources statement invokes `JdbcRowSet` method **`close`**, which closes the `RowSet`'s encapsulated `ResultSet`, `Statement` and `Connection`. In a `CachedRowSet`, invoking `close` also releases the resources held by that `RowSet`. The output of this application is the same as that of Fig. 24.23.

## 24.8 PreparedStatement

A **PreparedStatement** enables you to create compiled SQL statements that execute more efficiently than `Statements`. `PreparedStatement`s can also specify parameters, making them more flexible than `Statements`—you can execute the same query repeatedly with different parameter values. For example, in the books database, you might want to locate all book titles for an author with a specific last and first name, and you might want to execute that query for several authors. With a `PreparedStatement`, that query is defined as follows:

```
PreparedStatement authorBooks = connection.prepareStatement(
 "SELECT LastName, FirstName, Title " +
 "FROM Authors INNER JOIN AuthorISBN " +
 "ON Authors.AuthorID=AuthorISBN.AuthorID " +
 "INNER JOIN Titles " +
 "ON AuthorISBN.ISBN=Titles.ISBN " +
 "WHERE LastName = ? AND FirstName = ?");
```

The two question marks (?) in the the preceding SQL statement's last line are placeholders for values that will be passed as part of the query to the database. Before executing a `PreparedStatement`, the program must specify the parameter values by using the `PreparedStatement` interface's `set` methods.

For the preceding query, both parameters are strings that can be set with `PreparedStatement` method **`setString`** as follows:

```
authorBooks.setString(1, "Deitel");
authorBooks.setString(2, "Paul");
```

Method `setString`'s first argument represents the parameter number being set, and the second argument is that parameter's value. Parameter numbers are *counted from 1*, starting with the first question mark (?). When the program executes the preceding `PreparedStatement` with the parameter values set above, the SQL passed to the database is

```
SELECT LastName, FirstName, Title
FROM Authors INNER JOIN AuthorISBN
 ON Authors.AuthorID=AuthorISBN.AuthorID
INNER JOIN Titles
 ON AuthorISBN.ISBN=Titles.ISBN
WHERE LastName = 'Deitel' AND FirstName = 'Paul'
```

Method `setString` automatically escapes `String` parameter values as necessary. For example, if the last name is O'Brien, the statement

```
authorBooks.setString(1, "O'Brien");
```

escapes the ' character in O'Brien by replacing it with two single-quote characters, so that the ' appears correctly in the database.



### Performance Tip 24.2

*PreparedStatement*s are more efficient than *Statements* when executing SQL statements multiple times and with different parameter values.



### Error-Prevention Tip 24.2

Use *PreparedStatement*s with parameters for queries that receive *String* values as arguments to ensure that the *Strings* are quoted properly in the SQL statement.



### Error-Prevention Tip 24.3

*PreparedStatement*s help prevent SQL injection attacks, which typically occur in SQL statements that include user input improperly. To avoid this security issue, use *PreparedStatement*s in which user input can be supplied only via parameters—indicated with ? when creating a *PreparedStatement*. Once you've created such a *PreparedStatement*, you can use its *set* methods to specify the user input as arguments for those parameters.

Interface `PreparedStatement` provides *set* methods for each supported SQL type. It's important to use the *set* method that is appropriate for the parameter's SQL type in the database—`SQLException`s occur when a program attempts to convert a parameter value to an incorrect type.

### Address Book Application that Uses PreparedStatement

We now present an address book app that enables you to browse existing entries, add new entries and search for entries with a specific last name. Our `AddressBook` Java DB database contains an `Addresses` table with the columns `addressID`, `FirstName`, `LastName`, `Email` and `PhoneNumber`. The column `addressID` is an identity column in the `Addresses` table.

### Class Person

Our address book application consists of three classes—`Person` (Fig. 24.30), `PersonQueries` (Fig. 24.31) and `AddressBookDisplay` (Fig. 24.32). Class `Person` is a simple class

that represents one person in the address book. The class contains fields for the address ID, first name, last name, email address and phone number, as well as *set* and *get* methods for manipulating these fields.

---

```

1 // Fig. 24.30: Person.java
2 // Person class that represents an entry in an address book.
3 public class Person
4 {
5 private int addressID;
6 private String firstName;
7 private String lastName;
8 private String email;
9 private String phoneNumber;
10
11 // constructor
12 public Person()
13 {
14 }
15
16 // constructor
17 public Person(int addressID, String firstName, String lastName,
18 String email, String phoneNumber)
19 {
20 setAddressID(addressID);
21 setFirstName(firstName);
22 setLastName(lastName);
23 setEmail(email);
24 setPhoneNumber(phoneNumber);
25 }
26
27 // sets the addressID
28 public void setAddressID(int addressID)
29 {
30 this.addressID = addressID;
31 }
32
33 // returns the addressID
34 public int getAddressID()
35 {
36 return addressID;
37 }
38
39 // sets the firstName
40 public void setFirstName(String firstName)
41 {
42 this.firstName = firstName;
43 }
44
45 // returns the first name
46 public String getFirstName()
47 {

```

---

**Fig. 24.30** | Person class that represents an entry in an AddressBook. (Part 1 of 2.)

---

```

48 return firstName;
49 }
50
51 // sets the lastName
52 public void setLastName(String lastName)
53 {
54 this.lastName = lastName;
55 }
56
57 // returns the last name
58 public String getLastName()
59 {
60 return lastName;
61 }
62
63 // sets the email address
64 public void setEmail(String email)
65 {
66 this.email = email;
67 }
68
69 // returns the email address
70 public String getEmail()
71 {
72 return email;
73 }
74
75 // sets the phone number
76 public void setPhoneNumber(String phone)
77 {
78 this.phoneNumber = phone;
79 }
80
81 // returns the phone number
82 public String getPhoneNumber()
83 {
84 return phoneNumber;
85 }
86 } // end class Person

```

---

**Fig. 24.30** | Person class that represents an entry in an AddressBook. (Part 2 of 2.)

### *Class PersonQueries*

Class PersonQueries (Fig. 24.31) manages the address book application's database connection and creates the PreparedStatement variables that the application uses to interact with the database. Lines 18–20 declare three PreparedStatement variables. The constructor (lines 23–49) connects to the database at lines 27–28.

---

```

1 // Fig. 24.31: PersonQueries.java
2 // PreparedStatement used by the Address Book application.
3 import java.sql.Connection;

```

---

**Fig. 24.31** | PreparedStatement used by the Address Book application. (Part 1 of 5.)

---

```

4 import java.sql.DriverManager;
5 import java.sql.PreparedStatement;
6 import java.sql.ResultSet;
7 import java.sql.SQLException;
8 import java.util.List;
9 import java.util.ArrayList;
10
11 public class PersonQueries
12 {
13 private static final String URL = "jdbc:derby:AddressBook";
14 private static final String USERNAME = "deitel";
15 private static final String PASSWORD = "deitel";
16
17 private Connection connection; // manages connection
18 private PreparedStatement selectAllPeople;
19 private PreparedStatement selectPeopleByLastName;
20 private PreparedStatement insertNewPerson;
21
22 // constructor
23 public PersonQueries()
24 {
25 try
26 {
27 connection =
28 DriverManager.getConnection(URL, USERNAME, PASSWORD);
29
30 // create query that selects all entries in the AddressBook
31 selectAllPeople =
32 connection.prepareStatement("SELECT * FROM Addresses");
33
34 // create query that selects entries with a specific last name
35 selectPeopleByLastName = connection.prepareStatement(
36 "SELECT * FROM Addresses WHERE LastName = ?");
37
38 // create insert that adds a new entry into the database
39 insertNewPerson = connection.prepareStatement(
40 "INSERT INTO Addresses " +
41 "(FirstName, LastName, Email, PhoneNumber) " +
42 "VALUES (?, ?, ?, ?)");
43 }
44 catch (SQLException sqlException)
45 {
46 sqlException.printStackTrace();
47 System.exit(1);
48 }
49 }
50
51 // select all of the addresses in the database
52 public List< Person > getAllPeople()
53 {
54 List< Person > results = null;
55 ResultSet resultSet = null;
56

```

---

**Fig. 24.31** | PreparedStatements used by the Address Book application. (Part 2 of 5.)

---

```

57 try
58 {
59 // executeQuery returns ResultSet containing matching entries
60 resultSet = selectAllPeople.executeQuery();
61 results = new ArrayList< Person >();
62
63 while (resultSet.next())
64 {
65 results.add(new Person(
66 resultSet.getInt("addressID"),
67 resultSet.getString("FirstName"),
68 resultSet.getString("LastName"),
69 resultSet.getString("Email"),
70 resultSet.getString("PhoneNumber")));
71 }
72 }
73 catch (SQLException sqlException)
74 {
75 sqlException.printStackTrace();
76 }
77 finally
78 {
79 try
80 {
81 resultSet.close();
82 }
83 catch (SQLException sqlException)
84 {
85 sqlException.printStackTrace();
86 close();
87 }
88 }
89
90 return results;
91 }
92
93 // select person by last name
94 public List< Person > getPeopleByLastName(String name)
95 {
96 List< Person > results = null;
97 ResultSet resultSet = null;
98
99 try
100 {
101 selectPeopleByLastName.setString(1, name); // specify last name
102
103 // executeQuery returns ResultSet containing matching entries
104 resultSet = selectPeopleByLastName.executeQuery();
105
106 results = new ArrayList< Person >();
107
108 while (resultSet.next())
109 {

```

---

**Fig. 24.31** | PreparedStatement used by the Address Book application. (Part 3 of 5.)

---

```

110 results.add(new Person(resultSet.getInt("addressID"),
111 resultSet.getString("FirstName"),
112 resultSet.getString("LastName"),
113 resultSet.getString("Email"),
114 resultSet.getString("PhoneNumber")));
115 }
116 }
117 catch (SQLException sqlException)
118 {
119 sqlException.printStackTrace();
120 }
121 finally
122 {
123 try
124 {
125 resultSet.close();
126 }
127 catch (SQLException sqlException)
128 {
129 sqlException.printStackTrace();
130 close();
131 }
132 }
133
134 return results;
135 }
136
137 // add an entry
138 public int addPerson(
139 String fname, String lname, String email, String num)
140 {
141 int result = 0;
142
143 // set parameters, then execute insertNewPerson
144 try
145 {
146 insertNewPerson.setString(1, fname);
147 insertNewPerson.setString(2, lname);
148 insertNewPerson.setString(3, email);
149 insertNewPerson.setString(4, num);
150
151 // insert the new entry; returns # of rows updated
152 result = insertNewPerson.executeUpdate();
153 }
154 catch (SQLException sqlException)
155 {
156 sqlException.printStackTrace();
157 close();
158 }
159
160 return result;
161 }
162

```

---

**Fig. 24.31** | PreparedStatements used by the Address Book application. (Part 4 of 5.)



---

```

163 // close the database connection
164 public void close()
165 {
166 try
167 {
168 connection.close();
169 }
170 catch (SQLException sqlException)
171 {
172 sqlException.printStackTrace();
173 }
174 }
175 } // end class PersonQueries

```

---

**Fig. 24.31** | PreparedStatement used by the Address Book application. (Part 5 of 5.)

### *Creating PreparedStatement*

Lines 31–32 invoke Connection method **prepareStatement** to create the PreparedStatement named **selectAllPeople** that selects all the rows in the Addresses table. Lines 35–36 create the PreparedStatement named **selectPeopleByLastName** with a parameter. This statement selects all the rows in the Addresses table that match a particular last name. Notice the ? character that's used to specify the last-name parameter. Lines 39–42 create the PreparedStatement named **insertNewPerson** with four parameters that represent the first name, last name, email address and phone number for a new entry. Again, notice the ? characters used to represent these parameters.

### *PersonQueries Method getAllPeople*

Method **getAllPeople** (lines 52–91) executes PreparedStatement **selectAllPeople** (line 60) by calling method **executeQuery**, which returns a **ResultSet** containing the rows that match the query (in this case, all the rows in the Addresses table). Lines 61–71 place the query results in an **ArrayList** of **Person** objects, which is returned to the caller at line 90. Method **getPeopleByLastName** (lines 94–135) uses PreparedStatement method **setString** to set the parameter to **selectPeopleByLastName** (line 101). Then, line 104 executes the query and lines 106–115 place the query results in an **ArrayList** of **Person** objects. Line 134 returns the **ArrayList** to the caller.

### *PersonQueries Methods addPerson and Close*

Method **addPerson** (lines 138–161) uses PreparedStatement method **setString** (lines 146–149) to set the parameters for the **insertNewPerson** PreparedStatement. Line 152 uses PreparedStatement method **executeUpdate** to insert the new record. This method returns an integer indicating the number of rows that were updated (or inserted) in the database. Method **close** (lines 164–174) simply closes the database connection.

### *Class AddressBookDisplay*

The **AddressBookDisplay** (Fig. 24.32) application uses a **PersonQueries** object to interact with the database. Line 59 creates the **PersonQueries** object. When the user presses the **Browse All Entries** JButton, the **browseButtonActionPerformed** handler (lines 309–335) is called. Line 313 calls the method **getAllPeople** on the **PersonQueries** object to obtain all the entries in the database. The user can then scroll through the entries using the

**Previous** and **Next** JButtons. When the user presses the **Find** JButton, the `queryButtonActionPerformed` handler (lines 265–287) is called. Lines 267–268 call method `getPeopleByLastName` on the `PersonQueries` object to obtain the entries in the database that match the specified last name. If there are several such entries, the user can then scroll through them using the **Previous** and **Next** JButtons.

---

```

1 // Fig. 24.32: AddressBookDisplay.java
2 // A simple address book
3 import java.awt.event.ActionEvent;
4 import java.awt.event.ActionListener;
5 import java.awt.event.WindowAdapter;
6 import java.awt.event.WindowEvent;
7 import java.awt.FlowLayout;
8 import java.awt.GridLayout;
9 import java.util.List;
10 import javax.swing.JButton;
11 import javax.swing.Box;
12 import javax.swing.JFrame;
13 import javax.swing.JLabel;
14 import javax.swing.JPanel;
15 import javax.swing.JTextField;
16 import javax.swing.WindowConstants;
17 import javax.swing.BoxLayout;
18 import javax.swing.BorderFactory;
19 import javax.swing.JOptionPane;
20
21 public class AddressBookDisplay extends JFrame
22 {
23 private Person currentEntry;
24 private PersonQueries personQueries;
25 private List<Person> results;
26 private int numberOfEntries = 0;
27 private int currentEntryIndex;
28
29 private JButton browseButton;
30 private JLabel emailLabel;
31 private JTextField emailTextField;
32 private JLabel firstNameLabel;
33 private JTextField firstNameTextField;
34 private JLabel idLabel;
35 private JTextField idTextField;
36 private JTextField indexTextField;
37 private JLabel lastNameLabel;
38 private JTextField lastNameTextField;
39 private JTextField maxTextField;
40 private JButton nextButton;
41 private JLabel ofLabel;
42 private JLabel phoneLabel;
43 private JTextField phoneTextField;
44 private JButton previousButton;
45 private JButton queryButton;
46 private JLabel queryLabel;

```

---

**Fig. 24.32** | A simple address book. (Part I of 8.)

---

```

47 private JPanel queryPanel;
48 private JPanel navigatePanel;
49 private JPanel displayPanel;
50 private JTextField queryTextField;
51 private JButton insertButton;
52
53 // constructor
54 public AddressBookDisplay()
55 {
56 super("Address Book");
57
58 // establish database connection and set up PreparedStatement
59 personQueries = new PersonQueries();
60
61 // create GUI
62 navigatePanel = new JPanel();
63 previousButton = new JButton();
64 indexTextField = new JTextField(2);
65 ofLabel = new JLabel();
66 maxTextField = new JTextField(2);
67 nextButton = new JButton();
68 displayPanel = new JPanel();
69 idLabel = new JLabel();
70 idTextField = new JTextField(10);
71 firstNameLabel = new JLabel();
72 firstNameTextField = new JTextField(10);
73 lastNameLabel = new JLabel();
74 lastNameTextField = new JTextField(10);
75 emailLabel = new JLabel();
76 emailTextField = new JTextField(10);
77 phoneLabel = new JLabel();
78 phoneTextField = new JTextField(10);
79 queryPanel = new JPanel();
80 queryLabel = new JLabel();
81 queryTextField = new JTextField(10);
82 queryButton = new JButton();
83 browseButton = new JButton();
84 insertButton = new JButton();
85
86 setLayout(new FlowLayout(FlowLayout.CENTER, 10, 10));
87 setSize(400, 300);
88 setResizable(false);
89
90 navigatePanel.setLayout(
91 new BoxLayout(navigatePanel, BoxLayout.X_AXIS));
92
93 previousButton.setText("Previous");
94 previousButton.setEnabled(false);
95 previousButton.addActionListener(
96 new ActionListener()
97 {
98 public void actionPerformed(ActionEvent evt)
99 {

```

---

**Fig. 24.32** | A simple address book. (Part 2 of 8.)

---

```

100 previousButtonActionPerformed(evt);
101 }
102 }
103);
104
105 navigatePanel.add(previousButton);
106 navigatePanel.add(Box.createHorizontalStrut(10));
107
108 indexTextField.setHorizontalAlignment(
109 JTextField.CENTER);
110 indexTextField.addActionListener(
111 new ActionListener()
112 {
113 public void actionPerformed(ActionEvent evt)
114 {
115 indexTextFieldActionPerformed(evt);
116 }
117 }
118);
119
120 navigatePanel.add(indexTextField);
121 navigatePanel.add(Box.createHorizontalStrut(10));
122
123 ofLabel.setText("of");
124 navigatePanel.add(ofLabel);
125 navigatePanel.add(Box.createHorizontalStrut(10));
126
127 maxTextField.setHorizontalAlignment(
128 JTextField.CENTER);
129 maxTextField.setEditable(false);
130 navigatePanel.add(maxTextField);
131 navigatePanel.add(Box.createHorizontalStrut(10));
132
133 nextButton.setText("Next");
134 nextButton.setEnabled(false);
135 nextButton.addActionListener(
136 new ActionListener()
137 {
138 public void actionPerformed(ActionEvent evt)
139 {
140 nextButtonActionPerformed(evt);
141 }
142 }
143);
144
145 navigatePanel.add(nextButton);
146 add(navigatePanel);
147
148 displayPanel.setLayout(new GridLayout(5, 2, 4, 4));
149
150 idLabel.setText("Address ID:");
151 displayPanel.add(idLabel);
152

```

---

**Fig. 24.32** | A simple address book. (Part 3 of 8.)

---

```

153 idTextField.setEditable(false);
154 displayPanel.add(idTextField);
155
156 firstNameLabel.setText("First Name:");
157 displayPanel.add(firstNameLabel);
158 displayPanel.add(firstNameTextField);
159
160 lastNameLabel.setText("Last Name:");
161 displayPanel.add(lastNameLabel);
162 displayPanel.add(lastNameTextField);
163
164 emailLabel.setText("Email:");
165 displayPanel.add(emailLabel);
166 displayPanel.add(emailTextField);
167
168 phoneLabel.setText("Phone Number:");
169 displayPanel.add(phoneLabel);
170 displayPanel.add(phoneTextField);
171 add(displayPanel);
172
173 queryPanel.setLayout(
174 new BorderLayout(queryPanel, BorderLayout.X_AXIS));
175
176 queryPanel.setBorder(BorderFactory.createTitledBorder(
177 "Find an entry by last name"));
178 queryLabel.setText("Last Name:");
179 queryPanel.add(Box.createHorizontalStrut(5));
180 queryPanel.add(queryLabel);
181 queryPanel.add(Box.createHorizontalStrut(10));
182 queryPanel.add(queryTextField);
183 queryPanel.add(Box.createHorizontalStrut(10));
184
185 queryButton.setText("Find");
186 queryButton.addActionListener(
187 new ActionListener()
188 {
189 public void actionPerformed(ActionEvent evt)
190 {
191 queryButtonActionPerformed(evt);
192 }
193 }
194);
195
196 queryPanel.add(queryButton);
197 queryPanel.add(Box.createHorizontalStrut(5));
198 add(queryPanel);
199
200 browseButton.setText("Browse All Entries");
201 browseButton.addActionListener(
202 new ActionListener()
203 {
204 public void actionPerformed(ActionEvent evt)
205 {

```

---

**Fig. 24.32** | A simple address book. (Part 4 of 8.)

---

```

206 browseButtonActionPerformed(evt);
207 }
208 }
209);
210
211 add(browseButton);
212
213 insertButton.setText("Insert New Entry");
214 insertButton.addActionListener(
215 new ActionListener()
216 {
217 public void actionPerformed(ActionEvent evt)
218 {
219 insertButtonActionPerformed(evt);
220 }
221 }
222);
223
224 add(insertButton);
225
226 addWindowListener(
227 new WindowAdapter()
228 {
229 public void windowClosing(WindowEvent evt)
230 {
231 personQueries.close(); // close database connection
232 System.exit(0);
233 }
234 }
235);
236
237 setVisible(true);
238 } // end constructor
239
240 // handles call when previousButton is clicked
241 private void previousButtonActionPerformed(ActionEvent evt)
242 {
243 currentEntryIndex--;
244
245 if (currentEntryIndex < 0)
246 currentEntryIndex = numberOfEntries - 1;
247
248 indexTextField.setText("" + (currentEntryIndex + 1));
249 indexTextFieldActionPerformed(evt);
250 }
251
252 // handles call when nextButton is clicked
253 private void nextButtonActionPerformed(ActionEvent evt)
254 {
255 currentEntryIndex++;
256
257 if (currentEntryIndex >= numberOfEntries)
258 currentEntryIndex = 0;

```

---

**Fig. 24.32** | A simple address book. (Part 5 of 8.)

---

```

259
260 indexTextField.setText("" + (currentEntryIndex + 1));
261 indexTextFieldActionPerformed(evt);
262 }
263
264 // handles call when queryButton is clicked
265 private void queryButtonActionPerformed(ActionEvent evt)
266 {
267 results =
268 personQueries.getPeopleByLastName(queryTextField.getText());
269 numberOfEntries = results.size();
270
271 if (numberOfEntries != 0)
272 {
273 currentEntryIndex = 0;
274 currentEntry = results.get(currentEntryIndex);
275 idTextField.setText("" + currentEntry.getAddressID());
276 firstNameTextField.setText(currentEntry.getFirstName());
277 lastNameTextField.setText(currentEntry.getLastName());
278 emailTextField.setText(currentEntry.getEmail());
279 phoneTextField.setText(currentEntry.getPhoneNumber());
280 maxTextField.setText("" + numberOfEntries);
281 indexTextField.setText("" + (currentEntryIndex + 1));
282 nextButton.setEnabled(true);
283 previousButton.setEnabled(true);
284 }
285 else
286 browseButtonActionPerformed(evt);
287 }
288
289 // handles call when a new value is entered in indexTextField
290 private void indexTextFieldActionPerformed(ActionEvent evt)
291 {
292 currentEntryIndex =
293 (Integer.parseInt(indexTextField.getText()) - 1);
294
295 if (numberOfEntries != 0 && currentEntryIndex < numberOfEntries)
296 {
297 currentEntry = results.get(currentEntryIndex);
298 idTextField.setText("" + currentEntry.getAddressID());
299 firstNameTextField.setText(currentEntry.getFirstName());
300 lastNameTextField.setText(currentEntry.getLastName());
301 emailTextField.setText(currentEntry.getEmail());
302 phoneTextField.setText(currentEntry.getPhoneNumber());
303 maxTextField.setText("" + numberOfEntries);
304 indexTextField.setText("" + (currentEntryIndex + 1));
305 }
306 }
307
308 // handles call when browseButton is clicked
309 private void browseButtonActionPerformed(ActionEvent evt)
310 {

```

---

**Fig. 24.32** | A simple address book. (Part 6 of 8.)

---

```

311 try
312 {
313 results = personQueries.getAllPeople();
314 numberOfEntries = results.size();
315
316 if (numberOfEntries != 0)
317 {
318 currentEntryIndex = 0;
319 currentEntry = results.get(currentEntryIndex);
320 idTextField.setText("" + currentEntry.getAddressID());
321 firstNameTextField.setText(currentEntry.getFirstName());
322 lastNameTextField.setText(currentEntry.getLastName());
323 emailTextField.setText(currentEntry.getEmail());
324 phoneTextField.setText(currentEntry.getPhoneNumber());
325 maxTextField.setText("" + numberOfEntries);
326 indexTextField.setText("" + (currentEntryIndex + 1));
327 nextButton.setEnabled(true);
328 previousButton.setEnabled(true);
329 }
330 }
331 catch (Exception e)
332 {
333 e.printStackTrace();
334 }
335 }
336
337 // handles call when insertButton is clicked
338 private void insertButtonActionPerformed(ActionEvent evt)
339 {
340 int result = personQueries.addPerson(firstNameTextField.getText(),
341 lastNameTextField.getText(), emailTextField.getText(),
342 phoneTextField.getText());
343
344 if (result == 1)
345 JOptionPane.showMessageDialog(this, "Person added!",
346 "Person added", JOptionPane.PLAIN_MESSAGE);
347 else
348 JOptionPane.showMessageDialog(this, "Person not added!",
349 "Error", JOptionPane.PLAIN_MESSAGE);
350
351 browseButtonActionPerformed(evt);
352 }
353
354 // main method
355 public static void main(String args[])
356 {
357 new AddressBookDisplay();
358 }
359 } // end class AddressBookDisplay

```

---

**Fig. 24.32** | A simple address book. (Part 7 of 8.)



a) Initial **Address Book** screen.


Address Book

Previous 1 of 2 Next

Address ID:

First Name:

Last Name:

Email:

Phone Number:

Find an entry by last name

Last Name:  Find

Browse All Entries Insert New Entry

b) Results of clicking **Browse All Entries**.


Address Book

Previous 1 of 2 Next

Address ID:

First Name:

Last Name:

Email:

Phone Number:

Find an entry by last name

Last Name:  Find

Browse All Entries Insert New Entry

c) Browsing to the next entry.



Address Book

Previous 2 of 2 Next

Address ID:

First Name:

Last Name:

Email:

Phone Number:

Find an entry by last name

Last Name:  Find

Browse All Entries Insert New Entry

d) Finding entries with the last name **Green**.


Address Book

Previous 1 of 1 Next

Address ID:

First Name:

Last Name:

Email:

Phone Number:

Find an entry by last name

Last Name:  Find

Browse All Entries Insert New Entry

e) After adding a new entry and browsing to it.



Address Book

Previous 3 of 3 Next

Address ID:

First Name:

Last Name:

Email:

Phone Number:

Find an entry by last name

Last Name:  Find

Browse All Entries Insert New Entry

**Fig. 24.32** | A simple address book. (Part 8 of 8.)

To add a new entry into the AddressBook database, the user can enter the first name, last name, email and phone number (the AddressID will *autoincrement*) in the JTextFields and press the **Insert New Entry** JButton. The insertButtonActionPerformed handler (lines 338–352) is called. Lines 340–342 call the method addPerson on the PersonQueries object to add a new entry to the database. Line 351 calls browseButtonActionPerformed to obtain the updated set of people in the address book and update the GUI accordingly.

The user can then view different entries by pressing the **Previous** JButton or **Next** JButton, which results in calls to methods `previousButtonActionPerformed` (lines 241–250) or `nextButtonActionPerformed` (lines 253–262), respectively. Alternatively, the user can enter a number in the `indexTextField` and press *Enter* to view a particular entry. This results in a call to method `indexTextFieldActionPerformed` (lines 290–306) to display the specified record.

## 24.9 Stored Procedures

Many database management systems can store individual or sets of SQL statements in a database, so that programs accessing that database can invoke them. Such named collections of SQL statements are called **stored procedures**. JDBC enables programs to invoke stored procedures using objects that implement the interface **CallableStatement**. `CallableStatements` can receive arguments specified with the methods inherited from interface `PreparedStatement`. In addition, `CallableStatements` can specify **output parameters** in which a stored procedure can place return values. Interface `CallableStatement` includes methods to specify which parameters in a stored procedure are output parameters. The interface also includes methods to obtain the values of output parameters returned from a stored procedure.



### Portability Tip 24.6

*Although the syntax for creating stored procedures differs across database management systems, the interface `CallableStatement` provides a uniform interface for specifying input and output parameters for stored procedures and for invoking stored procedures.*



### Portability Tip 24.7

*According to the Java API documentation for interface `CallableStatement`, for maximum portability between database systems, programs should process the update counts (which indicate how many rows were updated) or `ResultSets` returned from a `CallableStatement` before obtaining the values of any output parameters.*

## 24.10 Transaction Processing

Many database applications require guarantees that a series of database insertions, updates and deletions executes properly before the application continues processing the next database operation. For example, when you transfer money electronically between bank accounts, several factors determine if the transaction is successful. You begin by specifying the source account and the amount you wish to transfer from that account to a destination account. Next, you specify the destination account. The bank checks the source account to determine whether its funds are sufficient to complete the transfer. If so, the bank withdraws the specified amount and, if all goes well, deposits it into the destination account to complete the transfer. What happens if the transfer fails after the bank withdraws the money from the source account? In a proper banking system, the bank redeposits the money in the source account. How would you feel if the money was subtracted from your source account and the bank *did not* deposit the money in the destination account?

**Transaction processing** enables a program that interacts with a database to *treat a database operation (or set of operations) as a single operation*. Such an operation also is known

as an **atomic operation** or a **transaction**. At the end of a transaction, a decision can be made either to **commit the transaction** or **roll back the transaction**. Committing the transaction finalizes the database operation(s); all insertions, updates and deletions performed as part of the transaction cannot be reversed without performing a new database operation. Rolling back the transaction leaves the database in its state prior to the database operation. This is useful when a portion of a transaction fails to complete properly. In our bank-account-transfer discussion, the transaction would be rolled back if the deposit could not be made into the destination account.

Java provides transaction processing via methods of interface `Connection`. Method `setAutoCommit` specifies whether each SQL statement commits after it completes (a true argument) or whether several SQL statements should be grouped as a transaction (a false argument). If the argument to `setAutoCommit` is false, the program must follow the last SQL statement in the transaction with a call to `Connection` method `commit` (to commit the changes to the database) or `Connection` method `rollback` (to return the database to its state prior to the transaction). Interface `Connection` also provides method `getAutoCommit` to determine the autocommit state for the `Connection`.

## 24.11 Wrap-Up

In this chapter, you learned basic database concepts, how to query and manipulate data in a database using SQL and how to use JDBC to allow Java applications to interact with Java DB databases. You learned about the SQL commands `SELECT`, `INSERT`, `UPDATE` and `DELETE`, as well as clauses such as `WHERE`, `ORDER BY` and `INNER JOIN`. You created and configured databases in Java DB by using predefined SQL scripts. You learned the steps for obtaining a `Connection` to the database, creating a `Statement` to interact with the database's data, executing the statement and processing the results. Then you used a `RowSet` to simplify the process of connecting to a database and creating statements. You used `PreparedStatement`s to create precompiled SQL statements. We also provided overviews of `CallableStatement`s and transaction processing. In the next chapter, you'll build graphical user interfaces using JavaFX—Java's GUI technology of the future.

## Summary

### Section 24.1 Introduction

- A database (p. 1038) is an integrated collection of data. A database management system (DBMS; p. 1038) provides mechanisms for storing, organizing, retrieving and modifying data.
- Today's most popular database management systems are relational database (p. 1038) systems.
- SQL (p. 1038) is the international standard language used to query (p. 1038) and manipulate relational data.
- Programs connect to, and interact with, relational databases via an interface—software that facilitates communications between a database management system and a program.
- A JDBC driver (p. 1038) enables Java applications to connect to a database in a particular DBMS and allows you to retrieve and manipulate database data.

**Section 24.2 Relational Databases**

- A relational database (p. 1039) stores data in tables (p. 1039). Tables are composed of rows (p. 1039), and rows are composed of columns in which values are stored.
- A table's primary key (p. 1039) has a unique in each row.
- Each column (p. 1039) of a table represents a different attribute.
- The primary key can be composed of more than one column.
- An identity column is the SQL standard way to represent an autoincremented (p. 1040) column. The SQL `IDENTITY` keyword (p. 1040) marks a column as an identity column.
- A foreign key is a column in a table that must match the primary-key column in another table. This is known as the Rule of Referential Integrity (p. 1042).
- A one-to-many relationship (p. 1043) between tables indicates that a row in one table can have many related rows in a separate table.
- Every column in a primary key must have a value, and the value of the primary key must be unique. This is known as the Rule of Entity Integrity (p. 1043).
- Foreign keys enable information from multiple tables to be joined together. There's a one-to-many relationship between a primary key and its corresponding foreign key.

**Section 24.4.1 Basic SELECT Query**

- The basic form of a query (p. 1044) is

```
SELECT * FROM tableName
```

where the asterisk (\*) (p. 1044) indicates that all columns from *tableName* should be selected, and *tableName* specifies the table in the database from which rows will be retrieved.

- To retrieve specific columns, replace the \* with a comma-separated list of column names.

**Section 24.4.2 WHERE Clause**

- The optional WHERE clause (p. 1045) in a query specifies the selection criteria for the query. The basic form of a query with selection criteria (p. 1044) is

```
SELECT columnName1, columnName2, ... FROM tableName WHERE criteria
```

- The WHERE clause can contain operators <, >, <=, >=, =, <> and LIKE. LIKE (p. 1045) is used for string pattern matching (p. 1045) with wildcard characters percent (%) and underscore (\_).
- A percent character (%) (p. 1045) in a pattern indicates that a string matching the pattern can have zero or more characters at the percent character's location in the pattern.
- An underscore (\_) (p. 1045) in the pattern string indicates a single character at that position in the pattern.

**Section 24.4.3 ORDER BY Clause**

- A query's result can be sorted with the ORDER BY clause (p. 1047). The simplest form of an ORDER BY clause is

```
SELECT columnName1, columnName2, ... FROM tableName ORDER BY column ASC
SELECT columnName1, columnName2, ... FROM tableName ORDER BY column DESC
```

where ASC specifies ascending order, DESC specifies descending order and *column* specifies the column on which the sort is based. The default sorting order is ascending, so ASC is optional.

- Multiple columns can be used for ordering purposes with an ORDER BY clause of the form

```
ORDER BY column1 sortingOrder, column2 sortingOrder, ...
```

- The WHERE and ORDER BY clauses can be combined in one query. If used, ORDER BY must be the last clause in the query.

#### **Section 24.4.4 Merging Data from Multiple Tables: INNER JOIN**

- An INNER JOIN (p. 1049) merges rows from two tables by matching values in columns that are common to the tables. The basic form for the INNER JOIN operator is:

```
SELECT columnName1, columnName2, ...
FROM table1
INNER JOIN table2
ON table1.columnName = table2.columnName
```

The ON clause (p. 1049) specifies the columns from each table that are compared to determine which rows are joined. If a SQL statement uses columns with the same name from multiple tables, the column names must be fully qualified (p. 1049) by prefixing them with their table names and a dot (.).

#### **Section 24.4.5 INSERT Statement**

- An INSERT statement (p. 1050) inserts a new row into a table. The basic form of this statement is

```
INSERT INTO tableName (columnName1, columnName2, ..., columnNameN)
VALUES (value1, value2, ..., valueN)
```

where *tableName* is the table in which to insert the row. The *tableName* is followed by a comma-separated list of column names in parentheses. The list of column names is followed by the SQL keyword VALUES (p. 1050) and a comma-separated list of values in parentheses.

- SQL uses single quotes (') to delimit strings. To specify a string containing a single quote in SQL, escape the single quote with another single quote (i.e., '' ).

#### **Section 24.4.6 UPDATE Statement**

- An UPDATE statement (p. 1051) modifies data in a table. The basic form of an UPDATE statement is

```
UPDATE tableName
SET columnName1 = value1, columnName2 = value2, ..., columnNameN = valueN
WHERE criteria
```

where *tableName* is the table to update. Keyword SET (p. 1051) is followed by a comma-separated list of *columnName = value* pairs. The optional WHERE clause determines which rows to update.

#### **Section 24.4.7 DELETE Statement**

- A DELETE statement (p. 1052) removes rows from a table. The simplest form for a DELETE statement is

```
DELETE FROM tableName WHERE criteria
```

where *tableName* is the table from which to delete a row (or rows). The optional WHERE *criteria* determines which rows to delete. If this clause is omitted, all the table's rows are deleted.

### **Section 24.5 Setting up a Java DB Database**

- Oracle's pure Java database Java DB (p. 1052) is installed with the JDK on Windows, Mac OS X and Linux.
- Java DB has both an embedded version and a network version.
- The Java DB software is located in the db subdirectory of your JDK's installation directory.
- Java DB comes with several files that enable you to configure and run it. Before executing these files from a command window, you must set the environment variable JAVA\_HOME to refer to the JDK's exact installation directory.

- You use the `setEmbeddedCP.bat` or `setEmbeddedCP` file (depending on your OS platform) to configure the `CLASSPATH` for working with Java DB embedded databases.
- The Java DB `ij` tool allows you to interact with Java DB from the command line. You can use it to create databases, run SQL scripts and perform SQL queries. Each command you enter at the `ij>` prompt must be terminated with a semicolon (;).

### *Section 24.6.1 Connecting to and Querying a Database*

- Package `java.sql` contains classes and interfaces for accessing relational databases in Java.
- A `Connection` object (p. 1057) manages the connection between a Java program and a database. `Connection` objects enable programs to create SQL statements that access data.
- `DriverManager` (p. 1057) method `getConnection` (p. 1057) attempts to connect to a database at a URL that specifies the protocol for communication, the subprotocol (p. 1057) for communication and the database name.
- `Connection` method `createStatement` (p. 1058) creates a `Statement` object (p. 1058), which can be used to submit SQL statements to the database.
- `Statement` method `executeQuery` (p. 1058) executes a query and returns a `ResultSet` object (p. 1058). `ResultSet` methods enable a program to manipulate query results.
- A `ResultSetMetaData` object (p. 1058) describes a `ResultSet`'s contents. Programs can use meta-data programmatically to obtain information about the `ResultSet` column names and types.
- `ResultSetMetaData` method `getColumnCount` (p. 1058) retrieves the number of `ResultSet` columns.
- `ResultSet` method `next` (p. 1058) positions the `ResultSet` cursor to the next row and returns `true` if the row exists; otherwise, it returns `false`. This method must be called to begin processing a `ResultSet` because the cursor is initially positioned before the first row.
- It's possible to extract each `ResultSet` column as a specific Java type. `ResultSetMetaData` method `getColumnType` (p. 1058) returns a `Types` (p. 1059) constant (package `java.sql`) indicating the column's type.
- `ResultSet` *get* methods typically receive as an argument either a column number (as an `int`) or a column name (as a `String`) indicating which column's value to obtain.
- `ResultSet` row and column numbers start at 1.
- Each `Statement` object can open only one `ResultSet` at a time. When a `Statement` returns a new `ResultSet`, the `Statement` closes the prior `ResultSet`.

### *Section 24.6.2 Querying the books Database*

- `TableModel` (p. 1059) method `getColumnClass` (p. 1060) returns a `Class` object that represents the superclass of all objects in a particular column. A `JTable` (p. 1059) uses this information to set up the default cell renderer and cell editor for that column in a `JTable`.
- `Connection` method `createStatement` has an overloaded version that receives the result type and concurrency. The result type specifies whether the `ResultSet`'s cursor is able to scroll in both directions or forward only and whether the `ResultSet` is sensitive to changes. The result concurrency (p. 1064) specifies whether the `ResultSet` can be updated.
- Some JDBC drivers (p. 1064) do not support scrollable or updatable `ResultSet`s.
- `ResultSetMetaData` method `getColumnClassName` (p. 1065) obtains a column's fully qualified class name.
- `TableModel` method `getColumnCount` (p. 1065) returns the number of columns in the `ResultSet`.
- `TableModel` method `getColumnName` (p. 1065) returns the column name in the `ResultSet`.

- `ResultSetMetaData` method `getColumnName` (p. 1065) obtains a `ResultSet` column's name.
- `TableModel` method `getRowCount` (p. 1065) returns the number of rows in the model's `ResultSet`.
- `TableModel` method `getValueAt` (p. 1065) returns the `Object` at a particular row and column of the model's underlying `ResultSet`.
- `ResultSet` method `absolute` (p. 1065) positions the `ResultSet` cursor at a specific row.
- `AbstractTableModel` method `fireTableStructureChanged` (p. 1066) notifies any `JTable` using a particular `TableModel` object as its model that the data in the model has changed.

### ***Section 24.7 RowSet Interface***

- Interface `RowSet` (p. 1072) configures a database connection and executes a query automatically.
- A connected `RowSet` (p. 1072) remains connected to the database while the object is in use. A disconnected `RowSet` (p. 1072) connects, executes a query, then closes the connection.
- `JdbcRowSet` (p. 1072) (a connected `RowSet`) wraps a `ResultSet` object and allows you to scroll and update its rows. Unlike a `ResultSet` object, a `JdbcRowSet` is scrollable and updatable by default.
- `CachedRowSet` (p. 1072), a disconnected `RowSet`, caches a `ResultSet`'s data in memory. A `CachedRowSet` is scrollable and updatable. A `CachedRowSet` is also serializable.
- Class `RowSetProvider` (package `javax.sql.rowset`; p. 1072) provides static method `newFactory` which returns an object that implements interface `RowSetFactory` (package `javax.sql.rowset`) that can be used to create various types of `RowSets`.
- `RowSetFactory` (p. 1072) method `createJdbcRowSet` returns a `JdbcRowSet` object.
- `JdbcRowSet` method `setUrl` specifies the database URL.
- `JdbcRowSet` method `setUsername` specifies the username.
- `JdbcRowSet` method `setPassword` specifies the password.
- `JdbcRowSet` method `setCommand` specifies the SQL query that will be used to populate a `RowSet`.
- `JdbcRowSet` method `execute` executes the SQL query. Method `execute` performs establishes a Connection to the database, prepares the query Statement, executes the query and stores the `ResultSet` returned by query. The Connection, Statement and `ResultSet` are encapsulated in the `JdbcRowSet` object.

### ***Section 24.8 PreparedStatements***

- `PreparedStatements` (p. 1074) are compiled, so they execute more efficiently than `Statements`.
- `PreparedStatements` can have parameters, so the same query can execute with different arguments.
- A parameter is specified with a question mark (?) in the SQL statement. Before executing a `PreparedStatement`, you must use `PreparedStatement`'s `set` methods to specify the arguments.
- `PreparedStatement` method `setString`'s (p. 1074) first argument represents the parameter number being set and the second argument is that parameter's value.
- Parameter numbers are counted from 1, starting with the first question mark (?).
- Method `setString` automatically escapes `String` parameter values as necessary.
- Interface `PreparedStatement` provides `set` methods for each supported SQL type.

### ***Section 24.9 Stored Procedures***

- JDBC enables programs to invoke stored procedures (p. 1090) using `CallableStatement` (p. 1090) objects.
- `CallableStatement` can specify input parameters. `CallableStatement` can specify output parameters (p. 1090) in which a stored procedure can place return values.

**Section 24.10 Transaction Processing**

- Transaction processing (p. 1090) enables a program that interacts with a database to treat a database operation (or set of operations) as a single operation—known as an atomic operation (p. 1091) or a transaction (p. 1091).
- At the end of a transaction, a decision can be made to either commit or roll back the transaction.
- Committing a transaction (p. 1091) finalizes the database operation(s)—inserts, updates and deletes cannot be reversed without performing a new database operation.
- Rolling back a transaction (p. 1091) leaves the database in its state prior to the database operation.
- Java provides transaction processing via methods of interface `Connection`.
- Method `setAutoCommit` (p. 1091) specifies whether each SQL statement commits after it completes (a `true` argument) or whether several SQL statements should be grouped as a transaction.
- When autocommit is disabled, the program must follow the last SQL statement in the transaction with a call to `Connection` method `commit` (to commit the changes to the database; p. 1091) or `Connection` method `rollback` (to return the database to its state prior to the transaction; p. 1091).
- Method `getAutoCommit` (p. 1091) determines the autocommit state for the `Connection`.

**Self-Review Exercise**

- 24.1** Fill in the blanks in each of the following statements:
- The international standard database language is \_\_\_\_\_.
  - A table in a database consists of \_\_\_\_\_ and \_\_\_\_\_.
  - Statement objects return SQL query results as \_\_\_\_\_ objects.
  - The \_\_\_\_\_ uniquely identifies each row in a table.
  - SQL keyword \_\_\_\_\_ is followed by the selection criteria that specify the rows to select in a query.
  - SQL keywords \_\_\_\_\_ specify the order in which rows are sorted in a query.
  - Merging rows from multiple database tables is called \_\_\_\_\_ the tables.
  - A(n) \_\_\_\_\_ is an organized collection of data.
  - A(n) \_\_\_\_\_ is a set of columns whose values match the primary-key values of another table.
  - \_\_\_\_\_ method \_\_\_\_\_ is used to obtain a `Connection` to a database.
  - Interface \_\_\_\_\_ helps manage the connection between a Java program and a database.
  - A(n) \_\_\_\_\_ object is used to submit a query to a database.
  - Unlike a `ResultSet` object, \_\_\_\_\_ and \_\_\_\_\_ objects are scrollable and updatable by default.
  - \_\_\_\_\_, a disconnected `RowSet`, caches the data of a `ResultSet` in memory.

**Answers to Self-Review Exercise**

- 24.1** a) SQL. b) rows, columns. c) `ResultSet`. d) primary key. e) `WHERE`. f) `ORDER BY`. g) joining. h) database. i) foreign key. j) `DriverManager`, `getConnection`. k) `Connection`. l) `Statement`. m) `JdbcRowSet`, `CachedRowSet`. n) `CachedRowSet`.

**Exercises**

- 24.2** (*Query Application for the books Database*) Using the techniques shown in this chapter, define a complete query application for the books database. Provide the following predefined queries:



- a) Select all authors from the Authors table.
- b) Select a specific author and list all books for that author. Include each book's title, year and ISBN. Order the information alphabetically by the author's last name then by first name.
- c) Select a specific title and list all authors for that title. Order the authors alphabetically by last name then by first name.
- d) Provide any other queries you feel are appropriate.

Display a JComboBox with appropriate names for each predefined query. Also allow users to supply their own queries.

**24.3** (*Data-Manipulation Application for the books Database*) Define a data-manipulation application for the books database. The user should be able to edit existing data and add new data to the database (obeying referential and entity integrity constraints). Allow the user to edit the database in the following ways:

- a) Add a new author.
- b) Edit the existing information for an author.
- c) Add a new title for an author. (Remember that the book must have an entry in the AuthorISBN table.).
- d) Add a new entry in the AuthorISBN table to link authors with titles.

**24.4** (*Employee Database*) In Section 10.5, we introduced an employee-payroll hierarchy to calculate each employee's payroll. In this exercise, we provide a database of employees that corresponds to the employee-payroll hierarchy. (A SQL script to create the employees database is provided with the examples for this chapter.) Write an application that allows the user to:

- a) Add employees to the employee table.
- b) Add payroll information to the appropriate table for each new employee. For example, for a salaried employee add the payroll information to the salariedEmployees table.

Figure 24.33 is the entity-relationship diagram for the employees database.

**24.5** (*Employee Database Query Application*) Modify Exercise 24.4 to provide a JComboBox and a JTextArea to allow the user to perform a query that is either selected from the JComboBox or defined in the JTextArea. Sample predefined queries are:

- a) Select all employees working in Department SALES.
- b) Select hourly employees working over 30 hours.
- c) Select all commission employees in descending order of the commission rate.


**24.6** (*Employee Database Data-Manipulation Application*) Modify Exercise 24.5 to perform the following tasks:

- a) Increase base salary by 10% for all base-plus-commission employees.
- b) If the employee's birthday is in the current month, add a \$100 bonus.
- c) For all commission employees with gross sales over \$10,000, add a \$100 bonus.

**24.7** (*Address Book Modification: Update an Existing Entry*) Modify the program in Figs. 24.30–24.32 to provide a JButton that allows the user to call a method named updatePerson in PersonQueries class to update the current entry in the AddressBook database.

**24.8** (*Address Book Modification: Delete an Existing Entry*) Modify the program of Exercise 24.7 to provide a JButton that allows the user to call a method named deletePerson in PersonQueries class to delete the current entry in the AddressBook database.

**24.9** (*Optional Project: ATM Case Study with a Database*) Modify the optional ATM Case Study (online Chapters 33–34) to use an actual database to store the account information. We provide a SQL script to create BankDatabase, which has a single table consisting of four columns—AccountNumber (an int), PIN (an int), AvailableBalance (a double) and TotalBalance (a double).



**Fig. 24.33** | Table relationships in the employees database.

# JavaFX GUI: Part I

# 25



*But, soft! what light through  
yonder window breaks?  
It is the east, and Juliet is  
the sun!*

—William Shakespeare

*Even a minor event in the life of  
a child is an event of that child's  
world and thus a world event.*

—Gaston Bachelard

*... the wisest prophets make sure  
of the event first.*

—Horace Walpole

*Do you think I can listen all day  
to such stuff?*

—Lewis Carroll

## Objectives

In this chapter you'll:

- Build JavaFX GUIs and handle events generated by user interactions with them.
- Understand the structure of a JavaFX app window.
- Use JavaFX Scene Builder to create FXML files that describe JavaFX scenes containing **Labels**, **ImageViews**, **TextFields**, **Sliders** and **Buttons** without writing any code.
- Arrange GUI components using the **VBox** and **GridPane** layout containers.
- Use a controller class to define event handlers for JavaFX FXML GUI.
- Build two JavaFX apps.

- 25.1 Introduction
- 25.2 JavaFX Scene Builder and the NetBeans IDE
- 25.3 JavaFX App Window Structure
- 25.4 **Welcome App**—Displaying Text and an Image
  - 25.4.1 Creating the App's Project
  - 25.4.2 NetBeans **Projects** Window—Viewing the Project Contents
  - 25.4.3 Adding an Image to the Project
  - 25.4.4 Opening JavaFX Scene Builder from NetBeans
  - 25.4.5 Changing to a VBox Layout Container
  - 25.4.6 Configuring the VBox Layout Container
- 25.4.7 Adding and Configuring a Label
- 25.4.8 Adding and Configuring an ImageView
- 25.4.9 Running the Welcome App
- 25.5 **Tip Calculator App**—Introduction to Event Handling
  - 25.5.1 Test-Driving the **Tip Calculator App**
  - 25.5.2 Technologies Overview
  - 25.5.3 Building the App's GUI
  - 25.5.4 TipCalculator Class
  - 25.5.5 TipCalculatorController Class
- 25.6 Features Covered in the Online JavaFX Chapters
- 25.7 Wrap-Up

Summary | Self-Review Exercises | Answers to Self-Review Exercises | Exercises | Making a Difference

## 25.1 Introduction

[*Note:* The prerequisites for this chapter are Chapters 1–11. This chapter does not require that you've read Chapter 12, GUI Components: Part 1, which discusses Swing GUI.]

A **graphical user interface (GUI)** presents a user-friendly mechanism for interacting with an app. A GUI (pronounced “GOO-ee”) gives an app a distinctive “look-and-feel.” GUIs are built from **GUI components**. These are sometimes called *controls* or *widgets*—short for window gadgets. A GUI component is an object with which the user interacts via the mouse, the keyboard or another form of input, such as voice recognition.



### Look-and-Feel Observation 25.1

*Providing different apps with consistent, intuitive user-interface components gives users a sense of familiarity with a new app, so that they can learn it more quickly and use it more productively.*

### History of GUI in Java

Java's original GUI library was the Abstract Window Toolkit (AWT). Swing (Chapters 12 and 22) was added to the platform in Java SE 1.2. Since then, Swing has remained the primary Java GUI technology. Swing is now in maintenance mode—Oracle has stopped development and will provide only bug fixes going forward; however, it will remain part of Java and is still widely used.

Java's GUI, graphics and multimedia API of the future is **JavaFX**. Sun Microsystems (acquired by Oracle in 2010) announced JavaFX in 2007 as a competitor to Adobe Flash and Microsoft Silverlight. JavaFX 1.0 was released in 2008. Prior to version 2.0, developers used JavaFX Script—which was similar to JavaScript—to write JavaFX apps. The JavaFX Script source code compiled to Java bytecode, allowing JavaFX apps to run on the Java Virtual Machine. Starting with version 2.0 in 2011, JavaFX was reimplemented as a set of Java libraries that could be used directly in Java apps. Some of the benefits of JavaFX vs. Swing include:

- JavaFX is easier to use—it provides one API for GUI, graphics and multimedia (images, animation, audio and video), whereas Swing is only for GUIs, so you need to use other APIs for graphics and multimedia apps.
- With Swing, many IDEs provided GUI design tools for dragging and dropping components onto a layout; however, each IDE produced different code. JavaFX Scene Builder (Section 25.2) can be used standalone or integrated with many IDEs and it produces the same code regardless of the IDE.
- Though Swing components could be customized, JavaFX gives you complete control over a JavaFX GUI's look-and-feel (online Chapter 26) via Cascading Style Sheets (CSS).
- JavaFX was designed for improved thread safety, which is important for today's multi-core systems.
- JavaFX supports transformations for repositioning and reorienting JavaFX components, and animations for changing the properties of JavaFX components over time. These can be used to make apps more intuitive and easier to use.

### *JavaFX Version Used in This Chapter*

In this chapter, we use JavaFX 2.2 (released in late 2012) with Java SE 7. We tested the chapter's apps on Windows, Mac OS X and Linux. At the time of this writing, Oracle was about to release JavaFX 8 and Java SE 8. Our online Chapters 26 and 27—located on the book's companion website (see the inside front cover of this book)—present additional JavaFX GUI features and introduce JavaFX graphics and multimedia features in the context of JavaFX 8 and Java SE 8.

## 25.2 JavaFX Scene Builder and the NetBeans IDE

Most Java textbooks that introduce GUI programming provide hand-coded GUIs—that is, the authors build the GUIs from scratch in Java code, rather than using a visual GUI design tool. This is due to the fractured Java IDE market—there are many Java IDEs, so authors can't depend on any one IDE being used.

JavaFX is organized differently. The **JavaFX Scene Builder** tool is a standalone JavaFX GUI visual layout tool that can also be used with various IDEs, including the most popular ones—NetBeans, Eclipse and IntelliJ IDEA. JavaFX Scene Builder is most tightly integrated with NetBeans,<sup>1</sup> which is why we use it in our JavaFX presentation.

JavaFX Scene Builder enables you to create GUIs by dragging and dropping GUI components from Scene Builder's library onto a design area, then modifying and styling the GUI—all without writing any code. JavaFX Scene Builder's live editing and preview features allow you to view your GUI as you create and modify it, without compiling and running the app. You can use **Cascading Style Sheets (CSS)** to change the entire look-and-feel of your GUI—a concept sometimes called **skinning**. In online Chapter 26, we'll demonstrate the basics of styling with CSS.

In this chapter, we use JavaFX Scene Builder version 1.1 and NetBeans 7.4 to create two complete introductory JavaFX apps. Online Chapters 26–27 use JavaFX Scene Builder 2.0, which was about to be released when this book went to publication.

---

1. <http://www.oracle.com/technetwork/java/javafx/tools/index.html>.

*What is FXML?*


As you create and modify a GUI, JavaFX Scene Builder generates **FXML (FX Markup Language)**—an XML vocabulary for defining and arranging JavaFX GUI controls without writing any Java code. You do not need to know FXML or XML to study this chapter. As you'll see in Section 25.4, JavaFX Scene Builder hides the FXML details from you, so you can focus on defining *what* the GUI should contain without specifying *how* to generate it—this is another example of declarative programming, which we used with Java SE lambdas in Chapter 17.

**Software Engineering Observation 25.1**

*The FXML code is separate from the program logic that's defined in Java source code—this separation of the interface (the GUI) from the implementation (the Java code) makes it easier to debug, modify and maintain JavaFX GUI apps.*

## 25.3 JavaFX App Window Structure

A JavaFX app window consists of several parts (Fig. 25.1) that you'll use in Sections 25.4–25.5:




**Fig. 25.1** | JavaFX app window parts.

- The window in which a JavaFX app's GUI is displayed is known as the **stage** and is an instance of class **Stage** (package `javafx.stage`).
- The stage contains one active **scene** that defines the GUI as a **scene graph**—a tree data structure of an app's visual elements, such as GUI controls, shapes, images, video, text and more. The scene is an instance of class **Scene** (package `javafx.scene`).
- Each visual element in the scene graph is a **node**—an instance of a subclass of **Node** (package `javafx.scene`), which defines common attributes and behaviors for all nodes in the scene graph. With the exception of the first node in the scene graph—known as the **root node**—each node has one parent. Nodes can have transforms (e.g., moving, rotating, scaling and skewing), opacity (which controls whether a node is transparent, partially transparent or opaque), effects (e.g., drop shadows, blurs, reflection and lighting) and more that we'll introduce in online Chapter 26.

- Nodes that have children are typically **layout containers** that arrange their child nodes in the scene. You'll use two layout containers (VBox and GridPane) in this chapter and learn several more in online Chapters 26–27.
- The nodes arranged in a layout container are a combination of controls and, in more complex GUIs, possibly other layout containers. **Controls** are GUI components, such as `Labels` that display text, `TextFields` that enable a program to receive text typed by the user, `Buttons` that initiate actions and more. When the user interacts with a control, such as clicking a `Button`, the control generates an event. Programs can respond to these events—known as event handling—to specify what should happen when each user interaction occurs.
- An event handler is a method that responds to a user interaction. An FXML GUI's event handlers are defined in a so-called **controller class** (as you'll see in Section 25.5.5).

## 25.4 Welcome App—Displaying Text and an Image


In this section, *without writing any code* you'll build a JavaFX **Welcome** app that displays text in a **Label** and an image in an **ImageView** (Fig. 25.2). First, you'll create a JavaFX app project in the *NetBeans IDE*. Then, you'll use visual-programming techniques and JavaFX Scene Builder to *drag-and-drop* JavaFX components onto the design area. Next, you'll use JavaFX Scene Builder's **Inspector** window to configure options, such as the `Label`'s text and font size, and the `ImageView`'s image. Finally, you'll execute the app from NetBeans. This section assumes that you've read the Before You Begin section, and installed NetBeans and Scene Builder. We used NetBeans 7.4, Scene Builder 1.1 and Java SE 7 for this chapter's examples.



**Fig. 25.2** | Final Welcome app running on Windows 7.


### 25.4.1 Creating the App's Project


You'll now use NetBeans to create a **JavaFX FXML App**. Open NetBeans on your system. Initially, the **Start Page** (Fig. 25.3) is displayed—this page gives you links to the NetBeans documentation and displays a list of your recent projects, if any.



**Fig. 25.3** | NetBeans IDE showing the Start Page.

### *Creating a New Project*

To create an app, you must first create a **project**—a group of related files, such as code files and images that make up an app. Click the **New Project...** () button on the toolbar or select **File > New Project...** to display the **New Project** dialog (Fig. 25.4). Under **Categories**, select **JavaFX** and under **Projects** select **JavaFX FXML Application**, then click **Next >**.



**Fig. 25.4** | New Project dialog.




**New JavaFX Application Dialog**

In the **New JavaFX Application** dialog (Fig. 25.5), specify the following information:

1. **Project Name:** field—This is your app's name. Enter `Welcome` in this field.
2. **Project Location:** field—The project's location on your system. NetBeans places new projects in a subdirectory of `NetBeansProjects` within your user account's Documents folder. You can click the **Browse...** button to specify a different location. Your project's name is used as the subdirectory name.
3. **FXML name:** field—The name of the FXML filename that will contain the app's GUI. Enter `Welcome` here—the IDE creates the file `Welcome.fxml` in the project.
4. **Create Application Class:** checkbox—When this is checked, NetBeans creates a class with the specified name. This class contains the app's main method. Enter `Welcome` in this field. If you precede the class name with a package name, NetBeans creates the class in that package; otherwise, NetBeans will place the class in the default package.

Click **Finish** to create the project.




**Fig. 25.5** | New JavaFX Application dialog.

**25.4.2 NetBeans Projects Window—Viewing the Project Contents**

The NetBeans **Projects** window provides access to all of your projects. The **Welcome** node represents this app's project. You can have many projects open at once—each will have its own top-level node. Within a project's node, the contents are organized into folders and files. You can view the `Welcome` project's contents by expanding the **Welcome > Source**

**Packages** > <default package> node (Fig. 25.6). If you specified a package name for the app class in Fig. 25.5, then that package's name will appear rather than <default package>.



**Fig. 25.6** | NetBeans **Projects** window.

NetBeans creates and opens three files for a **JavaFX FXML Application** project:

- **Welcome.fxml**—This file contains the FXML markup for the GUI. By default, the IDE creates a GUI containing a **Button** and a **Label**.
- **Welcome.java**—This is the main class that creates the GUI from the FXML file and displays the GUI in a window.
- **WelcomeController.java**—This is the class in which you'd define the GUI's event handlers that allow the app to respond to user interactions with the GUI.

In Section 25.5, when we present an app with event handlers, we'll discuss the main app class and the controller class in detail. For the **Welcome** app, you will not edit any of these files in NetBeans, so you can close them. You do not need the **WelcomeController.java** file in this app, so you can right click the file in the **Projects** window and select **Delete** to remove it. Click **Yes** in the confirmation dialog to delete the file.

### 25.4.3 Adding an Image to the Project


One way to use an image in your app is to add its file to the project, then display it on an **ImageView**. The **bug.png** image you'll use for this app is located in the **images** subfolder of this chapter's examples folder. Locate the **images** folder on your file system, then drag **bug.png** onto the project's <default package> node to add the file to the project.

### 25.4.4 Opening JavaFX Scene Builder from NetBeans

You'll now open JavaFX Scene Builder so that you can create this app's GUI. To do so, right click **Welcome.fxml** in the **Projects** window, then select **Open** to view the FXML file in Scene Builder (Fig. 25.7).

#### *Deleting the Default Controls*

The FXML file provided by NetBeans contains a default GUI consisting of a **Button** control and a **Label** control. The **Welcome** app will not use these default controls, so you can delete them. To do so, click each in the content panel (or in the **Hierarchy** window at the bottom-left of Scene Builder's window), then press the *Backspace* or *Delete* key. In each case, Scene Builder displays the warning "**Some components have an fx:id. Do you really want to delete them?**". This means that there could be Java code in the project that refers



**Fig. 25.7** | JavaFX Scene Builder displaying the default GUI in `Welcome.fxml`.

to these controls—for this app, there will not be any such code, so you can click **Delete** to remove these controls.

### *Deleting the Reference to the `WelcomeController` Class*

As you'll learn in Section 25.5, in Scene Builder, you can specify the name of the controller class that contains methods for responding to the user's interactions with the GUI. The **Welcome** app does not need to respond to any user interactions, so you'll remove the reference in the FXML file to class `WelcomeController`. To do so, select the `AnchorPane` node in the **Hierarchy** window, then click the **Inspector** window's **Code** section to expand it and delete the value specified in the **Controller class** field. You're now ready to create the **Welcome** app's GUI.

### 25.4.5 Changing to a `VBox` Layout Container

For this app, you'll place a `Label` and an `ImageView` in a **`VBox` layout container** (package `javafx.scene.layout`), which will be the scene graph's root node. Layout containers help you arrange and size GUI components. A `VBox` arranges its nodes *vertically* from top to bottom. `VBox` is one of several JavaFX layout containers for arranging controls in a GUI. We discuss the `GridPane` layout container in Section 25.5 and several others in online Chapter 26. By default, NetBeans provides an `AnchorPane` as the root layout. To change from the default `AnchorPane` to a `VBox`:

1. *Adding a VBox to the Default Layout.* Drag a VBox from the **Library** window's **Containers** section onto the default AnchorPane in Scene Builder's content panel.
2. *Making the VBox the Root Layout.* Select **Edit > Trim Document to Selection** to make the VBox the root layout and remove the AnchorPane.

### 25.4.6 Configuring the VBox Layout Container

You'll now specify the VBox's alignment, initial size and padding:

1. *Specifying the VBox's Alignment.* A VBox's **alignment** determines the layout positioning of the VBox's children. In this app, we'd like each child node (the Label and the ImageView) to be centered horizontally in the scene, and we'd like both children to be centered vertically, so that there is an equal amount of space above the Label and below the ImageView. To accomplish this, select the VBox, then in the **Inspector's Properties** section, set the **Alignment** property to **CENTER**. When you set the **Alignment**, notice the variety of potential alignment values you can use.
2. *Specifying the VBox's Preferred Size.* The **preferred size** (width and height) of the scene graph's root node is used by the scene to determine its window size when the app begins executing. To set the preferred size, select the VBox, then in the **Inspector's Layout** section, set the **Pref Width** property to 450 and the **Pref Height** property to 300.

### 25.4.7 Adding and Configuring a Label

Next, you'll create the Label that displays "Welcome to JavaFX!":

1. *Adding a Label to the VBox.* Drag a Label from the **Library** window's **Controls** section onto the VBox. The Label is automatically centered in the VBox because you set the VBox's alignment to **CENTER** in Section 25.4.6.
2. *Changing the Label's text.* You can set a Label's text either by double clicking it and typing the text, or by selecting the Label and setting its **Text** property in the **Inspector's Properties** section. Set the Label's text to "Welcome to JavaFX!".
3. *Changing the Label's font.* For this app, we set the Label to display in a large bold font. To do so, select the Label, then in the **Inspector's Preferences** section, click the value to the right of the **Font** property. In the window that appears, set the **style** property to **Bold** and the **size** property to 30.

### 25.4.8 Adding and Configuring an ImageView

Finally, you'll add the ImageView that displays bug.png:

1. *Adding an ImageView to the VBox.* Drag an ImageView from the **Library** window's **Controls** section onto the VBox. The ImageView is automatically placed below the Label. Each new control you add to a VBox is placed below the VBox's other children, though you can change the order by dragging the children in Scene Builder's **Hierarchy** window. Like the Label, the ImageView is also automatically centered in the VBox.
2. *Setting the ImageViews's image.* To set the image to display, select the ImageView and click the ellipsis (...) button to the right of the **Image** property in the **Inspector's Properties** section.

tor's **Properties** section. By default, Scene Builder opens a dialog showing the project's source-code folder, which is where you placed the image file `bug.png` in Section 25.4.3. Select the image file, then click **Open**. Scene Builder displays the image and resizes the `ImageView` to match the image's aspect ratio—the ratio of the image's width to its height—by setting the `ImageView`'s **Fit Width** and **Fit Height** properties.

3. *Changing the `ImageView`'s size.* We'd like to display the image in its original size. To do so, you must delete the default values for the `ImageView`'s **Fit Width** and **Fit Height** properties, which are located in the **Inspector**'s **Layout** section. Once you delete these values, Scene Builder resizes the `ImageView` to the image's exact dimensions. Save the FXML file.

You've now completed the GUI. Scene Builder's content panel should now appear as shown in Fig. 25.8.



**Fig. 25.8** | Completed design of the **Welcome** app's GUI in Scene Builder.

### 25.4.9 Running the Welcome App


You can run the app from NetBeans in one of three ways:

- Select the project's root node in the NetBeans **Projects** window, then click the **Run Project** (▶) button on the toolbar.
- Select the project's root node in the NetBeans **Projects** window, then press F6.
- Right click the project's root node in the NetBeans **Projects** window, then select **Run**.

In each case, the IDE will compile the app (if it isn't already compiled), then run the app. The **Welcome** app should now appear as shown in Fig. 25.2.

## 25.5 Tip Calculator App—Introduction to Event Handling

The **Tip Calculator** app (Fig. 25.9(a)) calculates and displays a restaurant bill tip and total. By default, the app calculates the total with a 15% tip. You can specify a tip percentage from 0% to 30% by moving the *Slider thumb*—this updates the tip percentage (Fig. 25.9(b) and (c)). In this section, you'll build a **Tip Calculator** app using several JavaFX components and learn how to respond to user interactions with the GUI.





**Fig. 25.9** | Entering the bill amount and calculating the tip.

You'll begin by test-driving the app, using it to calculate 15% and 10% tips. Then we'll overview the technologies you'll use to create the app. You'll build the app's GUI using the NetBeans and JavaFX SceneBuilder. Finally, we'll present the complete Java code for the app and do a detailed code walkthrough.

### 25.5.1 Test-Driving the Tip Calculator App

#### *Opening and Running the App*

Open the NetBeans IDE, then perform the following steps to open the **Tip Calculator** app's project and run it:

1. *Opening the Tip Calculator app's project.* Select **File > Open Project...** or click the **Open Project...** () button on the toolbar to display the **Open Project** dialog. Navigate to this chapter's examples folder, select **TipCalculator** and click the **Open Project** button. A **TipCalculator** node now appears in the **Projects** window.
2. *Running the Tip Calculator app.* Right click the **TipCalculator** project in the **Projects** window, then click the **Run Project** () button on the toolbar.

#### *Entering a Bill Total*

Using your keyboard, enter 34.56, then press the **Calculate Button**. The **Tip** and **Total** **TextFields** show the tip amount and the total bill for a 15% tip (Fig. 25.9(b)).

#### *Selecting a Custom Tip Percentage*

Use the **Slider** to specify a *custom* tip percentage. Drag the **Slider's thumb** until the percentage reads **20%** (Fig. 25.9(c)), then press the **Calculate Button** to display the updated tip and total. As you drag the thumb, the tip percentage in the **Label** to the **Slider's** left updates continuously. By default, the **Slider** allows you to select values from 0.0 to 100.0, but in this app we'll restrict the **Slider** to selecting whole numbers from 0 to 30.

### 25.5.2 Technologies Overview

This section introduces the technologies you'll use to build the **Tip Calculator** app.

#### *Class Application*

The main class in a JavaFX app is a subclass of **Application** (package **javafx.application.Application**). The app's main method calls class **Application's** static **launch** method to begin executing a JavaFX app. This method, in turn, causes the JavaFX runtime to create an object of the **Application** subclass and call its **start** method, which creates the GUI, attaches it to a **Scene** and places it on the **Stage** that method **start** receives as an argument.


#### *Arranging JavaFX Components with a GridPane*

Recall that layout containers arrange JavaFX components in a **Scene**. A **GridPane** (package **javafx.scene.layout**) arranges JavaFX components into *columns* and *rows* in a rectangular grid.

This app uses a **GridPane** (Fig. 25.10) to arrange views into two columns and five rows. Each cell in a **GridPane** can be empty or can hold one or more JavaFX components, including layout containers that arrange other controls. Each component in a **GridPane** can span *multiple* columns or rows, though we did not use that capability in this GUI.

When you drag a `GridPane` onto Scene Builder's content panel, Scene Builder creates the `GridPane` with two columns and three rows by default. You can add and remove columns and rows as necessary. We'll discuss other `GridPane` features as we present the GUI-building steps. To learn more about class `GridPane`, visit:

<http://docs.oracle.com/javafx/2/api/javafx/scene/layout/GridPane.html>



**Fig. 25.10** | Tip Calculator GUI's `GridPane` labeled by its rows and columns.

### *Creating and Customizing the GUI with Scene Builder*

You'll create `Labels`, `TextFields`, a `Slider` and a `Button` by dragging them onto the content panel in Scene Builder, then customize them using the **Inspector** window.

- A **`TextField`** (package `javafx.scene.control`) can accept text input from the user or display text. You'll use one editable `TextField` to input the bill amount from the user and two *uneditable* `TextFields` to display the tip and total amounts.
- A **`Slider`** (package `javafx.scene.control`) represents a value in the range 0.0–100.0 by default and allows the user to select a number in that range by moving the `Slider`'s thumb. You'll customize the `Slider` so the user can choose a custom tip percentage *only* from the more limited range 0 to 30.
- A **`Button`** (package `javafx.scene.control`) allows the user to initiate an action—in this app, pressing the **Calculate** Button calculates and displays the tip and total amounts.

### *Formatting Numbers as Locale-Specific Currency and Percentage Strings*

You'll use class **`NumberFormat`** (package `java.text`) to create *locale-specific* currency and percentage strings—an important part of *internationalization*.

### *Event Handling*

Normally, a user interacts with an app's GUI to indicate the tasks that the app should perform. For example, when you write an e-mail in an e-mail app, clicking the **Send** button tells the app to send the e-mail to the specified e-mail addresses. GUIs are **event driven**. When the user interacts with a GUI component, the interaction—known as an **event**—



drives the program to perform a task. Some common user interactions that cause an app to perform a task include *clicking* a button, *typing* in a text field, *selecting* an item from a menu, *closing* a window and *moving* the mouse. The code that performs a task in response to an event is called an **event handler**, and the process of responding to events is known as **event handling**.

Before an app can respond to an event for a particular control, you must:

1. Create a class that represents the event handler and implements an appropriate interface—known as an **event-listener interface**.
2. Indicate that an object of that class should be notified when the event occurs—known as **registering the event handler**.

In this app, you'll respond to two events—when the user moves the `Slider`'s thumb, the app will update the `Label` that displays the current tip percentage, and when the user clicks the **Calculate** Button, the app will calculate and display the tip and total bill amount.

You'll see that for certain events—such as when the user clicks a Button—you can link a control to its event-handling method by using the **Code** section of Scene Builder's **Inspector** window. In this case, the class that implements the event-listener interface will be created for you and will call the method you specify. For events that occur when the value of control's property changes—such as when the user moves a `Slider`'s thumb to change the `Slider`'s value—you'll see that you must create the event handler entirely in code.

### *Implementing Interface `ChangeListener` for Handling `Slider` Thumb Position Changes*

You'll implement the **`ChangeListener`** interface (from package `javafx.beans.value`) to respond to the user moving the `Slider`'s thumb. In particular, you'll use method `changed` to display the user-selected tip percentage as the user moves the `Slider`'s thumb.

### *Model-View-Controller (MVC) Architecture*

JavaFX applications in which the GUI is implemented as FXML adhere to the **Model-View-Controller (MVC) design pattern**, which separates an app's data (contained in the **model**) from the app's GUI (the **view**) and the app's processing logic (the **controller**).

The controller implements logic for processing user inputs. The model contains application data, and the view presents the data stored in the model. When a user provides some input, the controller modifies the model with the given input. In the **Tip Calculator**, the model is the bill amount, the tip and the total. When the model changes, the controller updates the view to present the changed data.

In a JavaFX FXML app, you define the app's event handlers in a **controller class**. The controller class defines instance variables for interacting with controls programmatically, as well as event-handling methods. The controller class may also declare additional instance variables, **static** variables and methods that support the app's operation. In a simple app like the **Tip Calculator**, the model and controller are often combined into a single class, as we'll do in this example.

### *FXMLLoader Class*

When a JavaFX FXML app begins executing, class **`FXMLLoader`**'s static method **`load`** is used to load the FXML file that represents the app's GUI. This method:

- Creates the GUI's scene graph and returns a **Parent** (package `javafx.scene`) reference to the scene graph's root node.
- Initializes the controller's instance variables for the components that are manipulated programmatically.
- Creates and registers the event handlers for any events specified in the FXML.


We'll discuss these steps in more detail in Sections 25.5.4—25.5.5.

### 25.5.3 Building the App's GUI

In this section, we'll show the precise steps for using Scene Builder to create the **Tip Calculator**'s GUI. The GUI will not look like the one shown in Fig. 25.9 until you've completed the steps.

#### *fx:id Property Values for This App's Controls*

If a control or layout will be manipulated programmatically in the controller class (as we'll do with one of the `Labels`, all of the `TextFields` and the `Slider` in this app), you must provide a name for that control or layout. In Section 25.5.4, you'll learn how to declare variables in your source code for each such component in the FXML, and we'll discuss how those variables are initialized for you. Each object's name is specified via its **fx:id** property. You can set this property's value by selecting a component in your scene, then expanding the **Inspector** window's **Code** section—the **fx:id** property appears at the top of the **Code** section. Figure 25.11 shows the **fx:id** properties of the **Tip Calculator**'s programmatically manipulated controls. For clarity, our naming convention is to use the control's class name in the **fx:id** property.



**Fig. 25.11** | Tip Calculator's programmatically manipulated controls labeled with their **fx:ids**.

#### *Creating the TipCalculator Project*

Click the **New Project...** (📁) button on the toolbar or select **File > New Project...**. In the **New Project** dialog, under **Categories**, select **JavaFX** and under **Projects** select **JavaFX FXML Application**, then click **Next >** and specify **TipCalculator** in the **Project Name**, **FXML name** and **Create Application Class** fields. Click **Finish** to create the project.


**Step 1: Changing the Root Layout from an AnchorPane to a GridPane**

Open `TipCalculator.fxml` in Scene Builder so that you can build the GUI and delete the default controls, then change from the default `AnchorPane` to a `GridPane`:

1. **Adding a `GridPane` to the Default Layout.** Drag a `GridPane` from the **Library** window's **Containers** section onto the default `AnchorPane` in Scene Builder's content panel.
2. **Making the `GridPane` the Root Layout.** Select **Edit > Trim Document to Selection** to make the `GridPane` the root layout and remove the `AnchorPane`.

**Step 2: Adding Rows to the `GridPane`**

By default, the `GridPane` contains two columns and three rows. Recall that the GUI in Fig. 25.10 consists of five rows. You can add a row above or below an existing row by right clicking a row and selecting **Grid Pane > Add Row Above** or **Grid Pane > Add Row Below**. After adding two rows, the `GridPane` should appear as shown in Fig. 25.12. You can use similar steps to add columns. You can delete a row or column by right clicking the tab containing its row or column number and selecting **Delete**.




**Fig. 25.12** | `GridPane` with five rows.

**Step 3: Adding the Controls to the `GridPane`**

You'll now add the controls in Fig. 25.10 to the `GridPane`. For those that have `fx:id`s (see Fig. 25.11), while the control is selected, set its `fx:id` property in the **Inspector** window's **Code** section. Perform the following steps:

1. **Adding the `Labels`.** Drag `Labels` from the **Library** window's **Controls** section into the first four rows of the `GridPane`'s left column (i.e., column 0). As you add each `Label`, set its text as shown Fig. 25.10.
2. **Adding the `TextFields`.** Drag `TextFields` from the **Library** window's **Controls** section into rows 0, 2 and 3 of the `GridPane`'s right column (i.e., column 1).
3. **Adding a `Slider`.** Drag a horizontal `Slider` from the **Library** window's **Controls** section into row 1 of the `GridPane`'s right column.
4. **Adding a `Button`.** Drag a `Button` from the **Library** window's **Controls** section into row 4 of the `GridPane`'s right column. You can set the `Button`'s text by double clicking it, or by selecting the `Button`, then setting its `Text` property in the **Inspector** window's **Properties** section.

The `GridPane` should appear as shown in Fig. 25.13.




**Fig. 25.13** | GridPane filled with the **Tip Calculator**'s controls.

#### *Step 4: Right-Aligning GridPane Column 0's Contents*

A GridPane column's contents are left-aligned by default. To right-align the contents of column 0, select it by clicking the tab at the top or bottom of the column, then in the **Inspector**'s **Layout** section, set the **Halignment** (horizontal alignment) property to **RIGHT**.

#### *Step 5: Sizing the GridPane Columns to Fit Their Contents*

By default, Scene Builder sets each GridPane column's width to 100 pixels and each row's height to 30 pixels to ensure that you can easily drag controls into the GridPane's cells. In this app, we sized each column to fit its contents. To do so, select the column 0 by clicking the tab at the top or bottom of the column, then in the **Inspector**'s **Layout** section, set the **Pref Width** property to **USE\_COMPUTED\_SIZE** to indicate that the column's width should be based on the widest child—the **Amount** Label in this case. Repeat this process for column 1. The GridPane should appear as shown in Fig. 25.14.



**Fig. 25.14** | GridPane with columns sized to fit their contents.

#### *Step 6: Sizing the TextFields*


Scene Builder sets each TextField's width to 200 pixels by default. You may size controls as appropriate for each GUI you create. In this app, we do not need the TextFields to be so wide, so we used the preferred width for each TextField, which is somewhat narrower. When setting a property to the same value for several controls, you can select all of them and specify the value once. To select all three TextFields, hold the *Ctrl* (or *Command*) key and click each TextField. Then in the **Inspector**'s **Layout** section, set the **Pref Width** property to **USE\_COMPUTED\_SIZE**. This indicates that each TextField should use its preferred width (as defined by JavaFX). Notice that the GridPane's right column resizes to the TextFields' preferred widths.

**Step 7: Sizing the Button**

By default, Scene Builder sets a Button's width based on its text. For this app, we chose to make the Button the same width as the other controls in the GridPane's right column. To do so, select the Button, then in the **Inspector's Layout** section, set the **Max Width** property to **MAX\_VALUE**. This causes the Button's width to grow to fill the column's width.

**Previewing the GUI**

As you design your GUI, you can preview it by selecting **Preview > Show Preview in Window**. As you can see in Fig. 25.15, there's no space between the Labels in the left column and the controls in the right column. In addition, there's no space around the GridPane, because the Stage is sized to fit the Scene's content. Thus, many of the controls touch or come close to the window's borders. You'll fix these issues in the next step.



**Fig. 25.15** | GridPane with the TextFields and Button resized.

**Step 8: Configuring the GridPane's Padding and Horizontal Gap Between Its Columns**

The space between a node's contents and its top, right, bottom and left edges is known as the **padding**, which separates the contents from the node's edges. Since the GridPane's size determines the size of the Stage's window, the padding in this example also separates the GridPane's children from the window's edges. To set the padding, select the GridPane, then in the **Inspector's Layout** section, set the **Padding** property's four values (**TOP**, **RIGHT**, **BOTTOM** and **LEFT**) to 14—the JavaFX recommended distance between the edge of a control and the edge of a Scene.

You can specify the default amount of space between a GridPane's columns and rows with its **Hgap** (horizontal gap) and **Vgap** (vertical gap) properties, respectively. Because Scene Builder sets each GridPane row's height to 30 pixels—which is greater than the heights of this app's controls—there's already some vertical space between the components. To specify the horizontal gap between the columns, select the GridPane in the **Hierarchy** window, then in the **Inspector's Layout** section, set the **Hgap** property to 8. If you'd like to precisely control the vertical space between components, you can set each row's **Pref Height** property to **USE\_COMPUTED\_SIZE** (as we did for the columns' **Pref Width** property in Step 5), then set the GridPane's **Vgap** property.

**Step 9: Making the tipTextField and totalTextField Uneditable and Not Focusable**

The `tipTextField` and `totalTextField` are used in this app only to display results, not receive text input. For this reason, they should not be interactive. You can type in a TextField only if it's "in focus"—that is, it's the control that the user is interacting with. When

you click an interactive control, it receives the focus. Similarly, when you press the *Tab* key, the focus transfers from the current focusable control to the next one—this occurs in the order the controls were added to the GUI. Interactive controls—such as `TextFields`, `Sliders` and `Buttons`—are focusable by default. Non-interactive controls—like `Labels`—are not focusable.


In this app, the `tipTextField` and `totalTextField` are neither editable nor focusable. To make these changes, select both `TextFields`, then in the **Inspector's Properties** section, uncheck the **Editable** and **Focus Traversable** properties.

### *Step 10: Setting the Slider's Properties*

To complete the GUI, you'll now configure the **Tip Calculator's Slider**. By default, a `Slider`'s range is 0.0 to 100.0 and its initial value is 0.0. This app allows tip percentages from 0 to 30 with a default of 15. To make these changes, select the `Slider`, then in the **Inspector's Properties** section, set the `Slider`'s **Max** property to 30 and the **Value** property to 15. We also set the **Block Increment** property to 5—this is the amount by which the **Value** property increases or decreases when the user clicks between an end of the `Slider` and the `Slider`'s thumb. Save the FXML file by selecting **File > Save**.

### *Previewing the Final Layout*

Select **Preview > Show Preview in Window** to view the final GUI (Fig. 25.16). When we discuss the `TipCalculatorController` class in Section 25.5.5, we'll show how to specify the **Calculate** Button's event handler in the FXML file.



**Fig. 25.16** | Final GUI design previewed in Scene Builder.

## 25.5.4 TipCalculator Class

When you created the **Tip Calculator** app's project, NetBeans created two Java source-code files for you:

- `TipCalculator.java`—This file contains the `TipCalculator` class, in which the `main` method (discussed in this section) loads the FXML file to create the GUI and attaches the GUI to a `Scene` that's displayed on the app's `Stage`.
- `TipCalculatorController.java`—This file contains the `TipCalculatorController` class (discussed in Section 25.5.5), which is where you'll specify the `Slider` and `Button` controls' event handlers.

Figure 25.17 presents class `TipCalculator`. We reformatted the code to meet our conventions. With the exception of line 18, all of the code in this class was generated by Net-

Beans. As we discussed in Section 25.5.2, the `Application` subclass is the starting point for a JavaFX app. The main method calls class `Application`'s static `launch` method (line 26) to begin executing the app. This method, in turn, causes the JavaFX runtime to create an object of the `TipCalculator` class and calls its `start` method.

---

```

1 // Fig. 25.17: TipCalculator.java
2 // Main app class that loads and displays the Tip Calculator's GUI
3 import javafx.application.Application;
4 import javafx.fxml.FXMLLoader;
5 import javafx.scene.Parent;
6 import javafx.scene.Scene;
7 import javafx.stage.Stage;
8
9 public class TipCalculator extends Application
10 {
11 @Override
12 public void start(Stage stage) throws Exception
13 {
14 Parent root =
15 FXMLLoader.load(getClass().getResource("TipCalculator.fxml"));
16
17 Scene scene = new Scene(root); // attach scene graph to scene
18 stage.setTitle("Tip Calculator"); // displayed in window's title bar
19 stage.setScene(scene); // attach scene to stage
20 stage.show(); // display the stage
21 }
22
23 public static void main(String[] args)
24 {
25 // create a TipCalculator object and call its start method
26 launch(args);
27 }
28 }

```

---

**Fig. 25.17** | Main app class that loads and displays the **Tip Calculator**'s GUI.

### ***Overridden `Application` Method `start`***

Method `start` (lines 11–21) creates the GUI, attaches it to a `Scene` and places it on the `Stage` that method `start` receives as an argument. Lines 14–15 use class `FXMLLoader`'s static method `load` to create the GUI's scene graph. This method:

- Returns a `Parent` (package `javafx.scene`) reference to the scene graph's root node (the `GridPane` in this example).
- Creates an object of the controller class.
- Initializes the controller's instance variables for the components that are manipulated programmatically.
- Registers the event handlers for any events specified in the FXML.

We discuss the initialization of the controller's instance variables and the registration of the event handlers in Section 25.5.5.

*Creating the Scene*

To display the GUI, you must attach it to a `Scene`, then attach the `Scene` to the `Stage` that's passed into method `start`. Line 17 creates a `Scene`, passing `root` (the scene graph's root node) as an argument to the constructor. By default, the `Scene`'s size is determined by the size of the scene graph's root node. Overloaded versions of the `Scene` constructor allow you to specify the `Scene`'s size and fill (a color, gradient or image), which appears in the `Scene`'s background. Line 18 uses `Scene` method `setTitle` to specify the text that appears in the `Stage` window's title bar. Line 19 places `Stage` method `setScene` to place the `Scene` onto the `Stage`. Finally, line 20 calls `Stage` method `show` to display the `Stage` window.

**25.5.5 TipCalculatorController Class**

Figures 25.18–25.21 present the `TipCalculatorController` class that responds to user interactions with the app's `Button` and `Slider`. Replace the code that NetBeans generated in `TipCalculatorController.java` with the code in Figs. 25.18–25.21.

*Class TipCalculatorController's import Statements*

Figure 25.18 shows class `TipCalculatorController`'s import statements.

---

```

1 // TipCalculatorController.jav
2 // Controller that handles calculateButton and tipPercentageSlider events
3 import java.math.BigDecimal;
4 import java.math.RoundingMode;
5 import java.text.NumberFormat;
6 import javafx.beans.value.ChangeListener;
7 import javafx.beans.value.ObservableValue;
8 import javafx.event.ActionEvent;
9 import javafx.fxml.FXML;
10 import javafx.scene.control.Label;
11 import javafx.scene.control.Slider;
12 import javafx.scene.control.TextField;
13

```

---

**Fig. 25.18** | `TipCalculatorController`'s import declarations.

Lines 3–12 import the classes and interfaces used by class `TipCalculatorController`:

- Class `BigDecimal` of package `java.math` (line 3) is used to perform precise monetary calculations. The `RoundingMode` enum of package `java.math` (line 4) is used to specify how `BigDecimal` values are rounded during calculations or when formatting floating-point numbers as `Strings`.
- Class `NumberFormat` of package `java.text` (line 5) provides numeric formatting capabilities, such as locale-specific currency and percentage formats. For example, in the U.S. locale, the monetary value 34.56 is formatted as \$34.95 and the percentage 15 is formatted as 15%. Class `NumberFormat` determines the locale of the system on which your app runs, then formats currency amounts and percentages accordingly.
- You implement interface `ChangeListener` of package `javafx.beans.value` (line 6) to respond to the user moving the `Slider`'s thumb. This interface's `changed`



method receives an object that implements interface `ObservableValue` (line 7)—that is, a value that generates an event when it changes.

- A `Button`'s event handler receives an `ActionEvent` (line 8; package `javafx.event`), which indicates that the `Button` was clicked. As you'll see in online Chapter 26, many JavaFX controls support `ActionEvents`.
- The annotation `FXML` (line 9; package `javafx.fxml`) is used in a JavaFX controller class's code to mark instance variables that should refer to JavaFX components in the GUI's FXML file and methods that can respond to the events of JavaFX components in the GUI's FXML file.
- Package `javafx.scene.control` (lines 10–12) contains many JavaFX control classes, including `Label`, `Slider` and `TextField`.

As you write code with various classes and interfaces, you can use the the NetBeans IDE's **Source > Organize Imports** command to let the IDE insert the `import` statements for you. If the same class or interface name appears in more than one package, the IDE will display a dialog in which you can select the appropriate `import` statement.

### *TipCalculatorController's static Variables and Instance Variables*

Lines 17–38 of Fig. 25.19 present class `TipCalculatorController`'s static and instance variables. The `NumberFormat` objects (lines 17–20) are used to format currency values and percentages, respectively. Method `getCurrencyInstance` returns a `NumberFormat` object that formats values as currency using the default locale for the system on which the app is running. Similarly, method `getPercentInstance` returns a `NumberFormat` object that formats values as percentages using the system's default locale. The `BigDecimal` object `tipPercentage` (line 22) stores the current tip percentage and is used in the tip calculation (Fig. 25.20) when the user clicks the app's **Calculate** Button.

---

```

14 public class TipCalculatorController
15 {
16 // formatters for currency and percentages
17 private static final NumberFormat currency =
18 NumberFormat.getCurrencyInstance();
19 private static final NumberFormat percent =
20 NumberFormat.getPercentInstance();
21
22 private BigDecimal tipPercentage = new BigDecimal(0.15); // 15% default
23
24 // GUI controls defined in FXML and used by the controller's code
25 @FXML
26 private TextField amountTextField;
27
28 @FXML
29 private Label tipPercentageLabel;
30
31 @FXML
32 private Slider tipPercentageSlider;
33

```

---

**Fig. 25.19** | `TipCalculatorController`'s static variables and instance variables. (Part I of 2.)

---

```

34 @FXML
35 private TextField tipTextField;
36
37 @FXML
38 private TextField totalTextField;
39

```

---

**Fig. 25.19** | TipCalculatorController's static variables and instance variables. (Part 2 of 2.)

#### *@FXML Annotation*

Recall from Section 25.5.3 that each control that this app manipulates in its Java source code needs an **fx:id**. Lines 25–38 (Fig. 25.19) declare the controller class's corresponding instance variables. The **@FXML annotation** that precedes each declaration (lines 25, 28, 31, 34 and 37) indicates that the variable name can be used in the FXML file that describes the app's GUI. The variable names that you specify in the controller class must precisely match the **fx:id** values you specified when building the GUI. When the FXMLLoader loads TipCalculator.fxml to create the GUI, it also initializes each of the controller's instance variables that are declared with @FXML to ensure that they refer to the corresponding GUI components in the FXML file.

#### *TipCalculatorController's calculateButtonPressed Event Handler*

Figure 25.20 presents class TipCalculatorController's calculateButtonPressed method, which is called with the user clicks the **Calculate** Button. The @FXML annotation (line 41) preceding the method indicates that this method can be used to specify a control's event handler in the FXML file that describes the app's GUI. For a control that generates an **ActionEvent** (as is the case for many JavaFX controls), the event-handling method must return **void** and receive one **ActionEvent** parameter (line 42).

---

```

40 // calculates and displays the tip and total amounts
41 @FXML
42 private void calculateButtonPressed(ActionEvent event)
43 {
44 try
45 {
46 BigDecimal amount = new BigDecimal(amountTextField.getText());
47 BigDecimal tip = amount.multiply(tipPercentage);
48 BigDecimal total = amount.add(tip);
49
50 tipTextField.setText(currency.format(tip));
51 totalTextField.setText(currency.format(total));
52 }
53 catch (NumberFormatException ex)
54 {
55 amountTextField.setText("Enter amount");
56 amountTextField.selectAll();
57 amountTextField.requestFocus();
58 }
59 }
60

```

---

**Fig. 25.20** | TipCalculatorController's calculateButtonPressed event handler.

### *Specifying the Calculate Button's Event Handler in Scene Builder*

When you created the TipCalculator project with NetBeans, it preconfigured the class TipCalculatorController as the controller for the GUI in TipCalculator.fxml. You can see this in Scene Builder by selecting the scene's root node (i.e., the GridPane), then expanding the **Inspector** window's **Code** section. The controller class's name is specified in the **Controller class** field. If you declare the method calculateButtonPressed in the controller class before specifying the **Calculate** Button's event handler in the FXML, when you open Scene Builder it scans the controller class for methods prefixed with @FXML and allows you to select from those methods to configure event handlers.

To indicate that calculateButtonPressed should be called when the user clicks the **Calculate** Button, open TipCalculator.fxml in Scene Builder, then:

1. Select the **Calculate** Button.
2. In the **Inspector** window, expand the **Code** section.
3. Under **On Action**, select #calculateButtonPressed from the drop-down list and save the FXML file.

When the FXMLLoader loads TipCalculator.fxml to create the GUI, it creates and registers an event handler for the **Calculate** Button's **ActionEvent**. An **ActionEvent**'s handler is an object of a class that implements the **EventHandler<ActionEvent>** interface, which contains a **handle** method that returns **void** and receives an **ActionEvent** parameter. This method, in turn, calls method **calculateButtonPressed** when the user clicks the **Calculate** Button. The FXMLLoader performs similar tasks for every event listener you specified via the **Inspector** window's **Code** section.

### *Calculating and Displaying the Tip and Total Amounts*

Lines 46–51 calculate and display the tip and total amounts. Line 46 calls method **getText** to get from the **amountTextField** the bill amount typed by the user. This **String** is passed to the **BigDecimal** constructor, which throws a **NumberFormatException** if its argument is not a number. In that case, line 55 calls **amountTextField**'s **setText** method to display the message "Enter amount" in the **TextField**. Line 56 then calls method **selectAll** to select the **TextField**'s text and line 57 calls **requestFocus**, which gives the **TextField** the focus. This allows the user to immediately type a new value in the **amountTextField** without having to first select its text. Methods **getText**, **setText** and **selectAll** are inherited into class **TextField** from class **TextInputControl** (package **javafx.scene.control**), and method **requestFocus** is inherited into class **TextField** from class **Node** (package **javafx.scene**).

If line 46 does not throw an exception, line 47 calculates the tip by calling method **multiply** to multiply the amount by the **tipPercentage**, and line 48 calculates the total by calling method **add** to add the tip to the bill amount. Next lines 50 and 51 use the currency object's **format** method to create currency-formatted **Strings** representing the tip and total amounts—these are displayed in **tipTextField** and **totalTextField**, respectively.

### *TipCalculatorController's initialize Method*

Figure 25.21 presents class TipCalculatorController's **initialize** method. When the FXMLLoader creates an object of class TipCalculatorController, it determines whether the class contains an **initialize** method with no parameters and, if so, calls that method

to initialize the controller. This method can be used to configure the controller before the GUI is displayed. Line 65 calls the currency object's `setRoundingMode` method to specify how currency values should be rounded. The value `RoundingMode.HALF_UP` indicates that values greater than or equal to .5 should round up—for example, 34.567 would be formatted as 34.57 and 34.564 would be formatted as 34.56.

---

```

61 // called by FXMLLoader to initialize the controller
62 public void initialize()
63 {
64 // 0-4 rounds down, 5-9 rounds up
65 currency.setRoundingMode(RoundingMode.HALF_UP);
66
67 // listener for changes to tipPercentageSlider's value
68 tipPercentageSlider.valueProperty().addListener(
69 new ChangeListener<Number>()
70 {
71 @Override
72 public void changed(ObservableValue<? extends Number> ov,
73 Number oldValue, Number newValue)
74 {
75 tipPercentage =
76 BigDecimal.valueOf(newValue.intValue() / 100.0);
77 tipPercentageLabel.setText(percent.format(tipPercentage));
78 }
79 }
80);
81 }
82 }

```

---

**Fig. 25.21** | TipCalculatorController's initialize method.

### *Using an Anonymous Inner Class for Event Handling*

Each JavaFX control has various properties, some of which—such as a `Slider`'s value—can notify an event listener when they change. For such properties, you must manually register as the event handler an object of a class that implements the `ChangeListener` interface from package `javafx.beans.value`. If such an event handler is not reused, you'd typically define it as an instance of an **anonymous inner class**—a class that's declared without a name and typically appears inside a method declaration. Lines 68–80 are one statement that declares the event listener's class, creates an object of that class and registers it as the listener for changes to the `tipPercentageSlider`'s value.

The call to method `valueProperty` (line 68) returns an object of class `DoubleProperty` (package `javafx.beans.property`) that represents the `Slider`'s value. A `DoubleProperty` is an `ObservableValue` that can notify listeners when the value changes. Each class that implements interface `ObservableValue` provides method `addListener` (called on line 68) for registering a `ChangeListener`. In the case of a `Slider`'s value, `addListener`'s argument is an object that implements `ChangeListener<Number>`, because the `Slider`'s value is a numeric value.

Since an anonymous inner class has no name, one object of the class must be created at the point where the class is declared (starting at line 69). Method `addListener`'s argument is defined in lines 69–79 as a class-instance creation expression that declares an anon-

ymous inner class and creates one object of that class. A reference to that object is then passed to `addListener`. After the new keyword, the syntax `ChangeListener<Number>()` (line 69) begins the declaration of an anonymous inner class that implements interface `ChangeListener<Number>`. This is similar to beginning a class declaration with

```
public class MyHandler implements ChangeListener<Number>
```

The opening left brace at 70 and the closing right brace at line 79 delimit the body of the anonymous inner class. Lines 71–78 declare the `ChangeListener<Number>`'s `changed` method, which receives a reference to the `ObservableValue` that changed, a `Number` containing the `Slider`'s old value before the event occurred and a `Number` containing the `Slider`'s new value. When the user moves the `Slider`'s thumb, lines 75–76 store the new tip percentage and line 77 updates the `tipPercentageLabel`.

An anonymous inner class can access its top-level class's instance variables, static variables and methods—in this case, the anonymous inner class uses instance variables `tipPercentage` and `tipPercentageLabel`, and static variable `percent`. However, an anonymous inner class has limited access to the local variables of the method in which it's declared—it can access only the `final` local variables declared in the enclosing method's body. (As of Java SE 8, an anonymous inner class may also access a class's effectively `final` local variables—see Section 17.3.1 for more information.)

### *Java SE 8: Using a Lambda to Implement the `ChangeListener`*

Recall from Section 10.10 that in Java SE 8 an interface containing one method is a functional interface and recall from Chapter 17 that such interfaces may be implemented with lambdas. Section 17.9 showed how to implement an event-handling functional interface using a lambda. The event handler in Fig. 25.21 can be implemented with a lambda as follows:

```
tipPercentageSlider.valueProperty().addListener(
 (ov, oldValue, newValue) ->
 {
 tipPercentage =
 BigDecimal.valueOf(newValue.intValue() / 100.0);
 tipPercentageLabel.setText(percent.format(tipPercentage));
 });
```

## 25.6 Features Covered in the Online JavaFX Chapters

JavaFX is a robust GUI, graphics and multimedia technology. In the online Chapters 26 and 27, you'll:

- Learn additional JavaFX layouts and controls.
- Handle other event types (such as `MouseEvents`).
- Apply transformations (such as moving, rotating, scaling and skewing) and effects (such as drop shadows, blurs, reflection and lighting) to a scene graph's nodes.
- Use CSS to specify the look-and-feel of controls.
- Use JavaFX properties and data binding to enable automatic updating of controls as corresponding data changes.
- Use JavaFX graphics capabilities.

- Perform JavaFX animations.
- Use JavaFX multimedia capabilities to play audio and video.

In addition, our JavaFX Resource Center

<http://www.deitel.com/JavaFX>

contains links to online resources where you can learn more about JavaFX's capabilities.

## 25.7 Wrap-Up

In this chapter, we introduced JavaFX. We presented the structure of a JavaFX stage (the application window). You learned that the stage displays a scene's scene graph, that the scene graph is composed of nodes and that nodes consist of layouts and controls.

You designed GUIs using visual programming techniques in JavaFX Scene Builder, which enabled you to create GUIs without writing any Java code. You arranged `Label`, `ImageView`, `TextField`, `Slider` and `Button` controls using the `VBox` and `GridPane` layout containers. You learned how class `FXMLLoader` uses the FXML created in Scene Builder to create the GUI.

You implemented a controller class to respond to user interactions with `Button` and `Slider` controls. We showed that certain event handlers can be specified directly in FXML from Scene Builder, but event handlers for changes to a control's property values must be implemented directly in the controllers code. You also learned that the `FXMLLoader` creates and initializes an instance of an application's controller class, initializes the controller's instance variables that are declared with the `@FXML` annotation, and creates and registers event handlers for any events specified in the FXML.

In the next chapter, you'll use additional JavaFX controls and layouts and use CSS to style your GUI. You'll also learn more about JavaFX properties and how to use a technique called data binding to automatically update elements in a GUI with new data.

---

## Summary

### *Section 25.1 Introduction*

- A graphical user interface (GUI) presents a user-friendly mechanism for interacting with an app. A GUI (pronounced "GOO-ee") gives an app a distinctive "look-and-feel."
- GUIs are built from GUI components—sometimes called controls or widgets.
- Providing different apps with consistent, intuitive user-interface components gives users a sense of familiarity with a new app, so that they can learn it more quickly and use it more productively.
- Java's GUI, graphics and multimedia API of the future is JavaFX.

### *Section 25.2 JavaFX Scene Builder and the NetBeans IDE*

- JavaFX Scene Builder is a standalone JavaFX GUI visual layout tool that can also be used with various IDEs.
- JavaFX Scene Builder enables you to create GUIs by dragging and dropping GUI components from Scene Builder's library onto a design area, then modifying and styling the GUI—all without writing any code.
- JavaFX Scene Builder generates FXML (FX Markup Language)—an XML vocabulary for defining and arranging JavaFX GUI controls without writing any Java code.

- The FXML code is separate from the program logic that's defined in Java source code—this separation of the interface (the GUI) from the implementation (the Java code) makes it easier to debug, modify and maintain JavaFX GUI apps.

### *Section 25.3 JavaFX App Window Structure*

- The window in which a JavaFX app's GUI is displayed is known as the stage and is an instance of class `Stage` (package `javafx.stage`).
- The stage contains one scene that defines the GUI as a scene graph—a tree structure of an app's visual elements, such as GUI controls, shapes, images, video, text and more. The scene is an instance of class `Scene` (package `javafx.scene`).
- Each visual element in the scene graph is a node—an instance of a subclass of `Node` (package `javafx.scene`), which defines common attributes and behaviors for all nodes in the scene graph.
- The first node in the scene graph is known as the root node.
- Nodes that have children are typically layout containers that arrange their child nodes in the scene.
- The nodes arranged in a layout container are a combination of controls and possibly other layout containers.
- When the user interacts with a control, it generates an event. Programs can use event handling to specify what should happen when each user interaction occurs.
- An event handler is a method that responds to a user interaction. An FXML GUI's event handlers are defined in a controller class.

### *Section 25.4 Welcome App—Displaying Text and an Image*

- To create an app in NetBeans, you must first create a project—a group of related files, such as code files and images that make up an app.
- The NetBeans **Projects** window provides access to all of your projects. Within a project's node, the contents are organized into folders and files.
- NetBeans creates three files for a JavaFX FXML Application project: an FXML markup file for the GUI, a file containing the app's main class and a file containing the app's controller class.
- To open a project's FXML file in JavaFX Scene Builder, right click the FXML file in the **Projects** window, then select **Open**.
- Layout containers help you arrange GUI components. A `VBox` arranges its nodes vertically from top to bottom.
- To make a layout container the root node in a scene graph, select the layout container, then select Scene Builder's **Edit > Trim Document to Selection** menu item.
- A `VBox`'s alignment determines the layout positioning of its children.
- The preferred size (width and height) of the scene graph's root node is used by the scene to determine its window size when the app begins executing.
- You can set a `Label`'s text either by double clicking it and typing the text, or by selecting the `Label` and setting its `Text` property in the **Inspector's Properties** section.
- When adding controls to a `VBox`, each new control is placed below the preceding ones by default. You can change the order by dragging the children in **Scene Builder's Hierarchy** window.
- To set the image to display, select the `ImageView` then set its `Image` property in the **Inspector's Properties** section. An image's aspect ratio is the ratio of the image's width to its height.
- To specify an `ImageView`'s size, set its `Fit Width` and `Fit Height` properties in the **Inspector's Layout** section.

### Section 25.5.2 Technologies Overview

- A JavaFX app's main class inherits from `Application` (package `javafx.application`).
- The main class's `main` method calls class `Application`'s static `launch` method to begin executing a JavaFX app. This method, in turn, causes the JavaFX runtime to create an object of the `Application` subclass and call its `start` method, which creates the GUI, attaches it to a `Scene` and places it on the `Stage` that method `start` receives as an argument.
- A `GridPane` (package `javafx.scene.layout`) arranges JavaFX nodes into columns and rows in a rectangular grid.
- Each cell in a `GridPane` can be empty or can hold one or more JavaFX components, including layout containers that arrange other controls.
- Each component in a `GridPane` can span multiple columns or rows.
- A `TextField` (package `javafx.scene.control`) can accept text input or display text.
- A `Slider` (package `javafx.scene.control`) represents a value in the range 0.0–100.0 by default and allows the user to select a number in that range by moving the `Slider`'s thumb.
- A `Button` (package `javafx.scene.control`) allows the user to initiate an action.
- Class `NumberFormat` (package `java.text`) can format locale-specific currency and percentage strings.
- GUIs are event driven. When the user interacts with a GUI component, the interaction—known as an event—drives the program to perform a task.
- The code that performs a task in response to an event is called an event handler.
- For certain events you can link a control to its event-handling method by using the **Code** section of Scene Builder's **Inspector** window. In this case, the class that implements the event-listener interface will be created for you and will call the method you specify.
- For events that occur when the value of a control's property changes, you must create the event handler entirely in code.
- You implement the `ChangeListener` interface (package `javafx.beans.value`) to respond to the user moving the `Slider`'s thumb.
- JavaFX applications in which the GUI is implemented as FXML adhere to the Model-View-Controller (MVC) design pattern, which separates an app's data (contained in the model) from the app's GUI (the view) and the app's processing logic (the controller). The controller implements logic for processing user inputs. The view presents the data stored in the model. When a user provides input, the controller modifies the model with the given input. When the model changes, the controller updates the view to present the changed data. In a simple app, the model and controller are often combined into a single class.
- In a JavaFX FXML app, you define the app's event handlers in a controller class. The controller class defines instance variables for interacting with controls programmatically, as well as event-handling methods.
- Class `FXMLLoader`'s static method `load` uses the FXML file that represents the app's GUI to create the GUI's scene graph and returns a `Parent` (package `javafx.scene`) reference to the scene graph's root node. It also initializes the controller's instance variables, and creates and registers the event handlers for any events specified in the FXML.

### Section 25.5.3 Building the App's GUI

- If a control or layout will be manipulated programmatically in the controller class, you must provide a name for that control or layout. Each object's name is specified via its `fx:id` property. You can set this property's value by selecting a component in your scene, then expanding the **Inspector** window's **Code** section—the `fx:id` property appears at the top.



- By default, the `GridPane` contains two columns and three rows. You can add a row above or below an existing row by right clicking a row and selecting **Grid Pane > Add Row Above** or **Grid Pane > Add Row Below**. You can delete a row or column by right clicking the tab containing its row or column number and selecting **Delete**.
- You can set a `Button`'s text by double clicking it, or by selecting the `Button`, then setting its **Text** property in the **Inspector** window's **Properties** section.
- A `GridPane` column's contents are left-aligned by default. To change the alignment, select the column by clicking the tab at the top or bottom of the column, then in the **Inspector**'s **Layout** section, set the **Alignment** property.
- Setting a node's **Pref Width** property of a `GridPane` column to `USE_COMPUTED_SIZE` indicates that the width should be based on the widest child.
- To size a `Button` the same width as the other controls in a `GridPane`'s column, select the `Button`, then in the **Inspector**'s **Layout** section, set the **Max Width** property to `MAX_VALUE`.
- As you design your GUI, you can preview it in Scene Builder by selecting **Preview > Show Preview in Window**.
- The space between a node's contents and its top, right, bottom and left edges is known as the padding, which separates the contents from the node's edges. To set the padding, select the node, then in the **Inspector**'s **Layout** section, set the **Padding** property's values.
- You can specify the default amount of space between a `GridPane`'s columns and rows with its **Hgap** (horizontal gap) and **Vgap** (vertical gap) properties, respectively.
- You can type in a `TextField` only if it's "in focus"—that is, it's the control that the user is interacting with. When you click an interactive control, it receives the focus. Similarly, when you press the *Tab* key, the focus transfers from the current focusable control to the next one—this occurs in the order the controls were added to the GUI.

#### Section 25.5.4 *TipCalculator Class*

- To display a GUI, you must attach it to a `Scene`, then attach the `Scene` to the `Stage` that's passed into `Application` method `start`.
- By default, the `Scene`'s size is determined by the size of the scene graph's root node. Overloaded versions of the `Scene` constructor allow you to specify the `Scene`'s size and fill (a color, gradient or image), which appears in the `c`'s background.
- `Scene` method `setTitle` specifies the text that appears in the `Stage` window's title bar.
- `Stage` method `setScene` places a `Scene` onto a `Stage`.
- `Stage` method `show` displays the `Stage` window.

#### Section 25.5.5 *TipCalculatorController Class*

- The `RoundingMode` enum of package `java.math` is used to specify how `BigDecimal` values are rounded during calculations or when formatting floating-point numbers as `Strings`.
- Class `NumberFormat` of package `java.text` provides numeric formatting capabilities, such as locale-specific currency and percentage formats.
- A `Button`'s event handler receives an `ActionEvent`, which indicates that the `Button` was clicked. Many JavaFX controls support `ActionEvents`.
- Package `javafx.scene.control` contains many JavaFX control classes.
- The `@FXML` annotation preceding an instance variable indicates that the variable's name can be used in the FXML file that describes the app's GUI. The variable names that you specify in the controller class must precisely match the `fx:id` values you specified when building the GUI.

- When the `FXMLLoader` loads an FXML file to create a GUI, it also initializes each of the controller's instance variables that are declared with `@FXML` to ensure that they refer to the corresponding GUI components in the FXML file.
- The `@FXML` annotation preceding a method indicates that the method can be used to specify a control's event handler in the FXML file that describes the app's GUI.
- When the `FXMLLoader` creates an object of a controller class, it determines whether the class contains an `initialize` method with no parameters and, if so, calls that method to initialize the controller. This method can be used to configure the controller before the GUI is displayed.
- An anonymous inner class is a class that's declared without a name and typically appears inside a method declaration.
- Since an anonymous inner class has no name, one object of the class must be created at the point where the class is declared.
- An anonymous inner class can access its top-level class's instance variables, static variables and methods, but has limited access to the local variables of the method in which it's declared—it can access only the `final` local variables declared in the enclosing method's body. (As of Java SE 8, an anonymous inner class may also access a class's effectively `final` local variables.)

## Self-Review Exercises

- 25.1** Fill in the blanks in each of the following statements:
- A(n) \_\_\_\_\_ can display text and accept text input from the user.
  - Use a(n) \_\_\_\_\_ to arrange GUI components into cells in a rectangular grid.
  - JavaFX Scene Builder's \_\_\_\_\_ window shows the structure of the GUI and allows you to select and reorganize controls.
  - You implement interface \_\_\_\_\_ to respond to events when the user moves a `Slider`'s thumb.
  - A(n) \_\_\_\_\_ represents the app's window.
  - The method \_\_\_\_\_ is called by the `FXMLLoader` before the GUI is displayed.
  - The contents of a scene are placed in its \_\_\_\_\_.
  - The elements in the scene graph are called \_\_\_\_\_.
  - \_\_\_\_\_ allows you to build JavaFX GUIs using drag-and-drop techniques.
  - A(n) \_\_\_\_\_ file contains the description of a JavaFX GUI.
- 25.2** State whether each of the following is *true* or *false*. If *false*, explain why.
- You must create JavaFX GUIs by hand coding them in Java.
  - The layout `VBox` arranges components vertically in a scene.
  - To right align controls in a `GridPane` column, set its **Alignment** property to `RIGHT`.
  - The `FXMLLoader` initializes the controller's `@FXML` instance variables.
  - You override class `Application`'s `launch` method to display a JavaFX app's stage.
  - The control that the user is interacting with "has the focus."
  - By default, a `Slider` allows you to select values from 0 to 255.
  - A node can span multiple columns in a `GridPane`.
  - Every `Application` subclass must override the `start` method.

## Answers to Self-Review Exercises

- 25.1** a) `TextField`. b) `GridPane`. c) **Hierarchy**. d) `ChangeListener<Number>`. e) Stage. f) `initialize`. g) scene graph. h) nodes. i) JavaFX Scene Builder. j) FXML.
- 25.2** a) False. You can use JavaFX Scene Builder to create JavaFX GUIs without writing any code. b) True. c) False. The name of the property is **Alignment**. d) True. e) False. You override class

Application's start method to display a JavaFX app's stage. f) True. g) False. By default a `Slider` allows you to select values from 0.0 to 100.0. h) True. i) True.

## Exercises

**25.3** (*Scrapbooking App*) Find four images of famous landmarks using websites such as Flickr. Create an app similar to the **Welcome** app in which you arrange the images in a collage. Add text that identifies each landmark. You can use images that are part of your project or you can specify the URL of an image that's online.

**25.4** (*Enhanced Tip Calculator App*) Modify the **Tip Calculator** app to allow the user to enter the number of people in the party. Calculate and display the amount owed by each person if the bill were to be split evenly among the party members.

**25.5** (*Mortgage Calculator App*) Create a mortgage calculator app that allows the user to enter a purchase price, down-payment amount and an interest rate. Based on these values, the app should calculate the loan amount (purchase price minus down payment) and display the monthly payment for 10-, 20- and 30-year loans. Allow the user to select a custom loan duration (in years) by using a `Slider` and display the monthly payment for that custom loan duration.

**25.6** (*College Loan Payoff Calculator App*) A bank offers college loans that can be repaid in 5, 10, 15, 20, 25 or 30 years. Write an app that allows the user to enter the amount of the loan and the annual interest rate. Based on these values, the app should display the loan lengths in years and their corresponding monthly payments.

**25.7** (*Car Payment Calculator App*) Typically, banks offer car loans for periods ranging from two to five years (24 to 60 months). Borrowers repay the loans in monthly installments. The amount of each monthly payment is based on the length of the loan, the amount borrowed and the interest rate. Create an app that allows the customer to enter the price of a car, the down-payment amount and the loan's annual interest rate. The app should display the loan's duration in months and the monthly payments for two-, three-, four- and five-year loans. The variety of options allows the user to easily compare repayment plans and choose the most appropriate.

**25.8** (*Miles-Per-Gallon Calculator App*) Drivers often want to know the miles per gallon their cars get so they can estimate gasoline costs. Develop an app that allows the user to input the number of miles driven and the number of gallons used and calculates and displays the corresponding miles per gallon.

## Making a Difference

**25.9** (*Body Mass Index Calculator App*) The formulas for calculating the BMI are

$$BMI = \frac{weightInPounds \times 703}{heightInInches \times heightInInches}$$

or

$$BMI = \frac{weightInKilograms}{heightInMeters \times heightInMeters}$$

Create a BMI calculator app that allows users to enter their weight and height and whether they are entering these values in English or metric units, then calculates and displays the user's body mass index. The app should also display the following information from the Department of Health and Human Services/National Institutes of Health so that users can evaluate their BMIs:

### BMI VALUES

|              |                       |
|--------------|-----------------------|
| Underweight: | less than 18.5        |
| Normal:      | between 18.5 and 24.9 |
| Overweight:  | between 25 and 29.9   |
| Obese:       | 30 or greater         |

**25.10** (*Target-Heart-Rate Calculator App*) While exercising, you can use a heart-rate monitor to see that your heart rate stays within a safe range suggested by your trainers and doctors. According to the American Heart Association (AHA), the formula for calculating your *maximum heart rate* in beats per minute is *220 minus your age in years* (<http://bit.ly/AHATargetHeartRates>). Your *target heart rate* is a range that is 50–85% of your maximum heart rate. [*Note:* These formulas are estimates provided by the AHA. Maximum and target heart rates may vary based on the health, fitness and gender of the individual. Always consult a physician or qualified health care professional before beginning or modifying an exercise program.] Write an app that inputs the person's age, then calculates and displays the person's maximum heart rate and target-heart-rate range.




# Chapters on the Web

The following chapters are available at *Java How to Program, 10/e, Late Objects Version's* Companion Website ([www.pearsonhighered.com/deitel](http://www.pearsonhighered.com/deitel)) as PDF documents:

- Chapter 26, JavaFX GUI: Part 2
- Chapter 27, JavaFX Graphics and Multimedia
- Chapter 28, Networking
- Chapter 29, Java Persistence API (JPA)
- Chapter 30, JavaServer™ Faces Web Apps: Part 1
- Chapter 31, JavaServer™ Faces Web Apps: Part 2
- Chapter 32, REST-Based Web Services
- Chapter 33, (Optional) ATM Case Study, Part 1: Object-Oriented Design with the UML
- Chapter 34, (Optional) ATM Case Study, Part 2: Implementing an Object-Oriented Design

These files can be viewed in Adobe® Reader® ([get.adobe.com/reader](http://get.adobe.com/reader)).

*This page intentionally left blank*



# Operator Precedence Chart

Operators are shown in decreasing order of precedence from top to bottom (Fig. A.1).


| Operator                               | Description                                                                                                                                       | Associativity |
|----------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------|---------------|
| ++<br>--                               | unary postfix increment<br>unary postfix decrement                                                                                                | right to left |
| ++<br>--<br>+<br>-<br>!<br>~<br>(type) | unary prefix increment<br>unary prefix decrement<br>unary plus<br>unary minus<br>unary logical negation<br>unary bitwise complement<br>unary cast | right to left |
| *<br>/<br>%                            | multiplication<br>division<br>remainder                                                                                                           | left to right |
| +<br>-                                 | addition or string concatenation<br>subtraction                                                                                                   | left to right |
| <<<br>>><br>>>>                        | left shift<br>signed right shift<br>unsigned right shift                                                                                          | left to right |
| <<br><=<br>><br>>=<br>instanceof       | less than<br>less than or equal to<br>greater than<br>greater than or equal to<br>type comparison                                                 | left to right |
| ==<br>!=                               | is equal to<br>is not equal to                                                                                                                    | left to right |
| &                                      | bitwise AND<br>boolean logical AND                                                                                                                | left to right |
| ^                                      | bitwise exclusive OR<br>boolean logical exclusive OR                                                                                              | left to right |

**Fig. A.1** | Operator precedence chart. (Part I of 2.)

| Operator | Description                                          | Associativity |
|----------|------------------------------------------------------|---------------|
|          | bitwise inclusive OR<br>boolean logical inclusive OR | left to right |
| &&       | conditional AND                                      | left to right |
|          | conditional OR                                       | left to right |
| ?:       | conditional                                          | right to left |
| =        | assignment                                           | right to left |
| +=       | addition assignment                                  |               |
| -=       | subtraction assignment                               |               |
| *=       | multiplication assignment                            |               |
| /=       | division assignment                                  |               |
| %=       | division assignment                                  |               |
| &=       | remainder assignment                                 |               |
| ^=       | bitwise AND assignment                               |               |
| =        | bitwise exclusive OR assignment                      |               |
| <<=      | bitwise inclusive OR assignment                      |               |
| >>=      | bitwise left-shift assignment                        |               |
| >>>=     | bitwise signed-right-shift assignment                |               |
|          | bitwise unsigned-right-shift assignment              |               |

**Fig. A.1** | Operator precedence chart. (Part 2 of 2.)





# ASCII Character Set

|    | 0   | 1   | 2   | 3   | 4   | 5   | 6   | 7   | 8   | 9   |
|----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|
| 0  | nul | soh | stx | etx | eot | enq | ack | bel | bs  | ht  |
| 1  | n1  | vt  | ff  | cr  | so  | si  | d1e | dc1 | dc2 | dc3 |
| 2  | dc4 | nak | syn | etb | can | em  | sub | esc | fs  | gs  |
| 3  | rs  | us  | sp  | !   | "   | #   | \$  | %   | &   | '   |
| 4  | (   | )   | *   | +   | ,   | -   | .   | /   | 0   | 1   |
| 5  | 2   | 3   | 4   | 5   | 6   | 7   | 8   | 9   | :   | ;   |
| 6  | <   | =   | >   | ?   | @   | A   | B   | C   | D   | E   |
| 7  | F   | G   | H   | I   | J   | K   | L   | M   | N   | O   |
| 8  | P   | Q   | R   | S   | T   | U   | V   | W   | X   | Y   |
| 9  | Z   | [   | \   | ]   | ^   | _   | '   | a   | b   | c   |
| 10 | d   | e   | f   | g   | h   | i   | j   | k   | l   | m   |
| 11 | n   | o   | p   | q   | r   | s   | t   | u   | v   | w   |
| 12 | x   | y   | z   | {   |     | }   | ~   | del |     |     |

**Fig. B.1** | ASCII character set.

The digits at the left of the table are the left digits of the decimal equivalents (0–127) of the character codes, and the digits at the top of the table are the right digits of the character codes. For example, the character code for “F” is 70, and the character code for “&” is 38.

Most users of this book are interested in the ASCII character set used to represent English characters on many computers. The ASCII character set is a subset of the Unicode character set used by Java to represent characters from most of the world’s languages. For more information on the Unicode character set, see the web bonus Appendix H.

# C



## Keywords and Reserved Words

| Java Keywords                               |            |         |            |              |
|---------------------------------------------|------------|---------|------------|--------------|
| abstract                                    | assert     | boolean | break      | byte         |
| case                                        | catch      | char    | class      | continue     |
| default                                     | do         | double  | else       | enum         |
| extends                                     | final      | finally | float      | for          |
| if                                          | implements | import  | instanceof | int          |
| interface                                   | long       | native  | new        | package      |
| private                                     | protected  | public  | return     | short        |
| static                                      | strictfp   | super   | switch     | synchronized |
| this                                        | throw      | throws  | transient  | try          |
| void                                        | volatile   | while   |            |              |
| <i>Keywords that are not currently used</i> |            |         |            |              |
| const                                       | goto       |         |            |              |

**Fig. C.1** | Java keywords.

Java also contains the reserved words `true` and `false`, which are boolean literals, and `null`, which is the literal that represents a reference to nothing. Like keywords, these reserved words cannot be used as identifiers.



# D

## Primitive Types

| Type                                                                                         | Size in bits | Values                                                                                                                                                                                               | Standard                    |
|----------------------------------------------------------------------------------------------|--------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------|
| boolean                                                                                      |              | true or false                                                                                                                                                                                        |                             |
| [Note: A boolean's representation is specific to the Java Virtual Machine on each platform.] |              |                                                                                                                                                                                                      |                             |
| char                                                                                         | 16           | '\u0000' to '\uFFFF' (0 to 65535)                                                                                                                                                                    | (ISO Unicode character set) |
| byte                                                                                         | 8            | $-128$ to $+127$ ( $-2^7$ to $2^7 - 1$ )                                                                                                                                                             |                             |
| short                                                                                        | 16           | $-32,768$ to $+32,767$ ( $-2^{15}$ to $2^{15} - 1$ )                                                                                                                                                 |                             |
| int                                                                                          | 32           | $-2,147,483,648$ to $+2,147,483,647$ ( $-2^{31}$ to $2^{31} - 1$ )                                                                                                                                   |                             |
| long                                                                                         | 64           | $-9,223,372,036,854,775,808$ to $+9,223,372,036,854,775,807$ ( $-2^{63}$ to $2^{63} - 1$ )                                                                                                           |                             |
| float                                                                                        | 32           | <i>Negative range:</i><br>$-3.4028234663852886\text{E}+38$ to $-1.40129846432481707\text{e}-45$<br><i>Positive range:</i><br>$1.40129846432481707\text{e}-45$ to $3.4028234663852886\text{E}+38$     | (IEEE 754 floating point)   |
| double                                                                                       | 64           | <i>Negative range:</i><br>$-1.7976931348623157\text{E}+308$ to $-4.94065645841246544\text{e}-324$<br><i>Positive range:</i><br>$4.94065645841246544\text{e}-324$ to $1.7976931348623157\text{E}+308$ | (IEEE 754 floating point)   |

**Fig. D.1** | Java primitive types.

You can use underscores to make numeric literal values more readable. For example, `1_000_000` is equivalent to `1000000`.

For more information on IEEE 754 visit <http://grouper.ieee.org/groups/754/>.  
For more information on Unicode, see Appendix H.

# E

## Using the Debugger

*And so shall I catch the fly.*

—William Shakespeare

*We are built to make mistakes,  
coded for error.*

—Lewis Thomas

*What we anticipate seldom  
occurs; what we least expect  
generally happens.*

—Benjamin Disraeli

### Objectives

In this appendix you'll learn:

- To set breakpoints to debug applications.
- To use the `run` command to run an application through the debugger.
- To use the `stop` command to set a breakpoint.
- To use the `cont` command to continue execution.
- To use the `print` command to evaluate expressions.
- To use the `set` command to change variable values during program execution.
- To use the `step`, `step up` and `next` commands to control execution.
- To use the `watch` command to see how a field is modified during program execution.
- To use the `clear` command to list breakpoints or remove a breakpoint.



|                                                                                                                            |                                           |
|----------------------------------------------------------------------------------------------------------------------------|-------------------------------------------|
| <b>E.1</b> Introduction                                                                                                    | <b>E.5</b> The <code>watch</code> Command |
| <b>E.2</b> Breakpoints and the <code>run</code> , <code>stop</code> ,<br><code>cont</code> and <code>print</code> Commands | <b>E.6</b> The <code>clear</code> Command |
| <b>E.3</b> The <code>print</code> and <code>set</code> Commands                                                            | <b>E.7</b> Wrap-Up                        |
| <b>E.4</b> Controlling Execution Using the<br><code>step</code> , <code>step up</code> and <code>next</code><br>Commands   |                                           |

## E.1 Introduction

In Chapter 2, you learned that there are two types of errors—syntax errors and logic errors—and you learned how to eliminate syntax errors from your code. Logic errors do not prevent the application from compiling successfully, but they do cause an application to produce erroneous results when it runs. The JDK includes software called a **debugger** that allows you to monitor the execution of your applications so you can locate and remove logic errors. The debugger will be one of your most important application development tools. Many IDEs provide their own debuggers similar to the one included in the JDK or provide a graphical user interface to the JDK's debugger.

This appendix demonstrates key features of the JDK's debugger using command-line applications that receive no input from the user. The same debugger features discussed here can be used to debug applications that take user input, but debugging such applications requires a slightly more complex setup. To focus on the debugger features, we've opted to demonstrate the debugger with simple command-line applications involving no user input. For more information on the Java debugger visit <http://docs.oracle.com/javase/7/docs/technotes/tools/windows/jdb.html>.

## E.2 Breakpoints and the `run`, `stop`, `cont` and `print` Commands

We begin our study of the debugger by investigating **breakpoints**, which are markers that can be set at any executable line of code. When application execution reaches a breakpoint, execution pauses, allowing you to examine the values of variables to help determine whether logic errors exist. For example, you can examine the value of a variable that stores the result of a calculation to determine whether the calculation was performed correctly. Setting a breakpoint at a line of code that is not executable (such as a comment) causes the debugger to display an error message.

To illustrate the features of the debugger, we use application `AccountTest` (Fig. E.1), which creates and manipulates an object of class `Account` (Fig. 7.8). Execution of `AccountTest` begins in `main` (lines 7–24). Line 9 creates an `Account` object with an initial balance of \$50.00. Recall that `Account`'s constructor accepts one argument, which specifies the `Account`'s initial balance. Lines 12–13 output the initial account balance using `Account` method `getBalance`. Line 15 declares and initializes a local variable `depositAmount`. Lines 17–19 then print `depositAmount` and add it to the `Account`'s balance using

its `credit` method. Finally, lines 22–23 display the new balance. [Note: The Appendix E examples directory contains a copy of `Account.java` identical to the one in Fig. 7.8.]

---

```

1 // Fig. E.1: AccountTest.java
2 // Create and manipulate an Account object.
3
4 public class AccountTest
5 {
6 // main method begins execution
7 public static void main(String[] args)
8 {
9 Account account = new Account("Jane Green", 50.00);
10
11 // display initial balance of Account object
12 System.out.printf("initial account balance: %.2f%n",
13 account.getBalance());
14
15 double depositAmount = 25.0; // deposit amount
16
17 System.out.printf("%nadding %.2f to account balance%n%n",
18 depositAmount);
19 account.deposit(depositAmount); // add to account balance
20
21 // display new balance
22 System.out.printf("new account balance: %.2f%n",
23 account.getBalance());
24 }
25 } // end class AccountTest

```

```

initial account balance: $50.00

adding 25.00 to account balance

new account balance: $75.00

```

**Fig. E.1** | Create and manipulate an Account object.

In the following steps, you'll use breakpoints and various debugger commands to examine the value of the variable `depositAmount` declared in `AccountTest` (Fig. E.1).

1. *Opening the Command Prompt window and changing directories.* Open the **Command Prompt** window by selecting **Start > Programs > Accessories > Command Prompt**. Change to the directory containing the Appendix E examples by typing `cd C:\examples\debugger` [Note: If your examples are in a different directory, use that directory here.]
2. *Compiling the application for debugging.* The Java debugger works only with `.class` files that were compiled with the `-g` compiler option, which generates information that is used by the debugger to help you debug your applications. Compile the application with the `-g` command-line option by typing `javac -g AccountTest.java Account.java`. This command compiles both `Account-`

Test.java and Account.java. The command `java -g *.java` compiles all of the working directory's .java files for debugging.

3. *Starting the debugger.* In the **Command Prompt**, type **jdb** (Fig. E.2). This command will start the Java debugger and enable you to use its features. [Note: We modified the colors of our **Command Prompt** window for readability.]

```
C:\examples\debugger>javac -g AccountTest.java Account.java

C:\examples\debugger>jdb
Initializing jdb ...
>
```

**Fig. E.2** | Starting the Java debugger.

4. *Running an application in the debugger.* Run the AccountTest application through the debugger by typing **run AccountTest** (Fig. E.3). If you do not set any breakpoints before running your application in the debugger, the application will run just as it would using the java command.

```
C:\examples\debugger>jdb
Initializing jdb ...
> run AccountTest
run AccountTest
Set uncaught java.lang.Throwable
Set deferred uncaught java.lang.Throwable
>
VM Started: initial account balance: $50.00

adding 25.00 to account balance

new account balance: $75.00

The application exited
```

**Fig. E.3** | Running the AccountTest application through the debugger.

5. *Restarting the debugger.* To make proper use of the debugger, you must set at least one breakpoint before running the application. Restart the debugger by typing **jdb**.
6. *Inserting breakpoints in Java.* You set a breakpoint at a specific line of code in your application. The line numbers used in these steps are from the source code in Fig. E.1. Set a breakpoint at line 12 in the source code by typing **stop at AccountTest:12** (Fig. E.4). The **stop command** inserts a breakpoint at the line number specified after the command. You can set as many breakpoints as necessary. Set another breakpoint at line 19 by typing **stop at AccountTest:19** (Fig. E.4). When the application runs, it suspends execution at any line that contains a break-

point. The application is said to be in **break mode** when the debugger pauses the application's execution. Breakpoints can be set even after the debugging process has begun. The debugger command `stop in`, followed by a class name, a period and a method name (e.g., `stop in Account.credit`) instructs the debugger to set a breakpoint at the first executable statement in the specified method. The debugger pauses execution when program control enters the method.

```
C:\examples\debugger>jdb
Initializing jdb ...
> stop at AccountTest:12
Deferring breakpoint AccountTest:12.
It will be set after the class is loaded.
> stop at AccountTest:19
Deferring breakpoint AccountTest:19.
It will be set after the class is loaded.
>
```

**Fig. E.4** | Setting breakpoints at lines 12 and 19.

7. *Running the application and beginning the debugging process.* Type `run AccountTest` to execute the application and begin the debugging process (Fig. E.5). The debugger prints text indicating that breakpoints were set at lines 12 and 19. It calls each breakpoint a “deferred breakpoint” because each was set before the application began running in the debugger. The application pauses when execution reaches the breakpoint on line 12. At this point, the debugger notifies you that a breakpoint has been reached and it displays the source code at that line (12). That line of code is the next statement that will execute.

```
It will be set after the class is loaded.
>run AccountTest
run AccountTest
Set uncaught java.lang.Throwable
Set deferred uncaught java.lang.Throwable
>
VM Started: Set deferred breakpoint AccountTest:19
Set deferred breakpoint AccountTest:12

Breakpoint hit: "thread=main", AccountTest.main(), line=12 bci=13
12 System.out.printf("initial account balance: $%.2f%n",
main[1]
```

**Fig. E.5** | Restarting the AccountTest application.

8. *Using the **cont** command to resume execution.* Type `cont`. The **cont** command causes the application to continue running until the next breakpoint is reached (line 19), at which point the debugger notifies you (Fig. E.6). AccountTest's normal output appears between messages from the debugger.



```

main[1] cont
> initial account balance: $50.00

adding 25.00 to account balance

Breakpoint hit: "thread=main", AccountTest.main(), line=19 bci=60
19 account.deposit(depositAmount); // add to account balance

main[1]

```

**Fig. E.6** | Execution reaches the second breakpoint.

9. *Examining a variable's value.* Type `print depositAmount` to display the current value stored in the `depositAmount` variable (Fig. E.7). The **print command** allows you to peek inside the computer at the value of one of your variables. This command will help you find and eliminate logic errors in your code. The value displayed is 25.0—the value assigned to `depositAmount` in line 15 of Fig. E.1.

```

main[1] print depositAmount
depositAmount = 25.0
main[1]

```

**Fig. E.7** | Examining the value of variable `depositAmount`.

10. *Continuing application execution.* Type `cont` to continue the application's execution. There are no more breakpoints, so the application is no longer in break mode. The application continues executing and eventually terminates (Fig. E.8). The debugger will stop when the application ends.

```

main[1] cont
> new account balance: $75.00

The application exited

```

**Fig. E.8** | Continuing application execution and exiting the debugger.

## E.3 The print and set Commands

In the preceding section, you learned how to use the debugger's `print` command to examine the value of a variable during program execution. In this section, you'll learn how to use the `print` command to examine the value of more complex expressions. You'll also learn the **set command**, which allows the programmer to assign new values to variables.

For this section, we assume that you've followed *Step 1* and *Step 2* in Section E.2 to open the **Command Prompt** window, change to the directory containing the Appendix E

examples (e.g., C:\examples\debugger) and compile the AccountTest application (and class Account) for debugging.

1. *Starting debugging.* In the **Command Prompt**, type `jdb` to start the Java debugger.
2. *Inserting a breakpoint.* Set a breakpoint at line 19 in the source code by typing `stop at AccountTest:19`.
3. *Running the application and reaching a breakpoint.* Type `run AccountTest` to begin the debugging process (Fig. E.9). This will cause AccountTest's `main` to execute until the breakpoint at line 19 is reached. This suspends application execution and switches the application into break mode. At this point, the statements in lines 9–13 created an Account object and printed the initial balance of the Account obtained by calling its `getBalance` method. The statement in line 15 (Fig. E.1) declared and initialized local variable `depositAmount` to 25.0. The statement in line 19 is the next statement that will execute.

```
C:\examples\debugger>jdb
Initializing jdb ...
> stop at AccountTest:19
Deferring breakpoint AccountTest:19.
It will be set after the class is loaded.
> run AccountTest
run AccountTest
Set uncaught java.lang.Throwable
Set deferred uncaught java.lang.Throwable
>
VM Started: Set deferred breakpoint AccountTest:19
initial account balance: $50.00

adding 25.00 to account balance

Breakpoint hit: "thread=main", AccountTest.main(), line=19 bci=60
19 account.deposit(depositAmount); // add to account balance

main[1]
```

**Fig. E.9** | Application execution suspended when debugger reaches the breakpoint at line 19.

4. *Evaluating arithmetic and boolean expressions.* Recall from Section E.2 that once the application has entered break mode, you can explore the values of the application's variables using the debugger's `print` command. You can also use the `print` command to evaluate arithmetic and boolean expressions. In the **Command Prompt** window, type `print depositAmount - 2.0`. The `print` command returns the value 23.0 (Fig. E.10). However, this command does not actually change the value of `depositAmount`. In the **Command Prompt** window, type `print depositAmount == 23.0`. Expressions containing the `==` symbol are treated as boolean expressions. The value returned is `false` (Fig. E.10) because `depositAmount` does not currently contain the value 23.0—`depositAmount` is still 25.0.

```
main[1] print depositAmount - 2.0
depositAmount - 2.0 = 23.0
main[1] print depositAmount == 23.0
depositAmount == 23.0 = false
main[1]
```

**Fig. E.10** | Examining the values of an arithmetic and boolean expression.

5. *Modifying values.* The debugger allows you to change the values of variables during the application's execution. This can be valuable for experimenting with different values and for locating logic errors in applications. You can use the debugger's `set` command to change the value of a variable. Type `set depositAmount = 75.0`. The debugger changes the value of `depositAmount` and displays its new value (Fig. E.11).

```
main[1] set depositAmount = 75.0
depositAmount = 75.0 = 75.0
main[1]
```

**Fig. E.11** | Modifying values.

6. *Viewing the application result.* Type `cont` to continue application execution. Line 19 of `AccountTest` (Fig. E.1) executes, passing `depositAmount` to `Account` method `credit`. Method `main` then displays the new balance. The result is \$125.00 (Fig. E.12). This shows that the preceding step changed the value of `depositAmount` from its initial value (25.0) to 75.0.

```
main[1] cont
> new account balance: $125.00

The application exited

C:\examples\debugger>
```

**Fig. E.12** | Output showing new account balance based on altered value of `depositAmount`.

## E.4 Controlling Execution Using the `step`, `step up` and `next` Commands

Sometimes you'll need to execute an application line by line to find and fix errors. Walking through a portion of your application this way can help you verify that a method's code executes correctly. In this section, you'll learn how to use the debugger for this task. The commands you learn in this section allow you to execute a method line by line, execute all the statements of a method at once or execute only the remaining statements of a method (if you've already executed some statements within the method).

Once again, we assume you're working in the directory containing the Appendix E examples and have compiled for debugging with the `-g` compiler option.

1. *Starting the debugger.* Start the debugger by typing `jdb`.
2. *Setting a breakpoint.* Type `stop at AccountTest:19` to set a breakpoint at line 19.
3. *Running the application.* Run the application by typing `run AccountTest`. After the application displays its two output messages, the debugger indicates that the breakpoint has been reached and displays the code at line 19. The debugger and application then pause and wait for the next command to be entered.
4. *Using the **step** command.* The **step** command executes the next statement in the application. If the next statement to execute is a method call, control transfers to the called method. The **step** command enables you to enter a method and study the individual statements of that method. For instance, you can use the `print` and `set` commands to view and modify the variables within the method. You'll now use the **step** command to enter the `credit` method of class `Account` (Fig. 7.8) by typing `step` (Fig. E.13). The debugger indicates that the step has been completed and displays the next executable statement—in this case, line 21 of class `Account` (Fig. 7.8).

```
main[1] step
>
Step completed: "thread=main", Account.deposit(), line=24 bci=0
24 if (depositAmount > 0.0) // if the depositAmount is valid

main[1]
```

**Fig. E.13** | Stepping into the `credit` method.

5. *Using the **step up** command.* After you've stepped into the `credit` method, type **step up**. This command executes the remaining statements in the method and returns control to the place where the method was called. The `credit` method contains only one statement to add the method's parameter `amount` to instance variable `balance`. The **step up** command executes this statement, then pauses before line 22 in `AccountTest`. Thus, the next action to occur will be to print the new account balance (Fig. E.14). In lengthy methods, you may want to look at a few key lines of code, then continue debugging the caller's code. The **step up** command is useful for situations in which you do not want to continue stepping through the entire method line by line.

```
main[1] step up
>
Step completed: "thread=main", AccountTest.main(), line=22 bci=65
22 System.out.printf("new account balance: %.2f%n",

main[1]
```

**Fig. E.14** | Stepping out of a method.

6. *Using the `cont` command to continue execution.* Enter the `cont` command (Fig. E.15) to continue execution. The statement at lines 22–23 executes, displaying the new balance, then the application and the debugger terminate.

```
main[1] cont
> new account balance: $75.00

The application exited

C:\examples\debugger>
```

**Fig. E.15** | Continuing execution of the `AccountTest` application.

7. *Restarting the debugger.* Restart the debugger by typing `jdb`.
8. *Setting a breakpoint.* Breakpoints persist only until the end of the debugging session in which they're set—once the debugger exits, all breakpoints are removed. (In Section E.6, you'll learn how to manually clear a breakpoint before the end of the debugging session.) Thus, the breakpoint set for line 19 in *Step 2* no longer exists upon restarting the debugger in *Step 7*. To reset the breakpoint at line 19, once again type `stop` at `AccountTest:19`.
9. *Running the application.* Type `run` `AccountTest` to run the application. As in *Step 3*, `AccountTest` runs until the breakpoint at line 19 is reached, then the debugger pauses and waits for the next command.
10. *Using the `next` command.* Type `next`. This command behaves like the `step` command, except when the next statement to execute contains a method call. In that case, the called method executes in its entirety and the application advances to the next executable line after the method call (Fig. E.16). Recall from *Step 4* that the `step` command would enter the called method. In this example, the `next` command causes `Account` method `credit` to execute, then the debugger pauses at line 22 in `AccountTest`.

```
main[1] next
>
Step completed: "thread=main", AccountTest.main(), line=22 bci=65
22 System.out.printf("new account balance: %.2f%n",
main[1]
```

**Fig. E.16** | Stepping over a method call.

11. *Using the `exit` command.* Use the `exit` command to end the debugging session (Fig. E.17). This command causes the `AccountTest` application to immediately terminate rather than execute the remaining statements in `main`. When debugging some types of applications (e.g., GUI applications), the application continues to execute even after the debugging session ends.

```
main[1] exit
C:\examples\debugger>
```

**Fig. E.17** | Exiting the debugger.

## E.5 The watch Command

In this section, we present the **watch command**, which tells the debugger to watch a field. When that field is about to change, the debugger will notify you. In this section, you'll learn how to use the watch command to see how the Account object's field balance is modified during the execution of the AccountTest application.

As in the preceding two sections, we assume that you've followed *Step 1* and *Step 2* in Section E.2 to open the **Command Prompt**, change to the correct examples directory and compile classes AccountTest and Account for debugging (i.e., with the -g compiler option).

1. *Starting the debugger.* Start the debugger by typing `jdb`.
2. *Watching a class's field.* Set a watch on Account's balance field by typing `watch Account.balance` (Fig. E.18). You can set a watch on any field during execution of the debugger. Whenever the value in a field is about to change, the debugger enters break mode and notifies you that the value will change. Watches can be placed only on fields, not on local variables.

```
C:\examples\debugger>jdb
Initializing jdb ...
> watch Account.balance
Deferring watch modification of Account.balance.
It will be set after the class is loaded.
>
```

**Fig. E.18** | Setting a watch on Account's balance field.

3. *Running the application.* Run the application with the command `run AccountTest`. The debugger will now notify you that field balance's value will change (Fig. E.19). When the application begins, an instance of Account is created with an initial balance of \$50.00 and a reference to the Account object is assigned to the local variable `account` (line 9, Fig. E.1). Recall from Fig. 7.8 that when the constructor for this object runs, if parameter `initialBalance` is greater than 0.0, instance variable `balance` is assigned the value of parameter `initialBalance`. The debugger notifies you that the value of `balance` will be set to 50.0.
4. *Adding money to the account.* Type `cont` to continue executing the application. The application executes normally before reaching the code on line 19 of Fig. E.1 that calls Account method `credit` to raise the Account object's balance by a specified amount. The debugger notifies you that instance variable `balance` will change (Fig. E.20). Although line 19 of class AccountTest calls method `deposit`, line 25 in Account's method `deposit` actually changes the value of `balance`.

```
> run AccountTest
run AccountTest
Set uncaught java.lang.Throwable
Set deferred uncaught java.lang.Throwable
>
VM Started: Set deferred watch modification of Account.balance

Field (Account.balance) is 0.0, will be 50.0: "thread=main", Account.<init>(),
line=18 bci=17
18 this.balance = balance; // assign to instance variable balance

main[1]
```

**Fig. E.19** | AccountTest application stops when account is created and its balance field will be modified.

```
main[1] cont
> initial account balance: $50.00

adding 25.00 to account balance
Field (Account.balance) is 50.0, will be 75.0: "thread=main",
Account.deposit(), line=25 bci=13

25 balance = balance + depositAmount; // add it to the balance

main[1]
```

**Fig. E.20** | Changing the value of balance by calling Account method credit.

5. *Continuing execution.* Type `cont`—the application will finish executing because the application does not attempt any additional changes to balance (Fig. E.21).

```
main[1] cont
> new account balance: $75.00

The application exited

C:\examples\debugger>
```

**Fig. E.21** | Continuing execution of AccountTest.

6. *Restarting the debugger and resetting the watch on the variable.* Type `jdb` to restart the debugger. Once again, set a watch on the Account instance variable balance by typing the watch `Account.balance`, then type `run AccountTest` to run the application.
7. *Removing the watch on the field.* Suppose you want to watch a field for only part of a program's execution. You can remove the debugger's watch on variable balance by typing `unwatch Account.balance` (Fig. E.22). Type `cont`—the application will finish executing without reentering break mode.

```

main[1] unwatch Account.balance
Removed: watch modification of Account.balance
main[1] cont
> initial account balance: $50.00

adding 25.00 to account balance

new account balance: $75.00

The application exited

C:\examples\debugger>

```

**Fig. E.22** | Removing the watch on variable balance.

## E.6 The clear Command

In the preceding section, you learned to use the `unwatch` command to remove a watch on a field. The debugger also provides the `clear` command to remove a breakpoint from an application. You'll often need to debug applications containing repetitive actions, such as a loop. You may want to examine the values of variables during several, but possibly not all, of the loop's iterations. If you set a breakpoint in the body of a loop, the debugger will pause before each execution of the line containing a breakpoint. After determining that the loop is working properly, you may want to remove the breakpoint and allow the remaining iterations to proceed normally. In this section, we use the compound interest application in Fig. 4.6 to demonstrate how the debugger behaves when you set a breakpoint in the body of a `for` statement and how to remove a breakpoint in the middle of a debugging session.

1. *Opening the Command Prompt window, changing directories and compiling the application for debugging.* Open the **Command Prompt** window, then change to the directory containing the Appendix E examples. For your convenience, we've provided a copy of the `Interest.java` file in this directory. Compile the application for debugging by typing `javac -g Interest.java`.
2. *Starting the debugger and setting breakpoints.* Start the debugger by typing `jdb`. Set breakpoints at lines 13 and 22 of class `Interest` by typing `stop at Interest:13`, then `stop at Interest:22`.
3. *Running the application.* Run the application by typing `run Interest`. The application executes until reaching the breakpoint at line 13 (Fig. E.23).
4. *Continuing execution.* Type `cont` to continue—the application executes line 13, printing the column headings "Year" and "Amount on deposit". Line 13 appears before the `for` statement at lines 16–23 in `Interest` (Fig. 4.6) and thus executes only once. Execution continues past line 13 until the breakpoint at line 22 is reached during the first iteration of the `for` statement (Fig. E.24).
5. *Examining variable values.* Type `print year` to examine the current value of variable `year` (i.e., the `for`'s control variable). Print the value of variable `amount` too (Fig. E.25).



```

It will be set after the class is loaded.
> run Interest
run Interest
Set uncaught java.lang.Throwable
Set deferred uncaught java.lang.Throwable
>
VM Started: Set deferred breakpoint Interest:22
Set deferred breakpoint Interest:13

Breakpoint hit: "thread=main", Interest.main(), line=13 bci=9
13 System.out.printf("%s%20s%n", "Year", "Amount on deposit");

main[1]

```

**Fig. E.23** | Reaching the breakpoint at line 13 in the Interest application.

```

main[1] cont
> Year Amount on deposit
Breakpoint hit: "thread=main", Interest.main(), line=22 bci=55
22 System.out.printf("%4d%,20.2f%n", year, amount);

main[1]

```

**Fig. E.24** | Reaching the breakpoint at line 22 in the Interest application.

```

main[1] print year
year = 1
main[1] print amount
amount = 1050.0
main[1]

```

**Fig. E.25** | Printing year and amount during the first iteration of Interest's for.

6. *Continuing execution.* Type `cont` to continue execution. Line 22 executes and prints the current values of `year` and `amount`. After the `for` enters its second iteration, the debugger notifies you that the breakpoint at line 22 has been reached a second time. The debugger pauses each time a line where a breakpoint has been set is about to execute—when the breakpoint appears in a loop, the debugger pauses during each iteration. Print the values of variables `year` and `amount` again to see how the values have changed since the first iteration of the `for` (Fig. E.26).

```

main[1] cont
> 1 1,050.00
Breakpoint hit: "thread=main", Interest.main(), line=22 bci=55
22 System.out.printf("%4d%,20.2f%n", year, amount);

main[1] print amount
amount = 1102.5
main[1] print year
year = 2
main[1]

```

**Fig. E.26** | Printing year and amount during the second iteration of Interest's for.

7. *Removing a breakpoint.* You can display a list of all of the breakpoints in the application by typing **clear** (Fig. E.27). Suppose you're satisfied that the `Interest` application's `for` statement is working properly, so you want to remove the breakpoint at line 22 and allow the remaining iterations of the loop to proceed normally. You can remove the breakpoint at line 22 by typing `clear Interest:22`. Now type `clear` to list the remaining breakpoints in the application. The debugger should indicate that only the breakpoint at line 13 remains (Fig. E.27). This breakpoint has already been reached and thus will no longer affect execution.

```
main[1] clear
Breakpoints set:
 breakpoint Interest:13
 breakpoint Interest:22
main[1] clear Interest:22
Removed: breakpoint Interest:22
main[1] clear
Breakpoints set:
 breakpoint Interest:13
main[1]
```

**Fig. E.27** | Removing the breakpoint at line 22.

8. *Continuing execution after removing a breakpoint.* Type `cont` to continue execution. Recall that execution last paused before the `printf` statement in line 22. If the breakpoint at line 22 was removed successfully, continuing the application will produce the correct output for the current and remaining iterations of the `for` statement without the application halting (Fig. E.28).

```
main[1] cont
> 2 1,102.50
 3 1,157.63
 4 1,215.51
 5 1,276.28
 6 1,340.10
 7 1,407.10
 8 1,477.46
 9 1,551.33
 10 1,628.89

The application exited

C:\examples\debugger>
```

**Fig. E.28** | Application executes without a breakpoint set at line 22.

## E.7 Wrap-Up

In this appendix, you learned how to insert and remove breakpoints in the debugger. Breakpoints allow you to pause application execution so you can examine variable values

with the debugger's `print` command. This capability will help you locate and fix logic errors in your applications. You saw how to use the `print` command to examine the value of an expression and how to use the `set` command to change the value of a variable. You also learned debugger commands (including the `step`, `step up` and `next` commands) that can be used to determine whether a method is executing correctly. You learned how to use the `watch` command to keep track of a field throughout the life of an application. Finally, you learned how to use the `clear` command to list all the breakpoints set for an application or remove individual breakpoints to continue execution without breakpoints.

*This page intentionally left blank*



# Appendices on the Web

The following appendices are available at Java How to Program, 9/e's Companion Website ([www.pearsonhighered.com/deitel](http://www.pearsonhighered.com/deitel)) as PDF documents:

- Appendix F, Using the Java API Documentation
- Appendix G, Creating Documentation with javadoc
- Appendix H, Unicode<sup>®</sup>
- Appendix I, Formatted Output
- Appendix J, Number Systems
- Appendix K, Bit Manipulation
- Appendix L, Labeled break and continue Statements
- Appendix M, UML 2: Additional Diagram Types
- Appendix N, Design Patterns

These files can be viewed in Adobe<sup>®</sup> Reader<sup>®</sup> ([get.adobe.com/reader](http://get.adobe.com/reader)).

*This page intentionally left blank*



# Index

## Symbols

$\Lambda$ , boolean logical exclusive OR 142, **144**  
truth table 144  
\_ SQL wildcard character **1045**, 1046  
, (comma) formatting flag **131**  
-- , predecrement/postdecrement **100**  
-, subtraction 51, 52  
!, logical NOT 142, **144**  
truth table 145  
!=, not equals 54  
? (wildcard type argument) **854**  
?:, ternary conditional operator **81**, 102  
. dot separator 271  
{, left brace 37, 38  
, right brace 37  
@Override annotation **361**  
\* SQL wildcard character **1044**  
\* wildcard in a file name 272  
\*, multiplication 51, 52  
\*=, multiplication assignment operator 100  
/, division 51, 52  
/\* \*/ traditional comment **36**  
/\*\* \*/ Java documentation comment **36**  
//, end-of-line comment **36**  
/=, division assignment operator 100  
\, backslash escape sequence 43  
\", double-quote escape sequence 43  
\\n, newline escape sequence 43  
\\r, carriage-return escape sequence 43  
\\t, horizontal tab escape sequence 43  
&, boolean logical AND 142, **144**  
&&, conditional AND 142, **143**  
truth table 142  
% SQL wildcard character **1045**  
%, remainder 51, 52  
%=, remainder assignment operator 100  
%b format specifier **145**  
%c format specifier 69  
%d format specifier **49**  
%f format specifier **69**, **282**  
%s format specifier **44**  
- (minus sign) formatting flag **130**  
+, addition 51, 52  
++, preincrement/postincrement **100**  
+ =, addition assignment operator **99**  
+=, string concatenation assignment operator 604  
<, less than 55  
<=, less than or equal 55  
<> (diamond notation in generics) **683**  
<> diamond notation for generic type inference (Java SE 7) **683**  
=, assignment operator 48  
-=, subtraction assignment operator 100

== to determine whether two references refer to the same object 379  
==, is equal to 54  
-> (arrow token in a lambda) **725**  
>, greater than 55  
>=, greater than or equal to 55  
|, boolean logical inclusive OR 142, **144**  
||, conditional OR 142, **143**  
truth table 143

## Numerics

0 flag **219**  
0 format flag 310

## A

abbreviating assignment expressions 99  
abs method of Math 168  
absolute method of ResultSet **1065**  
absolute path **639**, 641  
absolute value 168  
abstract class 389, **393**, 394, 395, 414  
abstract implementation 714  
abstract keyword **394**  
abstract method **394**, 396, 398, 485, 1138  
abstract superclass **393**  
Abstract Window Toolkit (AWT) **471**, 1100  
Abstract Window Toolkit Event package **176**  
AbstractButton class **487**, 490, 910, 915  
addActionListener method 490  
addItemListener method **493**  
isSelected method **917**  
setMnemonic method **915**  
setRolloverIcon method **490**  
setSelected method **916**  
AbstractCollection class **714**  
AbstractList class **714**  
AbstractMap class **714**  
AbstractQueue class **714**  
AbstractSequentialList class **714**  
AbstractSet class **714**  
AbstractTableModel class **1060**, 1066  
fireTableStructureChanged method **1066**  
accelerometer 5  
accept method of functional interface Consumer (Java SE 8) 743  
accept method of interface BiConsumer (Java SE 8) 747  
accept method of interface IntConsumer (Java SE 8) **730**  
access modifier **268**  
private **268**, 313, 356  
protected 313, **356**  
public **268**, 313, 356  
access modifier in the UML - (private) 273  
access shared data 976  
accessibility 472  
accessibility heuristic 254  
accessor method **323**  
Accounts Payable System Modification exercise 432  
accounts receivable file 674  
accumulator register 258, 261  
acquire a lock 960  
acquire the lock **960**  
action 77, 82  
action expression in the UML **75**  
action key **517**  
action state in the UML **75**, 149  
action state symbol **75**  
action to execute **73**  
ActionEvent class **481**, 482, 486, 533  
getActionCommand method **482**, 490  
ActionEvent class (JavaFX) 1121, 1123  
ActionListener interface **481**, 486  
actionPerformed method 481, 485, 526, 533  
actionPerformed method of interface ActionListener 481, 485, 526, 533  
activation record **174**  
activity diagram **75**, 78, 127, 149  
do...while statement 133  
for statement 127  
if statement 77  
if...else statement 78  
in the UML 82  
sequence statement 75  
switch statement 139  
while statement 83  
activity in the UML **75**  
actual type arguments **836**  
acyclic gradient **576**  
Ada Lovelace 16  
Ada programming language 16  
adapter class **510**  
Adapter Classes used to implement event handlers 514  
add method  
ArrayList<T> **240**  
BigInteger **776**  
ButtonGroup **496**  
JFrame 382, **475**  
JFrame class **106**  
JMenu **915**

- add method (cont.)
  - JMenuBar **916**
  - LinkedList<T> **687**
  - List<T> **682, 685**
- add method of class BigDecimal **339**
- add rows or columns to a GridPane **1115**
- addActionListener method
  - of class AbstractButton **490**
  - of class JTextField **481**
- addAll method
  - Collections **688, 698**
  - List **685**
- addFirst method of LinkedList **688**
- Adding Object Serialization to the MyShape Drawing Application (exercise) **675**
- addItemListener method of class AbstractButton **493**
- addition **6, 51, 52**
- addition compound assignment operator, += **99**
- addKeyListener method of class Component **517**
- addLast method of LinkedList **687**
- addListener method of interface ObservableValue **1124**
- addListSelectionListener method of class JList **502**
- addMouseListener method of class Component **510**
- addMouseMotionListener method of class Component **510**
- addPoint method of class Polygon **571, 573**
- addSeparator method of class JMenu **916**
- addTab method of class JTabbedPane **930**
- addTableModelListener method of TableModel **1060**
- addWindowListener method of class Window **909**
- "administrative" section of the computer **6**
- Agile Alliance
  - (www.agilealliance.org) **28**
- Agile Manifesto
  - (www.agilemanifesto.org) **28**
- agile software development **28**
- Airline Reservation System **252**
- Ajax (Asynchronous JavaScript and XML) **27**
- algebraic notation **51**
- algorithm **73, 83, 90, 777**
  - binary search **808**
  - bubble sort **828**
  - bucket sort **828**
  - in Java Collections Framework **688**
  - insertion sort **816**
  - linear search **804**
  - merge sort **819**
  - quicksort **829**
  - recursive binary search **829**
  - recursive linear search **829**
  - selection sort **813**
- alignment in a VBox (JavaFX) **1108**
- Alignment property of a VBox (JavaFX) **1108**
- alpha software **29**
- alphabetizing **592**
- ALU (arithmetic and logic unit) **6**
- Analytical Engine **16**
- anchor field of class GridBagConstraints **935**
- AND (in SQL) **1051, 1052**
- and method of interface Predicate (Java SE 8) **737**
- Android **14**
  - Google Play **15**
  - operating system **13, 14**
  - smartphone **14**
- Android for Programmers: An App-Driven Approach* **15**
- angle brackets (< and >) **835**
- annotation
  - @Override **361**
- anonymous inner class **308, 425, 481, 499, 515, 1124**
- anonymous method (Java SE 8) **725**
- anonymous methods **425**
- Apache Software Foundation **14**
- API (application programming interface) **45, 165**
- API documentation **177**
- append method of class StringBuilder **607**
- application **35**
  - command-line arguments **169**
- Application class (JavaFX) **1111**
  - launch method **1111, 1119**
  - start method **1111, 1119**
- application programming interface (API) **17, 165**
- apply method of functional interface Function (Java SE 8) **739**
- applyAsDouble method of interface ToDoubleFunction (Java SE 8) **749**
- applyAsInt method of interface IntBinaryOperator (Java SE 8) **732**
- applyAsInt method of interface IntUnaryOperator (Java SE 8) **734**
- arc **567**
- arc angle **567**
- arc width and arc height for rounded rectangles **566**
- Arc2D class **548**
  - CHORD constant **577**
  - OPEN constant **577**
  - PIE constant **577**
- Arc2D.Double class **573, 585**
- archive files **877**
- area of a circle **204**
- args parameter **233**
- argument promotion **175**
- argument to a method **39, 172, 272**
- arithmetic and logic unit (ALU) **6**
- arithmetic calculation **51**
- arithmetic compound assignment operators **99**
- arithmetic mean **52**
- arithmetic operators **51**
- arithmetic overflow **87, 443**
- ArithmeticException class **339, 436, 442**
- ARPANET **25**
- array **209, 637**
  - bounds checking **220**
  - ignoring element zero **222**
  - length instance variable **211**
  - pass an array element to a method **225**
  - pass an array to a method **225**
- array-access expression **211**
- array-creation expression **212**
- array initializer **214**
  - for multidimensional array **228**
  - nested **228**
- array of one-dimensional arrays **228, 229**
- ArrayBlockingQueue class **976, 987, 1002**
  - size method **978**
- arraycopy method of class System **235, 237**
- ArrayIndexOutOfBoundsException class **220, 223, 573**
- ArrayList<T> generic class **238, 680, 696**
  - add method **240**
  - clear method **238**
  - contains method **238, 241**
  - get method **240**
  - indexOf method **238**
  - isEmpty method **324**
  - remove method **239, 240**
  - size method **240**
  - toString method **854**
  - trimToSize method **239**
- Arrays class **235**
  - asList method **686, 687**
  - binarySearch method **235**
  - equals method **235**
  - fill method **235, 1012**
  - parallelPrefix method **1019**
  - parallelSetAll method **1019**
  - parallelSort method **1017**
  - parallelSort method (Java SE 8) **737**
  - sort method **235, 737, 809, 1017**
  - stream method (Java SE 8) **735, 736**
  - toString method **623, 806**
- Arrays method parallelSort **238**
- arrow **75**
- arrow key **517**
- arrow token (→) in a lambda **725**
- ascending order **235**
- ASC in SQL **1047, 1048**
- ascent **561**
- ASCII (American Standard Code for Information Interchange) character set **7, 139, 263**
- ASCII character set Appendix **1137**
- asList method of Arrays **686, 687**
- assembler **9**
- assembly language **9**
- assert statement **458, 1138**
- assertion **457**
- AssertionError class **458**
- assign a value to a variable **48**
- Assigning superclass and subclass references to superclass and subclass variables **392**
- assignment operator, = **48, 57**
- assignment operators **99**



assignment statement 48  
 associate  
   left to right 102  
   right to left 94, 102  
 associativity of operators 52, 58, 102  
   left to right 58  
   right to left 52  
 asterisk (\*) SQL wildcard character **1044**  
 asynchronous event **443**  
 atomic operation **966, 1091**  
 attribute  
   in the UML 12, 273  
   of a class 10  
   of an object 12  
 AuthorISBN table of Books database  
   040, 1042  
 authors table of books database 1040  
 auto commit state 1091  
 auto-unboxing **679**  
 autobox an int 839  
 autoboxing 614, **679**, 839  
 AutoCloseable interface 330, **459**,  
   1057  
   close method 459  
 autoincremented **1040**, 1050  
 automatic driver discovery (JDBC 4)  
   **1056**  
 automatic garbage collection 446  
 automatic scrolling 502  
 average 52, 83, 86  
 average method of interface  
   DoubleStream (Java SE 8) 749  
 average method of interface  
   IntStream (Java SE 8) **731**  
 await method of interface Condition  
   **995**, 999  
 awaitTermination method of interface  
   ExecutorService **965**  
 AWT (Abstract Window Toolkit) **471**,  
   1100  
   components 472  
 AWTEvent class 483

## B

Babbage, Charles 16  
 background color 555, 557  
 backing array **686**  
 backslash (\) **43**  
 backtracking **794**  
 bandwidth **26**  
 bar chart 161, 217, 218  
 bar of asterisks 217, 218  
 base case **770**, 776, 777, 782  
 base class **353**  
 base of a number 613  
 baseline of the font 559  
 BasePlusCommissionEmployee class  
   extends CommissionEmployee 405  
 BASIC (Beginner's All-Purpose Symbolic  
   Instruction Code) 16, 862  
 BasicStroke class **548**, 576, 577  
   CAP\_ROUND constant **577**  
   JOIN\_ROUND constant **578**  
 batch file **645**  
 behavior  
   of a class 10  
 beta software 29  
 between method of class Duration  
   **1018**  
 BiConsumer functional interface (Java  
   SE 8) **747**, 754  
   accept method **747**  
 bidirectional iterator **686**  
 big data **8**  
 Big O notation **806**, 812, 816, 819, 825  
 BigDecimal class 95, 132, **338**, 773,  
   1120  
   add method **339**  
   ArithmeticException class 339  
   multiply method **339**  
   ONE constant **339**  
   pow method **339**  
   setScale method 340  
   TEN constant **339**  
   valueOf method **339**  
   ZERO constant **339**  
 BigInteger class **773**, 1004  
   add method **776**  
   compareTo method **774**  
   multiply method **774**  
   ONE constant **774**, 776  
   subtract method **774**, 776  
   ZERO constant **776**  
 binary 206  
 binary digit (bit) **6**  
 binary file **638**  
 binary integer 118  
 binary operator **48**, 51, 144  
 binary search algorithm 696, **808**, 812  
 binary search tree **886**, 890  
 binary tree **862**, 891  
   delete 899  
   search 900  
   sort **891**  
 BinaryOperator functional interface  
   (Java SE 8) 725  
 binarySearch method  
   of Arrays **235**, 237  
   of Collections 688, **696**, 698  
 bit (binary digit) **6**  
 bitwise operators 142  
 Bjarne Stroustrup 16  
 blank line 37, 90  
 block **81**, 93  
 block increment of a JSlider **905**  
 blocked state **953**, 961  
 BlockingQueue interface **976**  
   put method **976**, 977  
   take method **976**, 978  
 body  
   of a class declaration **37**  
   of a loop 82  
   of a method **38**  
   of an if statement 54  
 body mass index (BMI) 33  
 Body Mass Index Calculator exercise 70,  
   1131  
 Bohm, C. 74  
 BOLD constant of class Font **559**, 559  
 book-title capitalization **470**, 487  
 books database 1040  
   table relationships 1043, 1098  
 Boolean class **679**  
 boolean  
   expression **81**, 1146  
   promotions 175  
 boolean logical AND, & 142, **144**  
 boolean logical exclusive OR, ^ 142, **144**  
   truth table 144  
 boolean logical inclusive OR, | **144**  
 boolean primitive type **81**, 1138, 1139,  
   1146  
 border of a JFrame **908**  
 BorderLayout class **382**, **510**, 520, 521,  
   524, 533  
   CENTER constant 382, **510**, 524, 526  
   EAST constant 382, **510**, 524  
   NORTH constant 382, **510**, 524  
   SOUTH constant 382, **510**, 524  
   WEST constant 382, **510**, 524  
 BOTH constant of class  
   GridBagConstraints **936**  
 bounded buffer **987**  
 bounding rectangle **153**, **565**, 567, 905  
 bounds checking **220**  
 Box class **532**, 931, 933  
   createGlue method **934**  
   createHorizontalBox method  
     **533**, 933  
   createHorizontalGlue method  
     **934**  
   createHorizontalStrut method  
     **933**  
   createRigidArea method **934**  
   createVerticalBox method **933**  
   createVerticalGlue method **934**  
   createVerticalStrut method  
     **933**  
   X\_AXIS constant **934**  
   Y\_AXIS constant **934**  
 boxed method of interface IntStream  
   (Java SE 8) **754**  
 boxing 238  
 boxing conversion **679**, 839  
 BoxLayout class **533**, 931  
 BoxLayout layout manager 931  
 braces { and } 80, 93, 125, 134, 214  
   not required 138  
 braille screen reader 472  
 break 1138  
 break mode **1144**  
 break statement **137**, 140, 162  
 breakpoint **1141**  
   inserting 1143, 1146  
   listing 1154  
   removing 1154  
 brightness **557**  
 brittle software **373**  
 browser 59  
 brute force 255, 256  
   Knight's Tour 255  
 bubble sort 828  
   improving performance 828  
 bucket sort 828  
 buffer **666**, **969**  
 buffered I/O **666**  
 BufferedImage class **577**  
   createGraphics method **577**  
   TYPE\_INT\_RGB constant **577**  
 BufferedInputStream class **667**  
 BufferedOutputStream class **666**  
   flush method **666**  
 BufferedReader class **667**  
 BufferedWriter class **667**  
 building block appearance 149

- building blocks 73
- Building Your Own Compiler 862
- Building Your Own Computer 258
- building-block approach to creating
  - programs 11
- bulk operation **679**
- business publications 30
- button **467**, **487**
- Button class (JavaFX) 1117
- button label **487**
- ButtonGroup class **493**, 910, 917
  - add method **496**
- byte 5, 7
- byte-based stream **638**
- Byte class **679**
- byte keyword 1139
- byte primitive type 134, 1138
  - promotions 175
- ByteArrayInputStream class 667
- ByteArrayOutputStream class 667
- bytecode **19**, 40, 862
- bytecode verifier **20**

**C**

- C programming language 16
- C++ 16
- CachedRowSet interface **1072**
  - close method 1074
- calculations 6, 61, 75
- call-by-reference **227**
- call-by-value **227**
- call method of interface Callable **1022**
- Callable interface **1022**
  - call method **1022**
- CallableStatement interface **1090**
- calling method (caller) 166, **171**
- camel case **48**
- camera 15
- Cancel button 61
- cancel1 method of class SwingWorker **1017**
- CANCEL\_OPTION constant of
  - JFileChooser **663**
- CAP\_ROUND constant of class
  - BasicStroke **577**
- capacity method
  - of class StringBuilder **604**
- capacity of a StringBuilder 603
- capturing lambdas **730**
- Car Payment Calculator app exercise
  - 1131
- carbon footprint calculator 33
- card games 284
- Card Shuffling and Dealing 305, 306
  - with Collections method shuffle 692
- Car-Pool Savings Calculator exercise 71
- carriage return 43
- Cascading 1101
- Cascading Style Sheets (CSS) 1101, **1101**
- case keyword **137**, 1138
- case sensitive **37**
  - Java commands 22
- casino 183
- cast
  - downcast **391**
  - operator 69, **94**, 175

- catch
  - a superclass exception 446
  - an exception 438
- catch
  - block **440**, 442, 443, 447, 450, 451
  - clause **440**, 1138
  - keyword **440**
- Catch block **222**
- catch handler
  - multi-catch **441**
- catch-or-declare requirement **445**
- cd to change directories 40
- ceil method of Math 168
- cell in a GridPane 1111
- Celsius 543
  - equivalent of a Fahrenheit temperature 204
- CENTER constant
  - BorderLayout **510**, 524, 526
  - FlowLayout **524**
  - GridBagConstraints **935**
- center mouse button click 513
- centered 522
- central processing unit (CPU) **6**
- chained exception **454**
- change directories 40
- change the default layout (JavaFX Scene Builder) 1107, 1115
- changed method of interface
  - ChangeListener (JavaFX) 1120
- ChangeEvent class **908**
- ChangeListener interface **908**
  - stateChanged method **908**
- ChangeListener interface (JavaFX)
  - 1113**, 1120, 1124
- changing look-and-feel of a Swing-based GUI 924
- char
  - array 591
  - keyword 1138, 1139
  - primitive type **47**, 134
  - promotions 175
- character 7
  - constant **139**
  - literal **589**
  - set 69
- character-based stream **638**
- Character class 589, 612, **679**
  - charValue method **614**
  - digit method **613**
  - forDigit method **613**
  - isDefined method **612**
  - isDigit method **612**
  - isJavaIdentifierPart method **612**
  - isJavaIdentifierStart method **612**
  - isLetter method **612**
  - isLetterOrDigit method **612**
  - isLowerCase method **612**
  - isUpperCase method **612**
  - static conversion methods 613
  - toLowerCase method **613**
  - toUpperCase method **612**
- character set 7
- character string **39**
- CharArrayReader class **668**
- CharArrayWriter class **668**

- charAt method
  - of class String 591
  - of class StringBuilder **606**
- CharSequence interface **623**
- charValue method of class Character **614**
- check protection exercise 631
- checkbox **487**, 493
- checkbox label **493**
- checked exception **444**
- checkerboard pattern 69
- Checking with assert that a value is
  - within range 458
- child node **885**
- child window 904, **925**, 927, 928
- CHORD constant of class Arc2D **577**
- Circles Using Class Ellipse2D.Double
  - exercise 584
- circular buffer **988**
- circumference 69, 584
- class **11**
  - anonymous inner class 308
  - class keyword 268
  - constructor **271**, 276
  - data hiding **275**
  - declaration **37**
  - default constructor **278**
  - file **40**
  - get method 316
  - instance variable **12**
  - name **37**
  - nested class 308
  - set method 316
- class 7
- class-average problem 83, 84, 90, 91
- class cannot extend a final class 412
- Class class 380, **410**, 476, 1065
  - getName method 380, **410**
  - getResource method **476**
- .class file **18**, **40**
  - separate one for every class 314
- class hierarchy **353**, 394
- class instance creation expression **271**, 277, 310
  - diamond notation (<>) **241**
- class keyword **37**, 268, 1138
- class library **354**
- class loader **19**, 476, **877**
- class method **167**
- class name
  - fully qualified 274
- class names
  - came case naming 171, 268
- class variable **168**, **330**
- classwide information **330**
- ClassCastException class 678
- Classes
  - AbstractButton **487**, 490, 910, 915
  - AbstractCollection **714**
  - AbstractList **714**
  - AbstractMap **714**
  - AbstractQueue **714**
  - AbstractSequentialList **714**
  - AbstractSet **714**
  - AbstractTableModel **1060**, 1066
  - ActionEvent **481**, 482, 486, 533
  - ActionEvent (JavaFX) 1121, 1123
  - Application (JavaFX) **1111**

## Classes (cont.)

Arc2D 548  
 Arc2D.Double 573  
 ArithmeticException 339, 436  
 ArrayBlockingQueue 976, 987, 1002  
 ArrayIndexOutOfBoundsException 220, 223  
 ArrayList<T> 238, 240, 241, 680, 681, 696  
 Arrays 235  
 AssertionError 458  
 AWTEvent 483  
 BasicStroke 548, 576, 577  
 BigDecimal 95, 132, 338, 773, 1120  
 BigInteger 773, 1004  
 Boolean 679  
 BorderLayout 510, 520, 521, 524, 533  
 Box 532, 931, 933  
 BoxLayout 533, 931  
 BufferedImage 577  
 BufferedInputStream 667  
 BufferedOutputStream 666  
 BufferedReader 667  
 BufferedWriter 667  
 ButtonGroup 493, 910, 917  
 Byte 679  
 ByteArrayInputStream 667  
 ByteArrayOutputStream 667  
 ChangeEvent 908  
 Character 589, 607, 612, 679  
 CharArrayReader 668  
 CharArrayWriter 668  
 Class 380, 410, 476, 1065  
 Collections 680, 838  
 Collector (Java SE 8) 737  
 Color 192, 548  
 CompletableFuture class 1022  
 Component 472, 505, 550, 551, 909, 940  
 ComponentAdapter 511  
 ComponentListener 521  
 ConcurrentHashMap 1002  
 ConcurrentLinkedDeque 1002  
 ConcurrentSkipListMap 1002  
 ConcurrentSkipListSet 1002  
 Container 472, 503, 521, 529, 530  
 ContainerAdapter 511  
 CopyOnWriteArrayList 1002  
 CopyOnWriteArraySet 1002  
 DataInputStream 666  
 DataOutputStream 666  
 DelayQueue 1002  
 Double 679, 853  
 DoubleProperty (JavaFX) 1124  
 DriverManager 1057  
 Ellipse2D 548  
 Ellipse2D.Double 573  
 Ellipse2D.Float 573  
 EmptyStackException 702  
 EnumSet 329  
 Error 443  
 EventListenerList 485  
 Exception 443  
 ExecutionException 1006  
 Executors 956  
 FileReader 668

## Classes (cont.)

Files 639, 751  
 FilterInputStream 666  
 FilterOutputStream 666  
 Float 679  
 FlowLayout 475, 521  
 FocusAdapter 511  
 Font 492, 548, 559  
 FontMetrics 548, 561  
 Formatter 639  
 Frame 908  
 FXMLLoader (JavaFX) 1113, 1119, 1122, 1123  
 GeneralPath 548, 578  
 GradientPaint 548, 576  
 Graphics 515, 548, 573  
 Graphics2D 548, 573, 577  
 GridBagConstraints 935, 940, 941  
 GridBagLayout 931, 934, 936, 941  
 GridLayout 521, 528  
 GridPane (JavaFX) 1111  
 HashMap 706  
 HashSet 703  
 Hashtable 706  
 IllegalMonitorStateException 980, 995  
 ImageIcon 476  
 ImageView (JavaFX) 1103  
 IndexOutOfBoundsException 223  
 InputEvent 506, 513, 517  
 InputMismatchException 437  
 InputStream 665  
 InputStreamReader 668  
 Instant (Java SE 8) 1025  
 Integer 470, 679, 853  
 InterruptedException 957  
 ItemEvent 493, 496  
 JApplet 909  
 JButton 471, 487, 490, 526  
 JCheckBox 471, 490  
 JCheckBoxMenuItem 909, 910, 916  
 JColorChooser 555  
 JComboBox 471, 496, 936  
 JComponent 472, 473, 475, 485, 497, 500, 514, 530, 548, 550  
 JDesktopPane 925, 948  
 JDialog 915  
 JFileChooser 662  
 JFrame 908  
 JInternalFrame 925, 927  
 JLabel 471, 473  
 JList 471, 500  
 JMenu 909, 916, 927  
 JMenuBar 909, 916, 927  
 JMenuItem 910, 927  
 JOptionPane 59, 468, 945  
 JPanel 471, 514, 521, 530, 905  
 JPasswordField 477, 482  
 JPopupMenu 917  
 JProgressBar 1013  
 JRadioButton 490, 493, 496  
 JRadioButtonMenuItem 909, 910, 917  
 JScrollPane 502, 505, 533, 534  
 JSlider 904, 905, 908  
 JTabbedPane 928, 934

## Classes (cont.)

JTable 1059  
 JTextArea 520, 531, 533, 936, 939  
 JTextComponent 477, 480, 531, 533  
 JTextField 471, 477, 481, 485, 531  
 JToggleButton 490  
 KeyAdapter 511  
 KeyEvent 486, 517  
 Label (JavaFX) 1103  
 Line2D 548, 577  
 Line2D.Double 573  
 LinearGradientPaint 576  
 LineNumberReader 668  
 LinkedBlockingDeque 1002  
 LinkedBlockingQueue 1002  
 LinkedList 680  
 LinkedTransferQueue 1002  
 ListSelectionEvent 500  
 ListSelectionModel 502  
 Long 679  
 Matcher 589, 623  
 Math 167, 168  
 MouseAdapter 510, 511  
 MouseEvent 486, 506, 920  
 MouseMotionAdapter 511, 514  
 MouseWheelEvent 507  
 Node (JavaFX) 1102  
 Number 853  
 NumberFormat 338, 1018, 1112, 1120  
 Object 330  
 ObjectInputStream 654  
 ObjectOutputStream 654  
 Optional class (Java SE 8) 744  
 OptionalDouble 731, 749  
 OutputStream 665  
 OutputStreamWriter 668  
 Parent (JavaFX) 1114, 1119  
 Paths 639  
 Pattern 589, 623  
 PipedInputStream 665  
 PipedOutputStream 665  
 PipedReader 668  
 PipedWriter 668  
 Point 515  
 Polygon 548, 570  
 PrintStream 666  
 PrintWriter 668  
 PriorityBlockingQueue 1002  
 PriorityQueue 702  
 Properties 710  
 RadialGradientPaint 576  
 Random 251  
 Reader 667  
 Rectangle2D 548  
 Rectangle2D.Double 573  
 ReentrantLock 994, 996  
 RoundRectangle2D 548  
 RoundRectangle2D.Double 573, 577  
 RowFilter 1071  
 RowSetFactory 1072  
 RowSetProvider 1072  
 RuntimeException 444  
 Scanner 47  
 Scene (JavaFX) 1102, 1111, 1119, 1120

## Classes (cont.)

- SecureRandom 178
- Short 679
- Slider (JavaFX) 1110, **1112**
- SQLException 1057
- SQLFeatureNotSupportedException 1065
- Stack 700
- StackTraceElement 453
- Stage (JavaFX) **1102**, 1111, 1119, 1120
- String 61, 589
- StringBuffer 604
- StringBuilder 589, **603**
- StringIndexOutOfBoundsException 599
- StringReader 668
- StringWriter 668
- SwingUtilities 924
- SwingWorker 1003
- SynchronousQueue 1002
- SystemColor 576
- TableModelEvent 1071
- TableRowSorter 1071
- TextField (JavaFX) **1112**
- TexturePaint 548, 576, 577
- Throwable 443, 453
- TreeMap 706
- TreeSet 703
- Types 1059
- UIManager 921
- UnsupportedOperationException 686
- Vbox (JavaFX) **1107**
- Vector 680
- Window 908, 909
- WindowAdapter 511, **1071**
- Writer 667
- class-instance creation expression 1124
- ClassName.this* 915
- CLASSPATH
  - environment variable 41, **877**
- classpath 877, 1056
- classpath command-line argument
  - to java **878**
  - to javac **877**
- CLASSPATH problem 22
- clear debugger command **1154**
- clear method
  - of ArrayList<T> 238
  - of List<T> **686**
  - of PriorityQueue 702
- clearRect method of class Graphics 564
- click a button 477, 1113
- click count 511
- click the scroll arrows 499
- clicking the close box 948
- client
  - of a class 275
- client code 390
- clone method of Object 380
- cloning objects
  - deep copy **380**
  - shallow copy **380**
- close a window 473, 477, 1113
- close method
  - of CachedRowSet 1074
  - of Connection 1059
- close method (cont.)
  - of Formatter **646**
  - of interface AutoCloseable 459
  - of interface Connection 1059
  - of interface ResultSet 1059
  - of interface Statement 1059
  - of JdbcRowSet **1074**
  - of ObjectOutputStream **659**
  - of ResultSet 1059
  - of Statement 1059
- closed polygons 570
- closed tour 256, 585
- closePath method of class
  - GeneralPath **580**
- cloud computing **29**
- COBOL (CCommon Business Oriented Language) 15
- code **12**
- code maintenance 283
- coin tossing 178, 205
- collect method of interface Stream
  - (Java SE 8) **737**, 747, 748, 754
- collection **238**, **677**
- collection implementation 713
- Collection interface **678**, 679, 683, 688
  - contains method **683**
  - iterator method **683**
- collections
  - synchronized collection 680
  - unmodifiable collection 680
- Collections class **680**, 838
  - addAll method 688, **698**
  - binarySearch method 688, **696**, 698
  - copy method 688, **695**
  - disjoint method 688, **698**
  - fill method 688, **694**
  - frequency method 688, **698**
  - max method 688, **695**
  - min method 688, **695**
  - reverse method 688, **694**
  - reverseOrder method **690**
  - shuffle method 688, **692**, 694
  - sort method **689**
  - wrapper methods **680**
- collections framework **677**
- Collections methods reverse, fill, copy, max and min 695
- Collector interface (Java SE 8) **737**
- Collectors class (Java SE 8) **737**
  - groupBy method 747, 748, 752, 754
  - toList method **737**
- College Loan Payoff Calculator app
  - exercise 1131
- collision in a hashtable **707**
- color 548
- Color class **192**, **548**
  - getBlue method **552**, 554
  - getColor method **552**
  - getGreen method **552**, 554
  - getRed method **552**, 554
  - setColor method **552**
- Color constant 551, 554
- color manipulation 550
- color swatches **557**
- Color.BLACK 192
- Color.BLUE 192
- Color.CYAN 192
- Color.DARK\_GRAY 192
- Color.GRAY 192
- Color.GREEN 192
- Color.LIGHT\_GRAY 192
- Color.MAGENTA 192
- Color.ORANGE 192
- Color.PINK 192
- Color.RED 192
- Color.WHITE 192
- Color.YELLOW 192
- color-chooser dialog 557
- colors 192
- column 228, **1039**, 1040
- column number in a result set 1045
- columns of a two-dimensional array 228
- combo box **467**, 496
- comma (,) 129
- comma (,) formatting flag **131**
- comma in an argument list 43
- comma-separated list 129
  - of arguments **43**, 47
  - of parameters 171
- command button **487**
- command line **39**
- command-line argument **169**, **233**
- Command Prompt 18, 39
- command window 21, **39**
- comment
  - end-of-line (single-line), // **36**, 39
  - Javadoc **36**
  - single line 39
- commercial data processing 672
- commission 115, 250
- CommissionEmployee class derived
  - from Employee 403
- commit a transaction **1091**
- commit method of interface
  - Connection **1091**
- Comparable interface 890
- Comparable<T> interface 423, 595, 689, **837**, 890
  - compareTo method 689, **838**
- Comparator interface **689**, 690, 740, 740
  - compare method **691**
  - thenComparing method (Java SE 8) **745**
- Comparator object 689, 695, 704, 706
  - in sort 689
- compare method of interface
  - Comparator **691**
- compareTo method
  - of class String 593, 595
  - of Comparable 689
- compareTo method of class
  - BigInteger **774**
- compareTo method of Comparable<T> **838**
- comparing String objects 592
- comparison operator 423
- compartment in a UML class diagram 273
- compilation error **36**
- compilation errors 40
- compile 39, 40
- compile a program **18**
- compile method of class Pattern **623**
- compile-time error **36**

- compile-time type safety 682
- compiler **10**
- compiler error **36**
- compiler options
  - d **876**
- compile-time type safety **832**
- compiling an application with multiple classes 272
- CompletableFuture class (Java SE 8) **1022**
  - runAsync method **1026**
  - supplyAsync method **1025**
- Complex 348
- complex curve 578
- complex number 349
- Complex Numbers (exercise) 348
- complexity theory 777
- component 10, 505
- Component class **472**, 505, 550, 551, 557, 909, 940
  - addKeyListener method **517**
  - addMouseListener method **510**
  - addMotionListener method **510**
  - getMinimumSize method 908
  - getPreferredSize method 907
  - repaint method **516**
  - setBackground method 557
  - setBounds method 521
  - setFont method **492**
  - setLocation method 521, **909**
  - setSize method 521, 909
  - setVisible method **526**, 909
- component of an array **210**
- ComponentAdapter class 511
- ComponentListener interface 511, 521
- composing lambda expressions 734
- composite primary key 1042, 1043
- composition **324**, 354, 356
- compound assignment operators **99**, 102
- compound interest 129, 160, 161
- computer-assisted instruction (CAI) 206, 207
- computer-assisted instruction (CAI):
  - Monitoring Student Performance 206
- computer-assisted instruction (CAI):
  - Reducing Student Fatigue 206
- computer-assisted instruction (CAI):
  - Varying the Types of Problems 207
- computer-assisted instruction (CAI):Difficulty Levels 207
- computer dump 262
- computer program **4**
- computer simulator 260
- computers in education 206
- concat method of class String **600**
- concatenate strings 333
- concatenation **172**
- Concentric Circles Using Class
  - Ellipse2D.Double exercise 584
- Concentric Circles Using Method
  - drawArc exercise 584
- concordance 750
- concrete class **394**
- concrete subclass 399
- CONCUR\_READ\_ONLY constant **1064**
- CONCUR\_UPDATABLE constant **1064**
- Concurrency API 951
- concurrency APIs 951
- concurrent access to a Collection by multiple threads 713
- concurrent operations 950
- concurrent programming **951**
- concurrent threads 976
- ConcurrentHashMap class 1002
- ConcurrentLinkedDeque class 1002
- ConcurrentSkipListMap class 1002
- ConcurrentSkipListSet class 1002
- condition **54**, 133
- Condition interface **995**, 996
  - await method **995**, 999
  - signal method **995**
  - signalAll method **995**
- condition object **995**
- conditional AND, && **142**, 143, 144
  - truth table 142
- conditional expression **81**
- conditional operator, ?: 81, 102
- conditional OR, || **142**, **143**
  - truth table 143
- confusing the equality operator == with the assignment operator = 57
- connect to a database 1055
- connected lines 570
- connected RowSet **1072**
- connection between Java program and database 1057
- Connection interface **1057**, 1059, 1064, 1091
  - close method 1059
  - commit method **1091**
  - createStatement method **1058**, 1064
  - getAutoCommit method **1091**
  - prepareStatement method **1081**
  - rollback method **1091**
  - setAutoCommit method **1091**
- constant 335
  - Math.PI 69
- constant integral expression **134**, 139
- constant run time **807**
- constant variable **139**, 216
  - must be initialized 216
- constructor **271**, 276
  - call another constructor of the same class using this 319
  - multiple parameters 279
  - no argument **319**
  - overloaded **316**
- Constructor failure exercise 464
- constructor reference (Java SE 8) 752
- constructors cannot specify a return type 278
- consume an event **481**
- consume memory 780
- consumer 951, **968**
- consumer electronic device 17
- Consumer functional interface (Java SE 8) 725, 730, 743
  - accept method 743
- consumer thread **969**
- cont debugger command **1144**
- Container class **472**, 503, 521, 529, 530
  - setLayout method **475**, 522, 526, 529, 934
  - validate method **529**
- container for menus 909
- ContainerAdapter class 511
- ContainerListener interface 511
- contains method
  - of Collection **683**
- contains method of class
  - ArrayList<T> 238, **241**
- containsKey method of Map **709**
- content pane 502, 917
  - setBackground method **503**
- context-sensitive popup menu **917**
- continue statement **140**, 141, 162, 163, 1138
- continuous beta 29
- control statement **73**, 74, 76, 77, 779
  - nesting **76**, 150
  - stacking **76**, 149
- control variable **84**, **122**, 123, 124
- controller (in MVC architecture) 1113
- controller class 1114
  - initialize instance variables 1119
- controller class (JavaFX) **1103**, **1113**
  - initialize method 1123
- controlling expression of a switch **137**
- controls 466, 1100, **1103**
- converge on a base case 770
- convert
  - between number systems 613
- Cooking with Healthier Ingredients 633
- coordinate system **103**, **548**, 550
- coordinates (0, 0) 103, 548
- copy method of Collections 688, **695**
- copying files 639
- copying objects
  - deep copy **380**
  - shallow copy **380**
- CopyOnWriteArrayList class 1002
- CopyOnWriteArraySet class 1002
- core package 40
- correct in a mathematical sense 147
- cos method of Math 168
- cosine 168
- count method of interface InputStream (Java SE 8) **731**
- counter **84**, 89, 96
- counter-controlled repetition **84**, 84, 92, 95, 96, 122, 124, 260, 779
- cp command line argument
  - to java **878**
- CPU (central processing unit) **6**
- Craigslist 26
- craps (casino game) 183, 205, 251
- create a reusable class 875
- create an object of a class 271
- create and use your own packages 874
- createGlue method of class Box **934**
- createGraphics method of class
  - BufferedImage 577
- createHorizontalBox method of class Box **533**, 933
- createHorizontalGlue method of class Box **934**
- createHorizontalStrut method of class Box **933**
- createJdbcRowSet method of interface RowSetFactory **1072**
- createRigidArea method of class Box **934**
- createStatement method of
  - Connection **1058**, 1064

- createVerticalBox method of class Box **933**
- createVerticalGlue method of class Box **934**
- createVerticalStrut method of class Box **933**
- creating and initializing an array 213
- creating files 639
- credit limit on a charge account 115
- crossword puzzle generator 633
- CSS(Cascading Style Sheets) **1101**
- <Ctrl>-d 137
- Ctrl key 503, 520
- ctrl key 137
- <Ctrl>-z 137
- currentThread method of class Thread **957**, 962
- currentTimeMillis method of class System 801
- cursor 39, 42
- curve 578
- custom drawing area 514
- customized subclass of class JPanel 514
- cyclic gradient **576**
- D**
- d compiler option 876
- dangling-else problem **80**, 117
- dashed lines 573
- data 4
- data entry 60
- data hiding **275**
- data hierarchy **6**, 7
- data integrity 323
- data source 723
- data structure **209**
- database **8**, **1038**, 1044
  - table **1039**
- database management system (DBMS) **1038**
- DataInput interface 666
- DataInputStream class **666**
- DataOutput interface 666
  - writeBoolean method 666
  - writeByte method 666
  - writeBytes method 666
  - writeChar method 666
  - writeChars method 666
  - writeDouble method 666
  - writeFloat method 666
  - writeInt method 666
  - writeLong method 666
  - writeShort method 666
  - writeUTF method 666
- DataOutputStream class **666**
- Date and Time Class (exercise) 349
- Date class
  - exercise 349
- Date/Time API 238, **313**
- Date/Time API package **177**
- DB2 1038
- De Morgan's Laws 162
- dead state 953
- deadlock **955**, 999, 1035
- dealing 284
- debugger 1141
  - break mode **1144**
  - breakpoint **1141**
- debugger (cont.)
  - clear command **1154**
  - cont command **1144**
  - defined **1141**
  - exit command **1149**
  - g compiler option **1142**
  - inserting breakpoints 1143
  - jdb command **1143**
  - logic error 1141
  - next command **1149**
  - print command **1145**, 1146
  - run command **1143**, 1146
  - set command **1145**, 1147
  - step command **1148**
  - step up command **1148**
  - stop command **1143**, 1146
  - suspending program execution 1146
  - unwatch command 1150, **1151**
  - watch command **1150**
- decimal digit **6**
- decimal integer formatting 49
- decision **54**, 77
  - symbol in the UML 77
- declaration
  - class **37**
  - import **45**, 48
  - method **38**
- declarative programming 1102
- decrement a control variable **127**
- decrement operator, -- **100**
- decrypt 119
- dedicated drawing area **514**
- deep copy **380**
- deeply nested statement 150
- default case in a switch **137**, 139, 182
- default constructor **278**, 322, 360
- default exception handler 453
- default initial value **271**
- default interface methods (Java SE 8) 424
- default keyword 1138
- default layout of the content pane 533
- default locale 1121
- default method in an interface (Java SE 8) 724, 755
- default method of an interface (Java SE 8) 723
- default methods in interfaces (Java SE 8) **424**
- default package **274**, 875
- default upper bound (Object) of a type parameter 843
- default value **271**
- define a custom drawing area 514
- definite repetition **84**
- degree 567
- Deitel Resource Centers 30
- DelayQueue class 1002
- delegate a method call **882**
- delegation event model **484**
- delete method of class StringBuilder **609**
- DELETE SQL statement 1044, **1052**
- deleteCharAt method of class StringBuilder **609**
- deleting an item from a binary tree 892
- deleting directories 639
- deleting files 639
- delimiter for tokens **615**
- delimiter string 615
- Department of Defense (DOD) 16
- dependent condition 143
- deprecated APIs **46**
- deprecation flag 46
- dequeue operation of queue **883**
- derived class **353**
- descending order 235
- descending sort (DESC) 1047
- descent **561**
- deserialized object **654**
- design pattern **28**
- design process **13**
- Determining points C and D for level 1 of "Lo fractal" 786
- dialog **468**
- dialog box **59**, 468, 915
- Dialog font 559
- DialogInput font 559
- diameter 69, 584
- diamond in the UML **75**, 162
- diamond notation **683**
- diamond notation (<>) **241**, 241
- dice game 183
- Dice Rolling 251
- digit 47, 614, 616
- digit method of class Character **613**
- digits reversed 205
- direct superclass 353, 355
- directories
  - creating 639
  - getting information about 639
  - manipulating 639
- DIRECTORIES\_ONLY constant of JFileChooser **662**
- directory 639
  - separator **877**
- DirectoryStream interface **639**, 766
  - entries method 766
- disconnected RowSet **1072**
- disjoint method of Collections **688**, **698**
- disk 4, 21, 637
- disk I/O completion 443
- disk space 863
- dismiss a dialog 469
- dispatch
  - a thread **954**
  - an event **486**
- display a line of text 39
- display monitor 104, 548
- display output 61
- displaying text in a dialog box 59
- disspose method of class Window **909**
- DISPOSE\_ON\_CLOSE constant of interface WindowConstants 909
- distance between values (random numbers) 182
- distinct method of interface Stream (Java SE 8) **746**
- divide-and-conquer approach **165**, 166, 770
- divide by zero 21, 90, 436
- division 6, 51, 52
- division compound assignment operator, /= 100
- DO\_NOTHING\_ON\_CLOSE constant of interface WindowConstants 908

- do...while repetition statement 76, **132**, 133, 152, 1138
  - document 904, 925
  - document a program **36**
  - dollar signs (\$) 37, 46
  - dot (.) separator 60, 131, 167, 168, **271**, 331, 573
  - dotted line in the UML **76**
  - (double) cast **94**
  - Double class **679**, 853
  - double equals, == 57
  - double keyword 171
  - double-precision floating-point number **92**
  - double primitive type 47, 91, **92**, 1138, 1139
    - promotions 175
  - double quotes, " 39, 43
  - double selection 152
  - double-selection statement 76, 96
  - DoubleProperty class (JavaFX) 1124
  - doubles method of class
    - SecureRandom (Java SE 8) **754**
  - DoubleStream interface (Java SE 8) **728**, 748
    - average method 749
    - reduce method 749
    - sum method 749
  - doubleValue method of Number **854**
  - downcast 410, 678
  - downcasting **391**
  - downstream Collector (Java SE 8) **748**
  - drag the scroll box 499
  - dragging the mouse to highlight 533
  - draw method of class Graphics2D **576**
  - draw shapes 548
  - draw3DRect method of class Graphics 564, **567**
  - drawArc method of class Graphics **243**, **567**, 584
  - drawing color 552
  - drawing on the screen 550
  - drawLine method of class Graphics **106**, **564**
  - drawOval method of class Graphics **152**, **153**, 564, **567**
  - drawPolygon method of class Graphics 570, **572**
  - drawPolyline method of class Graphics 570, **572**
  - drawRect method of class Graphics **152**, 564, 577, 584
  - drawRoundRect method of class Graphics **565**
  - drawString method of class Graphics **554**
  - driver class 269
  - DriverManager class **1057**
    - getConnection method **1057**
  - drop-down list 471, **496**
  - dual-core processor 6
  - dummy value **88**
  - Duplicate Elimination 250
  - duplicate elimination **891**
  - duplicate values 892
  - Duplicate Word Removal exercise 766
  - Duration class
    - between method **1018**
    - toMillis method **1018**
  - dynamic binding 393, **409**
  - dynamic content 17
  - dynamic data structure **862**
  - dynamic memory allocation **863**
  - dynamic resizing **209**
- ## E
- eager **726**
  - eager stream operation (Java SE 8) 731
  - eager terminal operation 733
  - EAST constant
    - of class BorderLayout **510**, 524
    - of class GridBagConstraints **935**
  - echo character of class JPasswordField **477**
  - Eclipse demonstration video 35
  - Eclipse 18
  - Eclipse Foundation 14
  - Ecofont 545
  - edit a program 18
  - editor 18
  - effectively final local variables (Java SE 8) **730**
  - efficiency of
    - binary search 812
    - bubble sort 828
    - insertion sort 819
    - linear search 808
    - merge sort 824
    - selection sort 816
  - Eight Queens exercise 255, 799
    - Brute Force Approaches 256
  - electronic mail (e-mail) 25
  - element of an array **210**
  - element of chance **178**
  - eligible for garbage collection 334
  - eliminate resource leaks 447
  - Ellipse2D class 548
  - Ellipse2D.Double class **573**, 584
  - Ellipse2D.Float class **573**
  - ellipsis (...) in a method parameter list **231**
  - else keyword 78, 1138
  - emacs 18
  - e-mail (electronic mail) 25
  - embedded system 14
  - embedded version of Java DB 1052
  - Employee abstract superclass 398
  - Employee class hierarchy test program 406
  - Employee class that implements Payable 418
  - employee identification number 8
  - empty set 349
  - empty statement (a semicolon, ;) **57**, 81, 134
  - empty string **482**, **591**
  - EmptyStackException class **702**
  - encapsulation **12**
  - encrypt 119
  - end cap **576**
  - End key 517
  - "end of data entry" 88
  - end-of-file (EOF)
    - indicator **136**
    - key combinations 646
    - marker **637**
  - end-of-line (single-line) comment, // **36**, 39
  - endsWith method of class String **596**
  - Enforcing Privacy with Cryptography exercise 119
  - English-like abbreviations 9
  - enhanced for statement **223**
  - enhanced-for statement
    - nested 231
  - Enhancing Class Date (exercise) 348
  - Enhancing Class Time2 (exercise) 348
  - enqueue operation of queue **883**, 883
  - ensureCapacity method of class StringBuilder **605**
  - Enter (or Return) key 39, 485
  - entity-relationship diagram **1043**
  - entries method of interface DirectoryStream 766
  - entry point 147
  - enum **186**
    - constant 327
    - constructor **327**
    - declaration **327**
    - EnumSet class 329
    - keyword 186, 1138
    - values method **328**
  - enum type **186**
  - enumeration constant **186**
  - EnumSet class **329**
    - range method **329**
  - environment variable CLASSPATH 41  
PATH 40
  - EOFException class **662**
  - equal likelihood 180
  - equality operator == to compare String objects 593
  - equality operators **54**
  - equals method
    - of class Arrays **235**
    - of class Object 379
    - of class String 593, 595
  - equalsIgnoreCase method of class String 593, 595
  - erasure **837**, 840
  - Error class **443**
  - Error-Prevention Tips overview xxxiv
  - escape character **43**, 1050
  - escape sequence **43**, 47, 643
    - \, backslash 43
    - \", double-quote 43
    - \t, horizontal tab 43
    - newline, \n 43
  - Euclid's Algorithm 205
  - Euler 253
  - evaluating expressions 897
  - event 424, **477**, 550, 1103, **1112**
  - event classes 483
  - event-dispatch thread (EDT) **550**, **1003**
  - event driven **477**, **1112**
  - event-driven process 550
  - event candle 1112
  - event handler 424, **477**, 1103, **1113**
    - implement with a lambda 755, 1125
    - lambda 755
  - event handling **477**, 480, 485, 1103, **1113**
    - event source **482**
  - event ID **486**

- event listener 424, 484, 510
  - adapter class 510
  - interface **480**, 481, 484, 485, 486, 505, 510, **1113**
- event object 484
- event registration 481
- event source **482**, 484
- `EventHandler<ActionEvent>` interface (JavaFX) **1123**
- `EventListenerList` class **485**
- `EventObject` class
  - `getSource` method 482
- examination-results problem 97
- exception **222**, 434
  - handler **222**
  - handling 220
  - parameter 223
- `Exception` class **443**
- exception handler **440**
- exception parameter **440**
- Exceptions 223
  - `IndexOutOfBoundsException` 223
- execute **20**, 39
- execute method
  - of `JdbcRowSet` **1074**
- execute method of the `Executor` interface **955**, 959
- `executeQuery` method
  - of `PreparedStatement` **1081**
  - of `Statement` **1058**
- `executeUpdate` method of interface `PreparedStatement` **1081**
- executing an application 21
- execution-time error **21**
- `ExecutionException` class 1006
- `Executor` interface **955**
  - execute method **955**, 959
- `Executors` class **956**
  - `newCachedThreadPool` method **957**
- `ExecutorService` interface **956**, 1022
  - `awaitTermination` method **965**
  - `shutdown` method **959**
  - `submit` method **1022**
- `exists` method of class `Files` **640**
- exit debugger command **1149**
- `exit` method of class `System` **447**, **645**
- exit point 147
  - of a control statement 76
- `EXIT_ON_CLOSE` constant of class `JFrame` **106**
- exiting a `for` statement 140
- `exp` method of `Math` 168
- expanded submenu 915
- explicit conversion **94**
- exponential method 168
- exponentiation 263
- exponentiation operator 131
- expression **49**
- extend a class **353**
- extends keyword **105**, **357**, 368, 1138
- extensibility 390
- extensible language **266**
- extension mechanism
  - extending Java with additional class libraries **877**
- external event **505**
- external iteration **723**, 753

## F

- Facebook 14
- factorial 119, 160, 771
- Factorial calculations with a recursive method 773
- `factorial` method 771
- Fahrenheit 543
  - equivalent of a Celsius temperature 204
- fail fast iterator 683
- fairness policy of a lock **994**
- false keyword **54**, **81**, 1138
- fatal error **81**, 263
- fatal logic error **81**
- fatal runtime error **21**
- fault tolerant 48, 434
- fault-tolerant program **222**
- feature-complete 29
- fetch 261
- `fibonacci` method 776
- Fibonacci series 258, 775, 777
  - defined recursively 775
- field **7**
  - default initial value **271**
- field of a class **8**
- field width **130**
- fields of a class **169**
- file **8**, **637**
- `File` class
  - `toPath` method **663**
  - used to obtain file and directory information 641
- file matching
  - exercise 672
  - program 672
  - with Multiple Transactions exercise 674
  - with Object Serialization exercise 674
- `FileInputStream` class 713
- `FileNotFoundException` class **645**
- `FileOutputStream` class 712
- `FileReader` class 668
- files
  - copying 639
  - creating 639
  - getting information about 639
  - manipulating 639
  - reading 639
- `Files` class **639**, 751
  - `exists` method **640**
  - `getLastModifiedTime` method **640**
  - `isDirectory` method **640**
  - `lines` method (Java SE 8) **751**
  - `newDirectoryStream` method **640**
  - `newOutputStream` method **657**, **660**
  - `size` method **640**
- `FILES_AND_DIRECTORIES` constant of `JFileChooser` **662**
- `FILES_ONLY` constant of `JFileChooser` **662**
- `FileWriter` class 668
- `fill` method
  - of class `Arrays` **235**, 237
  - of class `Collections2D` 688, **694**
  - of class `Graphics2D` **576**, 577, 580, 585
- `fill` method of class `Arrays` 1012
- `fill` pattern 577
- `fill` texture 577
- `fill` with color 548
- `fill3DRect` method of class `Graphics` 564, **567**
- `fillArc` method of class `Graphics` 241, **243**, **567**
- filled-in shape 192, 577
- filled rectangle 552
- filled three-dimensional rectangle 564
- `fillOval` method of class `Graphics` **192**, **516**, 564, **567**
- `fillPolygon` method of class `Graphics` 570, **573**
- `fillRect` method of class `Graphics` **192**, **552**, 564, 577
- `fillRoundRect` method of class `Graphics` **565**
- filter a stream **666**
- filter elements of a stream (Java SE 8) 733
- `filter` method of interface `InputStream` (Java SE 8) **733**
- `filter` method of interface `Stream` (Java SE 8) 737, 740
- `FilterInputStream` class **666**
- `FilterOutputStream` class **666**
- `final`
  - class **412**
  - keyword 139, **169**, 216, 335, 411, 960, 1138
  - local variable 499
  - method **411**
  - variable 216
- final release 29
- final state in the UML **75**, 149
- final value 123
- `finalize` method **330**, 380
- `finally`
  - block **440**, 446, 999
  - clause **446**, 1138
  - keyword **440**
- `find` method of class `Matcher` **623**
- Find the Minimum Value in an Array exercise 799
- `findFirst` method of interface `Stream` (Java SE 8) 744
- Firefox web browser 59
- `fireTableStructureChanged` method of `AbstractTableModel` **1066**
- first-in, first-out (FIFO) data structure **883**
- `first` method of `SortedSet` **705**
- first refinement 96
- first refinement in top-down, stepwise refinement 88
- `Fit` `Width` property of an `ImageView` (JavaFX) 1109
- five-pointed star 578
- fixed text 49
  - in a format string **44**
- flag value **88**
- flash drive 637
- `flatMap` method of interface `Stream` (Java SE 8) **752**
- `float`
  - literal suffix **F** **702**
  - primitive type **47**, **92**, 1138, 1139
  - primitive type promotions 175



- Float class **679**
  - floating-point constant 129
  - floating-point literal **92**
    - double by default **92**
  - floating-point number 86, 91, **92**, 92, 702
    - division 94
    - double precision **92**
    - double primitive type **92**
    - Float primitive type **92**
    - single precision **92**
  - floor method of Math 168
  - flow of control 82, 92
  - flow of control in the if...else statement 78
  - FlowLayout class **475**, 521, 522
    - CENTER constant **524**
    - LEFT constant **524**
    - RIGHT constant **524**
    - setAlignment method **524**
  - flush method
    - of class BufferedOutputStream **666**
  - focus **478**, **1117**
  - focus for a GUI application 905, 920
  - FocusAdapter class 511
  - FocusListener interface 511
  - font
    - manipulation 550
    - name **559**
    - size **559**
    - style **559**
  - Font class **492**, **548**, 559
    - BOLD constant **559**
    - getFamily method 558, **561**
    - getName method 558, **559**
    - getSize method 558, **559**
    - getStyle method 558, **561**
    - isBold method 558, **561**
    - isItalic method 558, **561**
    - isPlain method 558, **561**
    - ITALIC constant **559**
    - PLAIN constant **559**
  - font information 548
  - font manipulation 550
  - font metrics **561**
    - ascent 563
    - descent 563
    - height 563
    - leading 563
  - Font property of a Label (JavaFX) 1108
  - font style 491
  - FontMetrics class **548**, **561**
    - getAscent method 562
    - getDescent method 562
    - getFontMetrics method **561**
    - getHeight method 562
    - getLeading method 562
  - for repetition statement 76, **124**, 127, 129, 131, 152, 1138
    - activity diagram 127
    - enhanced **223**
    - example 127
    - header **125**
    - nested 219, 230
    - nested enhanced for 231
  - forDigit method of class Character **613**
  - forEach method of interface
    - IntStream (Java SE 8) **730**
  - forEach method of interface Map (Java SE 8) **747**
  - forEach method of interface Stream (Java SE 8) 737
  - foreign key **1042**, 1043
  - fork/join framework 1026
  - format method
    - of class Formatter 646
    - of class String **61**, **310**
  - format method of class NumberFormat **339**, 1018
  - format specifiers **44**
    - %.2f for floating-point numbers with precision 94
    - %b for boolean values **145**
    - %c 69
    - %d **49**
    - %f 69, **282**
    - %n (line separator) **44**
    - %s **44**
  - format string **44**
  - formatted output
    - , (comma) formatting flag **131**
    - %f format specifier **282**
    - (minus sign) formatting flag **130**
    - 0 flag **219**, 310
    - boolean values **145**
    - comma (,) formatting flag **131**
    - field width **130**
    - floating-point numbers **282**
    - grouping separator **131**
    - left justify **130**
    - minus sign (-) formatting flag **130**
    - precision **283**
    - right justification **130**
  - Formatter class **639**, 643
    - close method **646**
    - format method **646**
  - FormatterClosedException class **646**
  - formatting
    - display formatted data 43
  - formulating algorithms 84
  - Fortran (FORmula TRANslator) 15
  - fractal **783**
    - “Lo fractal” at level 0 785
    - “Lo fractal” at level 2 787
    - “Lo fractal” at level 2, dashed lines from level 1 provided 786
  - depth **784**
  - exercises 799
  - Koch Curve **783**
  - Koch Snowflake **784**
  - level **784**
  - “Lo fractal” at level 1, with C and D points determined for level 2 786
  - order **784**
  - self-similar property **783**
  - strictly self-similar fractal **783**
  - Fractal user interface 787
  - fragile software **373**
  - Frame class 908
  - frequency method of Collections **688**, **698**
  - FROM SQL clause 1044
  - full tour 585
  - fully qualified class name 274
  - fully qualified type name **876**
  - Function functional interface (Java SE 8) 725, 739
    - apply method **739**
    - identity method 754
  - function key 517
  - functional interface 723, 1022
  - functional interface (Java SE 8) **425**, 725
  - Functional Interfaces
    - Supplier **1022**
  - Functional interfaces (Java SE 8)
    - @FunctionalInterface annotation **756**
  - functional interfaces
    - ActionListener 755
    - ItemListener 755
  - Functional interfaces (Java SE 8) 724, 725
    - BiConsumer **747**, 754
    - BinaryOperator 725
    - Consumer 725, 730, 743
    - Function 725, 739
    - IntFunction 1019
    - IntToDoubleFunction 1019
    - IntToLongFunction 1019
    - IntUnaryOperator 1019
    - Predicate 725, 743
    - Supplier 725
    - UnaryOperator 725
  - functional programming **724**
  - @FunctionalInterface annotation **756**
  - Future interface **1022**
    - get method **1022**, 1026
  - fxid property of a JavaFX component **1114**
  - FXML (FX Markup Language) **1102**
  - @FXML annotation 1121, **1122**
  - FXML markup 1106
  - FXMLLoader class (JavaFX) **1113**, 1119, 1122, 1123
    - load method **1113**, **1119**
- ## G
- g command line option to javac 1142
  - Game of Craps 251
  - game playing 178
  - gaming console 15
  - garbage collection 951
  - garbage collector **330**, 442, 446
  - GCD (greatest common divisor) 798
  - general class average problem 87
  - general path **578**
  - generalities 390
  - GeneralPath class 548, **578**, 584
    - closePath method **580**
    - lineTo method **580**
    - moveTo method **579**
  - Generating Mazes Randomly exercise 801
  - generic class **238**
  - generics 678, **832**
    - ? (wildcard type argument) **854**
    - actual type arguments **836**
    - angle brackets (< and >) **835**
    - class **832**, 841
    - default upper bound (Object) of a type parameter 843
    - diamond notation **683**

- generics (cont.)
  - erasure **837**
  - interface **838**
  - method **832**, 834, 840
  - parameterized class **841**
  - parameterized type **841**
  - scope of a type parameter 843
  - type parameter **835**
  - type parameter section **835**
  - type variable **835**
  - upper bound of a type parameter **839**, 840
  - upper bound of a wildcard 854
  - wildcard type argument **854**
  - wildcard without an upper bound 856
  - wildcards **852**, 854
- gesture 15
- get method
  - of class `ArrayList<T>` **240**
  - of interface `Future` **1022**
  - of interface `List<T>` **682**
  - of interface `Map` **709**
- get method 316, 323
- get method of class `Paths` **639**, 640
- get method of interface `Future` 1026
- getActionCommand method of class `ActionEvent` **482**, 490
- getAscent method of class `FontMetrics` 562
- getAsDouble method of class `OptionalDouble` (Java SE 8) **731**, 749
- getAutoCommit method of interface `Connection` **1091**
- getBlue method of class `Color` **552**, 554
- getChars method
  - of class `String` **591**
  - of class `StringBuilder` **606**
- getClass method of class `Object` **476**
- getClass method of `Object` 380, **410**
- getClassName method of class `StackTraceElement` **453**
- getClassName method of class `UIManager.LookAndFeelInfo` **924**
- getClickCount method of class `MouseEvent` **513**
- getColor method of class `Color` **552**
- getColor method of class `Graphics` 552
- getColumnClass method of `TableModel` **1060**, 1065
- getColumnClassName method of `ResultSetMetaData` **1065**
- getColumnCount method of `ResultSetMetaData` **1058**, **1065**
- getColumnCount method of `TableModel` **1060**, 1065
- getColumnName method of `ResultSetMetaData` **1065**
- getColumnName method of `TableModel` **1060**, 1065
- getColumnType method of `ResultSetMetaData` **1058**
- getConnection method of `DriverManager` **1057**
- getContentPane method of class `JFrame` **502**
- getDescent method of class `FontMetrics` 562
- getFamily method of class `Font` 558, **561**
- getFileName method of class `StackTraceElement` **453**
- getFileName method of interface `Path` **640**
- getFont method of class `Graphics` **559**
- getFontMetrics method of class `FontMetrics` **561**
- getFontMetrics method of class `Graphics` 562
- getGreen method of class `Color` **552**, 554
- getHeight method of class `FontMetrics` 562
- getHeight method of class `JPanel` **106**
- getIcon method of class `JLabel` **476**
- getInstalledLookAndFeels method of class `UIManager` **921**
- getInt method of `ResultSet` **1059**
- getKeyChar method of class `KeyEvent` **520**
- getKeyCode method of class `KeyEvent` **520**
- getKeyModifiersText method of class `KeyEvent` **520**
- getKeyText method of class `KeyEvent` **520**
- getLastModifiedTime method of class `Files` **640**
- getLeading method of class `FontMetrics` 562
- getLineNumber method of class `StackTraceElement` **453**
- getMessage method of class `Throwable` **453**
- getMethodName method of class `StackTraceElement` **453**
- getMinimumSize method of class `Component` 908
- getModifiers method of class `InputEvent` **520**
- getName method of class `Class` 380, **410**
- getName method of class `Font` 558, **559**
- getObject method of interface `ResultSet` **1059**, 1065
- getPassword method of class `JPasswordField` **482**
- getPercentInstance method of class `NumberFormat` **1018**, 1121
- getPoint method of class `MouseEvent` **516**
- getPreferredSize method of class `Component` 907
- getProperty method of class `Properties` **710**
- getRed method of class `Color` **552**, 554
- getResource method of class `Class` **476**
- getRow method of interface `ResultSet` **1066**
- getRowCount method of interface `TableModel` **1060**, 1065
- getSelectedFile method of class `JFileChooser` **663**
- getSelectedIndex method of class `JComboBox` **500**
- getSelectedIndex method of class `JList` **503**
- getSelectedText method of class `JTextComponent` **533**
- getSelectedValuesList method of class `JList` **505**
- getSize method of class `Font` 558, **559**
- getSource method of class `EventObject` 482
- getStackTrace method of class `Throwable` **453**
- getStateChange method of class `ItemEvent` **500**
- getStyle method of class `Font` 558, **561**
- getText method 1123
- getText method of class `JLabel` **476**
- getText method of class `JTextComponent` 917
- getText method of class `TextInputControl` 1123
- getCurrencyCInstance method of class `NumberFormat` **339**
- getValue method of class `JSlider` **908**
- getValueAt method of interface `TableModel` **1060**, 1065
- getWidth method of class `JPanel` **106**
- getX method of class `MouseEvent` **510**
- getY method of class `MouseEvent` **510**
- GIF (Graphics Interchange Format) 476
- gigabyte 5
- GitHub 14
- glass pane 502
- Global Warming Facts Quiz exercise 163
- golden mean **775**
- golden ratio **775**
- Google Maps 26
- Google Play **15**
- Gosling, James 17
- goto elimination 74
- goto statement **74**
- GPS device 5
- gradient **576**
- GradientPaint class **548**, 576, 585
- graph 161
- graph information 218
- graphical user interface (GUI) **60**, 424, **466**, **1100**
  - component **60**
  - design tool **521**
- graphics 514
- Graphics class **104**, 192, 241, 426, 427, **515**, 548, 550, 573
  - clearRect method 564
  - draw3DRect method 564, **567**
  - drawArc method **567**, 584
  - drawLine method **106**, 564
  - drawOval method 564, **567**
  - drawPolygon method 570, **572**
  - drawPolyline method 570, **572**
  - drawRect method 564, 577, 584
  - drawRoundRect method **565**
  - drawString method **554**
  - fill3DRect method 564, **567**
  - fillArc method **567**
  - fillOval method **192**, **516**, 564, **567**

Graphics class (cont.)  
   fillPolygon method 570, **573**  
   fillRect method **192**, **552**, 564, 577  
   fillRoundRect method **565**  
   getColor method 552  
   getFont method **559**, 559  
   getFontMetrics method 562  
   setColor method **193**, 577  
   setFont method **559**  
 graphics context **550**  
 graphics in a platform-independent manner 550  
 Graphics Interchange Format (GIF) 476  
 Graphics2D class **548**, **573**, 577, 580, 584  
   draw method **576**  
   fill method **576**, 577, 580, 585  
   rotate method **580**  
   setPaint method **576**  
   setStroke method **576**  
   translate method **580**  
 greatest common divisor (GCD) 205, 798  
   exercise 798  
 greedy quantifier **621**  
 grid 528  
 grid for GridBagLayout layout manager 934  
 Grid Using Class Line2D.Double  
   exercise 584  
 Grid Using Class  
   Rectangle2D.Double exercise 584  
 Grid Using Method drawLine exercise 584  
 Grid Using Method drawRect exercise 584  
 GridBagConstraints class **935**, 940, 941  
   anchor field **935**  
   BOTH constant **936**  
   CENTER constant **935**  
   EAST constant **935**  
   gridheight field **936**  
   gridwidth field **936**  
   gridx field **936**  
   gridy field **936**  
   HORIZONTAL constant **936**  
   instance variables 935  
   NONE constant **936**  
   NORTH constant **935**  
   NORTHEAST constant **935**  
   NORTHWEST constant **935**  
   RELATIVE constant **941**  
   REMAINDER constant **941**  
   SOUTH constant **935**  
   SOUTHEAST constant **935**  
   SOUTHWEST constant **935**  
   VERTICAL constant **936**  
   weightx field **936**  
   weighty field **936**  
   WEST constant **935**  
 GridBagConstraints constants  
   RELATIVE and REMAINDER 941  
 GridLayout class 931, **934**, 936, 941  
   setConstraints method **941**  
 GridBagLayout layout manager 937

gridheight field of class  
   GridBagConstraints **936**  
 GridLayout class 521, **528**  
 GridLayout containing six buttons 528  
 GridPane class (JavaFX) **1111**, 1111  
   add rows or columns 1115  
   Hgap property 1117  
   Vgap property 1117  
 gridwidth field of class  
   GridBagConstraints **936**  
 gridx field of class  
   GridBagConstraints **936**  
 gridy field of class  
   GridBagConstraints **936**  
 gross pay 116  
 GROUP BY 1044  
 group method of class Matcher 624  
 grouping separator (formatted output) **131**  
 groupingBy method of class  
   Collectors (Java SE 8) **747**, 748, 752, 754  
 guard condition in the UML 77  
 guarding code with a lock **960**  
 “guess the number” game 205, 543  
 GUI (Graphical User Interface) 424  
   component **466**  
   design tool **521**  
 GUI (Graphical User Interface)  
   component **1100**  
   ImageView (JavaFX) **1103**  
   Label (JavaFX) **1103**  
   Label class (JavaFX) **1103**  
   naming convention 1114  
   Slider (JavaFX) 1110, **1112**  
   TextField (JavaFX) **1112**  
   TextField class (JavaFX) **1112**  
 guillemets (« and ») **279**

## H

half word 263  
 handle an exception 438  
 hard drive 4, 6  
 hardcopy printer 21  
 hardware **2**, 4, 9  
 has-a relationship **324**, **354**  
 hash table 703, 707  
 hashCode method of Object 379  
 hashing **706**  
 HashMap class **706**  
   keySet method **710**  
 HashSet class **703**  
 Hashtable class **706**, 707  
 hash-table collisions 707  
 hasNext method  
   of class Scanner **137**, 646  
   of interface Iterator **683**, 686  
 hasPrevious method of  
   ListIterator **686**  
 head of a queue **862**, 882  
 headSet method of class TreeSet **704**  
 heavyweight components **472**  
 height **561**  
 height of a rectangle in pixels 552  
 helper method **311**, 890  
 heuristic 254  
 hexadecimal (base 16) number system  
   206, 263

Hgap property of a GridPane 1117  
 hidden fields 187  
 hide a dialog 469  
 hide implementation details 166, 313  
 HIDE\_ON\_CLOSE constant of interface  
   WindowConstants 908  
 hierarchical boss-method/worker-method  
   relationship 167  
 Hierarchy window in NetBeans 1106, 1107  
 high-level language **10**  
 hold a lock 960  
 Home key 517  
 Hopper, Grace 15  
 HORIZONTAL constant of class  
   GridBagConstraints **936**  
 horizontal coordinate **103**, **548**  
 horizontal gap space **526**  
 horizontal glue **934**  
 horizontal JSlider component 905  
 horizontal scrollbar policy 534  
 horizontal tab 43  
 HORIZONTAL\_SCROLLBAR\_ALWAYS  
   constant of class JScrollPane **534**  
 HORIZONTAL\_SCROLLBAR\_AS\_NEEDED  
   constant of class JScrollPane **534**  
 HORIZONTAL\_SCROLLBAR\_NEVER  
   constant of class JScrollPane **534**  
 hot spots in bytecode 20  
 HourlyEmployee class derived from  
   Employee 401  
 HTML (HyperText Markup Language)  
   **26**  
 HTTP (HyperText Transfer Protocol) **26**  
 hue **557**  
 HugeInteger Class 350  
   exercise 350  
 HyperText Markup Language (HTML)  
   **26**  
 HyperText Transfer Protocol (HTTP) **26**  
 hypotenuse of a right triangle 203

## I

I/O performance enhancement 666  
 IBM Corporation 15  
 icon 470  
 Icon interface **476**  
 IDE (integrated development  
   environment) **18**  
 identifier 37, 46  
 identifiers  
   came case naming 171, 268  
 identity column 1040, 1075  
 IDENTITY keyword (SQL) **1040**  
 identity method of functional interface  
   Function (Java SE 8) 754  
 identity value in a reduction (Java SE 8)  
   **732**  
 IEEE 754 ([grouper.ieee.org/groups/754/](http://grouper.ieee.org/groups/754/)) 1139  
 IEEE 754 floating point 1139  
 if single-selection statement **54**, 76, 77, 134, 152, 1138  
   activity diagram 77  
 if...else double-selection statement 76, 77, 78, 91, 134, 152  
   activity diagram 78  
 ignoring array element zero 222

- IllegalArgumentException class 310
- IllegalMonitorStateException class 980, 995
- IllegalStateException class 649
- Image property of a ImageView 1108, 1109
- ImageIcon class 382, 476
- ImageView class (JavaFX) 1103
  - Fit Width property 1109
  - Image property 1108, 1109
- imaginary part 348
- immutability 724
- immutable 591
- immutable data 960
- immutable object 333
- immutable String object 591
- implement an interface 389, 413, 421
- implementation-dependent code 313
- implementation of a function 399
- implements 12
- implements 1138
- implements keyword 413, 418
- implements multiple interfaces 507
- implicit conversion 94
- import declaration 45, 48, 274, 1138
- improve performance of bubble sort 828
- in parallel 950
- increment 129
  - a control variable 123
  - expression 141
  - of a for statement 127
  - operator, ++ 100
- increment a control variable 122
- increment and decrement operators 100
- indefinite postponement 955, 999, 1035
- indefinite repetition 88
- indentation 78, 80
- index (subscript) 211, 220
- index of a JComboBox 499
- index zero 211
- indexed lists 902
- indexOf method of class
  - ArrayList<T> 238
- indexOf method of class String 597
- IndexOutOfBoundsException class 695
- IndexOutOfRangeException class 223
- indirect recursion 770
- indirect recursive call 770
- indirect superclass 353, 355
- infer a type with the diamond (<>) notation 241
- infer parameter types in a lambda 730
- infinite loop 82, 93, 126
- infinite recursion 378, 773, 779, 781
- infinite series 161
- infinite stream (Java SE 8) 754, 754
- infinity symbol 1043
- infix notation 897
- infix-to-postfix conversion algorithm 897
- information hiding 12, 275
- inherit 105
- inheritance 12, 105, 353
  - examples 354
  - extends keyword 357, 368
  - hierarchy 354, 395
- inheritance (cont.)
  - hierarchy for university CommunityMembers 355
  - multiple 353
  - single 353
- initial state 149
- initial state in the UML 75
- initial value of control variable 122
- initialization phase 88
- initialize a controller's instance variables 1119
- initialize a variable in a declaration 47
- initialize method of a JavaFX
  - controller class 1123
- initializer list 214
- initializing two-dimensional arrays in
  - declarations 229
- initiate an action 910
- inlining method calls 320
- inner class 480, 493, 515, 916
  - anonymous 499, 1124
  - object of 493
  - relationship between an inner class and its top-level class 493
- INNER JOIN SQL clause 1044, 1049
- innermost set of brackets 221
- inorder traversal 886
- input data from the keyboard 61
- input device 5
- input dialog 60, 468
- input/output operation 75, 258
- input/output package 176
- input unit 5
- InputEvent class 506, 513, 517
  - getModifiers method 520
  - isAltDown method 513, 520
  - isControlDown method 520
  - isMetaDown method 513, 520
  - isShiftDown method 520
- InputMismatchException class 437, 440
- InputStream class 655, 665, 713
- InputStreamReader class 668
- insert method of class
  - StringBuilder 609
- INSERT SQL statement 1044, 1050
- insertion point 237, 697, 864
- insertion sort 816
  - algorithm 816, 819
- Inspector window in NetBeans 1107
- instance 11
- instance (non-static) method 331
- instance method reference (Java SE 8) 739
- instance methods 173, 268
- instance variable 12, 268, 279
- instance variables 268
- instanceof operator 409, 1138
- Instant class
  - now method 1018
- Instant class (Java SE 8) 1025
- instruction execution cycle 261
- instructor resources for *Java How to Program, 10/e xxxv*
- int primitive type 47, 91, 100, 134, 1138, 1139
  - promotions 175
- IntBinaryOperator functional interface (Java SE 8) 732
  - applyAsInt method 732
- IntConsumer functional interface (Java SE 8) 730
  - accept method 730
- integer 44
  - array 214
  - division 86
  - quotient 51
  - value 47
- Integer class 235, 470, 679, 853
  - parseInt method 235, 470
- integer division 51
- integerPower method 203
- integer suffix L 701
- integral expression 139
- integrated development environment (IDE) 18
- intelligent consumer electronic device 17
- IntelliJ IDEA 18
- Interactive Drawing Application exercise 544
- interest rate 129
- interface 12, 389, 414, 422, 1058
  - declaration 413
  - implementing more than one at a time 507
  - tagging interface 655
- interface keyword 413, 1138
- Interfaces 413
  - ActionListener 481, 486
  - AutoCloseable 330, 459, 1057
  - BiConsumer functional interface (Java SE 8) 747, 754
  - BinaryOperator functional interface (Java SE 8) 725
  - BlockingQueue 976
  - CachedRowSet 1072
  - Callable 1022
  - CallableStatement 1090
  - ChangeListener 908
  - ChangeListener (JavaFX) 1113, 1120, 1124
  - CharSequence 623
  - Collection 678, 679, 688
  - Collector functional interface (Java SE 8) 737
  - Comparable 423, 595, 689, 837, 890
  - Comparator 689, 690, 740
  - ComponentListener 511
  - Condition 995, 996
  - Connection 1057, 1059, 1064
  - Consumer functional interface (Java SE 8) 725, 730, 743
  - ContainerListener 511
  - DataInput 666
  - DataOutput 666
  - default methods (Java SE 8) 424
  - DirectoryStream 639
  - DoubleStream functional interface (Java SE 8) 728
  - EventHandler<ActionEvent> (JavaFX) 1123
  - Executor 955
  - ExecutorService 956, 1022
  - FocusListener 511
  - Function functional interface (Java SE 8) 725, 739
  - Future 1022
  - Icon 476

- Interfaces (cont.)
  - IntBinaryOperator** functional interface (Java SE 8) **732**
  - IntConsumer** functional interface (Java SE 8) **730**
  - IntFunction** functional interface (Java SE 8) **1019**
  - IntPredicate** functional interface (Java SE 8) **733**
  - IntStream** functional interface (Java SE 8) **728**
  - IntToDoubleFunction** functional interface (Java SE 8) **1019**
  - IntToLongFunction** functional interface (Java SE 8) **1019**
  - IntUnaryOperator** functional interface (Java SE 8) **734**, **1019**
  - ItemListener** **493**, **916**
  - Iterator** **679**
  - JdbcRowSet** **1072**
  - KeyListener** **486**, **511**, **517**
  - LayoutManager** **520**, **524**
  - LayoutManager2** **524**
  - List** **678**, **686**
  - ListIterator** **680**
  - ListSelectionListener** **502**
  - Lock** **994**
  - LongStream** functional interface (Java SE 8) **728**
  - Map** **678**, **706**
  - Map.Entry** **752**
  - MouseInputListener** **505**, **510**
  - MouseListener** **486**, **505**, **511**, **920**
  - MouseMotionListener** **486**, **505**, **510**, **511**
  - MouseWheelListener** **507**
  - ObjectInput** **654**
  - ObjectOutput** **654**
  - ObservableValue** (JavaFX) **1121**
  - Path** **639**
  - Predicate** functional interface (Java SE 8) **725**, **743**
  - PreparedStatement** **1090**
  - PropertyChangeListener** **1016**
  - Queue** **678**, **702**, **976**
  - ResultSet** **1058**
  - ResultSetMetaData** **1058**
  - RowSet** **1072**
  - Runnable** **955**, **424**
  - Serializable** **424**, **655**
  - Set** **678**, **703**
  - SortedMap** **706**
  - SortedSet** **704**
  - Statement** **1059**
  - static methods** (Java SE 8) **425**
  - Stream** (Java SE 8) **726**, **736**
  - Supplier** **1022**, **1025**
  - Supplier** functional interface (Java SE 8) **725**
  - SwingConstants** **476**, **908**
  - TableModel** **1059**
  - ToDoubleFunction** functional interface (Java SE 8) **749**
  - UnaryOperator** functional interface (Java SE 8) **725**
  - WindowConstants** **908**
  - WindowListener** **510**, **511**, **909**, **1071**
- intermediate operation** **733**
- intermediate operations**
  - stateful** **734**
  - stateless** **734**
- intermediate stream operations** (Java SE 8)
  - filter** method of interface **IntStream** **733**
  - filter** method of interface **Stream** **737**, **740**
  - flatMap** method of interface **Stream** **752**
  - map** method of interface **IntStream** **734**
  - map** method of interface **Stream** **739**
  - sorted** method of interface **IntStream** **733**
  - sorted** method of interface **Stream** **737**, **740**
- internal frame**
  - closable** **928**
  - maximizable** **928**
  - minimizable** **928**
  - resizable** **928**
- internal iteration** **724**
- internationalization** **339**, **1112**
- Internet** **25**
- Internet domain name in reverse order** **875**
- Internet Explorer** **59**
- Internet of Things (IoT)** **27**
- interpreter** **10**
- interrupt** method of class **Thread** **957**
- InterruptedException** class **957**
- intersection of two sets** **349**
- IntFunction** functional interface (Java SE 8) **1019**
- IntPredicate** functional interface (Java SE 8) **733**
  - test** method **733**, **734**
- intrinsic lock** **960**
- ints** method of class **SecureRandom** (Java SE 8) **754**
- IntStream** interface (Java SE 8) **728**
  - average** method **731**
  - boxed** method **754**
  - count** method **731**
  - filter** method **733**
  - forEach** method **730**
  - map** method **734**
  - max** method **731**
  - min** method **731**
  - of** method **730**
  - range** method **735**
  - rangeClosed** method **735**
  - reduce** method **731**
  - sorted** method **733**
  - sum** method **731**
- IntToDoubleFunction** functional interface (Java SE 8) **1019**
- IntToLongFunction** functional interface (Java SE 8) **1019**
- IntUnaryOperator** functional interface (Java SE 8) **734**, **1019**
  - applyAsInt** method **734**
- invoke a method** **166**
- IOException** class **659**
- iOS** **13**
- is-a** relationship **354**, **390**
- isAbsolute** method of interface **Path** **640**
- isActionKey** method of class **KeyEvent** **520**
- isAltDown** method of class **InputEvent** **513**, **520**
- isBold** method of class **Font** **558**, **561**
- isCancelled** method of class **SwingWorker** **1012**
- isControlDown** method of class **InputEvent** **520**
- isDefined** method of class **Character** **612**
- isDigit** method of class **Character** **612**
- isDirectory** method of class **Files** **640**
- isEmpty** method
  - ArrayList** **324**
  - Map** **710**
  - Stack** **702**
- isItalic** method of class **Font** **558**, **561**
- isJavaIdentifierPart** method of class **Character** **612**
- isJavaIdentifierStart** method of class **Character** **612**
- isLetter** method of class **Character** **612**
- isLetterOrDigit** method of class **Character** **612**
- isLowerCase** method of class **Character** **612**
- isMetaDown** method of class **InputEvent** **513**, **520**
- isPlain** method of class **Font** **558**, **561**
- isPopupTrigger** method of class **MouseEvent** **920**
- isSelected** method
  - AbstractButton** **917**
  - JCheckBox** **493**
- isShiftDown** method of class **InputEvent** **520**
- isUpperCase** method of class **Character** **612**
- ITALIC** constant of class **Font** **559**
- ItemEvent** class **493**, **496**
  - getStateChange** method **500**
- ItemListener** interface **493**, **916**
  - itemStateChanged** method **493**, **917**
- itemStateChanged** method of interface **ItemListener** **493**, **917**
- iteration** **86**, **779**
  - of a loop **122**, **141**
- iteration (looping)**
  - of a for loop **221**
- iteration statements** **76**
- iterative (non-recursive)** **771**
- iterative factorial solution** **780**
- iterator** **677**
  - fail fast** **683**
- Iterator** interface **679**
  - hasNext** method **683**
  - next** method **683**
  - remove** method **683**
- iterator** method of **Collection** **683**

# J

- Jacopini, G. 74
- JApplet class 909
- java .time package **313**
- Java 2D API 548, **573**
- Java 2D shapes 573
- Java 2D Shapes package **176**
- Java Abstract Window Toolkit Event package **176**
- Java API 165
  - overview 177
- Java API documentation 49, 177
  - download 50
  - online 49
- Java Application Programming Interface (Java API) 17, **45**, 165, 176
- Java class library 17, **45**, **165**
- java command 19, 21, **35**
- Java compiler **18**
- Java Concurrency Package **177**
- Java Database Connectivity (JDBC) **1038**
- Java DB 1038, **1052**
  - embedded 1052
- Java DB Developer's Guide 1040
- Java debugger 1141
- Java development environment 18, 19, 20
- Java Development Kit (JDK) 39
- Java Enterprise Edition (Java EE) **3**
  - .java extension **18**
  - .java file name extension 268
- Java fonts
  - Dialog 559
  - DialogInput 559
  - Monospaced 559
  - SansSerif 559
  - Serif 559
- Java HotSpot compiler **20**
- Java How to Program, 8/e*
  - instructor resources xxxv
- Java Input/Output Package **176**
- java interpreter 40
- Java Keywords 1138
- Java Language Package **176**
- Java Micro Edition (Java ME) **4**
- Java Networking Package **176**
- Java Persistence API (JPA) 1039
- Java programming language 14
- Java SE 6
  - package overview 177
- Java SE 7
  - ConcurrentLinkedDeque 1002
  - fork/join framework 1026
  - LinkedTransferQueue 1002
  - type inference with the <> notation 683
- Java SE 7 (Java Standard Edition 7) **3**
- Java SE 8 210, 224, 238, 294, 313, 1019, 1022
  - @FunctionalInterface annotation 756
  - anonymous onner classes with lambdas 500
  - Arrays method parallelSort 238
  - BinaryOperator functional interface 725
  - Collector functional interface **737**
- Java SE 8 (cont.)
  - Collectors class **737**
  - CompletableFuture class **1022**
  - Consumer functional interface 725, 730, 743
  - Date/Time API 238, **313**
  - Date/Time API 177
  - default interface methods 424
  - default method in an interface 724, 755
  - default method of an interface 723
  - default methods in interfaces **424**
  - doubles method of class SecureRandom **754**
  - effectively final 499
  - Function functional interface 725, 739
  - functional interface **425**
  - functional interfaces 725
  - @FunctionalInterface annotation **756**
  - implementing event listeners with lambdas 483, 904
  - Instant class **1025**
  - IntBinaryOperator functional interface **732**
  - IntConsumer functional interface **730**
  - IntFunction functional interface 1019
  - IntPredicate functional interface **733**
  - ints method of class SecureRandom **754**
  - IntToDoubleFunction functional interface 1019
  - IntToLongFunction functional interface 1019
  - IntUnaryOperator functional interface **734**, 1019
  - java.util.function package 724, **730**
  - java.util.stream package **728**
  - lambdas **425**
  - lambdas and streams with regular expressions 625
  - lines method of class Files **751**
  - longs method of class SecureRandom **754**
  - Optional 744
  - OptionalDouble class **731**
  - Predicate functional interface 725, 737, 740, 743
  - reversed method of interface Comparator **740**
  - static interface methods 425
  - static method in an interface 724, 755
  - static method of an interface 723
  - Stream interface **736**
  - Supplier functional interface 725
  - Supplier interface **1022**, 1025
  - ToDoubleFunction functional interface **749**
  - UnaryOperator functional interface 725
- Java SE 8 (Java Standard Edition 8) **3**
- Java SE 8 Development Kit (JDK) 17
- Java Security Package **176**
- Java Standard Edition (Java SE)
  - 63**
  - 83**
- Java Standard Edition 7 (Java SE 7) **3**
- Java Standard Edition 8 (Java SE 8) **3**
- Java Swing Event Package **177**
- Java Swing GUI Components Package **177**
- Java Utilities Package **177**
- Java Virtual Machine (JVM) **19**, 35, 38
- JAVA\_HOME environment variable 1053
- java.awt package **471**, 550, 551, 570, 573, 908, 920
- java.awt.color package 573
- java.awt.event package 176, 177, **483**, 485, 510, 520
- java.awt.font package 573
- java.awt.geom package 176, 573
- java.awt.image package 573
- java.awt.image.renderable package 573
- java.awt.print package 573
- java.beans package 1016
- java.io package 176, **638**
- java.lang package **48**, 168, 176, 357, 379, 589, 955
  - imported in every Java program 48
- java.math package 95, **338**, 773, 1120
- java.net package 176
- java.nio.file package 637, **638**, 639, 751
- java.security package 178
- java.sql package 176, 1055, 1058
- java.text package **338**, **1112**, 1120
- java.time package 177
- java.util package **45**, 177, 238, 678, 700, 864
- java.util.concurrent package 177, 956, 976, 1001, 1022
- java.util.concurrent.locks package 994, 995
- java.util.function package (Java SE 8) 724, **730**
- java.util.prefs package **710**
- java.util.regex package 589
- java.util.stream package (Java SE 8) **728**
- Java™ Language Specification 52
- Java2D API 573
- javac compiler **18**, 40
- javacdeprecation flag 46
- Javadoc comment 36
- javadoc utility program **36**
- JavaFX 466, **1100**
  - @FXML annotation 1121, **1122**
  - ActionEvent class 1121, 1123
  - alignment in a VBox **1108**
  - Application class **1111**
  - Cascading Style Sheets (CSS) 1101
  - ChangeListener interface **1113**, 1120, 1124
  - controller class **1103**, **1113**
  - DoubleProperty class 1124
  - EventHandler<ActionEvent> interface **1123**
  - fxid property **1114**
  - FXML (FX Markup Language) **1102**
  - FXMLLoader class **1113**, 1119
  - GridPane class **1111**, 1111

- JavaFX (cont.)
  - ImageView class **1103**
  - Label class **1103**
  - Max Width property 1117
  - node **1102**
  - Node class **1102**
  - padding 1117
  - Padding property 1117
  - Parent class **1114**, 1119
  - Pref Height property of a component 1108
  - Pref Width property 1116
  - Pref Width property of a component 1108
  - preferred size **1108**
  - register event handlers 1119
  - scene **1102**
  - Scene class **1102**, 1111, 1119, 1120
  - scene graph **1102**
  - Slider class 1110, **1112**
  - stage **1102**
  - Stage class **1102**, 1111, 1119, 1120
  - TextField class **1112**
  - Vbox class **1107**
- JavaFX FXML Application NetBeans project 1103
- JavaFX Scene Builder **1101**, 1103
  - change the default layout 1107, 1115
- JavaFX Script 1100
- javafx.application.Application package **1111**
- javafx.beans.value package 1120, 1124
- javafx.event package 1121
- javafx.fxml package 1121
- javafx.scene package 1102, **1114**, **1119**
- javafx.scene.control package 1112, 1121
- javafx.scene.layout package 1107, **1111**
- javafx.stage package 1102
- JavaScript 1100
- javax.sql.rowset package **1072**
- javax.swing package **60**, 177, **466**, 468, 476, 485, 487, 532, 555, 908, 921, 927
- javax.swing.event package 177, **484**, 502, 510, 908
- javax.swing.table package 1060, **1071**
- JAX-WS package 177
- JButton class 471, **487**, 490, 526
- JCheckBox buttons and item events 491
- JCheckBox class 471, **490**
  - isSelected method **493**
- JCheckBoxMenuItem class 909, **910**, 916
- JColorChooser class **555**, 557
  - showDialog method **556**
- JColorChooser Dialog exercise 585
- JComboBox class 471, **496**, 936
  - getSelectedIndex method **500**
  - setMaximumRowCount method **499**
- JComboBox that displays a list of image names 497
- JComponent class **472**, 473, 475, 485, 497, 500, 514, 530, 548, 550
  - paintComponent method **105**, **514**, 548, 905, 907
  - repaint method **551**
  - setForeground method **916**
  - setOpaque method **514**, 516
  - setToolTipText method **475**
- jdb command **1143**
- JDBC
  - API **1038**, 1055, 1090
  - driver **1038**
- JDBC Package **176**
- jdbc Derby:books 1057
- JdbcRowSet interface **1072**
  - close method **1074**
  - execute method **1074**
  - setCommand method **1074**
  - setPassword method **1074**
  - setUrl method **1072**
  - setUsername method **1074**
- JDesktopPane class **925**, 948
- JDesktopPane documentation 928
- JDialog class **915**
- JDK 17, 39
- JFileChooser class **662**
  - CANCEL\_OPTION constant **663**
  - FILES\_AND\_DIRECTORIES constant **662**
  - FILES\_ONLY constant **662**
  - getSelectedFile method **663**
  - setFileSelectionMode method **662**
  - showOpenDialog method **662**
- JFrame class **106**, 194, 908
  - add method **106**, **475**
  - EXIT\_ON\_CLOSE 477
  - getContentPane method **502**
  - setDefaultCloseOperation method **106**, **477**, **908**
  - setJMenuBar method **909**, 916
  - setSize method **106**, **477**
  - setVisible method **106**, **477**
- JFrame class EXIT\_ON\_CLOSE constant **106**
- JFrame.EXIT\_ON\_CLOSE 477
- JInternalFrame class **925**, 927
- JInternalFrame documentation 928
- JLabel class **380**, 382, 471, **473**
  - getIcon method **476**
  - getText method **476**
  - setHorizontalAlignment method **476**
  - setHorizontalTextPosition method **476**
  - setIcon method **476**
  - setText method **476**
  - setVerticalAlignment method **476**
  - setVerticalTextPosition method **476**
- JList class 471, 500
  - addListSelectionListener method **502**
  - getSelectedIndex method **503**
  - getSelectedValuesList method **505**
  - setFixedCellHeight method **505**
  - setFixedCellWidth method **505**
- JList class (cont.)
  - setListData method **505**
  - setSelectionMode method **502**
  - setVisibleRowCount method **502**
- JMenu class **909**, 916, 927
  - add method **915**
  - addSeparator method **916**
- JMenuBar class **909**, 916, 927
  - add method **916**
- JMenuItem class **910**, 927
- JMenus and mnemonics 910
- JOIN\_ROUND constant of class BasicStroke **578**
- joining database tables **1043**, 1049
- Joint Photographic Experts Group (JPEG) 476
- JOptionPane class **59**, 60, **468**, 469, 945
  - constants for message dialogs 471
  - PLAIN\_MESSAGE constant **470**
  - showInputDialog method **61**, **469**
  - showMessageDialog method **60**, **470**
- JOptionPane constants for message dialogs
  - JOptionPane.ERROR\_MESSAGE 471
  - JOptionPane.INFORMATION\_MESSAGE 471
  - JOptionPane.PLAIN\_MESSAGE 471
  - JOptionPane-Pane.QUESTION\_MESSAGE 471
  - JOptionPane.WARNING\_MESSAGE 471
- JPanel class **104**, 105, 471, 514, 521, 530, 905
  - getHeight method **106**
  - getWidth method **106**
- JPasswordField class **477**, 482
  - getPassword method **482**
- JPEG (Joint Photographic Experts Group) 476
- JPopupMenu class **917**
  - show method **920**
- JProgressBar class 1013
- JRadioButton class **490**, 493, 496
- JRadioButtonMenuItem class 909, **910**, 917
- JScrollPane class **502**, 505, 533, 534
  - HORIZONTAL\_SCROLLBAR\_ALWAYS constant **534**
  - HORIZONTAL\_SCROLLBAR\_AS\_NEEDED constant **534**
  - HORIZONTAL\_SCROLLBAR\_NEVER constant **534**
  - setHorizontalScrollBarPolicy method **534**
  - setVerticalScrollBarPolicy method **534**
  - VERTICAL\_SCROLLBAR\_ALWAYS constant **534**
  - VERTICAL\_SCROLLBAR\_AS\_NEEDED constant **534**
  - VERTICAL\_SCROLLBAR\_NEVER constant **534**
- JScrollPane scrollbar policies 534

**JSlider** class **904**, **905**, **908**  
     block increment **905**  
     getValue method **908**  
     major tick marks **904**  
     minor tick marks **904**  
     setInverted method **905**  
     setMajorTickSpacing method **908**  
     setPaintTicks method **908**  
     snap-to ticks **904**  
     thumb **904**  
     tick marks **904**  
**JTabbedPane** class **928**, **934**  
     addTab method **930**  
     SCROLL\_TAB\_LAYOUT constant **934**  
     TOP constant **934**  
**JTable** class **1059**  
     RowFilter **1071**  
     setRowFilter method **1071**  
     setRowSorter method **1071**  
     TableRowSorter **1071**  
**JTextArea** class **520**, **531**, **533**, **936**, **939**  
     setLineWrap method **534**  
**JTextComponent** class **477**, **480**, **531**, **533**  
     getSelectedText method **533**  
     getText method **917**  
     setDisabledTextColor method **520**  
     setEditable method **480**  
     setText method **533**  
**JTextField** class **471**, **477**, **485**, **531**  
     addActionListener method **481**  
**JTextFields** and **JPasswordField** **478**  
**JToggleButton** class **490**  
   just-in-time compilation **20**  
   just-in-time (JIT) compiler **20**

## K

  Kelvin temperature scale **543**  
   kernel **13**  
   key constant **520**, **520**  
   key event **486**, **517**  
   Key event handling **517**  
   key value **892**  
   key-value pair **707**  
   KeyAdapter class **511**  
   keyboard **4**, **44**, **466**, **1100**  
   KeyEvent class **486**, **517**  
     getKeyChar method **520**  
     getKeyCode method **520**  
     getKeyModifiersText method **520**  
     getKeyText method **520**  
     isActionKey method **520**  
   KeyListener interface **486**, **511**, **517**  
     keyPressed method **517**, **520**  
     keyReleased method **517**  
     keyTyped method **517**  
   keyPressed method of interface **KeyListener** **517**, **520**  
   keyReleased method of interface **KeyListener** **517**  
   keySet method  
     of class **HashMap** **710**  
     of class **Properties** **713**

  keyTyped method of interface **KeyListener** **517**  
   keyword **37**, **76**  
   Keywords  
     abstract **394**  
     boolean **81**, **1146**  
     break **137**  
     case **137**  
     catch **440**  
     char **47**  
     class **37**, **268**  
     continue **140**  
     default **137**  
     do **76**, **132**  
     double **47**, **92**, **171**  
     else **76**  
     enum **186**  
     extends **105**, **357**, **368**  
     false **81**, **1138**  
     final **139**, **169**, **216**, **960**  
     finally **440**  
     float **47**, **92**  
     for **76**, **124**  
     if **76**  
     implements **413**  
     import **45**  
     instanceof **409**  
     int **47**  
     interface **413**  
     new **47**, **212**, **213**, **271**  
     null **212**, **276**, **1138**  
     private **268**, **313**, **323**  
     public **37**, **171**, **268**, **313**  
     reserved but not used by Java **1138**  
     return **166**, **172**, **174**, **267**  
     static **60**, **131**, **167**  
     super **356**, **379**  
     switch **76**  
     synchronized **960**  
     table of Keywords and reserved words **1138**  
     this **269**, **314**, **331**  
     throw **450**  
     true **81**, **1138**  
     try **439**  
     void **38**, **171**  
     while **76**, **132**  
   Knight's Tour **253**, **585**  
     Brute Force Approach **255**  
     Closed Tour Test **256**  
     exercise **585**  
   Koch Curve fractal **783**  
   Koch Snowflake fractal **784**  
   Koenig, Andrew **434**

## L

  label **380**, **473**  
   Label class (JavaFX) **1103**  
     Font property **1108**  
     Text property **1108**  
   label in a switch **137**  
   labels for tick marks **904**  
   Lady Ada Lovelace **16**  
   lambda (Java SE 8) **425**  
   lambda expression  
     composing **734**  
     type of **725**  
   lambda expression (Java SE 8) **725**  
   lambda expressions  
     arrow token (**->**) **725**  
     event handler **755**  
     method references **726**  
     parameter list **725**  
     target type **730**  
     with an empty parameter list **726**  
   lambdas  
     implementing an event handler **1125**  
   lamda expressions  
     statement block **725**  
     type inference **730**  
   LAMP **28**  
   language package **176**  
   last-in, first-out (LIFO) **174**  
   last-in, first-out (LIFO) order **846**  
   last-in, first-out (LIFO) data structure **878**  
   last method of **ResultSet** **1066**  
   last method of **SortedSet** **705**  
   lastIndexOf method of class **String** **597**  
   late binding **409**  
   launch method of class **Application** (JavaFX) **1111**, **1119**  
   layout **382**  
   layout containers (JavaFX) **1103**  
   layout manager **475**, **510**, **520**, **529**  
     BorderLayout **510**  
     FlowLayout **475**  
     GridLayout **528**  
   layoutContainer method of interface **LayoutManager** **524**  
   LayoutManager interface **520**, **524**  
     layoutContainer method **524**  
   LayoutManager2 interface **524**  
   Layouts  
     GridPane **1111**  
     VBox **1107**  
   lazy **726**  
   lazy quantifier **621**  
   lazy stream operation (Java SE 8) **733**, **734**  
   leading **561**  
   leaf node **885**  
     in a binary search tree **890**  
   left brace, { **37**, **38**, **46**  
   left child **885**  
   LEFT constant of class **FlowLayout** **524**  
   left justified **78**, **130**, **476**, **522**  
   left-mouse-button click **513**  
   left subtree **885**, **890**, **900**  
   left-to-right evaluation **53**  
   Left, center and right mouse-button clicks **511**  
   length field of an array **211**  
   length instance variable of an array **211**  
   length method of class **String** **591**  
   length method of class **StringBuilder** **604**  
   letter **6**  
   level of indentation **78**  
   level-order binary tree traversal **892**, **900**  
   lexical scope **730**  
   lexicographical comparison **594**, **595**  
   Library window in NetBeans **1107**, **1108**  
   life cycle of a thread **952**, **954**  
   LIFO (last-in, first-out) **174**, **846**  
   lightweight GUI component **472**



- LIKE operator (SQL) **1045**
- LIKE SQL clause 1046, 1048
- Limericks 629
- line 548, 563, 572
- line join **576**
- line wrapping **534**
- Line2D class 548, 577
- Line2D.Double class **573**, 584
- linear collection 864
- linear data structure **885**
- linear run time **807**
- linear search algorithm **804**, 806, 812
- LinearGradientPaint class 576
- LineNumberReader class **668**
- lines method of class Files (Java SE 8) **751**
- LineTo method of class GeneralPath **580**
- link 864, 885
- link to another node **863**
- linked list **862**, 864
- LinkedBlockingDeque class 1002
- LinkedBlockingQueue class 1002
- LinkedList class **680**, 696, 719
  - add method **687**
  - addFirst method **688**
  - addLast method **687**
- LinkedTransferQueue class 1002
- Linux 13, 39, 645
- Linux operating system **14**
- list 499
- List interface 678, **686**, 689, 690, 694
  - add method **682**, 685
  - addAll method **685**
  - clear method **686**
  - get method **682**
  - listIterator method **686**
  - size method **682**, **686**
  - subList method **686**
  - toArray method **687**
- list method of Properties **712**
- listen for events **481**
- ListIterator interface **680**
  - hasPrevious method **686**
  - previous method **686**
  - set method **686**
- ListIterator method of interface List **686**
- ListSelectionEvent class **500**
- ListSelectionListener interface **502**
  - valueChanged method **502**
- ListSelectionMode class **502**
  - MULTIPLE\_INTERVAL\_SELECTION constant **502**, 505
  - SINGLE\_INTERVAL\_SELECTION constant **502**, 503, 505
  - SINGLE\_SELECTION constant **502**
- literals
  - floating point **92**
- “Lo fractal” at level 0 785
- “Lo fractal” at level 1, with C and D points determined for level 2 786
- “Lo fractal” at level 2 787
- “Lo fractal” at level 2, dashed lines from level 1 provided 786
- load factor **707**
- load method of class FXMLLoader (JavaFX) **1113**, **1119**
- load method of Properties **713**
- load/store operations 259
- loading **19**
- local variable 85, 187, **269**
- locale-specific currency Strings 339
- locale-specific String 338
- localization **472**
- location of a variable in the computer’s memory 50
- lock
  - acquire 960
  - hold 960
  - release 960
- lock an object 982, 983
- Lock interface **994**
  - lock method **994**, 999
  - newCondition method **995**, 996
  - unlock method **994**, 999
- lock method of interface Lock **994**, 999
- log method of Math 169
- logarithm 168
- logarithmic run time **812**
- logic error **18**, 48, **81**, 124, 1141
- logical complement operator, ! **144**
- logical decision 4
- logical input operations **667**
- logical negation, ! **144**
- logical negation, or logical NOT (!) operator truth table 145
- logical operators **142**, 144
- logical output operations **666**
- logical unit **5**
- logo language 252
- long
  - literal suffix L **701**
- Long class **679**
- long keyword 1138, 1139
- long promotions 175
- longs method of class SecureRandom (Java SE 8) **754**
- LongStream interface (Java SE 8) **728**
- look-and-feel **471**, 472, 520, 920
  - Nimbus **468**
- Look-and-Feel Observations overview xxxiv
- Look-and-feel of a Swing-based GUI 921
- look-and-feel of an application **471**
- look-and-feel 468
- LookAndFeelInfo nested class of class UIManager **921**
- lookingAt method of class Matcher **623**
- loop 83, 86
  - body 132
  - continuation condition **76**
  - counter 122
  - infinite **82**, 93
  - nested within a loop 96
  - statement **76**
- loop-continuation condition **122**, 123, 124, 125, 126, 128, 132, 133, 141
- looping **86**
- Lord Byron 16
- Lovelace, Ada 16
- lowercase letter 7, 37
- lowered rectangle **567**
- M**
  - m-by-n* array **228**
  - Mac OS X 13, 39, 645
  - machine dependent 9
  - machine language **9**
  - machine language programming 258
  - Macintosh look-and-feel 921
  - main method **38**, 39, 46
  - main thread **959**
  - maintainability 862
  - major tick marks of class JSlider 904
  - make your point (game of craps) 183
  - making decisions 61
  - Mandelbrot, Benoit 783
  - “manufacturing” section of the computer 6
  - many-to-many relationship **1043**
  - many-to-one mapping **706**
  - map elements of a stream (Java SE 8) 734
  - Map interface 678, **706**
    - containsKey method **709**
    - forEach method (Java SE 8) **747**
    - get method **709**
    - isEmpty method **710**
    - put method **709**
    - size method **710**
  - map method of interface InputStream (Java SE 8) **734**
  - map method of interface Stream (Java SE 8) 739
  - Map.Entry interface 752
  - mapToDouble method of interface Stream (Java SE 8) **748**
  - marker interfaces 414
  - mashups 26
  - master file 672
  - Matcher class 589, **623**
    - find method **623**
    - group method 624
    - lookingAt method **623**
    - matches method **623**
    - replaceAll method **623**
    - replaceFirst method **623**
  - matcher method of class Pattern **623**
  - matches method of class Matcher **623**
  - matches method of class Pattern **623**
  - matches method of class String **616**
  - matching catch block 440
  - Math class **131**, 167, 168
    - abs method 168
    - ceil method 168
    - cos method 168
    - E constant **169**
    - exp method 168
    - floor method 168
    - log method 169
    - max method 168
    - min method 168
    - PI constant **169**, 199
    - pow method **131**, 167, 168, 199
    - sqrt method **167**, 168, 175
    - tan method 168
  - Math.PI constant 69, 584
  - MathContext class 340
  - mathematical computations 15
  - max method of Collections **688**, **695**
  - max method of interface InputStream (Java SE 8) **731**
  - max method of Math 168

**Max** property of a `Slider` (JavaFX) 1118  
**Max Width** property of a JavaFX control 1117  
 maximize a window 473, 927  
 maximized internal frame 928  
 Maze Traversal Using Recursive Backtracking exercise 800  
 Mazes of Any Size exercise 801  
 MDI (Multiple Document Interface) 904, **925**  
 mean 52  
 memory 4, **5**  
 memory buffer 667  
 memory leak 330, 446  
 memory location 50  
 memory-space/execution-time trade-off 707  
 memory unit **5**  
 memory utilization 707  
 menu **467**, 531, **909**, 910  
 menu bar **467**, **909**  
 menu item **910**, 915  
 merge records from tables 1048  
 merge sort **819**  
 merge sort algorithm **819**, 824  
 merge symbol in the UML **82**  
 merge two arrays 819  
 message dialog **59**, **468**, 470  
     types 470  
*Meta* key 513  
 metadata **1058**  
 metal look-and-feel 904, **921**  
 method **11**, **38**  
     declaration 38  
     local variable 269  
     parameter **171**  
     parameter list **171**  
     signature **191**  
     static 131  
 method call **11**, 166, 172  
 method-call stack **174**  
 Method calls made within the call `fibonacci( 3 )` 778  
 Method calls on the program execution stack 778  
 method declaration 172  
 method header **171**  
 method names  
     came case naming 171, 268  
 method overloading **189**  
 method parameter list 231  
 method reference **739**  
 method reference (Java SE 8) 739  
 method references 726  
 methods implicitly final 412  
 Metric Conversion Program 632  
 Microsoft SQL Server 1038  
 Microsoft Windows 137, 908, 920  
 Microsoft Windows-style look-and-feel 921  
 middle mouse button 513  
 mileage obtained by automobiles 115  
**Miles-Per-Gallon Calculator** app exercise 1131  
 min method of `Collections` 688, **695**  
 min method of interface `InputStream` (Java SE 8) **731**  
 min method of `Math` 168  
 minimize a window 473, 909, 927

minimize internal frame 927  
 minor tick marks of class `JSlider` 904  
 minus sign (-) formatting flag **130**  
 mnemonic **472**, **910**, 914, 916  
 mobile application 3  
 modal dialog **470**, 557  
 modal dialog box 915  
 model (in MVC architecture) 1113  
 Model-View-Controller (MVC) 1113  
 modifier key 520  
 Modifying the Internal Data  
     Representation of a Class (exercise) 348  
 modularizing a program with methods 166  
 monetary calculations 132, 338  
 monitor **960**  
 monitor lock **960**  
 Monospaced Java font 559  
 Moore's Law **4**  
 Morse Code 632  
 Motif-style (UNIX) look-and-feel 904, 921  
 motion information 5  
 mouse 4, 466, 1100  
 mouse-button click 513  
 mouse click 511  
 mouse event **486**, **505**, 920  
     handling 506  
 mouse wheel 507  
`MouseAdapter` class 510, 511  
     mousePressed method 1035  
 mouseClicked method of interface `MouseListener` 506, 511  
 mouseDragged method of interface `MouseMotionListener` 506, 514  
 mouseEntered method of interface `MouseListener` 506  
`MouseEvent` class **486**, **506**, 920  
     getClickCount method **513**  
     getPoint method **516**  
     getX method **510**  
     getY method **510**  
     isAltDown method **513**  
     isMetaDown method **513**  
     isPopupTrigger method **920**  
 mouseExited method of interface `MouseListener` 506  
`MouseListener` interface **505**, 510  
`MouseListener` interface **486**, **505**, 511, 920  
     mouseClicked method 506, 511  
     mouseEntered method 506  
     mouseExited method 506  
     mousePressed method 506, 920  
     mouseReleased method 506, 920  
`MouseMotionAdapter` class 511, 514  
`MouseMotionListener` interface **486**, **505**, 510, 511  
     mouseDragged method 506, 514  
     mouseMoved method 506, 514  
 mouseMoved method of interface `MouseMotionListener` 506, 514  
 mousePressed method of class `MouseAdapter` 1035  
 mousePressed method of interface `MouseListener` 506, 920

mouseReleased method of interface `MouseListener` 506, 920  
`MouseEvent` class **507**  
`MouseListener` interface **507**  
     mouseWheelMoved method **507**  
 mouseWheelMoved method of interface `MouseListener` **507**  
 moveTo method of class `GeneralPath` **579**  
 Mozilla Foundation 14  
 MP3 player 15  
 multi-button mouse 513  
 multi-core processor **6**  
 multi-catch **441**  
 multi-core 722  
 multidimensional array 228, 229  
 multiple class declarations  
     in one source-code file 314  
 multiple document interface (MDI) 904, **925**  
 multiple inheritance 353  
 multiple-selection list **500**, 502, 503  
 multiple-selection statement **76**  
`MULTIPLE_INTERVAL_SELECTION`  
     constant of interface `ListSelectionMode` **502**, 505  
 multiplication compound assignment operator, \*= 100  
 multiplication, \* **51**, 52  
 multiplicative operators: \*, / and % **94**  
 multiply method of class `BigDecimal` **339**  
 multiply method of class `BigInteger` **774**  
 multithreading 680, **951**  
 multitouch screen **15**  
 mutable data **960**  
 mutable reduction (Java SE 8) **737**  
 mutable reduction operations **727**  
 mutator method **323**  
 mutual exclusion **960**  
 mutually exclusive options **493**  
 MVC (Model-View-Controller) 1113  
`MyShape` hierarchy 426  
`MyShape` hierarchy with `MyBoundedShape` 427  
 MySQL 28, 1038

## N

%n format specifier (line separator) **44**  
 name collision **876**  
 name conflict **876**  
 name of a variable **50**  
 name of an array **211**  
 named constant **216**  
 naming convention  
     GUI (Graphical User Interface) component 1114  
 native keyword 1138  
 natural comparison method **689**  
 natural logarithm 168  
 natural order 740  
 negate method of functional interface `Predicate` (Java SE 8) **737**  
 negative arc angles 568  
 negative degree **567**  
 nested array initializers 228  
 nested building block 152

- nested class 308, **480**, 921
    - relationship between an inner class and its top-level class 493
  - nested control statements **95**, 150, 152, 181
    - Examination-results problem 98
  - nested enhanced-for statements 231
  - nested for statement 219, 229, 230, 231, 298
  - nested if...else selection statement **78**, 80
  - nested parentheses **52**
  - nesting rule **150**
  - NetBeans
    - Hierarchy** window 1106, 1107
    - Inspector** window 1107
    - JavaFX FXML Application** project 1103
    - Library** window 1107, 1108
    - Projects** window 1105
  - NetBeans demonstration video 35
  - NetBeans 18
  - network message arrival 443
  - networking package 176
  - new keyword 47, 212, 213, **271**, 1138
  - New Project** dialog (NetBeans) **1104**, 1114
  - new Scanner(System.in) expression 47
  - new state 953
  - newCachedThreadPool method of class Executors **957**
  - newCondition method of interface Lock **995**, 996
  - newDirectoryStream method of class Files **640**
  - newFactory method of interface RowSetProvider **1072**
  - newline character **42**
  - newline escape sequence, \n 43, 263
  - newOutputStream method of class Files **657**, **660**
  - next method
    - of Iterator **683**
    - of ResultSet **1058**
    - of Scanner **270**
  - nextDouble method of class Scanner **172**, **283**
  - nextInt method of class Random **178**, 181
  - nextLine method of class Scanner **270**
  - Nimbus look and feel **468**
    - swing.properties xlii, 468
  - Nimbus look-and-feel 921
  - no-argument constructor **319**, 320
  - Node class (JavaFX) **1102**, 1123
  - node in a JavaFX application **1102**
  - node in a list **864**
  - non-deterministic random numbers **178**
  - NONE constant of class
    - GridBagConstraints **936**
  - nonfatal logic error **81**
  - nonfatal runtime error **21**
  - nonlinear data structures 864
  - NORTH constant of class BorderLayout **510**, 524
  - NORTH constant of class
    - GridBagConstraints **935**
  - NORTHEAST constant of class
    - GridBagConstraints **935**
  - NORTHWEST constant of class
    - GridBagConstraints **935**
  - NoSuchElementException class **646**, 649
  - note in the UML **75**
  - Notepad 18
  - notify method of class Object **980**
  - notify method of Object 380
  - notifyAll method of class Object **980**, 983
  - notifyAll method of Object 380
  - now method of class Instant **1018**
  - null 1138
  - null keyword 60, 212, 272, **276**, 470, 863
  - NullPointerException exception 289
  - Number class 853
    - doubleValue method **854**
  - number systems 613
  - NumberFormat class **338**, 1018, **1112**, 1120
    - format method **339**, 1018
    - getCurrencyInstance method **339**
    - getPercentInstance method **1018**, 1121
    - setRoundingMode method 1124
  - numeric Classes 679
- O**
- $O(1)$  **807**
  - $O(\log n)$  **812**
  - $O(n \log n)$  time **825**
  - $O(n)$  time **807**
  - $O(n^2)$  time **807**
  - object 2, 10
  - Object class 330, 353, **357**, 662
    - clone method 380
    - equals method 379
    - finalize method 380
    - getClass method 380, **410**, **476**
    - hashCode method 379
    - notify method 380, **980**
    - notifyAll method 380, **980**, 983
    - toString method 360, 380
    - wait method 380, **980**
  - object of a derived class 391
  - object of a derived class is instantiated 379
  - object-oriented analysis and design (OOAD) **13**
  - object-oriented language **13**
  - object-oriented programming (OOP) **2**, 4, **13**, 353
  - object serialization **654**
  - ObjectInput interface **654**
    - readObject method **655**
  - ObjectInputStream class **654**, 655, 660
  - ObjectOutput interface **654**
    - writeObject method **655**
  - ObjectOutputStream class **654**, 654, 655, 712
    - close method **659**
  - ObservableValue interface 1121
  - ObservableValue interface (JavaFX)
    - addListener method 1124
  - octal number system (base 8) 206
  - of method of interface InputStream (Java SE 8) **730**
  - off-by-one error **124**
  - offer method of PriorityQueue **702**
  - OK button 61
  - ON clause **1049**
  - ONE constant of class BigDecimal **339**
  - ONE constant of class BigInteger **774**, 776
  - one statement per line 57
  - one-to-many relationship **1043**
  - one-to-one mapping **706**
  - one-, two- or three-button mouse 513
  - OOAD (object-oriented analysis and design) **13**
  - OOP (object-oriented programming) **13**, 353
  - opaque Swing GUI components **514**
  - open a file **638**
  - OPEN constant of class Arc2D **577**
  - Open Handset Alliance 14
  - open source **14**
  - operand **48**, 94, 258
  - operating system **13**, 14
  - operation code 258
  - operation in the UML **273**
  - operation parameter in the UML 273
  - operator **48**
  - operator precedence 52, 776
    - operator precedence chart 94
    - Operator Precedence Chart Appendix 1135
    - rules **52**
  - Operators
    - $\wedge$ , boolean logical exclusive OR 142, **144**
    - , predecrement/postdecrement **100**
    - , prefix decrement/postfix decrement 100, 101
    - !, logical NOT 142, **144**
    - ?, ternary conditional operator 81, 102
    - \*, multiplication assignment operator 100
    - /=, division assignment operator 100
    - &, boolean logical AND 142, **144**
    - &&, conditional AND **142**, 143
    - %, remainder assignment operator 100
    - ++, prefix increment/postfix increment 100, 101
    - ++, preincrement/postincrement 100
    - +=, addition assignment operator **99**
    - = **48**, 57
    - =, subtraction assignment operator 100
    - |, boolean logical inclusive OR 142, **144**
    - ||, conditional OR 142, **143**
    - arithmetic **51**
    - binary **48**, 51
    - boolean logical AND, & 142, **144**
    - boolean logical exclusive OR,  $\wedge$  142, **144**
    - boolean logical inclusive OR, | **144**
    - cast **94**
    - compound assignment 99, 102

## Operators (cont.)

- conditional AND, && **142**, 143, 144
- conditional operator, ?: **81**, 102
- conditional OR, || **142**, **143**, 144
- decrement operator, -- 100, 101
- increment and decrement 100
- increment, ++ 100
- logical complement, ! **144**
- logical negation, ! **144**
- logical operators **142**, 144, 145
- multiplication, \* **51**
- multiplicative: \*, / and % **94**
- postfix decrement **100**
- postfix increment **100**
- prefix decrement **100**
- prefix increment **100**
- remainder 118
- remainder, % **51**, 52
- subtraction, - 52
- optimizing compiler 131
- Optional** class (Java SE 8) 744
- optional package **877**
- OptionalDouble** class (Java SE 8) **731**, 749
  - `getAsDouble` method **731**, 749
  - `orElse` method **731**, 749
- or method of functional interface
  - Predicate** (Java SE 8) **737**
- Oracle Corporation 1038
- order 74
- ORDER BY** SQL clause 1044, **1047**, 1048
- order in which actions should execute **73**
- Order of catch blocks exercise 464
- order of exception handlers 464
- ordering of records 1044
- `orElse` method of class
  - OptionalDouble** (Java SE 8) **731**, 749
- orientation information 5
- origin component **920**
- out-of-bounds array index 443
- outer set of brackets 222
- OutOfMemoryError** 864
- output 39
- output cursor 39, 42
- output device **5**
- output parameter for a
  - CallableStatement** **1090**
- output unit **5**
- OutputStream** class 655, 665
- OutputStreamWriter** class **668**
- oval 563, 567
- oval bounded by a rectangle 567
- oval filled with gradually changing colors 576
- overflow 443
- overflow error 263
- overflow a method **189**
- overloaded constructors **316**
- overloaded method 832
- overloading generic methods 840
- override a superclass method **356**, 360

## P

- PaaS (Platform as a Service) **28**
- `pack` method of class **Window** **928**
- package **45**, 165, 176, 874
- package access **336**

- package-access members of a class 337
- package-access methods 336
- package declaration **875**
- package directory names 876
- package directory structure 875
- package keyword 1138
- package name 274
- package overview 177
- Packages
  - default package **274**
  - java .time **313**
  - java.awt **471**, 551, 573, 908, 920
  - java.awt.color 573
  - java.awt.event 176, 177, **483**, 485, 510, 520
  - java.awt.font 573
  - java.awt.geom 176, 573
  - java.awt.image 573
  - java.awt.image.renderable 573
  - java.awt.print 573
  - java.beans 1016
  - java.io 176, **638**
  - java.lang **48**, 168, 176, 357, 379, 589, 955
  - java.math 95, **338**, 773, 1120
  - java.net 176
  - java.nio.file 637, **638**, 639, 751
  - java.security 178
  - java.sql 176, 1055, 1058
  - java.text **338**, **1112**, 1120
  - java.time 177
  - java.util **45**, 177, 238
  - java.util.concurrent 177, 956, 976, 1001, 1022
  - java.util.concurrent.locks 994, 995
  - java.util.function (Java SE 8) 724, **730**
  - java.util.prefs **710**
  - java.util.regex 589
  - java.util.stream (Java SE 8) **728**
  - javafx.application.Application **1111**
  - javafx.beans.value 1120, 1124
  - javafx.event 1121
  - javafx.fxml 1121
  - javafx.scene 1102, **1114**, **1119**
  - javafx.scene.control 1112, 1121
  - javafx.scene.layout 1107, **1111**
  - javafx.stage 1102
  - javax.sql.rowset **1072**
  - javax.swing 177, **466**, 468, 476, 487, 532, 555, 908, 921, 927
  - javax.swing.event 177, **484**, 485, 502, 510, 908
  - javax.swing.table 1060, **1071**
- packages
  - create your own 874
  - naming 875
  - padding (JavaFX) **1117**
- Padding** property of a JavaFX layout container 1117
- Page Down* key 517
- page layout software 589

- Page Up* key 517
- Paint** object **576**
- `paintComponent` method of class
  - JComponent** **514**, 548, 905, 907
- `paintComponent` method of
  - JComponent** **105**
- palindrome 118, 799
- Palindromes exercise 799
- panel 530
- parallel **950**
- parallel operations 950
- parallel stream 1021
- `parallelPrefix` method of class
  - Arrays** **1019**
- `parallelSetAll` method of class
  - Arrays** **1019**
- `parallelSort` method of class **Arrays** 238, 1017
- `parallelSort` method of class **Arrays** (Java SE 8) 737
- parameter **171**, 272
- parameter in the UML 273
- parameter list **171**
- parameter list in a lambda 725
- parameterized class **841**
- parameterized type **841**
- Parent** class (JavaFX) **1114**, 1119
- parent node 886, 899
- parent window 60, 470, 904, **925**
- parent window for a dialog box **915**
- parent window specified as null 915
- parentheses **38**, 52
  - nested **52**
  - redundant 53
  - unnecessary 53
- parentheses to force order of evaluation 102
- `parseInt` method of class **Integer** 470
- `parseInt` method of **Integer** 61, 235
- partition step in quicksort 829, 830
- Pascal programming language 15
- pass an array element to a method 225
- pass an array to a method 225
- pass-by-reference **227**
- pass-by-value 225, **227**
- passing options to a program 233
- password 477
- PATH environment variable xl, 40
- Path** interface **639**
  - `getFileName` method **640**
  - `isAbsolute` method **640**
  - `toAbsolutePath` method **640**
  - `toString` method **640**
- Paths** class **639**
  - `get` method **639**, 640
- pattern 573
- Pattern** class 589, **623**
  - `compile` method **623**
  - `matcher` method **623**
  - `matches` method **623**
  - `splitAsStream` method (Java SE 8) **752**
- pattern matching **1045**
- pattern of 1s and 0s 7
- Payable** interface declaration 416
- Payable** interface hierarchy UML class diagram 415

- Payable interface test program
  - processing *Invoices* and *Employees* polymorphically 422
- Payroll System Modification exercise 431
- peek method of class *PriorityQueue* 702
- peek method of class *Stack* 702
- percent (%) SQL wildcard character 1045
- perfect number (exercise) 204
- perform a calculation 61
- perform a task 171
- perform an action 39
- performance of binary tree sorting and searching 902
- Performance Tips overview xxxiv
- performing operations concurrently 950
- Perl (Practical Extraction and Report Language) 16
- persistent 6
- persistent data 637
- persistent *Hashtable* 710
- phase 88
- Phishing Scanner 675
- PHP 16, 28
- physical input operation 667
- physical output operation 666
- PI 584
- “pick off” each digit 70
- pie chart 585
- Pie Chart exercise 585
- PIE constant of class *Arc2D* 577
- pie-shaped arc 577
- Pig Latin 629
- pipe 665
- PipedInputStream* class 665
- PipedOutputStream* class 665
- PipedReader* class 668
- PipedWriter* class 668
- pixel (“picture element”) 104, 548
- PLAF (pluggable look-and-feel) 904
- PLAIN constant of class *Font* 559
- PLAIN\_MESSAGE 470
- Platform as a Service (PaaS) 28
- platform dependency 955
- platform independent 19
- pluggable look-and-feel (PLAF) 904
- pluggable look-and-feel package 472
- PNG (Portable Network Graphics) 476
- point 559
- Point* class 515
- poker 305
- poll method of *PriorityQueue* 702
- polygon 570, 572
- Polygon* class 548, 570
  - addPoint method 571, 573
- polyline 570
- polylines 570
- polymorphic processing
  - of collections 680
- polymorphic processing of related exceptions 446
- polymorphically process *Invoices* and *Employees* 422
- polymorphism 140, 383, 388
- polynomial 53, 54
- pop method of *Stack* 702
- pop off a stack 174
- pop stack operation 879
- popup trigger event 917, 920
- portability 550
- Portability Tips overview xxxiv
- portable 19
- portable GUI 177
- Portable Network Graphics (PNG) 476
- position number 211
- positive and negative arc angles 568
- positive degrees 567
- postcondition 457
- postdecrement 100
- postfix decrement operator 100
- postfix expression evaluation algorithm 897
- postfix increment operator 100, 126
- postfix notation 897
- PostgreSQL 1038
- postincrement 100, 102
- postorder traversal 886, 890
- pow method of class *BigDecimal* 339
- pow method of class *Math* 131, 167, 168, 199
- power (exponent) 168, 204
- power of 2 larger than 100 82
- Practical Extraction and Report Language (Perl) 16
- prebuilt data structures 677
- precedence 52, 58, 102, 776
  - arithmetic operators 52
  - chart 52, 94
- Precedence Chart Appendix 1135
- precise floating-point calculations 338
- precision
  - format of a floating-point number 94
- precision of a formatted floating-point number 283
- precondition 457
- predecrement 100
- predefined character class 616
- predicate 733, 1045
- Predicate functional interface (Java SE 8) 725, 743
  - and method 737
  - negate method 737
  - or method 737
- predicate method 324, 870
- preemptive scheduling 955
- Pref Height property of a *JavaFX* component 1108
- Pref Width property of a *JavaFX* component 1108
- Pref Width property of a *JavaFX* control 1116
- Preferences API 710
- preferred size (JavaFX) 1108
- prefix decrement operator 100
- prefix increment operator 100
- preincrement 100, 102
- Preincrementing and postincrementing 101
- preorder traversal 886
- PreparedStatement* interface 1074, 1075, 1077, 1081, 1090
  - executeQuery method 1081
  - executeUpdate method 1081
  - setString method 1074, 1081
- prepareStatement method of interface *Connection* 1081
- previous method of *ListIterator* 686
- primary key 1039, 1043
  - composite 1043
- primary memory 5
- prime 204, 719
- prime number 256, 754
- primitive type 47, 103, 175, 210
  - boolean 1146
  - byte 134
  - char 47, 134
  - double 47, 91, 92
  - float 47, 92
  - int 47, 91, 100, 134
  - names are keywords 47
  - passed by value 227
  - promotions 175
  - short 134
- principal in an interest calculation 129
- Principle of Least Privilege 189
- principle of least privilege 335
- print a line of text 39
- print an array 799
- Print an Array Backward exercise 799
- Print an Array exercise 799
- print an array recursively 799
- print debugger command 1145
- print method of *System.out* 41, 42
- print on multiple lines 41, 42
- print spooling 883, 969
- printArray generic method 835
- printf method of *System.out* 43
- printing a binary tree in a two-dimensional tree format 892
- printing trees 901
- println method of *System.out* 38, 41, 42
- printStackTrace method of class *Throwable* 453
- PrintStream* class 666, 712
- PrintWriter* class 646, 668
- priority of a thread 954
- PriorityBlockingQueue* class 1002
- PriorityQueue* class 702
  - clear method 702
  - offer method 702
  - peek method 702
  - poll method 702
  - size method 702
- private
  - access modifier 268, 313, 356
  - data 323
  - field 322
  - keyword 323, 1138
- private static
  - class member 331
- probability 178
- procedure for solving a problem 73
- processing phase 88
- processing unit 4
- producer 951, 968
- producer thread 969
- producer/consumer relationship 968, 988
- product of odd integer 160
- program 4
- program construction principles 154
- program control 73
- program development tool 77, 90
- program execution stack 879
- program in the general 388, 431

- program in the specific 388
- programmer **4**
- project (NetBeans) **1104**
- Projects** window in NetBeans 1105
- promotion 94**
  - of arguments 175
  - rules 94, **175**
- promotions for primitive types 175
- prompt 48**
- Properties** class **710**
  - getProperty method **710**
  - keySet method 713
  - list method **712**
  - load method **713**
  - setProperty method **710**
  - store method **712**
- propertyChange method of interface PropertyChangeListener 1016
- PropertyChangeListener interface **1016**
  - propertyChange method 1016
- protected access modifier 313, 356, 1138
- protocol for communication (jdbc) 1057
- pseudocode 74, 78, 84, 95, 97
  - algorithm 90
  - first refinement **88**, 96
  - second refinement **89**, 97
- public**
  - abstract method 413
  - access modifier 171, 268, 313, 356
  - final static data 413
  - interface **308**
  - keyword **37**, 268, 1138
  - member of a subclass 356
  - method 106, 309, 313
  - method encapsulated in an object 312
  - service **308**
  - static class members 331
  - static method 331
- push method of class Stack **701**
- push onto a stack **174**
- push stack operation **879**
- put** method
  - of interface BlockingQueue **976**, 977
  - of interface Map **709**
- Pythagorean Triples 162
- Python 16

## Q

- quad-core processor 6
- quadratic run time 807
- qualified name **1049**
- quantifiers used in regular expressions **620**, 621
- quantum **954**
- query **1038**, 1040
- query a database 1055
- query application for the books database 1096
- query method **323**
- QUESTION\_MESSAGE 470
- queue 702, **862**, 882
- Queue interface **678**, **702**, 976
- quicksort algorithm 829

## R

- RadialGradientPaint class 576
- radians 168
- radio button **487**, **493**
- radio button group **493**
- radius 584
- radius of a circle 204
- radix (base) of a number **613**
- raised rectangle **567**
- RAM (Random Access Memory) **5**
- Random Characters exercise 584
- Random class 251
  - nextInt method **178**, 181
- Random Colors exercise 585
- random limericks 629
- Random Lines Using Class Line2D.Double exercise 584
- random numbers
  - difference between values 182
  - element of chance **178**
  - generation 284
  - generation to create sentences 629
  - scaling **179**
  - scaling factor **179**, 182
  - shift a range **179**
  - shifting value **179**, 182
- Random Triangles exercise 584
- randomly generated triangles 584
- randomly sized shapes 585
- range checking **87**
- range method of class EnumSet **329**
- range method of interface InputStream (Java SE 8) **735**
- range-view methods **686**, 704
- rangeClosed method of interface InputStream (Java SE 8) **735**
- ratio of successive Fibonacci numbers 775
- Rational class 349
- Rational Numbers (exercise) 349
- raw type **849**
- read-only file 659
- read-only text 473
- readability 36, 37, 96
- Reader class **667**
- reading files 639
- readObject method of ObjectInput **655**
- readObject method of ObjectInputStream 662
- ready state 954
- real number 47, 91
- real part 348
- realization in the UML **415**
- "receiving" section of the computer 5
- reclaim memory 334
- record 7, 643
- rectangle 348, 548, 552, 564
- Rectangle Class (exercise) 348
- Rectangle2D class 548
- Rectangle2D.Double class **573**
- recursion
  - overhead 780
  - quicksort 829
  - recursion step **770**, 776
  - recursive backtracking **794**
  - recursive binary search algorithm 829
  - recursive call **770**, 776, 777
  - recursive evaluation 772
  - Recursive evaluation of 5! 772
- recursion (cont.)
  - recursive factorial method 771
  - recursive linear search algorithm 829
  - recursive method **769**
  - Recursively power Method exercise 797
  - recursive step 829
  - recursively generating Fibonacci numbers 777
  - Recursively Print a List Backwards 899
  - Recursively Search a List 899
- Recursion Exercises
  - binary search 829
  - Eight Queens 799
  - Find the Minimum Value in an Array 799
  - Fractals 799
  - Generating Mazes Randomly 801
  - Greatest Common Divisor 798
  - linear search 829
  - Maze Traversal Using Recursive Backtracking 800
  - Mazes of Any Size 801
  - Palindromes 799
  - Print an Array 799
  - Print an Array Backward 799
  - quicksort 829
  - Recursive power Method 797
  - Time to Calculate Fibonacci Numbers 801
  - Visualizing Recursion 798
- recursive backtracking 801
- redirect a standard stream **638**
- reduce method of interface DoubleStream (Java SE 8) 749
- reduce method of interface IntStream (Java SE 8) **731**
- reduction (mutable) **737**
- reduction operations **727**
- redundant parentheses **49**, **53**
- reentrant lock **984**
- ReentrantLock class **994**, 996
- refactoring **28**
- refer to an object **210**
- reference **210**
- reference type **210**, 336
- refinement process 88
- regexFilter method of class RowFilter **1071**
- regionMatches method of class String **593**
- register an ActionListener 916
- register event handlers (JavaFX) 1119
- registered listener 486
- registering the event handler **480**, **1113**
- regular expression **616**, 750
  - $\wedge$  620
  - ? 620
  - . 624
  - {*n*,} 621
  - {*n*,*m*} 620
  - {*n*} 620
  - \* 620
  - \d 617
  - \d 617
  - \S 617
  - \s 617
  - \W 617

- regular expression (cont.)
    - \w 617
    - + 620
    - | 620
  - reinventing the wheel 11, 45, 235
  - relational database 1038, **1039**
  - relational database management system (RDBMS) **1038**
  - relational database table 1039
  - relational operators **54**
  - relationship between an inner class and its top-level class 493
  - RELATIVE constant of class
    - GridBagConstraints **941**
  - relative path **639**
  - release a lock 960, 982, 983
  - release a resource 447
  - release candidate 29
  - reluctant quantifier **621**
  - remainder 51
  - remainder compound assignment
    - operator, %= 100
  - REMAINDER constant of class
    - GridBagConstraints **941**
  - remainder operator, % **51**, 52, 118
  - remove duplicate String 703
  - remove method of class ArrayList<T> 239, **240**
  - remove method of interface Iterator **683**
  - removeTableModelListener method of interface TableModel **1060**
  - repaint method of class Component **516**
  - repaint method of class JComponent **551**
  - repetition 76, 150, 152
    - counter controlled 84, 92, 95, 96
    - definite **84**
    - sentinel controlled 87, 89, 90, 91, 92, 93
  - repetition statement **75**, **76**, 82, 89, 779
  - do...while 76, 132, 133, 152, 133, 152
  - for 76, 127, 152
  - while 76, **82**, 83, 86, 91, 92, 122, 152
  - repetition terminates 82
  - replaceAll method
    - of class Matcher **623**
    - of class String **621**
  - replaceFirst method
    - of class Matcher **623**
    - of class String **621**
  - requestFocus method 1123
  - requestFocus method of class Node 1123
  - requirements **13**
  - reservations system 252
  - reserved word **37**, 76, 1138
    - false 77
    - null 272, **276**
    - true 77
  - resizable array
    - implementation of a List 680
  - resolution 104, 548
  - resource leak 329, **446**
  - resource-release code 447
  - responses to a survey 220
  - result 1045
  - result set concurrency **1064**
  - result set type **1064**
  - ResultSet interface **1058**, 1064, 1065, 1066
    - absolute method **1065**
    - close method 1059
    - column name 1059
    - column number 1059
    - CONCUR\_READ\_ONLY constant **1064**
    - CONCUR\_UPDATABLE constant **1064**
    - currency constant 1064
    - getInt method **1059**
    - getObject method **1059**, 1065
    - getRow method **1066**
    - last method **1066**
    - next method **1058**
    - TYPE\_FORWARD\_ONLY constant **1064**
    - TYPE\_SCROLL\_INSENSITIVE constant **1064**
    - TYPE\_SCROLL\_SENSITIVE constant **1064**
  - ResultSetMetaData interface **1058**, 1065
    - getColumnClassName method **1065**
    - getColumnCount method **1058**, **1065**
    - getColumnName method **1065**
    - getColumnType method **1058**
  - ResultSetTableModel enables a JTable to display the contents of a ResultSet 1060
  - resumption model of exception handling **441**
  - rethrow an exception **450**, 464
  - Rethrowing Exceptions exercise 464
  - return keyword 166, **172**, 174, 1138
  - return statement 770
  - return type
    - of a method **171**
  - reusability 841, 862
  - reusable software components 10, 176, 354
  - reuse 11, 45
  - reverse method of class
    - StringBuilder **606**
  - reverse method of Collections 688, **694**
  - reversed method of interface
    - Comparator (Java SE 8) **740**
  - reverseOrder method of
    - Collections **690**
  - RGB value 551, **552**, 557
  - RGB values **192**
  - right aligned 522
  - right brace, } **37**, 38, 46, 85, 92
  - right child **885**
  - RIGHT constant of class FlowLayout **524**
  - right justify output **130**
  - right subtree 890, 900
  - right-align the contents of a column 1116
  - rigid area of class Box **934**
  - rise-and-shine algorithm 73
  - Ritchie, Dennis 16
  - robust 48
  - robust application 434
  - roll back a transaction **1091**
  - rollback method of interface
    - Connection **1091**
  - rolling two dice 185
  - rollover Icon **489**
  - root directory **639**
  - root node **885**, **1102**
  - rotate method of class Graphics2D **580**
  - round a floating-point number for display purposes 94
  - round-robin scheduling **954**
  - rounded rectangle 565, 577
  - rounding a number 51, 86, 132, 168, 202
  - RoundingMode enum 340, 1120
  - RoundRectangle2D class 548
  - RoundRectangle2D.Double class **573**, 577
  - row **1039**, 1043, 1044, 1045, 1046, 1050
  - RowFilter class **1071**
  - rows of a two-dimensional array 228
  - rows to be retrieved 1044
  - RowSet interface **1072**
  - RowSetFactory class **1072**
  - RowSetFactory interface
    - createJdbcRowSet method **1072**
  - RowSetProvider class **1072**
  - RowSetProvider interface
    - newFactory method **1072**
  - Ruby on Rails 17
  - Ruby programming language 17
  - Rule of Entity Integrity **1043**
  - Rule of Referential Integrity **1042**
  - rule of thumb (heuristic) 141
  - rules for forming structured programs 149
  - rules of operator precedence **52**, 776
  - run debugger command **1143**
  - run method of interface Runnable **955**
  - runAsync method of class
    - CompletableFuture **1026**
  - Runnable interface 424, **955**
  - run method **955**
  - runnable state 953
  - running an application 21
  - running state 954
  - running total 89
  - runtime error **21**
  - runtime logic error 48
  - RuntimeException class **444**
- ## S
- SaaS (Software as a Service) 28
  - Safari 59
  - SalariedEmployee class that
    - implements interface Payable
    - method getPaymentAmount 420
  - SalariedEmployee concrete class
    - extends abstract class Employee 400
  - Sales Commissions 250
  - SAM interface 724
  - SansSerif Java font 559
  - saturation **557**
  - savings account 129
  - SavingsAccount Class (exercise) 348
  - scalar **225**
  - scaling (random numbers) 179
    - scale factor 179, 182

- scaling `BigDecimal` values 340
- `Scanner` class 45, 47
  - `hasNext` method 137
  - `next` method 270
  - `nextDouble` method 172, 283
  - `nextLine` method 270
- scanning images 5
- `Scene Builder` 1101, 1103
- `Scene` class (JavaFX) 1102, 1111, 1119, 1120
- scene graph 1120
- scene graph in a JavaFX application 1102
- scene in a JavaFX application 1102
- scheduling threads 954
- scope 126
- scope of a declaration 187
- scope of a type parameter 843
- scope of a variable 126
- Scrapbooking** app exercise 1131
- screen 4, 5
- screen cursor 43
- screen-manager program 390
- Screen Saver exercise 584
- Screen Saver for Random Number of Lines exercise 585
- Screen Saver Using the Java2D API exercise 585
- Screen Saver Using Timer exercise 584
- Screen Saver with Shapes exercise 585
- scroll 498, 502
- scroll arrow 499
- scroll box 499
- `SCROLL_TAB_LAYOUT` constant of class `JTabbedPane` 934
- scrollbar 502, 534
  - of a `JComboBox` 499
- scrollbar policies 534
- SDK (Software Development Kit) 29
- search algorithms
  - binary search 808
  - linear search 804
  - recursive binary search 829
  - recursive linear search 829
- search key 803
- searching 862
- searching data 803
- second-degree polynomial 53, 54
- second refinement 97
- second refinement in top-down, stepwise refinement 89
- secondary storage 4
- secondary storage devices 637
- secondary storage unit 6
- sector 568
- `SecureRandom` class 178, 178
  - documentation 178
  - `doubles` method (Java SE 8) 754
  - `ints` method (Java SE 8) 754
  - `longs` method (Java SE 8) 754
  - streams of random numbers (Java SE 8) 754
- security 20
- security breach 271
- security breaches 178
- `SecurityException` class 645
- seful 639
- `SELECT` SQL keyword 1044, 1045, 1046, 1047, 1048
- `selectAll` method 1123
  - `TextInputControl` 1123
- selected text in a `JTextArea` 533
- selecting an item from a menu 477, 1113
- Selecting Shapes exercise 585
- selection 76, 150
- selection criteria 1045
- selection mode 502
- selection sort algorithm 813, 816
- selection statement 74, 76
  - `if` 76, 77, 134, 152
  - `if...else` 76, 77, 78, 91, 134, 152
  - `switch` 76, 134, 138, 152
- self-documenting 47
- self-documenting code 47
- self-referential class 863, 864
- self-similar property 783
- semicolon (;) 39, 46, 57
- send a message to an object 11
- sentence-style capitalization 469
- sentinel-controlled repetition 88, 89, 90, 91, 92, 93, 161, 260
- sentinel value 88, 89, 93
- separator character 642
- separator line in a menu 915, 916
- sequence 76, 149, 150, 680, 885
- sequence structure 74
- sequence-structure activity diagram 75
- `SequenceInputStream` class 667
- sequential-access file 637, 643
- sequential execution 74
- Sequentially searching an array for an item 805
- `Serializable` interface 424, 655
- serialized object 654
- `Serif` Java font 559
- service of a class 313
- `set` debugger command 1145
- `Set` interface 678, 703, 704, 706
  - `stream` method (Java SE 8) 752
- `set` method
  - of interface `ListIterator` 686
- `set` method 316
- `Set` of Integers (exercise) 349
- `Set` of recursive calls for `fibonacci(3)` 777
- `SET` SQL clause 1051
- `set-theoretic intersection` 349
- `set-theoretic union` 349
- set up event handling 480
- `setAlignment` method of class `FlowLayout` 524
- `setAutoCommit` method of interface `Connection` 1091
- `setBounds` method of class `Component` 241, 503, 557
- `setBounds` method of class `Component` 521
- `setCharAt` method of class `StringBuilder` 606
- `setColor` method of class `Graphics` 552, 577
- `setColor` method of `Graphics` 193
- `setCommand` method of `JdbcRowSet` interface 1074
- `setConstraints` method of class `GridBagLayout` 941
- `setDefaultCloseOperation` method of class `JFrame` 106, 477, 908
- `setDisabledTextColor` method of class `JTextComponent` 520
- `setEditable` method of class `JTextComponent` 480
- `setErr` method of class `System` 638
- `setFileSelectionMode` method of class `JFileChooser` 662
- `setFixedCellHeight` method of class `JList` 505
- `setFixedCellWidth` method of class `JList` 505
- `setFont` method of class `Component` 492
- `setFont` method of class `Graphics` 559
- `setForeground` method of class `JComponent` 916
- `setHorizontalAlignment` method of class `JLabel` 476
- `setHorizontalScrollBarPolicy` method of class `JScrollPane` 534
- `setHorizontalTextPosition` method of class `JLabel` 476
- `setIcon` method of class `JLabel` 476
- `setIn` method of class `System` 638
- `setInverted` method of class `JSlider` 905
- `setJMenuBar` method of class `JFrame` 909, 916
- `setLayout` method of class `Container` 475, 522, 526, 529, 934
- `setLength` method of class `StringBuilder` 605
- `setLineWrap` method of class `JTextArea` 534
- `setListData` method of class `JList` 505
- `setLocation` method of class `Component` 521, 909
- `setLookAndFeel` method of class `UIManager` 924
- `setMajorTickSpacing` method of class `JSlider` 908
- `setMaximumRowCount` method of class `JComboBox` 499
- `setMnemonic` method of class `AbstractButton` 915
- `setOpaque` method of class `JComponent` 514, 516
- `setOut` method of `System` 638
- `setPaint` method of class `Graphics2D` 576
- `setPaintTicks` method of class `JSlider` 908
- `setPassword` method of `JdbcRowSet` interface 1074
- `setProperty` method of `Properties` 710
- `setRollerIcon` method of class `AbstractButton` 490
- `setRoundingMode` method of class `NumberFormat` 1124
- `setRowFilter` method of class `JTable` 1071
- `setRowSorter` method of class `JTable` 1071
- `setScale` method of class `BigDecimal` 340
- `setSelected` method of class `AbstractButton` 916



- setSelectionMode method of class JList **502**
- setSize method of class Component 521, 909
- setSize method of class JFrame **106, 477**
- setString method of interface PreparedStatement **1074**, 1081
- setStroke method of class Graphics2D **576**
- setText method 1123
- setText method of class JLabel 382, **476**
- setText method of class JTextComponent 533
- setText method of class TextInputControl 1123
- Setting the PATH environment variable x1
- setToolTipText method of class JComponent **475**
- setUrl method of JdbcRowSet interface **1072**
- setUsername method of JdbcRowSet interface **1074**
- setVerticalAlignment method of class JLabel **476**
- setVerticalScrollBarPolicy method of class JScrollPane **534**
- setVerticalTextPosition method of class JLabel **476**
- setVisible method of class Component **477, 526**, 909
- setVisible method of class JFrame **106**
- setVisibleRowCount method of class JList **502**
- shadow 269
- shadow a field **187**
- shallow copy **380**
- shape 573
- Shape class hierarchy 355, 385
- Shape Hierarchy exercise 431
- Shape object 576
- share memory 951
- shared buffer 969
- shell **39**
- shell in Linux 18
- shell script **645**
- Shift* 520
- shift (random numbers) **179**
  - shifting value **179**, 182
- “shipping” section of the computer 5
- shopping list 82
- short-circuit evaluation **143**
- Short class **679**
- short primitive type 134, 1138, 1139
  - promotions 175
- short-circuiting terminal operation (Java SE 8) 744
- shortcut key **910**
- show method of class JPopupMenu **920**
- showDialog method of class JColorChooser **556**
- showInputDialog method of class JOptionPane **61, 469**
- showMessageDialog method of class JOptionPane **60, 470**
- showOpenDialog method of class JFileChooser **662**
- shuffle 284
  - algorithm 692
- shuffle method of class Collections 688, **692**, 694
- shutdown method of class ExecutorService **959**
- sibling nodes **885**
- side effect **144**
- Sieve of Eratosthenes 256, 754, **1012**
- signal method of interface Condition **995**, 999
- signal value **88**
- signalAll method of interface Condition **995**
- signature of a method **191**, 191
- simple condition 142
- simple name **876**
- simplest activity diagram 149
- Simpletron Machine Language (SML) 258, 862
- Simpletron simulator 260, 263, 863
- simulate a middle-mouse-button click on a one- or two-button mouse 513
- simulate a right-mouse-button click on a one-button mouse 513
- simulation 178
  - coin tossing 205
- Simulation: Tortoise and the Hare 257, 585
- simulator 258
- sin method of class Math 168
- sine 168
- single abstract method (SAM) interface 724
- single entry point 147
- single-entry/single-exit control statements **76**, 149
- single exit point 147
- single inheritance 353
- single-line (end-of-line) comment 39
- single-precision floating-point number **92**
- single-quote character 589, 1046
- single-selection list **500**
- single-selection statement **76**, 77, 152
- single static import **334**
- single-type-import declaration **877**
- SINGLE\_INTERVAL\_SELECTION
  - constant of interface ListSelectionMode1 **502**, 503, 505
- SINGLE\_SELECTION constant of interface ListSelectionMode1 **502**
- single-selection statement
  - if **77**
- singly linked list **864**
- size method
  - of class ArrayBlockingQueue **978**
  - of class ArrayList<T> **240**
  - of class PriorityQueue **702**
  - of interface List **682, 686**
  - of interface Map **710**
- size method of class Files **640**
- size of a variable **50**
- skinning **1101**
- sleep interval **953**
- sleep method of class Thread **957**, 970, 972, 973
- sleeping thread **953**
- Slider class (JavaFX) 1110, **1112**
  - Max property 1118
  - Value property 1118
  - valueProperty method 1124
- small circles in the UML **75**
- smallest of several integers 160
- smartphone 3
- SML 862
- SMS Language 635
- snap-to ticks for JSlider **904**
- software **2**
- Software as a Service (SaaS) **28**
- Software Development Kit (SDK) **29**
- software engineering 323
- Software Engineering Observations
  - overview xxxiv
- software model 260
- software reuse 11, **166**, 874
- software simulation 258
- solid circle in the UML **75**
- solid circle surrounded by a hollow circle in the UML **75**
- Solves Towers of Hanoi problem with a recursive method 782
- sort algorithms
  - bubble sort 828
  - bucket sort 828
  - insertion sort **816**
  - merge sort **819**
  - quicksort 829
  - selection sort **813**
- sort key **803**
- sort method
  - of class Arrays **235, 809**
  - of class Collections **689**
- sort method of class Arrays 737, 1017
- sorted array 864
- sorted method of interface IntStream (Java SE 8) **733**
- sorted method of interface Stream (Java SE 8) **737**, 740
- sorted order 704, 706
- SortedMap interface **706**
- SortedSet interface **704**, 705
  - first method **705**
  - last method **705**
- sorting 862
  - descending order 689
  - with a Comparator 690
- sorting data **803**, 812
- Sorting Letters and Removing Duplicates
  - exercise 767
- source code **18**
- SourceForge 14
- SOUTH constant of class BorderLayout **510**, 524
- SOUTH constant of class GridBagConstraints **935**
- SOUTHEAST constant of class GridBagConstraints **935**
- SOUTHWEST constant of class GridBagConstraints **935**
- space character 37
- Spam Scanner 634
- speaking to a computer 5
- special character 47, **589**
- Special Section: Advanced String-Manipulation Exercises 630

- Special Section: Building Your Own Compiler 862
- Special Section: Building Your Own Computer 258
- Special Section: Challenging String-Manipulation Projects 633
- special symbol 6
- specialization **353**
- specifics 390
- Spelling Checker project 633
- sphere 199
- spiral 585, 775
- split method of class String **615, 621**
- split the array in merge sort 819
- splitAsStream method of class Pattern (Java SE 8) **752**
- spooler **883**
- spooling 883
- SQL 1038, 1040, 1044, 1050
  - DELETE statement 1044, **1052**
  - FROM clause 1044
  - GROUP BY 1044
  - IDENTITY keyword **1040**
  - INNER JOIN clause 1044, **1049**
  - INSERT statement 1044, **1050**
  - LIKE clause 1046
  - ON clause **1049**
  - ORDER BY clause 1044, **1047**, 1048
  - SELECT query **1044**, 1045, 1046, 1047, 1048
  - SET clause **1051**
  - UPDATE statement 1044
  - VALUES clause **1050**
  - WHERE clause **1045**
- SQL (Structured Query Language) 1074
- SQL injection attack (preventing) 1075
- SQL keyword 1044
- SQL statement 1091
- SQLException class **1057**, 1059, 1075
- SQLFeatureNotSupportedException class 1065
- sqr method of class Math 167, 168, 175
- square brackets, [] **211**
- square root 168
- Squares eliminated by placing a queen in the upper-left corner of a chessboard 799
- stack **174**, 841, **862**, 878
  - method call stack **174**
  - stack overflow **174**
- Stack class 702, 878
  - isEmpty method **702**
  - of package java.util **700**
  - peek method **702**
  - pop method **702**
  - push method **701**
- stack frame **174**, 780
- Stack generic class 841
  - Stack< Double > 848
  - Stack< Integer > 848
- Stack generic class declaration 842
- stack operation
  - pop **879**
  - push **879**
- stack trace **436**
- stack unwinding **451**
- stacked building blocks 152
- stacking control statements 152
- stacking rule **149**
- StackTraceElement class **453**
  - getClassName method **453**
  - getFileName method **453**
  - getLineNumber method **453**
  - getMethodName method **453**
- Stage class (JavaFX) **1102**, 1111, 1119, 1120
  - stage in a JavaFX application **1102**
  - stale value **966**
- standard error stream **440, 449**
- standard error stream (System.err) 638, 666
- standard input stream (System.in) 47, 638
- standard output stream **449**
- standard output stream (System.out) 39, 638, 666
- standard reusable component **354**
- standard time format 311
- “warehouse” section of the computer 6
- start method of class Application (JavaFX) **1111**, 1119
- starting angle **567**
- startsWith method of class String **596**
- starvation **955**
- state button **490**
- state dependent **969**
- stateChanged method of interface ChangeListener **908**
- stateful intermediate operation **734**
- stateless intermediate operation **734**
- stateless stream operation 734
- statement **39**, 171
- statement block in a lambda 725
- Statement interface **1058**, 1059, 1074
  - close method 1059
  - executeQuery method **1058**
- Statements 89
  - break **137**, 140, 162
  - continue **140**, 162, 163
  - control statement **73**, 74, 76, 77
  - control-statement nesting **76**
  - control-statement stacking **76**
  - do...while 76, **132**, 133, 152
  - double selection **76**, 96
  - empty **57**, 81
  - empty statement 81
  - enhanced for **223**
  - for **76**, **124**, 127, 129, 131, 152
  - if **54**, 76, 77, 134, 152
  - if...else 76, 77, 78, 91, 134, 152
  - looping **76**
  - multiple selection **76**
  - nested **95**
  - nested if...else **78**, 80
  - repetition **75**, 76, 82
  - return 166, 174
  - selection **74**, **76**
  - single selection **76**
  - switch **76**, **134**, 138, 152
  - switch multiple-selection statement 182
  - try **222**
  - while 76, 82, 83, 86, 91, 92, 122, 152
- statements
  - throw **310**
  - try-with-resources **459**
- static
  - class member 330, 331
  - class variable 331
  - field (class variable) **330**
  - import **334**
  - import on demand **334**
  - keyword 167, 1138
  - method **60**, 131
- static binding **412**
- static interface methods (Java SE 8) 425
- static method in an interface (Java SE 8) 724, 755
- static method of an interface (Java SE 8) 723
- step debugger command **1148**
- step up debugger command **1148**
- stop debugger command **1143**
- store method of Properties **712**
- stored procedure **1090**
- straight-line form **51**
- stream **449**
- stream (Java SE 8)
  - DoubleStream interface **728**
  - eager operations 731
  - filter elements 733
  - intermediate operation **726**
  - IntStream interface **728**
  - lazy operation 733, 734
  - LongStream interface **728**
  - map elements to new values 734
  - pipeline **726**, 733, 734
  - terminal operation **726**
- Stream interface (Java SE 8) **726, 736**
  - collect method 737, 737, 747, 748, 754
  - distinct method **746**
  - filter method 737, 740
  - findFirst method 744
  - forEach method 737
  - map method **739**, 739
  - sorted method **737**, 740
- Stream interface (Java SE 8)
  - flatMap method **752**
- stream method of class Arrays (Java SE 8) **735**, 736
- stream method of interface Set 752
- stream of bytes **637**
- stream pipeline 730
- streaming 951
- streams **726**
- streams (Java SE 8)
  - infinite streams **754**
- strictfp keyword 1138
- strictly self-similar fractal **783**
- string **39**
  - literal **39**
  - of characters 39
- String class 589
  - charAt method **591**, **606**
  - compareTo method 593, 595
  - concat method **600**
  - endsWith method **596**
  - equals method 593, 595
  - equalsIgnoreCase method 593, 595
  - format method **61**, **310**
  - getChars method **591**
  - immutable **333**

- String class (cont.)
    - indexOf method **597**
    - lastIndexOf method **597**
    - length method **591**
    - matches method **616**
    - regionMatches method **593**
    - replaceAll method **621**
    - replaceFirst method **621**
    - split method **615, 621**
    - startsWith method **596**
    - substring method **599**
    - toCharArray method **602, 799**
    - toLowerCase **686**
    - toLowerCase method **602**
    - toUpperCase **686**
    - toUpperCase method **601**
    - trim method **602**
    - valueOf method **602**
  - String class searching methods **597**
  - string concatenation **172, 333**
  - string literal **589**
  - StringBuffer class **604**
  - StringBuilder class **589, 603**
    - append method **607**
    - capacity method **604**
    - charAt method **606**
    - constructors **604**
    - delete method **609**
    - deleteCharAt method **609**
    - ensureCapacity method **605**
    - getChars method **606**
    - insert method **609**
    - length method **604**
    - reverse method **606**
    - setCharAt method **606**
    - setLength method **605**
  - StringIndexOutOfBoundsException class **599**
  - StringReader class **668**
  - StringWriter class **668**
  - Stroke object **576, 577**
  - strongly typed languages **103**
  - Stroustrup, Bjarne **434**
  - structured programming **4, 74, 122, 141, 149**
    - summary **147**
  - Structured Query Language (SQL) **1038, 1040, 1044**
  - Student Poll exercise **675**
  - subclass **12, 105, 353**
  - sublist **686**
  - subList method of List **686**
  - submenu **910**
  - submit method of class
    - ExecutorService **1022**
  - subprotocol for communication **1057**
  - subscript (index) **211**
  - substring method of class String **599**
  - subtract method of class BigInteger **774, 776**
  - subtraction **6, 51**
    - operator, - **52**
  - subtraction compound assignment
    - operator, -= **100**
  - suffix F for float literals **702**
  - suffix L for long literals **701**
  - sum method of interface DoubleStream (Java SE 8) **749**
  - sum method of interface IntStream (Java SE 8) **731**
  - sum the elements of an array **217**
  - summarizing responses to a survey **220**
  - super keyword **356, 379, 1138**
    - call superclass constructor **370**
  - super.paintComponent(g) **106**
  - superclass **12, 105, 353**
    - constructor **360**
    - constructor call syntax **370**
    - default constructor **360**
    - direct **353, 355**
    - indirect **353, 355**
    - method overridden in a subclass **378**
  - Supermarket Simulation **898**
  - Supplier functional interface (Java SE 8) **725**
  - Supplier interface (Java SE 8) **1022, 1025**
  - supplyAsync method of class
    - CompletableFuture **1025**
  - swapping values **813, 816**
  - sweep **243, 567**
  - sweep counterclockwise **567**
  - Swing Event Package **177**
  - Swing GUI APIs **467**
  - Swing GUI components **466**
  - Swing GUI components package **177**
  - swing.properties file **xliv, 468**
  - SwingConstants interface **476, 908**
  - SwingUtilities class **924**
    - updateComponentTreeUI method **924**
  - SwingWorker class **1003**
    - cancel method **1017**
    - doInBackground method **1003, 1006**
    - done method **1003, 1006**
    - execute method **1003**
    - get method **1003**
    - isCancelled method **1012**
    - process method **1004, 1013**
    - publish method **1003, 1013**
    - setProgress method **1004, 1012**
  - switch logic **140**
  - switch multiple-selection statement **76, 134, 138, 152, 182, 1138**
    - activity diagram with break statements **139**
    - case label **137, 138**
    - controlling expression **137**
    - default case **137, 139, 182**
  - Sybase **1038**
  - synchronization **960, 980**
  - synchronization wrapper **713**
  - synchronize **951**
  - synchronize access to a collection **680**
  - synchronized
    - keyword **713, 960, 1138**
    - method **961**
    - statement **960**
  - synchronized collection **680**
  - synchronous error **443**
  - SynchronousQueue class **1002**
  - syntax error **36**
  - System class
    - arraycopy **235, 237**
    - currentTimeMillis method **801**
    - exit method **447, 645**
  - System class (cont.)
    - setErr method **638**
    - setIn method **638**
    - setOut **638**
  - System.err (standard error stream) **440, 638, 666**
  - System.in (standard input stream) **638**
  - System.out
    - print method **41, 41, 42**
    - printf method **43**
    - println method **38, 39, 41, 42**
  - System.out (standard output stream) **39, 638, 666**
  - SystemColor class **576**
- ## T
- tab character, \t **43**
  - Tab key **38**
  - tab stops **43**
  - table **228, 1039**
  - table element **228**
  - table of values **228**
  - TableModel interface **1059**
    - addTableModelListener **1060**
    - getColumnClass method **1060, 1065**
    - getColumnCount method **1060, 1065**
    - columnName method **1060, 1065**
    - getRowCount method **1060**
    - getValueAt method **1060**
    - removeTableModelListener **1060**
  - TableModelEvent class **1071**
  - TableRowSorter class **1071**
  - tabular format **214**
  - tagging interface **414, 655**
  - tail of a queue **862, 882**
  - tailSet method of class TreeSet **705**
  - take method of class BlockingQueue **976, 978**
  - tan method of class Math **168**
  - tangent **168**
  - target type of a lambda (Java SE 8) **730**
  - Target-Heart-Rate Calculator app
    - exercise **1132**
  - Target-Heart-Rate Calculator exercise **306**
  - Tax Plan Alternatives exercise **163**
  - TCP (Transmission Control Protocol) **25**
  - TCP/IP **26**
  - technical publications **30**
  - Telephone-Number Word Generator
    - exercise **674**
  - temporary **94**
  - TEN constant of class BigDecimal **339**
  - terabyte **6**
  - Terminal application (OS X) **18**
  - terminal operation **730**
    - eager **733**
  - terminal operations
    - mutable reduction **727**
    - reduction **727**
  - terminal stream operations (Java SE 8) **726, 737**
    - average method of interface IntStream **731**

- terminal stream operations (Java SE 8)
  - (cont.)
  - collect method of interface Stream **737**, 747, 748, 754
  - count method of interface IntStream **731**
  - findFirst method of interface Stream **744**
  - mapToDouble method of interface Stream **748**
  - max method of interface IntStream **731**
  - min method of interface IntStream **731**
  - reduce method of interface IntStream **731**
  - short-circuiting **744**
  - sum method of interface IntStream **731**
- terminal window **39**
- terminate a loop **89**
- terminate an application **915**
- terminate successfully **645**
- terminated state **953**
- termination housekeeping **330**, **380**
- termination model of exception handling **441**
- termination phase **88**
- termination test **779**
- ternary operator **81**
- test method of functional interface
  - IntPredicate (Java SE 8) **733**, **734**
- Text analysis **630**
- text editor **39**, **589**
- text field **61**
- text file **638**
- Text property of a Label (JavaFX) **1108**
- TextEdit **18**
- TextField class (JavaFX) **1112**, **1116**
- TextInputControl class (JavaFX) **1123**
- TexturePaint class **548**, **576**, **577**
- The “FairTax” **163**
- The Java™ Language Specification **52**
- thenComparing method of functional interface Comparator (Java SE 8) **745**
- thick lines **573**
- this
  - keyword **269**, **314**, **331**, **1138**
  - reference **314**
  - to call another constructor of the same class **319**
- thread **441**, **550**
  - life cycle **952**, **954**
  - of execution **951**
  - scheduling **954**, **973**
  - state **952**
  - synchronization **713**, **960**
- Thread class
  - currentThread method **957**, **962**
  - interrupt method **957**
  - sleep method **957**
- thread confinement **1003**
- thread-life-cycle statechart diagram **952**, **954**
- thread pool **955**
- thread priority **954**
- thread safe **966**, **1003**
- thread scheduler **954**
- thread states
  - blocked **953**, **961**
  - dead **953**
  - new **953**
  - ready **954**
  - runnable **953**
  - running **954**
  - terminated **953**
  - timed waiting **953**
  - waiting **953**
- three-button mouse **513**
- three-dimensional rectangle **564**
- ThreeDimensionalShape class **385**
- throw an exception **222**, **435**, **439**
- throw an exception **310**, **320**
- throw keyword **450**, **1138**
- throw point **437**
- throw statement **449**
- Throwable class **443**, **453**
  - getMessage method **453**
  - getStackTrace method **453**
  - hierarchy **444**
  - printStackTrace method **453**
- throws clause **442**
- throws keyword **1138**
- thumb of class JSlider **904**, **908**
- thumb position of class JSlider **908**
- tick marks on a JSlider **904**
- TicTacToe **350**
  - exercise **350**
- tightly packed binary tree **892**
- Time to Calculate Fibonacci Numbers
  - exercise **801**
- timed waiting state **953**
- Timer class **584**
- timeslice **954**
- timeslicing **954**
- title bar **467**, **473**, **908**
- title bar of a window **470**
- title bar of internal window **928**
- titles table of books database **1040**, **1041**
- toAbsolutePath method of interface Path **640**
- toArray method of List **687**, **688**
- toCharArray method of class String **602**
- toCharArray method of String **799**
- ToDoubleFunction functional interface (Java SE 8) **749**
  - applyAsDouble method **749**
- toggle buttons **487**
- token of a String **615**
- tokenization **615**
- toList method of class Collectors (Java SE 8) **737**
- toLowerCase method of class Character **613**
- toLowerCase method of class String **602**, **686**
- toMillis method of class Duration **1018**
- tool tips **472**, **475**, **477**
- top **88**, **702**
- TOP constant of class JTabbedPane **934**
- top-down, stepwise refinement **88**, **89**, **90**, **96**, **97**
- top-level class **480**
- top of a stack **862**
- toPath method of class File **663**
- Tortoise and the Hare **257**, **585**
- Tortoise and the Hare exercise **585**
- toString method
  - of class ArrayList **689**, **854**
  - of class Arrays **623**, **806**
  - of class Object **360**, **380**
- toString method of an object **172**
- toString method of interface Path **640**
- total **84**, **89**
- Total Sales **252**
- toUpperCase method of class Character **612**
- toUpperCase method of class String **601**, **686**
- Towers of Hanoi **781**
- Towers of Hanoi for the case with four disks **781**
- track mouse events **507**
- traditional comment **36**
- trailing white-space characters **602**
- transaction file **673**
- transaction processing **1090**, **1091**
- transaction record **674**
- transfer of control **74**, **260**, **261**, **262**
- transient keyword **657**, **1138**
- transition arrow **78**, **83**
  - in the UML **75**
- transition arrow in the UML **82**
- transition in the UML **75**
- translate method of class Graphics2D **580**
- translation **9**
- translator program **9**
- Transmission Control Protocol (TCP) **25**
- transparency of a JComponent **514**
- traverse a tree **890**
- traverse an array **229**
- tree **703**, **885**
- TreeMap class **706**, **752**
- TreeSet class **703**, **704**, **705**
  - headSet method **704**
  - tailSet method **705**
- trigger an event **471**
- trigonometric cosine **168**
- trigonometric sine **168**
- trigonometric tangent **168**
- trim method of class String **602**
- trimToSize method of class
  - ArrayList<T> **239**
- true **54**, **1138**
- true reserved word **77**, **81**
- truncate **51**
- truncate fractional part of a calculation **86**
- truncated **643**
- truth table **142**
- truth tables
  - for operator  $\wedge$  **144**
  - for operator  $!$  **145**
  - for operator  $\&\&$  **142**
  - for operator  $||$  **143**
- try block **222**, **439**, **451**
  - terminates **441**
- try keyword **439**, **1138**
- try statement **222**, **442**
- try-with-resources statement **459**
- Turtle Graphics **252**, **585**
- Turtle Graphics exercise **585**
- 24-hour clock format **308**

- two-dimensional array
  - representation of a maze 800
- 228, 229**
- two-dimensional data structure 885
- two-dimensional graphics 573
- two-dimensional shapes 548
- two largest values 116
- `TwoDimensionalShape` class 385
- type **46**
- type argument **843**
- type casting **94**
- type-import-on-demand declaration **877**
- type inference with the `<>` notation (Java SE 7) 683
- type inferring 683
- type of a lambda expression 725
- type of a variable **50**
- type parameter **835, 841, 848**
  - scope 843
  - section **835, 841**
- type safety 834
- type variable **835**
- type-wrapper class 610, **679, 837**
  - implements `Comparable` 837
- `TYPE_FORWARD_ONLY` constant **1064**
- `TYPE_INT_RGB` constant of class `BufferedImage` 577
- `TYPE_SCROLL_INSENSITIVE` constant **1064**
- `TYPE_SCROLL_SENSITIVE` constant **1064**
- `Types` class **1059**
- typesetting system 589
- type-wrapper classes **610**
- typing in a text field 477, 1113
- Typing Tutor: Tuning a Crucial Skill in the Computer Age 546

## U

- `UManager` class **921**
  - `getInstalledLookAndFeel` method **921**
    - `LookAndFeelInfo` nested class **921**
    - `setLookAndFeel` method **924**
- `UManager.LookAndFeelInfo` class
  - `getClassName` method **924**
- UML (Unified Modeling Language) 13
  - activity diagram 75, 78, 82, 127, 133
  - arrow 75
  - class diagram **273**
  - compartment in a class diagram 273
  - diamond 77
  - dotted line **76**
  - final state **75**
  - guard condition 77
  - merge symbol **82**
  - note **75**
  - solid circle **75**
  - solid circle surrounded by a hollow circle 75
- UML ([www.uml.org](http://www.uml.org)) 76
- unary operator **94, 144**
  - cast **94**
- `UnaryOperator` functional interface (Java SE 8) 725
- unbiased shuffling algorithm 287
- unboxing 841, 846
- unboxing conversion **679**

- uncaught exception **441**
- unchecked exceptions **444**
- uncovering a component 550
- underlying data structure 702
- underscore (`_`) SQL wildcard character 1045, 1046
- uneditable `JTextArea` 531
- uneditable text or icons 471
- Unicode character set 7, 69, 103, 139, **589, 594, 612, 1139**
- Unicode value of the character typed 520
- Unified Modeling Language (UML) 13
- Uniform Resource Identifier (URI) **640**
- Uniform Resource Locator (URL) **640**
- union of two sets 349
- universal-time format 308, 310, 311
- UNIX 39, 137, 645
- `unlock` method of interface `Lock` **994, 999**
- unmodifiable collection 680
- unmodifiable wrapper **713**
- unnecessary parentheses 53
- unspecified number of arguments 231
- `UnsupportedOperationException` class **686**
- `unwatch` debugger command **1151**
- unwinding the method-call stack 451
- `UPDATE` SQL statement 1044, **1051**
- `updateComponentTreeUI` method of class `SwingUtilities` **924**
- upper bound 838
  - of a wildcard 854
- upper bound of a type parameter **839, 840**
- upper-left corner of a GUI component 103, 548
- upper-left *x*-coordinate 552
- upper-left *y*-coordinate 552
- uppercase letter 37, 47
- URI (Uniform Resource Identifier) **640**
- URL (Uniform Resource Locator) **640**
- Use binary search to locate an item in an array 809
- Utilities Package 177
- utility method **311**

## V

- va* **646**
- valid identifier 46
- validate data **87**
- `validate` method of class `Container` **529**
- validity checking 323
- value of a variable **50**
- Value property of a `Slider` (JavaFX) 1118
- value to the nearest integer 202
- `valueChanged` method of interface `ListSelectionListener` **502**
- `valueOf` method of class `BigDecimal` **339**
- `valueOf` method of class `String` **602**
- `valueProperty` method of class `Slider` 1124
- `values` method of an enum **328**
- `VALUES` SQL clause **1050, 1050**
- van Rossum, Guido 16

- variable **45, 46, 47**
  - name **46, 50**
  - reference type **210**
  - size **50**
  - type **50**
  - value **50**
- variable declaration statement **47**
- variable is not modifiable 335
- variable-length argument list **231**
- variable names
  - came case naming 171, 268
- variable scope 126
- `VBox` class (JavaFX) **1107**
  - alignment **1108**
  - `Alignment` property 1108
- `Vbox` class (JavaFX) **1107**
- `Vector` class **680**
- `VERTICAL` constant of class `GridBagConstraints` **936**
- vertical coordinate **103, 548**
- vertical gap space **526**
- vertical scrolling 533
- vertical strut **933**
- `VERTICAL_SCROLLBAR_ALWAYS`
  - constant of class `JScrollPane` **534**
- `VERTICAL_SCROLLBAR_AS_NEEDED`
  - constant of class `JScrollPane` **534**
- `VERTICAL_SCROLLBAR_NEVER` constant of class `JScrollPane` **534**
- `Vgap` property of a `GridPane` 1117
- v1* editor 18
- video game 179
- video streaming 987
- View** 467
- view (in MVC) 1113
- virtual key code **520**
- virtual machine (VM) **19**
- Visual Basic programming language 16
- Visual C# programming language 16
- Visual C++ programming language 16
- visual feedback 490
- visual programming 1103
- Visualizing Recursion exercise 798
- `void` keyword **38, 171, 1138**
- volatile information 5
- `volatile` keyword 1138
- volume of a sphere 199, 201

## W

- W3C (World Wide Web Consortium) **26**
- `wait` method of class `Object` 380, **980**
- waiting line 702
- waiting* state 953
- waiting thread 983
- `watch` debugger command **1150**
- web browser 59
- web page 59
- web services 26
  - Amazon eCommerce 27
  - eBay 27
  - Facebook 27
  - Flickr 27
  - Foursquare 27
  - Google Maps 26
  - Groupon 27
  - Instagram 27
  - Last.fm 27

- web services (cont.)
  - LinkedIn 27
  - Microsoft Bing 27
  - Netflix 27
  - PayPal 27
  - Salesforce.com 27
  - Skype 27
  - Twitter 26
  - WeatherBug 27
  - Wikipedia 27
  - Yahoo Search 27
  - YouTube 27
  - Zillow 27
- weightx field of class
  - GridBagConstraints **936**
- weighty field of class
  - GridBagConstraints **936**
- WEST constant of class BorderLayout
  - 510, 524**
- WEST constant of class
  - GridBagConstraints **935**
- WHERE SQL clause 1044, **1045**, 1046, 1048, 1051, 1052
- while repetition statement 76, **82, 83**, 86, 91, 92, 122, 152, 1138
  - activity diagram in the UML 83
- white space 37, 39, 58
- white-space character 602, 615, 616
- widgets 466, 1100
- width 563
- width of a rectangle in pixels 552
- wildcard 854
  - in a generic type parameter **852**
  - type argument **854, 854**
  - upper bound 854
- window 59, 103, 104, 106, **908**
- Window class 908, 909
  - addWindowListener method **909**
  - dispose method **909**
  - pack method **928**
- window event **909**
- window event-handling methods 510
- window events **909**
- window gadgets 466, 1100
- windowActivated method of interface
  - WindowListener **909**
- WindowAdapter class 511, **1071**
- windowClosed method of interface
  - WindowListener **909, 1071**
- windowClosing method of interface
  - WindowListener **909**
- WindowConstants interface **908**
  - DISPOSE\_ON\_CLOSE constant 909
  - DO\_NOTHING\_ON\_CLOSE constant 908
  - HIDE\_ON\_CLOSE constant 908
- windowDeactivated method of
  - interface WindowListener **909**
- windowDeiconified method of
  - interface WindowListener **909**
- windowIconified method of interface
  - WindowListener **909**
- windowing system **472**
- WindowListener interface 510, 511, **909, 1071**
  - windowActivated method **909**
  - windowClosed method **909, 1071**
  - windowClosing method **909**
  - windowDeactivated method **909**
  - windowDeiconified method **909**
  - windowIconified method **909**
  - windowOpened method **909**
- windowOpened method of interface
  - WindowListener **909**
- Windows 13, 137, 645
- Windows look-and-feel 904
- Windows operating system **13**
- word character **616**
- word processor 589, 597
- workflow **75**
- World Population Growth Calculator
  - exercise 71
- World Population Growth exercise 119
- World Wide Web **26**
- World Wide Web (WWW)
  - browser 59
- World Wide Web Consortium (W3C) **26**
- worst-case run time for an algorithm 806
- wrapper methods of the Collections
  - class **680**
- wrapper object (collections) **713**
- wrapping stream objects **654, 659**
- wrapping text in a JTextArea 534
- writeBoolean method of interface
  - DataOutput 666
- writeByte method of interface
  - DataOutput 666
- writeBytes method of interface
  - DataOutput 666
- writeChar method of interface
  - DataOutput 666
- writeChars method
  - of interface DataOutput 666
- writeDouble method
  - of interface DataOutput 666
- writeFloat method
  - of interface DataOutput 666
- writeInt method of interface
  - DataOutput 666
- writeLong method of interface
  - DataOutput 666
- writeObject method
  - of class ObjectOutputStream 659
  - of interface ObjectOutputStream **655**
- Writer class **667**
- writeShort method of interface
  - DataOutput 666
- writeUTF method of interface
  - DataOutput 666
- Writing the Word Equivalent of a Check
  - Amount 632
- www 28

## X

- x-coordinate **103, 548, 572**
- X\_AXIS constant of class Box **934**
- x-axis **104, 548**

## Y

- y-coordinate **103, 548, 572**
- Y\_AXIS constant of class Box **934**
- y-axis **104, 548**

## Z

- zero-based counting 125
- ZERO constant of class BigDecimal **339**
- ZERO constant of class BigInteger **776**
- zero-based counting **214**
- zeroth element **211**

*This page intentionally left blank*

## Additional Comments from Recent Editions Reviewers

“Fantastic textbook and reference. Provides great detail on the latest Java features including lambdas. The code examples make it easy to understand the concepts.” — **Lance Andersen, Principal Member of the Technical Staff, Oracle Corporation**

“If you think a 10th edition is just going to be a repeat then you would not do this book justice. It has the breadth and depth to get a beginning Java programmer started, but at the same time it is a good companion for a more seasoned programmer who wants to get updated to the latest version of Java. Perfect introduction to strings. Good explanation of static vs. non-static methods and variables. Best introduction to Java 2D I’ve seen! The collections framework is well explained. Good introduction to the most essential data structures. A nice introduction to JavaFX.”

— **Manfred Riem, Java Champion**

“Clearly describes the use cases for different parts of the Java APIs. The tips and observations are very useful. Clearly explains opportunities and pitfalls in Java. Rather than telling the reader what to do and not do, the rationale behind these opportunities and pitfalls is explained. The new features introduced in Java 8 are well mixed with older functionality.” — **Johan Vos, LodgON and Java Champion**

“Really good, clear explanation of object-oriented programming fundamentals. Excellent polymorphism chapter. Covers all the essentials of strings. Good to see things like try-with-resources and DirectoryStream being used. Excellent generic collections chapter. Covering lambdas and streams in one chapter is a tough challenge; you’ve done pretty well. Concurrency chapter gives good coverage of numerous aspects. Good data structures chapter. Introduces JavaFX, the great new way to develop client applications in Java; I like the use of Scene Builder to create the GUI with drag-and-drop design rather than doing it by hand, which shows the way it should be done.” — **Simon Ritter, Oracle Corporation**

“GUI examples are very good and the exercises are well thought out. Graphics examples are easy to follow; good and challenging exercises. Recursion is a well-written chapter; factorials, the Fibonacci series and the Tower of Hanoi are good examples. The JavaFX GUI chapter provides a solid introduction to using the JavaFX Scene Builder demonstrating how easy it is to create Java-based GUI applications.”

— **Lance Andersen, Principal Member of the Technical Staff, Oracle Corporation**

“The Making a Difference exercises are well thought through. I like the DeckOfCards example [in the Introduction to Classes and Objects chapter]. The evolving inheritance example is a good approach to motivating inheritance. I like the employee [polymorphism] example. Very thorough and well explained GUI chapter; I liked the layout exercises. Thorough strings chapter; I like the clear definitions of regular expressions and the Pig Latin exercise. Good introduction to collections; Hashtable performance discussion was good. I like the summary of searching and sorting algorithms with Big O values. Solid treatment of threading.” — **Dr. Danny Coward, Oracle Corporation**

“Nice breadth of coverage of traditional core Java and programming topics as well as newer areas such as lambda expressions and areas becoming more critical such as concurrent programming. A fine intro chapter. I like the [Intro to Classes] bank account example. [Arrays and ArrayLists] is a fine chapter. [Classes and Objects: A Deeper Look] provides a good examination of data type creation. Nice chapter on exception handling. Very nice coverage of files, streams and object serialization. Very nice chapter on generics. Nice overview of hand-managed node-based data structures.”

— **Evan Golub, University of Maryland**

“I like the references to big data, Moore’s Law and encapsulation. The inheritance chapter is excellent; examples are gender neutral which is perfect; the University Community Member inheritance hierarchy is a great example.”

— **Khallai Taylor, Assistant Professor, Triton College and Adjunct Professor, Lonestar College—Kingwood**

“Good explanation of control statements, and translating from pseudocode to a Java program. Good approach to important concepts like static, accessors and private fields and their validation. [Classes and Objects: A Deeper Look] coverage is very interesting — I like how the book flows. Excellent explanation of Java SE 8 interfaces. Excellent explanation of exceptions.” — **Jorge Vargas, Yumbling and a Java Champion**

“Very interesting and entertaining introduction. Good job explaining arrays before the more abstract collections. Guiding the reader to avoid dangerous patterns is equally important as explaining the correct syntax; great work! Excellent introduction to object-oriented concepts; rather than just a theoretical overview, it points the reader to how OO is implemented. Great polymorphism chapter — should help the reader distinguish between abstract classes and Java 8 interfaces with default methods. Good discussion of analyzing stack traces, since exceptions provide useful debugging information. Great job explaining Java2D. Shows how easily files and the file system are accessible using Java. Very good introduction to hashtables. Pushing all lambda-related content into a single chapter is hard, but the authors succeeded; I like the way they show how lambda expressions compare to existing code with inner classes; they show that it’s the compiler that does the work. Recursion is well explained. Great introduction to BigInteger and BigDecimal. One of the best explanations of generics I’ve read. Clearly explains collections, and when and how they should be used; it’s important that developers understand this, since choosing a wrong implementation can lead to massive performance penalties or hard-to-understand programs. The explanations of linked lists, stacks and queues are excellent.” — **Johan Vos, LodgON and Java Champion**



## Additional Comments from Recent Editions Reviewers

“Updated to reflect the state of the art in Java technologies; deep and crystal clear explanations. The social-consciousness [Making a Difference] exercises are something new and refreshing. Nice introduction to Java networking.” — **José Antonio González Seco, Parliament of Andalusia**

“An easy-to-read conversational style. Clear code examples propel readers to become proficient in Java.” — **Patty Kraft, San Diego State U.**

“The introduction of the class concept is clearly presented. A comprehensive overview of control structures and the pitfalls that befall new programmers. I applaud the authors for their topical research and illustrative examples. The arrays exercises are sophisticated and interesting. The clearest explanation of pass-by-value and pass-by-reference that I’ve encountered. A logical progression of inheritance and the rationale for properly implementing encapsulation in a system involving an inheritance hierarchy. The polymorphism and exception handling discussions are the best I’ve seen. An excellent strings chapter. I like the [recursion] discussions of the ‘Lo Fractal’ and backtracking (which is useful in computer vision applications). A good segue into a data structures course.” — **Ric Heishman, George Mason University**

“Practical top-down, solution approach to teaching programming basics, covering pseudocode, algorithm development and activity diagrams. Of immense value to practitioners and students of the object-oriented approach. Demystifies inheritance and polymorphism, and illustrates their use in getting elegant, simple and maintainable code. The [optional] OO design case study presents the object-oriented approach in a simple manner, from requirements to Java code.” — **Vinod Varma, Astro Infotech Private Limited**

“Easy-to-follow examples provide great teaching opportunities! I like the [optional] graphics track early in the book — the exercises will be fun for the students. The concept of inheritance is built through examples and is very understandable. Great examples of polymorphism and interfaces. Great comparison of recursion and iteration. The searching and sorting chapter is just right. A simplified explanation of Big O — the best I’ve read! I appreciate the coverage of GUI threading issues. Great approach to Java web technologies.” — **Sue McFarland Metzger, Villanova University**

“The Making a Difference exercises are inspired — they have a real contemporary feeling, both in their topics and in the way they encourage the student to gather data from the Internet and bring it back to the question at hand.” — **Vince O’Brien, Pearson Education (our publisher)**

“Most major concepts are illustrated by complete, annotated programs. Abundant exercises hone your understanding of the material. JDBC is explained well.” — **Shyamal Mitra, University of Texas at Austin**

“The best introductory textbook that I’ve encountered. I wish I had this book when I was learning how to program! Good introduction to the software engineering process.” — **Lance Andersen, Oracle Corporation**

“You’ll be well on your way to becoming a great Java programmer with this book.” — **Peter Pilgrim, Java Champion, Consultant**

“Exceptionally well-written recursion chapter. Excellent descriptions of the search and sort algorithms and a gentle introduction to Big-O notation — the examples give the code for the algorithms, and output that creates a picture of how the algorithms work.”  
— **Diana Franklin, University of California, Santa Barbara**

“Suitable for new programmers, intermediate-level programmers who want to hone their skills, and expert programmers who need a well-organized reference. Event handling and layouts are well explained.” — **Manjeet Rege, Rochester Institute of Technology**

“Beautiful collections of exercises — a nice illustration of how to use Java to generate impressive graphics.” — **Amr Sabry, Indiana University**

“The [optional] OOD ATM case study puts many concepts from previous chapters together in a plan for a large program, showing the object-oriented design process — the discussion of inheritance and polymorphism is especially good as the authors integrate these into the design.”  
— **Susan Rodger, Duke University**

“The transition from design to implementation is explained powerfully — the reader can easily understand the design issues and how to implement them in Java.” — **S. Sivakumar, Astro Infotech Private Limited**

“Comprehensive introduction to Java, now in its eighth major iteration. With clear descriptions, useful tips and hints, and well-thought-out exercises, this is a great book for studying the world’s most popular programming language.” — **Simon Ritter, Oracle Corporation**

“Comprehensive treatment of Java programming, covering both the latest version of the language and Java SE APIs, with its concepts and techniques reinforced by a plethora of well-thought-through exercises.” — **Dr. Danny Coward, Oracle Corporation**

“There are many Java programming books in the world. This textbook is the best one.” — **Dr. Huiwei Guan, North Shore Community College**